



EPIGRAPHIA INDICA

Vol. VII (1902 - 1903)



PUBLISHED BY
THE DIRECTOR GENERAL
ARCHEOLOGICAL SURVEY OF INDIA
JANPATH, NEW DELHI-110001
1981

90/-
7/12/83

104266

EPIGRAPHIA INDICA

VOL. VII.—1902-03.



PUBLISHED BY
THE DIRECTOR GENERAL
ARCHAEOLOGICAL SURVEY OF INDIA
JANPATH, NEW DELHI-110011
1981

Reprinted 1981

©
ARCHAEOLOGICAL SURVEY OF INDIA
GOVERNMENT OF INDIA
1981

104266

Price : Rs. 90

Printed at Pearl Offset Press, 5/33, Kirti Nagar Indl. Area New Delhi-1

PUBLISHED UNDER THE AUTHORITY OF THE GOVERNMENT OF INDIA-
AS A SUPPLEMENT TO THE "INDIAN ANTIQUARY."

EPIGRAPHIA INDICA

AND


RECORD OF THE ARCHÆOLOGICAL SURVEY OF INDIA.

EDITED BY

E. HULTZSCH, Ph.D.,

LATE GOVERNMENT EPIGRAPhist; PROF. IN THE UNIVERSITY OF HALLE;
CORR. MEMB. OF THE BATAVIA SOCIETY OF ARTS AND SCIENCES,
AND OF THE ROYAL SOCIETY OF SCIENCES AT GÖTTINGEN.

VOL. VII.—1902-03.



CALCUTTA :

OFFICE OF THE SUPERINTENDENT OF GOVERNMENT PRINTING, INDIA.

BOMBAY: EDUCATION SOCIETY'S PRESS.

LONDON: LUZAC & Co. and KEGAN PAUL,
TRENCH, TRÜBNER & Co.

NEW YORK: WESTERMANN & Co.

CHICAGO: S. D. PEET.

LEIPZIG: OTTO HARRASSOWITZ.

VIENNA: A. HÖLDER & Co.

BERLIN: A. ASHER & Co.

PARIS: E. LEROUX.

CALCUTTA

GOVERNMENT OF INDIA CENTRAL PRINTING OFFICE,

8, HASTINGS STREET.

CONTENTS.

The names of contributors are arranged alphabetically.

	PAGE
D. R. BHANDARKAR, M.A.:—	
No. 6. Cambay plates of Góvinda IV.; Śaka-Saṃvat 852	26
J. F. FLEET, PH.D., C.I.E., Indian Civil Service (Retired):—	
No. 25. Kaluchumbargu grant of Vijayāditya-Amma II.	177
„ 28. Some records of the Rāshtrakūṭa kings of Mālkhēd:—	
D.—Mantrawādi inscription of the time of Amōghavarsha I.; A.D. 865.	198
E.—Sīrūr inscription of the time of Amōghavarsha I.; A.D. 866	202
F.—Nīdagundi inscription of the time of Amōghavarsha I.; about A.D. 874-75	208
The family-name of the Rāshtrakūṭas of Mālkhēd	214
The original home of the Rāshtrakūṭas of Mālkhēd	228
The banners and crests of the same and of the Rattas of Saundatti	227
Góvinda II., and the Alās plates which purport to have been issued in A.D. 770	230
PROFESSOR E. HULTZSCH, PH.D.:—	
No. 4. Three memorial stones	22
„ 5. A rock-inscription at Tandalam	25
„ 13. Baloda plates of Tivaradēva	102
„ 14. Inscriptions on the three Jaina colossi of Southern India	108
„ 15. Two Jaina inscriptions of Irugappa	115
„ 18. Arulāla-Perumāl inscription of the time of Pratāparudra; Śaka-Saṃvat 1238	128
„ 19. Six inscriptions at Tirunāmanallūr	132
„ 20. Fourteen inscriptions at Tirukkōvalūr	138
„ 23. Tiruvēndipuram inscription of Rājārāja III., Narasimha II. and Kōpperuñjīnga	160
„ 26. Four inscriptions at Śōlapuram	192
„ 27. A Vaishṇava inscription at Paḡān	197
PROFESSOR F. KIELHORN, PH.D., D. LITT., LL.D., C.I.E.:—	
Nos. 1 and 24. Dates of Chōla kings (<i>continued</i>)	1 and 169
No. 2. Dates of Pāṇḍya kings (<i>continued</i>)	10
„ 9. Kahlā plate of the Kalachuri Śōghadēva; [Vikrama-]Saṃvat 1134	85
„ 10. Lucknow Museum plate of Kīrtipāla; [Vikrama-]Saṃvat 1167	93
„ 11. Lār plates of Góvindahandra of Kanauj; [Vikrama-]Saṃvat 1202	98
„ 12. A note on the Buguḍa plates of Mādhavarman	100
„ 22. Maḡhuban plate of Harsha; the year 25	155
PROFESSOR H. LÜDERS, PH.D.:—	
No. 3. Amarāvati inscription of Kṛishṇarāya of Vijayanagara; Śaka-Saṃvat 1437	17
„ 17. Two inscriptions of Tammusiddhi; Śaka-Saṃvat 1129	119
„ 21. Two further inscriptions of Tammusiddhi	148
J. RAMAYYA, B.A., B.L.:—	
No. 8. Dēvalapalli plates of Immaḍi-Nṛisimha; Śaka-Saṃvat 1427	74
E. SENART:—	
No. 7. The inscriptions in the caves at Kārle	47
J. PH. VOGEL, LL.D.:—	
No. 16. Two Brāhmī and Kharōṣṭhī rock-inscriptions in the Kāḡra valley	116

	PAGE
INDEX.—By V. VENKAYYA, M.A.	233

APPENDIX.—A LIST OF INSCRIPTIONS OF SOUTHERN INDIA FROM ABOUT A.D. 500.

By PROFESSOR F. KIELHORN, C.I.E.	1
I.—LIST OF DATED INSCRIPTIONS. By THE SAME	171
II.—INDEX TO THE APPENDIX. By THE SAME	180

LIST OF PLATES.

1. Three memorial stones	to face page	24
2. Cambay plates of Govinda IV.—Plate i.	between pages	38 & 39
3. " " " " ii.	" "	40 & 41
4. Kārlē inscriptions.—Plate i.	to face page	56
5. " " " " ii.	" " "	64
6. " " " " iii.	" " "	72
7. " " " " iv.	" " "	74
8. Devulapalli plates of Immadi-Nṛsiṃha; Śaka-Saṃvat 1427	between pages	82 & 83
9. Lucknow Museum plate of Kīrtipāla; [Vikrama-]Saṃvat 1167	" "	96 & 97
10. Bugūda plates of Mādhavavarman	" "	100 & 101
11. Baloda plates of Tivaradēva	" "	104 & 105
12. Jaina colossus at Śravaṇa-Belgoḷa	to face page	108
13. Inscriptions on the same	" " "	109
14. Jaina colossi at Kārkaḷa and Vēṇūr	" " "	112
15. Rock-inscriptions in the Kāṅgra valley	" " "	118
16. Tirukkōvalūr inscriptions	" " "	144
17. Madhuban plate of Harsha; the year 25	" " "	158
18. Kaluchumbāṛṇa grant of Vijayāditya-Amma II.	between pages	186 & 187
19. Śōlapuram inscriptions and Paḡān inscription	to face page	194
20. Mantrawāḍi inscription of Amōghavarsha I.; A.D. 865	" " "	201
21. Sirūr inscription of Amōghavarsha I.; A.D. 866	" " "	206
22. Nīdagundī inscription of Amōghavarsha I.	" " "	213

ADDITIONS AND CORRECTIONS.

A.—VOLUME III.

- Page 103.—The Paiṭhaṇ plates of Gôvinda III. of A.D. 794.—For the localisation of this record, by identification of the places mentioned in it, see *Ind. Ant.* Vol. XXX. p. 515.—J. F. F.
- „ 158.—The spurious Sûḍi plates.—In text lines 71, 83, for “Suldhâtavî” read “Sulvâtavî;” and make the same correction in the translation, p. 184: see *Ind. Ant.* Vol. XXX. p. 264.—For a full note on the Kisukâḍ (Sulvâtavî) seventy district, see *ibid.* p. 259 ff.—Page 184, line 7, for “of his wife,” read “of his mistress;” see Vol. VII. below, p. 182, note 4.—J. F. F.
- „ 208, the last line but one.—For a full note on the Kûṇḍi country, see *Ind. Ant.* Vol. XXIX. p. 278 ff.—J. F. F.
- „ 230.—The Bhairammatṭi inscription.—Page 235, line 10, for “in the region,” read “on an island;” see *Ind. Ant.* Vol. XXXII. p. 55, and note 36.—J. F. F.
- „ 306.—The Tidgundi plates of Vikramâditya VI. of A.D. 1082.—For the identification of the Pratyandaka four-thousand province, see *Ind. Ant.* Vol. XXX. p. 380.—J. F. F.

B.—VOLUME IV.

- Page 204.—The Nîlgund inscription of Taila II. of A.D. 982.—For the identification of the Kôgalî country, see *Ind. Ant.* Vol. XXX. p. 106.—J. F. F.
- „ 212.—The inscriptions of A.D. 1064 and 1072 at the Jatiṅga-Râmêśvara hill.—For the identification of the Kaṇiyakal three-hundred district, see *Ind. Ant.* Vol. XXX. p. 108.—J. F. F.
- „ 278.—The Karhâḍ plates of Kṛishṇa III. of A.D. 959.—For the localisation of this record, by identification of the places mentioned in it, see *Ind. Ant.* Vol. XXX. p. 373.—For a full note on the Karahâṭa four-thousand province, see *ibid.* p. 377 ff.—J. F. F.
- „ 350.—The Hebbâl inscription of A.D. 975.—Page 351, line 1, and page 354, translation line 5, for “Rêvaka,” read “Rêvakanimmaḍi,” and in the translation omit the words “(holding her) in (his) lap;” see Vol. VI. below, p. 71, and note 4.—J. F. F.
- „ 371, column 2, last line,—for Hrahaḍagalli, read Hîrahaḍagalli.

C.—VOLUME VI.

- Page 208.—The Alâs plates, which purport to have been issued in A.D. 770.—The Alaktakâ *viśaya* of this record is mentioned as the Alataḡe seven-hundred district in a record of A.D. 1008; and the places mentioned in that record, and in another, locate it close on the east of Kôlhâpur, where there is now the Alṭem subdivision of that State; see *Ind. Ant.* Vol. XXIX. p. 273 ff. For the point that the Alâs plates are a spurious record, see Vol. VII. below, p. 231.—J. F. F.
- „ 341, text line 61,—insert the figure ² after ँऐ॥.
- „ 394, column 1, line 9,—for Vîrpêḍu-nâḍu, read Vîrpêḍu-nâḍu.
- „ „ column 2, last line,—for Piṅgâla, read Piṅgala.

D.—VOLUME VII.

- Page 19, note 4,—*for Odegany, read Odegary.*
 „ 23, note 4,— *for Kaśākūḍi, read Kāsākūḍi.*
 „ 27, line 5 from bottom,— *for Godâvarî, read Gôdâvarî.*
 „ 30, last line,— *for Khajurâho, read Khajurâhō.*
 „ 32, line 12,— „ „ „ „
 „ „ „ 20,— „ „ „ „
 „ 36, line 14 of paragraph 2,— *for Shêri (Shêdhi), read Shêrî (Shêḍi)*
 „ 45, line 13 from bottom,— *for Godâvarî, read Gôdâvarî.*
 „ 50, line 22,— *for Kausikîputra, read Kauśikîputra.*
 „ 66, line 13,— *for Nasik, read Nâsik.*
 „ 79, note 7, line 6,— *for Mēdinimîśvaragaṇḍa, read Mēdinimîśvaragaṇḍa.*
 „ „ „ 7, *for Narasiṅgaiyadēva, read Narasiṅgaiyadēva.*
 „ 86, last line,— *for fee of, read feet of.*
 „ 92, text line 42,— *insert a hyphen (-) between putra and Kusi(ṣi)°*
 „ 115, lines 10 and 16,— *for Chaicha and Chaichapa, read Baicha and*
 „ 122, line 10 from bottom,— *for Tiruppâsûr, read Tiruppâsûr.*
 „ 162, note 9,— *for Gedilam, read Gedilam.*
 „ 219, line 8,— *for Râshṭrakûta, read Râshṭrakûṭa.*

EPIGRAPHIA INDICA.

VOLUME VII.

No. 1.— DATES OF CHOLA KINGS.

By F. KIELHORN, PH.D., LL.D., C.I.E.; GÖTTINGEN.

(Continued from Vol. VI. page 285.)

A.—PARANTAKA I.

55.— In the Kēsava-Perumāḷ temple at Kūram.¹

- 1 Svast[i] śr[ī] [||*] [Ma]d[irai ko]ṇḍ=Ī[lam] pu[gun]da [kô]=Pparakkê[sa]ri[pan]-
ma[r*]k[ku] yāṇḍu nāṇḍāvaḍu
2 i[v*]v-āt[t]ai . . . [ḍa]ga-²nāya[r]ṛu apara-pa[ksha*]t[tu]=Chohaṇi-kkiḷamaiyum
nava[m]iyum peṇṇa Urōyaṇi-nāḷ irātri.

“In the fortieth year (*of the reign*) of king Parakēsarivarman who took Maḍirai and entered Īlam,— at night on the day of Rôhiṇi, which corresponded to a Saturday and to the ninth *tithi* of the second fortnight of the month of [Karkāṭa]ka in this year.”

Although I am unable to give with confidence the actual equivalent of this date, I may state that between A.D. 900 and 985 the only years for which the date would be quite regular are A.D. 919 and 946.

For A.D. 919 the date would correspond to Saturday, the 24th July, which was the 30th day of the month of Karkāṭaka, and on which the 9th *tithi* of the dark half (of the month Śrāvaṇa) ended 4 h. 41 m., and the *nakṣatra* was Rôhiṇi for 17 h. 44 m., after mean sunrise.

And for A.D. 946 it would correspond to Saturday, the 25th July, which was the last day of the month of Karkāṭaka, and on which the 9th *tithi* of the dark half (of the month Śrāvaṇa) ended 13 h. 11 m. after mean sunrise, and the *nakṣatra* was Rôhiṇi the whole day.

B.—KULOTTUNGA-CHOLA I.

56.— In the Lakṣminārāyaṇa temple at Kāvantaṇḍalam.³

- 1 Svasti śrī [||*] Tiru ma[ṇṇi] viḷaṅga

¹ No. 34 of the Government Epigraphist's collection for 1900.

² Read perhaps *Karkāḍaga*.

³ No. 206 of the Government Epigraphist's collection for 1901; *South-Ind. Inscr.* Vol. III. No. 77.

- 2 kôv=Irâjakêsarivatmar=âna uḍaiyâr śrī-[R]âjendra-Śôladêvaḥk
yāṇḍu 4âvadu
- 3 ivv-âṭṭai Mṛi(vṛi)śchika-nâyargu pûrvva-pakshattu 1ashashṭiyut
Tiruvôṇamum peṇṇa Vi[y]âla-kkilamai-nâ[n]ru.

"In the 4th year (of the reign) of king Râjakêsarivarman *alias* the lord, the glorious Râjendra-Chôladêva,— on a Thursday which corresponded to (the day of) Śravaṇa and to the sixth *tithi* of the first fortnight of the month of Vṛiśchika in this year."

A date of the fourth year of the king's reign will be expected to fall in A.D. 1073 or 1074, and this date actually corresponds to Thursday, the 7th November A.D. 1073. This was the 12th or 13th day of the month of Vṛiśchika, and on it the 6th *tithi* of the bright half (of the month Mârgasīra) commenced 1 h. 38 m. after mean sunrise, while the *nakshatra* was Śravaṇa, by the equal space system and according to Garga for 23 h. 38 m. after mean sunrise, and by the Brahma-siddhânta the whole day.

C.—VIKRAMA-CHOLA.

For reasons suggested partly by the new dates of this king, I must recapitulate here the *data* furnished by the dates already treated of,² and the results derived from them.

No. 10 (above, Vol. IV. p. 73).—"In the fifth year . . . on the three-hundred-and-fortieth day, which was (the day of the *nakshatra*) Hasta, a Sunday, and the seventh *tithi* of the first fortnight of the month of Mithuna." Taking this date to have been correctly recorded, I found the best equivalent for it between A.D. 1110 and 1125 to be Sunday, the 22nd June A.D. 1113; and counting backwards from this day, I obtained the 18th July A.D. 1108 as the day of the commencement of the king's reign.

No. 21 (*ibid.* p. 263).—"In the 4th year . . . on the day of Śatabhishaj, which corresponded to a Monday and to the eighth *tithi* of the second fortnight of the month of Rishabha." Guided by the result obtained under No. 10, I found this date to correspond to Monday, the 20th May A.D. 1112, when, to omit other particulars, the *nakshatra*, by the equal space system only, was Śatabhishaj for 0 h. 39 m. after mean sunrise.

No. 22 (*ibid.* p. 264).—"In the 5th year . . . on the day of Ârdra, which corresponded to a Monday and to the eleventh *tithi* of the second fortnight of the month of Simha." Guided again by the result obtained under No. 10, I found that this date would correspond to Monday, the 19th August A.D. 1112; but there was the difficulty that on this day the *nakshatra* was Punarvasu, not Ârdra.

No. 41 (above, Vol. VI. p. 279).—"In the . . . sixteenth year . . . in the month of Vaisâkha, in the second fortnight, at the time known as Monday combined with an Uttarâ (*nakshatra*)." Again guided by the result obtained under No. 10, I found that Monday, the 5th May A.D. 1124, would be an unobjectionable equivalent of this date.

No. 42 (*ibid.* p. 280).—"In the 9th year . . . in the Plava year which was the Śaka year 1049, on the occasion of an eclipse of the moon in the month of Jyaisṭha." This date for Śaka-Samvat 1049 expired (which was Plavaṅga, not Plava) was found to correspond to the 27th May A.D. 1127, but the result obtained under No. 10 led me to assume that the 9th year of the reign had been quoted erroneously instead of the 19th regnal year.

From this it will be seen that the results obtained under Nos. 21, 22 and 41, as well as the correction suggested with regard to the regnal year of No. 42, mainly depend on the correctness of the *data* furnished by the text of No. 10, which it did not occur to me to suspect. Setting aside the date No. 10, it may be asked, however, how the three dates Nos. 21, 22 and 41

¹ Read *ashashṭiyun*.

² I omit here the date No. 43, which will be reconsidered below.

would work out, if the date No. 42 were really, as it is stated to be, a date of the 9th year of Vikrama-Chôla's reign. Supposing this to be the case, the king's reign would have commenced some time between approximately the 28th May A.D. 1118 and the 27th May A.D. 1119, and with such a commencement of the reign the dates Nos. 21, 22 and 41 would yield the following equivalents:—

No. 21, of the 4th year, would correspond to **Monday, the 1st May A.D. 1122.** This was the 7th day of the month of *Vṛishabha*, and on it the 8th *tithi* of the dark half (of the month *Vaiśākha*) ended 13 h. 28 m., while the *nakshatra* was *Śatabhishaj*, by the equal space system and according to Garga from 0 h. 39 m., and by the *Brahma-siddhānta* from 1 h. 19 m., after mean sunrise.

No. 22, of the 5th year, would correspond to **Monday, the 31st July A.D. 1122.** This was the 4th day of the month of *Simha*, and on it the 11th *tithi* of the dark half (of the month *Śrāvaṇa*) ended 4 h. 24 m., while the *nakshatra* was *Ārdrā*, by the equal space system for 12 h. 29 m., and according to Garga for 0 h. 39 m., after mean sunrise.

No. 41, of the 16th year, would correspond to **Monday, the 16th April A.D. 1134,** when the 6th *tithi* of the dark half of *Vaiśākha* ended 13 h. 11 m., and the *nakshatra* was *Uttarāshāḍhā*, by the equal space system and according to Garga for 23 h. 38 m., and by the *Brahma-siddhānta* for 17 h. 4 m., after mean sunrise.

It is quite clear then, that, supposing the king's reign to have commenced between approximately the 28th May A.D. 1118 and the 27th May A.D. 1119, the three dates Nos. 21, 22 and 41 would work out in the best possible manner—better, in fact, than with the 18th July A.D. 1108 as the commencement of his reign, because on the equivalent here found for the date No. 22 the *nakshatra* really was *Ārdrā*, whereas on the equivalent previously given for the same date the *nakshatra* was found to be *Punarvasu* (instead of the *nakshatra* *Ārdrā*, quoted by the original date).

To the date No. 10 I shall have to revert below. For the present it will be sufficient to state that, irrespectively of No. 10, the four dates Nos. 21, 22, 41 and 42 for the commencement of the reign appear to yield some day between approximately the 28th May and the 31st July A.D. 1118. The new dates of Vikrama-Chôla may be expected to shew whether his reign really commenced at the time here given or on the 18th July A.D. 1108.

* * * * *

57.—In the Tyāgarāja temple at Tiruvārūr.¹

8 [Tribhuvana]cha[kra]vatti[gal] śr[ī-Vikrama]-Ch[ô]la[dēvarakku
y]āṇḍu aṇjāvadu Midhuna-nāyar[ū] pūrvva]-paksha[t*]tu pa[n̄chami]y[u]m
Magamum peṇṇa Vi[yā]la-[kk]iāmai-nāḷ.

“In the fifth year (of the reign) of the emperor of the three worlds, the glorious **Vikrama-Chôladēva**,— on a **Thursday** which corresponded to (the day of) **Maghā** and to the fifth *tithi* of the first fortnight of the month of **Mithuna**.”

If the king's reign commenced on the 18th July A.D. 1108, this date would correspond to **Thursday, the 16th June A.D. 1118**, which was the 26th day of the month of **Mithuna**, and on which the 5th *tithi* of the bright half (of the month *Āshāḍha*) commenced 5 h. 15 m., and the *nakshatra* was **Maghā**, by the equal space system only, for 7 h. 53 m., after mean sunrise.

On the other hand, if the reign commenced between the 28th May and the 31st July A.D. 1118, the date must correspond to **Thursday, the 31st May A.D. 1123**, which was the 6th day

¹ No. 164 of the Government Epigraphist's collection for 1894. Another date, which occurs in line 3 of the same inscription, was published above, Vol. IV. p. 73, No. 10.

of the month of **Mithuna**, and on which the 5th *tithi* of the bright half (of the first **Âshâdha**) ended 11 h. 37 m., and the *nakshatra* was **Maghâ**, by the **Brahma-siddhânta** for 11 h. 10 m., according to **Garga** for 13 h. 47 m., and by the equal space system from 1 h. 19 m., after mean sunrise.

Theoretically both the equivalents found might be taken to satisfy the requirements of the case, but there can be no doubt that the second, **Thursday, the 31st May A.D. 1123**, would be preferable because the *tithi* of the date ended on that day. This date therefore also would tend to shew, though it would not actually prove, that the king's reign commenced in A.D. 1118.

58.—In the **Divyajñânêśvara** temple at **Kôvilâḍi**.¹

1 Svasti śrī [||*] I(ti)ribuva[na]śakkaravattiga! śrī-Vikkirama-Śôladêvark=iyâṇḍu
llâva[d]u Magara-nâyaṅgu [p]û[rvva]-

2 pakshat[t]u trai(tra)yô[da*]śiyum Śaṇi-kiḷamaiyum peṅga P[u]ṇarbuda-nâl.

“In the 11th year (of the reign) of the emperor of the three worlds, the glorious **Vikrama-Chôladêva**,²—on the day of **Punarvasu**, which corresponded to a **Saturday** and to the thirteenth *tithi* of the first fortnight of the month of **Makara**.”

If the king's reign commenced on the 18th July A.D. 1108, this date would correspond to Friday, the 27th December A.D. 1118, which was the 3rd day of the month of **Makara**, and on which the 13th *tithi* of the bright half (of the month **Pausa**) ended 16 h. 30 m. after mean sunrise, and the *nakshatras* were **Mṛigaśirsha** and **Ârdra**.

On the other hand, if the king's reign commenced between the 28th May and the 31st July A.D. 1118, the date will correspond to **Saturday, the 5th January A.D. 1120**, which was the 13th day of the month of **Makara**, and on which the 13th *tithi* of the bright half (of the month **Pausa**) ended 5 h. 49 m. after mean sunrise, and the *nakshatra* was **Punarvasu**, by the **Brahma-siddhânta** and according to **Garga** the whole day, and by the equal space system from 9 h. 12 m. after mean sunrise.

As this date then would be entirely incorrect if the king's reign had commenced in A.D. 1108, and is in every way correct on the assumption that the reign commenced in A.D. 1118, I take it to prove that the latter was really the case. And in my opinion the six dates Nos. 21, 22, 41, 42, 57 and 58, for which—in entire agreement with the original *data*—absolutely faultless equivalents have now been given, shew beyond a doubt that the reign of **Vikrama-Chôla** must have commenced between approximately the 1st June and the 31st July A.D. 1118.

* * * * *

With the result now obtained, the equivalent previously given for the date No. 10 cannot, of course, be the proper equivalent of that date. A comparison of the dates No. 10 and No. 57, which are both from the same inscription, at once suggests to us that No. 10 is only three days later than No. 57. Both dates are of the first fortnight of the month of **Mithuna** of the 5th year of the king's reign; the week-day of No. 57 is **Thursday**, and that of No. 10 **Sunday**; and the *nakshatra* of No. 57 is **Maghâ** (10), while that of No. 10 is **Hasta** (13). If then the equivalent of No. 57 is **Thursday, the 31st May A.D. 1123**, the equivalent of No. 10 can only be **Sunday, the 3rd June A.D. 1123**. This day was the 9th day of the month of **Mithuna**, and on it the *nakshatra* was **Hasta**, by the **Brahma-siddhânta** for 22 h. 59 m., and by the equal space system and according to **Garga** from 1 h. 58 m., after mean sunrise; but the *tithi* which ended on the same day, 10 h. 12 m. after mean sunrise, was the 8th, not the 7th *tithi*, of the bright half.

¹ No. 276 of the Government Epigraphist's collection for 1901.

² It is impossible to say *a priori* whether the son of **Kulôttuṅga I.** is meant.

Considering the complete agreement of the six dates previously treated of, I have no doubt whatever that Sunday, the 3rd June A.D. 1123, is really the day intended by the date No. 10, and that the writer of this date, in recording the *tithi*, has erroneously written *saptamiyum*, instead of *ashṭamiyum*.

Since the date No. 10 is stated to have been the 340th day of the 5th year of the king's reign, the first day of that year would now have been the 29th June A.D. 1122, and the accession of Vikrama-Chōla must have taken place on (approximately) the 20th June A.D. 1118.¹

The result now arrived at receives an unexpected confirmation from a reconsideration of the date No. 43 (above, Vol. VI, p. 281). This date is of the seventeenth year (given in words) of the king's reign, and of the Śaka year 1054 (given in figures only), and gives us for calculation Thursday, the third *tithi* of the bright half of Vaiśākha. When previously examining it, I found that for Śaka-Samvat 1054 current it would correspond to Thursday, the 2nd April A.D. 1131; and as I found it to be incorrect for what I then had to consider the 17th year of the king's reign, I felt no hesitation in accepting Thursday, the 2nd April A.D. 1131, as the true equivalent of the date, and in assuming that the regnal year had been quoted erroneously.

But now, with the 29th June A.D. 1118 as the date of the king's accession, a date in the month Vaiśākha of his seventeenth year will be expected to fall in A.D. 1135, and for this year the date regularly corresponds to Thursday, the 18th April A.D. 1135, when the third *tithi* of the bright half of Vaiśākha ended 9 h. 30 m. after mean sunrise. I now therefore assume that the date is really of the 17th year of Vikrama-Chōla's reign, and that the Śaka year 1054 has been erroneously quoted instead of 1057 (expired).

59.—In the Vaidyanātha temple at Tirumalavādi.²

This inscription is dated in the 15th year of the reign of "king Parakēsarivarman *allā*—the emperor of the three worlds, the glorious Vikrama-Chōladēva." In the introduction it is stated that he made gifts to the temple at Chidambaram on the following date:³—

24 -ppattām=āṇḍil [ś]i[t]tirai-ttiṅga[ī] Attā-
25 m perṟa ādittavārattu=[t]tiru-vaḷar-madiyin trayōdasi=ppakkat[tu].

"In the tenth year, (*in*) the month of Śittirai, on a Sunday which corresponded to (*the day of*) Hasta, (*on*) the thirteenth *tithi* of the fortnight of the auspicious waxing moon."

This date, of the month of Śittirai (or Mēsha) of the 10th year of the king's reign, would be expected to fall in A.D. 1128, and for that year it would actually correspond to Sunday, the 15th April A.D. 1128, which was the 23rd day of the month of Śittirai, and on which the 13th *tithi* of the bright half (of the month Vaiśākha) ended 1 h. 25 m. after mean sunrise. But the *nakṣatra* on this day was Chitrā, by the equal space system and according to Garga for 17 h. 44 m., and by the Brahma-siddhānta for 14 h. 27 m., after mean sunrise.— If the week-day of the

¹ The following statement will shew at a glance what mistakes the seven dates Nos. 10, 21, 22, 41, 42, 57 and 58 would necessarily contain, if the accession had taken place on either the 18th July 1108 or the 29th June A.D. 1118.

If it had taken place on the 18th July A.D. 1108,—
in No. 22, *Ārdra* would have been wrongly quoted for *Punarvasu*;
in No. 42, the 9th year would have been wrongly quoted instead of the 19th;
No. 58 would be entirely incorrect.

On the other hand, assuming it to have taken place on the 29th June A.D. 1118,—
in No. 10, *saptamiyum* is wrong for *ashṭamiyum*.

² No. 82 of the Government Epigraphist's collection for 1895; *South-Ind. Insar.* Vol. III. No. 79.

³ The same date is quoted in the introduction of an inscription of the 11th year at Ālāṅḡḍi (No. 165 of 1931, 1, 4 f.).

date were Saturday, the date would correspond to Saturday, the 14th April A.D. 1128, when the 13th *tithi* of the bright half commenced 2 h. 33 m., and the *nakshatra* was Hasta, by the equal space system and according to Garga for 17 h. 44 m., and by the Brahma-siddhanta for 14 h. 27 m., after mean sunrise.—The earliest year of Vikrama-Chôla's reign, in which the date, as recorded, is quite correct, would be the 13th, for which the date would correspond to Sunday, the 12th April A.D. 1131, with the *nakshatra* Hasta.

D.—KULOTTUNGA-CHOLA III.

60.—In the Sômanâthêśvara temple at Sômanâgalam.¹

1 Tribhuvanachchakravarttigal Maduraiyum=[Ī]lamuṇ=gonḍ=aruḷiṇa
śrī-Kulōttuṅga-Śōḷadēvaṅku yāṇḍu lāḍvadu Magara-nāyayṛru pū[r]vva-pakshattu
Viyāḷa-kkilaṁaiyum Pū[śa]mum prathamaiyum=āṇav=ayṛru.

"In the 14th year (of the reign) of the emperor of the three worlds, the glorious Kulōttuṅga-Chōḷadēva who was pleased to take Madurai and Īlam,—on a day which was Thursday, (the day of) Pushya, and the first *tithi* of the first fortnight of the month of Makara."

The wording of this date is intrinsically wrong, because during the month of Makara the moon can never be anywhere near the *nakshatra* Pushya on the first *tithi* of the first fortnight. The probability is that the first fortnight has been erroneously quoted instead of the second, and for the second fortnight the date is correct.

A date of the month of Makara of the 14th year of the king's reign will be expected to fall in December A.D. 1191 or in January A.D. 1192, and in my opinion this date actually corresponds to Thursday, the 2nd January A.D. 1192, which was the 8th day of the month of Makara, and on which the first *tithi* of the dark half (of the month Pausha) ended 10 h. 12 m., and the *nakshatra* was Pushya, by the equal space system and according to Garga for 3 h. 56 m., and by the Brahma-siddhanta for 1 h. 58 m., after mean sunrise.

* * * * *

For convenience of reference I give below a list of all the dates of Chôla kings examined in Vols. IV.—VII., with the exception only of the date of the 40th year of Parāntaka I., No. 55, for which, as possible equivalents, I have given above Saturday, the 24th July A.D. 919, and Saturday, the 25th July A.D. 946. Under the name of each king, I state approximately the time when he must have commenced to reign.

A.—Rājarāja I. Rājakēsarivarman.²

(Between the 25th June and the 25th July A.D. 985.)³

- No. 1 (Vol. IV. p. 66).—Year 7: the 26th September A.D. 991.
No. 25 (Vol. V. p. 48).—Year 15: Tuesday, the 29th August A.D. 999.
No. 27 (Vol. V. p. 197).—Year 15: Wednesday, the 15th May A.D. 1000.⁴
No. 2 (Vol. IV. p. 67).—Śaka 929 (current). This date is incorrect.
No. 3 (Vol. IV. p. 68).—Year 28, Śaka 934. The date would correspond to the 23rd December A.D. 1012, but contains no details for verification.

¹ No. 133 of the Government Epigraphist's collection for 1901.

² Or Kēsarivarman.

³ See Vol. VI. p. 20.

⁴ In the original date the week-day is wrongly given as Thursday, instead of Wednesday.

B.—Rājēndra-Chōla I. Parakēsarivarman.

(Between the 26th November A.D. 1011 and the 7th July A.D. 1012.)

- No. 32 (Vol. VI. p. 20).—Year 9, Śaka 943 (current) : Thursday, the 7th July A.D. 1020.
 No. 4 (Vol. IV. p. 68).—Śaka 943 (current) : Wednesday, the 1st March A.D. 1021.
 No. 5 (Vol. IV. p. 69).—Year 31 (for 21),¹ Śaka 954 : Monday, the 23rd October A.D. 1032.
 No. 33 (Vol. VI. p. 21).—Year 22, Śaka 955 : Sunday, the 25th November A.D. 1033.
 No. 34 (Vol. VI. p. 21).—Year 26, Śaka 959. This date is incorrect.

C.—Rājādhirāja Rājakēsarivarman.

(Between the 15th March and the 3rd December A.D. 1018.)

- No. 15 (Vol. IV. p. 218).—Year [3]2 (for 22) : Thursday, the 22nd November A.D. 1020.
 No. 12 (Vol. IV. p. 216).—Year 26 : Wednesday, the 14th March A.D. 1044.
 No. 13 (Vol. IV. p. 217).—Year 27 : Wednesday, the 13th February A.D. 1045.
 No. 14 (Vol. IV. p. 217).—Year 29 : Wednesday, the 3rd December A.D. 1046.²
 No. 11 (Vol. IV. p. 216).—Year 30, Śaka 970 (current). The date does not admit of verification.
 No. 35 (Vol. VI. p. 22).—Year 35, Śaka 975 : probably Sunday, the 23rd May A.D. 1023.³

D.—Rājēndradēva Parakēsarivarman.⁴

(The 28th May A.D. 1052.)

- No. 38 (Vol. VI. p. 24).—The 82nd day of year 4 : Thursday, the 17th August A.D. 1055.
 No. 36 (Vol. VI. p. 23).—Year 6, Śaka 979 : Monday, the 27th October A.D. 1057.
 No. 37 (Vol. VI. p. 23).—Year 12 (for 11 ?), Śaka 984. The date does not admit of verification.

E.—Kulōttuṅga-Chōla I. Rājakēsarivarman.(Between the 14th March and the 8th October A.D. 1070.)⁵

- No. 56 (Vol. VII. p. 1).—Year 4 : Thursday, the 7th November A.D. 1073.
 No. 39 (Vol. VI. p. 278).—Year 7, Śaka 998 : Friday, the 10th February A.D. 1077.⁶
 No. 6 (Vol. IV. p. 70).—Year 37, Śaka 1030 (for 1028 ?). The date does not admit of verification.
 No. 9 (Vol. IV. p. 72).—Śaka 1035 : Sunday, the 22nd February A.D. 1114.
 No. 7 (Vol. IV. p. 70).—Year 44 : Friday, the 13th March A.D. 1114.
 No. 8 (Vol. IV. p. 71).—Year 45 : Thursday, the 8th October A.D. 1114.

¹ See Vol. VI. p. 22.In the original date the second *tithi* (*dvitigaityam*) is wrongly quoted instead of the third (*tritiyaityam*).² In the original date the 13th *tithi* has probably been wrongly quoted instead of the third. Assuming the above to be the true equivalent of the date, Rājādhirāja's reign would have commenced after (approximately) the 23rd May A.D. 1018.³ In No. 37 surnamed Rājakēsarivarman.⁴ If the dates 5 and 6 given by Dr. Hultzsch above, Vol. VI. p. 221, from No. 389 and No. 386 of 1898 can be trusted—and I see no reason to suspect them—the king's reign must have commenced on approximately the 9th June A.D. 1070. The first day of his 37th year would have been the 9th June A.D. 1108, and the 289th day of that year the 24th March A.D. 1107, which was the day of the Mēsha-(Vishuva-)sankrānti and Chaitra-radi 13 of Śaka 1029 expired.⁵ In the original date the month Māgha is wrongly quoted instead of Phālguna.

- No. 40 (Vol. VI. p. 279).—Year 45, Śaka 1036: Wednesday, the 9th December A.D. 1114.¹
 No. 26 (Vol. V. p. 48).—Year 48: Monday, the 7th January A.D. 1118.
 Nos. 20 and 28 (Vol. IV. p. 262, and Vol. V. p. 198).—Year 48: Friday, the 25th January A.D. 1118.²

F.—Vikrama-Chôla Parakêsarivarman.

(The 29th June A.D. 1118.)

- No. 21 (Vol. IV. p. 263, and Vol. VII. p. 3).—Year 4: Monday, the 1st May A.D. 1122.
 No. 22 (Vol. IV. p. 264, and Vol. VII. p. 3).—Year 5: Monday, the 31st July A.D. 1122.
 No. 57 (Vol. VII. p. 3).—Year 5: Thursday, the 31st May A.D. 1123.
 No. 10 (Vol. IV. p. 73, and Vol. VII. p. 4).—The 340th day of year 5: Sunday, the 3rd June A.D. 1123.³
 No. 42 (Vol. VI. p. 280).—Year 9, Śaka 1049: the 27th May A.D. 1127.
 No. 59 (Vol. VII. p. 5).—Year 10: Sunday, the 15th April, or Saturday, the 14th April, A.D. 1128.⁴
 No. 58 (Vol. VII. p. 4).—Year 11: Saturday, the 5th January A.D. 1129.
 No. 41 (Vol. VI. p. 279, and Vol. VII. p. 3).—Year 16: Monday, the 16th April A.D. 1134.
 No. 43 (Vol. VI. p. 281, and Vol. VII. p. 5).—Year 17, Śaka 1054 (for 1057): Thursday, the 18th April A.D. 1135.

G.—Kulôttunga-Chôla III. Parakêsarivarman.

(Between the 8th June and the 8th July A.D. 1178.)

- No. 23 (Vol. IV. p. 264).—Year 8: Monday, the 8th July A.D. 1185.
 No. 19 (Vol. IV. p. 220).—Year 12: Monday, the 4th December A.D. 1189.
 No. 60 (Vol. VII. p. 6).—Year 14: Thursday, the 2nd January A.D. 1192.⁵
 No. 24 (Vol. IV. p. 265).—Year 16: Saturday, the 4th June A.D. 1194.⁶
 No. 17 (Vol. IV. p. 219).—Year 19: Tuesday, the 12th November A.D. 1196.
 No. 16 (Vol. IV. p. 219).—Year 19 (for 20), Śaka 1119: Friday, the 21st November A.D. 1197.⁷
 No. 31 (Vol. V. p. 199).—Year 20. This date is quite incorrect.
 No. 44 (Vol. VI. p. 281).—Year 27: Thursday, the 5th May A.D. 1205.
 No. 29 (Vol. V. p. 198).—Year 29: Wednesday, the 7th March A.D. 1207.
 No. 18 (Vol. IV. p. 220).—Year 34: Monday, the 19th September A.D. 1211.
 No. 30 (Vol. V. p. 199).—Year 37: Sunday, the 7th June A.D. 1215.

¹ The original date contains the expression *uttardyaṇa-vyāṭpāta-nimittamuna*, the exact import of which here and elsewhere is doubtful.

² In the original date No. 28 the 12th *tithi* is wrongly quoted instead of the second which is correctly given in No. 20.

³ In the original date the 7th *tithi* (*saptamiyugam*) is wrongly quoted instead of the 8th (*ashṭamiyugam*).

⁴ In the original date either the *nakshatra* or the week-day is quoted incorrectly.

⁵ In the original date the first fortnight is wrongly quoted instead of the second.

⁶ In the original date the 4th *tithi* is wrongly quoted instead of the 14th.

⁷ In the original date the 15th solar day is wrongly quoted instead of the 25th.

H.—Rājarāja III. Rājakēsarivarman.¹(Between the 17th March and the 18th August A.D. 1216.)²

- No. 45 (Vol. VI. p. 281).—Year opposite to 16 : Saturday, the 25th September A.D. 1232.
 No. 46 (Vol. VI. p. 282).—Year 17 : Tuesday, the 18th January A.D. 1233.
 No. 47 (Vol. VI. p. 282).—Year 18 : Tuesday, the 23rd August A.D. 1233.
 No. 48 (Vol. VI. p. 282).—Year 18 : Wednesday, the 7th December A.D. 1233.
 No. 49 (Vol. VI. p. 283).—Year 18 : Monday, the 2nd January A.D. 1234.
 No. 50 (Vol. VI. p. 283).—Year 19 : probably Sunday, the 13th August A.D. 1234.³
 No. 51 (Vol. VI. p. 284).—Year 22 : Tuesday, the 16th March A.D. 1238.⁴
 No. 52 (Vol. VI. p. 284).—Year opposite to 22 : Monday, the 28th February A.D. 1239.
 No. 53 (Vol. VI. p. 284).—Year opposite to 22 : Wednesday, the 2nd March A.D. 1239.
 No. 54 (Vol. VI. p. 285).—Year opposite to 22 : Friday, the 4th March A.D. 1239.⁴

To the above I may add that, between A.D. 1054 and 1069, the date of the fifth year (of the reign) of Virarājendra Rājakēsarivarman, which occurs in *South-Ind. Inscr.* Vol. III. No. 30, is correct only for Monday, the 10th September A.D. 1067,⁵ and that therefore, if the date does fall within the sixteen years stated and has been correctly recorded, Virarājendra Rājakēsarivarman must have commenced to reign between (approximately) the 11th September A.D. 1062 and the 10th September A.D. 1063.

POSTSCRIPT.

Date of the Chellūr plates of Kulōttunga-Chōḍa II.

In the text of these plates, published by Dr. Fleet with a photo-lithograph in *Ind. Ant.* Vol. XIV. p. 56 ff., the date, in lines 49-51, is given thus:—

Śāk-ābdānām pramāṇē rasa-viśikha-viyach-chaandra-saṁkhyān prayātē . . . s-Ādrā-rakshē pūrvva-ma(pa)kshē vishuvati su-tithā(than)—

i.e. "when the measure of the Śaka years had advanced to the number of the flavours (6), the arrows (5), the sky (0), and the moon (1),"—i.e. in Śaka-Saṁvat 1056 — . . . "at the equinox combined with the Ādrā nakshatra, in the bright half, on an excellent tithi."

In *Ind. Ant.* Vol. XX. p. 191, Dr. Fleet has shown that this date would be incorrect for Śaka-Saṁvat 1056 current and expired, as well as for Śaka-Saṁvat 1057 expired; and he has communicated a suggestion of Mr. Sh. B. Dikshit's, in accordance with which the date would correspond to the 24th March A.D. 1132, in Śaka-Saṁvat 1055 current. But really the date would be incorrect even for Śaka-Saṁvat 1055 current, because in this year also the equinox was not combined with the Ādrā nakshatra.

In the twenty Śaka years from 1047 to 1066 the date is correct only for Śaka-Saṁvat 1065 expired. In this year the Mēsha-vishuva-saṁkrānti took place 16 h. 37 m. after mean sunrise

¹ This surname occurs only in the date No. 45.

² The latest date of this Rājarāja, known to me, is from the month of Karkāṭaka of his 28th year which was current after the Śaka year 1165; see *South-Ind. Inscr.* Vol. I. No. 64. This date would show that Rājarāja's reign could not have commenced after the last day of the month of Karkāṭaka in A.D. 1216, i.e. not later than the 27th July A.D. 1216.

³ In the original date either the nakshatra Uttaraṣṭādi (Uttara-Bhādrapadā) has been wrongly quoted instead of Uttirām (Uttara-Phalguni), or the first fortnight instead of the second.

⁴ In the original date the 4th tithi has been wrongly quoted instead of the 14th.

⁵ The day was the 15th day of the month of Kanyā, and on it the 14th tithi of the dark half (of the month Bhādrapadā) ended 9 h. 21 m. after mean sunrise; the nakshatra was Uttara-Phalguni, by the Brahma-siddhānta for 21 h. 40 m. after mean sunrise, according to Garga the whole day, and by the equal space system from 0 h. 39 m. after mean sunrise.

of the 24th March A.D. 1143, and on this day the 7th *tithi* of the bright half of Chaitra commenced 8 h. 9 m., and the *nakshatra* by the equal space system was Ârdra for 23 h. 48 m., after mean sunrise; i.e. the equinox took place while the moon was in the *nakshatra* Ârdra, during the 7th *tithi* of the bright half. This result, moreover, shows that the *tithi* on the day now given by me was really, in agreement with the term *su-tithi* of the original text, an excellent *tithi*; for, a seventh *tithi* of the bright half, on which — as is the case in the present instance — a Samkrânti takes place, is called *Mahâjayâ*, and for making donations is superior even to an eclipse.¹

For these reasons I have no doubt whatever that the 24th March A.D. 1143 is the proper equivalent of the date, and that the Śaka year intended is 1065, not 1056. The writer of the date has wrongly written *rasa-viśikha*-, instead of *viśikha-rasa*-.

NO. 2.—DATES OF PANDYA KINGS.

By F. KIELHORN, PH.D., LL.D., C.I.E.; GÖTTINGEN.

(Continued from Vol. VI. page 315.)

I herewith publish thirteen more Pāṇḍya dates, the European equivalents of which may be given with certainty. Eight of these dates, in addition to regnal years, also give the Śaka years in which the dates fell, and the three latest dates, Nos. 41-43, also quote the corresponding Jovian years, according to the southern luni-solar system. I have still a number of other dates — of apparently twelve different Pāṇḍya kings — the publication of which may be deferred to the time when more dates of the same kings have been discovered.²

A.—VIRA-PANDYA.

31.—In the Kailāsapati temple at Śrivaikunṭham.³

2 śrī-Vi(vi)ra-Pāṇḍiyadē[va]ṛkku yâ-
3 ṇḍu lṣvadu Kâ[r*]tt[i]gai-mâ[da*]ttu 13 tiyad[i]yum apara-pakshattu
saptam[i]yum Viyâḷa-kkiḷamaiyum peṇṇa Magattu nâḷ.

“In the 15th year (of the reign) of the glorious Vira-Pāṇḍyadēva,— on the day of Maghâ, which corresponded to a Thursday, and to the seventh *tithi* of the second fortnight, and to the 13th solar day of the month of Kārttigai.”

Between A.D. 1200 and 1500 the only year for which this date would be correct, is 1267. In this year the Vṛ̥schika-samkrânti took place 13 h. 33 m. after mean sunrise of Friday, the 28th October. The 13th day of the month of Vṛ̥schika (or Kārttigai) therefore was Thursday, the 10th November A.D. 1267; and on this day the 7th *tithi* of the dark half (of the month Kārttika) ended 8 h. 9 m., and the *nakshatra* was Maghâ, by the equal space system for 19 h. 42 m., by the Brahma-siddhânta for 5 h. 16 m., and according to Garga for 7 h. 53 m., after mean sunrise.

¹ Compare *Ind. Ant.* Vol. XXVI. p. 178.

² The date No. 32, here published, has been sent to me by Dr. Hultzsch quite recently. It proves the correctness of the equivalent which I had previously ascertained for the date No. 31, but which for want of confirmation I did not wish to publish with my first series of Pāṇḍya dates.

³ No. 174 of the Government Epigraphist's collection for 1895.

32.—In the Akshêśvara temple at Achcharapâkkam.¹

- 1 Svasti śrī [||*] Tribhuvaṇach[cha]kra[va]ttiga[!] śr[ī]-Vi[ra]-Pāṇḍi[ya]dēvaṛkku
[y]āṇḍu 7[va]du Kaṛkaḍaga-ṇāyaṛṛu apa[ra]-pakshattu N[ā]-
2 yaṛṛu-k[i]lamai[yu]m saptamiyum peṛṛa Aśvati-ṇā[!].

“In the 7th year (*of the reign*) of the emperor of the three worlds, the glorious **Vira-Pāṇḍyadēva**,— on the day of **Aśvini**, which corresponded to a **Sunday** and to the seventh *tithi* of the second fortnight of the month of **Karkaṭaka**.”

If the equivalent found for the date No. 31, which is of the 15th year of the king's reign, is the true equivalent of that date, this date No. 32, which is of the 7th year of the same reign, will in the first instance be expected to fall in A.D. 1259. The date actually corresponds to **Sunday, the 13th July A.D. 1259**, which was the 17th day of the month of **Karkaṭaka**, and on which the 7th *tithi* of the dark half (of the month **Āshāḍha**) ended 11 h. 3 m., and the *nakshatra* was **Aśvini** for 19 h. 3 m., after mean sunrise.

The two dates Nos. 31 and 32 together shew that the reign of **Vira-Pāṇḍya** commenced between (approximately) the 11th November A.D. 1252 and the 13th July A.D. 1253.

B.—MARAVARMAN PARAKRAMA-PANDYA.

33.—In the Rishabhêśvara temple at Śeṅgama.²

- 1 Svasti śrīh [||*] Śakā[bda][m*] 1262ṇ mēl kō Mārappaṇmar T[i]ru(ri)bu-
[va*]ṇasakravattigaḷ śrī-Parākrama-Pāṇḍiyadēvaṛkku yāṇḍu 6[vadu] Vṛiś-
chika-nāyaṛṛu pūrvva-pakshattu dvādaśiyum Budan-ki[lamaiyum peṛṛa*]
2 Uttaraṭṭādi-n[ā][!].

“After the Śaka year 1262 (*had passed*), in the 6th year (*of the reign*) of king **Māravarman** (*alias*) the emperor of the three worlds, the glorious **Parākrama-Pāṇḍyadēva**,— on the day of **Uttara-Bhadrpadā**, which corresponded to a **Wednesday** and to the twelfth *tithi* of the first fortnight of the month of **Vṛiśchika**.”

For Śaka-Saṃvat 1262 expired this date regularly corresponds to **Wednesday, the 1st November A.D. 1340**, which was the 5th day of the month of **Vṛiśchika**, and on which the 12th *tithi* of the bright half (of the month **Kārttika**) ended 22 h. 56 m., and the *nakshatra* was **Uttara-Bhadrpadā** for 1 h. 19 m., after mean sunrise.

34.—In the Kailāsanātha temple at Maṇṇārguḍi.³

- 1 Svast[i] śr[i] [||*] Kō [M]ārapaṇmar Tr[i]bhu[va]nachakra[vatti]gaḷ [śrī]-
Parākrama-Pā[ṇ]ḍiyadēvaṛkku yā[ṇ]ḍu Svadu] Dhanu-[n]āyaṛṛu apara-
pakshattu navamiyu[m] V[e]ḷli-kk[i]lam[ai]yum peṛ[ṛa]
2 Attattu nāḷ.

“In the [8th] year (*of the reign*) of king **Māravarman** (*alias*) the emperor of the three worlds, the glorious **Parākrama-Pāṇḍyadēva**,— on the day of **Hasta**, which corresponded to a **Friday** and to the ninth *tithi* of the second fortnight of the month of **Dhanu**.”

If this date were one of the 8th year of the king's reign, it ought, in accordance with the result obtained under No. 33, to fall in Śaka-Saṃvat 1263 or 1264 expired; but for either of these years it would be incorrect. The date, in my opinion, is really one of the 18th (*not* the 8th)

¹ No. 243 of the Government Epigraphist's collection for 1901.

² No. 113 of the Government Epigraphist's collection for 1900.

³ No. 100 of the Government Epigraphist's collection for 1897.

year of the king's reign and corresponds—for Śaka-Saṃvat 1274 expired—to Friday, the 30th November A.D. 1352, which was the 4th day of the month of Dhanus, and on which the 9th *tithi* of the dark half (of the month Mārgaśīrsha) commenced 0 h. 17 m., and the *nakshatra* was Hasta, by the Brahma-siddhānta from 0 h. 39 m., and by the equal space system and according to Garga from 2 h. 38 m., after mean sunrise.

The two dates Nos. 33 and 34 would shew that the reign of Māra-varman Parākrama-Pāṇḍya commenced between (approximately) the 1st December A.D. 1334 and the 1st November A.D. 1335.

C.—JATAVARMAN PARAKRAMA-PANDYA.

35.—In the Chōlēsvara temple at Chōlapuram near Nagercoil.¹

- 1 ॐ Svasti śrī [i*] Śakābdam 1293ṇ mēl
- 3 śr[i-k]ō=Chchaḍaipanmar=āṇa Tribhuvana-
- 4 chchakravartigaḥ śrī-Parākrama-Pāṇḍiyadēvar iyāṇḍu añjā-
- 5 vadiṇ edir pattāvadu Makara-ñāyirru pūrvva-pakshattu tṛiti(tī)yai-
- 6 yum Vell[i]-kki[ā]m[aiyum] peṇṇa Śadaiyattiṇ nāl.

"After the Śaka year 1293 (*had passed*), in the tenth (*year*) opposite to the fifth year (*of the reign*) of the glorious king Jata-varman *alias* the emperor of the three worlds, the glorious Parākrama-Pāṇḍyadēva,—on the day of Śatabhishaj, which corresponded to a Friday and to the third *tithi* of the first fortnight of the month of Makara."

For Śaka-Saṃvat 1293 expired this date regularly corresponds to Friday, the 9th January A.D. 1372, which was the 14th day of the month of Makara, and on which the third *tithi* of the bright half (of the month Māgha) ended 19 h. 59 m., and the *nakshatra* was Śatabhishaj, by the equal space system for 20 h. 21 m., according to Garga for 11 h. 50 m., and by the Brahma-siddhānta for 9 h. 12 m., after mean sunrise.

Being of the 10th opposite to the 5th, *i.e.* of the 15th year of the king's reign, the date would shew that the reign of Jata-varman Parākrama-Pāṇḍya commenced between (approximately) the 10th January A.D. 1357 and the 9th January A.D. 1358.

D.—JATILAVARMAN PARAKRAMA-PANDYA (ARIKESARIDEVA).

36.—In the Kuttalanātha temple at Kuttālam.²

- 1 Śakābdam 1377 mēl [ś]ellāniṇṇa
- Parākkira[ma*]-Pāṇḍyadēvarṅku yāṇḍu 31vadiṇ edir y[i]raṇḍāvadu
- Mi(mi)ṇa-jūāyarru irubattettān=diyadiyum pūrvva-pakshat[t]u shashayam³ Tiṅgaṭ-
- [k]ilamaiya(yu)m [pe]ṇṇa Mṛigaś[ir]shattu n[āl].

"In the second (*year*) opposite to the 31st year (*of the reign*) of Parākrama-Pāṇḍyadēva, which was current after the Śaka year 1377 (*had passed*),—on the day of Mṛigaśīrsha, which corresponded to a Monday, and to the sixth *tithi* of the first fortnight, and to the twenty-eighth solar day of the month of Mīna."

In solar Śaka-Saṃvat 1377 current the Mīna-saṃkrānti took place 1 h. 30 m. after mean sunrise of Tuesday, the 25th February A.D. 1455, which was the first day of the month of Mīna. The 28th day of the month of Mīna therefore was Monday, the 24th March A.D. 1455; and on this day the 6th *tithi* of the bright half (of the month Chaitra of luni-solar Śaka-Saṃvat 1377 expired) ended 15 h. 44 m., and the *nakshatra* was Mṛigaśīrsha, by the equal

¹ No. 30 of the Government Epigraphist's collection for 1896.

No. 203 of the Government Epigraphist's collection for 1895.

³ Read *shashthiyum*.

space system and according to Garga for 10 h. 30 m., and by the Brahma-siddhanta for 9 h. 12 m., after mean sunrise.

37.—In the Viśvanātha temple at Tenkāśi.¹

- 1 Svasti śrī [||*] Kō Jaṭilavarmanmar=āṇa Tribhuvanaścha(cha)kravarttiḡaḡ śrī-Parākrama-Pāṇḍyadēvaḡku yāṇḡu muppattonṡāvaḡḡ edirāvaḡu Ka[r]kkataka-ñāyayru irubattontṡān=diyadiyum pūrvva-pakshattu chcha(cha)turdasiyum Tiṅgaḡ-kiḡamaiyum peṡṡa Uttirāḡattu nāḡ.

“(In the year) opposite to the thirty-first year (of the reign) of king Jaṭilavarman *alias* the emperor of the three worlds, the glorious Parākrama-Pāṇḍyadēva,—on the day of Uttarāśhāḡhā, which corresponded to a Monday, and to the fourteenth *tithi* of the first fortnight, and to the twenty-first solar day of the month of Karkataka.”

Judging by the preceding date, this date would be expected to fall in about A.D. 1454; in my opinion, it corresponds to the 19th July A.D. 1453. In A.D. 1453 the Karkata-samkrānti took place 19 h. 36 m. after mean sunrise of the 28th June. The 21st day of the month of Karkataka therefore was the 19th July; and on this day the 14th *tithi* of the bright half (of the month Śrāvaṇa) ended 14 h. 14 m., and the *nakshatra* was Uttarāśhāḡhā, by the equal space system and according to Garga for 18 h. 24 m., and by the Brahma-siddhanta for 11 h. 50 m., after mean sunrise. But the day found was a Thursday, *not* a Monday.—Since in the whole of the 15th century A.D. there is not a single year for which the date, as recorded by the writer, would be correct, I take Thursday, the 19th July A.D. 1453, to be its proper equivalent, and have no doubt that the writer has quoted the week-day incorrectly.

38.—In the Kuttālanātha temple at Kuttālam.²

- 1 Svasti śrī [||*] Kō [Ś]edilavanmar=ā[na] Tribhuvana[cha]kravatt[i]ḡaḡ śr[i]-Parākk[i]rama-Pāṇḡi[yad]ēvaḡku yāṇḡu muppattonṡ[ā]vaḡḡ edir nā[l]ā[va]du Mi(mi)ṇa-ñāyayru iru[badān=diya]di[yu]m [apa]ra-[pa]kshattu pañchamiy[u]m Budan-kiḡamaiyum peṡṡa Anisha[ti=n]āḡ.

“In the fourth (year) opposite to the thirty-first year (of the reign) of king Jaṭilavarman *alias* the emperor of the three worlds, the glorious Parākrama-Pāṇḍyadēva,—on the day of Anurāḡhā, which corresponded to a Wednesday, and to the fifth *tithi* of the second fortnight, and to the twentieth solar day of the month of Mīna.”

Judging by the preceding dates, this date would be expected to fall in about A.D. 1457; it actually corresponds to Wednesday, the 16th March A.D. 1457. In A.D. 1457 the Mīna-samkrānti took place 13 h. 55 m. after mean sunrise of Thursday, the 24th February. The 20th day of the month of Mīna therefore was Wednesday, the 16th March; and on this day the 5th *tithi* of the dark half (of the month Phālguna) ended 10 h. 25 m., and the *nakshatra* was Anurāḡhā, by the equal space system and according to Garga for 4 h. 36 m., and by the Brahma-siddhanta for 0 h. 39 m., after mean sunrise.

39.—In the Viśvanātha temple at Tenkāśi.³

- 1 Sakābdam āyirattu-muṡṡūru-enbattu-onṡiṡ mēṡ=chellāniṡṡa
Ar[i]keśar[i]dēvar=āṇa Parākkirama-Pāṇḡiyadēvaḡku yāṇḡu 31[vadu] edir
Svadu Miduṇa-ñāyayru irubattumu(mū)-

¹ No. 195 of the Government Epigraphist's collection for 1895.

² No. 204 of the Government Epigraphist's collection for 1895.

³ No. 199 of the Government Epigraphist's collection for 1895.

- 2 $\eta\eta\eta\eta$ =diyadiyum $p\acute{u}ruva$ -pakshattu=tde(tta) \acute{s} amiyummyum¹ Budan- $k\acute{i}$ lamaiyum $pe\eta\eta$
 \acute{S} odi-nāḷ.

"In the 8th (year) opposite to the 31st year (of the reign) of Arikēsariḍēva alias Parākrama-Pāṇḍyadēva, which was current after the Śaka year one thousand three hundred and eighty-one (*had passed*),—on the day of Svāti, which corresponded to a Wednesday, and to the tenth *tithi* of the first fortnight, and to the twenty-third solar day of the month of Mithuna."

The three dates Nos. 36-38 shew that the reign of Jaṭilavarman Parākrama-Pāṇḍya commenced between (approximately) the 25th March and the 19th July A.D. 1422. A date of the month of Mithuna of the 8th year opposite to the 31st year, i.e. of the 39th year, of the same reign should therefore fall in either A.D. 1460 or 1461. Now assuming this date No. 39 to be really one of the 39th regnal year, its proper equivalent could only be Wednesday, the 17th June A.D. 1461. On this day the 10th *tithi* of the bright half (of the month Āshāḍha) ended 17 h. 51 m., and the *nakshatra* was Svāti, by the equal space system for 19 h. 42 m., by the Brahma-siddhānta for 3 h. 17 m., and according to Garga for 7 h. 13 m., after mean sunrise. But the 17th June A.D. 1461 was the 21st (not the 23rd) day of the month of Mithuna,² and fell in Śaka-Saṃvat 1383 (not 1381) expired.

No better result would be obtained if we were to assume the writer to have quoted the Śaka year correctly and the regnal year incorrectly. Śaka-Saṃvat 1381 *expired* would yield no satisfactory result at all. For Śaka-Saṃvat 1381 *current* the date might be said to correspond to Wednesday, the 21st June A.D. 1458, on which day the 10th *tithi* of the bright half (of the month Āshāḍha) ended 15 h. 35 m., and the *nakshatra* was Svāti, by the equal space system for 10 h. 30 m., after mean sunrise. But the 21st June A.D. 1458 was the 24th (not the 23rd) day of the month of Mithuna³ (and would fall in the 36th or 37th, not the 39th year of the king's reign).

The date therefore is certainly incorrect; but I have hardly any doubt that its incorrectness is caused by the writer's interchanging the last figures of the numbers of the Śaka year and of the solar day (i.e. by his giving us erroneously 1381 instead of 1383, and 23 instead of 21), and that the day intended is Wednesday, the 17th June A.D. 1461. And accepting this result as correct, it would follow that the king's reign commenced between (approximately) the 18th June and the 19th July A.D. 1422.

E.—JATILAVARMAN PARAKRAMA-PANDYA (KULASEKHARA).

40.—In the Viśvanātha temple at Tenkāṣi.⁴

- 1 Śubham=astu [$\eta\eta$] Śakābdam 1421ḷ mēḷ śellāṇṇa [$\eta\eta$] svasti \acute{s} ri [$\eta\eta$] Kō
 Jaṭilavarman=āna Tribhuvanachchakravattigaḷ Kā[r*]ttigai-nāḷ piṇḍa
 Parākki[r*]ma-Pāṇḍiyadēvar
 2 āṇa Kulasēgaradēvar nam yāṇḍu irubadāvadu Virichchiga-nāyaru paṇḍiṇḍāna
 diyadiyum \acute{p} ūrvava-pakshattu dvādaśiyum Bṛihaspati-vāramum $pe\eta\eta$
 3 Rēba(va)ti-nāḷ.

"In the twentieth year (of the reign) of king Jaṭilavarman alias the emperor of the three worlds, Parākrama-Pāṇḍyadēva alias Kulasēkharadēva who was born on the day of Kṛittikā, which (year) was current after the Śaka year 1421 (*had passed*),—on the day of Rēvati, which corresponded to a Thursday, and to the twelfth *tithi* of the first fortnight, and to the fifteenth solar day of the month of Vṛiśchika."

¹ Cancel the second yum .

² In A.D. 1461 the Mithuna-saṃkrānti took place 6 h. 41 m. after mean sunrise of Thursday, the 28th May.

³ In A.D. 1458 the same Saṃkrānti took place 12 h. 4 m. after mean sunrise of Sunday, the 28th May.

⁴ No. 197 of the Government Epigraphist's collection for 1895.

⁵ Read \acute{p} āruva.

In Śaka-Samvat 1421 expired the Vṛiśchika-samkrānti took place 13 h. 53 m. after mean sunrise of Wednesday, the 30th October A.D. 1499. The 15th day of the month of Vṛiśchika therefore was Thursday, the 14th November A.D. 1499, and on this day the 12th *tithi* of the bright half (of the month Mārgaśīrsha) ended 16 h. 13 m. after mean sunrise. On the day found the *nakṣatra* by our Tables ceased to be Rêvatî exactly at mean sunrise, but it may be reasonably assumed that by other Tables the moon continued in Rêvatî for some short time after mean sunrise.

Being of the 20th year of the king's reign, the date would shew that the reign of Jaṭilavarman Parākrama-Pāṇḍya Kulasêkhara commenced between (approximately) the 15th November A.D. 1479 and the 14th November A.D. 1480.

F.—JATILAVARMAN SRIVALLABHA.

41.—In the Viśvanātha temple at Tenkāsi.¹

- 2 Śakābdam āyirattu-nānūṟṟu-aṇbattu-aṇbadil mēṟ=chellāniṟṟa
 4 kō Jaṭilavarmmar=āna Tribhuvanachchakrava[r]tti Kōnērmaikoṇḍā[ā]ṇ
 5 Perumāḷ Śrīvallabhadēva[r]ku yāṇḍu mu(mū)ṇṟāvadu [Ē]vilāmbi-va[r]sham
 Vṛiśchika-[ravi iruba]t[tu]-aṇbadā[n]=diyadiyum [a]para-pakshattu [ē]kā[da]siy-
 6 m Budha-vāramum peṟṟa Śōdi-nāḷ.

“In the [H]ēvilambin year, the third year (of the reign) of king Jaṭilavarman alias the emperor of the three worlds, Kōnērmaikoṇḍāṇ Perumāḷ Śrīvallabhadēva, which (year) was current after the Śaka year one thousand four hundred and fifty-nine (*had passed*),—on the day of Svāti, which corresponded to a Wednesday, and to the eleventh *tithi* of the second fortnight, and to the twenty-ninth solar day of (*the month in which*) the sun (*was*) in Vṛiśchika.”

The Jovian year Hēvilambin (Hēmalamba) by the southern luni-solar system corresponds to Śaka-Samvat 1459 expired. In this year the Vṛiśchika-samkrānti took place on Tuesday, the 30th October A.D. 1537, by the Ārya-siddhānta 9 h. 48 m., and by the Sūrya-siddhānta 12 h. 30 m., after mean sunrise. By the Sūrya-siddhānta therefore—and by the Ārya-siddhānta also in case the Malabar rule was followed²—the month of Vṛiśchika commenced on the 31st October, and the 29th day of that month was Wednesday, the 28th November A.D. 1537. On this day the 11th *tithi* of the dark half (of the month Mārgaśīrsha) ended 9 h. 34 m. after mean sunrise, and the *nakṣatra* was Svāti, by the equal space system during the whole day, by the Brahma-siddhānta for 9 h. 12 m., and according to Garga for 13 h. 8 m., after mean sunrise.

Being of the third year of the king's reign, the date would shew that the reign of Jaṭilavarman Śrīvallabha commenced between (approximately) the 29th November A.D. 1534 and the 28th November A.D. 1535.

G.—MARAVARMAN SUNDARA-PANDYA.

42.—In the Kailāsapati temple at Gaṅgaikoṇḍāṇ.³

- 1 Svasti śrī [i*] Kō Māra[vaṇ]mar=āṇa Tribhuvanachśa(cha)kravat[t]i
 Kōnērmaikoṇḍā[ā]ṇ śrī-Śundara-Pāṇḍiyadēva[r]ku yāṇḍu 2 āvadu edir
 22āvadukku Śakābda[m*] 1477ṇ mēḷ sellān[i]ṇṟa Irākshasa-varusham
 Āṇi-mādam⁴ 3 tēdi⁴ pū[rva]-pakshattu
 2 duvādeṣiyum [Manda]-vāramum peṟṟa Śōdi-nāḷ.

¹ No. 200 of the Government Epigraphist's collection for 1895.

² See Sewell and Dikshit's *Indian Calendar*, p. 12.

³ No. 171 of the Government Epigraphist's collection for 1895.

⁴ The two words *mādam* and *tēdi* are expressed by their modern abbreviations.

"In the **Rākshasa** year which was current after the Śaka year 1477 (*had passed*), (*and which corresponded*) to the 22nd (*year*) opposite to the 2nd year (*of the reign*) of king **Māra-varman** *alias* the emperor of the three worlds, **Kōṇērmaikondān**, the glorious **Sundara-Pāṇḍyadeva**,—on the day of Svāti, which corresponded to a **Saturday**, and to the twelfth *tithi* of the first fortnight, and to the 3rd solar day of the month of Āṇi."

The Jovian year **Rākshasa** by the southern luni-solar system corresponds to Śaka-Samvat 1477 expired. In this year the Mithuna-samkrānti took place 14 h. 16 m. after mean sunrise of Wednesday, the 29th May A.D. 1555, and the third day of the month of Mithuna (or Āṇi) therefore was **Saturday**, the 1st June A.D. 1555. This day was entirely occupied by the 12th *tithi* of the bright half (of the month Jyāishṭha), and on it the *nakshatra* by the equal space system was Svāti for 11 h. 10 m. after mean sunrise.

Being of the 22nd opposite to the 2nd, i.e. of the 24th year of the king's reign, the date would shew that the reign of this **Māra-varman Sundara-Pāṇḍya** commenced between (approximately) the 2nd June A.D. 1531 and the 1st June A.D. 1532.

H.—JATILAVARMAN SRIVALLABHA (ATIVIRARAMA).

43.—In the Kulasēkharamudaiyār temple at Tenkāśi.¹

- 2 Śakā[bda]m 1489 l mēl śellāṇiṅṅa [*] svasti śrī [*] Kō
 Jaṭilava[r]mmar-āna Tribhuvanachchakrava[r]tt[i] Kōṇērmai[k]o[ṇ]ḍāṇ
 Śrī-[P]erumā[!]
 3 Aḷagaṇ-Perumā! Ativirarāmaṇ Śrīva[*]labha[d]ēvaṅku yāṇḍu aṇ[j]āvaḍu
 Piṇḍava-varuṣham² Āvaṇ[i]-mādam² 22 tēdi² apara-[pa]kshastu(ttu)
 4 tiṇḍigaiyūm Śukk[i]ṇa-vāramum Keṇḍa-[yō]gamum Vaṇik-karaṇamum perṇa
 Uttirattādi-nāḷ.

"In the **Prabhava** year (*corresponding to*) the fifth year (*of the reign*) of king **Jaṭilavarman** *alias* the emperor of the three worlds, **Kōṇērmaikondān** **Śrī-Perumāḷ Aḷagaṇ-Perumāḷ Ativirarāma Śrīvallabhadēva**, which (*year*) was current after the Śaka year 1489 (*had passed*),—on the day of **Uttara-Bhādrapadā**, which corresponded to the **Vaṇik-karaṇa** and to the **Gaṇḍa-yōga** and to a **Friday**, and to the third *tithi* of the second fortnight, and to the 22nd solar day of the month of Āvaṇi."

The Jovian year **Prabhava** by the southern luni-solar system corresponds to Śaka-Samvat 1489 expired. In this year the Simha-samkrānti took place 18 h. 35 m. after mean sunrise of Thursday, the 31st July A.D. 1567, and the 22nd day of the month of Simha (or Āvaṇi) therefore was **Friday**, the 22nd August A.D. 1567. On this day the third *tithi* of the dark half (of the month Bhādrapadā) ended 20 h. 28 m., the *karaṇa* **Vaṇij** ended 8 h. 43 m., the *nakshatra* was **Uttara-Bhādrapadā** for 1 h. 19 m., and the *yōga* was **Gaṇḍa** for 11 h. 37 m., after mean sunrise.

Being of the 5th year of the king's reign, the date would shew that the reign of **Jaṭilavarman Ativirarāma Śrīvallabha** commenced between (approximately) the 23rd August A.D. 1562 and the 22nd August A.D. 1563.

For convenience of reference I subjoin a list of the above dates, with the approximate commencement of the reign of each king, put in brackets after his name.

¹ No. 202 of the Government Epigraphist's collection for 1895.

² The three words *varuṣham*, *mādam* and *tēdi* are expressed by their modern abbreviations.

A.—Vira-Pāṇḍya (November 11, A.D. 1252—July 13, A.D. 1253).

No. 32. 7th year : July 13, A.D. 1259.

No. 31. 15th year : November 10, A.D. 1267.

B.—Māravarman Parākrama-Pāṇḍya (December 1, A.D. 1334—November 1, A.D. 1335).

No. 33. 6th year (Śaka 1262) : November 1, A.D. 1340.

No. 34. 8th [for 18th] year : November 30, A.D. 1352.

C.—Jaṭavarman Parākrama-Pāṇḍya (January 10, A.D. 1357—January 9, A.D. 1358).

No. 35. Year 10 opp. to 5 (i.e. 15th year ; Śaka 1293) : January 9, A.D. 1372.

D.—Jaṭilavarman Parākrama-Pāṇḍya Arikēsarideva (June 18—July 19, A.D. 1422).

No. 37. [Year] opp. to 31 (i.e. 32nd year) : July 19, A.D. 1453.

No. 36. Year 2 opp. to 31 (i.e. 33rd year ; Śaka 1377) : March 24, A.D. 1455.

No. 38. Year 4 opp. to 31 (i.e. 35th year) : March 16, A.D. 1457.

No. 39. Year 8 opp. to 31 (i.e. 39th year ; Śaka 1381 [for 1383]) : June 17, A.D. 1461.

E.—Jaṭilavarman Parākrama-Pāṇḍya Kulaśékha (November 15, A.D. 1479—November 14, A.D. 1480).

No. 40. 20th year (Śaka 1421) : November 14, A.D. 1499.

F.—Jaṭilavarman Śrīvallabha (November 29, A.D. 1534—November 28, A.D. 1535).

No. 41. 3rd year (Śaka 1459) : November 28, A.D. 1537.

G.—Māravarman Sundara-Pāṇḍya (June 2, A.D. 1531—June 1, A.D. 1532).

No. 42. Year 22 opp. to 2 (i.e. 24th year ; Śaka 1477) : June 1, A.D. 1555.

H.—Jaṭilavarman Śrīvallabha Ativirāma (August 23, A.D. 1562—August 22, A.D. 1563).

No. 43. 5th year (Śaka 1489) : August 22, A.D. 1567.

**No. 3.—AMARAVATI INSCRIPTION OF KRISHNARAYA
OF VIJAYANAGARA ; SAKA-SAMVAT 1437.**

By H. LÜDERS, PH.D. ; GÖTTINGEN.

This inscription,¹ which I edit from inked estampages supplied by Dr. Hultsch, is engraved on a slab in the *Samnyāsīn's* room in the *Amarēśvara* temple at *Amarāvati* in the Kistna district.

It contains 53 lines of writing. The average size of the letters is $\frac{5}{8}$ ". The alphabet is Telugu of the type described in Vol. VI. p. 108 f. *Ka* shows here everywhere the advanced form. *Ḥa* appears twice (ll. 10 and 14) in the older form of the *Biṭṭaṅṅa* and *Vānapalli* plates, but in l. 49 it shows a form which comes nearer to that of the *Maṅgalagiri* inscription. The *ottu* appears in *ḍha* (l. 35) ; in the case of *ḍha* and *bha* it occurs only in a few cases, and it is never

¹ No. 266 of the Government Epigraphist's collection for the year 1897.

found in *kha* and *tha*. As first letter of a group, *r* is represented by the full sign in *ryô* in l. 15 and *rvô* in l. 46. In all other cases the secondary sign has been used. The language is Sanskrit, and, with the exception of the introductory phrase *śubham=astu* in l. 1 and the concluding words *śrī śrī śrī* in l. 53, the whole text is in verse. As regards orthography, it may be noticed that a consonant is doubled after *r* in *dévair=mmathyamān* (l. 7), *kurvan* (l. 22), *sārththā* (l. 24), *-audāryyas* (l. 43), *arththi-sārththa* (l. 48), *kīrtti-dharmmau* (l. 50), after *anusvāra* in *tungga* (l. 1), *Vinikōṇḍaṁ* (l. 32), *Bellakōṇḍaṁ* (l. 32), *-āhittāḍ* (l. 48), and as first letter of a group in *jāta-ppratishṭhān* (l. 28) and *Anarēṣa-pprasādataḥ* (l. 52). The groups *tth* and *dh* are written *thth* and *dhdh*; compare, in addition to the cases cited above, *tadh-dhāma* (l. 4) and *samīdhdhā* (l. 49).

The inscription is one of king **Krishnarāya** of **Vijayanagara**. The greater portion of it consists of verses already known to us from other records.¹ New are only the verses 7, 9, 10 and 12. Verse 7 states that "from him (*i.e.* king Narasa) was born by **Nāgamāmbā** king **Krishnarāya**, who causes pleasure to the world, as the moon, who causes the fragrantcy of the water-lilies, was born from the milk-ocean." Krishnarāya's mother is generally called **Nāgalā**. However, the variant **Nāgāmbikā** is found also in the prose portion of the Hampe and Sankalpūra inscriptions.²

Of greater interest is verse 9, which praises Krishnarāya as him "who, having taken by a forcible attack **Śivanasamudra**, **Udayādri**, **Vinikōṇḍa** and **Bellakōṇḍa**, and having captured alive on the battle-field **Virabhadra**, the son of the **Gajapati** king, took **Koṇḍaviḍu**." This account, although rather meagre, is of considerable importance as being the first epigraphical record of Krishnarāya's warlike exploits up to the conquest of **Koṇḍaviḍu**. The enumeration of the events seems to follow the chronological order. The taking of **Śivanasamudra**, at any rate, appears to have been the first military success in Krishnarāya's career. The ancient city of **Śivanasamudra** is situated on an island between the two great falls of the **Kāvēri**, 9 miles north-east of the modern **Koḷḷēgāl** in the **Coimbatore** district. It belonged at that time to the **Ummatūr** chiefs, who regarded **Somēśvarasvāmin**, whose magnificent temple may still be seen at **Śivanasamudra**, as their family god.³ The **Ummatūr** chiefs were subject to the kings of **Vijayanagara**. The then lord of **Ummatūr** must have revolted against his sovereign; for, quite in accordance with the inscription, a native chronicle relates that, after having first settled the **Drāviḍa** country about **Conjeeveram**, Krishnarāya crushed a refractory **Rāja** in the **Maisūr** country, the **Gaṅga Rāja** of **Ummatūr**. In the war against the latter Krishnarāya captured the strong fort of **Śivanasamudra** and the city of **Śrīraṅgapattana**, after which all **Maisūr** submitted to him.⁴ We can even determine, with great probability, the cause which led to this war, by combining the facts ascertained hitherto with the statements of a Portuguese author. In his *Commentaries of the Great Afonso Dalboquerque*⁵ the son of the great conqueror gives us an abstract of a letter written by a certain **Luiz**, a **Franciscan friar**, who, after the disaster at **Calicut** in **January 1510**, was sent by **Albuquerque** to the court of **Vijayanagara** with the view of securing Krishnarāya's assistance against the **Zamorin**. The letter was delivered by the

¹ See *e.g.* Kuppēlūr plates of Krishnarāya, *J. Bo. Br. R.A.S.* Vol. XII. p. 351 ff.; Hampe inscription of the same, *Ep. Ind.* Vol. I. p. 361 ff.; Ūpamāñjēri plates of Achyutarāya, *ibid.* Vol. III. p. 147 ff., etc. Verse 5 of the present inscription is formed by combining the first halves of two *śloka*s of those inscriptions (vv. 6 and 9 of the Hampe inscription, vv. 7 and 8 of the Ūpamāñjēri plates).

² *Ep. Ind.* Vol. I. p. 365, and Vol. IV. p. 267.

³ *Ep. Carn.* Vol. IV. p. 60 of the text; compare for the **Ummatūr** chiefs Mr. Rice's account, *ibid.* Introduction, p. 27.

⁴ R. Sewell, *Sketch of the Dynasties of Southern India*, p. 109. Mr. Sewell quotes as his authorities Mr. Foulkes in the *Salem District Manual*, p. 45, and the summary of a manuscript in the *Madras Journal*, Vol. XIV. (I.), p. 39. I regret that these two books are not accessible to me at present.

⁵ Translated by Walter de Gray Birch (Hakluyt edit.), Vol. III. p. 35.

ambassadors whom Kṛishṇarāya sent to Goa immediately after having received the news of the recapture of that place by the Portuguese in November 1510. In this letter Fr. Luiz informed Albuquerque "that the king of Narsinga was getting himself ready with five thousand men on foot and two thousand on horse, for an expedition against one of his vassals who had risen up in rebellion and seized the city of Pergunda, (the rebel) declaring that to himself belonged the kingdom itself by right; and that directly he had taken the rebel the king would proceed with all this force of men to his places situated on the edge of the sea." There can be little doubt, I think, that the rebel spoken of in the letter is the Rāja of Ummatūr. Pergunda has already been correctly identified by Mr. Sewell¹ with Penakonda in the Anantapur district, situated about half-way between Vijayanagara and Sivanasamudra, and the war would thus appear to have arisen from a dispute about this hill-fort. This view is further strengthened by an inscription at Hōpakanahalli in the Guṇḍlupēṭe tāluka,² where Chikkarāja-Oḍeyar, the lord of Ummatūr, is given the *biruda* *Penugonḍa-chakrēśvara*. As this inscription is dated in Śrka-Saṁvat 1426, the Krōdhana *saṁvatsara*, during the reign of Narasa, it would seem that the Rājas of Ummatūr had taken possession of Penakonda already under Kṛishṇarāya's predecessor, and that it was not until Kṛishṇarāya's accession to the throne that their claims were seriously disputed.

The taking of the forts of Udayādri, Vinikonda, Bellakonda and Koṇḍaviḍu formed part of Kṛishṇarāya's campaign on the eastern coast against the Gajapati of Orissa. Fernão Nunes³ tells us that Kṛishṇarāya had a special desire of acquiring Udayagiri, because king Narsymga (Narasimha) in his testament had enjoined on his successors the necessity of taking the fortresses of Rracholl (Raichūr), Medegulla (Mudkal), and Odigair (Udayagiri).⁴ He therefore collected 34,000 foot-soldiers and 800 elephants and arrived with this army at Digary (Udayagiri), which, although its garrison numbered only 10,000 foot-soldiers and 400 horse, was nevertheless a very strong place on account of its natural position. The king laid siege to it for a year and a half, cutting roads through the surrounding hills in order to gain access to the towers of the fortress, and finally took it by force of arms. On this occasion an aunt of the king of Orissa fell into his hands.

The capture of Vinikonda, the modern Viṇṇukonda, and of Bellakonda, generally called Bellanṇukonda, is not mentioned by Nunes, probably because these places were only of secondary importance. He proceeds at once to the account of the siege of Koṇḍaviḍu, which I have discussed above, Vol. VI. p. 109 ff. According to inscriptions at Maṅgalagiri, Kāzā and Koṇḍaviḍu the fortress surrendered on Saturday, the *Harivādsara* of the bright half of the month Āshāḍha in Śaka-Saṁvat 1437, which, for Śaka-Saṁvat 1437 expired, corresponds to Saturday, the 23rd June A.D. 1515.

There remains the statement that the king took alive on the battle-field Vīrabhadra, the son of the Gajapati. This fact is mentioned by Nunes as well as by Domingos Paes. The latter has only the short notice that, in the war against the king of Orissa, Kṛishṇarāya took captive his enemy's son and kept him for a long time in the city of Bisnaga (Vijayanagara), where he died.⁵ Nunes' account is more detailed.⁶ He tells us that, after the capture of Koṇḍaviḍu, Kṛishṇarāya continued his march northward until he arrived at Comdepallyr (Koṇḍapalle). After a siege of three months he took it; among the prisoners he made was a wife of the king of Orissa, and one of his sons who was a prince, and seven principal captains of the kingdom, all of whom he sent to Bisnaga (Vijayanagara). When Kṛishṇarāya himself had returned to Bisnaga, he summoned

¹ *A Forgotten Empire (Vijayanagar)*, p. 126. Mr. Sewell was also the first to draw attention to the importance of this letter for the history of the first years of Kṛishṇarāya's reign.

² *Ep. Carn.* Vol. IV. p. 77 of the text.

³ *Chronica dos Reis de Bisnaga*, p. 19 f.; Sewell, *A Forgotten Empire*, p. 316 f.

⁴ *Ibid.* p. 13; by Sewell, *loc. cit.* p. 308, their names are given as Rachol, Odegany, and Conadolgi.

⁵ *Ibid.* p. 89; Sewell, *loc. cit.* p. 247.

⁶ *Ibid.* p. 21 f.; Sewell, *loc. cit.* p. 318 ff.

the son of the king of Orissa, who was renowned as being a good swordsman, to show his skill. The prince consented, but seeing that the antagonist whom the king had chosen for him was a man of low birth, he felt greatly offended and, unable to bear such an insult, he killed himself. The news of the death of this prince induced the king of Orissa to open fresh negotiations with Krishnarāya, which in the end led to a conclusion of peace.

Nunes generally shows himself so well informed that there is no reason to doubt that this story also is substantially correct. The only discrepancy between the chronicle and the inscription is with respect to the date when the prince was taken captive. Whereas the Portuguese author asserts that it took place more than three months after the capture of Koṇḍaviḍu, it would follow from the inscription that it was before that event. This is implied not only by the words of the text, which admit of no other interpretation, but also by the date of the inscription in verse 10, which states that 'in the Śaka year marked by the Munis (7), the towns (3), the oceans (4), and the moon (1), (i.e. Śaka-Samvat 1437), in the year Yuvaṇ, on the twelfth day in the month Āshāḍha, (the king) duly performed the gift called *tulāpūruṣa* and gave away many incomparable *agrahāras* in the presence of the god Śūlapāni, who is renowned in the world as Amarēśa, on the bank of the Krishnavēṇī, which destroys darkness.' This date, although it is incomplete and cannot be verified, is without doubt identical with the date given above as that of the capture of Koṇḍaviḍu, the *Harivāṣara* mentioned there being only another term for the twelfth day of the bright half of the month Āshāḍha.¹ Whether the chronicle or the inscription is to be trusted in this case, I do not venture to decide at present. It is quite possible that the text of the inscription was composed and engraved some months after the event which it is intended to commemorate, and that the author inadvertently referred to things which had happened in the meantime. But it is equally possible that Nunes has made a slight mistake, and that Virabhadra was taken captive on an earlier occasion.

The inscription concludes with a verse (12) invoking the blessing of Amarēśa on Krishnarāya. The Amarēśa mentioned here and in verse 10 is, of course, the god of the temple where the inscription is found.

TEXT.²

- 1 शुभमस्तु ॥ नम[स्तु]ग[शि]रधुवि-
- 2 चंद्रचामरचारवे । त्रैलोक्य-
- 3 नगरारंभमूलस्तंभाय शं-
- 4 भवे ॥ [१*] कल्याणायस्तु तद्भाम³ प्रत्यू-
- 5 हतिमिरापहं । यज्ञजीप्य[ग]जोद्धू-
- 6 तं हरिणापि [च] पूज्यते ।[२*] अस्ति क्षीरम-
- 7 [य]द्वैर्गन्धमानान्महांबुधेः । नयनी-
- 8 तमिवोद्धूत[मप]नीततमो महः ।[३*] तत्⁴
- 9 वंशि देवकी]जानिर्दिदीपे तन्मभूपतिः [।]
- 10 यशस्वो तुर्वेदेषु यदोः क-
- 11 ण [इवा]न्वये ।[४*] ततो[भू]द्धकमाज-

¹ See above, Vol. VI. p. 111, note 4.

² Read तद्भाम.

³ From inked estampages supplied to me by Dr. Hultzsch.

⁴ Read तद्वै.

- 12 निरीश्वरक्षितिपालकः । सर-
 13 सादुदभूतस्मान्नरसावनिपा-
 14 लकः ।[। ५*] चेरं चोळं च पांड्यं तमपि
 15 च मधुरावल्लभं मानभूषं वीर्यो-
 16 द[ग्रं] तुरुष्कं गजपतिनृपतिं चा-
 17 पि जित्वा तदन्यान् । आगंगातीरलंका-
 18 प्रथमचरमभूत्तटांतं नि-
 19 तांतं ।¹ ख्यातः क्षीणोपतीनां सजमि-
 20 व शिर[सां शा]सनं यो व्यतानीत् ॥ [६*] त-
 21 तोभून्नागमांवायां कृष्णराय-
 22 महीपतिः । कुर्वन् कुवलयामोदं
 23 क्षीराब्धेरिव चंद्रमाः ।[। ७*] महत्तामर्थि-
 24 साध्या² श्रियमिह सुचिरं भुंजता-
 25 मित्यवेत्य प्रायः प्रत्यूहहेतोस्त-
 26 पनरधगतेरालयां³ देवतानां । त[त्त]-
 27 द्विजैत्रवृत्त्यापि⁴ च बिरुदपदैरंकि-
 28 तांस्तत्र त[त्र] स्तंभान्⁵ जातघ्न-
 29 तिष्ठान् व्यतनुत भुवि यो भूभृ-
 30 दभ्रं कषाग्रान् ॥ [८*] अपि शिवनसमु-
 31 द्रं यो बलाच्चोदयाद्रिं तद-
 32 पि च विनिकीडुं वेत्तकीडुं च
 33 धाव्या [।*] गजपतिनृपसूनुं वी[र]-
 34 भद्रं गृहीत्वा समरभुवि सजीवं
 35 चाग्रहीत् कौडवीडुं ॥ [९*] आषाढे-
 36 व्दे युवाख्ये मुनिपुरजलधीं⁶-
 37 क्तिते यः शकान्दे विख्यातस्यामरेश⁶
 38 स्वयमिति भुवने सन्निधौ शूल-
 39 पाणेः । तीरे श्रीकृष्णवेण्या हत-
 40 तमसि तुलापूरुषाख्यं च दा-
 41 नं द्वादश्यां सा[धु] कृत्वा व्य[तर]-

¹ This sign of punctuation is superfluous.

² Read साध्याः.

³ Read पनरधगतेरालयान्.

⁴ Read °वृत्त्यापि; between त्या and पि an original न has been effaced

⁵ Read संभाज्जाल°.

⁶ Read °शः.

- 42 दनुपमानग्रहा[र]ाननेकान् ॥ [१०*]
 43 [स्तु]लौदार्यसुधीभिस्त विजयन-
 44 गरे रत्नसिंघानस्थः¹ क्षमापालान्
 45 कृष्णरायचितिपतिरधरीकृत्य
 46 नीत्या नृगादीन् ॥² आ पूर्वादे-
 47 रधास्तुतिधरकटकादा [च]
 48 हेमाचलात्तादा सेतोरथिर्थासाध्य³
 49 श्रियमिह बह्वीकृत्य कीर्त्यासमिंश्चे⁴ [॥ ११*]
 50 अस्य श्रीकृष्णरायस्य कीर्तिधर्मौ
 51 [स]होद्वौ । आकृत्यं तिष्ठतां लो-
 52 [के]वमरेशप्रसादतः । [॥ १२*]
 53 श्री श्री श्री [॥*]

No. 4.— THREE MEMORIAL STONES.

By E. HULTZSCH, Ph.D.

I.— BANGAVADI STONE OF NARASIMHAVIKRAMAVARMAN.

The stone which bears this inscription (No. 103 of 1899) was discovered by Mr. H. Krishna Sastri, B.A. It is set up near the Śiva temple at Baṅgavādi in the Muḷubāgal tāluka of the Kōlār district of the Mysore State and bears the representation of a warrior riding on a horse at full gallop.

The alphabet is archaic Tamil and resembles that of the published inscriptions of the same king.⁶ The only Grantha letter which occurs is *da* of *Daḍiya*⁷ (l. 2). The language is Tamil. An archaic form is *nāḷḡvadu* (l. 2) for *nāṅḡvadu*. Instead of *kāṅga* and *Daḍiyargaḷ* we find the vulgar forms *kāṅga* (l. 5) and *Daḍiyāṅgaḷ* (l. 2 f.). *Mayindiramikkiruma* (l. 3) is a Prākṛit corruption of *Mahēndravikrama*. The word *tonru* (l. 4) is a variant of *toru*, 'cattle.'⁸

The inscription is dated in the 24th year of the reign of the (Gaṅga-Pallava) king Vijaya-Narasimhavikramavarman.⁹ It records the death of a hero, who was in the service of Skanda, the *adhirāja* of the Bāṇas,¹⁰ and who fell in recovering cattle which had been seized by three persons. These were the *Daḍiya*,—evidently the chief of *Daḍigavādi*,¹⁰—an unnamed Bāṇa chief, and a certain *Mahēndravikrama*. The usual imprecation at the end of the inscription is only partially preserved.

¹ Read °सिंहासनस्थः.

² Read °दीन्।.

³ Read रथास.

⁴ Read °रथिसाध्य-.

⁵ Read कीर्त्या समिंश्चे.

⁶ Above, Vol. IV. No. 22, A. and No. 52.

⁷ See above, Vol. IV. p. 179, note 2, and Vol. VI. p. 168.

⁸ In two Kīl-Muttugūr inscriptions (see note 6 above) the name of this king appears in the shorter form Vijaya-Narasimhavarmān.

⁹ On the title *Adhirāja* see above, Vol. V. p. 50 and note 14.

¹⁰ See Dr. Fleet's remarks in *Ind. Ant.* Vol. XXX. p. 109 f. and above, Vol. VI. p. 256, note 8.

There is another *virakkal* lying near the same temple (No. 102 of 1899), which records, in the Kanarese language, that a hero met with his death when Bānarasa together with the *Mahārāja Mahāvali-Bānarasa* attacked Nōlamba, Rāchamalla, Mayindaḍiya and Daḍiga, and that the Kaṅgavaḍiyān (i.e. probably the Gaṅga king Rāchamalla) assigned land for setting up this stone¹ in memory of the hero. Here Bānamahārāja, Bānarasa, Mayindaḍiya and Daḍiga correspond to Bānādhirāja, Bānarāja, Mahēndravikrama and Daḍiya of the subjoined inscription. If Rāchamalla could be identified with one of the three Gaṅga kings named Rāchamalla or Rājamalla,² this would fix the time of king Vijaya-Narasimhavikramavarman to whose reign the subjoined inscription belongs.

TEXT.³

- 1 K[ô] Viśaiya-Naraśiṅgavikkirama[pa]ruma[ṛk=i*]-
- 2 yā[n]ḍu irubattu-nāl[g]āvadu Daḍiyaṅga-
- 3 [ḷu][m*] Vānarāśarum Mayindiramikkiramarum eṛ[i]-
- 4 nda toṇṇu Kanda-Vān[ā]diaraśar śēvagar Ś[e]-
- 5 ḷigar eṇind[u] paṭṭār=adu Kaṇṇāḍagaruṅ=gān[ga] [i*]
- 6 idaṛk=ali[ppu] pāda-
- 7 ga

TRANSLATION.

In the twenty-fourth year (of the reign) of king Vijaya-Narasimhavikramavarman, Śeḷigar, the servant of Skanda-Bānādhirāja, fell, having seized (back) the cattle that had been seized by Daḍiya, Bānarāja and Mahēndravikrama. Let the Kaṇṇāḍagas (i.e. the Kanarese people) look after⁴ this (stone)! [Those who] injure it [shall incur the five great] sins.

II.—HANUMANTAPURAM STONE OF VIJAYA-ISVARAVARMAN.

The stone which bears the two subjoined records (Nos. 16 and 17 of 1900) was discovered by Mr. G. Venkoba Rao. It is set up in a field at Hanumantapuram near Pennagaram in the Dharmapuri tāluka of the Salem district. Unlike other *virakkals*, the stone bears no sculptures of any kind.

The alphabet is Vaṭṭeḷuttu. The letters *k*, *ṭ* and *ṇ* resemble those of the Madras Museum plates of Jaṭilavarman,⁵ while *y* is more nearly allied to the *y* of the Cochin and Tirunelli plates.⁶ In two cases (*ḍa* of *paḍa* in l. 3 f. and *ṭi* of *Kāṭṭirai* in l. 4 of A.) the Tamil form of *ṭ* or *ḍ* seems to be used. The *ḍu* of *iḍḍu* (l. 2 of A.) is reversed. In *ḍai* (l. 3 of A. and l. 4 of B.) the vowel *ai* is drawn through the consonant *ḍ*. The *ā* of *ṭā* in *paṭṭān* (l. 4 of A. and l. 4 of B.) and the *ā* of *kā* in *Kāṭṭirai* (l. 4 of A.) go downwards instead of upwards. The language is Tamil. The *ḷ* of *paḍiṇḷḷāvaḍan* (l. 2 of A. and B.) is doubled, and the *saṁdhi* is not observed in *Kaṇaiṭṭur* (l. 3 of A.). The locative affix *kan*, which has been changed into *kaṭ* before the following *k*, occurs in both inscriptions (l. 3 of A. and l. 2 of B.).

The two inscriptions are dated in the 17th year of the reign of king Vijaya-Īśvaravarman, who, to judge from the prefix *vijaya*, seems to have been one of the Gaṅga-Pallavas, and record the death of two heroes in the service of Kāṭṭirai. This title means 'the king of the forest' and is synonymous with Kāḍavaṇ, 'the forester,' which according to Mr. V. Kanakasabhai

¹ This seems to be the meaning of the words *kal-nāḍu kottāḍu*, which occur also on the Doḍḍahundi stone; see above, Vol. VI. p. 43, note 1.

² See Dr. Fleet's Table, above, Vol. VI. p. 59. ³ From an inked estampane.

⁴ The infinitive *kāṅga* is used in a similar manner in l. 105 of the Kaśākūḍi plates; *South-Ind. Inscr.* Vol. II. p. 351.

⁵ *Ind. Ant.* Vol. XXII. p. 57 ff.

⁶ Above, Vol. III. No. 11, and *Ind. Ant.* Vol. XX. p. 285 ff.

Pillai was a title of the **Pallavas**.¹ The correctness of this view is proved by the *Periyapurāṇam*, in which, as Mr. Venkayya informs me, 'the king of the Kāḍavas' and 'the Pallava' are used as synonyms. The Kāḍava king whom the Hoysala king Narasimha II. claims to have defeated² was probably one of the Pallava chiefs of Nalambavāḍi. It thus appears that a descendant of the Pallava dynasty was tributary to the Gaṅga-Pallava king Vijaya-Īśvaravarman. Pūḍūr, the native village of the first of the two heroes (A. l. 5), is now a hamlet of Pennagaram.³

TEXT.⁴

A.— On the left of the stone.

- 1 Kō Viśaiya-īchchuvaraparuma-
- 2 [r]k-iyāṇḍu paḍiṇēllāvada-
- 3 ŋkaṭ=Kaṇaiyūr⁵ māṇṇ-udai pa-
- 4 ḍa=ttāṇ=aṇḇaṭṭāṇ. Kāṭṭirai-
- 5 gaḷ sēvagaṇ Pūḍūr Śāṭṭaṇ [||*]

B.— On the right of the stone.

- 1 Kō Viśaiya-īchchuvaraparuma[rk-i*]-
- 2 yāṇḍu paḍiṇēllāvadaṇka[t*]=
- 3 Kāṭṭirai[gaḷ] sēyi[k]kav=araśar
- 4 māṇṇ-udai sēṇṇa tāṇ=aṇḇaṭṭāṇ
- 5 K[ā]ḍaḍi Kaṇakka[ṇ] [||*]

TRANSLATION OF A.

In the seventeenth year (*of the reign*) of king Vijaya-Īśvaravarman, when Kaṇaiyūr fell into the possession of the enemies,⁶ Śāṭṭaṇ of Pūḍūr himself, the servant of Kāṭṭirai, was cut down.

TRANSLATION OF B.

In the seventeenth year (*of the reign*) of king Vijaya-Īśvaravarman, when Kāṭṭirai was victorious, Kāḍaḍi⁷ Kaṇakkaṇ himself, who went among the enemies of the king, was cut down.

III.—HEBBINI STONE OF VIJAYA-ISVARAVARMAN.

The stone which bears this inscription (No. 101 of 1899) is lying near the Gopālakrishṇa temple at Hebbini in the Mulubāgal tāluka of the Kōlār district. It bears the representation of a bearded warrior with helmet, sword, shield and sword-belt.

The alphabet is Vaṭṭeḷuttu, and the language Tamil. The inscription is dated in the 12th year of the same king as No. II. and records the death of a hero, who was killed by a Bāṇa chief named Kārōniri at Śiraiyūr.

¹ *Ind. Ant.* Vol. XXII. p. 143.

² Dr. Fleet's *Dyn. Kan. Distr.* p. 507.

³ See the *Postal Directory of the Madras Circle*, p. 1038.


⁴ From two inked estampages.

⁵ Read =Kaṇaiyūr.

⁶ *Māṇṇ* seems to be used in the sense of *māṇṇḍr*, 'enemies.'

⁷ This portion of the name consists of *kāḍu*, 'forest,' and *aḍi*, 'His Majesty,' and is evidently a synonym of Kāṭṭirai or Kāḍavaṇ.

Three memorial stones.



WIELE & KLEIN, PHOTO-ZINCO

SCALE 1/5.

E. HULTSCH.

TEXT.¹

- 1 Kô Visaiya-î[çh]chuvara-
 2 parumaṅki paṇṇira-
 3 ṇḍāvadu Kārōniri
 4 Vāṇarāśar=ṇḍō[īṅ]=
 5 ²Chiraiṭṭ[re]ṅṅiya Vāṇa-
 6 rāśar=[ariya] paṭṭār=Ad[i]y[ā][r][*]

TRANSLATION.

In the twelfth (year of the reign) of king Vijaya-īśvaravarman, when Kārōniri Bāṇarāja seized Śiraiyūr in battle, Aḍiyār fell, cut down by Bāṇarāja.³

No. 5.—A ROCK-INSRIPTION AT TANDALAM.

By E. HULTZSCH, PH.D.

The existence of this inscription (No. 1 of 1892) was brought to my notice by Mr. E. Srinivasachari, Deputy Collector, Madras. It is engraved on a rock near the tank at Tandalam, a village in the Kārvēṭinagar Zamindārī, 4½ miles west by north of Arkōṇam Junction. With the exception of the two Grantha words *svastī śrī* in the beginning, the alphabet is Tamil, and resembles that of the Vēlūr rock-inscription of Kaṇṇarādēva.⁴

The inscription is dated in the 10th year of Śatti, the king of the Kāḍavas, i.e. Pallavas.⁵ It consists of two Tamil verses, each of which states that Pallavamahārāja built a sluice for the tank at Tandalam. The donor may have been either a relative of, or identical with, Śatti, who, as his title implies, claimed descent from the ancient Pallava dynasty. Pōḷiyūr-nāḍu, to which Tandalam belonged, was perhaps named after the present Pōḷūr, a village 3 miles north-north-west of Arkōṇam Junction.

The Veṅkaṭēśa-Perumāḷ temple on the Tirupati hill bears on the north wall of its first *prākāra* four Chōḷa inscriptions, which were copied from their (now lost) originals when the temple was rebuilt in the fortieth year of Vira-Nārasimhadēva-Yādavarāja. The second and third of these four copies (Nos. 62 and 63 of 1888-89) are dated in the 14th year of "Paratramahēndravarman" and "Paratravarman"—evidently misreadings of the copyist for Parakēsarivarman. These two inscriptions record gifts by Śāmavai *alias* Kāḍavaṇ-Perundēvi, the daughter of Pallava-Perkaḍaiyār,⁶ (and) the queen of Śattiviḍaṅgaṇ *alias* Śrī-Kāḍapaṭṭigal.⁷ It is not improbable that this Pallava king Śattiviḍaṅgaṇ (i.e. Śakti-Viṭaṅka),⁸ who was a contemporary of the early Chōḷa king Parakēsarivarman,⁹ is the same person as the Pallava king Śatti (i.e. Śakti). In this case the subjoined inscription would belong roughly to the second half of the ninth century of the Christian era.

¹ From two inked estampages.

² Read *Chiraiyūr*.

³ Literally, 'while Bāṇarāja cut (him) down.'

⁴ Above, Vol. IV. No. 9.

⁵ See above, p. 23 f.

⁶ *Perkaḍai* seems to be a Tamil form of the Kanarēse *pergaḍe* and the Telugu *preggaḍa*, 'a minister.'

⁷ Compare Mr. Venkayya's paper in the *Madras Christian College Magazine* for August 1890. *Kāḍapaṭṭi* seems to be a mistake of the copyist for *Kāḍupaṭṭi*, which occurs in a Pallava inscription at Conjeeveram (*loc. cit.*) and in two Gaṅga-Pallava inscriptions (*South-Ind. Inscr.* Vol. III. p. 92 f.). Compare also *Kāḍupaṭṭi* (above, Vol. V. p. 171 and note 1) and *Kāḍuvittēśvara* (*ibid.* p. 143).

⁸ Dantīśakti-Viṭaṅki *alias* Lōkamahādēvi, a queen of the Chōḷa king Rājarāja I., built a shrine in the Paṭṭāṇadēśvara temple at Tiruvaiyāru; see my *Annual Report* for 1894-95, p. 4.

⁹ See above, Vol. V. p. 42 and note 7.

TEXT.¹

- 1 Svasti śrī [||*] ²Kāḍavar-daṇ=gōṇ Śatti [por]-rōttil=iṭṭa yāṇḍ=ēḍ=iyal=i(i)r-
aīdīl=iḍuvittā=ṇi(ṇi)-
2 ḍiya-śi(śi)r Pa[||*]lavamārāyaṇ paśi ni(ni)kki Taṇḍalattu=kkaḷl-ivar
ni(ni)r-ēri-kkaḷiṅgum=aṇḍattu-
3 [||]ōr maḍippavaṇ [||1*] Pōḷi[yu(yū)]r-nāṭṭu=Taṇḍalatt-ēri-kka-
4 liṅg=amaittāṇṇ=ōṇ-Paṇḍiḷ-ppār-maṅgai-dāṇ
5 virumbum Pallavamārāyaṇ=ēḷiṭṭ-pu(pū)-maṅgai-da[n]=
6 gōṇ purindu [||2*][ō-]

TRANSLATION.

Hail! Prosperity! (Verse 1.) In (*the year*) twice five (*i.e.* ten), which was engraved on palm-leaves,³ (*from*) the year when (*the name of*) Śatti, the king of the Kāḍavas, was entered on a gold leaf,⁴—Pallavamārāyaṇ of enduring fame, who is respected by (*all*) the inhabitants of the world, having freed (*the villagers*) of hunger, caused to be built also a sluice, composed of stones, for the water-tank at Taṇḍalam.

(V. 2.) The lord of the beautiful goddess of the (*lotus*) flower (*i.e.* Lakshmi), Pallavamārāyaṇ, who is beloved by the excellent goddess of the Tamiḷ country, graciously constructed a sluice for the tank at Taṇḍalam in Pōḷiyūr-nāḍu.

No. 6.—CAMBAY PLATES OF GOVINDA IV.;

SAKA-SAMVAT 852.

By D. R. BHANDARKAR, M.A.; POONA.

The copper-plates, a transcript and translation of which are given below, were originally found at Cambay, called Khambāyat by the people. While a husbandman was tilling his field, his plough struck against a hard substance. On digging a portion of the ground near that spot, he discovered a wooden box, which was so rotten that with little effort he broke it to pieces. It contained a black dirty object, which, until it was cleaned, was not recognised to be these plates. From the husbandman the plates afterwards went into the possession of a Gujarāṭi living at Petlad, which is not very far from Cambay. The Gujarāṭi was very unwilling to part with the plates. I requested Professor Abaji Vishnu Kathavate to intercede in my favour. This he kindly did, and was soon successful in securing the plates for me.

The plates are three in number, each about 13½" long by 10½" broad. The edges of them are fashioned slightly thicker, so as to serve as rims for the protection of the writing. The inscription is engraved on the inner sides of the first and third plates, and on both sides of the second plate. Two small pieces have been broken off near the lower corners of the third plate, and a few letters are here and there damaged on account of verdigris. Still the inscription is on the whole well preserved and legible throughout. The plates are strung together by a circular ring, of about 4½" in diameter and of about ¾" in thickness, passing through holes on one side of each plate. The ring had not yet been cut when the plates were sent to Dr. Hultzsch. The ends

¹ From an inked estampage.

² In this verse 'ḍ=ḍ=īya' rhymes with *nḍiya* and *Taṇḍa* with 'm=aṇḍa'.

³ *I.e.* with which all documents issued at this time had to begin.

⁴ This seems to refer to some custom observed at the coronation of a king; compare *South-Ind. Inscr.* Vol. III. p 185 and note 2.

of the ring are soldered into a roughly square seal, which measures $2\frac{1}{4}$ " in height and breadth, and bears, in relief on a countersunk surface, as the principal figure, an image of **Garuḍa**, squatting and facing to the full front, with his prominent beak-nose and expanded wings, and holding a snake in each hand. On Garuḍa's proper right there is a representation of Gaṇapati in the upper corner, and lower down a *chauri* and a lamp; and on his proper left, some goddess, seated on an animal, too indistinct to be recognised, and below her, a *śaṣṭika*.¹ Along the border of the seal are to be seen certain emblems, among which a dagger, a bow and an arrow, and a thunderbolt are recognisable. Beneath the central figure certain letters were doubtless engraved, but are now almost effaced.—The engraving is clear and well executed.—The characters agree fully with those of the other Rāshtrakūṭa records of this period, viz. the 10th century. The average size of the letters is about $\frac{3}{8}$ ".—The language is Sanskrit throughout. Excepting the introductory *ōṃ svasti*, down to the beginning of line 38 the inscription is in verse; and the rest is in prose, excepting the five benedictive and imprecatory verses (ll. 61-66) and another verse, containing the name of the person who drew up the charter (l. 66 f.). All the verses of this grant, excepting three of the introductory, and two of the genealogical, verses, occur in the Sāṅglī charter of the same royal grantor, viz. the Rāshtrakūṭa prince Gōvinda IV.—As regards orthography, it is sufficient to say (1) that the letter *b* is throughout denoted by the sign for *v*; (2) that the letters *g, j, n, t, d, p, m, l* or *v* following *r* are doubled; but in the case of *ju* or the conjunct *dyu* coming after *r*, the letter *j* or *d* is not doubled. There is also an indifference about the doubling of *y* following *r*; thus it is doubled in *Nāgamāryyasya* in l. 60, but not in *Nāgamāryāya* in l. 52; (3) that the letter *dh* is doubled (with *d* in the usual manner) in conjunction with a following *y*, once in *°samvaddhyamāna°* in l. 42; and (4) that the final *m* of a word, instead of being changed to an *anusvāra*, is twice joined to a following *p*, in *pulakam=pāyāt* and *phanindm=patyuh* in l. 4.—As regards prosody, it is worthy of note that the metre of verse 7, which occurs also in the Sāṅglī grant, cannot be determined. There can be little doubt that it is an instance of a half-equal metre (*ardha-sama-vṛtta*). But it cannot be identified with any one of the half-equal metres, given in ordinary works on prosody. There is, indeed, a rule of prosody that any two quarters of regular metres may be combined to form what is technically called an *upajīti*. But even here the unequal quarters of the verse in question cannot be severally identified with those of the regular metres.

The inscription is one of the Rāshtrakūṭa prince Gōvinda IV. or, as he is described in lines 40-42, the *Paramabhaṭṭāraka Mahārājādhirāja Paramēśvara*, the prosperous **Suvarṇavarsha-dēva-Prithivīvallabha**, the prosperous **Vallabhanarēndradēva**, who meditated on the feet of the *Paramabhaṭṭāraka Mahārājādhirāja Paramēśvara*, the prosperous **Nityavarsha**, i.e. his father Indra III. Govindarāja had, when this charter was issued, gone from his capital **Mānyakhōṭa** to **Kapitthaka** near the bank of the **Godāvarī**, for the festival of *paṭṭabandha*² (l. 46). On that occasion he weighed himself against gold. When he ascended the scales, he bestowed on Brāhmins six hundred *agrahāras* and three lacs of *suvarṇa* coins, and on temples eight hundred villages, four lacs of *suvarṇas* and thirty-two lacs of *drummas* (ll. 46-49). Afterwards, without descending from the pan, he granted the village of **Kēvañja**, lying near the holy place **Kāvikā** and

¹ The figures on this seal are identical with those on that of the Dēolī plates, excepting the central figure, which Dr. Hultzsch thinks to be that of Śiva. See above, Vol. V. p. 189, note 1.

² The term *paṭṭabandha*, which literally means 'binding of the fillet,' has been generally supposed to signify 'coronation-ceremony.' Though evidence may perhaps be adduced in support of this signification, there can be little doubt that it does not suit here. The earliest record of Gōvinda IV. gives for him the date Śaka 840 (expired), which is prior to Śaka 852 (expired), the date of our grant, by no less than twelve years. It is hardly credible that he remained uncrowned for at least twelve years, if *paṭṭabandha* is to be understood in the sense of 'coronation-ceremony.' Besides, in these as well as the Sāṅglī plates he is expressly said to have been 'permanently settled at his capital Mānyakhōṭa' when he issued the charters. Again, what can be more unnatural than that a king, instead of getting himself crowned at his own capital, goes to some place far away from it for his coronation? For these reasons, I think, the word *paṭṭabandha* does not here at any rate mean 'coronation-ceremony.'

situated in the Khēṣaka district of the Lāṭa country (ll. 52-54). It is to record the grant of this village that the present charter was issued. The donee was a Brāhman of the name of Nāgamārya, son of Mahādēvayya, a member of the Māthara gōtra and a student of the Vāji-Kāṇva śākhā (ll. 51-52). He is described as staying at Mānyakhēṣa and subsisting on the feet of Vallabhanarēndradēva, i.e. Gōvinda IV. himself, but is said to have originally resided at Kavikā.

The grant is dated, both in words and figures, in Śaka-Saṃvat 852 expired, in the current cyclic year of Khara, on Monday, the tenth tithi of the bright half of Jyāishṭha, when the moon was near the constellation Hasta (ll. 44-46). Professor Kielhorn kindly contributes the following remarks:—“This date, for Śaka-Saṃvat 852 expired, regularly corresponds to Monday, the 10th May A.D. 930, when the tenth tithi of the bright half ended 12 h. 3 m., and the nakshatra was Hasta, by the equal space system and according to Garga for 22 h. 59 m., and by the Brahma-siddhānta for 19 h. 42 m., after mean sunrise. By the northern luni-solar and strict mean-sign systems the day fell in the year Khara, which lasted from the 23rd December A.D. 929 to the 19th December A.D. 930. [By the southern system the year would have been Vikṛita.]”

Having thus disposed of the formal part of the grant, I shall now give an account of the thirty-one verses, descriptive of genealogy, and of the preamble of the prose passages that follow. After the introductory *ōṃ svasti*, the inscription opens with a verse (well known to us from other Rāshtrakūṭa records), invoking the protection of Vishṇu and Śiva. The next verse is in honour of the *Sāmaveda*, and the two verses following it (3-4) contain invocations to Vishṇu and Śēsha. In verse 5 we are told that from the Moon was descended the race of the Yadus, to the glorification of which the next verse is devoted. After thus bestowing praise on the Yadus, Dantidurgarāja is mentioned in verse 7 as having arisen in the spotless race of the Yadus, as the moon in the clear sky. He was succeeded on the throne by his paternal uncle Kṛishṇarāja (I.), who is represented to have destroyed the Chalukya race, as the sun dispels darkness (v. 8). After Kṛishṇarāja I. his eldest son Gōvindarāja (II.) came to the throne, and after Gōvindarāja II. his younger brother, who bore the appellation Nirupama (vv. 9-10). Dr. Fleet, who strongly holds that Gōvindarāja II. did not obtain sovereignty, brings forward the argument, among others in support of his view, that the Sāṅgli charter, though it places Gōvindarāja II. between Kṛishṇa I. and (Dhruva-)Nirupama, “does not make any assertion that he reigned.”¹ This statement can only be understood to mean that verse 6 of the Sāṅgli grant, which is identical with verse 9 of our grant, does not explicitly speak of Gōvindarāja II. as having become a king, but that his name occurs between those of Kṛishṇarāja I. and (Dhruva-)Nirupama. If this is what Dr. Fleet means, then we shall have to suppose that Jagattuṅga(-Gōvinda III.) and Amōghavarsha (I.) also did not reign. For verses 11 and 12, in which their names are mentioned, do not tell us in explicit words that they became kings, but simply place them between (Dhruva-)Nirupama and Akālavarsha(-Kṛishṇa II.). Hence, if Jagattuṅga(-Gōvinda III.) and Amōghavarsha I. are to be supposed to have reigned, Gōvindarāja II. too must, for the same reason, be regarded as having sat on the throne.

(Dhruva-)Nirupama was succeeded by his son Jagattuṅga(-Gōvinda III.), on whom nothing but conventional praise is bestowed (v. 11). After Jagattuṅga(-Gōvinda III.), Amōghavarsha (I.) became king, who, in the first half of verse 12, is said to have gratified the god Yama at Viṅgavallī with unprecedented morsels of cakes, which were the Chalukyas. This means that he inflicted a crushing defeat on the Eastern Chalukyas at Viṅgavallī, which, I think, probably signifies the Vēṅgimaṇḍala, the territory over which they ruled. The second half of the verse, if I have rightly understood it, seems to mention a reservoir or some such thing,

¹ See above, Vol. VI. p. 170 f., where Dr. Fleet meets the objections I brought against his view in my paper in *J. Bo. Br. E. A. S.* Vol. XX. p. 133 f.

which received the name of Jagattuṅga-sindhu after Jagattuṅga(-Govinda III.), father of Amôghavarsha I.

After Amôghavarsha I. the throne was occupied by his son Akâlavarsha(-Kṛishṇa II.), of whom verse 13 says that his enemies abandoned the city of Khêṭaka, which, in my opinion, is here meant to denote Mânyakhêṭa itself, the capital of the Râshtrakûṭa princes. Two Eastern Châlukya records¹ mention that Guṇaka-Vijayâditya III. (A.D. 844-888) "frightened the fire-brand Kṛishṇa and completely burnt his city,"² and that "king Vallabha did honour to the arms of Vijayâditya (III.)." It, therefore, appears that the Eastern Châlukya prince Guṇaka-Vijayâditya III. defeated the Râshtrakûṭa king Kṛishṇa II. and was in possession of his capital Mânyakhêṭa, and it is to the act of repulsing this Châlukya prince from Mânyakhêṭa that verse 13 of our grant refers.³ Verse 14 states that Akâlavarsha(-Kṛishṇa II.) married the daughter of Kôkkala, who belonged to the family of Sahasrârjuna, i.e. the Chêḍi dynasty. Now, the Bilhari inscription speaks of Kôkkala as having erected two columns of fame, viz. Kṛishṇarâja in the south and Bhôjadêva in the north.⁴ Similarly, the Benares plates of the Chêḍi prince Karna-dêva state that Kôkkala's hand, which granted freedom from fear, was on (the head of) Bhôja Vallabharâja, Śrî-Harsha and Śaṅkaragana.⁵ There can hardly be a doubt that the Kṛishṇarâja of the Bilhari inscription is identical with the Vallabharâja of the Benares plates, and that both are identical with the Râshtrakûṭa prince Akâlavarsha(-Kṛishṇa II.). And the support, which Kôkkala lent to Akâlavarsha(-Kṛishṇa II.), was given in all likelihood at the time when the latter was defeated, and his capital Mânyakhêṭa occupied, by the Eastern Châlukya king Guṇaka-Vijayâditya III. The last *pâda* of verse 14 tells us that from the union of Akâlavarsha (-Kṛishṇa II.) and the daughter of Kôkkala sprang Jagattuṅga, who, in verses 15 and 16, is said to have married Lakshmi, daughter of Raṇavigrâha, son of Kôkkala.⁶ Verse 16 speaks of a prince named Arjuna as having helped Jagattuṅga with his army and thus enabled him to acquire fame. It does not seem difficult to identify this Arjuna. In verse 20, Arjuna is mentioned as a son of Kôkkala. Arjuna was thus a brother of Raṇavigrâha, and consequently an uncle-in-law of Jagattuṅga. And, in all likelihood, it is this Arjuna who seems to have rendered him assistance.

Verses 17-18 relate that from this Jagattuṅga and Lakshmi king Indra (III.) was born. Verse 19 describes a great victory achieved by this Indra. The first line of this stanza may be thus translated :—"The courtyard (of the temple of the god) Kâlapriya (became) uneven by

¹ *Ind. Ant.* Vol. XX. p. 102.

² [For a different explanation of this statement and its bearing, see above, Vol. IV. p. 226 f.—E.H.]

³ Verse 13 is also susceptible of another interpretation. Khêṭaka may be taken to denote the modern Kaira, and the term *maṇḍala* to refer to the surrounding district. If so, the verse must be understood as containing an allusion to Kṛishṇa II.'s having supplanted the subordinate branch of the Râshtrakûṭa dynasty, reigning at Khêṭaka. But the word *parityakta* implies that Khêṭaka, before it was occupied by the enemies, was under the sway of Kṛishṇa II., and that, when it was so occupied, he by his prowess compelled the enemies to evacuate it. But the Râshtrakûṭas of the subordinate branch did not occupy Khêṭaka and the surrounding district at any time during Kṛishṇa II.'s reign, but were ruling over it long before him. Again, the word *ahita* as applied to these tributary Râshtrakûṭas does not seem to be appropriate. They are referred to as *śulbika-Râshtrakûṭas* when their rebellion against Amôghavarsha I. is mentioned (*Ind. Ant.* Vol. XII. p. 183, and Vol. XIV. p. 199). Again, they are spoken of as *bândhavas* when their disaffection towards the Gujarât Râshtrakûṭa prince Dhruva II. is alluded to (*Ind. Ant.* Vol. XII. p. 184). But in no case the word *ahita* or its synonyms are used to denote them. For these reasons the second interpretation does not commend itself to me as easily as the first, suggested in the text. The latter is much more probable, because we know that Mânyakhêṭa was once occupied during Kṛishṇa II.'s life-time by the Eastern Châlukyas, who can, with propriety, be called his *ahitas*, inasmuch as they were the mortal enemies of the Râshtrakûṭa dynasty.

⁴ See above, Vol. I. p. 256, verse 17.

⁵ *Ibid.* Vol. II. p. 306, verse 7.

⁶ The true spelling of the name appears to be Kôkkala, as attested by the records of the Chêḍi dynasty. It is spelt Kôkkala in verses 14 and 15, on account of the exigencies of the metre. The correct spelling of the name occurs in verse 20.

the strokes of the tusks of his rutting elephants." The god Kālapriya is the same as **Mahākāla**,¹ whose temple at Ujjain is so widely known all over India. It is on the occasion of the festival held in honour of this Kālapriya that the three plays of the poet Bhavabhūti were represented. It thus appears that, in his expedition of conquest in Northern India, Indra III. halted at Ujjain to pay his homage to the god. The remaining three lines may be thus rendered :— "His steeds crossed the unfathomable **Yamunā** which rivals the sea. He completely devastated that hostile city of **Mahodaya**, which is even to-day greatly renowned among men by the name of **Kuśasthala**." Indra III. therefore appears to have marched from Ujjain northward, crossed the Jumna and reduced the city of Mahodaya. The lexicon of Hémachandra tells us that Mahodaya and Kuśasthala are both names of **Kanyakubja**,² i.e. Kanauj, so that verse 19 represents Indra III. to have attacked the city of Kanauj. But the complete devastation of Mahodaya, which Indra III. is spoken of as having brought about, is merely poetical. For, the poet's object appears to be to introduce a play on the words *mahodaya* and *kuśasthala*, which in their conventional sense mean Kanauj, and in their etymological one, 'full of high prosperity' and 'a spot of *kuśa* grass' respectively: Mahodaya, i.e. Kanauj, ceased to be *mahodaya*, i.e. highly prosperous, and became *kuśasthala*, i.e. a mere spot of *kuśa* grass. Hence, the complete annihilation of the city of Mahodaya or Kanauj alluded to in this stanza cannot be reasonably assumed to be a historical fact. This is also seen from the consideration that, as a matter of fact, for long after the event recorded in this verse took place, Kanauj continued to be the capital of several princes, ruling over Northern India.³ What Indra III. actually did beyond attacking Mahodaya or Kanauj, cannot be inferred from the verse itself. But we can ascertain it with the help of other inscriptions. We shall, however, in the first place, see whether we can decide which of the rulers of Kanauj Indra III. vanquished. The Rāshtrakūṭa records give the dates 915 and 917 A.D. for Indra III.; and the succession and dates of the princes, reigning at Mahodaya or Kanauj about this period, as determined from the Gwalior, Pehwa and Siyāḍōṇī inscriptions, are as follows :

1. Bhōja, A.D. 862, 876 and 882.
2. Mahēndrapāla, A.D. 903 and 907.
3. Kshitipāla or Mahipāla, A.D. 917.
4. Dēvapāla, A.D. 948.⁴

Now, as for Indra (III.) we have the dates A.D. 915 and 917⁵ and for Kshitipāla or Mahipāla the date A.D. 917, there can hardly be a doubt that they were contemporaries. And it is almost certain that it is this Kshitipāla whom Indra III. conquered. Let us now find out what Indra III. did beyond obtaining a victory over Kshitipāla. A Khajurāho

¹ Jagaddhara, in his commentary on the *Mālatīmādhava*, says that Kālapriyanātha is *tad-dēśa-dēva-bhēda*, i.e. a particular deity belonging to that country. But what country Jagaddhara had in his mind, cannot be accurately made out. Śvarachandra Vidyāsāgara, in his edition of the *Uttararāmacharita*, says in a footnote that Kālapriyanātha is the name of a deity installed in Padmapura in Vidarbha, i.e. the native town of the poet Bhavabhūti. But this note appears to be based on the comment of Jagaddhara just quoted, and, according to Śvarachandra, it seems that the expression *tad-dēśa* must be understood to mean the country to which Bhavabhūti belonged. In the *St. Petersburg Dictionary*, however, Kālapriyanātha is identified with the Mahākāla of Ujjayini. This identification doubtless fits here excellently, but I have not been able to trace the authority which supports it.

² Hémachandra's *Abhidhānaśāntīmanjī*, v. 273 f.

³ The king of Mahodaya or Kanauj, whom Indra III. defeated, has been shown further on to be Kshitipāla or Mahipāla. And we have actual records to show that, after this Kshitipāla, there reigned at Kanauj his successors called Dēvapālādēva, Vijayapālādēva, Rājyapālādēva and Trilōchanapālādēva, respectively (see above, Vol. III. p. 295; *Ind. Ant.* Vol. XVIII. p. 83 ff.). They were followed by the Gaharwaras or Rāṭhōrs of Kanauj (C. Mabel Duff's *Chronology of India*, p. 285).

⁴ See above, Vol. I. p. 171 f.; C. Mabel Duff's *Chronology of India*, p. 296.

⁵ Dr. Fleet's *Dyn. Kan. Distr.* p. 415 f.

inscription¹ claims that a king named Kshitipāla was placed on his throne by the Chandēlla prince Harshadēva. As this Harshadēva flourished at the beginning of the tenth century, the Kshitipāla, whom he re-instated on his throne, can be no other than Kshitipāla, king of Kanauj, who was a contemporary of, and vanquished by, Indra III. Indra III., therefore, appears not only to have attacked Mahōdaya or Kanauj, but also to have defeated and ousted its ruler Kshitipāla.

Let us now proceed a step further. The Bhāgalpur grant of Nārāyaṇapāla² asserts that Dharmapāla, the second prince of the Pāla dynasty, acquired the sovereignty of Mahōdaya by conquering Indrarāja and others, but bestowed it upon one Chakrāyudha, just as Bali acquired the sovereignty of the three worlds by vanquishing Indra and other gods, and bestowed it upon Chakrāyudha (Vishṇu). The Bhāgalpur grant thus tells us that Dharmapāla first defeated Indrarāja and others, and obtained the sovereignty of Mahōdaya or Kanauj for himself, but gave it over to one Chakrāyudha. The same event is referred to in the Khālimpur charter³ of Dharmapāla himself, in the verse—

भोजैर्मत्स्यैः समद्वैः कुर्यदुयवनावन्तिगन्धारकीरै-
 भूपैर्व्यालोलमौलिप्रणतिपरिणतैः साधु संगीर्यमाणः ।
 हृथ्यत्पञ्चालवृद्धोदृतकनकमयस्त्राभिषेकोदकुम्भी
 दत्तः श्रीकन्यकुब्जसललितचलितमूलतालक्ष्म येन ॥

The stanza, as it stands, yields no intelligible sense. There can be little doubt that the reading of the last line is faulty, though it occurs, as given here, in the plates.⁴ Since we have *dattah* in the nominative case,—that which is given, or in this particular case *abhishēk-ōda-kumbhaḥ*, which is in the nominative case, must go with *dattah*. Further, the person to whom something is given must be in the dative case; but we have no such dative in the verse, and moreover the nominative *śrī-Kanyakub(b)jaḥ* remains unconnected. The sense, however, requires that *śrī-Kanyakubja* should be considered the person to whom the coronation pitcher was given. Evidently, therefore, *śrī-Kanyakubjaḥ* requires to be corrected into *śrī-Kanyakubjāya*, even at the risk of the break of the *cæsura*. With this emendation, the verse yields the following sense:—“With a sign of his eyebrows gracefully moved, he made over to the illustrious king of Kanyakubja his own golden water-pitcher of coronation, lifted up by the delighted elders of Pañchāla, and acquiesced in by the Bhōja, Matsya, Madra, Kuru, Yadu, Yavana, Avanti, Gandhāra and Kira kings, bent down while bowing with their heads trembling.” What the verse means is, that Dharmapāla earned for himself the sovereignty of Pañchāla, and was consequently entitled to the coronation as king of Pañchāla, which was approved of by the neighbouring rulers, such as Bhōja, Matsya and other kings; but he declined it and assented instead to the installation of the king of Kanyakubja. The Pañchāla country here referred to denotes the upper half of the Dōāb between the Ganges and the Jumna with Kanyakubja as its principal town, and to this effect we have the authority of the poet Rājasēkhara who flourished about this period.⁵ Hence the fact mentioned in the Khālimpur charter is the same as that reported in the Bhāgalpur grant. And

¹ See above, Vol. I. p. 121 f. Prof. Kielhorn, however, thinks that Harshadēva first vanquished Kshitipāla and subsequently restored him to his throne. But, in my humble opinion, the natural interpretation that can be put on the verse is that Harshadēva placed Kshitipāla on his throne, who was ousted, not by Harshadēva himself, but by a different king. This interpretation is supported by the fact mentioned in our grant, that Indra III. reduced Mahōdaya or Kanauj, in other words defeated the then reigning sovereign, who can be no other than Kshitipāla himself. This interpretation, again, agrees with what the Khālimpur and Bhāgalpur charters have to say, as will be shown further on.

² *Ind. Ant.* Vol. XV. p. 304 ff.; *ibid.* Vol. XX. p. 187 f.

³ See above, Vol. IV. p. 243 ff.

⁴ See the photo-etching of the plates in *J. B. A. S.* Vol. LXIII. Part I.

⁵ See the *Bālarāmāyaṇa*, X. 86.

piecing together the items of information furnished by these two charters, we find that Dharmapāla defeated a prince named Indrarāja, and acquired for himself the sovereignty of Mahōdaya or Kanauj, i.e. the supremacy of Pañchāla, but conferred it upon Chakrāyudha, according to the Bhāgalpur plates, and upon the king of Kanyakubja, according to the Khālimpur plates. Further, as Dharmapāla wrested the sovereignty of Mahōdaya or Kanyakubja, not from the king of Kanyakubja himself, but from Indrarāja, and bestowed it upon the king of Kanyakubja, the conclusion is irresistible that Indrarāja must have vanquished the king of Kanauj and occupied his capital before he himself suffered defeat at the hands of Dharmapāla. What we find, therefore, from these two charters is, that (i) Indrarāja vanquished the king of Kanyakubja, but (ii) was afterwards defeated by Dharmapāla; and that (iii) the king of Kanyakubja, who was ousted by Indrarāja, was restored to his throne by Dharmapāla; whereas the facts we have above ascertained from verse 19 of our grant and a Khajurāho inscription are, that (i) the Rāshtrakūṭa prince Indra III. reduced Mahōdaya or Kanauj and deprived its ruler of his dominions, that (ii) the name of this ruler was Kshitipāla or Mahīpāla, and that (iii) Kshitipāla or Mahīpāla regained his lost possessions through the assistance of the Chandēlla king Harshadēva. Thus in both cases we have a king named Indrarāja, who attacked Mahōdaya or Kanauj and ousted the king of Kanyakubja. The Indrarāja,¹ therefore, mentioned in the Bhāgalpur and Khālimpur grants must be identical with the Rāshtrakūṭa prince Indra III., and the king of Kanyakubja, whom he vanquished, is doubtless Kshitipāla or Mahīpāla. But the honour of placing Kshitipāla on his throne is claimed for the Chandēlla prince Harshadēva by the Khajurāho inscription above alluded to, and for Dharmapāla by the Bhāgalpur and Khālimpur charters. And what in all likelihood must have come to pass is, that both Harshadēva and Dharmapāla placed Kshitipāla on his throne.

There remains another conclusion yet to be deduced from the Bhāgalpur grant. The king of Mahōdaya or Kanyakubja, whom Indrarāja ousted, is mentioned therein as Chakrāyudha. And we have just shown that this king of Mahōdaya was Kshitipāla or Mahīpāla. Kshitipāla, therefore, appears to have borne the epithet Chakrāyudha. Now, the Nausārī charters² of the Rāshtrakūṭa prince Indra III. contain a verse, wherein Indra is represented to have conquered Upēndra. Of course, the terms Indra and Upēndra, according to one sense, refer to the gods Indra and Upēndra; but when we take them in their other sense, what the verse means to state is, that the Rāshtrakūṭa prince Indra III. vanquished a certain prince of the name of Upēndra. Upēndra is another name for Viṣṇu, and Viṣṇu is also known by the name Chakrāyudha. The allusion, therefore, in the Nausārī grants most probably refers to the defeat of Kshitipāla, mentioned by the name Chakrāyudha in the Bhāgalpur charter. The Nausārī and Bhāgalpur grants thus corroborate each other, and consequently there can be little doubt that Kshitipāla also bore the epithet Chakrāyudha or Upēndra.³

¹ In *J. B. A. S.* Vol. LXIII. p. 62, Mr. Batavyal has expressed the opinion that Indra, brother of the Rāshtrakūṭa prince Gōvinda III., is the same as the Indrarāja of the Bhāgalpur charter, and the *Lātēvara-maṇḍala*, which he is mentioned in the Kāvī grant to have received from this Gōvinda III., may be identical with the kingdom of Kanauj. I leave it to those who are interested in the subject to judge of the correctness of this view.

² *J. B. A. S.* Vol. XLIX. pp. 259 and 263.

³ In his note on verse 8 of the Bhāgalpur charter in *Ind. Ant.* Vol. XX. p. 188, Prof. Kielhorn suggests that, just as Bali wrested the sovereignty of the three worlds from the god Indra and gave it to Upēndra-Chakrāyudha, his younger brother, so Dharmapāla took away the kingdom of a prince named Indra and made it over to the prince Chakrāyudha, whom, on the analogy of the mythological allusion, he thinks to be a brother of the prince Indra. In this note he proposes, with some diffidence, that this name Chakrāyudha points to Ādivarāha, which was another name of Bhōjadēva of Kanauj. In his paper on the Khālimpur plate of Dharmapāladēva (above, Vol. IV. p. 246, note 1) he puts forth the conjecture that there was some connection between Indra and Chakrāyudha of the Bhāgalpur grant and Indrāyudha, who is spoken of as governing the north in the colophon of the Jaina *Harivamśa-Purāṇa*, meaning thereby, if I have correctly understood him, that Indra is identical with Indrāyudha and that both Indrāyudha and Chakrāyudha belonged to one and the same family. But now our plates have conclusively

Two other points of some importance deserve to be noticed. The first is with regard to the date of **Dharmapāla**, who has been placed conjecturally by Cunningham and Prof. Kielhorn in the earlier part, or about the middle, of the 9th century.¹ But we have seen that Dharmapāla was a contemporary of the Rāshtrakūṭa prince Indra III., for whom the Rāshtrakūṭa records furnish the dates 915 and 917 A.D. We thus have positive evidence that Dharmapāla lived in the earlier part of the 10th century, i.e. at least half a century later than he has hitherto been placed. Next, the Mungir plates of Dēvapāladēva tell us that Dharmapāla married **Raṇṇādēvi**, daughter of the Rāshtrakūṭa prince **Śrī-Paravala**. Prof. Kielhorn, who re-edited the inscription, corrects Śrī-Paravala into **Śrī-Vallabha**.² If this correction is accepted, the Rāshtrakūṭa king, who was the father-in-law of Dharmapāla, was either Kṛishṇa II. or Indra III. himself. For Jagattuṅga, father of the latter and son of the former, died without coming to the throne. Further, it appears unlikely that Dharmapāla, if he had been the son-in-law of Indra III., would have carried on hostilities with him. On the whole, therefore, it seems more probable that Kṛishṇa II. was the father-in-law of Dharmapāla.

So much for the historical conclusions to be drawn from verse 19 of our grant. From verse 20 we gather that Indra III. married **Vijāmbā** of the **Haihaya**, i.e. Chēdi, dynasty. She is therein said to be the daughter of **Ammanādēva**, who himself was the son of **Arjuna** and grandson of **Kōkkalla**. From Indra III. and Vijāmbā sprang the prince **Gōvinda (IV.)**, "the beauty of whose form excelled that of the god of love" (v. 21). The first three lines of verse 22 look as if the composer of the inscription were giving of his own accord quite an uncalled-for defence to establish the spotless character of his patron Gōvinda IV. This is enough to lead one to suspect that certain accusations, which the composer tries to confute, were in his time actually whispered against Gōvinda IV. The second and third lines of this verse, as will be seen from the translation, defend him against the attack of sensuality and incest. This indicates that Gōvinda IV. was popularly believed to have led a dissolute life and even looked upon as incestuous. And, that he had given himself up to sensual pleasures, is mentioned in the Khārēpāṭaṇ grant and in the Dēōlī and Karhād charters. The former calls him "an abode of the sentiment of love, surrounded by crowds of lovely women."³ The two latter represent him as "the source of the sportive pleasures of love" and as "one whose intelligence was entangled in the nooses which were the eyes of women."⁴ The Dēōlī and Karhād charters, moreover, tell us that, in consequence of his sensual courses, he undermined his health and bedimmed his natural lustre. Another sense is also here intended, viz. that Gōvinda IV. incurred the displeasure of his subjects, rendered the constituents of the political body loose, and thus met with destruction. To this may be added the further statement of the aforesaid grants that, after Gōvinda IV. had thus come to ruin, the feudatory chieftains besought his uncle **Amōghavarsha** to ascend the throne and thereby maintain the **Raṭṭa**, i.e. Rāshtrakūṭa, sovereignty, and that accordingly he acceded to their request.⁵ Mr. K. B. Pathak has drawn my attention to a passage in the *Vikramārjunaviṣaya* by the Kanarese poet **Pampa**, which has an important bearing

proved that the Indra, who is associated with Chakrāyudha in the Bhāgalpur charter, was a Rāshtrakūṭa prince, holding sway in the Dekkan, and cannot, therefore, be identified with Indrāyudha, who was ruling in the north, and that this Rāshtrakūṭa king Indra can neither be the elder brother of, nor belong to the same family with, Chakrāyudha, who was king of Kanauj.

¹ See above, Vol. IV. p. 246; *Ind. Ant.* Vol. XXI. p. 254; *Arch. Sur. Rep.* Vol. XV. p. 150, where Cunningham fixes the accession of Dharmapāla in A.D. 831. Now that we know that Dharmapāla was a contemporary of the Rāshtrakūṭa prince Indra III., the mention of the week-day and the regnal year in his Mahābōdhi inscription can be utilised to determine much more approximately the date of Dharmapāla's accession, as was first suggested by Cunningham.

² *Ind. Ant.* Vol. XXI. p. 254, and note 10 on p. 90.

³ Above, Vol. III. p. 298, text line 10.

⁴ Above, Vol. IV. p. 283 f., verse 20; Vol. V. p. 194, verse 18.

⁵ Above, Vol. IV. p. 284, verse 21; Vol. V. p. 194, verse 19.

on this point. The translation of the passage, as kindly supplied to me by him, is as follows:—
 “Arikēsari conquered the great feudatories sent by the emperor named Gojjiga and, destroying the emperor who offered opposition, gave universal sovereignty to Baddegadēva, who came placing confidence in him (Arikēsari).”¹ Of the personages mentioned in this passage, Arikēsarin (II.) was the patron of Pampa and was a Chalukya chieftain, ruling over the Jōla country, which in the main coincides with the Dharwar district; Gojjiga was the Rāshtrakūṭa sovereign Gōvinda IV., and Baddegadēva his uncle Vaddiga *alias* Amōghavarsha. Now, piecing these facts together, the conclusions that we arrive at, are (i) that Gōvinda IV. was a sensual monarch; (ii) that by his vicious courses he displeased his subjects, and some of his feudatories as may be naturally presumed; (iii) that these feudatories, including Arikēsarin II.,² rose in rebellion against Gōvinda IV., met him and his tributary allies in battle and killed him; and (iv.) that Arikēsarin II. together with the victorious feudatories requested his uncle Amōghavarsha to occupy the Rāshtrakūṭa throne, which had fallen vacant by the death of Gōvinda IV.

So far we have dealt with the second and third lines of verse 22. We have yet to find out the full significance of the first line, which, as will be seen from the translation, means to state that Gōvinda IV. did not practise cruelty towards his elder brother, although he had the power to do so. This evidently presupposes that, in his time, Gōvinda IV. was commonly understood to have acted cruelly towards his elder brother. This is the natural inference to be deduced from the first line, unless it is to be regarded as meaningless. It now behoves us to see what probably constituted this cruelty. The name of this elder brother, as known from copper-plate inscriptions, was Amōghavarsha (II.). That he came to the throne can scarcely be seriously doubted. Dr. Fleet, however, has taken exception to this view, on the ground that Gōvinda IV., in his Sāṅgī charter, describes himself as meditating on the feet of, not his elder brother Amōghavarsha, but his father (Indra-)Nityavarsha.³ But this conclusion is directly contradicted by the Rāshtrakūṭa and other records. The Bhādāna and Khārōpāṭa charters, which scrupulously give the list of those Rāshtrakūṭa princes only who reigned, mention therein the name of Amōghavarsha.⁴ The Dēlī and Karhāḍ grants, which mention those princes, who did not reign, as specifically not having reigned, do not speak of Amōghavarsha as not having reigned, but on the contrary, furnish positive indications that he did reign.⁵ Nay, we may proceed a step further. The last mentioned charters assert that Amōghavarsha II. went to heaven soon after his father's death, as if out of affection for the latter.⁶ This indicates that Amōghavarsha II. reigned only for a very short period. This inference receives a strong confirmation from the Bhādāna grant, which distinctly tells us that Amōghavarsha reigned for a year only. Now, placing together the fact that the duration of Amōghavarsha's reign was very brief, and the implication derivable from the first line of verse 22 that Gōvinda IV. was popularly supposed to have treated his elder brother, *i.e.* Amōghavarsha, cruelly, one is naturally inclined to hold that Gōvinda IV. was chiefly instrumental in shortening the period of Amōghavarsha's reign, or that, in other words, Gōvinda IV., if not actually caused, at any rate hastened, the death of his elder brother and usurped his throne. If this is so, Gōvinda IV. can by no means be expected in any one of his copper-plate grants to speak of himself as meditating on the feet of his elder brother Amōghavarsha, although the latter was his predecessor. But to conclude from this circumstance that Amōghavarsha did not reign, is entirely to set aside the

¹ Pampa's *Vikramārjunaviṣaya*, edited by Mr. Rice, Āśvāsa IX. p. 196, ll. 5-9.

² Pampa would have us believe that Arikēsarin II. played a prominent part in defeating the allies of Gōvinda IV. and putting him to death; but as Indian poets are in the habit of magnifying the deeds of their patrons, one may reasonably doubt whether Arikēsarin II. actually led the rebellion against Gōvinda IV. as his protégé tells us.

³ *Dyn. Kan. Distr.* p. 416 and note 5; above, Vol. VI. p. 176 f.

⁴ Above, Vol. III. p. 271, verse 6; *ibid.* p. 298, the second half of the last line of verse 8.

⁵ Above, Vol. IV. p. 283, verse 18; Vol. V. p. 193 f., verse 15.

⁶ See verses 19 and 17.

positive evidence, looking quite the other way, furnished by the copper-plate inscriptions, and to render the first line of verse 22 void of all meaning.

The last line of verse 22 tells us that Gôvinda IV. was known as *Sâhasânka* in consequence of his unparalleled heroic deeds. Verse 23 states that, although he had the appellation *Prabhûtavarsha*, he was styled *Suvarnavarsha*, because he rained down showers of gold and made the whole world golden. This means that Gôvinda IV. had previously the usual epithet *Prabhûtavarsha*, but that, on account of his profuse munificence, he earned for himself the additional *biruda* of *Suvarnavarsha*. And deservedly was he styled *Suvarnavarsha*. It has been mentioned above, in the summary of the contents of the formal part of the inscription, that Gôvinda IV. weighed himself against gold, bestowed upon the Brâhmanas no less than six hundred grants, together with three lacs of *suvarnas*, and granted, for repairing temples and feeding and clothing ascetics, eight hundred villages, four lacs of *suvarnas* and thirty-two lacs of *drammas*. Such exuberant liberality no other prince of the Râshtrakûta dynasty ever displayed, so far as their records inform us.

Little that is historically important can be gleaned from the remaining verses (24-31). Some historical fact, however, is undoubtedly contained in verse 28, wherein the *Gaṅgâ* and *Yamunâ* are represented as doing service at Gôvinda IV.'s palace. The exact sense of this can be determined by the consideration of two other epigraphic references to the same fact. The Baroda charter of the Gujarât Râshtrakûta prince Karka asserts that Gôvinda III., "after taking away simultaneously from his enemies (the rivers) *Gaṅgâ* and *Yamunâ*, charming through their waves, attained to the best and highest rank, by means of the display of the actual signs (of those rivers)."¹ This clearly means that Gôvinda III. wrested the territory intervening between the Ganges and the Jumna from a prince belonging to some northern dynasty, and assumed their signs as a part of his *insignia*. The same fact is mentioned in a Nerûr grant, wherein the early Chalukya prince Vijayâditya is represented as fighting before his own father with the hostile kings of Northern India, and securing for his father Vinayâditya the signs of the *Gaṅgâ* and *Yamunâ* among other *insignia* of paramount sovereignty.² When, therefore, the *Gaṅgâ* and *Yamunâ* are mentioned as doing service in the palace of Gôvinda IV., a similar thing is intended, *viz.* either that, after an expedition of conquest against Northern India, he added the signs of these rivers to his *insignia*, or that he inherited these signs from some one of his predecessors, perhaps his own father Indra III., who, as we have seen above, overran Northern India.

There now remains to be noticed the preamble of the prose passages, preceding the formal part of the inscription. These set forth the various appellations by which Gôvinda IV. was known. The topic of the appellations of the Râshtrakûta princes has already been handled in

¹ *Ind. Ant.* Vol. XII. p. 159, text lines 22 and 23. Here Dr. Fleet perceives a distinct allusion to some conquest over the Chalukyas, whether Western or Eastern, and further propounds the theory that the Râshtrakûtas wrested these signs from the Chalukyas, and the Chalukyas from the Early Guptas (*loc. cit.* pp. 157 and 248; *Dyn. Kan. Distr.* p. 338, note 7). In my humble opinion, the word *cha* in the second line of the verse, wherein Gôvinda III.'s assumption of the signs of the *Gaṅgâ* and the *Yamunâ* is mentioned, clearly indicates that he first conquered the regions round about the Ganges and the Jumna and then adopted the signs of these rivers as part of his *insignia*. Dr. Fleet himself recognises this fact (*loc. cit.* p. 157). If so, I cannot understand how Gôvinda III. wrested these signs from the Chalukyas, whether Western or Eastern, who were ruling in the Dekkan, far away from the Ganges and the Jumna. Again, I fail to understand how the Chalukyas, towards the end of the seventh century, wrested these signs from the Early Guptas, whose power was extinct by the middle of the sixth century A.D. The view which I have put forth here is, that an expedition of conquest in the regions round about the Ganges and the Jumna entitled both Gôvinda III. and Vijayâditya to add the signs of these rivers to their *insignia*. The same may also be said in regard to Gôvinda IV.; but, as we do not know for certain that he ever invaded Northern India, and as we do know that his father Indra III. overran it, it is equally reasonable to suppose that Gôvinda IV. perhaps inherited these signs from his father.

² *Ind. Ant.* Vol. IX. p. 131, text lines 20-22.

detail by a much abler antiquarian than myself.¹ I shall, therefore, be as brief as possible. The first of the appellations mentioned of Gōvinda IV. is *Nitya-Kandarpa*, which he is said to have received because he outshone the god of love. In accordance with this, verse 21 speaks of him as a prince, "the beauty of whose form excelled that of the god of love." His father Indra III. also bore the appellation *Raṭṭa-Kandarpadēva*,² from which it may be inferred that the Rāshtrakūṭa kings had some of their *birudas* ending in *Kandarpa*. The second of these appellations is *Chāṇakya-Chaturmukha* or '(the god) Brahman (in regard to the art) of Chāṇakya,' i.e. civil polity. What this phrase signifies is that, just as the Vēdas emanated from the god Brahman, so civil polity originated from Gōvinda IV. His third appellation is *Vikrānta-Nārāyaṇa*. This reminds us of the epithets *Vira-Nārāyaṇa* and *Kirti-Nārāyaṇa*, borne respectively by Amōghavarsha I. and Indra III.,³ and points to the conclusion that some of the Rāshtrakūṭa *birudas* ended in *Nārāyaṇa*. The last appellation of Gōvinda IV. referred to in the preamble is *Nripati-Trinētra*, which corresponds to *Mahārāja-Śarva*,⁴ mentioned by the Gujarāt Rāshtrakūṭa records with reference to Amōghavarsha I. The titles of Gōvinda IV., occurring in the formal part of the inscription, are too general to require any special notice.

As regards the places mentioned in the grant, *Kēvañja*, the village granted, is the *Kimōj* or *Kimaj* of the present day, *Kāvika* the well-known *Kāvi*, and *Sihukagrāma* the modern *Sigām* or *Śigām*. The names of these villages occur in the "Inscriptions from *Kāvi*"⁵ by Dr. Bühler, under the slightly altered forms of *Kēmajju*, *Kāpikā* and *Sihugrāma*. It deserves to be noticed that *Kāvika* is in our inscription called a *mahāsthāna*, i.e. a holy place. This indicates that *Kāvika* or *Kāvi* was not formerly noted as a mere sacred place of the Jainas, as it is now, but was a centre of Brāhmanism, and that its sanctity goes back to the beginning of the tenth century A.D. It is also interesting to note that *Kēvañja*, the village granted, is said in our plates to be situated in the *Khēṭaka* district of the *Lāṭa dēśa*. This implies that the province of *Lāṭa* included the city of *Khēṭaka* or *Kaira*, and also a small portion of territory to its north, as may naturally be presumed. The view of Dr. Bühler and Pandit Bhagwanlal Indraji⁶ that *Lāṭa* corresponds to the country between the *Mahī* and the *Konkan* or the *Tapti* is, therefore, not tenable, and that held by Dr. Hultzsch⁷ that it extended as far north as the *Shēri* (*Shēṭhi*) is correct.

TEXT.⁸

First Plate.

- 1 श्री⁹ स्वस्ति ॥ स¹⁰ वोव्यादेधसा धाम यन्नामिकमलङ्कृतम् । ह्वय
यस्य कान्तेन्दुकलया कमलङ्कृतम् ॥ [१*] जयन्ति ब्रह्मणः¹¹ सर्गनि-
2 व्यत्तिमुदितात्मनः । सरस्वतीकृतानन्दा मधुराः सामगीतयः ॥ [२*]
सान्द्रैः¹² श्रीस्तनभारभूरिमकरीकाश्रीरसमिश्रितैः

¹ Above, Vol. VI. pp. 160-198.

² *J. Bo. Br. R. A. S.* Vol. XVIII. pp. 259 and 263.

³ *Ibid.* pp. 258 f. and 262 f.

⁴ In *J. Bo. Br. R. A. S.* Vol. XX. p. 146, I understood the expression to mean 'the illustrious great king Śarva' but now I think that with Dr. Fleet it must be translated 'a very Śarva (Śiva) among *Mahārājās* or great kings' (above, Vol. VI. p. 174 and note 7; *Dyn. Kan. Distr.* p. 401 and note 4).

⁵ *Ind. Ant.* Vol. V. pp. 112, 114, 145 and 147.

⁶ *Ind. Ant.* Vol. V. p. 145; *History of Gujarāt*, in the *Gazetteer of the Bombay Presidency*, Vol. I. Part I. p. 7.

⁷ *Ind. Ant.* Vol. XIV. p. 198.

⁸ From the original plates.

⁹ Expressed by a symbol.

¹⁰ *Metre*: *Śloka* (Anuṣṭubh); and of the next verse. This verse, which occurs in almost all the Rāshtrakūṭa records, is, however, not to be found in the Sāngli plates.

¹¹ Read ब्रह्मणः.

¹² *Metre*: *Sārdūlavikrīḍita*; and of the next verse. Both these verses do not occur in the Sāngli plates.

- 3 प्रोम्नज्जजरजगैरिकरजःपुञ्जद्रवैः पिञ्जराः¹ । क्षीराब्धेः² क्षुभितस्य मन्द-
गिरिव्यावर्त्तनादुद्गताः कल्लोला जन-
- 4 यन्ति यस्य पुलकम्पायात् वः केशवः ॥ [३*] शम्भोर्यानि शिरःस्थि-
तस्य फणिनामृत्युः फणानां दश द्योतन्ते परितः
- 5 शतानि समण्योतीर्षि जूटाटवीम् । एनस्तान्युपरिसवत्सुरसरित्सिक्तेन्दु-
कन्दोत्तसज्ज्योत्स्नाकल्पलतालवालव-
- 6 लयश्रीभाञ्जि भञ्जन्तु वः ॥ [४*] ³ताराचक्राजप्रण्डावृतगगनसरःपद्भि-
नीराजहंसाक्षैलाक्षैकाधिपत्यस्थितमदनमहारा⁴
- 7 जशुभ्रातपचात् । लावण्यक्षीरसिन्धोर्युतिरजतगिरेर्द्विग्वधूदन्तपंचादंशः सोमा-
दयं यस्त्रिभुवनकमलावाससौधादुप्रेतः⁵ ॥ [५*]
- 8 ⁶तस्माच्छ्रियः कुलगृहं भवनं महिम्नः क्रीडास्पदं स्थितिमहर्द्धिगभीरता-
नाम् । आपन्नसत्त्वपरिपालनलब्धकीर्त्तिर्विशो⁷ वभूव⁸ भु-
- 9 वि सिन्धुनिभो यदूनाम् ॥ [६*] ⁹परिणतपरमण्डलः कलावाग्प्रवितत-
वहलयशोशपूरिताशः¹⁰ । शशधर इव दन्तिदुर्गराजो यदु-
- 10 कुलविमलवियत्यथोदियाय ॥ [७*] ¹¹तस्याद्यं नृपतेः पितृव्य उदयी
श्रीवीरसिंहासनं मेरोः शृङ्गमिवाधिरुह्य
- 11 रविवच्छ्रीकृष्णराजस्ततः । ध्वस्तोद्विक्तचलुक्थवंशतिमिरः पृथ्वीभृतां मस्तके
न्यस्ताङ्गिः¹² सकलं जगत्प्रविततैस्ते-
- 12 जीभिराक्रान्तवान् ॥ [८*] ¹³तस्मान्नोविन्दराजोभूदिन्दुविम्बशिलावले¹⁴ ।
यस्यारिप्लोषधूमोद्भूतः प्रशस्तिरिव लक्ष्यते ॥ [९*]
- 13 ¹⁵तस्याभवद्भुवनपालनवीरवृद्धिरुद्धूत[श]नुकुलसन्ततिरिद्धतेजाः¹⁶ । राजानुजो
निरुपमापरनामधेयो यन्मुद्रयास्त्रधिरपि¹⁷ प्रथितः
- 14 समुद्रः ॥ [१०*] तदनु¹⁸ जगत्तुङ्गीजनि परिहृतनिजसकलमण्डलाभोगाः ।
गतयौवनवनिताजन[कु]चसदृशा यस्य वैरिनुपाः ॥ [११*]
- 15 ¹⁹तस्माच्चामीघवर्षोभवदतुलवलो²⁰ येन कोपादपूर्वैश्चालुक्थाभ्युपखाद्यैर्जनितर-
तियमः प्रीणितो विङ्गवल्गाम्²¹ । वैरिंचा-

Read पिञ्जराः.

² Read क्षीराब्धेः.³ Metre: Sragdharā; read °चक्राज°.⁴ Read °क्षैलाक्षै°.⁵ Read °दुप्रेतः°.⁶ Metre: Vasantatilakā.⁷ Read °लक्ष्म°.⁸ Read वभूव.¹⁰ Read °वहल°.⁹ For the metre see the introductory remarks.¹¹ Metre: Śardūlavikrīḍita.¹² Read न्यस्ताङ्गिः. The middle vertical stroke of the letter gha is inadvertently omitted.¹³ Metre: Ślōka (Anuṣṭubh).¹⁴ Read °विम्बशिलावले°.¹⁵ Metre: Vasantatilakā.¹⁶ Read °वृद्धि°.¹⁷ Read °यास्त्रधि°.¹⁸ Metre: Āryā.¹⁹ Metre: Sragdharā.²⁰ Read °वलो°.²¹ Read °वल्गाम्°.

- 16 'ण्डोदरान्तर्विहिरपरितल' यत्र 'लब्धावकाशं तोयव्याजाद्विशुद्धं' यश्च इव
निहितं तज्जगत्तुङ्गसिन्धौ ॥ [१२*] 'तस्मादकालवर्षो नृपति-
17 रभूद्यत्पराक्रमवस्त्रैः । सद्यः समण्डलाग्रं खेटकमहितैः परित्यक्तम् ॥ [१३*]
'सहस्रार्जुनवंशस्य भूषणं कीकलात्मजा । तस्याभ-
18 वन्महादेवी जगत्तुङ्गस्तोजनि ॥ [१४*] 'गम्भीराद्रन्ननिधेर्भूभृद्यतिपक्ष-
रक्षणक्षमतः । कीकलसुतरणविग्रहजलधेर्लक्ष्मीः स-
19 सुत्यन्ना ॥ [१५*] सा⁷ जायाजायताजातशत्रोस्तस्य महीभृतः । भीम-
सेनार्जुनीपात्तयशोभूषणशालिनः ॥ [१६*] तत्र⁸ जगत्तुङ्गोदय-
20 ध[र]णीधरतः प्रतापकलितात्मा । लक्ष्म्या नन्दन उदितोजनि विजयी
राजमार्तण्डः ॥ [१७*] स्थितिचलितसकलभूभृत्पक्षच्छेदाभिसुक्त-
21 भुजवज्रः । अनिमिषदर्शनयोग्यो यः सत्यमिहेन्द्रराज इति ॥ [१८*]
'यन्माद्यद्विपदन्तघातविषम'¹⁰ कालप्रियप्राङ्गणं तीर्णं

Second Plate; First Side.

- 22 यत्तुरगैरगाधयमुना सिन्धुप्रतिस्पर्द्धिनी । येनेदं हि महोदयारिनगरं
निर्मलसुभूलितं नान्माद्यापि जनैः कुशस्थ-
23 लमिति ख्यातिं परां नोयते ॥ [१९*] यस्तस्मिन्दशकण्ठदर्पदलने श्री-
हैहयानां कुले कीकलः प्रतिपादितोऽस्य च गुणज्ये-
24 ष्ठोर्जुनोभूतः । तत्पुत्रोऽस्मिन् देव¹¹ इत्यतिवलस्तस्माद्विजास्वाभवत्पद्मेवासुनिधे-
रमेव¹² हिमवन्नाम्नः क्षमाभृत्प्र-
25 भोः ॥ [२०*] ¹³ श्रीन्द्रनरेन्द्रात्तस्यां सूनुरभूद्रूपतिर्विजाम्बायाम्¹⁴ । गोवि-
न्द्रराजनामा कामाधिकरूपसौन्दर्यः ॥ [२१*] सामर्थ्ये¹⁵ सति
26 निन्दिता प्रविहिता नैवापले क्रूरता¹⁶ वन्मुखीगमनादिभिः कुचरितैराव-
र्जितं नायशः । शौचाशौचपराङ्मुखं न च भि-
27 या पैशाच्यमङ्गीकृतं त्यागिनासमसाहसैश्च भुवने यः साहसाङ्गोभवत् ॥
[२२*] ¹⁷ वर्षन्मुवर्णवर्षः प्रभूतवर्षोऽपि कनकधा-
28 राभिः । जगदखिलमेककाञ्चनमयमकरोदिति¹⁸ जनैरुक्तः ॥ [२३*] कः¹⁹
केनार्थो को दरिद्रः प्रथिव्यामित्यं घृष्टे हारि लिप्सो-

¹ Read 'वर्द्धि'.

² Metre: Āryā.

³ Metre: Ślōka (Anuṣṭubh).

⁴ Metre: Śārdūlavikrīṭa; and of the next verse. This verse does not occur in the Sāngli plates.

⁵ Read यन्माद्यद्विप'.

⁶ Metre: Āryā.

⁷ Read वन्'.

⁸ Metre: Śālinī. This verse does not occur in the Sāngli plates.

⁹ Read 'तले'.

¹⁰ Metre: Ślōka (Anuṣṭubh).

¹¹ Metre: Āryā; and of the next verse.

¹² Read 'विषल'.

¹³ Read 'जाम्बा'.

¹⁴ Metre: Āryā.

¹⁵ Read 'काञ्चनमय'.

¹⁶ Read लब्धा'.

¹⁷ Metre: Āryā.

¹⁸ Read 'जाम्बा' and 'वासुनिधे'.

¹⁹ Metre: Śārdūlavikrīṭa.

²⁰ Read 'काञ्चनमय'.

E WIL T7SCH:

22

24

26

82

30

32

4

6

88

- 29 रभावात् । हेलसिद्धैर्दीपनाथैः प्रणीतोप्युच्चैः कोशः प्रीतयं यस्य नभस्तु
॥ [२४*] ^१यदधिदिग्विजयावसरे सति प्रसभसं-
- 30 भ्रमभावनयेव भूः । सपदि नृत्यति ^२पालिमहाध्वजोच्छृतकरान्यकुनय-
विवर्जिता ॥ [२५*] स[ह]ति^३ न हि मण्डलाधि-
- 31 पं परमेषोभ्युदयो समुद्धतम् । इति जातभियाविवाग्रतो रविचन्द्रापि
यस्य धावतः ॥ [२६*] ^४अवनतपर-
- 32 मण्डलेश्वरं सहविजयश्रमभिवेश्म शोभितम् । समहिमकरतोरणं चिर
निजतेजस्तति यस्य राजते ॥ [२७*] सहेत^५
- 33 समवाहिनीमयं न परेषां सविशेषशालिनीम् । यदनिन्दितराजमन्दिरं
ननु गङ्गा यमुना च सेवते ॥ [२८*] ^६यस्मिन् राज-
- 34 नि सौराज्यं निर्जितारि वितन्वति । विमानस्थितिरित्यासीन्न भोग्य
कदाचन ॥ [२९*] ^७यस्योद्दामप्रतापानलवहलशिखाकज्जलं
- 35 नीलमेघा विस्फूर्जितखड्गधारास्फुरणविसरणान्येव विद्युद्विलासाः । दुर्जारा-
रीभकुम्भस्थलदलनगलन्मीत्तिकान्येव ताराश्च-
- 36 न्द्रक्षीराब्धिग्रीवा^८ भृतभुवनयशोराशिनिथन्दितानि ॥ [३०*] ^९यस्मिन्कण्ट-
- कशोधनोत्सुकमनस्यभोजनालैर्मियेवोन्नतं न पयः-
- 37 सु कोशवसतिर्लक्ष्मीः क्षतोपायनम् । केतव्या पवनोल्लसन्निजरजःपुञ्जान्धकारो-
दरे भूगर्भे पनसेन वेत्ततया [दा]र्या-
- 38 लशुद्धै स्थितम् ॥ [३१*] यश्च समुपहसितहरनयनदहनविहि-
तानित्यकन्दर्परूपसौन्दर्यदर्पः श्रीनित्यकन्दर्पः । प्रभुमन्त्र-
- 39 ^{१०}शक्त्युपवृद्धितोत्साहशक्तिसमाक्षिप्तशतमुखसुखश्यामकचतुर्मुखः । प्रथितैकवि-
क्रमाक्रान्तवसुन्धराहितकरणपराय-

Second Plate; Second Side.

- 40 णः श्रीविक्रान्तनारायणः । स्वकरकलितहेतिहलदलितविपक्षवक्षःस्थलक्षेत्र-
श्रीनृपतिचिनेत्रः समभवत्स^{१२} च परमभट्टार-
- 41 कमहाराजाधिराजपरमेश्वरश्रीमन्त्रित्यवर्षदेवपादानुध्यातपरमभट्टारकमहाराजा-
धिराजपरमेश्वरश्रीमत्सुवर्णवर्ष-
- 42 देवपृथ्वीवत्सभश्रीवत्सभनरेन्द्रदेवः कुशलो । सर्वानिव ^{१३}यथासम्बद्धमानकाशा-
द्वपतिविषयपतिग्रामकूटमहत्तरयुक्तको-

^१ Metre: Drutavilambita.

^२ Metre: Aparavaktra.

^३ Metre: Sragdharā.

^४ Metre: Śārdūlavikrīḍita.

^५ Read 'सम्बद्धमान'.

^६ Read 'अजोक्षित'.

^७ Metre: Viyōgini.

^८ Read 'बहल'.

^९ Read 'बंहितो'.

^{१०} Metre: Viyōgini.

^{११} Metre: Ślōka (Anuṣṭubh).

^{१२} Read 'क्षीराब्धि'.

^{१३} Read समभवत् ॥ स च.

- 43 पयुक्तवाधिकारिकान्समादिशत्यस्तु वः संविदितं यथा मान्यखेटराजधानी-
स्थिरतरावस्थानेन मातापित्रोरात्मनश्च पुण्ययशो-
- 44 भिवृद्धये पूर्वपुस्तानपि देवभोगाग्रहारात्प्रतिपालयवा¹ प्रतिदिनं च निर-
वधिनमस्यग्रामशासनानि प्रयच्छता मया शकनृप-
- 45 कालातीतसंवत्सरशतेष्वष्टसु द्वापञ्चाशदधिकैस्वङ्गतोपि शकसंवत् ८५२ प्रव-
र्त्तमानखरसंवत्सरान्तर्गतज्येष्ठशुद्धदश-
- 46 म्यां सोमदिने हस्तसमीपस्थे चन्द्रमसि गोदावरीतटसमीपस्थे कपित्थकग्रामे
पट्टवन्धमकोत्सवे² तुलापुरुषमारुह्य
- 47 ब्राह्मणेभ्यः³ षट्छतान्यग्रहाराणां सुवर्णलक्षत्रयसमेतानि 'वलिचरुवैश्वदेवा-
तिथितर्पणार्थं दत्त्वा । देवभोगार्थं च
- 48 देवकुलेभ्यः खण्डस्फुटितादिनिमित्तं गन्धधूपपुष्पदीपनैवेद्याद्युपचारार्थं तपो-
वनस्य⁴ सचीत्तरासङ्ग-
- 49 दानाद्यर्थश्च⁵ ग्रामाणामष्टशतानि सुवर्णलक्षत्रचतुष्टयं द्रुमलक्षत्रात्रिंशतं च
दत्त्वा । तदनन्तरं च तुलापु-
- 50 रुषादननुत्तरतैव मया प्रथमकरोदकोत्सर्गेण लाटदेशखेटकमण्डलान्तर्गतका-
विकामह्मस्थानवि-
- 51 निर्गताय⁶ इहैव मान्यखेटे वास्तव्याय श्रीमद्वल्लभनरेन्द्रदेवपादपद्मी-
पुत्रीविने माठरसगोत्रवाजिकाखसत्र-⁷
- 52 ह्मचारिणे महादेवय्यसुताय नागमार्याय लाटदेशान्तर्वर्त्तिखेटकमण्डला-
न्तर्गतः केवञ्चनामा ग्रामः काविकामह्म-
- 53 स्थाननिकटतत्त्वर्त्ती । सवृक्षमालाकुलशतःसीमापर्यन्तः सकर्मान्तः सोदङ्गी
धान्यायहिरण्यायदण्डदोषद-
- 54 शापराधादिसमस्तोत्पत्तिसंहितो दत्तः । 'वलिचरुवैश्वदेवातिथितर्पणा-
र्थङ्काम्यनित्यनैमित्तिककर्मोपयोग-
- 55 निमित्तं दर्शपूर्णमासचातुर्मास्याष्टकाग्रयणपक्षादिश्राद्धकर्मोष्ठीक्रियाप्रवृत्तये
चरुपुरोडाशस्थालीपाकश्रवणा-
- 56 दिक्कर्मनिमित्तं होमनियमस्वाध्यायाध्ययनोपासनदानदक्षिणार्थं राजसूय-
वाजपेयाग्निष्टोमादिसप्तशोमसंस्था-¹⁰

¹ Read 'प्राप्तयता.² Read 'वन्धमकोत्सवे.³ Read ब्राह्मणेभ्यः.⁴ Read वलि.⁵ Read तपोवनस्य.⁶ Here the *sha* of *riha* is almost like the letter *sha*.⁷ Read 'तायैव.⁸ Read 'सत्र'.⁹ Read वलि.¹⁰ Read 'सप्तशोम'.

[illegible]

Third Plate.

- 57 कृतूपकरणार्थं ¹मित्रावरुणाध्वर्युहोतृब्राह्मणाच्छंसिग्रावस्तुदग्नीवभृतीनामृत्विजां
वस्त्रालंकारसत्कारदानदक्षिणा-
- 58 दिनिमित्तं ²सत्रप्रपाप्रश्रयदृष्टोत्सर्गवापीकूपतडारामदेवालयदिकरणोपकर-
णार्थञ्च ॥ यस्य च ग्रामस्याघाटाः ।
- 59 पूर्वतः काविकामहास्थानसीमान्तो दक्षिणतः सामगं नाम ग्रामः पश्चि-
मतः सीङ्गकग्रामः । उत्तरतोप्यस्यैव कावि-
- 60 काभिधानस्य स्थानस्य सम्बन्धी³ तलसीमान्तः ॥ एवममुं चतुराघाटवि-
शुद्धं केवञ्चनामानं ग्रामं नागमार्यस्य कृषतः क-
- 61 र्ययतो वा भुञ्जती भोजयती वा न केनचिद्वाघातः कर्त्तव्यः ॥
⁴सामान्योयन्मर्म्मसेतुर्नृपाणां काले काले पालनीयो भव-
- 62 ङ्गिः । सर्वानेतान्भाविनः पार्थिवेन्द्रान्भूयो भूयो याचते रामभद्रः ॥
[३२*] ⁵आगामिभूमिपतिभिः परिरक्ष्य एष धर्म्म प्रति
- 63 प्रतिनिविष्टतमैस्तथान्यैः । लक्ष्म्यास्तडितुलितवुहुदचञ्चलाया⁶ दानं फलं
परयशःप्रतिपालनं च ॥ [३३*] ⁷वहुभिर्व्वसु-⁸
- 64 धा दत्ता राजभिः सगरादिभिः । यस्य यस्य यदा भूमिस्तस्य तस्य
यदा⁹ फलम् ॥ [३४*] तथा चोक्तं वेदव्यासेन ॥ ष-
- 65 ष्टिं वर्षसहस्राणि स्वर्गे वसति भूमिदः । आच्छेत्ता ¹⁰सानुमन्ता च
तान्येव नरके वसेदिति¹¹ ॥ [३५*] स्वदत्तां प-
- 66 रदत्तां वा यो हरेत् वसुन्धराम् । अपि वर्षसहस्राणि विष्ठायां
जायते कृमिः ॥ [३६*] ¹²गङ्गाधरार्य्यतनये-
- 67 न कृतधिया नागवर्म्मणा लिखितम् । शासनमिदं प्रशस्तं श्रीमहो-
विन्दराजस्य ॥ [३७*] मङ्गलं महाश्रीः ॥¹³

TRANSLATION.

Om. Hail !

(Verse 1.) May he (Vishnu), the water-lily (*springing from*) whose navel was made (*his*) abode by Vêdhas (Brahman), protect you, and Hara (Śiva) whose head is adorned by the beautiful crescent of the moon !

(V. 2.) Triumphant are the sweet songs of the *Sāmapêda* of (*i.e.* sung by) Brahman whose soul was delighted by the creation of the world,—(*songs*) which gave delight to Sarasvatî !

¹ Read मैत्रावरुणा° and °ब्राह्मणा°. ² Read °प्रतिश्रय° and °तडागाराम°.

³ Read सम्बन्धी.

⁴ Metre: Śālinî.

⁵ Metre: Vasantatilakâ.

⁶ Read °वुहुद°.

⁷ Metre: Ślōka (Anuṣṭubh); and of the next two verses.

⁸ Read बहु°.

⁹ Read ददा.

¹⁰ Read चानु°.

¹¹ Read वसेत् । इति.

¹² Metre: Āryā.

¹³ Here follows a flower, for which see the accompanying Plate.

(V. 3.) May that Kēśava (Vishṇu) protect you, on whose person horripilation was caused by the waves, which sprang up in the milky ocean agitated by the revolution of the Mandara mountain, and which were reddened by the dense washings of quantities of red chalk of the best of the elephants,¹ emerging (*from the ocean*),—(*washings*) which were mixed with the saffron of the numerous (*marks of*) female crocodiles on the full breasts of Śrī!

(V. 4.) May these ten hundred hoods of the lord of snakes dwelling on the head of Śaṁbhu (Śiva) destroy your sin,—(*hoods*) which with the light of their jewels shine all round the forest of the mass of matted hair, and which bear the beauty of the circular basins of the wish-giving creepers (*consisting of*) the lustrous rays coming from the root, (*viz.*) the moon sprinkled by the celestial river (Gaṅgā) flowing on high!

(V. 5.) From the Moon, (*who is*) the royal swan of the lotus-plants of the lake (*viz.*) the sky, filled up with a crowd of lotuses (*which are*) the group of stars; (*who is*) the white parasol of the great king Cupid wielding the sovereignty of the three worlds; (*who is*) the milky ocean of beauty; (*who is*) the silvery mountain (Kailāsa) of lustre; (*who is*) the ear-ornament of the damsels (*viz.*) the quarters; (*and who is*) the dwelling-mansion of the goddess of wealth of the three worlds, there arose this race.

(V. 6.) From that (*race*) sprang up the family of the Yadus, (*which was*) the paternal residence of wealth, the abode of magnanimity, the pleasure-house of lawful conduct, great prosperity and gravity, (*and*) which acquired fame by the protection of distressed beings, just as the ocean (is the family-house of the goddess of wealth, the abode of grandeur, the play-ground of steadiness, vast magnitude and profundity, and is renowned for sheltering all creatures that come to it).

(V. 7.) Then there arose, in the spotless family of the Yadus, Dantidurgarāja, to whom the hosts of (*his*) enemies bowed down, who was versed in arts, (*and*) who filled the directions by (*his*) extensive and great fame, just as the moon (*rides*) in the clear sky, to whom other orbs bow down, who is possessed of digits, (*and*) who fills the quarters by (*his*) extensive and profuse rays.

(V. 8.) After him the prosperous (*and*) glorious Kṛishṇarāja, the paternal uncle of that king,—having ascended the pre-eminent (*and*) glorious lion-throne of the brave, as the rising sun (*ascends*) the peak of the Māru (*mountain*); having destroyed the vast race of the Chalukyas, (*as the sun destroys*) utter darkness; (*and*) having placed his foot on the heads of kings, (*as the sun casts*) his rays on the tops of mountains,—pervaded the whole universe by (*his*) extensive powers, (*as the sun fills*) the whole world with (*his*) overspreading rays.

(V. 9.) From him was born Gōvindarāja, whose panegyric is seen, as it were, (*engraved*) on the surface of the stone (*viz.*) the disc of the moon in the form of the mark which is dark by the burning of (*his*) enemies.

(V. 10.) His younger brother, possessed of burning lustre² (*and*) bearing the other appellation of Nirupama, became king, whose intellect was adequate for the protection of the world, who uprooted the continuous line of the family of (*his*) enemies, (*and*) by means of whose seal even the sea became renowned as *samudra* (sealed).³

(V. 11.) After him flourished Jagattuṅga, whose princely enemies, deprived of the extent of all their territory, (*became*) like the breasts of women destitute of youth,—(*breasts*) which are shorn of all their plump circumference.

¹ This refers to Airāvata, the elephant of Indra, who was produced by the churning of the milky ocean.

² I am inclined to hold with Dr. Fleet that *lādhatās* is not a mere attribute of Dhruva-Nirupama, but is intended to represent one of his *birudas* (*Ind. Ant.* Vol. XII. p. 252; above, Vol. VI. p. 172 f.). But I am by no means certain of it, as other Rāshtrakūṭa records do not mention it.

³ See *Ind. Ant.* Vol. XII. p. 252, note 30.

(V. 12.) And from him was born **Amôghavarsha** of unparalleled strength, by whom **Yama** who was pleased (*with him*) was angrily gratified at **Vingavalli** with unprecedented marvels of cakes¹ (*which were*) the **Châlukyās**, (*and by whom*) that pure fame, which could find no scope in the inside, outside and upper side of the universe, was, as it were, stored up in (*the reservoir of lake called*) **Jaggattuṅga-sindhu** under the pretext of water.²

(V. 13.) From him was born king **Akâlavarsha**, harassed by whose prowess, (*their*) shield (*also* **Khêtaka**) was forthwith abandoned by (*his*) enemies together with (*their*) scimitars (*also*, along with the leaders of (*their*) circles).³

(V. 14.) The daughter of **Kôkkala**, the ornament of the dynasty of **Sahasrârjuna**, became his chief queen; (*and*) from him was born **Jagattuṅga**.

(V. 15.) From the ocean (*viz.*) **Ranavigraha**, son of **Kôkkala**, who was grave (*as the ocean is profound*), who was a receptacle of gems (or of excellences), (*as the ocean is a store-house of gems*), who was capable of protecting kings from (*their*) foes (*as the ocean is capable of sheltering mountains from their adversary, viz. Indra*), there was born (*a daughter named*) **Lakshmi**, (*as from the ocean sprang up the goddess of wealth*).

(V. 16.) She became the wife of that king who had no enemy (*and*) who was possessed of the ornament (*consisting of*) fame acquired by **Arjuna** who had a terrific army, (*as Ajâtaśatru, i.e. Yudhishtîra*, was adorned by the ornament (*which was*) fame earned by **Bhîmasêna** and **Arjuna**).⁴

(V. 17.) From King **Jagattuṅga** there was born a victorious prince, son of **Lakshmi**, endowed with valour, (*as*) from the eastern mountain, the highest in the world, there rises the sun, full of heat.⁵

(V. 18.) Truly he was **Indrarâja**, whose arm was thrust forth for the destruction of the partizans of all kings swerving from lawful conduct, (*and*) who was fit to be seen with untwinkling eyes, (*as the god Indra*) discharged (*his*) thunderbolt to cut off the wings of all mountains swerving from their motionless condition (*and*) is fit to be seen by (*the gods whose eyes*) do not twinkle.

(V. 19.) The court-yard (*of the temple of the god*) **Kâlapriya** (*became*) uneven by the strokes of the tusks of his rutting elephants. His steeds crossed the unfathomable **Yamunâ** which rivals the sea.⁶ He completely devastated that hostile city of **Mahôdaya** (*also*, the highly prosperous city of his enemy), which is even to-day greatly renowned among men by the name of **Kuśasthala** (*also*, a spot of mere *kuśa* grass).⁷

(V. 20.) That **Kôkkala**, who was mentioned (*as belonging*) to that family of the illustrious **Haihayas**, which brought down the pride of **Daśakaṇṭha** (**Râvaṇa**), had a son (*named*) **Arjuna**,

¹ *Abhyûsha* is given in the *Amarakôśa* as synonymous with *pauli*, which corresponds to the Marâṭhī *pôlī*, i.e. cake or bread.

² Another rendering of the last line is also possible: "and by whom pure fame . . . was, as it were, stored up in Jagattuṅga, the ocean, in the shape of (oblation-)water." But this interpretation does not commend itself to me, because the last line is an instance of *apahnuti*, in which the real character of the subject in hand (*prakṛita*) is denied, and that of an alien object ascribed to it. *Tôya* is here denied, and must, therefore, be the *prakṛita* and hence, truly speaking, real. If *tôya* is thus real, then the *sindhu* into which it is put cannot be fictitious, but must be real. If, however, we take *Jagattuṅga-sindhu* as an instance of *rûpaka*, as has to be done in case the second rendering is preferred, *sindhu* ceases to become real. If, on the other hand, we accept the first translation proposed in the text above, *Jagattuṅga-sindhu* is no longer a *rûpaka*, and *sindhu* is made real, and thus the full significance of the *apahnutyalamkāra* is brought out; but we may perhaps adopt the second rendering and say that the composer of the inscription was not such a learned poet as to employ the *apahnutyalamkāra* consistently throughout.

³ See the introductory remarks.

⁴ Dr. Fleet thinks that *Râjamârtanḍa* is probably a *Śirûda* of Indra III. (above, Vol. VI. p. 176 and note 9). This seems to be borne out by the spurious Wadgaon grant (*Ind. Ant.* Vol. XXX. p. 218 and note 79).

⁵ The word *sindhu* may also mean the river Indus.

⁶ See the introductory remarks.

⁷ See the introductory remarks.

pre-eminent in virtue. His (Arjuna's) son, who was exceedingly strong, was Ammanadēva. From him was born Vijāmbā, as Lakshmi (*was produced*) from the ocean and Umā from the lord of the mountains called Himavat.

(V. 21.) To the glorious king Indra was born by that Vijāmbā a son, the prince named Gōvindarāja, the beauty of whose form excelled that of Kāma.

(V. 22.) Ignominious cruelty was not practised (*by him*) with regard to (*his*) elder brother, (*though he*) had the power; (*he*) did not obtain infamy by evil courses such as (*illicit*) intercourse with the wives of (*his*) relatives; (*he*) did not through fear resort to diabolical conduct which is indifferent to what is pure and impure; (*and*) by (*his*) munificence and unparalleled heroic deeds he became Sāhasāṅka in the world.

(V. 23.) Though he was Prabhūtararsha, he was called Suvarṇavarsha by the people, because, raining down showers of gold, he made the whole world consisting solely of gold.

(V. 24.) There being no mendicant at the door when there was made the proclamation 'who is the supplicant and what does he want? who is impoverished on earth?'—even the treasure which was brought (*to him*) in abundance by the easily conquered lords of the continents did not please him.¹

(V. 25.) On the occasion of his conquest of the quarters, the earth, with uplifted hands (*consisting of his*) mighty *pālīdhvajās* (*and*) abandoning other kings, forthwith quivers as if by the causing of a violent bustle (as a woman, when freed from an evil lord, dances with uplifted hands as if through intense joyous excitement).

(V. 26.) Even the sun and the moon,² as if with fear produced (*in their mind at the thought*) that he, the prosperous one, will not bear the rising up of another lord of a *maṇḍala* (country), run before him (inasmuch as they are the lords of *maṇḍalas*, i.e. orbs, and are *samuddhata*, i.e. rising in the sky).

(V. 27.) For long shines his gateway (*marked by*) the moon who is like (*him*), (*and*) decorated near (*his*) palace, before which other lords of *maṇḍalas* bow down, which is accompanied by the goddess of victory, and where the whole mass of his lustre (*is seen*).³

(V. 28.) Surely (*thinking that*) he cannot bear the army of (*his*) foes, which is equal (*to his own and*) which is possessed (*of men*) of excellent qualities, the Gaṅgā and the Yamunā resort to his flawless royal abode (because they themselves are *samavāhinī*, i.e. flowing in a level, and possessed of excellences).⁴

(V. 29.) While this king was administering excellent government wherein (*all*) enemies were subdued, there was *vimānasthiti* (i.e. sitting in celestial cars) among the gods (*nabhōga*), (*but*) there never was *vimānasthiti* (i.e. transgression of proper bounds) in enjoyments (*bhōga*).⁵

(V. 30.) The blue clouds (*are*) the soot springing from the copious flames of his luxuriant fire of heroism. The flashes of lightning (*are*) but the spreading-out of the gleams of the blade of (*his*) flourished sword. The stars (*are*) but the pearls issuing in consequence of the splitting-open

¹ There can be no doubt that the stanza is intended to yield two senses, as the words *pranīta* and *kōśa* unmistakably indicate. One of these senses is that given in the text above. What the other sense is cannot be accurately made out. It seems to refer to a lexicon composed by a certain author, who bore the name Hēlāsiddha or Dvīpanātha, or a name equivalent to either of these words in meaning. Is it Hēlārāja or Kshīrasvāmin? We must await further researches to settle this point.

² This probably refers, I think, to the figures of the sun and the moon on his banners.

³ This is a very knotty verse. I have, in the main, followed Dr. Fleet in point of the separation of words and translation. But I am by no means certain of either. Must we split up the third line of the stanza into *sa mahima-karatō-rājan* and translate it accordingly?

⁴ For the historical fact contained in this stanza, see the introductory remarks.

⁵ There is evidently here a play on *vimānasthiti* and on the double analysis of *nabhōgēṣu*, viz. (1) *nabhōg-geṣu*, 'among the aeronauts,' and (2) *na bhōgēṣu*, 'not in enjoyments.'

of the temples of the irresistible elephants of (*his*) enemies. The moon, the milky ocean and Śēsha (*are*) the trickling of the mass of (*his*) glory which has filled the world.

(V. 31.) While his mind was anxious to eradicate thorns, the lotus-stalks, as if through fear, did not emerge from water, (*but*) made (*to him*) a present of the beauty residing in (*their*) buds ;¹ for self-purification, the *kētakī* (plant) remained in the interior of the darkness caused by the quantities of its own pollen, set in motion by the wind, the jack-tree in the hollow of the earth, and the reed-branch at (*his*) gate.

(Line 38.) And he, laughing to scorn the vanity of the beauty of the form of Kāndarpa (Kāma), who was rendered transient through being burned by the eye of Hara (Śiva), (*became*) the glorious Nitya-Kāndarpa (*i.e.* a very eternal Kāndarpa); (*he*), destroying the happiness of Śatamakha (Indra) by means of the power of energy amplified by the powers of royal majesty and good counsel, (*became the very god*) Chaturmukha (Brahman) (*in the art of*) Chāṇakya (*i.e.* in politics); (*he*), intent upon working weal to the earth overrun solely by (*his*) renowned valour, (*became*) the glorious Vikrānta-Nārāyaṇa (*i.e.* a very Nārāyaṇa among heroes), (as Vishṇu became Vikrānta-Nārāyaṇa, *i.e.* the striding Nārāyaṇa, when intent upon doing good to the earth occupied by (*his*) single renowned step); (*he*), devastating the fields (*consisting of*) the breasts of (*his*) enemies by means of the ploughshare (*consisting of*) the weapon wielded by his hand, (*became*) the glorious Nṛpati-Trinētra (*i.e.* a very god Śiva among kings).²

(L. 40.) And he, the *Paramabhaṭṭāraka Mahārājādhirāja Paramēśvara*, the prosperous *Suvarṇavarshadēva-Prithvivallabha*, the prosperous *Vallabhanarēndradēva*, who meditates on the feet of the *Paramabhaṭṭāraka Mahārājādhirāja Paramēśvara*, the prosperous *Nityavarshadēva*,—being well, commands all the lords of provinces (*rāshṭra*), lords of districts (*viśaya*), chiefs of villages, leading persons, officials, employes and functionaries, according as they are concerned :—

(L. 43.) “Be it known to you that I, who am permanently settled at the capital of Mānyakhēṭa, who am maintaining grants to temples and *agrahāras*, though resumed by previous (*rulers*), and who day by day am issuing charters of villages, to be everlastingly respected (*by all*),—eight centuries of years increased by fifty-two having elapsed since the time of the Śaka king, also in figures Śaka-Samvat 852, on the tenth (*tithi*) of the bright (*half*) of Jyēsthā in the current Khara-samvatsara, on a Monday, when the moon was near (*the constellation of*) Hasta,—on the great festive occasion of the binding of the fillet in the village of Kapitthaka, situated near the bank of the Godāvāri, having ascended the *tulāpurusha*, gave unto the Brāhmaṇs six hundred *agrahāras* together with three lacs of *suvarṇa* (coins) for the sake of *bali*, *charu*, *vaiśvadēva* and *atithitarpaṇa*,³ and granted to the temples of gods for the enjoyment of the gods eight hundred villages, four lacs of *suvarṇas* and thirty-two lacs of *drammas*, for (*the repairs of*) broken parts and so forth, for ointment, frankincense, flowers, lamps, offerings and other requisite articles of worship, and for the purpose of (*providing*) a feeding-establishment, gifts of outer garments and so forth for ascetics; and after this, without descending from the *tulāpurusha*, bestowed first by pouring water from the hand, for the enhancement of the religious merit and fame of my parents and myself,—upon Nāgamārya, son of Mahādēvayya, belonging to the Māthara *gōtra*, student of the Vāji-Kāṇva *śākhā*, come from the holy place of Kāvika which is situated in the Khēṭaka district (*maṇḍala*) of the Lāṭa country (*dēśa*), resident here at Mānyakhēṭa, subsisting on the lotus-feet of the prosperous Vallabhanarēndradēva,—the village named Kēvañja, situated in the Khēṭaka district comprised in the Lāṭa country,

¹ *Ind. Ant.* Vol. XII. p. 254 and note 36.

² This is very curious; for, the god who wielded the weapon of the ploughshare and devastated fields is Balarāma, the brother of Kṛishṇa, and not Trinētra, *i.e.* Śiva. So far as my knowledge goes, Balarāma is nowhere called Trinētra, nor is Śiva anywhere spoken of as performing these functions of Balarāma.

³ *Gupta Inscr.* p. 116, note 3.

(and) lying quite close to the holy place of **Kāvikā**, together with its rows of trees, up to its four boundaries, together with its cultivated soil,¹ together with the royal share,² together with all the produce such as the produce of corn, the acquisition of gold, the fines, (*the proceeds of the punishments for*) faults and the ten offences, and so forth,— for the purpose of (*maintaining*) the *balī*, *charu*, *vaiśvadeva* and *atithitarpaṇa*; for the performance of the optional, indispensable and occasional rites; for the performance of the *śrāddha* and sacrificial ceremonies such as the *darśapūrṇamāsa*, *chāturmāsya*, *aṣṭakā* and *āgrayana*³ (rites) and the fortnightly (*śrāddhas*); for the purpose of preparing the *charu*, *purōḍāśu*, *sthālīpāka*⁴ and so forth; for the purpose of (*granting*) priestly fees and gifts in connection with *hōma*, *niyama*, the study of one's own Vēda,⁵ and religious service; for the purpose of (*providing*) accessory assistance for the rites concerning *rājāsūya* and the seven forms of the *sōma* sacrifice such as the *vājapēya*, *agnishīḥoma*⁶ and so forth; for the purpose of (*offering*) garments, ornaments, entertainment, gifts, sacrificial fees, etc. to the various priests, such as *Maitravaruna*, *Adhvaryu*, *Hōtri*, *Brāhmaṇāchchhamśin*, *Grāvastu* and *Agnīdh*; ⁷ and for the purpose of (*supplying*) the requisite materials for preparing *sattra*, *prapā*, *pratiśraya*, *vrishōtsarga*, reservoirs, wells,⁸ tanks, orchards, temples, etc."

(L. 58.) And the boundaries of this village (*are*), to the east the boundary of the holy place of **Kāvikā**, to the south the village named **Sāmagam**, to the west the village of **Sihuka**, and to the north the boundary of the land⁹ belonging to the same (*holy*) place named **Kāvikā**. No one should cause hindrance to Nāgamārya while cultivating this village called **Kēvañja**, thus defined by the four boundaries, or causing (*it*) to be cultivated, while enjoying (*it*) or allowing (*others*) to enjoy (*it*).

¹ So the word *karmānta* is explained in Monier Williams' *Sanskrit-English Dictionary*.

² *Gupta Inscr.* p. 97, note 6.

³ *Darśapūrṇamāsa* denotes "(the days of) new and full moon, ceremonies on these days (preceding all other ceremonies);" *aṣṭakā*, "the eighth day after full moon (especially that in the months Hēmana and Sīsira, on which the progenitors or manes are worshipped, . . . also a name of the worship itself or the oblations offered on those days);" and *āgrayana*, when masculine, "the first *sōma* libation at the *agnishīḥoma* sacrifice," and when neuter, "oblation consisting of first-fruits at the end of the rainy season."— Monier Williams' *Sanskrit-English Dictionary*.

⁴ *Charu* is "an oblation (of rice, barley and pulse) boiled with butter and milk for presentation to the gods or manes);" *purōḍāśa*, "a mass of ground rice rounded into a kind of cake (usually divided into pieces, placed on receptacles);" and *sthālīpāka*, "a dish of barley or rice boiled in milk (used as an oblation)."— Monier Williams' *Sanskrit-English Dictionary*.

⁵ *Hōma* signifies "the act of making an oblation to the Dēvas or gods by casting clarified butter into the fire;" and *niyama*, "any act of voluntary penance or meritorious piety (esp. a lesser vow or minor observance dependent on external conditions, and not so obligatory as *yama*)."— Monier Williams' *Sanskrit-English Dictionary*. I take *svādhyāyādhyayana* to be one word, meaning "study of one's own Vēda;" compare Āśvalāyana's *Gṛhya-sūtra*, III. 3, 1.

⁶ *Rājāsūya* is "a great sacrifice performed at the coronation of a king (by himself and his tributary princes . . .);" *vājapēya* is "the name of one of the seven forms of the *sōma* sacrifice (offered by kings or Brāhmanas aspiring to the highest position, and preceding the *rājāsūya* and the *Brihaspati-sana*);" *agnishīḥoma* is "the name of a protracted ceremony or sacrifice (forming one of the chief modifications of the *jyōtiṣhīḥoma* offered by one who is desirous of obtaining heaven . . .)."— Monier Williams' *Sanskrit-English Dictionary*.

⁷ *Maitravaruna*, otherwise called *Prasāstri*, is the first assistant of the *Hōtri*. The terms *Adhvaryu*, *Hōtri* and *Agnīdh* are well known. *Brāhmaṇāchchhamśin* is "a priest who assists the Brahman or chief priest at a *sōma* sacrifice;" and *Grāvastu* is one of the sixteen priests (called after the hymn [*RV.* X. 94, 1 ff.] addressed to the *sōma* stones).— Monier Williams' *Sanskrit-English Dictionary*.

⁸ The word *sattra* signifies an alms-house and is frequently met with in the Gupta inscriptions (e.g. Nos. 7, 8, 9 and 10). *Prapā* denotes a place of distributing water gratis to travellers; *pratiśraya* is "a shelter-house for travellers" (*Ind. Ant.* Vol. XII. p. 142). Both these words occur in the celebrated inscription of Ushavadāta at Nāsiik, which records his series of benefactions. *Vrishōtsarga*, according to the *Śabdakalpādruma*, means "setting free a bull and four heifers on the occasion of a *śrāddha* or as a religious act generally." As regards the details of this ceremony, see this lexicon, *sub voce*. According to Mahēśvara's commentary on the *Amarakōśa*, *kūpa* denotes an ordinary well, and *vāpi* means a well with a flight of stairs.

⁹ For *tala-stmā* see above, Vol. IV. pp. 155 and 157.

[Vv. 32-36 contain the usual admonitions to future rulers.]

(V. 37.) This praiseworthy grant of the prosperous Gōvindarāja has been written by the learned Nāgavarman, son of Gaṅgādhara.

(L. 67.) Good luck (*and*) great prosperity.

No. 7.—THE INSCRIPTIONS IN THE CAVES AT KARLE.¹

By E. SENART; PARIS.

The Editor of the *Epigraphia Indica* has been good enough to make over to me two sets of inked estampages of the inscriptions at Kārle and at Nāsik, which he caused to be taken in the year 1899 by his Assistant, Mr. G. Venkoba Rao; and he has kindly requested me to contribute a brief commentary on the Plates of them which he intends to issue. All these records have been commented on before by such scholars as Bhandarkar, Bhagwanlal Indraji and Bühler. Still, I cannot resist the temptation of adding my modest gloss in the wake of their learned interpretations. Nobody will expect, however, that I shall arrive at startling new results.

The difficulties with which the explanation of these precious documents has to cope are on the whole due to two causes—(1) their imperfect state of preservation; and (2) the employment of a certain number of obscure terms or formulas. Since the comparatively recent date to which the preceding treatments of these inscriptions belong, few important new materials have come to light. On the other hand, as regards *fac-similes*, the Plates now issued may at first sight appear more imperfect than those which were published by the Archæological Survey. But, having worked direct from the inked estampages, I can testify that the new Plates seem to have been executed with scrupulous care, and that the collotypes are purely mechanical reproductions of the estampages. Of course they do not show all the details of the originals,—because this is impossible,—but they have not been subjected to any touching up by hand. The estampages were made quite recently; and, in the course of several years which separate them from the earlier copies, the disintegration of the rocks which bear the inscriptions will have continued, and characters which existed before may have lost in clearness. Is this enough to account for the difference between the old and the new Plates? It seems to me that the former, or at least portions of them, were touched up by hand in details. These retouches, which were executed by competent readers who worked from the monuments, certainly have a value of their own. Nevertheless they imply certain minute alterations which are hardly compatible with the scrupulous care that is now considered indispensable in such matters. I am dwelling on this point only in order to vindicate myself for not appearing to be quite so well informed as my predecessors in the treatment of several passages, and besides, for admitting that certain apparent readings of the earlier *fac-similes* do not exclude *a priori* some slightly different hypotheses. I do not know if, in this field of enquiry and in the present state of our knowledge, it is not more dangerous to affirm too much than to be too cautious. It goes without saying that I have nowhere neglected the invaluable help which the earlier reproductions and transcriptions furnished; if reduced to my own resources, I would have had to leave more than one lacuna in the texts. Nevertheless the readings which I propose are such as I consider to be actually warranted by the context of the estampages which I have in my hands and which are represented by the new Plates. In several cases where, though believing in a certain transcription, I do not venture to affirm that it is perfectly sure, I enclose in square brackets the letters which to my mind are more or less doubtful. I confess that even this distinction has not been a very easy matter. One need only look at some of the Plates in order to understand that in many cases, if the reading hardly admits of any doubt, the reason is that it is corroborated either by the

¹ Translated from the French by the Editor.

authority of parallel passages or by the evidence of the context in which it occurs. Notably, in a vast number of instances it is perfectly impossible to decide whether we have to deal with intentional strokes or with accidental cracks of the stone. This observation refers to the vowel-signs, and especially to the *anusvāra*. The latter, we know, is frequently omitted; hence it is all the more uncertain in doubtful cases. Fortunately these are details of secondary importance, at least for the interpretation. Is there any need to add that I have scrupulously recorded all the various readings of former editors whenever they are of any interest, i.e. unless they are due to palpable mistakes or to misprints?

The chief value of these documents consists in their throwing light—though dimly—on a number of historic, palæographic and linguistic problems. But they are not the only documents of their kind, nor are such documents our only source of information. Though interesting, it is unwise to take up general questions in connection with a partial publication. This manner of proceeding is inevitable in the first period of researches and of discoveries, but later on it is apt to scatter the information inordinately and to hamper its discussion. It is at any rate natural to rescind the explanatory remarks and the historical conclusions. To my re-edition of the texts and to the explanations which it will suggest to me, I propose to add as a postscript the more comprehensive remarks which appear to be called for.

The really useful bibliography of the Kārlê inscriptions comprises only two works¹—(1) *Inscriptions from the Cave-temples of Western India*, 1881 (CTI.), and (2) *Reports of the Archaeological Survey of Western India*, Vol. IV., 1883 (AS.). In the first publication, Dr. Burgess has transcribed and translated the inscriptions in accordance with the readings and remarks furnished by Pandit Bhagwanlal Indrajī; and in the second the texts and explanations have been subjected to a fresh revision by Bühler. Though this edition is more recent and marks in the majority of cases a progress on the first, it has the drawback of assigning texts of the same locality to different chapters according to their official or private character. The new Plates follow Bhagwanlal's numbering. I have added in brackets the number given in AS.; "K." refers to the chapter entitled "Earliest Kārlê inscriptions" (p. 90 ff.) and "Ksh." to "Kshatrapa and Andhra inscriptions" (p. 98 ff.). The remarks regarding the position of each inscription are copied from the labels accompanying the estampages.

No. 1, Plate iii. (K. 1).

Chaitya cave. Left end of the verandah.

TEXT.

Vejayam̐tito seṭhinaṁ Bhutapālen[ā] (1) selaghara (2) parinīṭhapita[m̐] (3) Ja[m̐]bu-dipamhi (4) ūtama[m̐] (5).

REMARKS.

(1) CTI. *Bhāta*^o. The mark of *ā* seems to exist clearly in *nā*; but it is rather short and, as there are traces of a crack on its right, it may be the result of the wearing of the stone.—(2) AS. and CTI. *gharam*.—(3) Probably the *anusvāra* has disappeared in the crack; it cannot be said to exist with certainty.—(4) I feel inclined to explain the development of the central loop of *ja* by the presence of an *anusvāra*.—(5) AS. *utama*; CTI. *uttama*. The long *ū* appears to

¹ The partial attempts at interpretation of Bird (*Historical Researches on the Origin and Principles of the Buddha and Jaina Religion*, 1847) and Stephenson (*J. Bo. Br. E. As. Soc.* Vol. V. p. 152 ff. and p. 426 ff.) possess now only a historical interest. As regards the general description of the caves, the first exact reports are those of Fergusson (*J. R. As. Soc.* Vol. VIII. p. 30 ff.) and of Wilson (*J. Bo. Br. E. As. Soc.* Vol. III. p. 48 ff.). At present exact and methodical information may be found in the *Rock-cut Temples of India* of Fergusson and Burgess, and in the *Reports of the Archaeological Survey of Western India*, Vol. IV.

me certain; this is the only possible meaning of the double hook, contrasted with the ordinary form of *u*. It seems that at the end an *anusvāra* did exist, which got mixed up by the wearing of the stone with the upper hook of the last symbol, for which compare the beginning of No. 5.

TRANSLATION.

“(This) rock-mansion, the most excellent one in Jambudvīpa, has been completed by the *Seṭṭhi Bhūtapāla* from *Vaijayanti*.”

Vaijayanti seems to have been the ancient name of Banavāsi in the North Kanara district, Bombay.¹ In addition to the instances quoted by Dr. Burgess, where Jayanti seems to represent Banavāsi, one might perhaps ask if in the Banavāsi inscription² the letter which has been read *sa* or *saṃ* before *jayaṃtakasa* (l. 2) might not be a *ve*, in which case the sculptor Damōraka would be designated as a native of Vaijayanti.—In spite of the general meaning of *selaghara*, it seems—if we compare the occurrence of *chaityagriha* at Kuṇḍā (CTI. Nos. 15 and 20), of *chetiyaghara* at Nāsik (Nos. 18 and 19), of *gharamukha* and *gharasa mugha* at Kārlē (Nos. 4 and 6), and of *gharamukha* at Ajaṇṭā (CTI. No. 1)—that the expression *griha* or *ghara* was habitually restricted to the halls used for worship, those which are generally styled “*chaitya* caves.”—The expression *pariniṣṭhapita* implies the idea of completion, which must not be lost sight of. Even if one leaves out of consideration the open screen, the decoration of which may be secondary, several inscriptions describe certain pillars as particular gifts. Hence it may be assumed that the present record attributes to Bhūtapāla the honour of having completed the *chaitya* cave.

No. 2, Plate iv. (K. 2).

On the lion-pillar in front of the *chaitya* cave.

TEXT.

Mahārāṭhisa Gotiputrassa Agimitraṇakasa sihathabho dānam.

REMARK.

Though there can be no doubt, I think, regarding any important detail of the text, the inscription is much worn, and the certainty of some points, *e.g.* the initial *a* of *Agimitraṇaka* and the *th* of *thabho*, is in some way only a moral certainty. I do not venture to affirm that there is no *anusvāra* on the right of *si*, but incline towards the negative.

TRANSLATION.

“(This) lion-pillar (is) the gift of the **Mahārāṭhi Agimitraṇaka**, the son of **Goti**.”

Mahārāṭhi is an obscure and difficult term. It would be essential to know first whether the actual orthography of the inscriptions is *°raṭhī* or *°raṭhī*. The *th* seems probable here, and it is certain in an inscription at Bēḍṣā (CTI. No. 2); though on the other hand the *th* is probable in No. 14 of the Kārlē inscriptions and in Bhājā No. 2. The writing of *th* by error for *ṭh* being more probable than the reverse, the form *Mahārāṭhi* is the proper one to start from.³ If this is the case, the comparison with the epic epithet *Mahāratha* and with *brihadratha* must be discarded. CTI. (p. 24) declares that “*Mahārathi* is a Paurāṇic title of a great warrior; it is common in the families of Rājas.” I do not know on what this statement rests; if its first part

¹ Dr. Fleet's *Dyn. Kan. Distr.* p. 278, note 2.

² CTI. p. 100; compare *Ind. Ant.* Vol. XIV. p. 331.

³ Dr. Hultzsch reads *Mahārāṭhi* also on the coins reproduced on Plate iii.

were correct, one would at least expect *Mahāratha* and not *Mahārathi*, which is not necessarily the same thing. At any rate *Mahārathi* is a title. This is also Bühler's view (AS. p. 107, note); but the special reason which he adduces in support of it is not at all decisive, viz. that in the Kārlē inscription No. 14 *Okhalakīyānām Mahārathi* should be translated by "the *Mahārathi* of the Okhalakīyas." Nothing proves that the genitive depends on *Mahārathi*. Several instances show us the proper name of a donor accompanied by the name of the tribe or the people to which he belongs in the genitive plural, e.g. Junnar Nos. 5 and 6 (CTI. and AS.). The fact that, in the other cases where we find the word again and in that same No. 14 in the very next line, *Mahārathi* does not govern a genitive, forces us to reject altogether the construction proposed by Bühler.¹ Hence this instance cannot furnish, as he thought, a positive argument against the interpretation previously proposed by Garcez,² who saw in it a kind of ethnical name equivalent to *Marāṭha*. Etymologically this explanation seems to me strongly supported by the *th*, which presupposes a Sanskrit form *Mahārāshṭrin*. But *Mahārāshṭrin* has not necessarily a geographical meaning, and it is difficult to separate the word from *Mahābhōja* and *Mahāsāmanta*, which are connected with it in our inscriptions. As *rāshṭra* often means a province, it is quite natural that *rāshṭrin* follows the same analogy as *bhōja* and *sāmanta*, so that, if *Mahābhōja* has become a title applied even to women, the same could very easily happen in the case of *Mahārāshṭrin* and *Mahārāshṭrinī*, or *Mahārathi* and *Mahārathinī*.³ This is possible, but not absolutely certain; it may as well have been that the name, starting from the geographical and ethnical meaning, became fixed as a title of honour in certain families, perhaps because of certain important relatives or of special circumstances.⁴ It may be noted that to our *Mahārathi* Agimitrapaka corresponds a *Mahārathi* Mitadeva in No. 14; that this Mitadeva is a Kausikīputra, like Vishnudatta at Bhājā (No. 2); and lastly that the *Mahārathinī* Sāmaṇikā at Bēḍṣā (No. 2) was married to an Āpadevapaka. Do not these different names look as if they were connected with each other in such a way as to suggest the idea that they may have belonged to the same circle of families or relations? We find a *Sthavira* Agimitra, i.e. Agimitra, at Kuḍā (CTI. No. 5). I believe that the names in *ṇaka* in our inscriptions, as here and as Nandanaka at Junnar (CTI. No. 22), etc., are not different names, but simply equivalents of Agimitra, Nanda, etc.—Gotiputra⁵ is the same as Gaupitiputra, from Gupta.

Dr. Hultzsch contributes the following note on the three coins figured at the bottom of Plate iii., which are of interest in connection with the explanation of *Mahārathi*:—

"In the year 1888, Mr. A. Mervyn Smith, while prospecting for gold, found a number of lead coins on an ancient site near Chitaldroog in the Mysore State and distributed them to various coin-collectors. The smaller ones among these coins bore only Buddhist and other symbols, but a few larger ones had incomplete legends. On my specimen (Plate iii. B.) I found

¹ The occurrence of the feminine *Mahārathinī* in Bēḍṣā No. 2 also indicates rather that the term does not imply the actual office of governor of a district or province, but an honorific or nobiliary title.

² *Journ. Asiat.* VIIth series, Vol. XX. p. 201 f.

³ I may here as well draw attention to the use of *raṭṭhika* in Pāli (e.g. *Jātaka*, II. 258, 12) as an equivalent of *grihapati* and *Vaṭṭiya*. Compare *Śatapatha-Brāhmaṇa*, XIII. 2, 9, 7, where the *Vīṣas* are brought in special connection with the *rāshṭrin*, the wielder of royal power.

⁴ We may compare the parallel use of the attributes *Sādhya(ke)ra* and *Mandava* (*Māṇḍavya*); on the latter see Jacobi in *Ind. Ant.* Vol. VII. p. 254. The occurrence of *Māṇḍavānām* at Kuḍā (CTI. No. 14) leaves no doubt regarding the ethnical meaning of the word, though the use of the dental *d* renders the identification with the *Māṇḍavyas* of literature problematical. At Bēḍṣā (CTI. No. 2) *Mandava* is connected with *Mahārathi*; the reading *Māṇḍariya* is quite clear in the fac-simile and excludes the useless and improbable conjecture *ma[ḥd*]deviya*. It will be remarked that in this instance *Māṇḍavi* precedes *Mahārathinī*. Seeing that *Mahābhōja* always precedes either attribute when connected with it, this position does not seem to indicate that *Mahārathi* could imply a title of superior nobility, and consequently still less that it could designate a very high dignity.

⁵ [The same epithet occurs in the Śūṅga inscription of the Bharhut Stūpa; see *Ind. Ant.* Vol. XIV. p. 138 f. —E.H.]

the title *Mahārāṭhi*, which occurs in the cave-inscriptions (Kārlē) Nos. 2 and 14; A.S.W.I. Vol. IV. p. 83, No. 7 (Bhājā), and p. 90, No. 3 (Bēdsā). At my request Mr. R. Sewell kindly sent me for comparison the two lead coins (Plate iii. A. and C.) which he had received from Mr. Mervyn Smith in 1888. These supply the first word of the legend, *Sadalakana* (see Plate iii. A.) and contain portions of the second word, *Kaḷalāya*, while the third word, *Mahārāṭhisa*, is preserved in B. and C. The three coins may be briefly described as follows:—

Plate iii. A. (Sewell).

Obverse.—A humped bull, standing towards the proper right. Round it, the words *Sadalakana-Ka[ḷalā]*

Reverse.—A *bōdhi*-tree between two symbols.

Plate iii. B. (Hultzsch).

Obverse.—Similar to A. There is a deep and distinct punch-mark below the bull. Round the latter, [*Sa*] . . [*ka*] *na-Kaḷalāya-Mahārāṭh[i]sa*.

Reverse.—A *bōdhi*-tree, a *chaitya*, and a symbol between them.

Plate iii. C. (Sewell).

Obverse.—Similar to A. Round the bull, *Sa* . . . [*Kaḷa*] *lāya-Mahārāṭhisa*.

Reverse.—A *bōdhi*-tree and a *chaitya*.

“Taking the three coins together, it appears that the complete legend, of which each bears a portion, is *Sadalakana-Kaḷalāya-Mahārāṭhisa*.

“The curious word *Kaḷalāya* reminds us of the equally peculiar Andhra name *Puṣumāyī*. *Sadalakana* is the same as *Sātakaṇi* in the Andhra inscriptions. Perhaps *Kaḷalāya*, with the surname or family name *Sadalakana* and the title *Mahārāṭhi*, held Chitaldroog as a vassal of the Andhra kings. From the emblems pictured on his coins we learn that he was a Buddhist, and that his crest was a bull.

“Since writing the above, I found that the Mysore Government Museum at Bangalore possesses two lead coins of the same type, presented by Mr. Mervyn Smith, who found them near Chitaldroog in 1888.”

No. 3, Plate ii. (K. 3).

Chaitya cave. Below the feet of the three elephants at the right end of the verandah.

TEXT.

Therānam bhāṇyamāta-(1) I[m]dādevasa hathi cha puvādo hathinām cha uparimā hethimā cha veyikā dānam.

REMARK.

(1) AS. and CTI. read *bhayam*°. I do not feel inclined to believe that the *anusvāra* of *bham* is intentional; but it certainly seems to exist on the stone.

TRANSLATION.

“The elephants and, before the elephants, the rail-mouldings above and below (are) the gift of the *Sthavira*, the venerable *Indradēva*.”

In separating *do* and in considering it to represent the numeral *dvau*, previous editors have created difficulties which they found it hard to overcome. It is sufficient to look at a photograph to recognise that the elephants are actually separated from the spectator by the balustrade

which hides the bottom of their legs. The Prâkrit *pubbādo* = *pūrvataḥ* does not raise any difficulty. Bühler has well defined the meaning of *védikā* by "bands or string-courses carved with the rail pattern." In No. 17 and elsewhere the term *veyikā* is applied to fragments of this kind.

No. 4, Plate i. (K. 4).

Chaitya cave. Over the right doorway.

TEXT.

Dhenukākataḥ (1) gamdhikasa Si[m]hadatasa (2) dānam gharamugha.

REMARKS.

(1) The vowel-signs are not very pronounced; but the two *ā*-signs seem to be certain. After this word is a space filled with cracks, which would leave room for two characters; one might feel tempted to believe that originally the stone bore *Dhenukākatakasa* (compare No. 6). But I reject this conjecture because the *ā* of *śā* is very probable, and there are no traces of *ka* and *sa*, which ought to show among the cracks. Besides, the simple ablative is frequently used in the same sense elsewhere.— (2) Though neither AS. nor CTI. notices the *anusvāra* of *Siṃ*, it seems to me probable.

TRANSLATION.

"(This) door (is) the gift of *Siṃhadata*, a perfumer from *Dhēnukākata*."

Dhēnukākata is a name of frequent occurrence in the cave-inscriptions here and elsewhere in these parts. Several Yavanas profess to be natives of that place. Therefore it ought to be looked for in the north-west; but it has not yet been identified. Compare AS. p. 24.

No. 5, Plate iii. (K. 5).

Chaitya cave. On the pillar of the verandah in front of the central door, above the inscription No. 6.

TEXT.

- 1 Gahatasa Mahādeva-
- 2 ṇakasa mātu Bhāyilāyā (1) dānam.

REMARK.

(1) I cannot say that the *ā* of the last syllable appears to me certain.

TRANSLATION.

"The gift of *Bhāyilā*, the mother of the householder *Mahādevanaka*."

Regarding the name *Mahādevanaka* = *Mahādēva*, compare No. 2.— The name *Bhāyilā* has been explained by *Bhrājilā*. This transcription is not the only possible one, though it appears to me the most probable. But could not this be the transcription of a foreign name? It occurs again at Kuṇḍā (AS. No. 13), where a Brāhmaṇi *Bhāyilā* is stated to have been the wife of a certain *Ayitila* who, though called a Brāhmaṇa, bears a name of very barbarous form, which reminds us curiously of *Azilizes*, etc. I do not pretend to affirm that our *Bhāyilā* is the same, though the writing of the two inscriptions appears to be quite contemporaneous and to be intimately related in certain details, e.g. the *yī*. I may add that the title of *grihastha*,¹ applied to

¹ For the loss of the aspiration in *gahata* compare e.g. *stāna* in an inscription at Mathurā, *Ep. Ind.* Vol. I. p. 390, No. XVIII.

her son, seems to indicate a Brāhmaṇical origin. In the case of an ordinary householder of the Vaiśya class we would doubtlessly have *gahapati* as elsewhere.

No. 6, Plate iv. (K. 6).

Chaitya cave. On the pillar of the verandah in front of the central door.

TEXT.

- | | | | | |
|---|-------------------|-----|--------------|----------------------|
| 1 | Dhenuk[ā]katakēṇa | (1) | vaḍhakinā | Sāmi- |
| 2 | ṇa | (2) | Vēṇuvāsa-put | . . ṇa (3) ghara[ṇa] |
| 3 | mugha | (4) | kata durem | . . dhu . . (5). |

REMARKS.

(1) AS. and CTI. read °*ṇukāka*°. The long *ā* seems very doubtful; the slanting stroke resembles a simple crack.—(2) After *Sāmi*, CTI. inserts *ka* and AS. *le*; but in the estampage there is no trace of a letter which might have disappeared. The *ṇa* is very probable, but the crack which crosses the top of the character does not absolutely exclude the reading *ud*.—(3) AS. and CTI. read *puteṇa*; but the *e* attached to the *t* is at least very indistinct. Besides, it appears from a comparison of the preceding line that there ought to have been an additional letter here. The existing traces would seem to point to the reading *putakeṇa*, though this diminutive is not very plausible.—(4) AS. and CTI. read *mughaṇ*. I cannot distinguish the *anu-* *svāra*, but will not deny that it exists. The stone is so much defaced that no detail is quite certain here.—(5) The *ā* has a hook at the bottom which can easily be taken for *u*; but it must not be forgotten that here, as in other cases, this vowel is represented by a vertical line. The hook at the top is too slanting to be considered an *ā*. The *e* expressed by the stroke at the top of *r* seems less doubtful. As the whole lower right portion of the *m* is obliterated, the reading *mu* of AS. and CTI. is possible, but simply hypothetical. Between this character and the *dhu* the space makes it probable that one letter is lost. Certain traces suggest an *h*, perhaps *māhā*. The last letter, read as *ka* in AS. and CTI., is at least very doubtful. CTI. adds a final *sa* which, in my opinion, is inadmissible. The stone may have originally borne one or more additional letters. The sign of punctuation which AS. seems to discover, not without hesitation, is at any rate improbable.

TRANSLATION.

“By the carpenter *Sāmi*, son of *Vēṇuvāsa*, a native of *Dhēnukākata*, there was made the opening of the cave”

The mutilation of the text renders its explanation imperfect. What is sure, is, that we have here in some way the signature of a workman or artist. The separation of the usual compound *gharamukha* into *gharasa mukha* produces the impression that the inscription does not refer to the whole of the door, but to details connected with the opening. These may have been specified by the word or words which remain obscure at the end of the inscription. And as in fact the work of a carpenter is spoken of, we may have to think of some piece of carpentry or wood-decoration. The uncertainty of the reading leaves the name of this sculptor, Śyāmila, Svāmin, or otherwise, undetermined.

No. 7, Plate i. (K. 7).

Chaitya cave. On the top of the third pillar; left row.

TEXT.

- Dhenukakata* (1) *Yavanasa* *Siṇhadhayaṇa* *tharibho* *dānaṇ* (2)

REMARKS.

(1) The first *ā* of *śkāpā* in AS. is surely only a clerical mistake.— (2) The final *anusvāra* seems to me perfectly visible.

TRANSLATION.

"(This) pillar (is) the gift of the Yavana Sihadhaya from Dhēnukākāṭa."

For the combination of the singular *Yavanasa* with the plural *Sihadhayāna[m]* compare No. 3, where the plural *therānaṃ* is followed by the singular *Imādadevasa*.

No. 8, Plate iii. (K. 8).

Chaitya cave. On the fifth pillar; left row.

TEXT. (1)

1	Sopārakā	bhayatānaṃ	Dhamutari-	(2)
2	yāna	sa . nathasa	(3)	therasa . (4)
3	bha . . sa	(5)	amtevasisa	bhāna-
4	kasa	Na . pat . sa	(6)	Sātimitasa
5	saha . . .	t[i]hi	(7)	[tha]bho dānamukha (8).

REMARKS.

(1) The inscription is much defaced, perhaps intentionally, as Bühler thinks, in order to be replaced by the following one (No. 9). Hence all statements referring to it will have to be made with special caution.— (2) AS. and CTI. read *°tāna* and *°tara°*. I consider the *anusvāra* and the *i* of *ri* comparatively certain.— (3) CTI. and, with hesitation, AS. read *samānatha°*. A single letter seems to be lost; but which? The *m* does not seem to me more probable than any other.— (4) CTI. reads *na* and AS. *a* as the last letter which I am unable to make out.— (5) AS. and CTI. read *°tulasa*. The first letter appears to be certainly a *bh*; compare the *t* of *amtevasisa*. And I have no doubt that two letters have to be supplied between this letter and the final *sa*.— (6) AS. *Nadipatisa*; CTI. *Nadāputisa*. *Dā* or *dī* are possible, but neither is certain. I do not discover any trace of an *u* below the *p*; but, after all, *°putasa* is *a priori* so probable that I can hardly doubt that this was the original reading of the stone.— (7) AS. . . . *tipe*; CTI. *[mutapī]tuya*. The *i* above the *t* is more probable than the *u* below, and the reading *hi* is, though not at first sight, at least as admissible graphically as *ya*. This agrees with the possible restoration *mutapī*, a completely satisfactory form. The reading *tuya*, admitting the restoration [. . . *dha*]tuya, would seem to be recommended by the expression *śāstīya* in the following inscription (No. 9), which seems to have been intended to replace the present one. But why this substitution? Was it only in order to avoid the mention of the master of Sātimita? Or perhaps for inserting the mention of the relics, which would have been passed over in silence in the first redaction and added ultimately by the donor?— (8) The *th* is quite indistinct, but nevertheless certain. The final letter, read *la* by CTI. and left undetermined by AS., must be *kh*, which gives us the excellent reading *dānamukha[m]*. The form of *kh* is not quite usual. But it seems to be so nearly allied to certain variants of the same letter as to make this interpretation probable, which also gives a good sense. To judge from the form of *kh* in No. 13, the shape of this letter seems to have been particularly changeable and undetermined.

TRANSLATION.

"(This) pillar (is) the gift of the preacher Sātimita, the son of Nanda (P) (and) the disciple of the *Śhācīya* of the venerable Dhammutariyas (Dhammutariyas), from Sopāraka, together with [his father and mother?]."

In explaining these lines one cannot separate them from the following inscription (No. 9) its abridged reproduction, the motive of which we cannot quite make out. This comparison proves that the connection with the sect of the Dharmottariyas applies in the mind of the author to Sātimita himself. What is more doubtful, is, whether the first genitive following *sama[nāthasa* applies to him or to his master. I do not believe in Bühler's conjecture *sama[nāthasa* is too risky to restore a purely hypothetical title of hardly satisfactory meaning at the cost of a mistake attributed to the engraver, and I am unable to suggest a plausible restoration of my own. It seems to me very tempting to find here the proper name (e.g. *Sacanāthasa* or *Sakranāthasa*, i.e. 'of Śarvanātha' or 'of Śakranātha') of this master of our donor; but generally the *nāthasa* precedes the proper name. Hence it is *a priori* more probable that the name is hidden in the letters following *therasa*, which cannot be restored with any certainty. I have said that the remaining traces would favour the reading *putasa* for the second part of the word which AS reads *Nadipatīsa* and OTI. *Nadāputīsa*. If we read at the beginning *Na[m]da*, or *Na[m]di* or *Na[m]di*, the reading *putasa* seems to me assured by the consideration that Sātimita, being a preacher and belonging to the sect of the Dharmottariyas, ought to have been a monk and consequently unmarried.¹ As regards the use of *dānamukha* as an equivalent of *dāyadharmā*, it is well known in the Buddhist epigraphy of the North-West, and its occurrence in literature is sufficiently well established.

No. 9, Plate iii. (K. 9).

Chaitya cave. Immediately below the preceding inscription.

TEXT.

- 1 Sopārakā bhayaṃtānaṃ Dhammutariyaṇaṃ (1) bhāṇa-
- 2 kasa Sātimitasa
- 3 sasariro thabo dānaṃ.

REMARK.

- (1) AS. and OTI. *yāna*; but this *anusvāra* appears to me as certain as the other.

TRANSLATION.

"(This) pillar containing relics (is) the gift of the preacher Sātimita, (of the sect) of the venerable Dharmmutariyas, from Sopāraka."

As I have stated in connection with the preceding inscription, I think that the *Dhammutariyaṇaṃ* cannot depend, as Bühler thinks, on *bhāṇakasa*, but goes with *Sātimita*. Compare the genitives *Gatānaṃ* and *Apaguriyaṇaṃ* at Junnar (AS. Nos. 5 and 6).

No. 10, Plate i. (K. 10).

Chaitya cave. On the fourth pillar; left row.

TEXT.

- 1 Dhenukākataḥ
- 2 Dhaṇḍma-Yavanasa.

¹ We find another Sātimita at Kuṣā (AS. No. 5). But the type of the writing is there considerably later than that of our inscription and does not permit us to identify the two homonyms.

TRANSLATION.

"Of **Dhamma**, a Yavana from **Dhēnukākaṭa**."

This translation is that of my predecessors. I confess that the explanation of *Dhamma-Yavanasa* appears to me somewhat doubtful. At Nāsik (No. 18, l. 1) we find a Yavana who was the son of Dharmadēva. But the simple name of Dhamma applied to a Buddhist surprises me.¹ This combination of a proper name with a tribal name in a compound is unusual. In other cases (above, No. 7, and at Junnar, CTI. Nos. 5 and 8) the word *Yavana* precedes the proper name, and both have the termination of the genitive. On the other hand, an inscription at Junnar (CTI. No. 4) supplies a compound which resembles ours at first sight. This is the attribute *dhammanigama* applied to a certain Virasēna. It has been translated 'an upright merchant.' I doubt this translation for several reasons. First, it is hardly probable that the donor, a simple private person, should bestow such compliments on himself; what one would expect, is, not an encomium, but a positive statement like the title *grīhapatipramukha*, which resembles *dhammanigama*. Further, *nigama* does not mean 'a merchant,' which would be *negama*. Of course the change of *e* into *i* is not impossible in Prākṛit, but it is *a priori* improbable in a case where the change would produce a confusion with the usual *nigama*, which means, among other things, 'a group of people' or 'a company of merchants.' It is still less credible, if one compares the two expressions, that *Dhamma-Yavana* could be used for 'an upright Yavana.' Hence I feel tempted to take *Dhamma* in both cases in a specifically Buddhist sense, and to understand by *dhammanigama* 'a member of the guild of Buddhist merchants;' compare *nigamasabhā* at Nāsik (No. 12, l. 4). On this analogy, *Dhamma-Yavana* would be 'the community of the Buddhist Yavanas,' or rather a Buddhist Yavana who has modestly omitted his personal name.

No. 11, Plate i. (K. 11).

Chaitya cave. On the seventh pillar; left row.

TEXT.

- 1 **Dhenukākaṭā Usabhadatta-putasa Mitade-**
- 2 **vaṇakasa thabho dānaṃ.**

TRANSLATION.

"(This) pillar (is) the gift of **Mitadevaṇaka**, son of **Usabhadatta**, from **Dhēnukākaṭa**."

I feel inclined to believe that this *Mitradēva* is the son of that *Ṛṣabhādatta* who is mentioned in No. 13 and many other inscriptions as the son-in-law of *Nahapāna*. For this name is not very common, and I find another connecting link in the name of *Ṛṣabhādatta*'s wife **Dakhamitrā** (Nāsik No. 11). The silence kept regarding *Nahapāna* as well as the titles and donations of *Ṛṣabhādatta* would suggest that the inscription is later than the downfall of the *Khaharātas*; compare Nāsik No. 4. In the palaeographic forms I do not see sufficient reasons for denying that the present inscription could be slightly later than No. 13.

No. 12, Plate i. (K. 12).


Chaitya cave. On the inside of the belt which forms the base of the great arch.

TEXT.

Asāḍhamitāye bhikhūpi . dānaṃ (1).

¹ It is evident that the intentional application of this name to a purely fictitious being as the *dēva* in the *Jātaka* No. 457 is a totally dissimilar case and cannot be quoted as a precedent.


Karle Inscriptions. — Plate I.



SCALE · 125



SCALE · 125



SCALE · 125




SCALE · 125



SCALE · 06



SCALE · 125



SCALE · 125



SCALE · 17

REMARK.

(1) AS. and CTI. °*khunī[ye]* The letter *ye* seems to have disappeared in the crack, and I think I can see after it *d[d]nam*; the *nam*, especially, is comparatively clear.

TRANSLATION.

“The gift of the nun *Āsāḍhamitā*.”

At Kuḍā (CTI. No. 5) we find a nun named *Āsāḍhamitā*, the disciple of Padumivikā. That inscription looks later than the present one. But it may be that the engravers of Karle had kept up a slightly more archaic tradition.

No. 13, Plate ii. (Ksh. 6).

Chaitya cave. On the upper frieze to the right of the central door.

The estampage does not throw much more light on the text than the Plate. From this it will be understood that this inscription in its actual state leaves very much room for the ingenuity of the reader, and that the earlier reproductions greatly exaggerate the actual certainty of several readings. To become convinced of this, one need only compare the differences between AS. and CTI. at the end of the 3rd line.

TEXT.

- 1 Sidham [||*] Raño Khaharātasa khatapasa Nahapānasa jā[ma]tarā (1) . n .
kapūtena (2) Usabhadātena ti-(3)
- 2 gosatasahasa[de]ṇa nadiyā (4) Baṇāsāyā (5) s[u]vaṇatathakarena (6) . . .
brahmaṇa (7) cha soḷa[sa]gā-
- 3 ma[d]e . Pabhāse pūtatithe (8) brahmaṇa aṭhabhāyāp[r]a . . [a]nuvāsam
pi tu (9) satasahasam bho-(10)
- 4 japayita Valūrakesu leṇavāsinam (11) pavajitānam . ohātudisasa saghasa
- 5 yāpaṇatha gāmo [Ka]r[a]jiko (12) dato sa . na . . . vāsitanam (13).

REMARKS.

(1) CTI. °*mā*°. I cannot discover any trace of the *ā*.—(2) The reading *Dinika* is no doubt certain; but the *d* is quite indistinct on the estampages, and the *k* is much worn.—(3) I believe that there is nothing but *ti* at the end of this line. What has been taken for *pi* (AS.) would run into the bottom of *ti*. Besides, *tini* = *trini* would be a serious and unusual mistake.—(4) AS. *nadiyā*, which is inadmissible.—(5) CTI. reads °*ṇāsayaṇ*.—(6) I do not see any trace of the *u* below the *s*, though the reading *su* is certain. AS. and CTI. read °*ratha*°, though admitting that the word corresponds to *tīha* = *tīrtha*. The still visible stroke would not be so straight if it were a *ra*. It is the remnant of a *t*, above which the *i* is lost.—(7) I do not see anything of *devāna*, though this word is warranted by the comparison with the Nāsik inscription No. 10. AS. and CTI. read *brahmaṇa*[ṇ] with a long *ā*, of which I do not discover any trace.—(8) AS. *puṇatithe*; but the *ta* is sure.—(9) The *p* has at the right bottom a perpendicular line which may express the *r*, as in *brāhmaṇa*. The restoration *ḍena* seems certain; but nothing remains of these letters. After this, CTI. reads *gāvasāpi trisa*°. The reading of AS., which resembles mine closely, appears to me almost certain, though the initial *s* is much spoiled.—(10) AS. °*tasāḍhasi[bho]*°. The final *bho* is quite clear. Though believing that I see °*sahasam* in the estampages, I do not venture to deny that the actual reading may be °*hasiṇ*.—

(11) AS. and CTI. °*vāsdna*.—(12) The first *k* is very indistinct, and the *r* would seem to have at the top the vowel-mark *ā* or *o*.—(13) I am quite willing to believe that the reading proposed by the first editors, *savāna vāsavāsītānaṃ*, is well founded; but a portion of it has become quite invisible, and between *na* and *vā* there is certainly room for another letter. It is true that between *si* and *tā* there is also room for one more character, which is, however, quite improbable.

TRANSLATION.

“Success! By Usabhadāta, the son of Dinika (and) son-in-law of the king, the Khaharāta, the Kshatrapa Nahapāna,— who gave three-hundred-thousand cows, who made gifts of gold and a *tīrtha* on the river Banāsā, who gave to [the Dēvas] and the Brāhmaṇas sixteen villages, who at the pure *tīrtha* Pabhāsa gave eight wives to the Brāhmaṇas, and who also fed annually a hundred-thousand (Brāhmaṇas),— there has been given the village of Karajika for the support of the ascetics living in the caves at Valūraka without any distinction of sect or origin, for all who would keep the *varsha* (there).”

In explaining these lines, we have to compare closely Nos. 10 and 14 at Nāsik. A portion of the first, especially, which is better preserved, comes very near to our text. The river Banāsā (compare Nāsik No. 14, l. 10) or Bārṇāsā (Nāsik No. 10, l. 1) is represented in Western India by two rivers named Banās, with which it has been successively identified. The first belongs to Northern Gujarāt, passes Pālampur, and falls into the Rap of Kachh (Burgess). The second flows through Eastern Rājputāna and joins the Chambal (Burgess, and Bhagwanlal Indrajī, *Bombay Gazetteer*, Vol. XVI. p. 633). In Nāsik No. 10, l. 4, we shall see that, after a campaign in the south, Rishabhadatta returned to the sacred lake of Pushkar near Ajmere, bathed there, and made pious gifts. Hence it may be assumed that this country possessed a special importance for his family; and it is *a priori* natural to localise there other donations of his. Now it is precisely in those parts that the second river Banās flows, and until better information is obtained it seems to me more probable that this river is here alluded to; but the precise nature of the gifts alluded to is not easy to determine with certainty. The reading *suvarṇatītha*^o is supported by the comparison with Nāsik No. 10, l. 1, where we find *suvarṇadānatīrthakārēna*. Our text is an abridgment of this expression, on which it is based, just as *satasahasam* in l. 3 corresponds to *brāhmaṇasatasahasāri* at Nāsik. After having hesitated between the two translations ‘the founder of a *tīrtha* and giver of a gift of gold’ and ‘the founder of a *tīrtha* by means of a gift of gold’ (CTI. p. 33, note), Bühler seems to have decided in favour of the second (AS. p. 101). I decidedly prefer to adopt the first, like Bhagwanlal (*Bombay Gazetteer*, Vol. XVI. p. 571). If the second were true, *suvarṇadāna* would represent nothing but a kind of tautology. It is evident that a *tīrtha* cannot be established without expending money. Besides, to take the first portion of the compound *suvarṇadānatīrthakara* in the sense of the instrumental is not inadmissible, but rather far-fetched. Finally, I notice at least one case where the two different ideas are combined in the same way, but in terms which are not ambiguous. The Naḍupūru grant of Annavēma¹ says:—*Yēn=āgrahārā bahavō vitīrṇā Hēmādri-dānāni kṛitāni yēna ! tīrthēshu satīrāṇi tatāni yēna*. Though this text is much more modern than that of Kārīḥ, it has its value as witness of a tradition whose constancy we shall have occasion to verify in still other formulas. We would have certainly found some decisive argument in favour of the correct interpretation, whichever it may be, in the Nāsik inscription No. 14, l. 11, which follows a different redaction; but unfortunately its text is mutilated.

Nāsik No. 14 has *punyatīrthē*; *pāta* is a perfect equivalent of *punya*, and, besides the shape of the letter, the long *ā* attached to the *p* confirms this reading. Everybody agrees, I believe, in identifying this Pabhāsa with Prabhāsa or Sōmanāthapaṭṭana in Kāthiāwār, where

¹ Above, Vol. III. p. 238, verse 9.

the epic legend locates the death of Kṛishṇa. In connection with the 'gift of wives to Brāhmaṇas,' Bhagwanlal Indraji (*Bombay Gazetteer*, Vol. XVI. p. 571) aptly quotes a passage in the Aphaṣṭ inscription of Ādityasēna.¹ If *kanyās* are there referred to, while here the donor speaks of *bhṛgyās*, the position is in the main identical. Only, it is in the first case considered from the point of view of the Brāhmaṇas who were the fathers of the young women, and in the second case from that of the Brāhmaṇas who became their husbands. There is nothing in this variation to justify the unlikely interpretation which Bhagwanlal (from an argument which in my opinion could easily be turned against him) has tried to substitute for the true one, viz. that Rishabhādatta boasts of having given wives to eight Brāhmaṇas by exempting eight young women of the Brāhmaṇa caste from all the expenses which are involved by the costly ceremonial of Hindū marriages and the acquisition of the ornaments which in a certain way represent the dowry.²

Pi tu are two particles. Bühler's translation 'for the sake of his father' presupposes in the text *pitarāṃ uddiśa*. Besides, independently of the omission of the 'mother,' which would be surprising and contrary to custom, the mention would be curiously placed here in a brief recapitulation; it is certainly missing in the parallel passage in Nāsik No. 14.

Valūraka seems to designate Kārlā; compare the following inscriptions. The plural is used frequently in the case of village names. It remains to ascertain in what manner have to be construed all the genitives *leṇavāsinaṃ pavajitānaṃ chātudisasa saṅgha*. We may compare several analogous formulas. In No. 19, l. 1 f. we find: *leṇeṃ Valurakesu rātharāna pavajitāna bhikkhuna nikāyasa Mahāsāṅghiyāna yāpanāya gāma* *dadāma*; in Nāsik No. 2, l. 10: *leṇa mahādevī dadāti nikāyasa Bhaddāranīyānaṃ bhikkhusaṅgha*; in Nāsik No. 3, l. 12: *gāmo bhikkhū devīleṇavāsehi nikāyena Bhaddāyanīyehi patiga[h]ya dato*; and *ibid.* l. 13: *gāma bhikkhū devīleṇa[vāsehi nikā]yena Bhaddāyanīyehi patigayha dato*. The passage in No. 19 was intentionally copied from the present inscription and has therefore no independent value. In both cases one might be tempted to separate the two genitives and to let the first depend on *dadāti*, the second on *yāpanāya* or *yāpanātha*. But the long distance from the verb would be little favourable to this hypothesis. And in Nāsik No. 2, where *yāpanāya* has no equivalent, it is quite excluded. Besides, in Nāsik No. 3, where a different case is used, both terms are, just as here, in the same case. Hence we must conclude that in all these instances the terms *bhikkhu* or *saṅgha*, *nikāya*, and *Mahāsāṅghīya* or *Bhaddāyanīya* are co-ordinate. Thus the donation is made here "for the support of the universal *Saṅgha* in the person of the monks residing in the caves at Valūraka;" in No. 19 "for the support of the brotherhood constituted by the Mahāsāṅghikas in the person of the monks (of this community) residing in the caves at Valūraka"; in Nāsik No. 2, "to the *Saṅgha* of the monks in the person of the brotherhood constituted by the Bhaddāyanīyas;" and so on. We shall see in due time how the change of the case in Nāsik No. 3 is to be explained. Here I would only remark that in the two passages of that inscription we find both *nikāya* and *Bhaddāyanīya* in the instrumental case and are thus prohibited in No. 19 to construe, as would seem natural, *Mahāsāṅghiyāna* as dependent on *nikāya*,—'the brotherhood of the Mahāsāṅghikas.'

This point being established, we shall have to fix more clearly than seems to have been tried hitherto the meaning which our inscriptions assign to the expression *chātudisasa saṅgha*. In my opinion *chātudisasa* is not a kind of *epitheton ornans*, a common-place formula. The expression has an intentional meaning; it signifies the clergy of every origin, i.e. the clergy in its universality

¹ Dr. Fleet's *Gupta Inscriptions*, p. 203, l. 2.

² Hemādri in his *Chaturvargachintāmaṇi* (I. 9, p. 678) has collected a certain number of *kanyādānas* by which, according to the epic, certain kings conferred on Brāhmaṇas women over whom they had authority. But these are at least exceptional, if not absolutely fictitious cases, from which an analogy could not, I think, be invoked for explaining gifts of an ordinary kind, which were frequently repeated.

beyond all particular limitation; and this is why the donor adds *savāna vāsavāsītānaṃ*. In fact, it was for the retreat of the *varsha* that the monks of every other denomination or residence (*chātudīsa saṃgha*) could be brought to take up their abode in the caves of Valūraka along with their resident hosts. If the donor had meant only the monks living at Valūraka, he would have said simply *Valūraka-saṃgha*, as in the following inscription. In the same way a gift is made in Nāsik No. 15, l. 7, *Triraśmīparvatavihāravāstavyasya chāturdīśabhikkhusaṃghasya gilānabhēśhajārtham*, i.e. "to be applied for the medical treatment of the monks of every origin who shall reside in the *vihāras* of the Triraśmī hill." Monastic communities may be classified in two respects, viz. according to their residence and according to the sect to which they belong. This double restriction is excluded in principle by the mention of the *chātudīsa saṃgha*, though in some cases and according to the dispositions of the donor it may mean specially one or the other. Thus in Nāsik No. 10, l. 4 f. a donation is made as follows: *eto mama lepe vasatānaṃ chātudīsasa bhikkhusaṃghasa mulhāhāro bhavisati*. Here we have a restriction to a certain locality, while *chātudīsa* excludes only the restriction as to sect; and the donation is accordingly intended for the feeding of the monks who reside or shall reside in this cave, to whatever denomination they belong. The same is the case in Nāsik No. 12, l. 2, where a rent is allotted to the *chātudīsa saṃgha*, y[a] *imasmīn lepe vasatānaṃ bhavisati chivarika*, i.e. "for furnishing clothes to the monks who shall reside in this cave without reserve or distinction as to sect." The same idea is expressed in the donation recorded in Nāsik No. 24, l. 3 f. On the other hand, in Kārlī No. 20, l. 3, "a hall of nine cells is given to the *saṃgha chātudīsa* as property of the Mahāsāṃghikas,"—*Mahāsaghiyānaṃ parigrahaṃ saghe chātudīse dāna*. We have to compare a passage in the inscription of Tōramāna at Kura (*Ep. Ind.* Vol. I, p. 240). Bühler has justly remarked the antithesis existing between *chāturdīsa saṃgha* and *parigraha dehārya-Mahāsāsakānām*. But I feel inclined to think that he has not solved it in a quite satisfactory manner. According to him "the meaning seems to be that all Buddhist monks shall participate in the use of the *vihāra*, but that it is specially made over to the Mahāsāsaka teachers." Does it not rather seem that, in allotting to the *chāturdīsa saṃgha* the gift which was at the same time made the property of the Mahāsāṃghikas or Mahāsāsakas, Tōramāna in the Kura inscription and Rishabhādatta in the present case desired that their donation should benefit only the members of the sect which they wanted to favour, of whatever origin and usual residence? This conclusion seems to be strongly corroborated by the comparison of Kārlī No. 19, l. 1 f., where the village of Karajaka is given "for the support of the Mahāsāṃghika monks residing in the caves of Valūraka,"—*lepesu Valūrakesu vāthavāna pavajitāna bhikkhuna nikāyasa Mahāsaghiyāna yāpandya*. Here the donation is expressly restricted to the Mahāsāṃghika monks residing at Valūraka. Shall we not conclude from this, that, in other cases where the *chāturdīsa saṃgha* is referred to, the gift is made to the Mahāsāṃghikas of whatever origin? While in the preceding examples the wording excluded all restriction as to sect, it excludes here all restriction founded on origin or residence. It is hardly necessary to add that, if used alone and without an explicit clause, the expression excludes both the first and second restrictions. No. 19 informs us that the village of Karajaka was given to the monks of Valūraka by Vāsīṭhīputa Puṣumāyi or Gotamīputa Sātakaṇi. This inscription is certainly later than the present one. Though it does not allude to a previous donation, and though the form *Karajika*, which we have here, differs slightly from *Karajaka*, the only form which occurs in No. 19, I think that Bühler is right in admitting (*AS.* p. 113; compare p. 24) that the two names refer to the same village. The renewal of the donation was brought about by the new state of affairs created by the victories of Gautamīputra Sātakaṇi and by the destruction, of which he boasts, of that dynasty of the Khaharātas with which our Rishabhādatta was directly connected by his father-in-law Nahapāna. What persuades

¹ This shade of meaning is expressed with particular precision by such a phrase as that which we find in the inscription of Chandragupta II. at Sāñchi, where a donation is made *Kākaṇḍābhojīśrīmahāvihāre* *chāturdigabhydgatya* *āryasaṃghāya*; Dr. Fleet's *Gupta Inscriptions*, p. 31.

me of this, is the parallelism existing between the phraseology of our inscription and that of No. 19; thus—

No. 13.

*Valûrakesu leṇavāsinaṃ pavajitānaṃ
chātudisasa saghasa yāpanatha
gāmo Karajiko dato.*

No. 19.

*Lenes[u] Valûrakes[u] vāthavāna pavajitāna
bhikkhuna nikāyasa Mahāsaghiyāna y[ā]pan[ā]ya
. gāma Karajaka dadama.*

The close similarity proves that this parallelism was intentional, and it is all the more significant that the second donor, who was probably filled with a particular sympathy for the Mahāsāṃghikas, restricts the benefit of the donation to the monks of this sect alone. If the identification is well founded, it localises the village in question in the Māwal subdivision, west-north-west of Poona.

No. 14, Plate ii. (Ksh. 17).

Chaitya cave. On the upper frieze to the left of the central door.

TEXT.

- 1 Raño Vāsīthiputasa (1) Sāmisirip s . (2) savachhare satame 7
[g]imhapakhē pachame 5
2 [d]jivase pathame 1 etāya puvāya Okhaḷakiyāna Mahārathisa (3)
Kosikiputasa Mitadevasa putena
3 hārathinā Vāsīthiputena Somadevena gāmo dato Valuraka-saghasa (4)
Valuraka-lenāna (5) sakarukaro (6) sadeya-
4 meyo.

REMARKS.

(1) AS. *Vasi*°. The long *ā* is certain.—(2) From the traces, the restoration *Puḷumdyisa* can hardly be called conjectural.—(3) CTI. °*rathisa*; but the central dot of the *th* can still be recognised, and the certain reading °*rathi*° in the following line leaves no reasonable doubt regarding the transcription.—(4) AS. °*rakāsawghasa*.—(5) AS. *Valûrakalenana*. I do not share the opinion of Bühler who considered that the long *ā* is certain. In my opinion it would be less improbable in the preceding word, were it not that the condition of the stone deprives certain apparent but accidental strokes of any real significance.—(6) CTI. *sakarā[ra]karo[ra]*. The transcription of AS., which is ours, seems to me certain.

TRANSLATION.

“In the seventh—7th—year of the king lord Siri-Puḷumāyi, son of Vāsīthi, in the fifth—5th—fortnight of summer, on the first—1st—day, on the above, by the Mahārāṭhi Sômadêva son of Vāsīthi, the son of the Mahārāṭhi Mitadeva son of Kosiki, of the Okhaḷakiyas, there was given to the community of Valûraka, of the Valûraka caves, a village with its taxes ordinary and extraordinary, with its income fixed or proportional.”

I have stated on p. 50 why the genitive *Okhaḷakiyānaṃ* must be connected with *Somadevena* and cannot depend on *Mahārathisa*. It is the geographical name of a country, or rather of a tribe. Bühler (AS.) has pointed out the name of a district, Ukhaḍa, from which it may be derived. The end of the inscription presents a difficulty which has not yet been solved satisfactorily. Bhagwanlal read *sakarākarosa deyameyo*, which he transcribed in Sanskrit as *saṃskārakārāṇāya dēya ēśhak*. I can hardly believe that Bühler could have approved of such an explanation; but, though he read *sakaruka*°,—a reading which seems to be warranted by an examination of the back of the estampage,—he adopted the same translation as Bhagwanlal in CTI., viz. “this gift is in order to keep the Valûraka caves in repair.” As in his transcription (AS.) he separates

"*karosa deya*", I imagine that he admitted that the text was disfigured by several mistakes, and that he restored *saṃkarakurasa* = *saṃkhara*¹. But in this hypothesis the use of the genitive for the dative and the use of *kara* = *kāraṇa* would seem inadmissible. This preconceived notion has caused the end of the inscription after *Valūrakasāṅghasa* to be considered a separate sentence, *Valūrakalenānaṃ* being necessary for completing the following word. I believe that, if one reads the text without prejudice and keeps in mind the customary wording of grants, one cannot fail to connect the words *sakarukaro sadeyameyo* with *grāmo dato*, and to take them for epithets resembling *sōdraṅga sōparikara*, etc., which occur in other grants in precisely the same place. Besides, by this construction we avoid having recourse to the expedient of corrections, which is always objectionable. The first result is to condemn the break of the sentence between *Valūrakasāṅghasa* and *Valūrakalenānaṃ*. These two terms are closely connected. The gift is made to the *Valūraka-jenas*, i.e. as the preceding inscription expressed it in a slightly different way, "to the *Valūrakesu leṇavāsīs*," of the *Saṅgha* of *Valūraka*. *Valūraka* is the general designation of the village where the so-called *Kārle* caves are situated. Doubtlessly this locality contained still other monks besides those who had found an asylum on the slopes of the hill. To these last ones was confined the benefit of the royal donation.

There remain the terms *sakarukaro* and *sadeyameyo*. It is well known and will be noted again more than once how much uncertainty is felt in the explanation of technical terms repeated incessantly in grants of all ages, which define or describe the rights and advantages conferred on the donees. If this is the case even in quite a modern protocol, it is not surprising that we are embarrassed by more ancient formulas which have fallen more or less into disuse. But ours is not without analogies. *Kara* is so well known in the sense of 'dues payable to Government,' that I need not dwell on it,¹ The same is not the case with *utkara*; but *uparikara*, which is its exact equivalent, appears almost invariably at the head of the customary formulas which begin generally with *sōdraṅga sōparikara*. The meaning of *udraṅga* is not yet established. I do not know if *kara* can strictly correspond to it. At any rate, there is no doubt that nothing but a kind of revenue is meant here, so that in a general way *sakarukaro* = *sakarōtkaraḥ* becomes the natural equivalent of *sōdraṅgaḥ sōparikaraḥ*. The meaning of *uparikara* is as little settled as that of *udraṅga*, and it will not be wondered at that I cannot be positive regarding the translation of our new term. The certain meaning of *kara*, combined with the modification which is implied by *ut* or *upari*, the first member of *utkara* or *uparikara*, seems to recommend as plausible the general sense which I have attributed to these two terms.

The adjective which follows has at least the advantage that it can be translated etymologically,—'together with what has to be given and what has to be measured.' This is vague, but not at all unintelligible. Here also, I think, the comparison of the more modern formulas can assist us. Several grants combine with the epithets *sōdraṅga* and *sōparikara* the expression *savūtabhūtaḥ dhānyahiranyādēya*.² More commonly it is resolved into *sabhūtaḥ pratyāya* and *sadhānyahiranyādēya*,³ which prove that, contrary to the hesitating conjectures of Dr. Fleet (*l.c.* p. 170, note 9) and in conformity with Dr. Hultzsch's translation, *ādēya*, 'what is to be taken,' is nothing but an equivalent of *pratyāya*, 'revenue.' Hence *dhānyahiranyādēya* means 'the revenue both in grain and in specie.' The expression used in our inscription is not quite identical; for we have not *sādēya*, but *sadēya*. Nevertheless it seems to me very probable that it corresponds on the whole to the idea expressed by the Sanskrit formula and, like it, embraces 'what is given or paid directly,' i.e. the taxes in money, and 'what is measured,' i.e. the dues in kind which were levied on the products of the fields.

¹ Compare in the inscriptions of Jayanātha and Śarvanātha (Dr. Fleet's *Gupta Inscriptions*, p. 118, l. 9, and p. 127, l. 17): *asya (grāmasya) samuchītaibhāgaibhōgakarapratyāyōpanayam karisāyathā*.

² See e.g. the Māliya plates in Dr. Fleet's *Gupta Inscriptions*, p. 166, l. 26.

³ See e.g. the Alinā plates, *ibid.* p. 179, l. 68, and the Lunsatī plates, above, Vol. IV, p. 80.

No. 15, Plate I. (K. 13, 14).

Chaitya cave. Above a pair of figures at the right corner of the verandah.

TEXT.

Bhadasamasa bhikhusa deyadhama mithûna (1) ve (2).

REMARKS.

(1) Though the *fac-similes* in CTI. have only a trace of the long *û*, it seems to me very probable from the new estampages that the writer formed an *û*, as in the following inscription which to all appearances is written in the same hand. One might feel inclined to believe that the letter is only an exceptional form of the short *u*; but in No. 1 we have found clearly *ûtama* beside *Bhutapûla*. and in No. 13 there are several distinct instances of long *û*. We must therefore transcribe the sign by *û*, without forgetting—what is attested by many cases and notably by the numerous inscriptions which do not make any distinction between the long and the short vowel—how negligent our inscriptions are in marking vowels.—(2) Though this inscription is closely connected with the following one, I do not believe, after minute examination, that, as my predecessors thought, the two inscriptions are absolutely identical. In No. 16 the reading is free from doubt. The same is not the case here. The last letter, which has been read *n*, looks rather like *v* with the vowel *e*, and in the crack between *thû* and *ve* there is room for the final *n* of *mithûna*. It looks as if an *n* with *â* could be distinguished. One might even believe that one sees a distinct *nâ* subscribed to this damaged character, as if the letter above had been spoiled by some accident and subsequently restored below the line. At any rate it seems to me wrong to transcribe the last letter otherwise than by *ve*.

TRANSLATION.

“Two pairs, the pious gift of the *Bhikshu Bhadasama*.”

If my impression regarding the reading of this inscription is justified, the proposed translation would be certain. In the presence of the following inscription, it would have to be assumed that the donor originally had the intention to perpetuate his double gift by only a single mention, but that on second thoughts he added his name a second time on the other pillar. As regards the form *ve*, we find *be* = *dvar* in Nâsik No. 4, l. 3, and No. 12, l. 3, and *do* in Nâsik No. 26, l. 3.

No. 16, Plate i. (K. 13, 14).

Chaitya cave. On the inner side of the right hand screen of the verandah; above a pair of figures.

TEXT.

Bhadasamasa bhikhusa deyadhamam (1) mithûnam (2).

REMARKS.

(1) AS. and CTI. °dhama; but the *anusvâra* seems to me sufficiently clear.—(2) AS. and CTI. °hûna; compare the preceding inscription.

TRANSLATION.

“(This) pair (is) the pious gift of the *Bhikshu Bhadasama*.”

No. 17, Plate i. (K. 15).

Chaitya cave. On the wall to the right of the central door (close to the rail pattern).

TEXT.

. maṇayūtāya (1) dānaṁ veyikā.

REMARK.

(1) AS. and CTI. . . . [sa]maṇḍya mātuya. No traces remain of the pretended *sa*, which appears entirely conjectural. The *n* is certainly not accompanied by an *ḍ*. To judge by their own plates, AS. and CTI. have inserted the *mḍ*, which is completely invisible and for which there is no room. The *y* which precedes bears a clear subscribed *ḍ* of the same shape as in the two preceding inscriptions. The following *t* has at the top the mark of *ḍ*, and the lower stroke, which has been taken for *u*, ought to have been attached to the right of *t* if it had this meaning.

TRANSLATION.

"(This) rail (is) the gift of"

I can make nothing of the existing remains of the proper name. We see only that the sculpture of this balustrade was the gift of a female.

No. 18, Plate iii. (K. 18).

Chaitya cave. On the wall to the left of the central door (close to the rail pattern).

TEXT.

Koṭiya (1) bhikhūpiya Ghuṇika-mātu (2) veyikā dānaṁ (3) [Nam]ḍikenā (4) kataṁ.

REMARKS.

(1) AS. and CTI. *Koṭiya*. The second letter seems to me rather a *ṭi*; but it is doubtful.—(2) AS. °māta; the *u* is certain.—(3) AS. °dāna, CTI. °dāna.—(4) The first letter is doubtful, the horizontal basis of the *n* being singularly slanting. But the final *ḍ* is sure.

TRANSLATION.

"(This) rail, the gift of the *Bhikhūpi* Koṭi, the mother of *Ghuṇika*, was made by *Nandika*."


No. 19, Plate II. (Ksh. 20).

Chaitya cave. On the 2nd and 3rd tiers of the frieze between the central and the right-hand doors.


TEXT.

- 1 [ānapayati] Māmāḍe (1) amacha par . gata .
masu (2) etha lenesa Vāḷurakosa (3) vāthavāna (4)
- 2 pavajitāna bhikhūna nikāyasa Mahāsagh.yāna y' pan. ya etha Māmālāhāre
utare (5) mage g. m. Karajak. (6)
- 3 bhikhuhale[la] (7) dadama — etesa [tu] (8) — gāma (9) — Karajake (10) —
bhikhuhala — deya — pāpehi (11) — etasa — chasa
- 4 gāmasa Karajakāna bhikhuhalaparihāra vitarāma apāvesa a (12)
. pārihārika cha etehi na parihārehi pariharah. (13) et . chasa
gāma Karajake (14)
- 5 bhikhuhalaparihāre cha etha nibadhāpehi (15) aviyena ānata
. chhato vijayathasatāre (16) dato the . . (17) [paṭikā]
sava 1[4] (18)
- 6 vā pa 4 diva 1 Sivakhadagutena kaṭā.

Inscriptions. - Plate II.




SCALE · 125



SCALE · 1



SCALE · 1



SCALE · 125



Collotype by Hömmler & J.

REMARKS.

(1) Of this inscription, CTI. gives only a *fac-simile* without transcript or commentary. Hence only AS. has to be considered here. AS. *Māmā[le]*; the *de* is certain.—(2) AS. *pa . ga . . masu*. The *r* is certain, though I cannot say whether it was accompanied by an *ā* or an *i*. The last syllable looks like *sa*; but on the back the mark for *u*, which AS. gives, can be clearly distinguished.—(3) AS. *lenasa Valurakasa*. The letters *vā* and *ke* appear certain. I do not doubt that we have to read *su* in both cases, though the vowel-mark is not visible anymore: compare the preceding note. The locative is indeed what we would expect.—(4) AS. *vāthavāna*. The *th* is not doubtful.—(5) AS. *utaramag[e]*.—(6) AS. *gām[e] Karajake[su]* . . . The final *e* of *g* [e] is just possible, as well as the *e* of *°jak[e]*. But I do not believe that the syllable *su* and any following syllables exist.—(7) AS. *bhikkhukala*; but there is certainly a letter between *ka* and *la*, which seems to be *le*. Its bottom is not exactly in the same line with the neighbouring letters and the top runs into the crack. Could it have been repeated because it had come out badly the first time?—(8) AS. *etesa gā°*. The *sa* is certainly followed by a letter, which seems to be *tu*.—(9) AS. *gām[e]*. The *m* is clear and does not bear any vowel-mark.—(10) AS. *Karajake[su]*. The *ke* is probable, though the enlargement of the top of the *k* (compare the initial *k*) is frequent enough to leave room for doubt. The *su* may have dropped out. But in the rest of the line the projection of the tops of the beams does not seem to have caused any breaks in the inscription. Accordingly, the latter must have been engraved subsequently; or, if anterior, it must have been calculated in such a way as to leave space for those projections.—(11) AS. *papahi*. The *i* and the *e* seem clear. Between *°tasa* and *chasa* there is room for two letters, but nothing seems to have been engraved there, unless the traces of the crack in the stone should mark the place of letters which might have been engraved by mistake and obliterated subsequently. It seems that the engraver had reserved the necessary space for the top of a beam analogous to the preceding ones, which was, however, not added.—(12) AS. *u[pa]vesa* —(13) AS. *pariharaha*. I do not discover any trace of an *i* accompanying the *r*, and would rather read *°reh[i]*.—(14) AS. *ete chasa gām[e] Karajake[su]*. It seems to me impossible to say whether the stone bears *eta* or *ete*. I feel inclined to read *etan*. It is very improbable that the *m* of *gāma* bore the mark of *e*. As to the syllable *su*, neither the length of the following line nor the appearance of the free space after *ke* authorises us to assume its existence.—(15) AS. *eta nibadhō[lehi]*. The reading is uncertain. What I propose, *pe* for *le*, appears to me on the whole more plausible.—(16) AS. to *vijayathasātāre*. The *th* seems to be accompanied at the left top by a mark like *e*, which is however a little too slanting. The *r* of the last syllable might as well be read *kh*.—(17) AS. *the rañā*. This reading seems to me extremely problematical, especially in the case of the letters *ra* and *ñā*. The last syllable of *pañikā* would also remain doubtful if it were not supported by analogous cases.—(18) I follow Bühler in transcribing the second figure by '4': but he considered it very doubtful; and I see no particular reason for reading '4' rather than any other unit.

TRANSLATION.

"[King] commands the officer at **Māmāda**:—For the support of the sect of the **Mahāsāṃghikas**, of the mendicant friars dwelling here in (*these*) caves of **Valūraka**, all pervaded with religion (?), we give as monks' land the village **Karajaka** here in the **Māmāla** district on the northern road. To them I have secured the property of the village of **Karajaka** as monks' land, and to this village of **Karajaka** we grant the immunities belonging to monks' land, not to be entered (*by royal officers*) and to enjoy (*all kinds of*) immunity; with all these immunities I have invested it. And this village of **Karajaka** and the immunities enjoyed by monks' land I have had registered here. Ordered verbally, written given at the victorious camp (?) The deed was executed by

Sivakhadaguta (Śivaskandagupta) in the year 14, on the 1st day of the 4th fortnight of the rainy season."

There is no means of deciding whether this inscription emanates from Vāsish[hiputra] Tālmāyi like Nāsik No. 3, or from Gautamīputra Sātakarṇi like Kārle Nos. 4 and 5. I incline however towards the first hypothesis. The phraseology is quite identical in Nāsik No. 3 and in the present inscription, and the break which, to our regret, we find here, could be filled exactly by what precedes *anapayati* in Nāsik No. 3.—Māmāla or Mamāla has been identified (AS. p. 24) with the modern Māwal or Māul along the Ghauts. Regarding *āhāra*, compare Dr. Fleet's *Gupta Inscriptions*, p. 173, note. The final *u* of *par . gata . masu* and the *e* of *lonesa* and *Vālurakesu* seem to prove that we have to read in each case the locative plural in *ésu*, and that the three words are connected, the first being only an epithet of the second. I propose to restore it as *parigatadhamesu*, which might be a proper epithet of these places, 'wholly devoted to religion.' It is quite clear on the other hand that the analogy of the parallel passages (Nāsik Nos. 3; 2; 4. 2) would make us expect in this place the proper name of the officer. It is only out of despair, and especially under the influence of the final *su*, that I have recourse to this hypothesis. The phrase has to be explained by comparing Kārle No. 13, l. 4, from which an additional argument in favour of the reading *Vālurakesu* is derived, and Nāsik No. 3, l. 12 f: *bhikkhuhi nikāyena bhaddāyanyehi*. The 13th edict of Aśoka (Khālsi, l. 38) already employs *nikāya* in the particular meaning of 'religious corporation.' Though *pavajita* and *bhikhu* are equivalent in meaning, we find the two words combined elsewhere, e.g. in Nāsik No. 5, l. 8. As regards the construction and the details of the translation, I refer to the remarks on Kārle No. 14, of which I have stated that our text intentionally imitates the wording. I will only add here that the construction of *Mahāsaghiyāna* as in apposition to *nikāyasa*, which is forced on us by the comparison of Nāsik No. 3, but which is a little puzzling to us, has at least one analogy, which the genitive *gūmasa Karajakāna* (l. 4) makes obvious, in the frequent construction of *grāma* with a proper noun, the occurrence of which in the plural seems to indicate that originally it designated less the locality than its inhabitants.

Bühler (p. 111) proposed to take *maga* (*mārga*) as the name of a territorial division, which is not found in other documents. He quoted the analogy of *pathaka* which occurs elsewhere in a similar sense. We have to wait for fresh facts to confirm this conjecture; but even in its current meaning *uttara mārga*, 'the northern road,' 'the northern direction,' gives a sufficiently good sense.

Whatever may be the cause of the erroneous form *bhikkhuhalala*, it can only be meant for *bhikkhuhalah*. Unfortunately the meaning of this expression, which occurs not only here, but also in Nāsik No. 3, is far from distinct. *Hala* designates in certain cases a measure of land (*Ep. Ind.* Vol. I. p. 8, note), the extent of which varies according to the word which precedes and determines *hala*; see *dharmahala*, *Hārītasmiti* quoted by Kullūka on Manu, VII. 119; *vrīhaddhala*, inscription of Harsha (*Ep. Ind.* Vol. II. p. 125), etc. But *hala* has also the meaning of 'cultivated field,' as in *dēvabhōgahala*;¹ compare *brāhmaṇānāṃ halakshētra* in the Uruvupalli plates (*Ind. Ant.* Vol. V. p. 52, text line 23), etc. With these expressions we may certainly compare that of our text. In the Buddhist language, *bhikkhuhala* is the equivalent of those religious donations which in the Brāhmanical phraseology are termed *dēvabhōgahala*, *dēvadāya* (above, Vol. III. p. 274, l. 60) and *brahmadāya*, and convey, like the *bhikkhuhala* (here and Nāsik No. 3, etc.), certain privileges,—*parihāra*,² which the Māliya copper-plates (Dr. Fleet's *Gupta Inscriptions*, p. 167) sum up by the formula *uchitā brahmadāyasthitiḥ*. There, as here, the king grants not only a certain portion of land, but the village itself is given away by him as *bhikkhuhala* and participates in its entirety of the immunities implied by this

¹ Above, Vol. III. p. 146, l. 13 f. Admitting that the authenticity of this donation is doubtful, it would be nevertheless certain that it borrows its phraseology from genuine documents.

Above, Vol. III. p. 146: *sarvaparihārōpētādēvabhōgahala*.

term. I have no doubt that, at the end of l. 2 as well as in ll. 3 and 4, the text had *gāma[m] Karajak[e]*, in which *Karajake* is the accusative plural. If the text had the locative *gāme*, we would also have *Karajakesu*, which I have stated to be inadmissible. But this is the reading which I find with certainty in the continuation of the line as in *bhikkhuhala[m]*. But even if we had the locative, we should arrive by a roundabout way to the same meaning: "the *bhikkhuhala* in the village of Karajaka." It is because the village embraces the whole village, that no limit is stipulated and that the whole village is included in the immunities promised, while the contrary holds good in Nāsik Nos. 4 and 5.

After *etesu[m]* I read *tu*. Perhaps *cha* has to be read; but this does not matter. In fact we have two co-ordinate sentences. I do not understand how Bühler analysed the first sentence, which he read *papahi* and which I read without hesitation *pāpāhi*. This is the first singular aorist of the causative *prāpayāmi*, and for which we shall find in the sequel the distinct parallels *pariharāhi[m]*, and *niba[m]dhāpāhi[m]*. *Dāya* *prāpayāmi* means 'to cause to obtain, to confer, a gift.' I believe that *bhikkhuhala* is not compound with *dāya*, but must be understood as in apposition to *gāma[m] Karajake*. I conclude this from a passage in Nāsik No. 3, where we shall find the same expression with an identical meaning of both constructions would, however, be exactly the same. Without attempting to trace with certainty the reasons why the first singular and the first plural were both employed in the same phrase, I should like to suggest that the singular may have been used here in order to give a personal and deliberate turn to the affirmation or order. In the same way, the use of accentuating the idea more strongly has caused the employment of the causative *pāpāhi* after the simple *dadhima*. The king is not content to give; he wants to state that he has issued the necessary orders for realising his intention. I may quote here the expression used by Vijayabuddhavarman, to which I shall return presently: *savaparihārahī parihāraṇa pāpāhi* *īpetha* (this is the actual reading; ¹ *Ind. Ant.* Vol. IX. p. 101, l. 10). Compare also the grant of Śivaskandavarman, l. 36: *pariharitavān parihāpetarva cha*, etc. The subsequent passage is clear; and one can see now why the donor uses the two symmetrical propositions. It is clear he has assigned the village to the monks, that he grants to it the immunities of churchland. *Parihāra* has, I think, been well explained by Professor Leumann (*Ep. Ind.* Vol. I. p. 184). The original meaning, — 'exception, immunity,' quite naturally leads to the more general one — 'privilege, privileged position.'

The cognate inscriptions leave no doubt as to the privileges which were expressly mentioned here; we have to restore: *a[nomasam aloṇakhādakam vṛāṭhasamēvayikam savajita pṛithivīnā]*. The translation is less certain than the reading. Regarding *apīcesa*, in Sanskrit *apīcayana*, it is sufficient to refer to Dr. Fleet's *Gupta Inscriptions*, p. 98, note. *Anomasa* represents *anuvamṛśyam*; its certain equivalent in the later terminology, namely *saṁastardjakīḍa* or *ahastapṛakṣhāpāṇyam*, etc. (*ibid.* p. 171, note), seems to imply that the royal officers were prohibited from taking possession of anything belonging to the village. For *aloṇakhādaka* the later inscriptions offer several equivalents, — *alavanakrēṇikhanaka*, which Bühler (p. 104) has already quoted (Dr. Fleet's No. 55, l. 28, and No. 56); *aloṇagulachchhobha* in l. 32 of the plates of Śivaskandavarman (*Ep. Ind.* Vol. I. p. 6); and *salōhalavanākara* in l. 17 of the plates of Gōvinchandra (above, Vol. IV. p. 101). These words are far from clear; but if we remember the fact that the production of salt is a royal monopoly (Bühler in *Ep. Ind.* Vol. I. p. 9, note, and the details quoted by Bhagwanlal (*Bombay Gasetteer*, Vol. XVI. p. 556 and p. 179) regarding the manner of digging the soil for salt which prevails in the very region of our inscriptions, it seems to me that the explanation proposed by Bhagwanlal, *viz.* *alavanukhātaka* with the Prakrit softening of *t* into *d*, is quite satisfactory. The object of this immunity would thus be to deny to the representatives of the king the right of digging pits for extracting salt.

¹ [Compare above, Vol. VI. p. 88, note 10.—E. H.]

The next term seems to be written in our inscriptions *arathasavinayika* or *°savinavika*; but l. 32 of the grant of Śivaskandavarman (*Ep. Ind.* Vol. I. p. 6) distinctly reads *aratthasavinayikam*. In stating that this spelling excluded his earlier explanation, Bühler did not suggest another instead of it. I do not know any parallel expression which clears up this one finally. The word seems to represent *arāṣṭrasaṁvinayika*; but etymology alone is an unsafe guide in the interpretation of technical terms. *Vineti* is only used in a moral sense. Could we think of translating: "exempted from the police, the magistrate of the district (*rāṣṭra*; compare Dr. Fleet's *Gupta Inscriptions*, p. 32, note), or of the *rāṣṭrin*?" This would remind us of those grants in which, on the other hand, it is stated that the right of punishing thefts and offences is reserved to the king, or of those in which the right to punish the 'ten offences' ¹ is transferred to the donee. At least I have nothing more plausible to suggest. It is well known that the different formulas of immunities were variable and always incomplete. And it is not to be wondered at that they should be summed up in a comprehensive and general expression like *survajātapārihārika*. Elsewhere, the texts are more precise in stating that there are eighteen kinds of immunities. It will be enough to quote the inscriptions of the Pallavas, and notably that of Śivaskandavarman, which reads *aṭṭhārasajātiparihāra* (*Ep. Ind.* Vol. I. p. 6).

More clearly still than our estampage, those of Nāsik Nos. 3 and 4 appear to exclude the reading *pariharimha* and to recommend the first singular *pariharehiṁ*. We thus obtain an exact counterpart of the expression employed for the grant of the village. The king begins by announcing his intention of granting: *dadāma* and *vitaraṁa* in the first plural. Then he sums up the donation in the first singular: *pāpehiṁ*, *pariharehiṁ*.

The reading *nibaddhāpekhi[m]* seems to be established incontestably by the comparison of *nibaddhāpekha* in Nāsik No. 5. The approximate meaning of this word is not doubtful. *Nibandha* is a technical term meaning 'endowment'; see Yājñavalkya, I. 317: *dattvā bhūmim nibandhan nū kṛtvā lēkhyam tu kārayēt*. Hence the corresponding use of the verb *nibaddh*. In Nāsik No. 5, we shall actually find *nibaddhō nibandhaḥ*; this sentence is accompanied by a separate date which is several months prior to the date of the grant. Hence *nibandha* refers to a distinct official formality which precedes the completion of the grant. I do not know in what it exactly consisted; perhaps it was a kind of registration of the royal decision in the archives of the State. The four corresponding passages of this portion here and in Nāsik Nos. 3, 4 and 5 seem to read,—

Kārlē No. 19: *eta[m] chasa gāma Karajake bhikkhulaparihāre cha.*

Nāsik „ 3: *eta[m] cha gāma Samalipada[m] parihāre cha.*

„ „ 4: *et[e] chasa khetaparihāre cha.*

„ „ 5: *eta[m] chasa khetaparihāre cha.*

In spite of the comparative uncertainty as to details, which the condition of the stone almost always entails, it follows from a comparison of these quotations that the correct reading is *etaṁ*, not *ete*. This is supported also by the accusatives *gāma Karajake* and *gāma Samalipadam* to which the pronoun refers, and by the following two cases where *etaṁ* is connected with *khetaparihāre* by the double *cha* and hence can be nothing but an accusative, with which either *khetam* is to be supplied or which sums up the principal object of the grant in a general fashion. As regards the wording of the phrase, the point in which the four versions differ most obviously is the absence of the syllable *sa* after the first *cha* in Nāsik No. 3. At first thought we might feel inclined to resolve everywhere *chasa* into *cha asya*, as it has to be done for instance in Nāsik No. 6, ll. 2 and 3 (compare Kārlē No. 20, l. 4). The same is just possible in l. 3 of our inscription (*etasa chasa gāmasa*) and in l. 3 of Nāsik No. 4 (*etasa chasa khetasa*), where the tautology *ētasya asya* is admissible. But this analysis is not possible either here or in Nāsik No. 4, l. 5,² and

¹ *Sadasāpardāha*; see e.g. the Alinā plates, l. 67, in Dr. Fleet's *Gupta Inscriptions*, p. 179, and the Dēś-Bārāṇṣī inscription, l. 17, *ibid.* p. 217.

No. 5. Though the syllable *sa* is wanting in Nāsik No. 3,—which seems to imply that the addition is at least redundant,—we cannot well consider such a frequent repetition as a material error. Bühler also was surprised at this expression in Nāsik No. 5 (p. 104, note) and suggested that “the *sa* is purely pleonastic, just as in Pāli *sacche*, ‘if,’ and similar words.” He thought evidently of *sayadi* and *sayyathā* of the Buddhist Sanskrit and of Pāli. I cannot see what “pleonastic” means here; perhaps he wanted to say ‘expletive.’ But it seems to me difficult to assimilate, without positive proof, a prothetical particle to an enclitical one, which we are obliged to admit here. I can discover only a single expedient, viz. to take *sa* = *syā* = *syid*, as in the language of the *Mahāvastu*; see my edition, Vol. I. p. 412. In the expression *trayāṣaṣṭhi* which I have quoted, as well as in the Pāli *tayassu*, the particle seems to imply a shade of doubt which would be inadmissible here; but I do not know any other example of its use after *cha*.

Bühler happily explained *aviyena* by a reference to Hémachandra, who gives *aviyā* as a synonym of *ukta*. This is the equivalent of the formula *svamukhijñā*, etc., of later inscriptions; see Dr. Fleet's *Gupta Inscriptions*, p. 100, note. I do not believe that Bühler was equally successful with regard to *chhata*. His interpretation rested on the supposed parallelism of *chhata* in Nāsik No. 5; but as this inscription actually reads *chhata*, his argument loses its support. Besides, I cannot persuade myself that the king required the ‘permission’ of a subordinate officer (*amacha*) for making his grants valid, and even that *chhanta* could really be used in this way. As regards the guess of Bhagwanlal, according to whom *chhata* stands probably for the Sanskrit *chhupta*, meaning ‘touched,’ neither is it admissible phonetically nor is it corroborated by the analogies which he invoked (*Bombay Gazetteer*, Vol. XVI. p. 558, note). The operations and formalities connected with royal grants which our inscriptions record (Kārlē No. 19, and Nāsik Nos. 3, 4 and 5) are characterised by the terms *āyata* and *chhata* (in all four), *darā paṭikā* (in three of them, but not in Nāsik No. 5), *kafā* (here and in Nāsik No. 5) and *uparakṣita* (Nāsik No. 4), the equivalent of which I believe to find in Nāsik No. 3. The later inscriptions offer us a large quantity of probable or at least possible equivalents. I need not dwell on *āyata*, the meaning of which is clear; it refers to the announcement of the royal order either by the sovereign himself, or by his representative who is generally delegated to this duty by the title of *dātaka*; see Dr. Fleet's *Gupta Inscriptions*, Index, s. v. Besides, frequent mention is made of the manual drafting of the document (*likhita*) and of its transcription on copper or on stone, expressed by *utkirṣa*; see Dr. Fleet's *Gupta Inscriptions*, p. 99, note. In the grant of Śivaskandavarman (*Ep. Ind.* Vol. I. p. 7, text line 50) we read *Bhaṭṭisanmaza sahatthalikhitaṇa paṭikā kada=tti*. The participle *kr̥ta* refers here to the drafting, as the writing is expressed by *likhita*, while in our inscriptions *kafā*, which ends the text and whose agent, being always named without any title, is evidently a subordinate officer, clearly corresponds to *utkirṣa*; compare the end of No. 35 of Dr. Fleet's *Gupta Inscriptions*. Besides, I believe that in our documents this ‘engraving’ does not mean the preparation of the stone, but that of the copper-plates which served as title-deeds to the donees, and of which our epigraphs only state the delivery. Several documents mention a keeper of records (*ākṣhapāṭalika* or *ākṣhaśālaka*), who consequently must have been in charge of the documents. I believe that such an officer was Rohaṇi—for, Rohaṇi-guttā=ti must be read—who is mentioned at the end of the grant of Vijayabuddhavarman (*Ind. Ant.* Vol. IX. p. 102).¹ In this connection we have to understand the word *uparakṣita* in Nāsik Nos. 3 and 4. If it is not admitted that our *chhata* corresponds to the *likhita* of the traditional formulas, it would lead us to the paradoxical conclusion that the operation which is nowhere wanting in the known protocol is the only one of which there is no trace in our own inscription, and on the other hand that the only operation which is common to our four documents is just the only one unknown to the later redactions. What would be a conjecture, though very probable to

¹ [Monsieur Senart's improved reading is no doubt correct; but I would prefer to translate:—“The *djūṣṭi* (or *dātaka*) was Rohaṇigupta.”—E. H.]

my mind, is raised to a certainty by Nāsik No. 5, where we read *chhato lekho*. *Chhata* would thus correspond to *kshata* from the root *kshan*. It is quite true that *kshan* ordinarily means only 'to hurt;' but this meaning rests on the primary signification 'to hollow out,' which is also attested for the form *khan* and is altogether quite analogous to the primary and essential meaning of *likh*. Why is the word *likh*, consecrated as it is by old custom, replaced in our texts by this equivalent? I have no means to explain this; but the fact cannot be denied, I think. I can at least quote cases where *khanati* is employed as an equivalent of *likhati* with reference to the engraving of a *tāmrapaṭṭa*; see the inscription of Madanapāla in the *J. As. Soc. Beng.* 1900, p. 73. I do not venture to assert that our *chhata* is only a graphical variant of *khata* = *khanita*. At any rate, the close relation which exists between the two roots *khan* and *kshan* renders this explanation possible.

The characters which follow *chhato*, namely *vijayaṭhasatāre*, are perfectly certain, except that the *ṭh* may be accompanied by an *e*, and except the last letter, which I would decidedly read *kh* because of the curve at the bottom, if the hook at the top were a little more rounded. As it is, the reading *khe* seems to me just as possible as the reading *re*. Is it at all probable that, as Bühler thought (p. 112, note, and compare p. 105, note), we have here a triple error of the scribe for *vijayakha[n]dhāḍāre*? This designation of the residence of a king is indeed well-known; but, putting aside the fact that such a conjecture is a little violent, one would wonder that such a camp is here, contrary to usage and to what we find in Nāsik No. 4, not determined by any topographical name. Should we look for such a name in the very indistinct characters following *dato*? As may be seen, they are far too doubtful to guide us by themselves; but *a priori* the interposition of *dato* between *vijayakhamdhāḍāre* and the name of the locality, whatever it could be, renders that hypothesis very suspicious.

If we stick to the apparent reading *vijayaṭhe satākhe* (or *re*), we are again obliged to embark on an ocean of conjectures fertile in shipwrecks. Here two comparisons suggest themselves, which are curious, but at the same time perhaps not very safe. *Satāre* (or perhaps *sātāre*) reminds of the well-known town and district of Sātārā on the south of Kārlē. It is true that the name Sātārā has not yet been discovered in any document of ancient date (*Bombay Gazetteer*, Vol. XIX. p. 224); but this may be simply accidental. Besides, it is not very probable—whatever the original form of the name may be—that it should have already assumed the form Sātārā in the time to which our inscriptions carry us back. At least it ought to have begun with *Sāta*, whatever this means, and *Sātākhyā* as the designation of 'a town whose name commences with *Sāta*' would not be without analogies. On the other hand *vijayaṭhe*, i.e., without doubt, *vijayasthē*, 'situated in my territory' or 'in the province called Vijaya,' reminds of the name of Vaijayanṭi, which we have already found applied to the town that has since received the name Banavāsi, and which occurs again in Nāsik No. 4. The very peculiar manner in which this inscription introduces the word *senāye* suggests that we might have here a name given by virtue of a recent conquest to these southern territories, where the district of Sātārā occupies an intermediate position between Kārlē and Banavāsi. If this conjecture had any foundation, we should feel inclined to attribute this grant not to Vāsishṭhīputra Puṣumāyi, but to Gautamīputra Sātakarpi, to whose reign Nāsik No. 4 belongs. Of course I am aware of the fragility of this assumption. As for the characters following *dato*, the reading *ṭheraṇā* is, with reference to the two last letters, as improbable as the evidently desperate analysis of the word, which Bühler suggested. The first letter might be *ṭhe*, but could also be *ve*. The comparison of Nāsik No. 4 suggests *Bendakaṭā* or *Bendakaṭāḍā*; but the place which *dato* occupies does not lead us to expect a topographical name, and I may add that the remaining traces would be little favourable to this restoration.

The figure '4' of the number '14' is hardly possible; I would rather think of a '5.' But in fact the only point which is beyond doubt, is, that the year must fall between '11' and '19.'

One cannot help remarking the similarity of the names of several officers who are employed here and at Nāsik by Vāsishṭhīputra Puṣumāyi and Gautamīputra Sātakarpi. In Nāsik No. 3

Śivaskanda is the governor of the district; in Nāsik No. 4 the *amātya* Śivagupta writes the grant; and here Śivaskandagupta engraves the document on copper. The simultaneous occurrence of names into the composition of which Vishṇu enters prevents us from drawing from this fact hasty conclusions regarding the state of the sects in this region. Could these resemblances be the result of relationship?

I must not fail to recall the link which seems to connect this inscription with No. 13, to the commentary of which the reader is referred. I will only add that, renewed by a royal personage, the grant of the village of Karajaka was necessarily accompanied by fiscal and administrative privileges which, in spite of his high connections, Rishabhadata had been doubtlessly unable to confer.¹

No. 20, Plate iii. (Ksh. 21).

North of the *chaitya* cave. On the wall of the second cell (from the south) of a *vihāra*, right of entrance, top.

TEXT.

- 1 Sidha (1) rañño (2) Vāsīṭhiputasa Sirī-Puḷumāvisa savachhare chatuvisē 24
hemamāna pakhe (3) tatiye 3 divase bi-
2 tiye 2 upāsakasa Harapharaṇasa Setapharaṇa-puttasya So[va]sakasya Abulāmāya
vathavasya ima deydhamā maḍapo (4)
3 navagabha (5) Māhāsaghiyānaṁ (6) parigaho (7) saghe chātudise dina . (8)
mātāpitunam puḍā (9) savasatānaṁ hitasughasthataye (10) ekavise (11) sa-
4 vachhare niṭhito saheta (12) cha me puna Budharakhitena mātara chasya (13)
. . upāsikāya (14) Budharakhitasa māt[u deya]dhamma (15) [pāṭho] a[no] (16).

REMARKS.

(1) CTI. *sidham*.—(2) AS. *raño*.—(3) CTI. and AS. *hematū°*.—(4) AS. and CTI. *maḍapo*. The *ḍa* is not absolutely perfect, but at least probable, which cannot be said of the *ṭa*.—(5) The *bh* has a vertical stroke at the top, which is so pronounced that I am doubtful if we ought not to read °*garbha*, with which the Sanskritisms °*puttasya* and °*Savasakasya* would have to be compared.—(6) AS. °*ghiyāna*.—(7) AS. and CTI. *parigaho*; the *ho* seems to me certain.—(8) CTI. *chatudise dinam mā°*. After *na* there is certainly room for a character, but no positive trace of it which would show that it did really exist.—(9) AS. and CTI. °*pituna pūḍā*. The tail of the subscribed *u* of *pu* seems to be a little more pronounced here than in the rest of the inscription. But our engraver was so fond of this flourish that, in the absence of any additional trace on the right, we are not authorised to attribute a special phonetical value to such an imperceptible differentiation.—(10) CTI. °*sṭhataya*, AS. °*sṭhataya*. The *th* and the final *e* are much more distinct in the estampage than they appear in the Plate.—(11) CTI. *ekavisa*;

¹ Together with the proofs of this article, I received from Dr. Hultzsch a proof of his paper on the newly discovered Konḍamudi plates (above, Vol. VI. No. 31), which throw fresh light on some doubtful points in Kārlē No. 19. In pointing out several of these corrections, Dr. Hultzsch has quoted my present article. It is consequently too late to modify my remarks, and it will be enough at present to draw attention to the principal corrections which the new plates suggest.—(1) The reading *oyapḍepēhi*, instead of *deya pḍepēhi*; (2) the explanation of this verb, as well as of *pariharehi* and *nibaddhāpēhi*, not as 1st singular aorist (with alteration of final °*hi* into °*hiṁ*), but as 2nd singular imperative. (3) The proposed interpretation of *vijayathasatdḥke* ought surely to be given up; but I do not consider the general meaning attributed to the phrase by Dr. Hultzsch as altogether satisfactory. (4) Nor do I consider his translation of *chhata* by 'signed' beyond every doubt, although the word is here accompanied by *suḥsṁ*. (5) The reading *etamsi tam* in l. 25 of the Konḍamudi plates suggests a similar correction for *etasa[m] tu* in l. 3 of Kārlē No. 19. But such a correction, at least so far as the second syllable is concerned, would be opposed to the apparent testimony of the estampage. Anyhow, my forthcoming article on the Nāsik inscriptions will give me an opportunity for returning to several of these difficult points.

AS. *ekatise*. The *v* is not doubtful; the *t* and the *v* differ in the alphabet of this inscription in a quite distinct manner.—(12) CTL. *sahata*. I cannot vouch for the *s*; the third letter is not a very clear *t*, but can hardly be interpreted differently.—(13) The reading proposed by AS., *Mātarakhīd*, cannot be upheld; but after the group *syā* there is room for two characters, the first of which seems to have left remnants that might be interpreted easily as *d*.—(14) The *kā* is very indistinct.—(15) CTL. and AS. °*dhama*.—(16) The character read *pho* remains doubtful; if, as it would appear, the next following letter is really an initial *a*, there is hardly room for *ph* between this *a* and the preceding *p*, and we are obliged to suppose its being reduced to minute proportions. As to the letter *n*, I can say that it is visible in the estampage, especially on the back of it, though not in the Plate.


TRANSLATION.

“Success! On the second—2nd—day of the third—3rd—fortnight of winter in the twenty-fourth—24th—year of king Siri-Puṣumāvi, son of Vāsithi, this pious gift of the lay-worshipper Harapharaṇa, son of Setapharaṇa, a Sovasaka, living in Abulāmā, (*viz.*) a nine-celled hall, has been given to the universal Saṅgha, as special property of the Mahāsāṅghikas, in honour of his parents and for securing the welfare and happiness of all beings. In the twenty-first year it had been completed and to me by Budharakhita and his mother, a lay-worshipper. The a pious gift of Budharakhita's mother.”

As regards the proper names, I have nothing to add to Bühler's commentary. One can see from Fergusson and Burgess's *Rock-cut Temples*, p. 241, that the excavation where this inscription was found is really a hall flanked by nine cells. I have said that I would rather read *parigaḥo* than *pariguho*. I am aware that an exactly similar passage which has to be compared with ours, in l. 12 of the inscription of Tōramāṇa at Kura (*Ep. Ind.* Vol. I. p. 240), to which I have alluded before (No. 13), seems to read certainly: *ayam puna viḥārasyōpakaraṇa chāturdśś bhikṣu-saṅghē parigrāhē dhārryamahāsāsakānām*. Whatever the true reading may be, only one interpretation of the general sense is to my opinion possible. That of Bühler is not acceptable. He took *parigrāha* to mean ‘circle, group,’ and took the adherents of the school of the Mahāsāṅghikas to be opposed to the *chāturdśśa bhikṣusaṅgha*, though in his commentary on the Kura inscription he recognised that *parigrāha* can only mean ‘possession, property,’ and that the ‘universal Saṅgha’ can only be understood in antithesis to the special sect of the Mahāsāṅghikas. We have already seen that certain grants seem to stipulate that gifts attributed to particular sects should be meant for monks of every origin and of every denomination without distinction; compare No. 13, l. 4. Whether we take, as basis, the nominative in translating “has been given as property of the Mahāsāṅghikas,” or the locative in rendering “has been given into the possession of the Mahāsāṅghikas,” both versions come to the same. We shall find a very similar sentence repeated twice in Nāsik No. 3. I shall there return to this subject, because the two groups of passages seem to explain each other.


With *ekavise* the obscurities begin. Bühler has clearly ‘thrown the haft after the blade;’ still it is easier to condemn his evidently provisional attempt at interpretation than to replace it by a more probable one. I do not pretend to solve the difficulty, but would submit some observations with the desire that they may be of service to some more fortunate interpreter. The difficulty consists chiefly in two points: the word which I transcribe *saheta*, and the four last characters which are read *pāṭho ano*. As regards *saha*—(the *s*, as I have said, is not sure),—one feels tempted (considering that many other inscriptions at the end of a grant introduce the dependents of the chief donor as having joined him in the donation) to expect an enumeration of relatives taking part in the pious work of Harapharaṇa. But the characters which separate *ha* from *Budharakhitena* do not furnish the epithet of relationship which that hypothesis would require, and with the exception of the vowels the reading, especially of the three last letters, seems quite

1




SCALE .08

8




SCALE .125

5




SCALE .1

9




SCALE .125

18



SCALE .17

20



SCALE .125



A



B



FULL-SIZE



Collotype by H

E. HULTZSCH.

clear. That of the two first, *tacha*, is at least very probable. The *cha*, then, invites us almost irresistibly to join *sahata* and to find in it some participle co-ordinate with *nīṭhito*. Unfortunately, none of the restorations which suggest themselves,—*sakito*, *samhito* and *samhato*,—furnish us a decisive meaning, or a construction with which the following word *me* could be easily connected. Further, to which substantive do *nīṭhito* and the other hypothetical participle refer? Apparently to the *maṇḍapa* whose donation is mentioned before. With *Budharakhīṭasa* a new sentence must begin; it would be contrary to all the habits of the style of these epigraphs that the object of the donation, before being mentioned, should be enveloped in such long circumlocution. Perhaps we should see clearer if this object were well defined, which unfortunately it is not. I have noted it elsewhere only in a single case at Kuṭā (No. 31 of CTI. and No. 28 of AS.), where we seem to read *pāṭho deyo*. If any point is certain, it is that there as well as here the dental *th* is excluded. This circumstance alone would suffice to condemn the translation 'passage,' proposed by Bhagwanlal and adopted, without conviction, by Bühler. I have no more probable conjecture to substitute for it. Whatever the meaning is, we seem to be confronted by the same term at Kuṭā and here. Now, at Kuṭā the part of the sentence in question begins with the characters *saha*, which seem to be followed immediately by the characters *tasu* at the beginning of the next line. Neither the testimony of the editors nor the *fac-similes* enable us to decide whether the break between the second *sa* and the initial *pā* of *pāṭho* is real or only apparent. In any case, one cannot help comparing this instance with our *sahata* or *saheta*, and consequently asking whether here also this word opens the sentence of which *pāṭho* is the subject, while *īkaviṃśa samvachhare nīṭhito* would refer only to *maṇḍapo*. I have stated why *a priori* a full stop seems to be indicated before *Budharakhīṭasa*; without being absolute, this objection seems to me much stronger than the coincidence which I have just quoted against it, and which is extremely vague and perhaps altogether illusory. Another doubtful point has to be referred to. Between the letter which Bühler transcribes *d*, while I read *syā* in accordance with Bhagwanlal, and the *pā* of *pāsi-kāya*, there is room for three characters; but the previous editors read simply *u* without admitting a break. They seem to interpret thus the character which follows the group *syā*. Hence they must have assumed that the distinct traces immediately before *pā* are not the remains of a letter, probably of an *u*, but accidental flaws in the stone. An inspection of the original could alone decide if another character has disappeared. The distance between the letters certainly suggests this, and it is *a priori* probable that the title *upāsikā*, attributed to Budharakhita's mother, should be accompanied by her name as in other cases. Thus I incline towards believing that the letter which comes after *syā*, and which may be *d* or *u*, formed the first syllable of this name, the second syllable of which is lost in the break, and that the traces which follow represent the initial *u* of *upāsikā*.

No. 21, Plate iv. (K. 18).

North of the *chaitya* cave. On two sides of a semicircular cistern in a *viḥāra*.

TEXT.

- | | | |
|-------------|--|-----------------------|
| 1 | (1) 5 hematāṇaṃ pa . e (2) | ya purāya bhayata (3) |
| 2 | hiṇa atevāsiniṇa leṇaṃ (4) bhagi | kāṇa (5) |
| sadigā | | |
| 3 | kale (6) pavaṭṭāṇa saṃghāya bu | dhama (7) poḍhi |
| 4 | (8) | |
| 5 | atevāsinihi (9) | |

REMARKS.

(1) CTI. and AS. supply *savachhare*, which is not doubtful, but of which only the last character has left any traces.—(2) CTI. and AS. *hematāṇa pakhe*. The *kh* is not doubtful, but

cannot say that I discover any remains of it.—(3) CTI. and AS. *dha[bha]yata*. I recognise the outline of a *bh* rather than of a *dh*, and everybody agrees that *bha* is the necessary reading.—(4) CTI. and AS. *lena*.—(5) CTI. and AS. *bhagine* *sāvikaṇa*.—(6) CTI. and AS. *ghasu kile*.—(7) CTI. and AS. *cha deyaḍhama*.—(8) CTI. and AS. *parivāraṇa upaya* —(9) CTI. and AS. *nhi Usabhāe*

It will be seen that the new *fac-simile*, far from completing the fragmentary text of this epigraph, only shows the more advanced deterioration of the stone. Consequently, still less than my predecessors am I able to offer even an approximate translation. It is clear that the inscription commemorated the donation of a cistern, made, it seems, by nuns, and that the date referred to the winter of the 5th year of some sovereign. But it is not at all certain whether the term *sāvika* is applied to the female donor or to one of the nuns, and still less whether it has the meaning 'lay-worshipper,' as in the terminology of the Jains.

No. 22, Plate iv. (K. 17).

One furlong south of the *chaitya* cave. On the front wall of a *vilāra*, left of entrance, top.

TEXT.

Sidham (1) pavaṭṭasa (2) Budharakhitasa deyaḍham (3)

REMARKS.

(1) CTI. and AS. *sidha*.—(2) CTI. and AS. *pavaṭṭasa*.—(3) CTI. *deyaḍhama*; AS. *deyaḍhamam*. The truth is that the end of the line is indistinct, with the exception of the upper portion of the *m*.

TRANSLATION.

"Success! The pious gift of the ascetic Budharakhita."

I cannot explain the transcription *pavaṭṭasa* otherwise than as a mistake. This Budharakhita is probably the same as the person mentioned in No. 20.

No. 8.—DEVULAPALLI PLATES OF IMMADI-NRISIMHA;

SAKA-SAMVAT 1427.

By J. RAMAYYA B.A., B.L.

As noticed in Mr. Sewell's *Lists of Antiquities*, Vol. I. p. 134, these plates are preserved at Devulapalli in the Vāyalpāḍu taluka of the Cuddapah district. At my request Mr. A. Krishna-svami Nayudu, B.A., Acting Tahsildar of Vāyalpāḍu, obtained a loan of the original plates and forwarded them to Dr. Hultsch, who has kindly furnished me with a set of ink-impressions, from which I edit the inscription.

Dr. Hultsch has supplied the following information regarding the original plates:—"Three copper-plates with rounded tops; 11" in height and about 6½" in breadth; strung on a ring which is not soldered and which measures 4" in diameter and ½" in thickness. On the ring is soldered a rectangular seal which measures 1½" by 1" and bears, in relief on a countersunk surface, a standing boar which faces the proper left. In front of the boar is a dagger, and above the boar the sun and a crescent."


Karle Inscriptions. — Plate IV.

2




SCALE .06

6




SCALE .125

21



SCALE .125

22



SCALE .1

Collotype by Rössner & Jonas, Dresden.

E. HULTZSCH.

The language of the inscription is Sanskrit poetry, with the exception of a few words in Sanskrit prose in lines 1 and 77 f., and the alphabet is Nāgarī of the Vijayanagara type.¹ The very last word, *śrī-Rāmachandra* (l. 78), which stands for the signature, is in Telugu characters.

The inscription records that Immaḍi-Nṛisimha (ll. 39 and 46 f.), son of Nṛisimharāya (ll. 22 f. and 46), granted to a Brāhmaṇa the village of Dēvulapalli (l. 67 f.) in the Mārjavāḍa-siman² (l. 65) of the Penugoṇḍa-mahārājya³ (l. 64). Dēvulapalli, which is identical with the modern village of that name in the Vāyalpāḍu tāluka of the Cuddapah district, is said, in the inscription, to have been situated within the limits of the village of Guṇḍūru⁴ (l. 65), south-east of Sūrināyani-Muṣṭūru (l. 66), and north of Aḍavi-Muṣṭūru (l. 67). Mr. Krishnaswami Nayudu informs me that Sūrināyani-Muṣṭūru is now called Errakōṭapalli in the public accounts, while popularly it is known as Muṣṭūru without any prefix, and that Aḍavi-Muṣṭūru is now known as Kōṇa, though it is sometimes called also Kōṇa-Muṣṭūru. He also tells me that Dēvulapalli is no longer an *agrahāra*.

The plates have been borrowed from Dēvulapalli Veṅkaṭaramaṇappa, who is said to be a lineal descendant of the donee. It is said that the original name of the family was Vyālapāṭi,⁵ that it was given up in favour of Bollapini, which, in course of time, became corrupted into Gollapini, and that finally the family adopted the name of Dēvulapalli, which is the name of the village where it is living to this day.

The occasion for the grant was a lunar eclipse which occurred on Sunday, the full-moon *tithi* of Bhādrapada in the cyclic year Raktākshin and Śaka-Saṃvat 1427 (in numerical words) (v. 32 f.). This date corresponds to Sunday, the 25th August A.D. 1504, on which day there was a lunar eclipse.⁶

Historically the inscription is of great value, as it relates to a line of chiefs who exercised considerable authority on the east coast of Southern India in the 15th century of the Christian era, and one of whom, the donor's father Nṛisimharāya, was the principal actor in the drama which involved the overthrow of the first dynasty of the Kārṇāṭa or Vijayanagara empire. Little or nothing has been hitherto published concerning these chiefs, whom I would call Śāḷva⁷ chiefs. I have compiled the following genealogy from the information furnished by this inscription and by the Telugu poems *Jaimini-Bhāratam* and *Varāhapurāṇam*. The former book was dedicated to Immaḍi-Nṛisimha's father Nṛisimharāya, also called Narasiṅgarāya,⁸ and the latter to Nṛisimharāya's general Narasiṃha of the Tuḷu family, who afterwards became the founder of one of the dynasties of the Vijayanagara empire. The *Jaimini-Bhāratam* has been printed, and my references are to the Madras edition of 1893. The *Varāhapurāṇam* has not been printed, but manuscript copies of it are extant. I quote from a copy made for me from the manuscript available in

¹ [It deserves to be noted that the rare letter *jha* occurs in l. 50; that the aspiration of *pha* is expressed by a hook at the top of the line (ll. 4, 5 and 75); and that the *virāma* after *t* (ll. 17, 25, 30, 34, 38 and 75) and *n* (ll. 26, 29, 31, 44 and 70) is added to the right of the letter.—E. H.]

² [Regarding this district, the head-quarters of which was Vallūru near Cuddapah, see *South-Ind. Inscr.* Vol. III. p. 106, and above, Vol. V. p. 206.—E. H.]

³ [The province (*rājya*) of Penugoṇḍa or Penugoṇḍa is mentioned above, Vol. III. No. 34 (vv. 19 and 32), and Vol. VI. p. 327 and note 2.—E. H.]

⁴ According to Mr. Sewell's *Lists of Antiquities*, Vol. I. p. 134, this is a village 13 miles north-north-east of Vāyalpāḍu.

⁵ [This is evidently the same as Vyālapāṭipura (the modern Vāyalpāḍu), which was the residence of the donee's great-great-grandfather according to l. 49 of these plates.—E. H.]

⁶ According to Prof. Kielhorn it was "a total eclipse of the moon, visible in India, from 13 h. 43 m. to 17 h. 13 m. after mean sunrise."

⁷ The title *Śāḷva* occurs in ll. 14, 15, 24 and 26 of these plates.

⁸ He is styled *Narasiṅga* or *Narasiṃha* indiscriminately, but I prefer to call him Nṛisimharāya as in the inscription, in order to distinguish him easily from his general Narasiṃha.

the Government Library of Oriental Manuscripts, Madras.¹ The *Vardhapurāṇam* gives the names of only those persons who are in the direct line of descent, and the names of the collaterals are taken from the *Jaimini-Bhāratam* and the inscription. The Sāluva family traces its descent from Yadu and is hence called Yādava-vamśa. The earliest historical person mentioned is Vaṅkidēva, who is referred to in the *Vardhapurāṇam* only. Vaṅki's son was Guṇḍa.² Guṇḍa had six sons,³ of whom Maṅgu or Sāluva-Maṅgu⁴ was the greatest. The *Jaimini-Bhāratam* is very eloquent in its praises of this person and says that, among other things, he gained success for Sāmparāya in his battles with the "Sultān of the South" and thereby earned the title of "the establisher of Sāmparāya," that he founded (the temple of) the god Śrīraṅga and gave sixty thousand *māḍas* (half-pagodas) for the expenses of the temple, and that he killed (in battle) the "Sultān of Madhurā."⁵

In the temple at Simhāchalam in the Vizagapatam district there is an inscription dated in the Śaka year 1350. It records that Teluṅgurāya, son of Samburāya of Kannaḍa-dēśa, delivered into the possession of two shepherds one hundred cows for the maintenance of two perpetual lights (*akhaṇḍa-dīpa*) in the temple, and that he gave the shepherds a *putti* of land in the village Vaḍḍadi in lieu of wages. There is another inscription of Teluṅgurāya, also dated in the Śaka year 1350, at Santarāvūru in the Bāpaṭla tāluka of the Kistna district, in which the king is described as the "*Mahāmaṇḍalēśvara Misaragaṇḍa Kaṭhāri Sāluva Teluṅgurāya*."⁶ Rao Bahadur K. Viresalingam Pantulugaru quotes a verse of the poet Śrīnātha (who lived about this time), in which the poet laments the death of several of his patrons including Teluṅgurāya⁷ and there is another verse which is attributed to the same poet and which ends in the words *Sāmparāyani Teluṅḡ nīku dirgh-āyuvam*: "O Teluṅga, (son) of Sāmparāya! May you be blessed with long life!" There seems no doubt that the king or prince Teluṅgu mentioned in the above-quoted inscriptions was one and the same, and if his father Sāmparāya *alias* Samburāya is identical with the Sāmparāya of the *Jaimini-Bhāratam*, he would appear to have belonged to the same Sāluva family as Maṅgu—apparently to a senior branch of it. It would appear also that the sovereignty, which was originally in the senior branch of the family, subsequently passed on to the junior branch to which Maṅgu belonged, though we do not know at present how and when this change took place. The "Sultān of the South" who was at war with Sāmparāya was, no doubt, the Bahmani king, and by the "Sultān of Madhurā" we should, I think, understand the Pāṇḍya king,⁸ the temple of Śrīraṅgam which Maṅgu built is evidently the celebrated temple in Śrīraṅgapattana in the Mysore country.

Maṅgu had six sons, of whom one was Gauta,⁹ who had four sons: Guṇḍa,¹⁰ Sāluva, Boppa and Tippa. The *Jaimini-Bhāratam* devotes a couple of verses to the eulogy of Tippa,¹¹ who appears to have been a great warrior, and to whom are applied the birudas of Misaragaṇḍa, Kaṭhāri, Sāluva and Pañchaghantānināda—titles which are ascribed to Nṛsiṁharāya in the subjoined inscription (vv. 13 and 16). An inscription at Tēkal in the Mysore territory makes mention of a certain Gōparāja, son of Sāluva-Tipparāja-Oḍeyar, to whom the village of

¹ The author of the *Vardhapurāṇam* gives the genealogy of his patrūn Narasimha, which tallies with the published genealogy of that family, and he also gives the genealogy of Narasimha's master Sāluva-Nṛsiṁharāya.

² See v. 6 of the Dēvulapalli plates.

³ See v. 7 f. of the same plates.

⁴ He is called Sāluva-Maṅgi in vv. 8 and 9 of the same plates.

⁵ *Jaimini-Bhāratam*, p. 4.

⁶ Mr. Sewell's *List of Antiquities*, Vol. I, p. 84.

⁷ *Lies of Telugu Poets* (edition of 1895), Part I, p. 114.

⁸ [This reference may as well be to one of the Musalmān rulers of Madhurā, on whom see above, Vol. VI, p. 334 and note C.—E. H.]

⁹ See v. 10 of the Dēvulapalli plates.

¹⁰ See v. 11 of the same plates.

¹¹ [A certain Gōpa-Tippa-nṛpati is mentioned in an undated Grantha inscription at Śendalai (No. 56 of 1897), and an inscription of Gōpa-Tippa-nahipati at Rāmēśvaram appears to be dated in Śaka-Samvat 1390 Burgess and Natesa Sastri's *Tamil and Sanskrit Inscriptions*, p. 59, No. 11, where I would correct नञ्जयै (which the translator calls "very bad Sanskrit" because he does not understand it) into नञ्जयै, i.e. 1390.—E. H.]

Tēkal was given under the orders of Dēvarāya-mahārāya of Vijayanagara. Goparāja is called a *Mahāmaṇḍalēśvara* and the "setter-up of Ganga Hale Sambā Rāya."¹ The copy of the inscription from which the translation was made appears to have been so imperfect that no safe conclusions can be drawn from it. But a thorough examination of this inscription seems likely to throw some light on the history of the Sāluva chiefs. Tippa's eldest brother Guṇḍa had, by his wife Mallāmbā, two sons: Timma² and Nṛsiṃharāya,³ and Nṛsiṃharāya had, by his wife Śriraṅgamāmbā,⁴ a son named Immaḍi-Nṛsiṃha or Nṛsiṃha II.

From all accounts Nṛsiṃharāya appears to have been a very powerful prince. Both according to Ferishta and the author of the *Burhān-i Ma'āsir* he was the most powerful prince in all Karnāṭa and Teliṅgāna and owned extensive territories on the east coast right up to Masulipatam. According to the latter authority Nṛsiṃharāya was constantly at war with the Bahmani king Muḥammad II. They met first at Rājamahēndri, "on the further side of which the infidel Narasiṃharāya with 700,000 cursed infantry and 500 elephants like mountains of iron had taken his stand."⁵ No battle took place, however, as Nṛsiṃharāya is said to have taken to flight on the arrival of the Sultān's army. This was probably in the year 1479 A.D. Next year they seem to have met again at Koṇḍaviḍu, the people of which, "throwing themselves on the protection of Narasiṃharāya, had altogether withdrawn from their allegiance to the rule of Islām." After quelling this rebellion, the Sultān marched against the kingdom of Nṛsiṃharāya, because "the destruction of the infidels was an object much to be desired: and as the infidel Narasiṃha who, owing to his numerous army and the extent of his dominions, was the greatest and most powerful of all the rulers of Teliṅgāna and Vijayanagar, had latterly shown delay and remissness in proving his sincerity towards the royal court by sending presents and *nul-bahū* (money given to foreign troops to abstain from plunder and devastation)."⁶ The Sultān laid siege to the fort of Mālūr (in the Mysore territory), "the greatest of the forts of that country," and was ultimately bought off with valuable presents of jewellery and other valuables, elephants and horses, and with a confession by Nṛsiṃharāya of his weakness and a promise of obedience and submission. This did not, however, prevent the Sultān from straightway marching against Kāñchī, "situated in the centre of the dominions of that malignant one" (Nṛsiṃharāya), and sacking the town and temples "which were the wonder of the age."

We shall now turn to the Hindū accounts of the same period. The *Jaimini-Bhāratam* gives Nṛsiṃharāya credit for having vanquished the kings of the Tigula⁷ (or Tamil) and Oḍḍi (or Orissa) countries and for having conquered the forts of Kapāladurga, Penugonḍa,⁸ Bonagiri, Cheṇḍi, and Kommadhārāpura.⁹ In another part of the *Jaimini-Bhāratam* we are told that Nṛsiṃharāya "decorated the golden palaces (temples?) of Kāñchī, Venkāṭa (Tirupati) and Kālahasti with the precious stones annually given as tribute by the kings of Pāñchāla, Draviḍa, Aṅga, Mālava, Śāka and Prāgyjyōtisha."¹⁰ This is, of course, hyperbolic, but shows that the three important places of pilgrimage referred to were in the dominions of Nṛsiṃharāya.

¹ Mr. Rice's *Mysore Inscriptions*, p. 208.

² [The Raṅganātha temple at Śrīraṅgam contains a Sanskrit and Tamil inscription (No. 59 of 1892), dated in Śaka-Samvat 1385, Subhānu, of Sāluva-Gōpa-Timma-nṛpati, who is also called the *Mahāmaṇḍalēśvara* Mēdini-misaragaṇḍa Kattāri Sāluva Dharanivarāha Sāluvasāluva Tirumalaidēva-mahārāja. Another inscription of the same king at Tanjore, dated in Śaka-Samvat 1377, Yuvan, has been published in *South-Ind. Inscr.* Vol. II. No. 23; and a third one at Tirukkāṭṭupallī (No. 55 of 1897) is dated in the Vikrama year (i.e. Śaka-Samvat 1382).—E. II.]

³ See v. 12 of the Devulapalli plates.

⁴ See v. 21 of the same plates.

⁵ *Ind. Ant.* Vol. XXVIII. p. 283.

⁶ *Loc. cit.* p. 289.

⁷ Tigula is a Kanarese name for Tamil; see Dr. Kittel's *Kannada-English Dictionary*, s.v.

⁸ *Jaimini-Bhāratam*, p. 5.

⁹ *Jaimini-Bhāratam*, p. 95. Bonagiri is apparently the well-known town of that name in the Hyderabad territory. Cheṇḍi is Gingee in the South Arcot district. I am unable to identify Kommadhārāpura.

Jaimini-Bhāratam, p. 115.

According to the *Varāhapurāṇam* Nṛsiṃharāya's first general Īśvara of the Tulu family conquered the forts of (1) Udayādri, (2) Huttari, (3) Gaṇḍikōṭa, (4) Penugonḍa, (5) Beggulūru, (6) Kōvela-Nellūru, (7) Kundāni, (8) Goḍuguchinta, (9) Bāḡūru, (10) Naragonḍa, (11) Āmūru and (12) Śrīraṅgaṭṭaṇam, and "destroyed the cavalry of the Yavanas of Beḍandakōṭa at Gaṇḍikōṭa."¹ The Yavanas referred to here are the Bahmanī kings, who transferred their capital from Kulbarga to Bidar in June 1423 A.D., during the reign of Aḥmad Shāh.² Referring to the same event, the author of the Telugu poem *Pārijātōpaḥaraṇam* says that Īśvara "gave rise to thousands of rivers of blood by killing the horses of the Yavanas of Beḍandakōṭa,"³ but he transfers the scene to Kandukūru.⁴ The Muḥammadan historians do not, of course, refer to this event.

Nṛsiṃharāya's dominions were extensive, and they probably comprised the whole of the modern districts of North Arcot, Chingleput and Nellore, and portions at least of South Arcot, Cuddapah, Kistna and Mysore. The *Varāhapurāṇam* calls Nṛsiṃharāya "the possessor of arms which are capable of protecting the kingdom of Karṇāṭa,"⁵ which shows his connection with that kingdom. According to the same work he was one of the *Sūmantas* or tributary princes of the Karṇāṭa empire, and both Īśvara and his son Narasiṃha were his generals one after the other. It would appear also that Nṛsiṃharāya was probably related to the kings of the first dynasty of the Karṇāṭa empire, since both claimed to belong to the Yādava line of the lunar race of Kshatriyas. This description closely tallies with that given by the Portuguese chronicler Fernão Nuniz of "Narsymgua" who overthrew the first dynasty of the empire. In fact according to Nuniz there was a double usurpation of the Vijayanagara throne about this time, the first usurpation being by "Narsymgua," whom I identify with Saḷuva Nṛsiṃharāya, father of Immaḍi-Nṛsiṃha, the donor of the present grant, and the second by Nṛsiṃharāya's general "Narsenaque" or Narasiṃha, the founder of the Tuḷuva dynasty.

According to Nuniz, the following are briefly the circumstances that led to the downfall of the first and the accession of the second dynasty. The last great king of the first dynasty was Dēvarāya II, who ruled till about the year A.D. 1449. The next forty or fifty years saw no less than five sovereigns, all of them weak and imbecile. The last of them, whom Nuniz calls "Padea Rao," seems to have been the worst of the lot, and in his time the empire declined even more than in the time of his four immediate predecessors. It occurred to Nṛsiṃharāya, who was the principal minister and general of the state, that a change of sovereign was necessary to prevent the kingdom from falling an easy prey to its hereditary enemy, the Bahmanī king, and, with the consent and support of the other generals and ministers, he seized the throne and kingdom, allowing the king to make his escape. Nṛsiṃharāya died, leaving two infant sons and a general named "Narsenaque" or Narasa-Nāyaka, in whom he had much confidence and whom he therefore appointed regent during the minority of his sons. In a short time Nṛsiṃharāya's eldest son was murdered by one of Narasa-Nāyaka's enemies, who wanted it to be believed that Narasa-Nāyaka murdered the boy for the sake of his crown. Subsequently the second prince was murdered at the instance of Narasa-Nāyaka himself, who thereupon

¹ Verses 42 and 43 of the first *divāṇa*. I am not able to identify Nos. 6, 7, 8 and 9. Huttari (2) is probably Puttūr in the Kārvēṭinagar Estate, and Beggulūru (5) is perhaps Bangalore. No. 10 may be Naragallu (*kallu* means 'a rock' and *koṇḍa* a 'hill') in the Chittūr tāluka, where there is an old fort (see the *North Arcot District Manual*, new edition, Vol. II. p. 349), and Āmūru (11) is evidently Gid-Āmūru or Ambūrudurga in the Guḍiyātam tāluka. The other places are well-known.

² *Ind. Ant.* Vol. XXVIII, p. 210. Beḍandakōṭa or Beḍadakōṭa is 'the fort of Beḍada,' which is a corruption of Bidar.

³ Vaijayanti Press edition of 1895, p. 10.

⁴ The words Kandukūru and Gaṇḍikōṭa suit the metre equally well, and one of the readings is necessarily incorrect.

⁵ Verse 30 of the first *divāṇa*.

proclaimed himself king. Narasa-Nâyaka was succeeded by his son "Busbal Rao," who died after a reign of six years and was succeeded by his younger brother **Kṛishṇadēvarāya**.¹

Nuniz expressly states that Narasa-Nâyaka was the father of Kṛishṇadēvarāya and that "Busbal Rao" was his eldest son and successor. Narasa-Nâyaka must therefore be identified with **Narasimha**, the founder of the second dynasty, and "Busbal Rao" with his eldest son, **Vira-Narasimha**.² Mr. Sewell finds this account confusing and conflicting with known facts. This is because he identifies "Narsyngua," the first usurper, with **Narasimha**, the founder of the Tuluva dynasty, which leads him to the conclusions that his successor Narasa-Nâyaka, whom he identifies with **Vīra-Narasimha**, was not his son, and that between **Vīra-Narasimha** and **Kṛishṇadēvarāya** there was an intermediate king—conclusions which are certainly opposed to express statements contained in several inscriptions and books.

These difficulties would vanish entirely if we admit the theory of double usurpation and identify Narasa-Nâyaka with the founder of the Tuluva dynasty. The theory of double usurpation is not only not inconsistent with known facts, but is highly probable, since but for the first usurpation **Narasimha** would have had no *locus standi* in the affairs of the empire and certainly no opportunities or excuse for usurping the throne. The statement in the inscription that **Nṛisimharāya** with the aid of his sword defeated all and became a *Sūrabhauma* or emperor (v. 13) seems to me to point unmistakably to his usurpation of the Karpāṭa throne.

The account of Nuniz as to the nature of the relationship which existed between **Sāluva-Nṛisimharāya** and **Narasimha** is directly and fully corroborated by the *Varāhapurāṇam*.³ The first chapter (*āśvāsa*) of the book gives the genealogy of both these persons and says that **Narasimha**'s father **Īśvara**, who is also called **Īśvara-Nâyaka**, was **Nṛisimharāya**'s general, and that he was succeeded by his son in that office. In another place **Narasimha** is said to have been honoured by **Nṛisimharāya** and appointed commander of his forces,⁴ and in a third place he is described as the "supporter of the kingdom of **Nṛisimharāya**."⁵ In the penultimate verse of the sixth *āśvāsa* he is addressed as *Sāluva-Narasīṅga-dharādharma-daṇḍanātha*, i.e. 'commander of the forces of king **Sāluva-Nṛisimharāya**.'

There are at present no means of fixing the exact year in which **Nṛisimharāya** usurped the **Vijayanagara** throne; but this event must be placed between the Śaka year 1408 (= A.D. 1486-87), which is the latest known date of the first dynasty,⁶ and the Śaka year 1418, *Rākshasa* (= A.D. 1495-96), which is the earliest known reliable date of **Immaḍi-Nṛisimharāya**.⁷ That the latter was recognised as king of **Vijayanagara**, at least in name, is expressly stated by Nuniz, and Dr. Hultsch informs me that an inscription at **Bārūkūr** (No. 166 of 1901) of Śaka-Saṁvat 1421, *Siddhārthin* (= A.D. 1499-1500), states that in this year the *Mahāmaṇḍalēśvara* **Mēdinimīśaraṅgaṇḍa Kāṭhāri Sāluva Immaḍi-Narasimharāya-mahārāya** was ruling at

¹ *A Forgotten Empire*, pp. 305-315.

² I confess I cannot derive "Busbal Rao" from **Vira-Narasimha**, but there is no doubt about the identity of the persons.—[Perhaps the name is connected with *Bhujabala*, a surname of the Hoysalas.—E.H.]

³ *A Forgotten Empire*, p. 308, note 2.

⁴ Verse 35 of the first *āśvāsa*.

⁵ The penultimate verse of the second *āśvāsa*.

⁶ *A Forgotten Empire*, pp. 96 and 404.

⁷ *South-Ind. Inscr.* Vol. I. p. 131, No. 115. Inscriptions Nos. 116 and 119 of the same volume appertain to the reign of **Immaḍi-Nṛisimha**'s father **Nṛisimharāya**. Dr. Hultsch's suggestion that these two donors were kings of **Vijayanagara** is clearly untenable. The donors style themselves *Mahāmaṇḍalēśvara*, and their family name **Sāluva** is also given. There was no **Narasimha** on the throne of **Vijayanagara** in Śaka 1395 and 1404, which are the dates of the inscriptions Nos. 116 and 119.—[An inscription at **Vallam** near **Wandiwash** (No. 75 of 1900), dated in Śaka-Saṁvat 1391, *Virōdhin*, belongs to the time of the *Mahāmaṇḍalēśvara* **Mēdinimīśaraṅgaṇḍa Kāṭhāri Sāluvasāluva Narasiṅgaīyadēva**, and the same chief is mentioned in an **Āmbūr** inscription of the **Vijayanagara** king **Rājasēkhara**, son of **Mallikārjuna**, dated in Śaka-Saṁvat 1390, *Sarvadhārin* (No. 4 of 1890). **Bukka**, an ancestor of the third **Vijayanagara** dynasty, is said to have "firmly established even the kingdom of **Sāluva-Nṛisimha**" (above, Vol. III. p. 288), whence it may be concluded that he was the minister of **Nṛisimharāya**. **Kṛishṇarāya** had a minister named **Sāluva-Timma**; see above, Vol. VI. pp. 109 and 281.—E.H.]

Vijayanagara,¹ and that his chief minister was Narasa[ṇ]ṇa-Nāyaka.² This Narasanna-Nāyaka may be identical with the founder of the Tuluva dynasty and the "Narsanaque" of Nuniz. If this identification is correct, Narasimha's usurpation of the throne of Nṛsiṃharāya, or rather of his son and successor Immaḍi-Nṛsiṃharāya, cannot have taken place earlier than A.D. 1499-1500.³

Mr. Sewell quotes five inscriptions of "Narasimharāya of Vijayanagara" appertaining to years prior to A.D. 1500.⁴ One of these inscriptions was dated in 1451, one in 1469, and one in 1471. It is clear that these three inscriptions cannot be referred to the founder of the Tuluva dynasty, as they came into existence long before he could have become king of Vijayanagara according to any account. The last of the five inscriptions belongs to Sāluva Immaḍi-Nṛsiṃha,⁵ son of Nṛsiṃharāya. The remaining inscription is to be found at Conjeeveram, and it is possible that, when examined, it will be found to belong to the time of Sāluva-Nṛsiṃharāya.

As Dr. Hultzsch informs me, a Bārukār inscription (No. 152 of 1901) of the *Mahārājā-Śrīrāja Rājaparamēśvara Virapratāpa Vira-Narasimharāya* of Vijayanagara is dated in Śaka-Saṃvat 1424, Durmatī (=A.D. 1501-02). This date suggests that Immaḍi-Nṛsiṃharāya was ousted by Narasimha (or by his son Vīra-Narasimha?) between A.D. 1499 and 1502. In accordance with this fact the subjoined copper-plate inscription of A.D. 1504 does not represent him any more as a king of Vijayanagara, but as the ruler of the province of Penugonda.

TEXT.⁶

First Plate.

- 1 शुभमस्तु । वंदेहं देवदेवं तं तुदिलं [प्र]दिक्षं पट ।
- 2 कारणं जगतां विघ्नवारणं वारणं⁷ मुखे । [१*] पायाह[:*] स
- 3 महाक्रौडः कीडतंबुधिपल्वेलि⁸ । ⁹ यह[द्वा]दंडम[१]लंव्य¹⁰
- 4 मग्ना भूः पुनरुद्यिता¹¹ । [२*] या रत्नाकरमेखल[१]विवर्द्धितशफा-¹²
- 5 रोजम[न्म]ध्यमा क्षमाभ्युत्पीनपयोधरोरुपुलिनस्फूर्जन्नि-
- 6 तंबस्थली । गाढं गूढपदोद्यिता¹³ कथमपि श्यामा नृदेकार्थि-
- 7 नो सातत्येन समग्ररत्नजननी सा रत्नगर्भास्तु वः । [३*] अस्ति श्री-
- 8 मदपां पुष्पसामोदितदिगंतरं । यन्नित्यं मूर्ध्नि संधत्ते यन्ने-
- 9 न महता शिवः । [४*] ¹⁴ तस्मादभूदुधस्तस्मात्पुरुकीर्तिः पुरुरवा[:]
- 10 । सम्राजः समजायंत ¹⁵ क्रमयोगेकशस्ततः । [५*] तद[न्व]यप[यो]-

¹ In v. 22 of the present inscription this city is alluded to by the statement that Immaḍi-Nṛsiṃha "ascended the throne existing on Hēmakūṭa." This is the local and traditional name of the hill which adjoins the temple of Virūpākṣasvāmī, the principal deity in the city of Vijayanagara and the patron god of the kings of that empire.

² The same two persons are mentioned in an inscription of Śaka-Saṃvat 1418, Nala (=A.D. 1496-97), at Hāliche in the Mysore tāluka (*Ep. Carn.* Vol. III, My. 88), where however Immaḍi-Narasimharāya is called simply Narasimharāya.

³ Mr. Sewell places it between A.D. 1487 and 1490 (*A Forgotten Empire*, p. 98) and elsewhere in A.D. 1498 (*ibid.* p. 110).

⁴ *Lists of Antiquities*, Vol. II. pp. 62-64.

⁵ Mr. Sewell's *Lists of Antiquities*, Vol. I. p. 116.

⁶ The transcript has been prepared by Dr. Hultzsch from ink-impressions.

⁷ Read वारणं.

⁸ Read कौडतंबुधिपल्वेलि.

⁹ Read यहद्वा°.

¹⁰ Read °लंव्य.

¹¹ Read °रुद्यिता.

¹² Read °स्फारोजम°.

¹³ Read °दोद्यिता.

¹⁴ Read °भूदुध°.

¹⁵ Read क्रमयोगी°.

- 11 भोघी ^१युंडदेवो गुणीत्तरः । ^२अपारिजात्तेप्युदभूत्पारिजात
 12 इवापरः । [६*] गुडवोमो^३ गुणाब्धः श्रीमादिराजो महायशोः^४
 13 गीतयो^५ गीतसत्कीर्तिर्वीरश्रीवीरहोबलः । [७*] सावित्रिमंगिभू-
 14 पश्च तथा ^६सालुवमंगिरा[ट् ।*] तस्मादुदभवद्वन्ये षडर्त^७ चक्र-
 15 वर्तिनः । [८*] तेषामभूत्साकुव[मंगि]देवो महीमहेंदो^८ महनीयकी-
 16 र्तिः । विजित्य वीरं रणधुर्यमेकं कठारिकां योस्य कराद-
 17 गृह्णात् । [९*] ^९तस्मान्मोनोरथ इवाधिकभागधेयाज्ञौतक्षमापति-
 18 रजायत भव्यकीर्तिः । यद्दानवारिनववारिधिजातकी-
 19 र्तिचंद्रः सदा धवळ्यत्यमलस्त्रिलोकीं । [१०*] गुंडचितोशी
 20 गुणवांस्ततोभून्नव्यप्रसूनादिव भव्यगंधः । ^{१०}दिषद्दत्ता[ब्धिं]
 21 भुजमंदरेण विमथ्य वीरश्रियमग्रहीद्यः । [११*] गुणांबुधे-
 22 गुंडविभीस्ततोभून्मल्लांविक्कायां^{११} महनीयकीर्तिः । नृसि-^{१२}
 23 ह्वरायोयमहोवळ्स्त्रीनृसिह्मदेवस्य^{१३} वरप्रसादा[त्] । [१२*] मी-
 24 सरगंडकठारीसाकुवधरणीवराहविरुदांकः । यः ख-
 25 ^{१४}कसच्चायः सर्वान्निर्जित्य सार्वभौमोभूत् । [१३*] ^{१५}आसीध्वराय-
 26 राहो यः खलाब्धेध्वरन्^{१६} धरां । साकुवः शत्रुसंघातं प-
 27 क्षिघातं निहत्य च । [१४*] किणीकृतमहाबाहोरत्विप्रत्ययिदा-^{१७}

Second Plate; First Side.

- 28 नतः । यस्य बर्बरवाहत्वं^{१८} यथार्थमभवत्परं । [१५*] यः पं-
 29 ^{१९}चसाखशाखाभिर्जित्वा पंचामरद्रुमान् । पंचघंटा-
 30 निनादोभूत्पंचघटानिनादनात्^{२०} । [१६*] सत्यसत्त्वेषुसंघ[र्त]-^{२१}
 31 नरूपलावण्यधीगुणैः [१*] जित्वा यः पांडवान् पंच
 32 प्रापदैवरगंडतां । [१७*] यस्त्रीनस्त्री चारचोरपांडवराया-
 33 व्रणाजिरे । मूरुरायरगंडोभूद्भीरुक्तत्य स्वपौरुष[र्त]-
 34 त् । [१८*] ^{२२}प्ररापेनाकवडैरितमस्तोमं निरस्य यः । प्र-
 35 काशयन्निमामुवीमुर्वरादित्यतां^{२३} गतः । [१९*] चौहत्त[म]-
 36 क्त्वा^{२४} धरणीवराहश्चाकुव्यनारायण इत्यमीभिः । सु-

^१ Read गुंड°.

^४ Read °यशः.

^७ Read षडर्ते.

^{१०} Read दिष°.

^{११} Read °हीनलश्रीनृसिंह°.

^{१६} Read °वधरन्.

^{१९} Read °शाख°.

^{२३} Read प्ररापेनाकवडैरि°.

^३ Read °जातोपु°.

^५ Read गीतयो.

^८ Read °महेंद्री.

^{११} Read °विक्कायां.

^{१४} Read खड्गैक°.

^{१७} Read °प्रत्ययि°.

^{२०} Read °घंटा°.

^{२३} Read °मुर्वीमु°.

^३ Read गुंडवोमी.

^४ Read साकुव°.

^९ Read तस्मान्मोनो°.

^{१२} Read नृसिंह°.

^{१५} Read आसीध्वरा°.

^{१८} Read °बाह्वं.

^{२१} Read °सत्त्वेषु°.

^{२४} Read °ज्ञो.

- 37 रारिरित्यप्यथ मोहनादिः स्वनामभिर्यो हरिर[र्थ]-
 38 तोभूत् । [२०*] ¹तथासीन्महिषी हरेरिव रम[र]* श्रीरंगमां-
 39 वा सती तस्यां तेन कुमार इमडिनसिद्धेद्रः² समुत्प[र]-
 40 दितः । य(र)स्तादृङ्महिमानमात्मगुरुमप्यौदार्यशौच्य[र]-
 41 दिभिः संख्यामत्सरिभिर्गुणैरतिपतन्नन्वर्थनामा-
 42 यते । [२१*] सुमेरुं सुरशासीव³ सुमनःसुरभीकृतः । हे-
 43 मकूटप्रभूतं ⁴तस्मिन्हासनमुपैति यः । [२२*] समग्रहारा-
 44 न् ददतोग्रहारदानं कियद्यस्य वदान्यमौळेः । किं वा
 45 बह्वत्थाखिलविश्वचक्रब्रह्म[र]* उदातुः किमदेयमस्ति
 46 । [२३*] सोयं ⁵नृसहस्रायस्य तनयो विनयोज्ज्वलः⁶ । इमडि-
 47 श्रीनृसिद्धेद्रः⁷ स्वस्तिमानस्ति भूतले ॥ [२४*] — ॥ श्रीमाने-
 48 ष महारायः सीमा भूदानशीलिनां । श्रीवत्सान्व-
 49 यरत्नस्य ⁸य[जु]वेदिशिखामणेः ॥ [२५*] वेलपा[टि]पु-
 50 राधीशसूरायोक्तसुधीमणेः । सुनोः श्रीपिनया-

Second Plate; Second Side.

- 51 र्यस्य तनयस्य तपोनिधेः [१*] ⁹नरसिंहबुधेद्रस्य
 52 पौत्राय सुगुणांबुधेः । [२६*] पदवाक्यप्रमाणजप्रथ-¹⁰
 53 मोदाहृतात्मनः । महनीयचरित्रस्य महामहि-
 54 मशालिनः । [२७*] ¹¹सर्वविद्यातपोराशेः सर्वज्ञैकशि-
 55 खामणेः । राजरत्नशिरोरत्नरंजितांगिसरोरु-
 56 हः । [२८*] संपनिधेरनदातभट्टस्य प्रियसूनवे [१*] स-
 57 हुणैकनिधानाय सदाचारविचारिणे । [२९*] पदक्र-
 58 मजटावर्णक्रमविक्रमशालिने । सर्वशास्त्रर-
 59 हस्यैकवेदिने ¹²बुद्धवेदिने । [३०*] विद्याविवेकविनया-
 60 दिगुणौघधाने हृद्यानवद्यसुपवित्रचरित्रसौम¹³
 61 । सौभाग्यभाग्यनिधिमाचनभट्टनाम्ने विहङ्गलैकति-
 62 लकाय महामहिम्ने । [३१*] शाकेन्द्रे परिसंख्याते गिरिनेत्र-
 63 युगेदुभिः । रक्ताक्ष्याख्ये भाद्रपदपौर्णमास्यां रवेदिने । [३२*] चन्दो-

¹ Read तस्यां.

⁴ Read तस्मिन्हा.

¹ Read नृसिद्धेद्रः.

¹⁰ Read एव.

¹¹ Read सीवे.

² Read नृसिद्धेद्रः.

⁵ Read नृसिंह.

⁶ Read यजुवेदि.

¹¹ Read सर्व.

¹² Read चन्द्री.

³ Read शाखीव.

⁶ Read योज्ज्वलः.

⁹ Read सिंह.

¹³ Read ब्रह्म.

28 30 32 34 36 38 40 42 44 46 48 50

W. GRIGGS, PHOTO-LITH.

SCALE '55

2 4 6 8 0 2 4 6 8 10 12 14 16 18 20 22 24 26

E. HULTZSCH.

9

ବିଦ୍ୟାଧର

78

- 64 परागसमये महापुष्पफलप्रदे । पेतुर्गोडमहाराज्ये
 65 मार्जवाडस्य सीमनि । [३३*] गुंडलूनामग्रामस्य स्थले विख्या-
 66 तनामकं । सूरिनायनिमुष्टूग्रामस्याग्नेयभागतः । [३४*]
 67 तथैवाडविमुष्टूग्रामस्योत्तरभागतः । ग्रामं देवुलप-
 68 ल्याख्य^१ सर्वमान्यतया स्थितं । [३५*] एकभोगं चाष्टभोगतेजः^२ स्ता-
 69 म्यसमन्वितं । आचंद्रार्कं पुत्रपौत्रपारंपर्येण भुक्तये । [३६*] स-
 70 द्विरण्यपयोधारापूर्वकं दत्तवान् ध्रुवं ॥ [३७*]

Third Plate.

- 71 ^२ दामपालनयोर्मध्ये ^३ दानाच्छेयोनपालनं । दानात्स्वर्नमवा-^४
 72 प्रीति पालनादच्युतं पदं । [३८*] एकैव भगि[नी] लोके सर्वेषामे-
 73 व भूभुजां । न भोग्या न करग्राह्या विप्रदत्ता वसुंधरा । [३९*]
 स्वद-
 74 त्ता[द*]द्विगुतं^५ पुण्यं परदत्तानुपालनं । परदत्तापहारेण
 75 स्व[द]त्तां^६ निष्फलं भवत्^७ । [४०*] स्वदत्तां परदत्तां वा यो
 हरेत वसुं-
 76 धरां । ^८ षष्टिर्वर्षसहस्राणि विष्टायां जायते किमि^९ ॥ [४१*] — ॥
 77 मंगळमहाश्रीश्री ॥
 78 श्रीरामचंद्र^{१०} [॥*]

ABRIDGED TRANSLATION.

The first three verses are in praise of Vighnêśvara, the boar-incarnation of Vishnu, and the goddess of the Earth.

(Verse 4 f.) From that glorious flower of the waters (the Moon), which perfumes (*illuminates*) the whole space, (*and*) which Śiva always wears on (*his*) head with great solicitude, was produced Budha, (*and*) from him the renowned Purûravas. Several kings were afterwards born (*in that family*) in course of time.

(V. 6.) In the milk-ocean of this family was born the virtuous king Guṇḍa (I.), like a second *Pārijāta* (tree), though (*he became*) an *Apārijāta*¹¹ (by conquering his enemies).

(V. 7 f.) To him were born the virtuous Guṇḍa (II.)-Bomma, the glorious Mādirāja of great fame, Gautaya (I.) whose high fame was sung (*by all*), the heroic and glorious Virahô-bala, prince Sâvitri-Maṅgi, and king Sâḷuva-Maṅgi—(*like*) a second set of six emperors.

(V. 9.) Most famous of these was king Sâḷuva-Maṅgi, a Mahendra on earth, who vanquished a hero foremost in battle and seized the dagger (*kaṭhadrîkâ*) from his hand.¹²

¹ Read °ल्लाख्यं.

⁴ Read °स्वर्गम°.

⁷ Read भवेत्.

¹⁰ In large Telugu characters.

¹² This incident probably accounts for the title *Kaṭhadrî* assumed by Maṅgi and his descendants.

² Read दान°.

⁵ Read °पुण्यं.

⁸ Read षष्टि वर्ष°.

¹¹ This compound has to be dissolved into *apa + ari + jâta*.

³ Read दानाच्छेयो°.

⁶ Read स्वदत्तं.

⁹ Read किमि.

(V. 10.) To him was born the renowned king **Gauta (II.)**, the unblemished moon of whose fame, born in the fresh ocean (*created by*) the waters (*poured out on the occasion of his* gifts, always whitened the three worlds.

(V. 11.) To him was born, even as delicious fragrance out of a fresh blossom, the virtuous king **Guṇḍa (III.)**, who won the goddess of victory by churning the ocean of (*his*) enemies' force with the Mandara (*mountain*) of (*his*) arm.

(Vv. 12-20.) By the grace of the god Nṛsiṃha of Ahōbala,¹ this lord **Guṇḍa (III.)**, the ocean of good qualities, begot on (*his wife*) **Mallāmbikā Nṛsiṃharāya** of great fame, who possessed the titles of **Misaragaṇḍa**, **Kaṭhāri**, **Sāluva** (*i.e.* 'the hawk') and **Dharaṇivarāha** who, aided only by (*his*) sword, defeated all (*his enemies*) and became an emperor (*Sārvabhauma*); who became **Dharaṇavarāha** (*i.e.* 'the boar of the earth') by saving (*uplifting*) the earth from the ocean of wicked (*kings*), and **Sāluva** by smiting the crowd of (*his*) enemies like (*a flight of* birds;² whose title **Barbarabāha** became full of meaning, because his powerful arm (*hand*) had become rough through the killing of enemies and the making of gifts to the needy;³ who by conquering (*excelling in making gifts*) the five divine trees with the fingers of (*his*) hand (*and* ringing the bell five times (*in celebration of the five-fold victory*)) became **Pañchaghaṇṭanināda**; who obtained the title of **Aivaragaṇḍa** by conquering (*excelling*) the five Pāṇḍavas in truthfulness, strength, archery, personal beauty and intelligence (*respectively*);⁴ who, wielding the weapon became **Mūruṛāyagaṇḍa**⁵ by making through his valour the three kings of **Chāra**, **Chōra** and **Pāṇḍya** afraid on the battle-field; who obtained the title **Urvarāditya** by dispelling the thick darkness—(*his*) enemies by the sunshine of (*his*) valour (*and thereby*) illuminating this earth (*and*) who was Hari (Vishṇu) in reality by virtue of his titles **Chauhattamalla**,⁶ **Dharaṇivarāha**, **Chālukya-Nārāyaṇa**¹⁰ and **Mōhana-Murāri**.

(V. 21f.) His queen was the virtuous **Śriraṅgamāmbā**, even as **Ramā** of Hari. By her was born to him prince **Immaḍi-Nṛsiṃhendra**, who, by excelling even his father, who was so noble, in generosity, valour and other innumerable good qualities, made his name literally true,¹¹ (*and*) who, praised by learned men, ascended his (*viz.* his father's) throne, which rose on the **Hēmakūṭa** (*mountain*), even as the divine tree, perfumed with flowers, (*adorns*) Mount **Mēru**, which abounds in golden peaks (*hēma-kūṭa*).

(V. 23.) What are gifts of *agrahāras* to this chief of benefactors, who gave complete necklaces (*sumagra-hāra*)? What is the use of many words? What is there that could not be made a gift of by the donor of a full *viśvachakra* and *brahmāṇḍa*?¹²

(V. 24.) This well-bred, glorious **Immaḍi-Nṛsiṃhendra**, son of **Nṛsiṃharāya**, is prosperous on earth.

¹ This is the celebrated place of pilgrimage in the Kurnool district.

² This is an evident reference to Nṛsiṃharāya's usurpation of Vijayanagara.

³ The tradition is that the title was due to the fact of Nṛsiṃharāya's ancestors having acted as fowlers to the kings of Kaṇṇāṭa.

⁴ There is a pun in the original on the word *ddna*, which means 'cutting' and also 'a gift.'

⁵ This etymology is fanciful. *Pañchaghaṇṭanināda* is apparently the same as *Pañchamahādāda*.

⁶ Another graceful etymology. The meaning of *Aivaragaṇḍa* is 'the lord of five (chiefs),' a title which Nṛsiṃharāya seems to have borrowed from the Vijayanagara kings.

⁷ This title also was borrowed from the Vijayanagara kings.

⁸ *Chāra* stands for *Chēra*, and *Chōra* for *Chōla*.

⁹ In this sense the word is a corruption of *chatur-hasta-malla*. Another derivation is from *chatur-hasti-malla*, which means 'a hero having the strength of four elephants.'

¹⁰ This is an anachronism.

¹¹ Here is a play on the word *immaḍi*, which means 'the second' as well as 'double.'

¹² [These are the names of two of the sixteen great gifts (*maḥādāna*); see *Ep. Ind.* Vol. I. p. 368 and note 58. — E. H.]

(Vv. 25-37.) This glorious *Mahārāya*, who is the type of habitual givers of land, on the auspicious occasion of an eclipse of the moon, on Sunday, the full-moon *tīthi* of *Bhādrapada* in (the year) called *Raktākshin* (corresponding to) the *Śāka* year reckoned by the mountains (7) the eyes (2), the Yugas (4), and the moon (1),— (i.e. 1427)—granted with libations of water, a *sarvamānya* and *śkabhōga*, with the eight rights of ownership, the village of *Dēvulapalli*, south-east of the village *Sūrināyani-Mushtūru* and north of the village *Adavi-Mushtūru*, within the limits of the village of *Gundlūru* in the *śīman* of *Mārjayāda* in the *mahārājya* of *Penugonḍa*, to *Māchanabhaṭṭa*, who was the son of *Annadātabhaṭṭa*, grandson of *Narasimha*, great-grandson of *Pinnayārya*, and great-great-grandson of *Sūrayōjha* of *Vēlapātipura*,¹ a *Yajurvādīn* of the *Śrīvatsa gōtra*.

Vv. 38-41 are imprecatory verses.

No. 9.—KAHLA PLATE OF THE KALACHURI SODHADEVA;

[VIKRAMA-]SAMVAT 1134.

By F. KIELHORN, PH.D., LL.D., C.I.E.; GÖTTINGEN.

This plate was found on the 15th August 1889 by the cultivator Shiusewak Rai in his field at *Kahla*, a village in the tappa *Athaisi* of the pargana *Dhuriāpār* of the *Gōrākhpur* district in the United Provinces, and presented by Dr. W. Hoey to the Provincial Museum of Lucknow in January 1895. I edit the inscription which it contains from impressions, kindly furnished to Dr. Hultzsch by the late Mr. E. W. Smith.²

This is a single copper-plate which, to judge from the impressions, is about 1' 5½" broad by 1' ¾" high, and is inscribed on both sides. In the middle of the lower part of it there is a ring-hole, ⅜" in diameter, and together with the impressions of the plate I have received impressions of a circular seal, about 3" in diameter, which contains in high relief the figure of a bull, lying down and facing to the proper right; below it, the legend *śrīmat-Sōḍhadēvasya*, in *Nāgarī* letters about ⅜" high; and below this again, an arrow pointing to the proper right. An arrow is engraved also on the second side of the plate, in line 59, before the words *sva-hastō-yaṁ*. In general, both the writer and the engraver have done their work carefully. The writing on the second side of the plate is well preserved, but that on the first side has suffered from corrosion so that in several places, which will be pointed out in the notes, the reading of the text is doubtful. Fortunately, with a single exception in line 28, the names and dates may be given with absolute certainty. The size of the letters is about ¼". The characters are those of the *Nāgarī* alphabet of the time and locality to which the inscription belongs; they resemble those of the copper-plates of *Gōvīndachandra* and *Jayachchandra* of *Kanauj*. In lines 48-50 they furnish signs for the fractions ½ and ⅔, which I have not met with in other northern inscriptions: 1½ is denoted by the figure for 1 with two vertical lines after it, and the fraction ⅔ by the circle for nought followed by three vertical lines. The sign of *avagraha* occurs once, in *sampradattī samābhīḥ*, l. 47. The language is Sanskrit, but the names of some of the *Brāhmanas* mentioned in lines 40-50 are given in their vernacular forms or in forms based on them. Lines 1-32 contain

¹ This is evidently the modern village of *Vāyalpāḍu*.

² After the lamented death of Mr. E. W. Smith—he died on the 21st November 1901 in the *Bahraich* district of *Oudh*—I was informed by Mr. *Gholam Rasool Beg*, Head Draftsman of the *Archæological Survey*, United Provinces, that the village *Kahla* is on the *Gōrākhpur* to *Azamgarh* metalled road, about 28 miles from the former town; but I have not found the name in the *Indian Atlas*, sheet No. 102, which gives '*Dhooreapar*' in long. 83° 18', lat. 26° 25'.—Mr. *Gholam Rasool Beg* has kindly furnished me with two very good additional impressions of the *Kahla* plate.

thirty verses with genealogical matter, and lines 51-57 ten benedictive and imprecatory verses (*dharma-slokaḥ*, l. 51); the latter are all numbered with numeral figures (from 1 to 10), but of the former only the last verse has the number 30 placed after it. The rest of the text is in prose. Unusual terms which occur in the latter will be drawn attention to below. As regards orthography, the sign for *v* throughout serves for both *v* and *b*; the dental sibilant is frequently employed for the palatal; the palatal for the dental in *śīṭ*, ll. 3, 5, 7 and 22, *ajātram*, l. 16, *śāsana* (for *śāsana*), l. 22, and *sahasra*, l. 53; for the palatal sibilant preceded by *anuvāra* we have *ns* in *vansa*, ll. 6 and 50, *vansya*, l. 3, *vinsat*, l. 37, and *trinsat*, l. 39; *j* is used instead of *y* in *Kṛitavirja*, l. 3, *Kārttavirjā*, l. 4, and *jātā*, l. 23; *gh* instead of *h* in *Naghushaḥ*, l. 2, and *siṅghāsana*, l. 13; and *āmra* and *tāmra* are spelt *āmora* and *tāmra*, ll. 38 and 57.

The inscription belongs to a hitherto unknown branch of the Kalachuri family. It records a grant of land by the *Paramabhaṭṭāraka Mahārājādhirāja Paramēśvara*, the devout worshipper of Mahēśvara (Śiva), the glorious Sōḍhadēva, who meditated on the feet of the *P. M. P.*, the glorious Maryādāsāgaradēva (l. 33). The introductory verses give an account of Sōḍhadēva's ancestors.

After the words *ōṃ svasti*, verses 1-4 eulogize the following mythical and legendary beings:—the Moon who was Atri's son, Budha, Purūras, Nahusha, Haihaya, Kṛitavīrya, and Kārtavīrya Arjuna.¹ In the family descended from the last there was a personage who by conquering Ayōmukha² and subduing the Krathas possessed himself of Kālāñjara (v. 5). This ornament of the Kalachuris, after having conquered his enemies, gave the kingdom to his younger brother, and the latter, Lakshmanarāja, in turn conquered Śvetaṭpada³ (v. 6). In Lakshmanarāja's family there was the king Rājaputra, who captured the lord of horses Vāhali (or Bāhali), defeated the kings of the east, and lowered the fame of Kiriṭin and other princes (v. 7). From him sprang Śivarāja [I.], and his son was Śaṅkaragaṇa [I.] (v. 8). His son again was Guṇāmbhōdhidēva (Guṇasāgara [I.]), who had some dealings with a Bhōjadēva⁴ and by a warlike expedition took away the fortune of the Gauḍa (v. 9). From his first wife Kāñchanadēvi this king had a son named Ullabha who, after reigning himself, placed on the throne his brother Bhāmānadēva (a son of Guṇasāgara from another wife named Madanādēvi), who had distinguished himself in a war with a king of Dhārā (vv. 10-15). Bhāmāna's son from Dēhaṭṭadēvi was Śaṅkaragaṇa [II.] Mugdhatuṅga (vv. 16 and 17); his son from the queen Vidyā was Guṇasāgara [II.] (vv. 18 and 19); his son from Rājavā was Śivarāja [II.] Bhāmāna (vv. 20-22); his son from Sūgalladēvi was Śaṅkaragaṇa [III.] (v. 23); and his son from Yaśōlēkhyādēvi was Bhīma (v. 24). The inscription then, after stating that Bhīma by the decree of fate lost his kingdom (or was dethroned), records that the king Guṇasāgara [II.] had by Lāvanyavatī a son named Vyāsa and that this Vyāsa⁵—if I understand the text rightly—was raised to the throne, when the (royal) camp was at Gōkulaghaṭṭa, on Monday, the day of the eighth *tithi* in the bright half of the second Jyaisṭha of the year 1087 (given in words, v. 27). Vyāsa's son was the king Sōḍhadēva, who (in v. 30) is described as the life of Sarayūpāra (or 'the bank of the Sarayū'), and who is the donor of this grant. Since, as has been already stated, Sōḍhadēva is represented as meditating on the feet of

¹ Compare *Ep. Ind.* Vol. II. p. 5, and other inscriptions of the Kalachuris of Chēdi (or Pāhāla).

² I do not know the legend here referred to. *Ayōmukha* is the name of a demon and of a mountain, *Krathas* the name of a race or people. The well-known mountain or fort of Kālāñjara was taken from the (Kalachuri) kings of Chēdi by the Chandēllas, who from it took the title *Kālāñjaraḍḍhipati*; but the Kalachurys of the South, at any rate, kept the hereditary title of 'lords of Kālāñjara, the best of towns.'

³ This must be the name of a country, but the name has not yet been found elsewhere.

⁴ The compound of which this name forms part is somewhat ambiguous. The Bhōjadēva referred to may be Bhōjadēva of Kanauj (see my *List of North. Inscr.* No. 14).

In line 28 of the text there seem to be references to a person named Sasva(?), but the text is damaged in that line, and the sense is not clear to me.

Maryādāsāgaradēva, Maryādāsāgara must be another name of his father and predecessor Vyāsa (the son of Guṇasāgara II.).

In the prose part of the inscription Sôḍhadēva from his residence at Dhuliāghatta (l. 32) informs the *Mahārājñi* (or *Mahārājñis*), *Mahārājaputras*, *Mahisāndhikigrahitās* and other officials and the inhabitants concerned that, after bathing in the great river Gandaki on the occasion of the *Uttarāyana-samkrānti* on Sunday, the seventh *tithi* of the bright half of *Pausa* in the year 1134 (given in words, l. 39), he granted twenty *nālukas* of land in the field, of certain villages or hamlets to fourteen Brāhmanas whose names, *gōtras*, etc., and exact shares in the land are given in lines 40-50. Among the titles of officials enumerated here, and in the description of the several classes of inhabitants mentioned, there are some terms which I have not met before or about the proper reading of which I am doubtful: they are the terms *mahāmahātaka*, *mahādānika*, *mahāpāndhākulika* (or *mahāpāndha* and *kulika*?) in line 34, and *viskayadānika*, *khaṇḍavāla*,¹ *valādāhira* (or *balādāhira*) and *bhaṭṭāmukutika* (or *bhaṭṭa* and *mukutika*?) in line 35. The term *nāluka* (or, abbreviated, *nālu*), which also occurs in a plate of Gōvinda-chandra of Kanauj (above, Vol. V. p. 114, l. 19), apparently is derived from, and equivalent to, the Sanskrit *nalva*, a measure of distance equal to 400 (or, according to others, 100, or 120) *hastas*; what I do not understand in the present inscription is, that 'the land measuring twenty *nālukas*' in line 37 is further qualified by the expression *dēvakūṭikāśṭha-parimita*. Nor am I able to give the meaning of the word *pāṭikā* in the expression *pāṭikayā vibhajya* which occurs in line 47.

The land granted by the king was in (the district of) *Ṭikarikā* that belonged to the *Guṇakala-vishaya* (l. 36). It formed part of the fields of *Mahiāri-pāṭaka*, *Asathi-pāṭaka*, *Thiula-pāṭaka*, *Vaṇiā-pāṭaka*, *Duāri-pāṭaka* and *Chhiḍādāṣṭembhā*, a group of villages bounded on the east by *Annāḍha*, on the north by *Ṭikari*, on the south by *Avadachana*, and on the west by *Chanduliā*. The terms in which the land was given are well known from the grants of Gōvindachandra and other kings of Kanauj.

Each of the fourteen donees is described by a term indicating his place of residence or origin, and in each case the text gives the father's name, the *gōtra*, the number of *pravaras* (three or five), and the Vêdic *sākhā*. The *gōtras* so mentioned are those of *Kātyāyana*, *Kāśyapa*, *Kuśika*, *Kṛishṇātra* (for *Kṛishṇātrēya*?), *Kauṇḍinya*, *Dhaumira*, *Pārāsara* (or *Parāsara*), *Bhāradvāja*, *Rāhula*, *Sāvarṇa* and *śrī-Śāṇḍilya*; the *sākhās* the *Bahvricha-ś.*, *Chhandōga-ś.*, *Vājasaneyā-ś.*, *Mādhyaṇdina-ś.* and *Yajuh-ś.* The donees and their fathers mostly have one of the titles *paṇḍita*, *dākshta*, *agnihōtrīn*, *divēdān*, *bhaṭṭa*, or simply *brāhmaṇa*. Among their proper names occur² *Gōvindāyichcha*, *Chhāñchhi* (gen. *īkasya*), *Jākhū*, *Jālū* (gen. *ākasya*), *Tihuyapa-siha*, *Dāndū* (gen. *ākasya*), *Nimbō*, *Bhōgū*, *Māḍha*, *Mālḥ* (gen. *ākasya*), *Vāhmaṇa*, and *Sīdhū* (gen. *ākasya*). The adjectives derived from the names of the places of residence or origin of the donees are *Kaṭaughanagrāmiya* (from *Kaṭaughanagrāma*), *Kahallīya* (from *Kahallī*), *Kulāndhiya* (from *Kulāndhī*), *Ṭikarikīya* (from *Ṭikari*), *Tālīkiya* (from *Tālī*), *Nāgara* (from *Nagara*), *Nikhatigrāmiya* (from *Nikhatigrāma*), *Mahuālīkiya* (from *Mahuālī*), *Māthura* (from *Mathurā*), *Sāṅkasasthāniya* (from *Sāṅkasasthāna*), and *Hastigrāmiya* (from *Hastigrāma*).— In the passage which records the exact partition among the donees of the land granted it is stated (in line 50) that one of the donees together with his 3 *nālus* of land received a dwelling-place.

After the ten benedictive and imprecatory verses already mentioned it is stated (in line 57) that this *tāmra-paṭṭa* was written by the *Ādēsa-naṭbandhika* or 'recorder of orders' Janaka on Sunday, the sixth *tithi* of the dark half of *Chaitra* of the year 1135 (given in figures only);

¹ This would remind one of *khaṇḍarakṣha* which is common enough.

² Compare the list of names given above, Vol. IV. p. 171 ff.

and the inscription ends with the words: 'this is the own hand of the *Mahārājādhirāja*, the glorious *Sōḍhadēva*.'

I regret to say that I have not been able to identify with confidence any of the numerous localities mentioned in this inscription. The river *Gaṇḍaki* in which the king had bathed when making his donation must be the Gandak or Little Gandak of the United Provinces; but I have not found on their banks any name like *Dhuliāghaṭṭa*. The *Sarayū* after which *Sōḍhadēva*'s territory appears to have been called *Sarayūpāra*¹ most probably is the river Gogra, which in Oudh is known 'by the names Deoha, Surjoo or Sarayu, as well as Ghogra.'² The rivers would indicate in a general way where the *Gupakala-vishaya* and (the district of) *Ṭikarikā*, in which the villages containing the land granted were situated, should be looked for.

Of the three dates which the inscription contains, the date on which the grant was made regularly corresponds, for Vikrama-Saṃvat 1134 expired, to Sunday, the 24th December A.D. 1077, when the 7th *tithi* of the bright half of Pausa ended 17 h. 21 m., and the *Uttarāyana-samkrānti* took place 5 h. 35 m., after mean sunrise. And the date on which the grant was written regularly corresponds, for the *Kārttikādi* Vikrama year 1135 expired and the *pūrṇimānta* Chaitra, to Sunday, the 24th February A.D. 1079, when the 6th *tithi* of the dark half of the *pūrṇimānta* Chaitra ended 21 h. 42 m. after mean sunrise. From this it may be seen that the grant was written as much as fourteen months after the making of the donation. The date given in lines 28 and 29 for the accession of *Sōḍhadēva*'s father *Vyāsa* must fall in the *Kārttikādi* Vikrama year 1087 expired, because of the three years which might be denoted by the number 1087 that year alone contained an intercalary *Jyāishṭha*; and for the *Kārttikādi* Vikrama year 1087 expired the date corresponds to Monday, the 31st May A.D. 1031, when the 8th *tithi* of the bright half of the second *Jyāishṭha* commenced 9 h. 47 m. after mean sunrise. It may seem somewhat remarkable that the week-day should have been connected here with a *tithi* which commenced so late in the day, but this is no reason for suspecting the authenticity of the date; the accession of *Vyāsa* may have taken place late in the afternoon.

This last date, of A.D. 1031, is earlier than any date known to us from the inscriptions of the Kalachuris of Chēdi.³ In my opinion, it shews that the founder of this new branch of the Kalachuri family, *Rājaputra*, cannot be placed later than the beginning of the 9th century A.D.

TEXT.⁴

First Side.

- 1 Ōm⁵ svasti [||*] ⁶Abhūt-Sōmah sauṃya-dyutir-amṛita-sūr=Atri-tanayaḥ sphurach=chūḍā-ratnaṃ Smara-vijayinaḥ saṃhṛita-tamāḥ | Vu(bu)dhas=tasmāj=jātaḥ kumuda-vi[śa]da-jnā(jñā)na-sadanaṃ grabagrāma-slā(ślā)gh-ā v a d h i r=a d h i k a-saubhāgya-vasatiḥ || [1*] ⁷Tasmāj=jaga-
- 2 t-patir=apatyam=abhūt=prabhūta-bhūpāla-maṇi-chumvi(mbi)ta-pādapadmaḥ | sadma tvishāṃ vinaya-vēsma(śma) Purūravāḥ sa yasy=Ōrvvasi(śi) priyatamā puratō va(ba)bhūva || [2*] ⁸Taj-janmā Naghu(hu)shaḥ kṛitī nijapada-bhramāsa(śa)-bhramākūta-bhṛid=yēn=⁹ōttapta-

¹ Compare in the 'Sirkār Gorakhpūr' names of parganas like Bamhūpāra, Bhāwāpāra, Chilūpāra, Dhurīpāra, etc., in Sir H. M. Elliot's *Races of the N. W. Provinces of India*, Vol. II, p. 119.

² See E. Thornton's *Gazetteer* (1857), p. 333. 'Deoha' clearly is the *D[ar]vāḥ*, which we have in *D[ar]vāḥ-pāra* in a plate of Jayachandra of Kanauj, *Ind. Ant.* Vol. XVIII, p. 138.

³ Their earliest certain date corresponds to the 18th January A.D. 1042; compare my *List of North. Inscr.* No. 407. The *Śaṅkaragana* who was a contemporary of *Kōkkalla I.* may have been the *Śaṅkaragana I.* of the present inscription.

⁴ From impressions supplied by the Curator of the Lucknow Museum.

⁵ Denoted by a symbol.

⁶ Metre: Śikharīṇī.

⁷ Metre of verses 3 and 4: Śārdūlavikrīṇī.

⁸ Metre: Vasantatilakā.

⁹ Originally =yīn= was engraved.

- 3 *tapaśchayēna* *bhagavān*=Indrō=py=animādraḥ *kṛitah* | *tasy*=āśi(sī)=jita-
saptasāgaradharā-dhuryaḥ kulē Haihayas=tad-vansyaḥ¹ *Kṛitavirjja*(ryya)-bhūbhṛid-
abhavat=trātā trayi-vartmanah || [3*] *Tasmād*=bharttur=abhūn=nirantarānamat
kshmapāla-chūḍāma-
- 4 *ni-chehhāyā-samvalit*² āngghripaṅkaja-rajāḥ śrī-Kārttavirjō(ryyō)=rjjunah | yēn
ānanyasamāḥ *kramān*=nripatayaḥ kimchit=kalōllīlayā³ dōrddanḍa-[jvar]i[na]h⁴
parēna [va(ba)]li[nām=ā]vā(bā)lyam=ullaṅghitāḥ || [4*] *Tatah*⁵ *prabhru*-
samtatē
- 5 *prapata-rāja-rāji-si*[ra]ś-charach-charaṇapaṅkajadvitaya-rēpur=āśi(sī)=kulē [1*] *Ay*-
mukha-jaya-Krath-ākramaṇa-siddha-Kālamjaraḥ sphurat-paravarūthini-jaradaraḥ ya-
dāvanalāḥ || [5*] ⁶*Kalachuri*-tilakaḥ sa(sa)trūn(ñ)=jitvā
- 6 *rājyam* dadau *laghu*-bhrātuh | sa śrī-Lakshmanarājāḥ *Své*(śvé)tapadam yub
punar=jjitavān [(1)] [6*] ⁷*Tad*-vansē *visva*(śva)-bharttā *turaga*-⁸patim-
athō *va(ba)ddhāvān*=Vāhalim yō yaś=cha prā[chi]-kshitīndr-ānavasara-karaṇa-
khyāta-dōrddanḍa-*carppah* | *rājā* śrī-
- 7 *Rājaputraḥ* sa *bhaya*bhṛid-abhaya-vyaktir=avyakta-garvvaḥ *kharv*vīkurvvan *Kiriti*-
prabhṛiti-nripa-yaśō-rāsi(sī)m=āśi(sī)n=manishi || [7*] *Tatah*⁹ *prithvinātha*
dvitaya-varaṇiyah *prabhur*=abhūt=pramāthi sa(sa)trūnām samiti *Śivarājah*
- 8 *Śivi*(bi)r=iva | *sutas*=tasmāj=jātaḥ sa *rapakarūṇa*-vṛittir=asakṛit-kshma¹⁰
nāthaḥ *kshēmi* *prakṛiti*-saralāḥ *Sam*(sam)karagaṇah || [8*] ¹¹*Tat*-sūnur-
ddhāma *dhāmna* *nidhir*=adhika-dhiyām *Bhōjadēv*-āpta-bhūmiḥ *pratyāvṛitya*
*prakārah*¹² *prathī*-
- 9 *ta*-prithu-yaśā(śā)ḥ śrī-Guṇāmbhōdhidēvaḥ | yēn=ōddām-aikadarppa-dvipa-ghaṭita-
ghaṭ-āghāta-samsakta-muktā-sōpān-ōddantur-āsi-prakāṭa-prithu-pathēn=ābṛitā *Gauḍa*-
lakshmīḥ || [9*] *Tasya*¹³ *cha* jyāyāsi jāyā mūrtyā
- 10 *kirttir*=iv=āparā | *nāmna* śrī-Kāmchanadēvi *Lakshmīr*=iva *Mura*-dvishah || [10*]
¹⁴*Tasmād*=asyām=anindyadyuti-rachita-phañi(nā)chakra[bhṛi]d-vakraśalyah *śrīmān*=
dēvaḥ *sitārchchih*-sita-vitatayāsā(śā)ḥ *krānta*-bhūr=Ullabh-ākhyah [1*]
- 11 *drishṭē* *yasminn*=akasma(smā)t=tarala-mṛigadrīśām [m]ékhalāgramthi-[d]antah¹⁵
trāsād=astram *cha* sa(sa)trōḥ skhalati kara-talād=arthinām=artha-trishṇā || [11*]
Yad-bhūmyā *vra*(bra)hmalōkāyitam=udadhim=iva *prāpya* *yam* *cha* *trasantaḥ*
paksha-chohhēttur=mma-
- 12 *bēndrād*=dravād=avanibhṛitō=py=āsatē *kshēma*-bhājah | yō=sau *sāmanta*-sēvāmjali-
valaya-valat-pāḍapadm-āśrita-śrīḥ *sāmyāt*=simḍūra-mudrā-prabhṛitibhir=udayakshma-
bhṛitō *datta*-vārttaḥ || [12*] *Bhrāṭṛi*-snēhāch=cha yē-
- 13 *na* *prasara*d-uru-kari-śrēṇi-saṅgha[ṭṭa]-chaṇḍa-prājy-āji-khyāta-saṅga-prahata-ripu-
si(sī)rah-pūjita-kshmatālēna [1*] *kli*[pta]h¹⁶ *si*[m]ghā(hā)sanasthō nija-vijayi-pa[d-ō]
ddhāra-*Dhārāvanīśa*-[hrishya]t-¹⁷*sēnā*-jayaśrī-haṭhaha-

¹ Read *-vamsyah*.² Read *-samvalit*.³ Apparently altered to =*kalōllīlayā*; read =*kalēr*=*llīlayā*.⁴ The *aksharas* in brackets are doubtful, here and in the following words of this verse.⁵ Metre: *Prithvi*.⁶ Metre: *Āryā*. Every *akshara* of this verse is quite clear.⁷ Metre: *Sragdharā*.—Read *Tad-vamśē*.⁸ The *ga* of *turaga* was originally omitted and is engraved below the line.⁹ Metre: *Śikharinī*.¹⁰ Read =*kshamā*.¹¹ Metre: *Sragdharā*.¹² Read *prakāra-prathī*-(P); this alteration seems to have been made in the original.¹³ Metre: *Ślōka* (Anuṣṭubh).¹⁴ Metre of verses 11-13: *Sragdharā*.¹⁵ Read *-dantas*. I take *danta* to be used in the sense of 'a pin.'¹⁶ Originally *kṛipitah* was engraved, but the sign of the vowel *i* has been undoubtedly struck out, and *pat* may have been altered to *pta*.¹⁷ I am doubtful about the correctness of the two *aksharas* in brackets. Only the letters *h* and *y* are certain.

- 14 rapa-kalā-dhāma **Bhāmānadēvaḥ** || [13*] Putrah¹ śrī-Guṇasāgarasya
Madanādēvyā[m] satām=agraṇir=nnēmīr=nyāya-pathasya vēsma(śma) yasa(śa)sām
dharman-āmbhasām=arṇavaḥ | śrīmān=āsrita-vatsalaḥ Kali-kalā-vai-
- 15 mukhya-mukhya-sthitiḥ sthēmaḥ sthānam=a[na]lpatā paripatēr=²bharttā
kshitēr=ddhīra-dhīḥ || [14*] Yaś=chintāmaṇir=arthinām prapayinām pratyagra-
kalpakalpadrumaḥ³ sū(sū)rah sūrisarōruḥ⁴āritarunivaktrāvji(bji)nī-
- 16 chandramāḥ | yasmin=Vāsukisaṃgi-Maṃga(da)ra-guru-grāh-āhrit-ārisriyaḥ saṃgāt
sērsham=aśaśra(sra)m=aśru-salilam Vidyādharī-chakshushām || [15*] Ētasmāt=
tanayaḥ kṛitī nijaguna-vyāpt-ākhalakshmatā-
- 17 [bhāsvatsubhra].⁵yasa(śa)s-tiraskṛita-śaśichhāyāḥ prabhur=bhūdharah | kāntyā
[su]ddha-chitir=gupaiḥ sumanasām=apy-āspadam vismayē sa śrī-Saṃ(śam)kara-
pūrvva ēsha gaṇavān Dēhaṭṭadi(dē)vy-ātmajaḥ || [16*] Śrī-Bhāmānad-
dīpād=
- 18 pari kṛitākṛita iv=āparō dīpaḥ | nijakṛita-maṇḍala-vēsma(śma)ni sa śrī-
Saṃ(śam)karagaṇō dēvaḥ || [17*] ⁷Jyōtan=ēv=ōdgata-pūrnṇa-sāgara-vidhōr=
Llakshmir=ivā Śrī-patēḥ saubhāgyē Girij=ēva Manmatha-ripōḥ sā(śā)-
- 19 kh=ēva kalpāṃghripē | saubhāgyōdgama-bhūtibhāra-vai(vi)saratkand-ōllasatkandāḥ
tasya śrīyuta-Mugdhatunga-nripatēḥ⁸ dēvi tu Vidyābhidhā || [18*] Dāridra-
[dru]ma-duḥkhasamtatilatām chobhēttum⁹ kuṭhār-ōpamō garjja-
- 20 tkurjarasamgha-tūla-hutabhu[g=bhū]pāla-chūdāmaṇiḥ || [1] mādyat-prānta-samasta-
bhūpati-ghatā-sphōṭē Kṛitānt-ōpamō dēvaḥ śrī-Guṇasāgarō giri-samaḥ¹⁰ tasyāḥ
pra[sū]tō nripaḥ || [19*] Sau(sau)rēḥ Śrīr=iva Rōhin=iva Hi-
- 21 magōr=Ggeur=iva Gaṅgābhṛitāḥ Paulōm=iva Sa(śa)takratōḥ samabha[va*]t=tasya
priyā Rājavā | sā lēbhā Śivarājam=ātmajam=Aja-prakhyam kshitau
visru(śru)tam sau(sau)ry-audārya-guṇ-ālayam lalitayā pūtam girā satyayā || [20*]
- 22 Sa śrīmān=nripa-śāśa(sa)nān=nripa-padam saṃprāpya sarvv-arthinām=āśī(sī)t=
kalpamahātarur=nnijakul-āmbhōjākarē bhāskarah || [1] kimcha spha(sphā)ratarā-
pratāpadahana-jvālāvalī-tāpitā nirvāṇam katham=apy=ayur=na
- 23 jaladhīm tṛttv=āpi yasya dvishah || [21*] Mukhyām¹¹ vṛttim kila Kṛita-yugē
yah Prithāv=ēva jā(yā)tō yas=Trētāyām=avasita-ripau Rāmabhadre prasiddhah |
jyēshtham Pāṇḍōḥ sutam=abhaja[ta*] Dvāparē yah Kalau sa śrī-Bhā-
- 24 mānē vinihita-padē¹² rājatē rāja-śavda(bda)ḥ || [22*] ¹³Tasmāt=sūnur=asūn=iva
kshiti-talē yah pālayan¹⁴ prāṇinah punyāchāravisēsha-tōshita-gurugrāmō guṇa-
grāhinām¹⁵ || [1] jātaḥ Saṃ(śam)kara ēsha Saṃ(śam)karaga-
- 25 nō dēvaḥ sadarppa-dvishām vidhvamsa.¹⁶prasahō=rthi-kalpavitāpi
Sūgalladēvyām tataḥ || [23*] Tatō¹⁷ Bhimō=bhīshṭō naya-vinaya-saṃpatti-
nilayō Yaśōlēkhyādēvyās=tanaya iva Kuntā[h] pitṛi-padē | [ha]san
- 26 [sa]llōkṣnām pramadabharajanm-āśrusalilaiḥ su(su)bhāi[h*] kumbhām[bhō*]bhīḥ
snapita-varamūrttir=vvilasati || [24*] Asmin¹⁸ rājya-parichyutē vidhi-vasā(śā)l=
Lāvanya[va]tyām=abhūd=dēvyām śrī-Guṇasāgarān=narapatēr=utpa-

¹ Metre of verses 14-16: Śārdūlavikṛīḍita.

² Read -kalpadrumaḥ.

³ The akṣaras in brackets are doubtful; read bhāsvachchhūbhra-.

⁴ Metre: Āryā.

⁵ Read -nripatēr=.

⁶ Read -namas=.

⁷ Read -padō. Originally rājītō was engraved, but it has been altered to rājatē.

⁸ Metre: Śārdūlavikṛīḍita.

⁹ Originally guṇigrāhinām was engraved.

¹⁰ Originally guṇigrāhinām was engraved.

¹¹ Metre: Śikharīṇī.

¹² Originally piri^o was engraved.

¹³ Originally sarōruḥōri^o was engraved.

¹⁴ Metre of verses 18-21: Śārdūlavikṛīḍita.

¹⁵ Read chhēttum.

¹⁶ Metre: Mandākrāntā.

¹⁷ Originally pāliyan was engraved.

¹⁸ Originally vidhvamsē was engraved.

¹⁹ Metre: Śārdūlavikṛīḍita.

- 27 nna-janmā tataḥ || (1) śrī-Vyāsaḥ sa Parāsa(śa)rād=iva munēr=Vyāsaḥ si(śi)su(śu)tvê=pi na prāptāḥ¹ tyāga-day-ādibhir=ggūṇa-gaṇaiḥ² yasy=āparē tulyatām || [25*]
³Kim=vā Va(ba)liḥ kim=ayam=Ushṇamarām(rī)chi-sūnuḥ kim Rāghavaḥ kim=u
- 28 Nṛigaḥ kim=ayam Yayātiḥ | évaṁ janaiḥ prati-dinaṁ paritarkkayadbhir=yaḥ stūyatē jagati Sasva-pa[d]ē⁴ p[r]ati[shṭha]ḥ || [26*] Śrīmān⁵ Sasva-pit[uh] pa[dē] gatavati Jyēsthē dvitīyē kramād=vārē Śitaruchēḥ sudhā-
- 29 sudhavalē pakshē=shṭami-vāsarē | saptāsi(śi)ti-samanvitē dasa(śa)-guṇē samvatsarāṇām⁶ satē bhūpō Gōkulaghaṭṭa-bhāji kṛtākē bhāty=ēsha lavdhō(bdhō)dayaḥ || [27*] Tat-putraḥ sukṛitair=jjanasya nṛipatām=āsāditaḥ [svai]-
- 30 r=guṇaiḥ⁷ rājā nirjita-Kārttavīryacharitaḥ śrī-⁸Sōḍhadēvō=dhunā | satya-tyāga-vivēka-vikrama-naya-vyāpāra-visphārita-Prālēyāchalachūlanirmmala-yaśō-dhauta-trilō-
- 31 kītalaḥ || [28*] ⁹Praudhapratāpa-paritāpa[chay-āri]bhūpa-kīrttēḥ sṛitā jalanidhīn=api sapta tū[r]ṇam | Laksh[mī]ḥ punar=jjaladhi-madhya-nivāsa-sai(sai)tyāt¹⁰ śrī-Sōḍhadēva-charaṇam śara-

Second Side.

- 32 ṇam prayātā || [29*] [Sa*]¹¹ śrīmat-Sōḍhadēvō=yam Sarayūpāra-jīvitam | viduśām=agraṇā[h*] stū(śū)rō dharmma-rāsi(śi)ḥ prajēsva(śva)raḥ || 30 [||*] Svasti | Dhuliśghaṭṭa-samāvāsāt |¹² paramabhaṭṭāraka-mahārājā-
- 33 dhirāja-paramēsva(śva)ra-śrī-Maryādāsāgaradēva-pādānudhyāta-para m a b h a ṭ ṭ ā r a k a - mahārājādhirāja-paramēsva(śva)ra-paramamāhēsva(śva)ra-śrīmat-Sōḍha d ē v a - p ā d ā ḥ kalyāṇināḥ¹³ | mahārājñi- |
- 34 mahārājaputra- | mahāsāndhivigraḥika- | mahāmahamṭaka- | mahāpratihāra- | mahāsēnāpati- | ¹⁴mahāakshapaṭalika- | mahāsāchanika- | mahāsrēshṭhi- | mahādānika- | mahāpāndhākulika-¹⁵ | sau(śau)lkika- | gaulki(lmi)ka- |
- 35 ghaṭṭapati- |¹⁶ tarapati-vishayadānika- | duṣṭasādhaka- | khaṇḍavāla- | valādhīra-¹⁷ prabhṛitān samasta-rājapurushān | bhaṭṭamākutika-¹⁸ | mahattama-pramukhān(ñ=) janapad-ādīn¹⁹=¹⁹cha mānayanti | vō(bō)dhayanti | samājñāpaya-
- 36 nti cha | yathā | Viditam=astu bhavatām | ²⁰Gūṇakala-vishaya-pratīva(ba)ddha-Ṭikarikāyām pūrvvē Annāḍha | uttarē Ṭikari | dakṣiṇē Avaḍachana | paśchimē Chandulīā | atra chatur-āghāṭ-ābhyantarē Mahīāri-pāṭaka- | Asathī-pāṭa-

¹ Read *prāptās* = .² Read *-gaṇaiḥ* = .³ Metre: Vasantatilakā.— Read *Kim vā*.⁴ The letters in brackets in this line are doubtful. *Sasva* seems to be certain both here and in the next verse.⁵ Metre of verses 27 and 28: Śārdūlavikrīḍita.⁶ Read *samva*°.⁷ Read *-guṇaiḥ*.⁸ Originally *śrīsa* seems to have been engraved.⁹ Metre: Vasantatilakā.—The first Pāda of this verse is very indistinct in the impressions.¹⁰ Read *-śaityāch* = .¹¹ Metre: Ślōka (Anuṣṭubh).¹² All the signs of punctuation from here to the word *yathā* in line 36 are superfluous.¹³ Here and in other places below the rules of *samdhī* have not been observed.¹⁴ Read *mahāksa*°.¹⁵ This word is quite clear in the impressions; I am unable to explain it.¹⁶ This sign of punctuation seems to have been struck out.¹⁷ Read, perhaps, *valādhīra*; but the term is unknown to me.¹⁸ Read, perhaps, *bhaṭṭa*-*mākutika*-; but the latter term is unknown to me.¹⁹ Originally *janapadā* *dīnī*= was engraved.²⁰ From here to *śamdhī* in line 47 the text forms one sentence, and the signs of punctuation in this part are really superfluous.

- 37 ka- | Thiula-pāṭaka- | Vapiā-pāṭaka- | Duāri-pāṭaka- | Chchhidāḍāṭem bhā-
kshētrēshu dēvakuṭīkāśhṭha-parimita-vinsati-nālu-ka-parimāṣā bhūmiḥ || aṅkēn=āpi
bhūmi-nālu 20 bhūmi-ya[m] sa-jalasthalā | s-ā-
38 [mra(mra)]madhukā² si-vanavāṭikā | sa-garttōsharā | sa-lōhalavanākarā | sa-
gōprachāra-triṇa-pūrita-chatuṣṣimā-paryantā | samasta-bhāgabhogakara-rājapratyāḍāya-
samētā | akiñchidgrāhyā | achāṭabhaṭapraṇṇā(śā)
39 [arihrita-sarvvaṇḍā | ā-chandrārkkakshityudadhi-samakālam chatustrinsat-
samvatsar-³ādhik-aikādasā(śā)-sa(śā)ta-samvatsar⁴ Pausha-māsi su(śu)kla-
saptamyām Ravi-dinē | ady-ōttarāyana-samkrāntau mahānadi-Gaṇḍakyām vi-
40 dhivat snātā āchamya ishṭadēvatāpūjā-samanantaram sadarbha-ti[lō]daka-pāṇinā
mātāpitūr-ātmanas=cha puṇyāyāsō(śō)-bhivridhayē paralōka-srēyōrtham cha |
Mahālikiya-paṇḍitaNimvō(mbō)putra-Kā-
41 sya(śya)pagōtra-tripravara-Vājasaneyāsā(śā)khi-paṇḍita-Chchhāmchchhi-⁵ Māthura-
dikshitaRāmaputra-Dhaumragōtra-tripravara-Va(ba)hvrichasā(śā)khi-dikshita-Gautama-
Hastigrāmiya-dikshitaSridharaputra-⁶Pārāsa(śā)ragōtra-tripravara-Mā-
42 dhyamindasā(śā)khi-agnihōtri-Bhāskara- | Nikhatigrāmiya-dikshitaDēvesva(śva)ra-
putra Kusi(śi)kagōtra-tripravara-Mādhyamindasā(śā)khi-agnihōtri(tri) - V ā h m a ṭ a -
Māthura-vrā(brā)hmapaDēvadharaputra-Dhaumragōtra-tripravara-Va(ba)hvricha-
43 sā(śā)khi-dvivēdi-Mālā- | Tālikiya-paṇḍitaGadādhara-putra-Sāvarṇagōtra-pañcha-
pravara-Chchhandōgasā(śā)khi-paṇḍita-Dāndū- | Sāṅkasasthāniya-Vri(bri)haspati-
putra-Kātyāyanagōtra-tripravara-Va(ba)hvrichasā(śā)khi-vrā(brā)hmapa-Māḍha- |
44 K[u]lāndh[ī]ya-Mahānandaputra-śrīSā(śā)ṇḍilyagōtra-tripravara-Chchhandōgasā(śā)khi-
paṇḍita-Jālū- | Nāgara-paṇḍitaMāhilaputra-Kō(kau)ṇḍinyagōtra-tripravara-
Chchhamdōgasā(śā)khi-paṇḍita-Bhāskara- | Kaṭaughanagrāmiya-paṇḍi-
45 taBhōgūputra-Rāhulagōtra-tripravara-Va(ba)hvrichasā(śā)khi-paṇḍita-Sidhū- | Kahalliya-
bhaṭṭaSundara-putra-Bhāradrā(dvā)jagōtra-tripravara-Va(ba)hvrichasā(śā)khi-bhaṭṭa-
Si(śi)vadāsa- | Kahalliya-ta(bha)ṭṭaJākhūputra-Bhāradvājagōtra-triprava-
46 ra-Va(ba)hvrichasā(śā)khi-Tihuyapasīha- | Kahalliya-bhaṭṭaJākhūputra-Bhāradvāja-
gōtra-tripravara-Va(ba)hvrisa(cha)sā(śā)khi-Gōvindāyichcha- | Tikarikiya-[Bhā]skara-
putra-Krishnātragōtra-⁷pañchapravara-Yajusā(śā)khi-vrā(brā)hmapaSam(sam)kara-
dēv-
47 bhyaś=chaturdasa(śā)-vrā(brā)hmapāṇḍhyō yathālikhita-gōtrapravaraḍibhyaḥ pāṭikayā
vibhajya sā(śā)sanikṛitya sampradattā samābbhiḥ || Sarvvair=ēva bhavadbbhir=
anumantavyā | tannivāsi-janapadais=ch=āmishām ājñāsa(śra)vapa-vi-
48 dhēyibhūya samasta-bhāgabhogakara-hiranya-pratyāḍāyān dadadbbhiḥ sukham
sthātavyam || Atra vibhāgē paṇḍita-⁸Chchhāmchchhikasya¹⁰ bhūmi-nālu 1½
vrā(brā)hmapa-Gautamasya bhūmi-nālu 1½ ta[th]ā Bhāskarasya
49 nālu 1½ Mālhekasya bhū-nālu 1½ Dāndūkasya nālu 1½ Māḍhasya nālu 1½
dvi-¹¹Bhāskarasya nālu 1½ Sidhūkasya nālu 1½ Si(śi)vadāsasya nālu 1½
Vāhmaṭasya nālu 1 Jālūkasya nālu 1
50 Tihuyapasīhasya nālu ½ Gōvindāyich[ch*]asya nālu ½ Sam(sam)karadēvasya
vasatyā saba bhūmi-nālu 3 ēvaṁ vrā(brā)hmapa 14 bhūmi-nālu 20 dānam=
ētat sarvvair=ēv=āsmad-vansajaiḥ¹² pari-

¹ Read -vinsati-.² Read -samvatsarē.³ Read °kā | sa-vana °.⁴ Read -Chchhāmchchhi-.⁵ Read chatustrinsat-samvatsar-.⁶ Perhaps altered to -Parā°.⁷ I am slightly doubtful about this reading; what is actually engraved looks like K[u]lāndhā | ya-.⁸ Read -Kishnātragōtra- (?).⁹ Originally paṇḍita- was engraved.¹⁰ Read -Chchhāmchchhi-.¹¹ Dvi- apparently stands for dvitīya-.¹² Read -vansajaiḥ.

- 51 pāṇiyan̄ || ○ || Tathā cha dharmma-slō(ślō)kāḥ || Saṁ(śaṁ)kham¹ bhāṣa-
 āsanam̄ chchhatram² var-āsvā(śvā) vara-vāraṇāḥ | bhūmi-dāna-ya chhūmān
 phalam=etat=Purandara || 1 || Sarvvēshām=ēva dānānām=ēka-jannu-ānugam
 52 phalam | hāṭaka-kshiti-gauriṇām sapta-jannu-ānu(nu)gam phalam || 2 || Bhūm-
 yaḥ pratigrihṇāti yaś=cha bhūmim̄ prayachchhati [*] ubhau tau paṇi-
 karmṇāpau niyatau³ svargga-gāminau || 3 || Shashṭhim̄(śṭim̄) varsha-sāna-
 53 śrā(śrā)pi svarggē tishṭhati bhūmi-daḥ | āchchhētā ch=ānumantā cha tāny=ē.
 narakē vasēt || 4 || Sva-dattām para-dattām vā yo harēt=ā
 vasundharām⁴ | sa viśṭhāyām kṛimīr=bhūtvā pīṭhibhiḥ saha pachyatē
 [||*] 5 [||*]
 54 Gām=ēkām svarggam=ēkam vā bhūmēr=apy-ēkam=amgulaḥ | harām=5narakau=
 āyāti yāvad-āhūtasamplavam̄ || 6 || Sva-dattām para-dattām=6vā yatnād-rakṣa-
 Yudhisṭhira | mahim̄ mahibhritām śrēṣṭha dānāt⁷ śrēyō=
 55 nupālanam̄ || 7 || Aham̄ Rāghava Mārkaṇḍaḥ sapta-kalp-ānujivakāḥ |
 sru(śru)tō na mayā dṛishṭaḥ svayamdatt-āpahārakāḥ || 8 || Va(ba)hubh-
 vvasudhā dattā rājabhiḥ Sagar-ādibhiḥ [*]
 56 yasya yasya yadā bhūmis=tasya tasya tadā phalam̄ || 9 || Iti⁸ kamaladal-ānuvambha-
 lōlām⁹ śriyam=anuchintya jīvitam̄¹⁰ cha | sakalam=idam=udāhṛitam̄ ch.
 vu(bu)ddhvā na hi purushaiḥ
 57 para-kīrttayō vilōpyāḥ || 10 || Samvat¹¹ 1135 Chaitra-va(ba)hula-shashṭhyām ||
 Ravi-dinē | likhitō=yam̄ tāmva(mra)-paṭṭa ādēsa,śa-naivam̄(bam̄)dhika-śri-
 Janakēn=ēti || ○ ||
 58 || tha || tha || || tha || Maṅgalam̄ mahā-śrīḥ || tha ||
 59 Sva-hastō=yam̄ mahārājādhirāja-śrīmat-Sōḍhadēvasya ||

No. 10.— LUCKNOW MUSEUM PLATE OF KIRTIPALA;

[VIKRAMA.]SAMVAT 1167.

By F. KIELHORN, PH.D., LL.D., C.I.E.; GÖTTINGEN.

This plate was brought by a tenant to a fair at Bhatpar in the Gōrākhpur district, United Provinces, and sold as waste to a copper-smith. Dr. W. Hoey who heard of this followed up the plate to another district and, having recovered it, presented it in September 1898 to the Provincial Museum, Lucknow. I edit the inscription which it contains from excellent impressions, sent to Dr. Hultzsch by the late Mr. E. W. Smith.

This is a single copper-plate which measures about 11½" broad by 1' high, not including a semicircular projection¹² which rises from the middle of the top and is about 4" broad and 3¼" high. On the front side of this projection there is a neatly engraved figure of the god Vishnu

¹ Metre of verses 1-9: Ślōka (Anusṭubh).

² Perhaps altered to *niyataḥ*, which it should be.

³ Read *haran*.

⁴ Metre: Pushpitāgrā.

⁵ Read *manushya-jīvitam*.

⁶ Similarly shaped is e.g. the Gurmha (in Gōrākhpur district) plate of Jayāditya II., *Jour. Beng. As. Soc.*

Vol. LXX. Part I. Plate i. In the Gōrākhpur grant of the time of the same prince (see my *List of North. Inscr.* No. 604) the projection is at the proper right side of the plate.

⁷ Read *chhatram*.

⁸ Originally *vasundharām*.

⁹ Read *dānāch*.

in his boar incarnation,¹ with a small figure of a woman (representing the earth) resting, as it seems, on one of the god's arms. The god himself is represented as standing over a serpent, in front of which there is a flower. On the back the projection contains the engraving of a conch-shell. The writing commences immediately beneath the projection and covers the whole of the first side and two-thirds of the second side of the plate. It is well preserved nearly throughout. The size of the letters is between $\frac{5}{16}$ and $\frac{7}{16}$ ". The characters differ little from the ordinary Nāgarī. The language is Sanskrit, but some of the names towards the end of the inscription appear in their vernacular forms or rather in forms based on them. Lines 2-12 contain six verses, five of which give the genealogy of the donor, and lines 21-33 contain benedictive and imprecatory verses. Of the introductory verses two (verses 2 and 6) are incorrect. Owing to carelessness on the part of the writer or engraver the text, besides numerous minor errors, contains several corrupt passages, one or two of which I am unable to correct with confidence. In respect of orthography it may suffice to state that the letter *v* denotes both *v* and *b*, and that the dental sibilant is often used for the palatal.

The inscription records a grant of land by the *Paramabhaṭṭāraka Mahārājādhirāja Paramēśvara*, the devout worshipper of Mahēśvara (Śiva), the glorious *Kirtipālādēva*, who by inheritance had obtained the lordship over *Uttarasamudra*, and who meditated on the feet of the *P.M.P.*, the devout worshipper of Mahēśvara (Śiva), the glorious *Vikramapālādēva*, who had acquired the lordship over *Uttarasamudra* by his own arms (ll. 18-21). The document differs from other grants in this that it does not contain an order to officials and others, but simply records the fact that the king made a certain donation.

The text, after the auspicious word *śrīh*, commences with the words "this is the own hand of the glorious *Kirtipālādēva*," words such as we ordinarily find at the end of a grant. Then follow the words *ōm ōm svastī*, and a verse glorifying the god Paśupati (Śiva). After that, verses 2-6 give the donor's genealogy. There was a king (*nripa*) *Bhuvanapāla*, an ornament of the rulers of the earth of the family of *Sāvarṇi* (*Manu*), descended from the Sun. His son was *Vikramapāla*, who by his own arms acquired the sovereignty over *Saumyasindhu* (i.e. *Uttarasamudra*). And his son again was *Kirtipāla*.

This *Kirtipāla*, having worshipped the god *Nārāyaṇa* (*Vishnu*), in his presence, on a date which will be considered below, gave two villages to the *Brāhman*, the *Thakkura* *Prahasitaśarma*, who was born at a *bhaṭṭa*-village, viz. the village of *Ḍavirāmakula* in the *Śrāvastīya-vishaya*, belonged to the *Gautama gōtra*, and was a son of the *Paṇḍita* *Viśvarūpa* and grandson of the *Paṇḍita* *Kṣēṣa*. Both villages were in the *Daradagaṇḍakī* country (*ḍāḍā*); one was the village of *D[amba]ūli* (or perhaps *Dēvaūli*), which belonged to (the) *śaśhō[ravi?]śā* (district), and the other the village of *Vikara*, belonging to (the) *śhō[thā?]viśā* (district; ll. 12-17).

The names of three of the localities mentioned in the preceding paragraph unfortunately are partly so indistinct in the original that I am unable to make them out with certainty; and I have not succeeded in identifying any of the places on the maps at my disposal. With the passage describing the birth-place of the donee we may compare above, Vol. III. p. 357, l. 38, *Śrāvastī-maṇḍanē(lē) Kāśīllī-bhaṭṭagrāma-vinirggatāya*;² the name *Daradagaṇḍakī* must be connected with the river *Gaṇḍakī* (the Great or Little *Gandak* in the United Provinces); and the names of the two districts remind one of similarly ending names of districts in the grants

¹ Compare *Gupta Inscr.* p. 159. In the *Jour. Beng. As. Soc.* Vol. XVII. Part I. p. 306, Captain J. C. Cunningham, describing a sculptured representation of *Vishnu* as the boar, at *Pathārī*, says: 'The statue is about 4½ feet high; it is covered with figures disposed in ranks; it has a diminutive woman hanging by the tusk of the god, and the remains of a serpent may be traced on the ground on which it is standing.'

² Compare also *Ind. Ant.* Vol. XVII. p. 121, l. 35, *śrī-Maḍhyadē-āntaḥpādi-Takkārikābhaṭṭagrāma-vinirggata*.

of the kings of Kanauj. With the name Davirāmakula one may perhaps compare the name 'Ramkola,' which occurs in the Gōrākhpur district, *Indian Atlas*, sheet No. 102, long 83° 53' lat. 26° 54'.

The donation, in lines 15 and 16, is stated to have been made on the second *tithi* of the bright half in the month Phālguna, at a *saṁkrānti* of Bṛhaspati (or Jupiter), on a **Saturday**, in the year 1167, given in words; and the same *data*, without the reference to Jupiter's position, are repeated in figures in line 40. So far as I know, in quoting a *saṁkrānti* of Jupiter the date is quite unique. For the Vikrama year 1167 expired it regularly corresponds to **Saturday, the 11th February A.D. 1111**, when the second *tithi* of the bright half of Phālguna commenced 0 h. 47 m. after mean sunrise. As the true longitude of Jupiter at mean sunrise of this day by the *Sūrya-siddhānta* was 1° 0' 2' 5', Jupiter had entered the sign Vṛṣabha 12 h. 2 m. before mean sunrise of the given day. The result shews that, instead of saying *Bṛhaspati-saṁkrāntau*, the writer might have said, more accurately, *Bṛhaspatiṛ-Vṛṣabha-saṁkrāntau* 'at the time of Jupiter's entrance into the sign Vṛṣabha.'¹

After recording the grant, the inscription in line 21 ff. has two verses containing prayer addressed to the Earth, and after that a number of benedictive and imprecatory verses, introduced by the words "speech of the sacrificer (or donor) after granting the land." These verses are followed in lines 34-39 by the names of 17 persons, each of which has prefixed to it a title shewing his rank or occupation or official position. Of these titles those which I do not remember to have met elsewhere are *Āṣṭavargika*, *Daivāgārika*, *Mahārthasāsanika*(?) and *Saṁkadhārīn*. Of the names themselves *Ānūka*, *Jāgūka*, *Kṣavapadumā*, *Mahichanda*, *Mahika*, *Rāndhūka*, *Sāṁkhāka* and *Sihaḍa*² may be drawn attention to.—The grant itself is called in line 39 a *tāmrasya paṭṭakam*; it was caused to be engraved by the *Paṇḍita* Rāndhūka, and engraved by the goldsmith Gaṇeśvara (ll. 39 and 40).

I have not found hitherto any reference to the kings or chiefs of **Uttarasamudra** and am unable to locate their principality. Apparently it must have been somewhere between the Gogra and Gandak rivers and Nêpāl.

TEXT.³

First Side.

- 1 Śrīḥ || Śrīmat-Kirttipāla-
 2 Ōm⁴ ōm svasti || Jayati⁵ sakala-[ś]avda(bda)grāma-nirmamāpa-kalpa(īya)ḥ prapata-
 jana-nikāya-dhva-
 3 sta-samsāra-sa(śa)lyah | Pasu(śu)patir-anuruddh-āsē(śē)sha-dēv-ādi-pālyah priyatama-
 himadhṛiktudmalli-⁶
 4 kāmōda-mālyah || [1*] 7Ās[ī]t=samasta-bhuvana-pratipālana-ladhva(bdha)-samjūah
 Sa(śa)kr-ōpamō Bhuvanapāla-
 5 nṛpa[h*] prasiddhah | yas=Tivrabhānu-samavāpta-sa(śa)rīrayasṭi-Sāvarṇi-va[n]sa-
 vasudhēsva(śva)ra-sē(śē)khara-
 6 śrīḥ || [2*] Tasy=ātma-jā(jō) nijabhuj-ārjjita-Saumāsinvā-⁷rājādhipatya iha
 Vikramapāla-nāmā | ya-

¹ Compare *Ind. Ant.* Vol. XV. p. 113, l. 12, *śavituh Kumbha-saṁkrāntau*.

² See the names *Jāgūka*, *Padumē* and *Sihaḍa* in the list given above, Vol. IV. p. 171 ff.

³ From impressions supplied by the Curator of the Provincial Museum, Lucknow.

⁴ Denoted by a symbol.

⁵ Metre: Mālinī.

⁶ In the original the reading given here is quite clear; I can only suggest *Himadhṛikṛid-malli*.

⁷ Metre of verses 2-4: *Vasantatilakā*. The first Pāda of verse 2 contains three syllables too many.

⁸ Read *-vamsā-*.

⁹ Read *-Saumyasindhu*, a synonym of *Uttarasamudra* in lines 19 and 20 below.

- 7 d-vikramēṇa paripālita-bhūmichakram=ahny=akka-vôdhitam=iva prativuṣṭasāsīt¹ || [3*]
 Yaś=ch=āgam-ōkta-
- 8 vivu(bu)dh-ārva(reche)na-vipra-vrinda-santarppaṇ-ābhyudaya-vriddhi-paramparā vān |
 ni[r]jītya sarvva-va(ba)lavad-ripu-maṇḍa-
- 9 lāni lōbhē sukhaṁ paramam=Indra-nibhaḥ sabhāyām || [4*] ²Tasmād=a[ja*]ni
 sat-putraḥ Kirttipālaḥ pratāpavān |
- 10 Sūryād=iva Manur=ddhanvi mūrttiśrī-jita-Manmathaḥ || [5*] ³Yēn=ōddanḍa-
 vidamva(mba)n-ōdyata-r[ri]hat-kōdanḍa-ni[r*]yach-chhara-
- 11 vrāt-ōddanḍam=akhaṇḍi maṇḍalam=alam [cha]ṇḍa-dvishām khaṇḍasa(śa)ḥ |
 bhūbhṛin-maṇḍala-maṇḍanēna va(ba)linā takvā(tkā)-
- 12 laḍanḍa-srijā⁴ dōrddanḍa-dvaya-vikrama-pratibhuvā prāptam cha rājyam nijam ||
 [6*] Śrī-Stāvastāya-⁵vishaya-Ḍavi-
- 13 rāmak[u]la-grāmē⁶ bhattachāram-ā(ō)tpannāya Gautama-gotrāya paṇḍita-śrī-
 Kēsa(śa)va-nāpra⁷ paṇḍita-śrī-Vinva(śva)-
- 14 rūpa-putrāya ṭhakkura-śrī-Prahasitasa(śa)rmmaṇa(ṇē) vrā(brā)hmaṇāya prakṣhālita-
 pāda-samyag-archchita-mū[r*]ttayē sam-
- 15 pūjita-śrīmad-bhagavan-Nārāyaṇ-āgrē Phāl[gu]nē māsi su(su)kla-paksha-
 dvitīyāyām Vri(bri)haspati-samkrā-
- 16 ntau Sauri-dinē saptashashṭy-adhikē ēkādaśa-savatsarē⁸ śrī-Daradaganḍaki-
 dē[sē(sē)]⁹ Sashō[ravi]śā-pratīva(ba)ddha-Vikar a - grāma¹⁰
- 17 ddha[h]¹¹ D[amva(mba)]ūli-¹²grāma-Shō[thāp]visā-pratīva(ba)ddha-Vikar a - grāma¹³
 saalākau¹⁴ sa-jalau sa-sthalau sāmra-ma-
- 18 dhūkau sa(śva)śisā(mā)-yuktan sā(śā)sanīkṛitya paramata(bha)ṭṭāraka-mahārājādhirāja-
 paramēśva(śva)ra-para-
- 19 mamāhēśva(śva)ra-nijabhujōpārjīti-Ōttarasasū(mu)dr-ādhipatya-śrīmad-Vikram a p ā l a -
 dēva-charaṇānu-
- 20 dhyāta-paramabhaṭṭāraka-mahārājādhirāja-paramēśva(śva)ra-paramamāhēśva(śva)ra-kram-
 āpt-Ōttarasa-
- 21 mudr-ādhipatya-śrīmat-Kirttipālādēvō dadau |(l)| Tvam¹⁵ Dharē sa[r]vva-
 savō(ttvā)nām=ālayē¹⁶ Vra(bra)hma-nirmō(rmmi)tē | ā-
- 22 dhārē sarvva-bhūtānām=ataḥ sā(śā)ntim prayachchha mē || [7*] Lakshmi-
 tū(rū)pēṇa Vishṇau tvam sū(mū)rtti-bhūtā Yi(pi)nā[kina]ḥ | sam-

¹ Here again the writing in the original is quite clear; I would suggest =ahny=arkka-bôdhitam=iva prativuṣṭasāsīt, but am not sure that this is the intended reading.

² Metre: Ślōka (Anuṣṭubh).

³ Metre: Śārdūlavikrīḍita.

⁴ The metre is faulty, but the reading is quite clear in the original, and I do not see what correction could be suggested. The author apparently pronounced *srijā* as *srijā*.

⁵ Read -Śrāvastīya-.

⁶ The sign for *ē* of *māsi* may have been struck out, and in my opinion the reading should be -grāma-bhaṭṭa^o.

⁷ Read -nāprā.

⁸ Read -adhika ēkādaśa-kata-savatsarē.

⁹ After the *akṣhara dē* there are two marks in the plate shewing that something has been omitted, and on the margin at the bottom of the plate is the *akṣhara sē* with the figure 9, indicating the 9th line from the bottom (i.e. line 16).

¹⁰ This sign of *visarga* may have been, and should be, struck out.

¹¹ Possibly the name in the plate may be *Dhānūli*.

¹² Here one would have expected -grāma-.

¹³ Originally *saalākau* was engraved, but the vowel *i* of the first syllable has been struck out; perhaps it was wrongly put in the place of the sign for *au* which one would have expected at the end of the preceding word (*grāma*). I am unable to explain *saalākau*, and can only suggest that the right reading may be either *sa-pātāka* or *sa-pallika*. *Sa-pātāka* occurs frequently in the grants of Northern India of the same period; and for *sa-pallika* compare *sa-pallik-ōpēta* in the Gurmha plate of Jayāditya II., *Jour. Beng. As. Soc.* Vol. LXIX. Part I. p. 91, l. 12.

¹⁴ Metre of verses 7-20: Ślōka (Anuṣṭubh).

¹⁵ Read =dlayō, and further on -nirmītaḥ and dāhāraḥ.

First Side.



COLLOTYPE BY W. GRIGGS.

KIELHORN.

SCALE '54

FROM IMPRESSIONS SUPPLIED BY THE LATE E. W. SMITH.



Second Side.

यमर २

26

28

30

32

34

36

38

40

मन्त्रवाक्यवशात्तु गारुडानामभिधानस्य विज्ञापितं स्वर्गमविरुद्धादह निवेदनं
 २६ कृतं भगवद्विषयं यत्तु नमिष्यत इत्येतन्मांशो यत्तु नमिष्यत इत्येतन्मांशो यत्तु नमिष्यत इत्येतन्मांशो
 २८ तस्मिन् सत्तास्य विष्णोः पौनःपुन्यं यत्तु नमिष्यत इत्येतन्मांशो यत्तु नमिष्यत इत्येतन्मांशो
 ३० लोकादिबोधकं यत्तु नमिष्यत इत्येतन्मांशो यत्तु नमिष्यत इत्येतन्मांशो यत्तु नमिष्यत इत्येतन्मांशो
 ३२ अथात्र यत्तु नमिष्यत इत्येतन्मांशो यत्तु नमिष्यत इत्येतन्मांशो यत्तु नमिष्यत इत्येतन्मांशो
 ३४ रूपं यत्तु नमिष्यत इत्येतन्मांशो यत्तु नमिष्यत इत्येतन्मांशो यत्तु नमिष्यत इत्येतन्मांशो
 ३६ यत्तु नमिष्यत इत्येतन्मांशो यत्तु नमिष्यत इत्येतन्मांशो यत्तु नमिष्यत इत्येतन्मांशो
 ३८ यत्तु नमिष्यत इत्येतन्मांशो यत्तु नमिष्यत इत्येतन्मांशो यत्तु नमिष्यत इत्येतन्मांशो
 ४० यत्तु नमिष्यत इत्येतन्मांशो यत्तु नमिष्यत इत्येतन्मांशो यत्तु नमिष्यत इत्येतन्मांशो

23. sâra-sâgarâd=asmân=samuddhara Vasundharê || [8*] Bhûdân-ânantaram yajamâna-
[vâkya]m || Bhûmim yah prati-
24. gri[hñâ]ti yas=cha bhûmim prayachchhati | ubhau tau puṇya-karmamâṇau
niyatam svargga-gâminau || [9*] Si[m*]hâ-

Second Side.

25. sanam tathâ chchhatram(ttram) var-âsvâ(śvâ) vara-vârapâḥ | bhûmi-dânasya
chihñâni phalam svarggas=tath=aiva cha || [10*] Va(ba)hubhir=vvasudhâ
[datt]â râ-
26. jabhê(bhi)ḥ Sagar-âdibhir=yasya yasya yadâ¹ bhûmis=tasya tadâ² tadâ phalam ||
[11*] Prâg=dattâm bhûmim viprêbhyô yatnâd=raksha Yudhishtîra | mahyâm
ma-
27. hîbhritâm śrêshṭha dânach=chhrêyô=nupâlana[m] || [12*] Âsphôṭayanti pitarah
pravalganti pitamahâḥ | bhûmi-dâtâ kulê jā-
28. taḥ sa naḥ santârayishyati || [13*] ³Ghôrâś=cha dârupâḥ pâsâ(śâ) n=
ôpasarppanti bhûmi-dam |(l) [14*] Pitarah pitrîlôka-sthâ dēva-
29. lôkê divaukasah | santarppayanti dâtâram . bhûmêḥ prabhavatâm vara || [15*]
Gâm=êkâm svarṇam=êka[m*] ra(cha) bhûmêr=apy=êkam=amgu-
30. lam [i*] haran=narakam=âyâti yâvad-âhûtasamplavam || [16*] Vindhy-âṭavishv=atôyâsu
su(śu)ahka-kôtara-vâsinah | kṛishṇasarppâ [h]i
31. jāyantê yê haranti vasunva(ndha)râm || [17*] Shashṭhim(shtim) varsha-
sahasrâṇi sva[r]ggê vasati bhûmi-daḥ | âchchêtvâ(ttâ) ch=ânumantâ va(cha)
tâ-
32. ny=êva narakam(kê) vaśê(sê)t || [18*] Sva-dattâm para-dattâ[m] vâ yô harêta
vasudhva(ndha)râm | sa vishṭhâyâm kṛimir=bhûtvâ pitribhiḥ sa-
33. ha pachyatê || [19*] Patanty=asrû(śrû)ṇi [ru]datâm dinânâm=api sîdatâm |
vrâ(brâ)hmapânâm hritê kshêtrê hatyâttvipurusham⁴ ku-
34. lam || [20*] Mahâpurôhita-ṭhakkura-śrî-Vâmu(su)dēvah | mahâpurôhita-śrî-Śrîdharah |
dhammâdhikarâṇika-śrî-Ma-
35. sivarah⁵ | daivâgârika-śrî-Kêsa(śa)vapadumâ || sam(śam)khadhâri-śrî-Va(vâ)ma-
harîḥ | paṇḍita-śrî-Rânvû(ndhû)kaḥ | upâdhyâ-
36. ya-śrî-Risikêsaḥ | upâdhyâya-śrî-Ântûkaḥ | upâdhyâ[ya*]-śrî-Sihaḍaḥ | paṇḍita-śrî-
Sâmkhâkaḥ | daivajña-
37. śrî-Ratichha(ka)rah | va(ṭha)kkura-śrî-Dēvapâlah | mahâkshapaṭalika-śrî-
Mahira(cha)ndaḥ | âshṭavarggika-śrî-Jâ-
38. gûkaḥ | karânakâyastha-śrî-Vanapâlah⁶ | mahâtthâ[sâ]sanika-⁷śrî-Mahikaḥ⁸ |
sa(ma)bâsâdhanika-śrî-
39. Haripâlah || ⁹Sarvva-pâtra-parijñâ[n]âd=dattam tâmrasya paṭṭakam || Khânitam
paṇḍita-śrî-Rânvû(ndhû)kêna ||

¹ This word was originally omitted and is engraved on the margin at the top.

² This word also is engraved on the margin at the top, wrongly for *tasya*.

³ Half of this verse has been omitted by the writer. ⁴ Read *hanyât=tri-purusham*.

⁵ Read *-Śatîdharah*. ⁶ Possibly the reading may be *-Varapâlah*.

⁷ The vowel *d* of the *akshara* *tthâ* may have been struck out. The *akshara* in brackets is faintly engraved; it looks as if originally *sa* had been engraved and as if this had been either struck out or altered to *sd*. Read *mahârithâsâsanika* (?).

⁸ Originally *-Mahîkaḥ* was engraved, but the *d* of *md* is struck out.

⁹ This is half a śloka.

40 khañitam¹ suvarṇṇakāra-Gaṇēśva(śva)rēṇa || Samvat² 1167 Phālva(igu)na-sudi
2 Sa(śa)nau pradattam=iti || gva³ ||

No. 11.—LAR PLATES OF GOVINDACHANDRA OF KANAUJ ;

[VIKRAMA-JSAMVAT 1202.]

By F. KIELHOEN, PH.D., LL.D., C.I.E. ; GÖTTINGEN.

These copper-plates were found at the village of Lār in the Gōrākhpur district, United Provinces, the 'Lār' of the *Indian Atlas*, sheet No. 103, long. 84° 2', lat. 26° 14'. They were handed over to Dr. W. Hoey by Babu Ramsaran Singh and Babu Mahadeo Singh, and presented by him to the Provincial Museum, Lucknow, in September 1898. My account of them is based on impressions, sent to Dr. Hultzsch by the late Mr. E. W. Smith.

The plates are two in number, each of which, to judge from the impressions, measures about 1' 3½" broad by 11" high, and is inscribed on one side only. There is a ring-hole in the centre of the lower part of the first plate and a corresponding hole in the centre of the upper part of the second plate; and together with the impressions of the plates there has been sent to me the impression of a circular seal, about 2½" in diameter, which bears in high relief, across the centre, the legend *śrīmad-Gōvinda[n]dradēva[h]*, in Nāgarī letters about ⅞" high; above the legend, apparently a figure of Garuḍa; and below the legend, a conch-shell.—The first plate contains 21 and the second 17 lines of writing, which is generally very well preserved. The size of the letters is about ⅜". The characters are Nāgarī, and the language is Sanskrit. As regards orthography, the letter *b* is denoted by the sign for *v*, except in the word *babhrāmura* =, l. 11; the dental sibilant is frequently employed instead of the palatal, and the palatal occasionally instead of the dental; and the words *āmra* and *tāmra* are written *āmura* and *tāmura*, in lines 19 and 37.

The inscription is one of the *Paramabhaṭṭāraka Mahārājādhirāja Paramēśvara Gōvinda-chandradēva*.⁴ The king records in it that, when in residence at Mudgagiri, after bathing in the Ganges on the occasion of the Akshaya-tṛtīyā festival, on Monday, the third *tithi* of the bright half of the month Vaiśākha in the year 1202 (given both in words and in figures, ll. 20 and 21), he granted the village of Pōtāchavaḍa in the Pāndala pattalā, in Gōvisālaka that belonged to Dudhāli in Saruvāra, to the *Thakkura* Śrīdhara, the son of the *Thakkura* Mādhava and son's son of the *Thakkura* Uddharana (?), a Brāhmaṇ (learned in the four Vēdas) of the Kāśyapa gōtra, whose three *pravara*s were Kāśyapa, Āvatsāra and Naidhruva.—The taxes specified (in line 26) are the *bhāgabhogakara*, *pravaṇikara* and *turushkadanḍa*. The grant (*tāmra-paṭṭaka*) was written by the *Karaṇika*, the *Thakkura* Sēlhaṇa.

The date regularly corresponds, for the *Kārttikādi* Vikrama-Samvat 1202 expired, to Monday, the 15th April A.D. 1146, which was entirely occupied by the third *tithi* of the bright half of the month Vaiśākha.⁵ Of the localities, Mudgagiri is the modern Monghyr, the 'chief town and administrative head-quarters of the Monghyr district, Bengal; situated on the south bank of the Ganges.' Regarding the other places or districts mentioned, I can only say that Saruvāra

¹ Wrong for *khātam*.

² Read *samvat*.

³ Compare the symbol which looks like *chāa*, e.g. above, Vol. IV. p. 101, note 8.

⁴ Compare the inscriptions edited by me above, Vol. IV. p. 99 ff., and Vol. V. p. 113 ff..

⁵ The *tithi* commenced 0 h. 47 m. before mean sunrise and ended 1 h. 4 m. after mean sunrise of the next day, and was therefore, for the Monday, a *prathama-tṛtīyā*.—The date would shew that the date of the inscription edited by me above, Vol. V. p. 115, must after all be taken to correspond to Monday, the 19th April A.D. 1148, because the king could not have bathed in the Ganges both at Benares and at Monghyr on one and the same day.

occurs also in the Pālī plate of Gōvīndachandra referred to by me above, Vol. V. p. 114, note 4, in the passage *Saruvārā-* (or, more probably, *Saruvāra* |) *Ōpavala-pathakē* | *Sirasī-pattalāyām* || *Pālī-grāma-*. Of the localities mentioned in this passage, Pālī is the village 'Palee' in *Indian Atlas*, sheet No. 102, long. 83° 25', lat. 26° 30'; Sirasī is 'Sirsi,' *ibid.* sheet No. 87, S.E., long. 83° 9', lat. 26° 32'; and Ōpavala survives in Unaula, (Unoula, Unaola, Anaola, Aonla),¹ a name of one of the parganas in the western part of the Gōrākhpur district. As the Ōpavala *pathaka* (with Sirasī and Pālī included in it) according to the Pālī plate formed part of Saruvāra, this would indicate in a general way where the localities mentioned in the present inscription should be looked for; but I have searched for them in vain on the maps at my disposal.

EXTRACT FROM THE TEXT.²

First Plate.

- 15 ³śrīmad-Gōvīndachandradēvō vijayī ||⁴ Sar[u]vārē
 Dudhālī-samvaddha-⁵Gōvisālakē Pāndala-pattalāyām⁶
 16 Pōtāchavaḍa-grāma-nivāsi(si)nō nikhila-janapadān=upagatān=api cha rāja-rājñi-
 yuvarāja-mantri-purōhita-sēnāpati-pratīhāra-
 17 bhāṇḍāgarīk-ākṣhapāṭalika-bhishag-naimittik-āntahpurika-dūta-
 karitragapattanākarasthānagōkulādhikāri-⁷purushān=ājñāpayati vō(bō)dha-
 18 yaty=ādisati cha yathā viditam=astu bhavatām yath=ōparilikhita-grāmaḥ sa-jala-
 sthalah sa-lōha-lavan-ākaraḥ sa-matsy-ākaraḥ sa-
 19 madhūk-āmra-⁸vana-vātikā-viṭapa-trīpa-yūti-gōchara-paryantaḥ sa-giri-gahana-nidhānaḥ
 sa-gartī-ōsharaḥ s-ōrdv(rddhv)-ādhaḥ⁹ chatur-āghāṭa-visu(su)ddhaḥ
 20 sva-sīmā-paryantaḥ dvayadhika-dvādaśa-śata-samvatsarē¹⁰ Vaisā(śā)khē¹¹ mā[si]
 su(su)kla-pakṣhē tṛtīyāyām tithau Sōma-dīnē śukātō-pi sa-
 21 yat¹² 1202 Vaisā(śā)kha-sudi 3 Sōmē ady=ēha Mudgagī[ri]-samāvāsē
 akshaya-tṛtīyāyām Gaṅgāyām vidhivat=snātvā

Second Plate.

- 22 mantra-dēva-muni-manuja-bhūta-pitṛi-gaṇāms=tarppayitvā timira-pāṭala-pātana-paṭu-
 mahasam=Ushnarōchisham=upasthāy=Aushadhipati-
 23 sa(śa)kala-sē(śē)kharām samabhyarchohya tribhuvana-trātura=Vāsudēvasya pūjām
 vidhāya prachura-pāyasēna havishā havirbhujām hutvā mātāpi-
 24 trōr=ātmanas=cha punya-yasō(śō)-bhivṛiddhayē smābhīr=gōkarṇṇa-kusālatā-pūta-
 karatal-ōdaka-pūrvvakam Kāśya(śya)pa-sagōtrāya Kāśya(śya)p-Ā-

¹ In the *Indian Atlas*, on the margin of sheet No. 87, S. E., we have 'Unaula,' in *Archæol. Survey of India*, Vol. XXII. p. 66, 'Unaola' and 'Anaola,' and in the *Imperial Gazetteer*, 2nd ed., Vol. V. p. 166, 'Aonla.' According to Thornton's *Gazetteer*, 'Unoula' is the principal place of the pargana of the same name (in the Gōrākhpur district); it is described as a small town, 13 miles south of Gōrākhpur, in lat. 26° 32' and long. 83° 21'. If this is correct, it must be the 'Bubhnowlee' of the *Indian Atlas*, sheet No. 102, 2½ miles north-west of 'Palee.' The same sheet, 10 miles south by west from 'Palee,' contains the name 'Oonowlee.'

² From impressions supplied by the Curator of the Provincial Museum, Lucknow.

³ Up to this, the text is practically identical with the text of the Kamauli plate of Gōvīndachandra, published above, Vol. IV. p. 100 f.

⁴ This sign of punctuation is superfluous.

⁵ Read *-sambaddha-*.

⁶ Read *-pattalāyām*; the second *yā* most probably is struck out already in the original.

⁷ The two *aksharas kārī* were originally omitted and are engraved on the margin at the foot of the plate.

⁸ Read *-āmra-*.

⁹ Here and in some places below the rules of *sandhi* have not been observed.

¹⁰ Read *-samvatsarē*.

¹¹ The second *akshara* of this word originally was *śō*. ¹² Read *samvat*.

- 25 vatsyâ (tsâ)ra-Nai[dhru]va-tripravarâya ðhakkura-śrî-[U]dharana-¹pauttâ(trâ)ya
 ðhakkura-śrî-Mâdhava-putrâya va(cha)turthê(rvvê)dauidyâvijitaTanamjaya-²
 vâ(brâ)hma-
- 26 pa-ðhakkura-śrî-Śrîdharâya chaindr-ârkkam yâvach=chhâsanîkritya pradattô mandâ³
 yathâdiyamâna-bhâgabhogakara-pravanîkara-turushkadanda-pra-
- 27 bhriti-niyatâniyat-âdâyan-âjñâvidhêyî⁴ dâsyath=êti || chha || Bhavanti ch=âtra
 smṛiti-slô(ślô)kâh ||⁵
- 37 Likhitam=idam tāmva-⁶paṭṭakam
 karāṇika-⁷ðhakkura-śrî-Sêlhanêna [||*]
- 38 Taḍâgânâm sahasrêṇ=⁸âsya(śva)mêdha-sa(śa)têna cha | gavâm kôṭi-pradânêna
 bhûmi-ha[r]ttâ na su(śu)dhyati || * (||) Mangalam mahâ-śriyam⁹ [||*]

No. 12.— A NOTE ON THE BUGUDA PLATES OF MADHAVAVARMAN.

By F. KIELHORN, PH.D., LL.D., C.I.E.; GÖTTINGEN.

Wishing to publish the accompanying photo-lithograph of the Buguda plates of Mâdhavavarman, the text of which I have given above, Vol. III. p. 41 ff., Dr. Hultzsch has asked me to write a note on the alphabet of that inscription. In complying with his request, I take the opportunity of correcting one or two errors which I have allowed myself to commit eight years ago, and of adding a few remarks on certain expressions which occur in the formal part of Mâdhavavarman's grant.

In my previous account I have represented the donor, Mâdhavavarman, as a son of Sainyabhîta. As pointed out by Dr. Hultzsch, above, Vol. VI. p. 144, note 1, the facts of the case are that Sainyabhîta is a surname of Mâdhavavarman himself, and that this Mâdhavavarman Sainyabhîta was a son of Yaśôbhîta. Moreover, a reconsideration of verse 11 of the inscription leads me to think that Mâdhavavarman also had the *biruda* Śrinivâsa.—The name of the village granted I have stated to be Puipîṇa; I now see that the actual reading of the name, in line 36, is either Puipîṇô or, more probably, Pûipîṇô. For the form of the initial *i*, here used, we may compare the sign for *i* in -âdhyâi, above, Vol. III. p. 342, l. 17, Plate.

In the passage enumerating the persons to whom the order is addressed, my text, in line 35, has vyavahârîṇâḥ sa[ðhâ]raṇân=, which I have proposed to alter to vyavahârîṇâḥ sâdharanân=. I now see that the *akshara* in brackets should be read *ka*, the word intended being sa-karanân=. The terms *vyavahârin* and *karana* occur together also in lines 14 and 15 of the Gumsûr plates of Nêṭṛibhaṇja, Jour. Beng. As. Soc. Vol. VI. Plate xxxiii. (where the published text, *ibid.* p. 669, has bhyupadravinam and karana); and karana and vyavahârika we find together in the Gauhati plates of Indrapâlavarmā, the Nowgong plates of Balavarman, and the Bargâon plates of Ratnapâlavarmā (*ibid.* Vol. LXVI. Part I. p. 126, l. 7, and p. 291, l. 10, and Vol. LXVII. Part I. p. 111, l. 54).

The term saliladhârtâ-puraḥsarêṇa in line 40 I had proposed to alter to the grammatically correct °puraḥsaram. But whatever may be the rules of grammar, saliladhârtâ-puraḥsarêṇa

¹ Read -try-Uddharana- (?).

² Read -Dhanamjaya-. Dhanamjaya is the name of a Vyâsa.

³ Read matod.

⁴ Read °vidhêyîbhâya.

⁵ Here follow the eleven verses commencing Bhûmim yaḥ pratigrihîdî, Saṅgham bhadr-danam, Sarvân=êtan=âdâvinah, Bahubhir=vasudhâ, Shastim varsha-sahasrâni, Na visham visham, Gâm=êkâm, Yâna=tha datidni, Vâi-dhira-vibhramam, Sva-dattâm para-dattâm vâ, and Vâri-hnêshv=aranyêshu.

⁶ Read tāmva-.

⁷ Originally kâranika- was engraved.

⁸ Read °sêva atra°.

⁹ Read -śrîh.

२
 ४
 ६
 ८
 १०

12
 14
 16
 18
 20

22
24
26
28
30

iii a.

32 ह्य दोगा दोगा दन कृती दवतु र्दुवाया ताहू र्दुक्ता
मा ह्य वीरुनया वृक्ता विलिख्य पतिरे पूा ह्य कृ पत्
34 एका दी बंधा मा वृक्ता दन वय मंगु ह्य वृक्ता न स विष्णि
ह्य व दोगा दोगा दन कृती दवतु र्दुवाया ताहू र्दुक्ता
36 कृ मा दोगा दोगा दन कृती दवतु र्दुवाया ताहू र्दुक्ता
कृ मा दोगा दोगा दन कृती दवतु र्दुवाया ताहू र्दुक्ता
38 कृ मा दोगा दोगा दन कृती दवतु र्दुवाया ताहू र्दुक्ता
कृ मा दोगा दोगा दन कृती दवतु र्दुवाया ताहू र्दुक्ता
40 कृ मा दोगा दोगा दन कृती दवतु र्दुवाया ताहू र्दुक्ता
कृ मा दोगा दोगा दन कृती दवतु र्दुवाया ताहू र्दुक्ता
42 कृ मा दोगा दोगा दन कृती दवतु र्दुवाया ताहू र्दुक्ता

iii b.

44 कृ मा दोगा दोगा दन कृती दवतु र्दुवाया ताहू र्दुक्ता
कृ मा दोगा दोगा दन कृती दवतु र्दुवाया ताहू र्दुक्ता
46 कृ मा दोगा दोगा दन कृती दवतु र्दुवाया ताहू र्दुक्ता
कृ मा दोगा दोगा दन कृती दवतु र्दुवाया ताहू र्दुक्ता
48 कृ मा दोगा दोगा दन कृती दवतु र्दुवाया ताहू र्दुक्ता
कृ मा दोगा दोगा दन कृती दवतु र्दुवाया ताहू र्दुक्ता
50 कृ मा दोगा दोगा दन कृती दवतु र्दुवाया ताहू र्दुक्ता
कृ मा दोगा दोगा दन कृती दवतु र्दुवाया ताहू र्दुक्ता
52 कृ मा दोगा दोगा दन कृती दवतु र्दुवाया ताहू र्दुक्ता

turns out to be so well established a term that it should not be altered. We find it, sometimes spelt incorrectly, in the plates of the time of Śaśāṅkarāja, above, Vol. VI. p. 145, l. 21; in one of the grants of Daṇḍimahādēvi, *ibid.* p. 142, l. 33; the Gañjām plates of Prithivivarmadēva, above, Vol. IV. p. 200, l. 19; the Kudopali plates of Mahābhavagupta II., *ibid.* p. 259, l. 17; and the Purī plates in *Jour. Beng. As. Soc.* Vol. LXIV. Part I. p. 126. Instead of it, we have *salīla-dhārā-puraḥsarēṇa vidhinā* in the plates of Vidyādharaḥaṇḍa, *ibid.* Vol. LVI. Part I. p. 160, l. 6; *dhārāsālīla-puraḥsarēṇa vidhinā* in the Gumsūr plates of Nēṭṭribhaṇḍa, *ibid.* Vol. VI. p. 669; and *udakapūrvēṇa* in the Chicacole plates of Nandaprabhaṇḍanavarman, *Ind. Ant.* Vol. XIII. p. 49, l. 4.

Like the expressions just now enumerated, the term *akarīkṛitya* in line 40 of our grant seems to be peculiar to inscriptions from the Gañjām district and the countries adjacent to it, in which it occurs frequently. Instead of it we also find, in inscriptions from the same localities, *akaratvēṇa*, or, as in the Chicacole plates of Nandaprabhaṇḍanavarman, simply *akuram*.

The term *lāṅchhitam*, which we have in line 50, also occurs in the plates of Nēṭṭribhaṇḍa, the plates of Vidyādharaḥaṇḍa, and the plates of Prithivivarmadēva, all from the Gañjām district.

The characters employed in these plates are the same as those of *e.g.* the Gumsūr plates of Nēṭṭribhaṇḍa, of which a rough lithograph is given in *Jour. Beng. As. Soc.* Vol. VI. Plate xxxiii.; the plates of Vidyādharaḥaṇḍa, of which there is a photo-lithograph *ibid.* Vol. LVI. Part I. Plate ix.; and the Gañjām plates of Prithivivarmadēva. They represent a variety of the northern alphabet which has developed out of the northern alphabet such as we find it in the [Gañjām] plates—below denoted simply by the letter Ś.—of the time of Śaśāṅkarāja or the Gupta year 300,¹ published with a photo-lithograph above, Vol. VI. p. 144, and which I would call the **Gañjām variety of the northern alphabet**.

Of initial vowels the text contains *a*, *ā*, *i*, *ī*, and *u*. Of these, *a* and *ā* are denoted by one and the same sign, which, as may be seen from a comparison with the sign for *ā* in line 26 of Ś., is really the sign for *a* only; see *Ādityadēvasya*, l. 39, *akarīkṛitya*, l. 40, *api*, l. 42, and *ākṣheptā*, l. 49. The sign for *i* is nearly the same as that used in Ś.; compare the *i* of *iva* in line 6 of the latter with the *i* of *indōr* in line 1 of the present plates. The sign for *ī* occurs only in *Pūṭipīṇō* (or *Pūṭipīṇō*), l. 36, and that for *u* *e.g.* in *utkīrṇam*, l. 50.

Of the signs for medial vowels only *ā*, *u* and *ū* call for remarks. In *īā*, *āchhā* (the *ā* of which does not really differ from the sign for *ṇ*), and occasionally in *ṇā*, the *ā* is denoted by a small hook, turned upwards and attached to the top of the consonant-sign; see *jaṭāḥ*, l. 4, *vāñchhā*, l. 13, and *charaṇḍya*, l. 38, and compare in Ś. *taṭā*, l. 6, *guṇā*, l. 14, and *kaṇṭhā*, l. 7. The sign for *ā* used (exceptionally) in *mā* at the end of line 25 may be compared with the sign for *ā* in *pā* at the end of line 1 of Ś.—For either of the vowels *u* and *ū* we have² (similarly to what is the case in Ś.) two signs; compare *punḍarīkāḥ*, l. 22, and *kumbha*, l. 23; *mūrtī*, l. 7, and *bhūmi*, l. 18 (and with the last again compare *bhūmi* in lines 25 and 26 of Ś.). There is a fifth sign, resembling the ordinary sign for *ū* in Ś., which is employed by the writer of the present

¹ The inscription is dated in the Gupta year 300, and the grant recorded in it was made at an eclipse of the sun. During the time which could correspond to a Gupta year 300 there was no solar eclipse which was visible in the Gañjām district. The two solar eclipses nearest to that time which were visible in the Gañjām district were one of the 4th November A.D. 617, and one of the 2nd September A.D. 620.—Perhaps I may state here that in line 22 of the same inscription, in the place of the corrupt *akṣayanīyē*, we must in my opinion read *akṣayanīyēd*. The term *akṣayanīyē* occurs also (corrupt) in one of the [Gañjām] grants of Daṇḍimahādēvi, above, Vol. VI. p. 139, l. 34.

² I have disregarded in the above the exceptional denotation of *u* and *ū* after *r*, *e.g.* in *gurur*, l. 4, and *prardāḥ*, l. 20; compare in Ś. *chaturādāli*, l. 1.—In line 19 of the present plates the writer has really written *mumūḍē*, not *mumudē*.

plates for both *u* and *ū*; compare *durīla-* at the end of line 23, *dūtako*, l. 51, *puraḥsarēna*, l. 40, and *pūrvva*, l. 34.

Of the consonants, *jh* and *b* do not occur in the text, and the signs for *chh* and *th*—the latter hardly to be distinguished from the sign for *t*—occur only as subscript letters. In general, it may suffice to draw the reader's attention to the forms of *kh*, e.g. in *khyātah*, l. 9; *g* and *ṣ* in *Gaṅgā*, l. 3; *ś* in *śāsvata*, l. 12; *gh* in *vighaṭṭi*, l. 19; *ch* in *chandrah* and *j* in *jālēshu*, l. 17; *th* in *slathā*, l. 3; *dh* and *v* in *pravōdha*, l. 16; *ph* in *phala*, l. 48; *bh* and *h* in *mahābhakumbha*, l. 23, and *graha*, l. 26; *l* in *kōmaladalāyatalō*, l. 9; and *s* in *sañchaya*, l. 8.

The signs for *t* and *tt* are those which we find generally used in inscriptions from Eastern India; compare *paṭumā*, l. 29, *śatpada*, l. 22, *pāṭṭaka*, l. 36, and *bhaṭṭa*, l. 40.

For the form of the single *ṇ* see e.g. *phaṇa*, l. 2, and *guṇind*, l. 10. When in *Ṣ*, *ṇ* or *ṇ̄* form the first part of a conjunct, two distinctly different signs are used to denote the two nasals; compare in *Ṣ*, *maṇḍana*, l. 14, and *sañchhannō*, l. 6. In the present plates the signs for *ṇ* and *ṇ̄* as first parts of conjuncts differ very slightly, if at all, and one sign only is used to denote the same two nasals as last parts of conjuncts; compare *maṇḍalam*, l. 10, *sañchaya*, l. 8, *vāñchhā*, l. 13, *lāñchhitam*, l. 50, *kṛishṇā*, l. 8, and *yajñais*, l. 28. One sign only is used in the present plates also for the subscript *chh* and *th*,³ just as the plates of the time of Śaśāṅkarāja use one sign for the same two letters; compare in *Ṣ*, *sañchhannō*, l. 6, and *sthitīyū*, l. 16, and in the present plates *vāñchhā*, l. 13, and *sthalī*, l. 23.

When *r* precedes another consonant, it is always, as in the modern Nāgarī, denoted by a superscript sign; but, excepting in the conjunct *ry*, the letter *y*, when it follows upon another consonant, is everywhere denoted by the secondary form of the letter *y* which in the same position is used throughout (even in *ry*) in *Ṣ*. So it happens that the signs for such *aksharas* as *tya*, *nya*, *shya*, *śya* of the present plates differ very little from the corresponding signs of *Ṣ*.

The sign of *avagraha* is not used in these plates; nor do we find in them the sign of *virāma*, except perhaps in the final form of *h*, used in the word *sanyak* at the commencement of line 43. Of other special signs for final consonants the plates contain one for *t*, in *asakrit*, l. 15, *kamālākaravat*, l. 24, *Āṅgirōvat*, l. 39, and *svadānāt*, l. 48, and one for *n*, in *gari(rī)yaṇ*, l. 18.

To determine with confidence the exact time of these plates from the characters seems to me impossible; my impression is that they cannot be earlier than about the 10th century A.D. and that probably they are not much later.

NO. 13.—BALODA PLATES OF TIVARADEVA.

By E. HOLTZSCH, PH.D.

These copper-plates were sent to me in February 1902 by Mr. A. B. Napier, I.C.S., on special duty in the office of the Commissioner of Settlements and Agriculture, Nāgpur, before whom they had been produced in an enquiry into the succession to an estate. They "belong to one Ude Singh, a resident of Baloda in the Phuljhar Zamindari of the Sambalpur district" of the Central Provinces.

¹ In line 25 the writer has really written *mabḥōdayēna*, not *mahōdayēna*.

² In *tñdītham* (for *tñdītham*), l. 10, the writer or engraver has used the subscript sign for *th* also for the first *th*. For the *śva* of *śva-gōtram*, l. 24, he had originally put *stha*, but the back of the paper-impression seems to shew that this *stha* has been altered to *śva*.

The plates are three in number and measure about 9½" in breadth and about 5¾" in height. Their edges are not raised into rims. The first plate is engraved only on the inner side, and the second on both sides. The third plate is full of writing on the inner side and bears one additional line, which records the name of the engraver, a little above the middle of the outer side. Some of the lines on the inner side of the third plate are so deeply cut that they show through on the outer side. The writing is on the whole in a state of very good preservation. In the syllable *nai* of l. 10, a square hole was cut into the plate by the engraver and a fresh piece of copper inserted into the hole. This was probably done in order to correct the syllable *nai*, which may have been spoiled accidentally in the original engraving. On the left side of each plate is bored a roughly square hole for a ring to connect them. The ring, which had not yet been cut when the plates reached my office, is about 4¼" in diameter and about ⅜" in thickness. Its ends are secured in the lower part of a circular seal, which measures 3¼" in diameter and closely resembles the seal of the Rājīm plates of the same king.¹ The seal bears, in relief on a deep countersunk surface, across the centre a legend in two lines; at the bottom a floral device; and at the top a figure of *Garuḍa*, facing the front and somewhat worn, with a *chakra* on his proper right and a *śaṅkha* on his proper left.

The alphabet is of the same box-headed type as in the Rājīm plates. The *jihvāmūliya* occurs in l. 36, and the secondary form of *jh* in *ujjhita* (l. 13). No distinction is made between the secondary forms of *ri* and *ṛi* (in *bhōktrīṇām*, l. 26), and between *ḍ* and *ḍh* (in *gūḍhō gāḍham*, l. 12). In ten instances (*kirīṭa*, l. 3; *lakṣmī*, ll. 4 and 32; *tyāgi*, l. 13; *kāminī-kriḍāsu*, l. 16; *śrī*, ll. 18, 19, 21; *sūchī*, l. 20) the secondary form of *i* is marked by a point in centre of the mark for *i*; but in the majority of cases the *i* is not distinguished from the *i*. The *r* of *śrī* (ll. 1, 2, 18, 19, 21, 25) has the same shape as the secondary form of *ri*. Final *t* occurs in *sampat* (l. 8), *dadyāt* (l. 36) and *vasēt* (l. 37), and final *m* in *ṛitām* (l. 2). In l. 40 we have the numerical symbols for 7, 9, and 20.

The language is Sanskrit, mostly prose; but there is one verse on the seal and another in l. 1 f., and six verses from the *Smṛitis* are quoted in ll. 30-40. As in the Rājīm plates, the vernacular form *samvatsaru* occurs in l. 40. As regards orthography, *v* is used instead of *b* in *vahala* (l. 5) and *Indravala* (l. 18), and *b* instead of *v* in *bapushi* (l. 11) and *abhibhiddhayē* (l. 28 f.). The *anusvāra* before *ś* is changed into *ṣ* in *nistrīṣṭa* (l. 4 f.), *vanīṣasya* (l. 18 f.), *trīṣṭataḥ* (l. 27), and *nṛīṣaṇṣā* for *nṛīṣaṇṣāḥ* (l. 32). Between a vowel and *r*, *t* is always doubled, except in *ch=ātra*, l. 34; in *jagatrāya* (l. 1) *tra* is used for *ttra*, and in *śtad=āvayaṁ* (l. 32) *dva* is used for *ddva*.

Like the Rājīm plates, this inscription records a grant by *Tivaradēva*, as he is called on the seal and in the opening verse, or *Mahāśiva-Tivararāja* (l. 21). On the seal he is styled 'sovereign of *Kōśala*,' and in l. 19 he is stated to have "acquired the sovereignty of the whole of *Kōśala*."² He was the son of *Nannadēva* of the family of *Pāṇḍu*, and the grandson of *Indrabala* (l. 18 f.). *Nannadēva* and his father *Indrabala*, who was a son of *Udayana* of the lunar race, are mentioned also in an inscription at *Sirpur*, which has been published by Professor Kielhorn,³ who has also found the names of *Udayana* of the *Pāṇḍava* family, and perhaps of *Indrabala*, in a fragmentary inscription of the *Nāgpur Museum*.⁴ According to the same scholar, *Tivaradēva* must be assigned to about the middle of the eighth century of the Christian era.⁵

¹ Dr. Fleet's *Gupta Inscriptions*, Plate xlv.

² This epithet seems to have been omitted accidentally by the engraver of the Rājīm plates (l. 16), where *prāptaḥ* corresponds to *prāpta-sakala-Kōśal-adhipatyāḥ* in the Baloda plates (l. 19).

³ *Ind. Ant.* Vol. XVIII. p. 179. In l. 4 of this inscription, I would correct *Nannāivar-āhīyō* into *-āhīyair*; compare e.g. *Narēndrēśvara* in *South-Ind. Inscr.* Vol. I. p. 38 and note 2.

⁴ *Above*, Vol. IV. p. 257.

⁵ *Above*, Vol. IV. p. 258.

Tivaradēva's edict was issued from Śrīpura (l. 2), which Dr. Fleet has identified with the modern Sirpur,¹ and is dated on the 27th day of the month Jyaisṭha in the 9th year of his reign (l. 40), i.e. about two years after the Rājim plates. The king granted the village Menkidḍaka in the district of Sundarikāmārga (l. 22) for the benefit of a rest-house (*sattra*) which had been established at Bilvapadraka at the request of his son-in-law Nannarāja (l. 25 f.). I am unable to identify the geographical names mentioned in the preceding sentence.

TEXT.²

First Plate.

- 1 ओ³ [॥*] जयति 'जगचयतिलकचित्तिभृत्कुलभवनमङ्गलस्तम्भः [॥*] श्रीमत्ती-
वरदेवो
- 2 धीरेयः[*] सकलपुण्यकृताम् ॥ [१*] स्वस्ति श्रीपुरात्समधिगतपञ्चमहाशब्दा-
नेकान-
- 3 तन्मृपतिकिरीटकोटिष्टचरणनखदर्पणोद्भासितोपकण्ठदिक्षुखः प्र-
- 4 कटरिपुराजलक्ष्मीः(ः)केशपाशाकर्षणदुर्लभितपाणिपङ्क्तवः⁵ निशितनि-
- 5 स्त्रिङ्गघनघ[॥*]तपातितारिद्विरदकुम्भमण्डलगलहलशोणित-⁷
- 6 सटासिक्तमुक्ताफलप्रकरमण्डितरणाङ्गणः⁸ विविधरत्नसंभारला-
- 7 भलोभविजृम्भमाणारिचरवारिवाडवानलक्ष्मन्दोदय इवाकृतकरीडे-
- 8 गः क्षीरोद इवाविर्भूतानेकातिशयिरत्नसम्पत् ॥ गरुत्मानिव भुजङ्गोडा-
- 9 रचतुरः[*] परासृष्टशत्रुकलघनेच्छाञ्जनकोमलकपोलकुङ्कुमपञ्च-
- 10 भङ्गः शिष्टाचारव्यवस्थापरिपालनैकदत्तचित्तः [॥*] अपि च प्राक्तने तप-

Second Plate; First Side.

- 11 सि यशसि रहसि चेतसि चक्षुषि वपुषि⁹ च पूजितो जनेनाक्षिष्टतया
नि-
- 12 तान्तमवितृप्ती गूढो गाढं स्वच्छः प्रसन्नो यौवनेन चालङ्कृतः¹⁰ स्वामी भ-
- 13 वनप्यबहुलपनीतुष्कितकुतुष्कोपि नितान्तत्यागी रिपुजनप्रच-
- 14 ण्डोपि सौम्यदर्शनो भूतिविभूषणोप्यपरुषस्वभावः [॥*] किञ्चासन्तुष्टो
- 15 धर्माजने¹¹ न सम्पन्नानि स्वल्पः क्रोध¹² न प्रभावे लुब्धो यशसि न प-
- 16 रवितापहारे सक्तः[*] सुभाषितपु¹⁴ न कामिनीक्रीडासु प्रतापानल-
- 17 दग्धाशेषरिपुकुलतूलराशिस्तुहिनशिलाशैलधवलयशोराशिप्र-
- 18 काशितदिगन्तः कान्तः प्रकृत्या ¹⁵श्रीमदिन्द्रवलसूनोरलङ्कृतपाण्डुव-

¹ Gupta Inscriptions, p. 293.² From the original copper-plates.³ Expressed by a symbol.⁴ Read जगचय⁰.⁵ Read °पङ्क्तवो.⁶ Read °स्त्रिङ्ग⁰.⁷ Read °हल⁰.⁸ Read °रणाङ्गणी.⁹ Read वपुषि.¹⁰ Read चालङ्कृतः.¹¹ Read °वपुष्य⁰.¹² Read धर्माजने.¹³ Read क्रोधे.¹⁴ Read °तेषु.¹⁵ Read °दिन्द्रवल⁰.

ॐ नमो भगवते वासुदेवाय ॥ १ ॥
 अथ श्रीतिवारदेवप्रतिमास्तोत्रम् ॥ २ ॥
 तिवारदेव प्रसीद मे भक्त्या ॥ ३ ॥
 तिवारदेव प्रसीद मे भक्त्या ॥ ४ ॥
 तिवारदेव प्रसीद मे भक्त्या ॥ ५ ॥
 तिवारदेव प्रसीद मे भक्त्या ॥ ६ ॥
 तिवारदेव प्रसीद मे भक्त्या ॥ ७ ॥
 तिवारदेव प्रसीद मे भक्त्या ॥ ८ ॥
 तिवारदेव प्रसीद मे भक्त्या ॥ ९ ॥
 तिवारदेव प्रसीद मे भक्त्या ॥ १० ॥

ॐ नमो भगवते वासुदेवाय ॥ ११ ॥
 अथ श्रीतिवारदेवप्रतिमास्तोत्रम् ॥ १२ ॥
 तिवारदेव प्रसीद मे भक्त्या ॥ १३ ॥
 तिवारदेव प्रसीद मे भक्त्या ॥ १४ ॥
 तिवारदेव प्रसीद मे भक्त्या ॥ १५ ॥
 तिवारदेव प्रसीद मे भक्त्या ॥ १६ ॥
 तिवारदेव प्रसीद मे भक्त्या ॥ १७ ॥
 तिवारदेव प्रसीद मे भक्त्या ॥ १८ ॥
 तिवारदेव प्रसीद मे भक्त्या ॥ १९ ॥
 तिवारदेव प्रसीद मे भक्त्या ॥ २० ॥

W. GRIGGS, PHOTO-LITH.

- 19 इत्स¹ श्रीनन्ददेवस्य तनय[ः*] प्राप्तसकलकोसलाधिपत्यः स्वपुत्र-
 20 सभारप्रशमिताशेषजगदुपद्रवः स्वप्रज्ञासूचीसमुद्भूताखि-

Second Plate ; Second Side.

- 21 लक्षणकः परमवैष्णवी मातापितृपादानुद्धातः श्रीमहाशिवत्तीवरराजः²
 22 सुन्दरि कामार्गीयमेङ्गिङ्गुके प्रतिवासिनः समान्नापयति [।*] विदितमस्तु
 23 भवता³ यथायं ग्रामो यावद्रविशशिताराकिरणप्रतिहतघोराभकारं
 24 जगदवतिष्ठते तावदुपभोग्यस्मनिधिः सोपनिधिरचाटभटप्रवेशः
 25 सर्व्वकरसमेतः समधिगतपञ्चमहाशब्दप्रियजामादृश्री-
 26 नन्दराजविज्ज(र)स्या विष्णुपद्रुके परिकल्पितस[त्त]भोक्तृणां यथ[।*]प्रा-
 27 सन्नान्न[ण*]दिज्जमाना⁴ त्रिङ्गतः प्रत्यहमुपभोगाय अधिष्ठानेन च
 28 प्रतिपालना⁵ कार्य्यैत्यनया व्यवस्थयास्माभिर्म[।*]तापिन्नोरात्मनश्च पुण्याभि-
 29 वृद्धये⁶ प्रतिपादित इत्युप[ल*]भ्य यथोचितभोगभागमुपनयन्त[ः*] सु-
 30 खं प्रतिव[त्स्य]यति ॥ भाविनश्च⁷ भूमिपालानुदिश्येदमभिधीयते [।*] भू-

Third Plate ; First Side.

- 31 मिप्रदा दिवि ललन्ति पतन्ति हन्त हत्वा मही⁸ नृपतयो नरके
 32 नृशङ्का[ः⁹ ।*] एतद्वय¹⁰ परिकलय्य चलाञ्च लक्ष्मीमायुस्तथा कुरुत यज्ञ-
 33 व[त]ामभीष्टः¹¹ [॥ २*] अपि च [।*] रक्षापालनयोस्तावत्फल¹² सुगति-
 दुर्गती [।*] को नाम
 34 स्वर्गमुत्सृज्य नरक¹³ प्रतिपद्यते ॥ [३*] व्यासगीताश्चात्र¹⁴ श्लोकानुदाह-
 [र*]न्ति [।*] अग्ने-
 35 रपत्य¹⁵ प्रथमं सुवर्णं भूर्वैष्णवी सूर्य्य[सुताश्च] गावः[।*] दत्त[र]स्त्रयस्तेन
 36 भवन्ति लोका यज्ञ[।*]ञ्चन¹⁶ गाञ्च महीञ्च दद्यात् ॥ [४*] षष्टिवर्ष-
 सहस्राणि
 37 स्वर्गं मोदति भूमिदः [।*] 17अच्छेत्ताञ्चानुमन्ता च तान्येव नरके
 वसेत् ॥ [५*] बहु-
 38 भिर्व्वसुधा दत्ता र[।*]जभिस्सगरादिभिः [।*] यस्य यस्य यदा भूमि-
 तस्य¹⁸ तस्य तदा

¹ Read °वृक्षस्य.

² Read °जानानां विंशतः.

³ Read °मुद्दिश्ये.

⁴ Read एतद्वयं.

⁵ Read नरकं.

⁶ Read °ञ्चनं.

⁷ Read °शिवतीवर°.

⁸ Read कार्य्यैत्य°.

⁹ Read मही°.

¹⁰ Read °भीष्टं.

¹¹ Read °गीताश्चात्र.

¹² Read आच्छेत्ता चानु°.

¹³ Read भवतां.

¹⁴ Read °वृद्धये.

¹⁵ Read नृशङ्काः.

¹⁶ Read °फलं.

¹⁷ Read °पत्यं प्रथमं सुवर्णं भूर्वैष्णवी.

¹⁸ Read भूमितस्य.

- 39 फलं ॥ [६*] स्वदत्ता¹ परदत्ताम्वा यत्नाद्रक्ष युधिष्ठिर [१*] मही-
नहीमता² श्रेष्ठ
40 दानाच्छेयोतुपालनमिति ॥ [७*] प्रवर्द्धमानविजयराज्ये सम्वत्स³ ८
ज्येष्ठ दि २० ७ [॥*]

Third Plate ; Second Side.

- 41 उत्कीर्ण⁴ आर्कशालिकसोत्तणामसूनुना बोप्यणागेनः⁵

Seal.

- 1 श्रीमत्तीवरदेवस्य कोसल[र]धिपतेरि[दं] [१*]
2 शास[नं] ध[र्म]वृ[द्धार्थ] स्थितमाचन्द्रत[र]र[क्तं] [॥ ८*]

TRANSLATION.

Om. (Verse 1.) Victorious is the glorious Tivaradēva, the foremost of all performers of meritorious acts, (and) the auspicious pillar (supporting) the mansion—the family of kings (who are) ornaments of the three worlds.

(Line 2.) Hail! From Śrīpura,—he who illuminates the neighbouring regions by the mirror of the nails of (his) feet, which are rubbed by the edges of the diadems of many bowing princes who have obtained the five great sounds; whose sprout-like hand rudely pulls the abundant hair of the goddess of Fortune of kings (who are his) declared enemies; who adorns the battle-field with heaps of pearls, which are drenched with copious streams of blood (and) which drop from the round temples of hostile elephants, struck down⁷ by the heavy blows of (his) sharp sword; (who is) the submarine fire to the ocean of (his) enemies, swelling with the desire of acquiring a mass of various gems; who does not cause distress by (heavy) taxes, just as the rising moon does not cause distress by (hot) rays; who, like the milk-ocean, displays a wealth of many surpassing jewels; who is skilled in uprooting the wicked, just as Garuḍa is skilled in picking up snakes; who, (by making them widows), wipes away the collyrium below the eyes, and the saffron marks on the tender cheeks, of the wives of (his) enemies; whose mind is bent exclusively on maintaining the rules of good conduct;

(L. 10.) who, moreover, is spontaneously worshipped by men on account of (his) penance, performed in a previous birth; who is quite insatiable in (acquiring) fame; who is very reserved in (keeping) secrets; who is quite pure in mind; whose eyes are pleasant; and whose body is ornamented with youth; who, though he is a master (śvāmin), does not talk much. (while the god Svāmin, i.e. Kārttikēya, has many, viz. six, faces);⁸ who, though not free from the desire

¹ Read स्वदत्ता परदत्ता वा.

² Read महीनहीमता.

³ The *ru* of सम्वत्स seems to be engraved on an erasure and differs from the *ru* occurring in ll. 8, 14 and 32; but in the corresponding passage of the Bājim plates (l. 36) the *ru* is quite distinct.

⁴ Read उत्कीर्णमाक्ष.

⁵ The *visarga* here represents a full stop.

⁶ The photo-lithograph of the seal of the Bājim plates also reads स्थित⁶, while the printed text (*Gupta Inscr.* p. 284) has स्थिर⁶.

⁷ I do not consider it absolutely necessary to alter *pdīta* into *pdīta*, as proposed in *Ind. Ant.* Vol. XVIII. p. 2: O.

⁸ *Lapana* means both 'talking' and 'the mouth.'

for (*conquering*) the earth (*ku*),¹ is very liberal; who, though very fierce to enemies, is of gentle² aspect; who, though adorned with majesty (*bhāti*), is not cruel in disposition (while Śiva is both smeared with ashes (*bhūti*) and cruel in disposition);

(L. 14.) who, moreover, is never satisfied in acquiring merit, but the contrary in accumulating wealth; who is devoid of anger, but not of power; who is covetous of fame, but not of taking the property of others; who is fond of clever remarks, but not of playing with women; who by the fire of (*his*) valour burns the families of all (*his*) enemies (*like*) heaps of cotton; who by the mass of (*his*) fame, white as the mountain of ice, illuminates the quarters; who is handsome by nature;

(L. 18.) the son of the glorious Nannadēva,— (*who was*) the son of the glorious Indrabala (*and*) adorned the race of Pāṇḍu,— the glorious Mahāśiva-Tivaraśja, who has acquired the sovereignty of the whole of Kōśala; who by the abundance of his merit has allayed all the calamities of the world; who has removed all thorns (*or small enemies*) with the needle of his wisdom; (*who is*) a devout worshipper of Viṣṇu; (*and*) who meditates on the feet of (*his*) mother and father,— issues (*the following*) command to the inhabitants of Menkiḍḍaka, which belongs to (*the district of*) Sundarikāmārga :—

(L. 22.) “Be it known to you that, for the increase of the merit of (*our*) mother and father and of ourselves, we have granted this village, to be enjoyed as long as the world endures, in which terrible darkness is dispelled by the rays of the sun, the moon and the stars; together with treasures; together with deposits; not to be entered by regular or irregular troops; accompanied by all taxes; in order to feed daily thirty Brāhmanas or other men who happen to arrive (*and*) who use the rest-house established at Bilvapadraka at the request of (*our*) beloved son-in-law, the glorious Nannarāśja, who has obtained the five great sounds; and under the condition that (*this charity*) has to be maintained by the (*local*) authority.”³

(L. 29.) “Knowing this, you shall dwell in happiness, delivering (to the *sattra*) the proper share of the enjoyment.”

(L. 30.) And the following is addressed to future rulers of the earth.

[Here follow two of the customary verses.]

[L. 34.] And with reference to this they quote (*the following*) verses sung by Vyāsa.

[Here follow four other verses.]

(L. 40.) The year 9 in the increasing reign of victory; the 27th day of Jyēṣṭha.

(L. 41.) (*This edict was*) engraved by Boppanāga, the son of the goldsmith⁴ Sottraṇāga.

Seal.

(V. 8.) This edict, the object of which is the increase of merit, of the glorious Tivaraśja, the sovereign of Kōśala, (*shall*) endure as long as the moon and the stars.

¹ In order to understand the *virāḍha*, the primary meaning of *ku-triṣṭha*, viz. ‘mean greed,’ must be also kept in mind.

² *Saumya* means also ‘moon-like,’ while the word *prachanḍa*, ‘very fierce,’ hints a comparison with the sun (*chandrāmīn*).

³ Or, perhaps, ‘by the town (of Bilvapadraka).’ The meaning of *adhishṭhāna* is doubtful.

⁴ *Arkaśālika* is a Sanskrit form of the Kanarese *akkasālika* or *akkasāli* (above, Vol. III. p. 218), ‘a goldsmith,’ which Dr. Kittel (*Kannada-English Dictionary*, s.v. *aka*, 2) derives from *arka*, ‘metal.’ In the Eastern Ganga copper-plates we find the Prākṛit form *akhas[ā]lin* (above, Vol. III. p. 19) and the (apparently erroneous) Sanskrit forms *akhasālin* (*Ind. Ant.* Vol. XVIII. p. 145) and *akhasālika* (*ibid.* Vol. XIII. p. 123). The Sanskrit form *akhasālika* has to be distinguished from the *akshapāṭalika*, an officer who wrote grants, but did not engrave them; see above, Vol. IV. pp. 126 and 128, and compare *ibid.* pp. 121, 129 and 210. Professor Bühler’s and Monsieur Senart’s remarks (*Indische Palaeographie*, p. 94 f., and p. 69 above) have to be modified in accordance with this result.

No. 14.—INSCRIPTIONS ON THE THREE JAINA COLOSSI
OF SOUTHERN INDIA.

By E. HULTZSCH, PH.D.

In the course of my two last cold-weather tours I had occasion to visit the sites of the three famous monolithic images at Śravaṇa-Belgoḷa in the Hassan district of the Mysore State and at Kārkaḷa and Vēṇūr in the South Canara district of the Madras Presidency. For descriptive notices of these monuments the reader is referred to Mr. Rice's *Inscriptions at Śravaṇa-Belgoḷa*, Introduction, p. 29 ff., and Mr. Sewell's *Lists of Antiquities*, Vol. I. pp. 231 and 236 f. The largest and most ancient of them is the one at Belgoḷa, which, according to Mr. Rice, is 57 feet high and was set up by the minister Chāmuṇḍarāja between A.D. 977 and 984. The second, at Kārkaḷa, is 41' 5" high and was erected by the chief Vira-Pāṇḍya in A.D. 1432. Along with the two inscriptions on the image at Kārkaḷa, I publish an inscription (E. below) on a neighbouring pillar which was raised by the same Vira-Pāṇḍya in A.D. 1436. The smallest and most recent of the three monoliths is the one at Vēṇūr, which is 35 feet high and was established by the chief Timmarāja in A.D. 1604.

The saint or god whom the three images represent is called in Sanskrit Bāhubalin or Bhujabalin¹ and was believed to have been the son of Āḍijina (G. below), i.e. the first Jina Rishabhanātha.² His vernacular name was Gummaṭa (D.), Gummaṭēsa (G.), Gommaṭa or Gommaṭēśvara.³

The inked estampages from which I am publishing the Kārkaḷa inscriptions (Nos. C., D. and E. below) were prepared by my peons. Those of the Belgoḷa and Vēṇūr inscriptions (Nos. A., B., F. and G.) had to be done by Jains under my supervision, because none but Jains are permitted to touch the images at Belgoḷa and Vēṇūr.⁴

A.—On the proper right side of the colossus at Belgoḷa.

This inscription (No. 52a of 1902) was first published by Mr. Rice,⁵ who, however, did not succeed in reading the second word in l. 2.

The alphabet and language of the first and third lines are Kanarese. The second line is a Tamil translation of l. 1 and consists of two words, of which the first is written in the Grantha and the second in the Yaṭṭeluttu alphabet. The first two lines record that Chāmuṇḍarāja caused to be made the image at the foot of which the inscription is engraved, and the third line, that Gaṅgarāja caused to be made the buildings which surround the image.

In Mr. Rice's opinion, these inscriptions "are undoubtedly of the period when that work was completed."⁶ A comparison of the alphabet of l. 1 with that of the epitaph of Mārasimha II.⁷ and of the alphabet of l. 3 with that of an inscription of Gaṅgarāja⁸ has convinced me that Mr. Rice is correct, i.e. that l. 1 belongs to the time of Chāmuṇḍarāja, the minister of the two Gaṅga kings Mārasimha II. and Rāchamalla II.,⁹ and that l. 3 belongs to the time of Gaṅgarāja, the minister of the Hoysala king Viṣṇuvardhana.¹⁰ The second line is probably contemporaneous

¹ See the inscriptions C. and F. below.

² Compare *Ind. Ant.* Vol. II. p. 184.

³ *Inscriptions at Śravaṇa-Belgoḷa*, Index, s. v.

⁴ Mr. Walhouse had the same experience; see *Ind. Ant.* Vol. V. p. 37.

⁵ *Inscriptions at Śravaṇa-Belgoḷa*, No. 76.

⁶ *Op. cit.* Introduction, p. 22.

⁷ Above, Vol. V. No. 18, Plate.

⁸ No. 78 of 1893 (*Inscriptions at Śravaṇa-Belgoḷa*, No. 59).

⁹ Above, Vol. V. pp. 171 and 173.

¹⁰ Dr. Fleet's *Dyn. Kan. Distr.* p. 499 f.

Taina Colossus at Sarana-Belgala.



E. HULTZSCH, PHOTO.

WIELE & KLEIN, HALF-TON

Sravana-Belgola Inscriptions.

No. 1.



No. 2.



E. HULTZSCH.

SCALE '066.

WIELE & KLEIN, PHOTO-ZINGO.

with the first line. In Mr. Rice's opinion, ll. 1 and 2 were engraved between A.D. 977 and 984,¹ and l. 3 between A.D. 1115 and 1118.²

TEXT.³

- 1 Śrī-Chāmundaṛājaṃ māḍisidaṃ
- 2 Śrī-Chāmundaṛājaṃ⁴ [śe]yv[v]ittāṇ⁴
- 3 Śrī-Gaṅgaṛāja suttālayavaṃ māḍisida

TRANSLATION.

- (Line 1.) The glorious Chāmundaṛāja caused (*this image*) to be made.
 (L. 2.) The glorious Chāmundaṛāja caused (*this image*) to be made.
 (L. 3.) The glorious Gaṅgaṛāja caused the enclosure to be made.

B.— On the proper left side of the colossus at Belgola.

This inscription (No. 52b of 1902) also was first published by Mr. Rice.⁵

The alphabet is Nāgarī and the language is Marāṭhī. The first line is a translation of l. 1 of the preceding inscription (A.), and the second line of l. 3 of the same inscription. As the type of the alphabet of ll. 1 and 2 is quite identical, it may be assumed that both lines were engraved in the time of Gaṅgaṛāja, whose name occurs in the second line. The Marāṭhī language was perhaps adopted for the benefit of Jaina pilgrims from the Marāṭha country.

TEXT.⁶

- 1 Śrī-Chāvundaṛājēṃ karaviyalēṃ
- 2 Śrī-Gaṅgaṛājē suttālē karaviyalē

TRANSLATION.

- (Line 1.) The glorious Chāvundaṛāja caused (*this image*) to be made.
 (L. 2.) The glorious Gaṅgaṛāja caused the enclosure to be made.

C.— On the proper right side of the colossus at Kārkaḷa;
Śaka-Samvat 1353.

This inscription (No. 63 of 1901) was first published in a tentative manner by Dr. Burnell.⁷ Mr. Rice's reprint of Dr. Burnell's text⁸ contains a few improvements, based on a copy which was supplied to him by the late Brahmasuri Sastri, the well-known Jaina scholar of Śravaṇa-Belgola.

The alphabet is Kanarese, with the exception of the colophon Śrī-Pāṇḍyaṛāja in l. 15, which is in Grantha characters. The inscription consists of two Sanskrit verses and a few words in Sanskrit prose (l. 14 f.). It records that the chief Vira-Pāṇḍya (l. 11) or Pāṇḍyaṛāja (l. 15), who was the son of Bhairavēndra of the lunar race, caused to be made the image of Bāhubalin, on which the inscription is engraved.

¹ *Inscriptions at Śravaṇa-Belgola*, Introduction, p. 22.

² *Loc. cit.* p. 23; see *Ind. Ant.* Vol. XXIII. p. 116, Nos. 17 and 13.

³ From two inked estampages.

⁴ The *virāma* after °rdjan and °ttāṇ is expressed by a dot (*puḷḷi*) at the top of the letter. There is another unexplained dot behind °rdjan.

⁵ *Inscriptions at Śravaṇa-Belgola*, No. 75.

⁶ From two inked estampages.

⁷ *Ind. Ant.* Vol. II. p. 353.

⁸ *Inscriptions at Śravaṇa-Belgola*, Introduction, p. 31 f.

According to verse 1, Vira-Pāṇḍya was prompted to undertake this work by the Jaina priest Lalitakīrti, who belonged to the lineage of Panasōge¹ and to the *Dēśigaṇa*. The same verse occurs in another Kārkaḷa inscription² of Immaḍi-Bhairarasa of the family of Jinadatta,— apparently one of the successors of Vira-Pāṇḍya,— who built the Chaturmukhabasti at Kārkaḷa in Śaka-Samvat 1508 (expired), the Vyaya year. It follows from this, that the Jaina *śvāmīns* of Hanasōge bore the hereditary title Lalitakīrti³ and were the spiritual preceptors of the chiefs of Kārkaḷa.

The day on which the image was consecrated fell into the (expired) Śaka year 1353 (in numerical words, 1. 5 f., and in figures, 1. 14 f.), the cyclic year Virōdhikṛit. According to Professor Kielhorn's calculation, the date corresponds to Wednesday, the 13th February A.D. 1432.⁴

TEXT.⁵

- 1 श्रीमद्देशीगणे ख्या-
- 2 ते पनसोगीवलीखरः⁶ ।
- 3 योभूल्ललितकी-
- 4 र्त्थाख्यस्तन्मुनीन्द्रोपदे-
- 5 शतः ॥ [१*] खस्ति श्रीशकभूपते-
- 6 स्त्रिशरवक्त्रीदोर्विरोध्या-
- 7 दिक्कद्वर्षे फाल्गुनसौ-
- 8 म्यवारधवलश्रीद्वा-
- 9 दशीसत्तिथौ । श्रीसोमा-
- 10 न्वयभैरवेंद्रतनु-
- 11 जश्रीवीरपाणेशिना नि-
- 12 र्माय्य प्रतिमाच वा-
- 13 हुवलिनो जीयाद्य-
- 14 तिष्ठापिता ॥ [२*] शकवर्ष
- 15 १३५३ [॥*] श्रीपांचराय [॥*]

TRANSLATION.

(Verse 1.) At the advice of that chief of sages, named Lalitakīrti, who was the lord of the lineage (*āvali*) of Panasōge, (*which arose*) in the holy (*and*) famous *Dēśigaṇa*,—

(V. 2.) Hail! In the (*cyclic*) year Virōdhyaḍikṛit⁷ (*which corresponded*) to (*the y. measured by*) three, the arrows (5), the fires (3) and the moon (1) of the glorious Śaka kir

¹ This is the modern Hanasōge in the Yeḍatore tāluka of the Mysore district. See Mr. Rice's *Ep. O.* Vol. IV., Introduction, p. 16.

² No. 62 of 1901. For a very incorrect transcript of this record see *Ind. Ant.* Vol. V. p. 40 ff. The *titā* the date is the sixth, and not the fifth as the published transcript has it.

³ Thus the *śvāmīns* of Śravaṇa-Belgoḷa and Māḍabidure have the title Chārakīrti, and those of Humche title Dēvēndrakīrti.

⁴ *Ind. Ant.* Vol. XXIII. p. 119, No. 42.

⁵ From an inked estampage.

⁶ Read °सोगावली°.

⁷ I.e. 'kṛit beginning with Virōdhya,' which is an artificial way of expressing Virōdhikṛit.

⁸ I.e. Śaka-Samvat 1353.

(on) a Wednesday in Phālguna, on the auspicious *tithi* of the holy *dvādaśī*¹ of the bright (fortnight),— an image of Bāhubalin was here caused to be made and was consecrated by the glorious lord Vira-Pāṇḍya, the son of Bhairavēndra of the glorious family of the Moon. Let (this image) be victorious !

(Line 14.) The Śaka year 1353.

(L. 15.) O glorious Pāṇḍyarāya!²

D.— On the proper left side of the colossus at Kārkaḷa.

This inscription (No. 64 of 1901) consists of one verse in the Kanarese alphabet and language, and two words in Nāgarī characters and Sanskrit prose (l. 7). Like the preceding inscription (C.), it records that the image was caused to be made by Pāṇḍyarāya (ll. 2 f. and 7), the son of Bhairavēndra. But the image is here stated to be one of Gummaṭa, the lord of Jinās.

TEXT.³

- 1 स्वरिनुतभैरवै-
- 2 द्रकुमारश्रीपांछ-
- 3 रायनिंदतिमु-
- 4 ददिं । कारित गुमट-
- 5 जिनपतिचारुश्रीमू-
- 6 र्ति कुडुगे निमगभिम-
- 7 तमं ॥ श्रीपांछराय जय [॥*]

TRANSLATION.

Let it grant you (every) wish,— the beautiful holy image of Gummaṭa, the lord of Jinās, which was caused to be made with great delight by the glorious Pāṇḍyarāya, the son of Bhairavēndra who was praised by wise men ! O glorious Pāṇḍyarāya, be victorious !

**E.— On the Brahmadvastambha in front of the colossus at Kārkaḷa;
Śaka-Saṃvat 1353.**

This inscription (No. 65 of 1901) is written in the Kanarese alphabet and language. It consists of one verse, which is preceded by a short prose passage, and records that Vira-Pāṇḍya, the son of Bhairava of the family of Jinadatta,— the same prince whose name we have found in the two preceding inscriptions (C. and D.),— set up this pillar which bears at the top an image of Brahman. The date was the 12th *tithi* of the bright fortnight of Phālguna in Śaka-Saṃvat 1353 (current), the cyclic year Rākshasa, i.e. A.D. 1436.

TEXT.⁵

- 1 ॥ यकनृपन १३५८ राक्षससंवत्सर[द फ]ाशुन शु
- 2 १२ शु ॥ 'जिनदत्ताख्यभैरवतनयश्री[की]रपां-

¹ I.e. on the twelfth *tithi*.

Compare the colophon of the next inscription (D.).

² From an inked estampage.

³ From an inked estampage.

⁴ Metre : Kanda.

⁵ Metre : Kanda. Read जिनदत्ता.

3 बह्वृपतिगे वरमं । मनमोल्धीय[लु]¹ नेल[सि]द

4 जिनभक्तं ब्रह्मनीगे निमगभि[मत]मं ॥

TRANSLATION.

On the 12th (*tithi*) of the bright (*fortnight*) of Phālguna in the Rākshasa year (*which corresponded to the year*) 1358 of the Śaka king. Let it grant you (*every*) wish,— (*the image of*) Brahman, the devotee of Jina, who took up his abode² (*here*) in order to grant with pleasure (*every*) desire to the glorious prince Vira-Pāṇḍya, the son of Bhairava of the family of Jinadatta !

F.— On the proper right side of the colossus at Vēṇūr;
Śaka-Samvat 1525.

A fairly correct transcript of this inscription (No. 72 of 1901) was published by Mr. Rice in the Introduction to his *Inscriptions at Śravaṇa-Belgoḷa*.³

The inscription is disfigured by a crack, which has injured one or more letters in almost every line. The alphabet is Kanarese, and the language is Sanskrit verse. In several instances the letter *d* is closed and consequently identical in shape with *dh*. This remark applies also to the next inscription (G.).

The inscription records that Timmarāja of the family of Chāmuṇḍa set up the image of the Jina named Bhujabalin⁴ at Ēnūra (the modern Vēṇūr). This chief was the younger brother of Pāṇḍya, the son of queen Pāṇḍyaka, and the nephew and son-in-law of Rāyakuvāra.⁵ From the fact that the inscription mentions his uncle and mother, but not his father, it may be concluded that he and his family practised the *aḷiya-santāna*, i.e. the inheritance through nephews. Even now the Jaina laymen (*śrāvaka*) of South Canara follow this rule, while the Jaina priests (*indra*) practise the *makkāḷa-santāna*, i.e. the inheritance through sons.

Timmarāja is stated to have set up the image at the instance of the Jaina priest Chārukirti,⁶ who belonged to the *Dēṣigaṇa* and was the pontiff of Belgoḷa (the modern Śravaṇa-Belgoḷa). Hence the latter must have been the spiritual preceptor of his family. This suggests that the Chāmuṇḍa to whose family Timmarāja belonged (l. 14 f.) may be identical with the minister Chāmuṇḍarāja who had set up the colossal statue at Belgoḷa.⁷

The day on which the image was consecrated fell into the expired Śaka year 1525 (in numerical words, l. 4 f.), the cyclic year Śōbhakṛit. Professor Kielhorn kindly contributes the following calculation :—

"The date regularly corresponds, for Śaka-Samvat 1525 expired = Śōbhakṛit, to Thursday, the 1st March A.D. 1604, when the 10th *tithi* of the bright half ended 3 h. 33 m., and the *nakshatra* was Pushya from 1 h. 58 m. (or 2 h. 38 m.), after mean sunrise.—The sign Mithuna was *lagna* from about 5 h. 20 m. to about 7 h. 20 m. after true sunrise, i.e. the time indicated by the date is about midday."

¹ Read "दीयलु."

² I. e. who was set up by the king.

³ Loc. cit. p. 32. The transcript supplied to Mr. Rice contains three misreadings :—*Indu-Pushyakt* for *Guru Pushyakt* (l. 7); *Ēnūra* for *Enūra* (l. 10 f.); and *anuj-Endra-su-rāj-dhhyas* for *anuj-Tēṣṇamardj-dhhyas* (l. 14).

⁴ This is a synonym of *Bhujabalin* in the Kārkaḷa inscription, C. above.


⁵ In the next following inscription (G.) he is called Rāyakumāra. *Kuvāra* is a *śāḍhava* of *Kuvāra*.

⁶ Compare above, p. 110, note 3.

⁷ See p. 108 above.


Jaina Colossi.

VENUR.



WIELE & KLEIN, HALF-TONE.

KARKALA.



E. MULTECH, PHOTO.

TEXT.¹

- 1 श्रीमत्परमगंभीरस्याद्वा-
- 2 दामोघलांछ[नं] । जीयान्ते-
- 3 लोकनाथस्य शास[नं] जिनशास-
- 4 नं ॥ [१*] शकवर्षेष्वतीतेषु विषया-
- 5 क्षिप्रैरेदेषु । वर्त्तमाने शोभन्त-
- 6 ति वत्सरे फाल्गुना[ख्यके] ॥ [२*] मासिथ शु-
- 7 क्लपक्षेष्टदशम्यां शु[क्लपु]ष्यके । सु-
- 8 लग्ने मिथुने देशी[गणांव]रदिनेशितुः
- 9 [॥] [३*] वैष्णुकाख्यपुरीपट्टक्षी[र]ाबुधिनिशा-
- 10 पतेः । चारुकी[र्त्ति]सु[नि]र्हिव्यवाक्वादे-
- 11 नूरपत्तने ॥ [४*] श्री[र]ायकुवरस्याथ
- 12 जामाता त[त्सहो]दरी- । पांड्यका-
- 13 ख्यमहादेव्याः [सु]पुत्रः पांड्यभू-
- 14 पतेः । [५*] अ[नु]ज[स्ति]मरा[जा]ख्यबामुं-
- 15 डाख्य[भूष]कः । अस्या[प]यत्यति[ष्टाप्य]
- 16 भुजवत्स्याख्यकं जिनं ॥ ५^२ ॥ शुभमस्तु ॥

TRANSLATION.

(Verse 1.) Let it be victorious,— the holy religion of the lord of the three worlds, the religion of **Jina**, the unfailing characteristic of which is the extremely profound scepticism !²

(Vv. 2-6.) After the **Saka** years (*measured by*) the objects of the senses (5), the eyes (2), the arrows (5) and the moon (1)⁴ had passed, while the (*cyclic*) year **Śōbhakṛit** was current, in the month named **Phālguna**, on the brilliant (?) tenth *tithi* of the bright fortnight, in (the *nakshatra*) **Pushyaka** (*combined with*) **Thursday**, (*and*) in the auspicious *lagna* **Mithuna**,— at the divine order of the sage **Chārūkirti**, the sun on the firmament of the *Déśigana* (*and*) the moon in the milk-ocean of the pontificate⁵ of the town named **Belguḷa**,— he who was named **Timmarāja**, the ornament of the family of **Chāmunḍa**, the son-in-law of the glorious **Rāyakuvara**, the virtuous son of his sister—the great queen named **Pāṇḍyaka**, the younger brother of prince **Pāṇḍya**, consecrated and set up the **Jina** named **Bhujabalin** at the town of **Entūra**.

(Line 16.) Let there be prosperity !

G.— On the proper left side of the colossus at Vēṇār ;
Saka-Samvat 1526.

This inscription (No. 73 of 1901) consists of two verses in the **Kanarese** alphabet and language. Like the preceding inscription (F.), it records that the image was set up by **Timma**,

¹ From two inked estampages.

² Read ६.

Compare e.g. *South-Ind. Inscr.* Vol. I. No. 152, verse 2, and No. 153, verse 1.

⁴ *J.s. Saka-Samvat* 1525.

Regarding *paṭṭa* see *South-Ind. Inscr.* Vol. I. p. 159, note 1.

the younger brother of Pāṇḍya, the son of queen Pāṇḍyaka, and the nephew of Rāyakumāra. But the image is here stated to be one of the Jina Gummatēśa, the son of Ādjina, and Timma is stated to have belonged to the lunar race and to have ruled over the kingdom of Puñjālike.¹

The date (v. 1) is identical in every detail with that of the preceding inscription (F.); but the Śaka year is here 1526 (in words) current, while there it was 1525 expired.

Two shrines in front of the Vēṇūr image contain two inscriptions (Nos. 74 and 75 of 1901) which are dated in the same year. The shrine on the proper left is a *chaityālaya* of Chandranātha and was built by two queens of Vira-Timmarāja-Oḍeyaru alias Ajilaru, "the beloved chief disciple of the holy Chārukirtidēva," viz. Pāṇḍyakadēvi alias Vardhamānaka, and Mallidēvi. The shrine on the proper right is a *chaityālaya* of Śāntiśvara and was built by alias Binnāpi, another queen of the same chief.²

TEXT.³

- 1 श्रीशकव[र्ष]मं⁴ गणि[से स]सिरदिं मि-
- 2 गुवट्टुलेक्कु[कु]र शतदिप्यता[००]निय
- 3 श्रीभक्तद्वद फालुनाख्यमासात्रि-
- 4 [त]शुक्लपक्षदशमी गुरुपुथद यु-
- 5 [म्स]ल[ग्न]दोळ्देशिगणा[ग्र]गण्यगुरु-
- 6 पंडितदे[व]न दिव्यवाक्य[दिं] ॥ [१*] राय-⁵
- 7 कुमार[नी]प्पुवळियं सति पांड्य-
- 8 कदेवि[य पुन्ननच]⁶ सोमायतवं-
- 9 श[धु]श्र्यनुरुसाहसि पांड्यनृ-
- 10 पानुजनुव्वदानराधेयनुदा-
- 11 र[पुंजळि]केपट्टवनाळ्व नृपाग्रणि
- 12 तिमभूभुजं श्रियुतनं प्रति[ष्ठि]-
- 13 [सि]द[न]दिजिना[ळ]ज[नं जि]नगुं[म]टेशनं ॥ [२*]

TRANSLATION.

(Verse 1.) In the year Śōbhakṛit (which was) the glorious Śaka year counted by twenty six after one hundred having the number five, exceeding one thousand,⁷ (on) the tenth tithi the bright fortnight falling into the month named Phālguna, in (the nakshatra) Push (combined with) Thursday, (and) in the lagna Yugma,—at the divine order of Gurupāṇḍitadēva⁸ who is the foremost of the Dēśīgana,—

(V. 2.) Prince Timma, the beautiful nephew of Rāyakumāra, the son of the virtuous Pāṇḍyakadēvi, the chief of the great family of the Moon, the very daring younger brot

¹ The kingdom (*rājya*) of Puñjāli or Puñjālike is mentioned also in two other inscriptions at Vēṇūr (Nos. 74 and 75 of 1901).

² A very inaccurate translation of Binnāpi's inscription was given in *Ind. Ant.* Vol. V. p. 38, note.

³ From two inked estampages.

⁴ Metre: Utpalamāle.

⁵ I cannot find the name of this metre; it is a *samavṛtta* of 4 times 23 syllables.

⁶ The doubtful syllable *tra* looks as if it had been corrected from *ga*.

⁷ This is a "poetical" way of expressing Śaka-Samvat 1526.

⁸ This title refers to Chārukirti of Belguḷa; see l. 9 f. of the preceding inscription (F.)

of prince **Pāṇḍya**, a **Rādhēya** (**Karṇa**) in excellent gifts, the foremost of princes, who was ruling the noble kingdom of **Puñjālike**, consecrated here (*the image of*) the blessed **Jina Gummatēsa**, the son of **Āḍijina**.

No. 15.—TWO JAINA INSCRIPTIONS OF IRUGAPPA.

By E. HULTZSCH, Ph.D.

A.—Dated in the Dundubhi year.

From an inscription on a lamp-pillar in front of a Jaina temple at Vijayanagara¹ it is known that the general **Chaicha** or **Chaichapa** and his son **Iruga** or **Irugapa** were hereditary ministers of king **Harihara II.** of Vijayanagara. An inscription at **Śravaṇa-Belgoḷa** states that the general **Chaicha** or **Chaichapa** had already been the minister of **Bukkarāya**,² i.e. of **Bukka I.**, the predecessor of **Harihara II.**

The subjoined Tamil and Grantha inscription (No. 41 of 1890) is engraved on the base of the north wall of the store-room in the Jaina temple of **Vardhamāna** at **Tirupparuttikkunru**³ near **Conjeeveram**. It records that the village of **Mahēndramangalam** in the division of **Māvaṇḍūr**⁴ was granted to the temple by the minister **Irugappa**, the son of the general **Vaichaya**. The donor is of course identical with **Irugapa**, the son of **Chaichapa**, who was mentioned in the preceding paragraph. He is stated to have made the gift for the merit of **Bukkarāja**, the son of **Arihararāja**, i.e. **Bukka II.**, the son of **Harihara II.** Hence the **Dundubhi** year in which the grant was made must correspond to **A.D. 1382**. But Professor **Kielhorn** has shown that the details of the date do not work out correctly.⁵

TEXT.⁶

- 1 Svasti śr[i]ḥ [!]* Dundubhi-varsham Kāt[tig]ai-[m]āḍatt[i]l pūrvva-pakshattu=
Tt[i]ṅgaṭ-kiḷamaiyum paupaiyum⁷ peṇṇa Tā(kā)tt[i].
- 2 gai-nāḷ mahāmaṇḍalēśvaran Arihararāja-kumāran śrīmat(d-)Bukkarājan dharmmam
āga Vaichaya-danḍanātha-putran
- 3 Jain-ōttaman Iruga[pa]-mahāpradhāni Ti[rup]paruttikkunru-nāyaṇār Trailōkyavalla-
bharkku pūjaikku
- 4 śālaikkum tiruppanik[ku]m Māvaṇḍūr-pparṇil Mahēndramangalam nār-pār-k-
ellaiyum iṇai-ili paḷḷichchandam=āga chandr-āditya-varaiyum naḍakka=ttaruvittār
Dharmam[ō]=ya[ū=ja]yatu ॐ

TRANSLATION.

Hail! Prosperity! (*In*) the **Dundubhi** year, (*on*) the day of **Kāttigai** (**Kṛittikā**), which corresponded to a Monday and to the full-moon *tithi* of the first fortnight in the month **Kāttigai**,— for the merit of the glorious **mahāmaṇḍalēśvara Bukkarāja**, the son of **Arihararāja**,— the best of Jains, the great minister **Irugappa**, the son of the general **Vaichaya**, caused to be

¹ *South-Ind. Inscr.* Vol. I. No. 152.

² *Inscriptions at Śravaṇa-Belgoḷa*, No. 82. The Śubhakṛit year in which this inscription is dated corresponds to A.D. 1422, and not to A.D. 1362 as Mr. Rice thinks.

³ No. 61 on the *Madras Survey Map* of the Conjeeveram taluka.

⁴ This is evidently **Māvaṇḍūr**, 5 miles from Conjeeveram; see Mr. Sewell's *Lists*, Vol. I. p. 166. I cannot identify **Mahēndramangalam**.

⁵ Above, Vol. VI. p. 329, No. 1.

⁷ The syllable *ṇai* is entered below the line.

⁶ From two inked estampages.

given to Trailôkyavallabha, the god of **Tirupparuttikkunru**, for worship, for the alms-house, and for repairs of the temple,— (*the village of*) **Mahêndramangalam** in the division (*parru*) of **Māvandûr**, (*up to its*) boundaries on the four sides, as a tax-free *pallichchandam*,¹ to continue as long as the moon and the sun. Let this pious gift be victorious !

B.—Dated in the Prabhava year.

This Grantha inscription (No. 42 of 1890) is engraved on the roof of the *maṇḍapa* in front of the shrine in the same temple as the preceding inscription (A.), and consists of one Sanskrit verse in the Śārdûlavikrîḍita metre. It records that the *maṇḍapa* on which it is found was built by the same general **Irugappa**, the son of the general **Vaichaya**, at the instance of (his spiritual preceptor, the Jaina priest) **Pushpasêna**, in the year **Prâbhava**. This year might be meant for **Parâbhava** = A.D. 1366-67, which would, however, fall into the reign of **Bukka I.** Hence it follows that **Prâbhava** is used on account of the metre instead of **Prabhava** = A.D. 1387-88, which falls into the time of **Bukka II.**,² the contemporary of **Irugappa**.³

In this inscription the temple of the Jina **Vardhamâna** is said to have been included in **Kâñchi**, of which **Tirupparuttikkunru**⁴ was evidently considered a suburb.

TEXT.⁵

- 1 Śrîmat(d-)Vaichaya-daṇḍanâtha-tanayas=samvatsarê Prâbhavê saṁkhyâvân=Irugappa-daṇḍanripatis=śrî-Pushpasên-âjñayâ ||
2 śrî-Kâñchi-Jina-Vardhamâna-nîlayasy=âgrê mahâ-maṇḍapam saṁgîṭ-ârttham=achîkarach=cha śîlayâ baddham samantât sthalam || ८

TRANSLATION.

In the year **Prâbhava**, at the order of the holy **Pushpasêna**,— the wise general **Irugappa**, the son of the glorious general **Vaichaya**, caused to be built, in front of the temple of the Jina **Vardhamâna** at the prosperous **Kâñchi**, a great hall for concerts and (*caused to be*) paved with stones the space all round.

No. 16.—TWO BRAHMI AND KHAROSHTHI ROCK-INSRIPTIONS IN THE KANGRA VALLEY.

By J. PH. VOGEL, LL.D.

The first of these two rock-inscriptions was discovered by Sir E. C. Bayley at **Kanhiâra**, three miles to the east of Lower **Dharmasâlâ** on the bank of the **Mânjî** torrent, and was edited by him in 1854 from drawings made by Lieutenants **Crofton** and **Dyas**.⁶ In 1875 it was reproduced again and discussed by General **Cunningham**.⁷

The second inscription I found last summer in the course of an archæological tour in the **Kangra** district near a place called **Paṭhyâr**, situated nine miles south of **Kanhiâra** on the bank of the **Baner** rivulet, at a distance of about one mile from the **Dâdh Travellers' Bungalow**.

¹ This term means 'land belonging to a Jaina temple;' see *South-Ind. Inscr.* Vol. II. p. 52, note 2, and above. Vol. IV. p. 138.

² See above, Vol. VI. p. 329 f.

³ See p. 115 above.

⁴ See above, A. I. 3.

⁵ From an inked estampage.

⁶ *J. A. S. B.* Vol. XXIII. p. 57.

⁷ *Arch. Survey Reports*, Vol. V. p. 175, Plate xlii.

The two inscriptions are so nearly alike in script, substance and general character that it appears desirable to publish them together, the more so as the Kanhiâra inscription has not yet been edited satisfactorily and the Paṭhyâr inscription, as far as I know, has not been noticed before by any archæologist.

The legend in both cases is given in two different alphabets,—Brâhmî and Kharôshthî, though evidently of two very different periods. In each case the inscription contains only two words in both scripts, whereas a third word occurs in one script only. But at Kanhiâra this additional word belongs to the Brâhmî, while at Paṭhyâr it forms part of the Kharôshthî legend. The explanation of this third word is somewhat difficult. Otherwise the reading may be said to be beyond doubt, owing to the enormous size and the clearness of the letters, which are deeply cut in hard granite boulders. Finally two auspicious symbols are in each case added after the Brâhmî legend, one of which is the well-known *svastika*.

The Kanhiâra inscription was read by Sir E. C. Bayley as follows:—*Krishnayasasa ârâma* in Kharôshthî, and *Krishnayasasya ârâma medangisya* in Brâhmî. I may state at once that the correct reading of the first word appears to be *Krishnayasasa* and *Krishnayasasya* respectively, whereas the length of the first *a* of *ârâma*, as a matter of fact, is not expressed in Kharôshthî.¹ He explains it as “the garden of Krishnayasas, to which in the second inscription some wag has apparently added the epithet *medangisya* (corpulent) from *med* (fat) and *anya* (body).”

Cunningham, however, preferred to consider *ârâma* as a synonym of *vihâra*, translating it by “the monastery of Krishnayasas,” and even went so far as to derive the name Kanhiâra from *Kanhiya-yasas-ârâma*, Kanhiya being a synonym of *Krishna*. The third word he read *mâdangisya*, and he thought it to be “the name of the district or possibly of the recorder of the inscription.”

Now, before entering upon any discussion of these doubtful points, it will be well to examine the other inscription, which from its similarity is likely to contribute fresh evidence. The Paṭhyâr inscription consists of two lines, cut into one stone. The upper line gives the two words in Brâhmî followed by a *svastika* and a foot-print. In the lower line, which was partly buried in the ground, is the Kharôshthî legend, which consists of three words. The Brâhmî letters are of considerable size, the final one being not less than $1\frac{1}{2}$ high. The Kharôshthî characters are much smaller (5" to 9"). Thus, notwithstanding the difference in the number of letters, both lines are about equal in length, viz. $7\frac{1}{2}$ ’.

It is evident at once that the two words in Brâhmî correspond to the second and third words of the Kharôshthî legend. I read them *Vayulasa pukarini*² or, in correct spelling, *Vâyulassa pukkhariṇi*, the meaning being simply “Vâyula’s lotus-pond.” With regard to the first word of the Kharôshthî, the meaning is less obvious. Manifestly it is a genitive defining the proper name *Vâyulassa*. It seems to me almost certain that it has to be read *rathidarasa*, i.e. in Sanskrit *rathitarasya*. The *i* may be either short or long. If short, the word is to be taken as the comparative of *rathin*; if long, of the Vêdic *rathî*. The meaning remains the same, viz. ‘charioteer’ (from *ratha*). According to the *St. Petersburg Dictionary* the word *rathâtara* occurs as a proper name in the *Vishṇupurâṇa* also. But the meaning which has to be assigned to the word in the Paṭhyâr inscription is, I believe, a different one. *Râthî* is the name of an agricultural caste in Kângra.³ If Vâyula really was a *Râthî*, we may infer that, in the time of the inscription, the *Râthîs* were not inhabitants

¹ I have to point out that the *a* has a small horizontal stroke to the right. But it is little prominent and may be a natural hole in the rock.

² The length of *a* in *vâ* is expressed only in the Brâhmî. The *u*-stroke of *yu* is not found in the Brâhmî, but is perfectly clear in the Kharôshthî legend.

³ *Gazetteer of the Kangra District*, Vol. I. (1883-84), p. 88 f.

of that fertile part of the valley to which Paṭhyâr certainly belongs. For, if this had been the case, a man belonging to the Râṭhî caste would hardly have designated himself as such in order to distinguish himself from his neighbours. This, as far as I can see, is the only historical conclusion which can be drawn from the Paṭhyâr inscription. Its chief interest therefore, is purely palæographical.

If we compare the two inscriptions, it is obvious that the Paṭhyâr stone exhibits a much earlier type of script than the Kanhiâra one. This is evident in part from some of the Kharôshṭhî letters, *e.g.* the *s*, which at Paṭhyâr has the closed shape of the Aśoka period whereas at Kanhiâra it is open as in the Śaka-Kushana inscriptions. On the whole, however the Kharôshṭhî of both inscriptions is fairly identical. But a striking difference is shown in the Brâhmî legends. The Kanhiâra inscription was assigned by Bayley and Cunningham to the first century after Christ. Possibly it is later. The *y* with its three vertical strokes of equal length agrees best with forms of the 2nd and 3rd centuries.¹ The *ā* shows a great resemblance to the type of this letter in the 2nd century.² The *m* is angular instead of rounded as in the more ancient type. The *ś*, on the contrary, with its straight strokes has a more archaic form. So has the *g*, which is angular and not rounded.

The Brâhmî type of the Paṭhyâr inscription, however, corresponds entirely with that of the Aśoka period — the earlier Maurya type as Professor Bühler called it — and therefore can safely be said to belong to the 3rd century B.C.³ We may infer that both Brâhmî and Kharôshṭhî were known and used in the Kāngra valley from that time until the first or second century after Christ.

It is a fact worth noticing, that, while the indigenous character had developed considerably during the course of the three or four centuries, the foreign alphabet had practically remained the same. The most plausible explanation would be that in those parts the Brâhmî was the popular script used in commerce and common life, while the use of the Kharôshṭhî was limited to official documents and was in consequence fairly constant. The greater importance attached to the Brâhmî may also appear from its taking the first place in the Paṭhyâr inscription and from the larger size of the letters, though it must be admitted that the fuller reading is given in Kharôshṭhî. In the Kanhiâra inscription the Brâhmî has the additional word. But in both inscriptions the *maṅgalas* are placed after the Brâhmî and not after the Kharôshṭhî.

Now, to return to the Kanhiâra inscription, it remains to be considered whether the newly found inscription throws any light on its meaning. First of all one feels inclined to assign to the word *ārāma* the ordinary meaning of 'garden,' and not that of 'monastery' as Cunningham did.⁴ For, considering that Vâyula found it worth while to cut an inscription which would stand the ages, simply to indicate that he was the owner of a lotus-pond, there is no reason to assume that Krishṇayaśas did not do the same with regard to his garden. Moreover, in the case of a monastery the founder would preferably have written his name on the building, and not on two boulders lying near it.

With regard to the doubtful term *medamgisya*, we may with Cunningham reject Bayley's supposition that the word was added by some wag in order to ridicule Krishṇayaśas. It would have been a very poor joke indeed and scarcely worth the trouble of cutting into hard granite. And are we to believe that the same wag had cut the two *maṅgalas* also, possibly to make amends for the offence? Corpulence, moreover, is looked upon with a different eye by the Hind

¹ See Bühler's *Indische Palæographie*, Plate iii. 31, XV. and XVIII.

² *Ibid.* 2, XI.

³ Since writing the above, I had an opportunity of showing the impression to Dr. M. A. Stein, who, judging from a superficial examination of the Kharôshṭhî, thought that the inscription was rather of the early Śaka type.


⁴ This meaning is not even mentioned in the *St. Petersburg Dictionary*.

Rock-Inscriptions in the Kangra Valley.

KANHIARA INSCRIPTION.



PATHYAR INSCRIPTION.



E. H. TZSCH.

SCALE '07.

WIELE & KLEIN, PHOTO-ZINCO.

From inked estampages supplied by Dr. J. Ph. Vogel.

and by the European. Large and round limbs were considered characteristics of a *mahāpuruṣa*,¹ and every traveller in India will get the impression that this is the case even now.

Most probably the third word in both inscriptions indicates the caste or clan of the person mentioned. Among the meanings assigned to the word *mēda* by the *St. Petersburg Dictionary* there is that of 'a certain mixed caste.' But this explanation would have to be abandoned, if with Cunningham we read *mādaṅgisya*. It is true that the *ā*-stroke is ordinarily attached to the right, not to the left leg of the *m*; but, on the other hand, we never find the *e*-stroke turned to the right. Comparing the manner in which the *ā*-stroke is attached to *p*, *s* and *h*, we must consider Cunningham's reading correct. Unfortunately *mādaṅgisya* is as difficult to explain as *medaṅgisya*. If we ignore the *i* in the penultimate syllable, it would correspond to the Sanskrit *Mātaṅgasya*; but that a member of this caste would be the owner of a garden and bear the name of Krishṇayaśas is scarcely admissible.

It was stated above that one of the two *maṅgalas* added to the Brāhmī legend is the *svastika*. The other Cunningham interpreted as an abbreviation of the syllable *śm*. This, however, does not seem very probable considering that that sacred syllable is always found at the beginning, never at the close of a sentence. But when we compare the two inscriptions in this respect, we discover a remarkable resemblance between the two *maṅgalas* also. The mystic sign of the Kanhiāra inscription appears to be nothing but an ornamental development of the foot-print. It would be hazardous to draw from these signs any conclusions with regard to the creed of the authors. It is true that the foot-print and the *svastika* are favourite signs of good omen with the Buddhists; but it should be borne in mind that they are equally honoured by the Hindūs in general and probably were so even in pre-Buddhistic times.

One point still remains to be discussed,—the language. In the older inscription it is Prākṛit or Middle-Indian of the Śaurasēni-Mahārāṣṭrī, not of the Māgadhi type, as appears from the *r* in *pukkhariṇī*.² In the Kanhiāra inscription there is a difference of language in the two legends. The Kharōṣṭhī legend is written in a Prākṛit of which the distinction made between the three sibilants is a remarkable feature. The language of the Brāhmī legend would best be characterised as Sanskritised Prākṛit, such as came into vogue among the Northern Buddhists with the rise of the Mahāyāna system. Thus linguistic evidence also would assign to this inscription the same time of origin as was found probable in view of palæographic considerations. That Cunningham was wrong in calling the language simply Sanskrit scarcely needs to be demonstrated.

NO. 17.—TWO INSCRIPTIONS OF TAMMUSIDDHI,

SAKA-SAMVAT 1129.

By H. LÜDERS, PH.D.; GÖTTINGEN.

The first of the following two stone inscriptions is engraved on the east wall of the Natarāja shrine in the *Vaṭāranyēśvara* temple at *Tiruvālaṅgādu*, 3 miles N.-N.-E. of the Chinnamapēt Railway Station in the North Arcot district. The second is on the north wall of the central shrine of the *Vāchiśvara* temple at *Tiruppāśūr*, 2 miles W.-S.-W. of Tiruvallūr in the Tiruvallūr tāluka of the Chingleput district. They are now edited for the first time from inked estampages supplied to me by Dr. Hultsch.³

¹ A. Grünwedel, *Buddhistische Kunst in Indien*, sec. ed. (1900), p. 138.

² See Professor Pischel's *Grammatik der Prakrit-Sprachen* (1900), p. 24.

³ Nos. 408 and 407 of the Government Epigraphist's collection for the year 1896.

and by the European. Large and round limbs were considered characteristics of a *mahāpuruṣa*,¹ and every traveller in India will get the impression that this is the case even now.

Most probably the third word in both inscriptions indicates the caste or clan of the person mentioned. Among the meanings assigned to the word *māda* by the *St. Petersburg Dictionary* there is that of 'a certain mixed caste.' But this explanation would have to be abandoned, if with Cunningham we read *mādaṅgisya*. It is true that the *ā*-stroke is ordinarily attached to the right, not to the left leg of the *m*; but, on the other hand, we never find the *e*-stroke turned to the right. Comparing the manner in which the *ā*-stroke is attached to *p*, *s* and *h*, we must consider Cunningham's reading correct. Unfortunately *mādaṅgisya* is as difficult to explain as *medaṅgisya*. If we ignore the *i* in the penultimate syllable, it would correspond to the Sanskrit *Mātāṅgasya*; but that a member of this caste would be the owner of a garden and bear the name of Kṛishṇayaśas is scarcely admissible.

It was stated above that one of the two *maṅgalas* added to the Brāhmī legend is the *svastika*. The other Cunningham interpreted as an abbreviation of the syllable *ōm*. This, however, does not seem very probable considering that that sacred syllable is always found at the beginning, never at the close of a sentence. But when we compare the two inscriptions in this respect, we discover a remarkable resemblance between the two *maṅgalas* also. The mystic sign of the Kanhiāra inscription appears to be nothing but an ornamental development of the foot-print. It would be hazardous to draw from these signs any conclusions with regard to the creed of the authors. It is true that the foot-print and the *svastika* are favourite signs of good omen with the Buddhists; but it should be borne in mind that they are equally honoured by the Hindūs in general and probably were so even in pre-Buddhistic times.

One point still remains to be discussed,—the language. In the older inscription it is Prākṛit or Middle-Indian of the Śaurasēni-Mahārāṣṭrī, not of the Māgadhi type, as appears from the *r* in *pukkhariṇī*.² In the Kanhiāra inscription there is a difference of language in the two legends. The Kharōṣṭhī legend is written in a Prākṛit of which the distinction made between the three sibilants is a remarkable feature. The language of the Brāhmī legend would best be characterised as Sanskritised Prākṛit, such as came into vogue among the Northern Buddhists with the rise of the Mahāyāna system. Thus linguistic evidence also would assign to this inscription the same time of origin as was found probable in view of palæographic considerations. That Cunningham was wrong in calling the language simply Sanskrit scarcely needs to be demonstrated.

NO. 17.—TWO INSCRIPTIONS OF TAMMUSIDDHI,

SAKA-SAMVAT 1129.

By H. LÜDERS, PH.D.; GÜTTINGEN.

The first of the following two stone inscriptions is engraved on the east wall of the Naṭarāja shrine in the Vaṭāraṇyēśvara temple at Tiruvālaṅgāḍu, 3 miles N.-N.-E. of the Chinnamapēṭ Railway Station in the North Arcot district. The second is on the north wall of the central shrine of the Vāchiśvara temple at Tiruppāśūr, 2 miles W.-S.-W. of Tiruvallūr in the Tiruvallūr tāluka of the Chingleput district. They are now edited for the first time from inked estampages supplied to me by Dr. Hultsch.³

¹ A. Grünwedel, *Buddhistische Kunst in Indien*, sec. ed. (1900), p. 138.

² See Professor Pischel's *Grammatik der Prakrit-Sprachen* (1900), p. 24.

³ Nos. 408 and 407 of the Government Epigraphist's collection for the year 1896.

Both of them are intended to commemorate the donations of a king **Tammusiddhi** or **Tammusiddha**, who belongs to a family of Telugu chiefs of whom numerous records have been discovered since 1892 in the Chingleput, North Arcot, Nellore and Kistna districts. On these materials Mr. Venkayya has based his valuable account of the Chôḍas of the Telugu country in the *Annual Report for 1899-1900*. However, as none of the inscriptions made use of by Mr. Venkayya have been published until now, I shall confine my remarks to the facts furnished by the following two inscriptions alone.

The **Tiruvālaṅgāḍu** inscription is damaged in a few places, but the illegible passages can easily be restored, partly from the context alone, and partly with the help of the Tiruppāśūr inscription. It is written in **Grantha** characters. The size of the letters varies from $\frac{3}{4}$ " to 2". Line 8 contains the rare subscript sign for *jha* in *nirjḥarā*. The language is **Sanskrit**, and, with the exception of the concluding words *svasty=astu*, the whole text is in verse. As regards orthography, it may be pointed out here that in the middle of a word *t* is written instead of *d* before a sonant consonant in the word *patma* in ll. 1, 2, 3, and in *bhavatbhir* in l. 21.

After two introductory verses in praise of the donor, who, as stated above, is called both **Tammusiddhi** (ll. 2, 17, 18) and **Tammusiddha** (ll. 1, 20, 21), the inscription gives his genealogy, which shows the characteristic features of the Chôḍa genealogies.

It begins with some mythical ancestors. From the lotus of Vishnu's navel sprang Brahman (vv. 3, 4), from him Marichi, from him Kaśyapa (v. 5), from him the Sun (v. 6), and from him Manu (v. 7), in whose family there were born many kings (v. 8). This is the genealogy of the solar race as taught in the *Purāṇas*.¹ It is found also in the Udayēndiram plates of Prithivīpati II.² and those of Vīra-Chôḍa,³ as well as in the *Kalīṅgattu-Parani*⁴ and the *Vikkirama-Śōḷaṅ-Uḷā*;⁵ but in the last three passages the third name appears as **Kāśyapa** or **Kāchchipaṇ** instead of **Kaśyapa**. The *Vikkirama-Śōḷaṅ-Uḷā* differs besides in placing **Kāśyapa** before Marichi, and the Udayēndiram plates of Prithivīpati II. omit Manu.

The inscription next mentions three kings who form the connecting link between these sages of old and the direct ancestors of **Tammusiddhi**. The first of them, born in the lineage of Manu, is **Kalikāla** (v. 9). **Kalikāla** is identical, of course, with the ancient half-mythical Chôḍa king whose name is generally given as **Karikāla**. The various traditions about him have been collected by Dr. Hultsch.⁶ In the present inscription we are told that he constructed the banks of the **Kāvēri**, and that, when he had lifted Mount **Mēru** with his play-staff, the quarters were greatly disturbed or confounded. The story about the construction of the banks of the **Poṇṇi** or **Kāvēri** is alluded to also in the *Kalīṅgattu-Parani*,⁷ the *Vikkirama-Śōḷaṅ-Uḷā*,⁸ and the large Leyden grant.⁹ The second legend, implied by the words of the inscription, is not known to me, but it is probably connected in some way with another legend recorded by the two Tamil poems. According to the *Kalīṅgattu-Parani* **Karikāla** inscribed on the side of Mount **Mēru** the whole history of the Tamil race as foretold by the *Rishi* **Nārada**, and in the *Vikkirama-Śōḷaṅ-Uḷā* he is spoken of as "the king who set his tiger-banner on the mountain whose summit gleams with crystal waterfalls," where the mountain meant by the poet would seem to be again Mount **Mēru**.

¹ See, e.g., *Agnipurāṇa*, 5, 2:—

Vishṇuṇḍibhyabjaśō Brahmd Marichir-Brahmaṇaḥ sutaḥ |

Marichir Kaśyapa=taṁcāt Sūryō Vaidasvatō Manuḥ ||

Compare also 272, 1 f.; *Rāmāyaṇa*, I, 70, 19 f.; 2, 110, 5 f.

² *South-Ind. Inscr.* Vol. II. p. 382.

³ Above, Vol. III. p. 80 f.

⁴ Canto 8, vv. 9, 10; *Ind. Ant.* Vol. XIX. pp. 330, 340.

⁵ *Ind. Ant.* Vol. XXII. pp. 144, 147 f. Manu is not mentioned here by name, but alluded to as "the stern

sire who drove his chariot over his son to soothe a cow in dire distress."

⁶ *South-Ind. Inscr.* Vol. II. p. 377 f.

⁷ Canto 8, v. 20; *loc. cit.* pp. 331, 341.

⁸ *Loc. cit.* pp. 144, 148.

⁹ *Archaeological Survey of Southern India*, Vol. IV. p. 208.

The verses 10 and 11 are devoted to a king who is said to have been born in the lineage of Kalikāla, and to have had two names,—**Madhurāntaka**, i.e. 'the death to Madhurā,' and **Pottapi-Chōla**. The former name he acquired by conquering **Madhurā**, the capital of the **Pāṇḍyas**, whose women he made widows; the latter was given to him for having founded, in the country of the **Andhras**, the town of **Pottapi**. **Madhurāntaka Pottapi-Chōla** is a name frequently met with as that of a local chief in the inscriptions at Conjeeveram, the ancient **Kāñchīpura**; in the list compiled by Mr. Sewell¹ it occurs more than thirty times. Provided, however, that all these inscriptions are to be referred to the same person, it is impossible that that chief of **Kāñchīpura** should be identical with the ancestor of **Tammusiddhi**; for one of his inscriptions is dated in the 18th,² and another in the 21st year of *Tribhuvanachakravartin* **Rājarājadēva**,³ which correspond to A.D. 1233-34 and 1236-37, respectively. He must have been a much younger member of the family, and Mr. Venkayya, for other reasons, is inclined to identify him with **Chōla-Tikka**, who probably was the successor of **Tammusiddhi**.⁴ The identification of **Pottapi**, which **Madhurāntaka Pottapi-Chōla** is said to have founded, must be left to future researches.⁵

In **Madhurāntaka Pottapi-Chōla**'s race was born **Tilūṅgavidya** (v. 12). The only feat recorded of him is the erection of a pillar of victory with a figure of **Garuḍa** at the top of it at **Ujyapuri**.⁶ **Ujyapuri** may be the modern **Ūjīpuram** or **Ujjapuram**, 18 miles east-south-east of **Kollēgāl** in the Coimbatore district. Mr. Sewell states that there is an old ruined fort at that place,⁷ and there is no difficulty in assuming that one of these Telugu **Chōlas** should have extended his conquests beyond the **Kāvērī**, if another boasts even to have taken **Madhurā**.

With verse 13 begins a coherent genealogy of the direct ancestors of **Tammusiddhi**. In **Tilūṅgavidya**'s family was born king **Siddhi** (v. 13). His younger brother was **Betta (I.)**, who had several sons (v. 14), the eldest of whom was **Dāyabhīma** (v. 15). **Dāyabhīma**'s younger brother was **Ērasiddhi** (v. 16). He again had three sons, **Manmasiddhi** or **Manmasiddha**, **Betta (II.)**, and **Tammusiddhi**, whose mother bore the name of **Śrīdēvi** (vv. 17-20). Of these only **Siddhi**, **Dāyabhīma** and **Manmasiddhi** are described in terms implying that they actually reigned, while of **Betta II.** it is expressly stated that, being given to the practice of austerities, he conferred, after the death of **Manmasiddhi**, the government on his younger brother **Tammusiddhi**.

In verse 21 we are informed that in the **Śaka year 1129** (= A.D. 1207-8) **Tammusiddhi** allotted to the lord of **Vaṭāṭavi** all the revenues due to the king in the villages belonging to the temple. The inviolability of this order is enjoined in the two concluding verses (22, 23). As regards the name of the god, it is apparently derived from that of the village where the temple is situated, **Vaṭāṭavi** or its modern synonym **Vaṭārāpya** being Sanskrit renderings of the Tamil **Tiruvālaṅgādu**, 'the holy banyan forest.'

The **Tiruppāsūr** inscription closely resembles the **Tiruvālaṅgādu** inscription in outward appearance as well as in its contents. It is written in **Grantha** characters, about 1½" high. The form of the subscript *jha* in *nirjjharā* in l. 19 slightly differs from that of the **Tiruvālaṅgādu** inscription, the loop to the left having disappeared here altogether. The initial *ē* also has a

¹ *Lists of Antiquities*, Vol. I. p. 178 ff.

² No. 37 of the Government Epigraphist's collection for 1893.

³ *Lists of Antiquities*, Vol. I. p. 187 (No. 277). Mr. Sewell mentions also an inscription (No. 74) dated "in Śaka-Samvat 1232, in the 24th year of his reign."

⁴ *Loc. cit.* p. 19. In the genealogical table, *ibid.* p. 18, Mr. Venkayya mentions a certain **Madhurāntaka Pottapi-Chōlasiddhi** who belonged to another branch of the Telugu **Chōlas**. But he also cannot possibly be the person of that name in the present inscription, as he is represented as a descendant of **Telūṅgabijjana**, whereas the **Madhurāntaka Pottapi-Chōla** of our inscription was an ancestor of that king.


⁵ [See *South-Ind. Inscr.* Vol. III. p. 33, note 1. The *Postal Directory of the Madras Circle* mentions a village "Potapi" near "Tongootoor" in the Pullampēt taluka of the Cuddapah district.—E. H.]

⁶ Or, possibly, **Ūjyapuri**. The quantity of the initial vowel cannot be made out from the text, as it is united here with the final vowel of the preceding word (*yēn=Ūjyapuryydm*).

⁷ *Lists of Antiquities*, Vol. I. p. 215.

very peculiar form in l. 61, whereas in l. 11 it appears in the usual shape. The language is **Sanskrit**, and the whole is in verse, with the exception of the words *svasty=astu* at the end. Here also a surd consonant is written instead of a sonant in *patma* (ll. 2, 3, 4) and *bharatbhir* (l. 64), and besides in *drīkbbhyām* (l. 4) and *dik dakṣiṇā* (l. 35).

Of the 23 verses of the Tiruvālaṅgāḍu inscription 16 reappear in this inscription, occasionally with slight variations.¹ With respect to the earlier part of the genealogy (vv. 2-9) it is to be noticed that the verses about Manu and Tiluṅgavidya are omitted here. That portion also which deals with the direct line of Tammusiddhi's ancestors (vv. 10-17) shows one important point of difference. No mention is made of Betta I. and of Dāyabhīma. Instead of the two verses devoted to them in the Tiruvālaṅgāḍu inscription we find here a verse (11) stating that in king Siddhi's family was born king Nallasiddhi. In the following verse Śrasiddhi is called his younger brother, which term in the identical verse 16 of the Tiruvālaṅgāḍu inscription applies to Dāyabhīma spoken of in the preceding verse, and it might therefore easily be imagined that Dāyabhīma and Nallasiddhi were only different names of the same king. Fortunately, an inscription at Tiruvorriyūr,² quoted by Dr. Hultzsch in his *Annual Report for 1893*, paragraph 13. leaves no doubt that they were two distinct persons, and the pedigree to be derived from the two inscriptions edited here is thus to be arranged in the following manner :³—



Besides the name of Nallasiddhi the Tiruppāsūr inscription contains little that is new. Nallasiddhi seems to have taken possession of Kāñchi or Conjeeveram; for in verse 11 it is said, with a well-known pun, that, when the southern quarter had obtained him as her husband, she was *gaḷita-kāñchi-guṇā*, which may be understood as 'having dropped her girdle' or 'having lost Kāñchi.' In verse 15 we are told once more, but in a more explicit way, that after the death of Manmasiddhi the government passed without any disturbances into the hands of Tammusiddhi, Betta II. being of a religious turn of mind and therefore renouncing his claims to the throne in favour of his younger brother.

The verses 18 and 19 record that in the Śaka year 1129 (=A.D. 1207-8) Tammusiddhi allotted to the lord of Pāśipura the revenues due to the king in the villages belonging to the

¹ The name of the town founded by Madhurāntaka Pottapi-Chōla is here spelled Pottappi (v. 9).

² No. 104 of the Government Epigraphist's collection for the year 1892.

³ The purely fictitious first portion has been omitted here.

temple, and that in the same year he presented the village of **Kaivaṇṭūr** to the god. Pāṣipana, of course, is nothing but the Sanskrit name of Tiruppāsūr. The village of Kaivaṇṭūr, as Dr. Hultzsch informs me, is identical with Kaivaṇḍūr,¹ 1 mile W.-N.-W. of Tiruppāsūr.

A.—TIRUVALANGADU INSCRIPTION.

TEXT.²

- 1 Svasti śrī-Tammusiddhāya tasmai yat-sainya-rēpava[h] [*] [Brahma-pa]tma(dma) spriśās=śamkē bhāvi-bhū-sṛiṣṭi-hētavaḥ || [1*] Jayati vijayi-chāpaḥ kṣaṇit-ā[śē]sha-[pāpa]s=satata-madhura-lā-
- 2 paḥ prāpta-vidyā-kalāpaḥ [*] vitata-vitaran-āpaś=śatru-māyā-durāpaḥ pra[samita]-kali-tāpas=Tammusiddhi-kṣhamāpaḥ || [2*] Udadhi-śayana-bhājaḥ Patma(dma)-nābhasya nābhēḥ kim=api nikhila-hētur=jjātam=āścha-
- 3 ryya-patma(dma)m [*] yad=abhajad=api sṛiṣṭēḥ pūrvam=ētasya dṛighhyā[ra]=mṛidu-kāthina-ma[h]bhēḥm=mīlan-ōmīlanāni || [3*] Tasmād=Viriñchir=abhavar suchiran=tad-a-
- 4 ntar=vvāsād=iva prakatayann=rajasah pra[vṛittim] [*] ya[h*] Śrīśa-ta[pa-phaṇi-mauli]-maṇi-prarūḍha-bimbās=srijaṇn=iva babhau sadṛśās=sahāyān³ || [4*]
- 5 Marīchir=udagāt=tasmād=uday-ādrēr=iv=āmsumān [*] [tataḥ] Kāśyapa ēta-sarva prakāśa iva nirgataḥ⁴ || [5*] Asmāj=ja[gat*]-trita[ya-maṅgala-rat]nadīpaś=chhanā-
- 6 s-tanus=timira-kānana-dāvavahniḥ [*] di[k*]-kālayōḥ kim=aparam vyavahā[ra*]-hētu[h] kō=py=āvirāsa vasudhādhipa-vamśa-kandaḥ || [6*] Tasmād=idam prathama-sambhṛita-rāja-śa-
- 7 bdaḥ pūrnō guṇair=nnikhila-nīti-patha-prayōktā [*] dēvō Manus=sapadi gōptum=iv=āvatirṇnas=tan-maṇḍal-ānta[ra*]-gata[h] p]urushaḥ purāṇaḥ || [7*] Babhū-
- 8 vur=ullāsita-kīrtti-nirjharā Manōḥ kulē=smin bahavaḥ kṣhamābhṛitaḥ [*] divas-prithivyōr=api yair=nniyantṛibhir=nnirāmkuśō nīti-pathaḥ⁵ pravartita[h] || [8*]
- 9 Tat-kulē **Kālikālōlō**=bhūt⁶ [Kāvērī-tīra-kṛin=nṛipaḥ] [*] [yat-kē]lī-yashī-tulitē Mērau vyatikṛitā diśaḥ || [9*] Jātō=sya vamśē Madhurām viji-
- 10 tyā paśchād=udañchana(n-Ma)dhurāntak-ākhyah [*] nitānta-mukt-ābha[ra*]nāḥ prachandah Pāṇḍy-āṅganāḥ prāg=iva yaś=chakāra || [10*] Jishnur=Andhrēshu yah kṛitvā purim Pottapi-samñjitām⁷ [*]
- 11 tatas=tat-pūrvva-[Chō][*]-ākhyah⁸ prakhyāta-bhujā-vikramaḥ || [11*] Tad-vamśē sa Tilumgavidya-nṛipatir=yyēn=Ōjyapuryyām=asau chañchata(t)-kīrtti-patākayā tilakita-stambhaḥ pratishṭhāpi-
- 12 taḥ [*] yasy=āgrē Garuḍan=nirīkshya sahaja-snēhēna sūtē sthitē maddhyē-vyō[ma] vilambatē dinapatiḥ prāyas=tad-ādi kṣhaṇam || [12*] Tat-kulē Siddhi-bhūpālāḥ pālayām=ā-
- 13 sa mēdinim [*] yadiya-dōḥ-pad-āyattam=artthi-pratyartthi-jīvitam || [13*] Anujānna=ābhavat=tasya Betta-bhūpaḥ pratāpavān [*] tasy=āpi jajūirē putrās=tatāraś-śaran-ārtthinām || [14*] Dāyabhimō n[ri]pa-
- 14 s=tēshā[ra] jyēshṭhaḥ kṣhōṇim=apālayat [*] yat-pāpīś=śātrava-śrīpān=kēs-ākṛiṣṭi-kash[ā*]yitaḥ || [15*] Tasy=Airasiddhi-nṛipatis=sahajaḥ kantiyān=dūran=nirasya kalim=asya punaḥ-pravēśam [*] rōddhum pravṛi[t]ta

¹ No. 63 on the *Madras Survey Map* of the Tiruvallūr taluka.

² From inked estampages supplied by Dr. Hultzsch.

³ Read *sahāyān*.

⁴ The sign for *rga* looks rather strange, but it cannot possibly be meant for anything else.

⁵ The *visarga* has been added below the line.

⁶ Read *Kālikālōlō*.

⁷ The *chō* has been added below the line.

⁸ Read *samñjitām*.

- 15 iva yaḥ prachuraṁ yaśa[h*] sva[n*]=dik-sīmasu sphaṭika-sāla-nibha[m babandha ||
[16*] [A]sy=ābhavann=avani-maṇḍala-rakshitāraḥ putrās=traya[h*] sphurita-
pauruṣa-bhūṣaṇās=tē [i*] yair=anvitaḥ prasavitaḥ suchiraṁ vyarājat=tējō-
- 16 mayair=iva n[i*]jair=nnayanais=Triṇētraḥ [|| 17*] Jyāy[ān=ēshām]=**Manmasiddh-**
īśvaraḥ kṣamām kṣhār-āmbhōdhi-śyāma-sīmā[m] śasāsa [i*] nity-ōdañichad-yad-
yaśaḥ-pañjar-āntar=vyōma dhyāmaṁ kōkila-
- 17 tvam bibharti || [18*] Tatra svar-lōkam=ārūḍhē madhyamō Be[tta-bhū]patiḥ [i*]
tapasvī rājyam=ādhatta **Tammusiddhau** kaniyasi [|| 19*] Sa **Śrīdēvyām-**
Ērasiddhi-kṣhitīśā[j*]=jāta[h*] śrīmān=**Manmasiddh-ānujanmā** [i*] dhātrīm=ā-
- 18 tām=drā(trā)yamāpas=samastām=ast-ārātis=**Tammusiddhi-kṣhamāpaḥ** || [20*] Asmai
Vatāṭaviśāya Śak-ābdē dhira-
- 19 yāyini [i*] grāmēshv=asya nripa-grāhyam prādād=āyam=aśēshataḥ || [21*] Ētat
kṣhōṇibhritām=aṁsu-jatā-
- 20 lair=mmakutair=dhṛitam [i*] jagat[t*]-traya-prasiddhasya **Tammusiddhasya** śāsanam ||¹
[22*] Yatnēna dharmma-sarapīḥ parirakṣa-
- 21 nīyā s=ēyam bhavatbhi(dhbi)r=akhlair=iti **Tammusiddhaḥ** [i*] āgāmināḥ prapayatē
nripatīn=ajasran=dūran=natēna sira-
- 22 sâ na śarâ-
- 23 sanēna || [23*]
- 24 Svasty=astu [||*]

TRANSLATION.

(Verse 1.) Hail to that glorious **Tammusiddha**, the dust of whose troops, which touches the lotus of Brahman, (*will be*) the cause, I imagine, of creating the future world!

(V. 2.) Triumphant is king **Tammusiddhi**, whose bow is victorious, who **has** washed off all sins, whose talk is always sweet, who has acquired the whole range of sciences, who has poured out the water of donation, who is difficult to be overcome by the tricks of (*his*) enemies, (*and*) who has appeased the torments of the Kali (*age*).

(V. 3.) From the navel of Padmanābha² reposing on the waters sprang a certain wonderful lotus, the cause of all things, which, on account of his (*Vishṇu's*) eyes emitting light now soft, now fierce,³ used to close and to open even before the creation.

(V. 4.) From this (*lotus*) sprang Viriñchi,⁴ who, manifesting, as it were, the action of *rajas*⁵ because (*he*) dwelt long in its interior, seemed to create companions similar (*to himself*), when his image was reflected by the crest-jewels of the snake (*which formed*) the couch of the husband of Śrī.⁶

(V. 5.) From him rose Marīchi as the sun from the eastern mountain. From him (*again*) went forth Kaśyapa as the light from that (*sun*).

¹ After this stands a sign much like the sign for medial *e*; and though it would be possible to read *yetnēna*, I think that it is intended to mark the end of the proper grant, as the spiral is used in Kanarese inscriptions.

² *I.e.* Vishṇu.

³ [Vishṇu's right eye is the sun, and his left eye the moon; compare above, Vol. III. No. 34, verse 3.—E.H.]

⁴ *I.e.* Brahman.

⁵ The word *rajas* must be understood here in its double sense of 'pollen' and 'energy,' the latter being the quality predominant in Brahman, especially at the time of creation; compare the introductory stanza of Bāṇa's *Kaddambart*.

⁶ *I.e.* Vishṇu.

(V. 6.) From him originated a certain bulb (*which was the origin*) of a race¹ of kings, the auspicious jewel-lamp to the three worlds, the body of which is the Vêda,² which was a fire destroying the forest of darkness, the cause, moreover, of fixing quarters and times.

(V. 7.) The divine Manu quickly descended from thence, he who first acquired the title of king, who had plenty of virtues, (*and*) who composed all the rules of policy, in order to rule this (*world*), like the primeval spirit (Vishnu) who resides in the orb of that (*sun*).

(V. 8.) In this family of Manu were many kings who made their fame rush along like torrents,³ rulers even of heaven and earth who laid down the principles of (*just*) policy without opposition.

(V. 9.) In that family was king Kalikâla who constructed the banks of the Kâvêri. When (*he*) had lifted Mount Mêru with his play-staff, the quarters were greatly disturbed.

(V. 10.) In his race was born he who, after his conquest of Madhurâ getting renowned by the name of Madhurântaka, cruelly caused the Pândya women to take off completely their ornaments (*so that they were*) as before (*when they had been wearing fine pearl ornaments*);⁴

(V. 11.) Who, crowned with victory (*and*) famous for the strength of (*his*) arm, after having founded in (*the country of*) the Andhras the town called Pottapi, bore the title of Chôla preceded by that (*name*).

(V. 12.) In his race (*was*) that king Tiluṅgavidya who erected the famous pillar adorned with a waving banner of fame at Ujyapuri; I am sure, it is since that time that the sun tarries for a moment in the midst of the sky,⁵ (*his*) charioteer⁶ stopping out of brotherly affection, when he perceives the Garuḍa at the top of that (*column*).

(V. 13.) (*Born*) in his family, king Siddhi ruled the earth, on whose arms and on whose feet depended the life of his clients and that of his enemies (*respectively*).

(V. 14.) His younger brother was the mighty king Betta. To him also were born sons who defended those who asked them for protection.

(V. 15.) The eldest of them, king Dâyahima, whose hand was reddened by pulling the hair of the goddesses of royal fortune belonging to (*his*) enemies, ruled the earth.

(V. 16.) His younger brother (*was*) king Êrasiddhi, who, having driven far away the Kali (*age*), determined, as it were, to prevent its return, piled up his abundant fame like a wall of crystal at the ends of the quarters.

(V. 17.) He had three sons, rulers of the globe, (*attired*) with the brilliant jewel of heroism. Attended by them who were full of energy, the father shone for along time like Tripêtra⁷ with his beaming (*three*) eyes.

(V. 18.) The eldest of these, the lord Manmasiddhi, ruled the earth, the dark-blue limits of which were the briny ocean. The dark-blue sky became a cuckoo in the cage (*which was*) his continually rising fame.

¹ Or 'a cane.' The sun from which the solar dynasty descends is compared to a bulb with a sprouting shoot.

² With *ehhandas-tanuḥ* compare such epithets of the sun as *vêda-āgaḥ* in *Mahābh.* 3, 3, 19, or *vêda-mūrtiḥ* in the *Mārkaṇḍēyapurāna*, 102, 22. The latter passage contains also an account of the origin of this appellation.

³ The term *nirjhara* is used in allusion to the second meaning of *kṣhamadbhṛt*, 'a mountain.'

⁴ The pun contained in the word *nīdānta-muktā-dbharaṇāḥ*, the correct interpretation of which I owe to Dr. Hultsch, can hardly be rendered in English. In the first case the compound must be taken as *nīdāntaḥ muktāny ddbharaṇāni yābhīḥ*, in the second as *nīdāntā muktā ddbharaṇāni yāśām*.

⁵ The compound *madhyē-vyōma* is formed in accordance with Pāṇini, 2, 1, 18. Prof. Kielhorn, who drew my attention to this rule, quotes as an analogous case *madhyē-dīnam*, 'in the midst of the day,' in *Trivikramabhaṭṭa's Damayantīkathā*, in the first prose passage after l. 30 (p. 15 of the Nirṇayasāgara Press edition).

⁶ The charioteer of the sun is Aruṇa or Anūru, the son of Kāśyapa and Vinatā, and brother of Garuḍa.

⁷ I.e. Śiva.

(V. 19.) When he had ascended to the celestial region, the middle (*brother*), king **Betta**, being given to the practice of austerities, conferred the government on (*his*) younger (*brother*) **Tammusiddhi**.

(V. 20.) This glorious king **Tammusiddhi**, the son of king **Êrasiddhi** and **Śrīdēvi**, the younger brother of **Manmasiddha**, who, having destroyed (*his*) enemies, was ruling over this whole earth,—

(V. 21.) Allotted, in the **Śaka year** (denoted by the *chronogram*) **Dhirayāyin** (*i.e.* 1129), to this lord of **Vaṭāṭavi** all the revenues due to the king in the villages belonging to his (*temple*).

(V. 22.) This (*is*) the order of **Tammusiddha** famous in the three worlds, which is borne by kings on (*their*) radiant diadems.

(V. 23.) "This road of piety should be carefully preserved by all of you;" thus does **Tammusiddha** make a perpetual request to future kings, (*his*) head being lowly bent, (*but*) not (*his*) bow.

(Line 24.) Let there be prosperity!

B.—TIRUPPASUR INSCRIPTION.

TEXT.¹

- 1 Svasti śrī-Tammusiddhāya tasmai yat-sainya-rēṇavaḥ [*] Bra-
- 2 hma-patma(dma)-sprīśās=sāmkē bhāvi-bhū-sprīṣṭi-hētavaḥ || [1*] Udadhi-śāyana-
- 3 bhājāḥ Patma(dma)nābhāsyā nābhēḥ kim=api nikhila-hētun=jjātam=ā-
- 4 ścharyya-patma(dma)m [*] yad=abhajad=api sprīṣṭēḥ pūrvvam=ētasya dṛik(dṛig)-
- 5 bhyān=mṛidu-kaṭhina-mahōbhyām=mīlan-ōmīlanāni || [2*] Ta-
- 6 smād=Vinūchir=udabhūt suchiran=tad-antar=vvāsā[d=iva]
- 7 prakāṭayan rajasaḥ pravṛttim [*] ya[h*] Śrīśa-talpa-
- 8 phaṇi-mauli-maṇi-pravishṭa-bimba-
- 9 s=sriṇann=iva babhau sadrīśās=sahāyā-
- 10 n || [3*] Marīchir=udagāt=tasmād=uday-ādrēr=j-
- 11 v=āmsūmān [*] tataḥ Kāśyapa ētasmā-
- 12 t prakāśa iva nirgataḥ || [4*] Tasmā-
- 13 j=jaga[t*]-tritaya-maṅgala-ratnadīpa-
- 14 ś=chhandas-tanus=timira-kānana-dā-
- 15 vavahniḥ [*] di[k*]-kālayōḥ kim=a-
- 16 param(ram) vyavahāra-hētuh
- 17 kō=py=āvirāsa vasudhādhi-
- 18 pa-vamśa-kandaḥ || [5*] Babhūvur=ullāsi-
- 19 ta-kīrtti-nirjharā Manōḥ kulē=smi-
- 20 n bahavaḥ kshamābhṛitaḥ [*] divas-pri-
- 21 thivyōr=api yair=nniyantṛibhi-
- 22 r=nniraṇkuśō nīti-pathaḥ pravarttitaḥ || [6*] Tat-
- 23 kulē **Kalikālō**=bhūt² **Kāvēri**-tī-
- 24 ra-kṛin=nripaḥ [*] yat-kēḷi-yashṭi-tulitē
- 25 Mērau vyatikṛitā dīśaḥ || [7*] Jātō=sya
- 26 vamśē **Madhurām** vijitya paśchād=udañchan-**Madhu**-
- 27 rāntak-ākhyāḥ [*] nīlānta-mukt-ābharaṇāḥ prachanda-
- 28 ḥ **Pāṇḍy**-āṅganāḥ prāg=iva yaś=chakāra || [8*] Ji-
- 29 shṇur=**Andhrēshu** yaḥ kṛitvā purīm **Pottappi**-sa[m]-

¹ From inked estampages supplied by Dr. Hultzsch.

² The *akshara bhū* seems to have been corrected out of something else, perhaps *bhāta*.

- 30 jñit[ām] [*] tatas=tat-pūrvva-Chôl-ākhyah prakhyāta-bhu-
 31 ja-vikramah || [9*] Tad-vamśe Siddhi-bhūpālah pālayām=[ā].
 32 sa mēdinim [*] yadya-dôh-pad-āyattam=artthi-pratyartthi-jī-
 33 vitam || [10*] Tad-vasē(mśa)jas=sahaja-jitvara-satva(ttva)-rāsīś=śatru-kshi-
 34 tśvara-yaśās-sīśirāmśu-Rāhuḥ [*] śrī-Nallasiddhi-nṛipa-
 35 tir=yyam=upētya kāntan=dik(g) dakshipā galita-ka(kā)ñchi-guṇā
 36 babhūva || [11*] Tasy=Airasiddhi-nṛipatis=sahajah kanī-
 37 yān dūran=nirasya kalim=asya punah-pravēsam [*]
 38 rōddhum pravṛitta iva yah prachuram yaśa[h*] svan=clik-
 39 sīmasu sphatikā-sāla-nibham babandha || [12*] Asy=ā-
 40 bhavann=avani-maṇḍala-rakshitārah putrās=traya[h*] sphurita-pau-
 41 rusha-bhūṣaṇās=tē [*] yair=anvitaḥ prasavitā suchira[in]
 42 vyarājat=tējōmayair=iva nijair=nnayanais=Trinētra[h] || [13*]
 43 Jyāyān=ēshān(shām)=Manmasiddh-īśvarah kshamām kshā-
 44 r-āmbhōdhi-śyāma-sīmām śāsāsa [*] nity-ōda-
 45 ñchad-yad-yaśah-pañjar-āntar=vyōma dhyāman kōkila-
 46 tvam bibharti || [14*] Tan-madhyamas=tad=anu Betta-nṛip ā-
 47 bhidhānās=śāntas¹=tapōbhīr=avadhīrita-bhōga-
 48 vāñchah [*] jyēshthē gatē divam=anākulam=ēva rā-
 49 jyau=nikshiptavān=api kanyasi Tammusi-
 50 ddhau² || [15*] Jayati vipula-bhūbhīd-vamśa-janmā suvṛitta.
 51 h parichita-guṇa-gumphas=sambhavan-nāyaka-
 52 śrīh [*] suchiram=avani-bhūshā Tammusiddh-ābhidhāna-
 53 s=sarasa-madhura-mūrtiś=chētanaḥ kō=pi hārah || [16*] Sa
 54 Śrīdēvyām=Ērasiddhi-kshitīśāj=jāta[h*] śrīmān=Ma-
 55 nmasiddh-ānujanmā [*] dhātrim=ētān=trāyamāṇas=sama-
 56 stām=ast-ārātis=Tammusiddhi-kshamāpah || [17*] Asmai
 57 Pāśipurēśāya Śak-ābdē dhirayāyini [*] grāmē-
 58 shv=asya nṛipa-grāhyam prādād=āyam=asēshi(sha)taḥ || [18*] Chāma.
 59 ñ=cha dattavān=asmai Kaivaṇṭūr=iti viśrutam [*] svā-
 60 pura-śrēshṭhinām prītyai sō=yam=atr=aiva va-
 61 tsarē || [19*] Ētat kshōṇ[*]bhṛitām=amśu-jatā-
 62 lair³=mmakuṭair=dhṛitam [*] jaga[t*]-traya-prasiddhasya Tammusi-
 63 ddhasya śāsanam || [20*] Yatnēna dharmma-saraṇiḥ pa-
 64 rirakshaṇīyā s=ēyam bhavatbhi(dbhī)r=akhi-
 65 lair⁴=iti Tammusiddhaḥ [*] āgāminah prapaya-
 66 tē⁵ nṛipatīn=ajasran=dūran=natēna śirasā na
 67 śarāsanēna || [21*] Svasty=astu ||

TRANSLATION.⁶

(Verse 11.) In his (*i.e.* king Siddhi's) family was born the glorious king Nallasiddhi, the model (of a man) of innate, conquering energy, (a very) Rāhu to the moon-like fame of hostile

¹ After *śa*, the engraver seems to have originally engraved some other *akshara*.

² The first component of the sign for *au* stands at the end of the preceding line.

³ The sign for *ai* stands at the end of the preceding line.

⁴ The sign for *ai* stands at the end of the preceding line.

⁵ The sign for *ē* stands at the end of the preceding line.

⁶ Only the verses which are not found in the Tiruvālaṅgādu inscription have been translated here. Verse 18 also has been omitted here, because it differs from verse 21 of the Tiruvālaṅgādu inscription only with respect to the name of the god.

kings. When the southern quarter had obtained him as (*her*) husband, she dropped her girdle (*or she lost Kāñchi*).

(V. 15.) After that, when the eldest (*brother*) had gone to heaven, the middle one of them, who was called king *Betta*, being free from passions on account of (*his religious*) austerities (*and*) despising the desire for (*worldly*) pleasures, conferred the government, without any disturbances, on *Tammusiddhi*, though being the younger (*brother*).

(V. 16.) Victorious is a certain living necklace of pearls, called *Tammusiddha*, an ornament to the earth for a very long time, which comes from a ridge of high mountains, which is well rounded, which has numerous windings of strings, which shows a fine gem in the centre, which has an elegant and pleasant form, (*and which thus resembles the king, who is born in a family of great kings, who leads a virtuous life, who combines in himself a series of good qualities, who enjoys the dignity of a chief, and who has a handsome and graceful appearance*).

(V. 19.) And in the same year (*viz.* 1129) this (*king* *Tammusiddhi*) gave to him (*i.e.* the lord of *Pāṣipura*) the village called *Kaivaṇṭūr*, to the delight of the merchants of his town.

NO. 18.—ARULALA-PERUMAL INSCRIPTION

OF THE TIME OF PRATAPARUDRA;

SAKA-SAMVAT 1238.

By E. HULTZSCH, PH.D.

This inscription (No. 43 of 1893) is engraved on the west side of the base of the verandah surrounding the stone-platform called "the hill" (*malai*) in the *Arulāla-Perumāl temple at Little Conjeeveram*. The first six lines are fully preserved; but of ll. 7-10 the beginnings are built in. The preserved portion contains seven verses in the Sanskrit language and the Grantha alphabet. Verse 4 is followed by a prose passage in the Tamil alphabet and language, and another Tamil prose passage occurs between vv. 5 and 6.

Vv. 2-4 record that *Muppiḍi*, a general (*nāyaka*) of the *Kākatiya* king *Pratāparudra* of *Ēkaśilānagari*, came to *Kāñchi* and installed a certain *Mānavira* as governor of *Kāñchi*. The Tamil portion records that the same *Muppiḍi-Nāyaka* granted the revenue from two villages to the *Arulāla-Perumāl temple at Kāñchipuram*. This revenue amounted to an annual sum of 1,002 "*māḍai* of *Gaṇḍagōpāla*." Of this sum, 240 *māḍai* were set aside for paying the attendants of a flower-garden on the southern bank of the *Velka*, which the donor had purchased for 500 *paṇam* from a certain *Perumāl-tādar*;¹ 360 *māḍai* for daily offerings, etc.; 20 *māḍai* for purificatory rites in *Chaitra*; and 382 *māḍai* for buildings. Those lines which are only partially preserved seem to have contained a list of gifts of ornaments and articles of worship (l. 6 f.), a list of buildings to be erected in the temple (l. 8), and a list of trees to be planted in the flower-garden (l. 9). The inscription ends with praises of *Muppiḍi-Nāyaka*.

The inscription contains two dates, both of which fell into *Śaka-Samvat 1238* (expired), the *Nala-samvatsara*, = A.D. 1316-17. On the first date *Muppiḍi* installed *Mānavira* (verse 4), and on the second date he made his grant to the temple (line 3). Professor Kielhorn has favoured me with the following calculation of these two dates:— "The first date regularly corresponds to Friday, the 11th June A.D. 1316, when the 5th *tithi* of the dark half in the solar month *Śuchi* (*Mithuna*) ended 7 h. 5 m. after mean sunrise. The second date regularly

¹ This name is the Tamil equivalent of *Vishṇu-dāsa*.

corresponds to Wednesday, the 16th June A.D. 1316, which was the 21st day of the month of Mithuna (Âṇi) and on which the 11th *tithi* (of the dark half of Jyāishṭha) ended 17 h. 47 m. after mean sunrise."

The two villages granted by Muppiḍi were **Paiyyūr**, with the hamlets of **Âyirachchēri** and **Gummiḍippūṇḍi**, in the district of **Paiyyūr-kōṭṭam**, and **Pondaipākkam** in **Kachchiyūr-nāḍu**. According to Mr. Crole's *Manual of the Chingleput District* (p. 438), **Paiyyūr-kōṭṭam** formed part of the modern **Ponnēri tāluḱa**, and several villages which are stated to have been situated in that *kōṭṭam* have actually been traced in this tāluḱa.¹ **Paiyyūr**, the head-quarters of the district, is not found on the map, but its position is indicated by its hamlet **Gummiḍippūṇḍi**.² The whereabouts of **Pondaipākkam** and **Kachchiyūr-nāḍu** are settled by a copper-plate grant of **Veṅkaṭapati**, dated Śaka-Saṁvat 1526, Krōdhin,³ where both **Podavākam** and **Kachchūr** are stated to have belonged to **Kachchi-nāḍu**, a subdivision of **Īkkāṭṭu-kōṭṭam**. According to the *Chingleput Manual* (p. 438), the district of **Īkkāṭṭu-kōṭṭam** corresponded to the modern **Tiruvallūr tāluḱa** and was subdivided into **Kāḱkaḷūr-nāḍu** and **Kachchi-nāḍu**. **Īkkāḍu**, **Kāḱkaḷūr**, and several other villages of **Kāḱkaḷūr-nāḍu**, **Kachchūr-nāḍu** and **Malaya-nāḍu** in **Īkkāṭṭu-kōṭṭam**, which are mentioned in the British Museum plates of **Sadāśivarāya**, can still be traced on the maps of the **Tiruvallūr tāluḱa** and the **Kālahasti Zamindārī**.⁴ **Pondaipākkam** or **Podavākam** is also found on the former map as **Pondavākkam**,⁵ and **Kachchiyūr**, **Kachchi** or **Kachchūr**, the head-quarters of the *nāḍu* to which this village belonged, is represented on the second map by **Kachchūr**, about one mile south of **Pondavākkam**. The river **Veḷkā** mentioned in line 4 is the **Veḷkā** or **Vēgavati**, which flows past the **Arulāla-Perumāl** temple.⁶

The chief interest of this inscription lies in the statement that, in June 1316 A.D., **Conjeeveram** was tributary to the **Kākatṭya** king **Pratāparudra** of **Ēkaśilānagarī**, i.e. **Warangal**.⁷ Another inscription of **Pratāparudra** is found as far south as the **Jambukēśvara** temple near **Trichinopoly**.⁸ Three inscriptions of his at **Bezvāḍa** (No. 306 of 1892), **Warangal** (No. 109 of 1902) and **Palivela** (No. 501 of 1893) are dated in Śaka-Saṁvat 1220 (**Vilambin**), the **Pramādi-saṁvatsara** (i.e. Śaka-Saṁvat 1235), and Śaka-Saṁvat 1239 (**Piṅgala**).

Who was the **Mānavira** whom **Pratāparudra**'s general **Muppiḍi** installed as governor of **Kāñchi**? An inscription of Śaka-Saṁvat 1219, **Hēmalambin** (= A.D. 1297-98), at **Narasarāvu-pēṭa** (No. 213 of 1892) states that **Manma-Gaṇḍagōpāla**, **Rāya-Gaṇḍagōpāla** or **Manuma-Gaṇḍagōpāladēva-Chōḍamahārāja**, the eldest son of **Nallesiddhi**, was a subordinate of **Pratāparudra**⁹ and took possession of **Kāñchipura**.¹⁰ An earlier chief of the same family, **Vijaya-Gaṇḍagōpāladēva**, was also connected with **Conjeeveram**, where three of his inscriptions, dated in Śaka-Saṁvat 1187, have been found.¹¹ Two records of the **Arulāla-Perumāl** temple (Nos. 34 and 35 of 1893), dated in Śaka-Saṁvat 1156 and 1127, belong to two other chiefs of the same family, **Chōḷa-Tikka** and **Tammusiddhi**.¹² **Nallasiddhi**, an uncle of **Tammusiddhi**, is stated to have occupied **Kāñchi**.¹³ If it is borne in mind that several of these later **Chōḷas**

¹ Above, Vol. IV. p. 9, and *South-Ind. Inscr.* Vol. III. p. 118, notes 1 and 5; see also *ibid.* p. 139.

² **Gummiḍippūṇḍi** is No. 199 on the *Madras Survey Map* of the **Ponnēri tāluḱa**.

³ See my *Progress Report* for May to September 1890, p. 3, No. IX.

⁴ See above, Vol. IV. pp. 8, 9 and 10.

⁵ No. 229 on the *Madras Survey Map* of the **Tiruvallūr tāluḱa**.

⁶ See *South-Ind. Inscr.* Vol. III. p. 186 and note 8; above, Vol. IV. p. 146 and note 5.

⁷ *Ind. Ant.* Vol. XXI. p. 198 and note 12.

⁸ *Ibid.* p. 200.

⁹ *Tatradgrajas=utō Manma-Gaṇḍagōpāla-bhūpatiḥ*

Pratāparudra-bhūpasya prasād-śrījīta-vaiḷharaḥ ll.

¹⁰ *Kāñchipura-Tripura-Trinētra* occurs among his *birudas*.

¹¹ *Ind. Ant.* Vol. XXI. p. 122.

¹² The second of these two inscriptions will be published by Dr. Lüders in this *Journal*.

¹³ See page 122 above.

seem to have ruled over Conjeeveram and that the last of them, Manma-Gaṇḍagôpâla, was a subordinate of Pratâparudra, it becomes probable that the Mânâvîra of the subjoined inscription was a member of the same family. Another point in favour of this theory is the fact that, at the time of the inscription, the standard coin of Conjeeveram was the "māḍai of Gaṇḍagôpâla"¹ (l. 4), which owes its name evidently to one of the later Chôlas, several of whom bore the surname Gaṇḍagôpâla. The latest known date of Râja-Gaṇḍagôpâladêva (i.e. Manma-Gaṇḍagôpâla) is Śaka-Saṃvat 1221, which was the 9th year of his reign, in an inscription at Nellore (No. 194 of 1894). This date is 17 years prior to the installation of Mânâvîra. In the meantime Conjeeveram had been in the possession of Ravivarman of Kêraḷa, who was crowned at Kâñchi in A.D. 1312-13 and made a grant to the Aruḷâḷa-Perumâl temple in A.D. 1315-16.² Can it be that he was driven out by Muppiḍi, who installed Mânâvîra in June 1316? An allusion to this might be found in the statement (verse 3) that, before entering Kâñchi, Muppiḍi "put to flight the princes of the South."

TEXT.³

- 1 Svasti śrī [||*] Yad-dêhê tanu-lôma-kûpa-vivarê śailâ nagâ dig-gajâ nadyas=sapta
[sa]mudra-mudrita-mahî vistâram=adhyâsatê ||(1) dâṃshtrâ-daṇḍa-karâḷa-kâla-
vadana[h*] str[î]-la[mgh]it-âgr-âsanô lîlâ-kôla-kalêba(va)ras=sa Murabhit pâyâd=
apâyât(d=) bhuvam || [1*] Śrîman-mahâ-maṇḍala-chakravartî Pratâparudrah
kila Kâ-
- 2 katiyaḥ | karôti rājyaṃ kamanîya-kirttiḥ pratâpavân=Ēkaśilâ[na]garyyâm || [2*]
*Tan-nâyakas=samprati *Muppiḍ-i[n]draḥ pratâpa-nissêshita-śatru-pakshaḥ ||(1)
vidrâvya bhûpân=api dâkshinâtyân purîṇ=cha Kâñchim=aviśan=Naḷ-âbdê || [3*]
Mâsê Śuchau Sarppadinê cha kṛishṇê vâre sa-Śukrê divasê=parâhṇê ||(1)
śrî-Mânâviran=nîja-paṭṭabandham(ndham) vya-
- 3 [dh]ât=tad-âjî-ânuchariṇ=cha Kâñchim || [4*] Śakar varsham 1238âvadu
Naḷa-saṃvatsaram Âpi-mâdam irubattu-oprân-di[ya]di Budaṇ-kilamaiyum
êkâdasiyum perṇa nâl svasti śrîmatu-Muppiḍi-nâyakkar śrî-Kâñchipura[t]tu
Perumâl Aruḷâṇâthanukku sarvva-niyôgattukku dakshinâ-sahitam=âga udakam
panṇiṇa ūr 2-ttara[m*] Pa[ya]-
- 4 r-kkôṭṭa-stalattu⁶ Paiyyûrum piḍagai Âyirachchériyum Gumm[i]ḍippuṇḍi
uṭ[pa]ḍa Gaṇḍagôpâlap māḍai=ttaram 526m Kachchiyûr-nâṭṭil
Pondaipâkkam māḍai=ttaram 476 âga ūr irap[du*]m māḍai 1002kkum
piṇivu Perumâl-tâdar⁷ kaiyyil 500 paṇa-vilaiy=âga koṇḍa Veḷkâvil teṇ-
karaiyil tiru-

¹ The Tamil *māḍai* and the Telugu *māḍa* form part of the names of various gold coins, e.g. *Māḍurāntakay-māḍai* (above, Vol. V. p. 106 and note 3; *South-Ind. Inscr.* Vol. III. pp. 143 and 164), *Bhujabala-māḍai* (see my *Annual Report* for 1896-97, p. 4), *Gaṇḍa-māḍa* (above, Vol. V. p. 32), *Kulōttunga-māḍa*, *Birudu-māḍa*, *Jaya-māḍa*, *Chāmara-māḍa*, *Gandhadrâṇa-māḍa* or *Gandahasti-māḍa*, *Uttamagaṇḍa-māḍa* and *Râjardja-māḍa* (see the Appendix of my *Annual Report* for 1897-98). Of these, the *Râjardja-māḍa* and *Jaya-māḍa* are perhaps identical with certain gold coins published in *Ind. Ant.* Vol. XXV. p. 321, Nos. 24 and 25, and p. 322, No. 29. The *Gandhadrâṇa-māḍa* is mentioned in two inscriptions of Śaka-Saṃvat 1039 and 1042 (Nos. 232 and 212 of 1897). It seems to be the coin which is known in the *bâzars* of Southern India as *Gajapati-vardha* and which, according to the *Râjataranginî*, was imitated by Harsha of Kâśmîr; compare Sir A. Cunningham's *Coins of Medieval India*, pp. 34 f. and 36; and Mr. Rapson's *Indian Coins*, pp. 32 and 36. It may be that these coins were first struck by Vikramāditya VI., because the *Râjataranginî* (vii. 926) expressly states that Harsha copied his new gold coin from those of Kârṇāṭa, and because the only king of Kârṇāṭa who reigned during Harsha's time was Parmāḍi or Parmāṇḍi (*Râjataranginî*, vii. 935 and 1119) of Kalyāṇapura (*ibid.* 1124), i.e. the Western Châlûkya Vikramāditya VI.

² Above, Vol. IV. p. 146.

³ The syllable *ya* of *nadyaka* is entered below the line.

⁶ Read *Paiyyûr-kkôṭṭa-stalattu*.

⁷ From two inked estampages.

⁸ The syllable *mu* is entered below the line.

⁹ The *d* of *td* is entered below the line.

- 5 nandavaṇattukkum idil śeyya=kkaḍava śeṅgaḷa(lu)ṇīr ḍḍai 4kkum mēl
 śeyyum vyavasāyattukkum nā[ī] lkku niṅkum āḷ 20kku āṇḍ=onṇukku
 māḍai 240m tiru[v]ottaśāmattukku ariśikku paṇam 2m sarvva-sugandh[i-
 dra]vyaṅgaḷukku¹ paṇam 1½m tiruviḷakkukku paṇam ½ pāl-miḷagukku
 utpaṭṭavaikku paṇa-
- 6 m 1m āga nāḷ lkku māḍai [1] āga āṇḍu lkku māḍai 360m [*]
 tiruppaḷittāmamu[m*] paḷamum kaṇi-amudum tirunandavaṇattilē naḍattavum [*]
 [Ch]aiyitra-pavitraṅgaḷukku māḍai 20m abi(bhi)shēka-maṇḍapam uḷḷiṭṭa
 tiruppaniḷaḷukku 382 māḍaiyum=āga naḍakkavum [*] Perumāḷukku=ppo[r]-
 ppaṭṭamum padaḱkamum
- 7 kkiḍāra-ku[ttu]-v[i]ḷakku 2m [ś]ōmakkaḷam 4m
 dūpa-dīpa-p[ātraṅga]ḷi kai[y]-maṇi 2m tiruvāḷa[tti*]-ttattī 1m kaḱchu-kkaṭṭil
 1m [i*] inda ōr iraṇḍum sakala-prāptigaḷḍum chandr-āditya-varai sarvva-
- 8 nīyō bhavat(d)bhiḷ ||(1) tasmād=ētān bhāvinaḷ
 pārtthivēndrā[n*] bhūyō bhūyō yāchatē Rāmachandraḷ ௭ [5*] Aruḷāṇāḍan
 kōyilil śe[y*]yum tiruppaṇi āyirakkāl-tirumaṇḍapam Muḍivaḷaḱgiṇṇ-tirumaṇi-
 p[pa]-²
- 9 javvandi alari piḱchi śādi śeṇbagam magiḷ
 śeṇ[ga]ḷu[nī]r ḍ[ḍ]ai 4 mā=ppilā teṇṇamaram [m]āḍai elumbiḱchai nārttai
 maṅṅum=uḷḷa maraṅga[ḷum] vaippadu || Yasy=ājñā sakala-kṣhītśvara-ś[i]rō-
 ratn-[ā*][mśu]-sa[m]p[ā]-
- 10 āḷ Varāha[h*] sva-dhanaṇ=cha [d]āna[m](nam)
 nidyam(tyam) prapō[ji]yas=sa cha Sōmanāthaḷ ||(1) kiṁ va[rṇnya](rṇya)tē
 [ta]sya cha bhāgatē(dhē)ya[m] kṣhōpītālē Mupp[ilṭi](ḍi)-nāyakasya || [7*]

TRANSLATION.

(Line 1.) Hail ! Prosperity !

[Verse 1 contains an invocation of the boar-incarnation of Vishnu].

(V. 2.) The glorious ruler of a great province (*mahā-maṇḍala-chakravartin*), the **Kākatīya Pratāparudra**, whose fame is beautiful (*anū*) who possesses valour, conducts the kingdom at **Ēkaśīlānagari**.

(V. 3.) And now his general (*nāyaka*), the lord **Muppiḍi**, who has annihilated the party of the enemies by (*his*) valour, having put to flight also the princes of the South, entered the city of **Kāñchi** in the **Nala year**.

(V. 4.) And in the month **Śuchi**, on the day of the serpents,¹ in the dark (*fortnight*), on a **Friday**, in the afternoon of (*this*) day, (*he*) made the glorious **Mānavira** possessed of the tying of the fillet (*paṭṭabandha*)² and (*made*) **Kāñchi** obedient to his orders.

(Line 3.) (*In*) the **Śaka year 1238**, the **Nala-saṁvatsara**, (*on*) a day which corresponded to an eleventh *tithi*, to a **Wednesday**, and to the twenty-first solar day (*of*) the month **Āṇi**,—Hail ! the glorious **Muppiḍi-Nāyaka** granted, (*with a libation of*) water, accompanied by presents (*to Brāhmaṇas*), as exclusive property (*sarva-niyōga*), to (*the temple of*) **Perumāḷ Aruḷāṇātha** in the prosperous **Kāñchipuram** the revenue (*taram*) of 2 villages, (*viz.*) (1) in the land of **Paīyyūr-kōṭṭam** (*the village*) **Paīyyūr**, (*having*), together with (*its*) hamlets **Āyirachohēri** and **Gummiḍippūṇḍi**, a revenue of 526 māḍai of **Gaṇḍagōpāla**, and (2)

¹ The syllable *dra* seems to be entered below the line.

² Read probably *tirumaṇippandal*.

³ I.e. the fifth *tithi*.

⁴ Read perhaps *Prāptō*.

⁵ I.e. he invested him with the dignity of governor.

Pondaipákkam in Kachchiyūr-nādu, (having) a revenue of 476 māḍai; altogether two villages, (having a revenue of) 1,002 māḍai.

(L. 4.) Out of this, 240 māḍai per year (shall be spent) for 20 people per day, in order to (maintain) a flower-garden on the southern bank of the Velkā, which (he) had purchased at the price of 500 paṇam from Perumāl-tādar; in order to construct 4 lotus-tanks in this (flower-garden); and, besides, in order to cultivate the fields.

(L. 5.) 2 paṇam (shall be spent) for rice for (offerings at) midnight;¹ 1½ paṇam for perfumes of all (kinds); ½ paṇam for lamps; and 1 paṇam for the ingredients of pepper-milk; altogether, 1 māḍai² per day and 360 māḍai per year.

(L. 6.) The temple garlands, fruits and vegetables for offerings shall be grown in the (above-mentioned) flower-garden. 20 māḍai shall be spent for the Chaitra-pavitra,³ and 382 māḍai for the abhiśhēka-maṇḍapa and other buildings. To (the god) Perumāl (were given) a gold diadem, a breast-ornament,, 2 brass chandeliers, 4 gongs, (two) vessels for incense and lights, 2 hand-bells, 1 salver for waving lights (before the god), and 1 webbed bedstead. These two villages⁴ with all the revenue (prāpti), as long as the moon and the sun shall last.

[Verse 5, which is incomplete, contains one of the usual admonitions to future kings].

(L. 8.) The buildings to be erected in the temple of Aruḷālanātha (are) a maṇḍapa of one thousand pillars, a canopy of gems for (the image of) Muḍivalaṅgiṇṇ

(L. 9.) javvandi,⁵ oleander (alari), picchi, śāḍi, champaka,⁶ bakula, 4 lotus-tanks,⁷ mangoes, jacks, cocoanut-trees, pomegranates, limes,⁸ oranges and other trees shall be planted.

(V. 6.) Whose command the rays of the jewels on the heads of all princes

(V. 7.) Varāha⁹ has received his wealth (as) a gift, and that Sōmanātha¹⁰ is to be worshipped (by him) daily: How can the fortune of that Muppiḍi-Nāyaka be described on earth?

No. 19.—SIX INSCRIPTIONS AT TIRUNAMANALLUR.

By E. HULTZSCH, PH.D.

Tirunāmanallūr is a village in the Tirukoilur (Tirukkōvalūr) tāluca¹¹ of the South Arcot district. It contains a Śiva temple which is now called Bhaktajanēśvara. This Sanskrit name is represented in the inscriptions of the temple by its Tamil equivalent Tiruttonḍiśvara. Both names refer to the 63 devotees of Śiva¹² (Tiruttonḍar or Bhaktajana), whose lives are narrated in the Periyapurāṇam, and one of whom is supposed to have been a chief of Tirunāmanallūr itself.¹³

¹ Ottaiānam is a tadbhava of the Sanskrit ardhayama.

² This total shows that 1 māḍai was equal to 5 paṇam.

³ Compare above, Vol. V. pp. 22 and 259.

⁴ This refers to Paiyyūr and Pondaipákkam in line 4.

⁵ According to the dictionaries, *javvandi* is the Indian chrysanthemum.

⁶ Regarding Tamil *śenbagam* = Sanskrit *champakā*, compare *Ind. Ant.* Vol. XVIII. p. 105, note.

⁷ These were already mentioned in line 5.

⁸ *Elumichchai* is meant for *elumichchai*. ⁹ I.e. the boar-incarnation of Vishnu.

¹⁰ This is an epithet of Śiva and suggests that Muppiḍi worshipped this god as well as Vishnu.

¹¹ No. 320 on the *Madras Survey Map* of this tāluca.

¹² Compare *South-Ind. Inscr.* Vol. II. pp. 184, 152 ff., 167, 172 and 252 f.

¹³ See page 136 below.

An inscription of the Chôla king Parântaka I. (A. below) states that the stone temple of Tiruttonḍisvara was built by his son Râjâdityadêva. Hence it is also called Râjâdityêsvara in some of its inscriptions.

Besides the shrine of Tiruttonḍisvara or Râjâdityêsvara, the same temple included the shrine of Agastyêsvara, which is mentioned in several inscriptions of the temple. Another inscription (No. 365 of 1902) records a gift to the temple of Kalinârisvara. This temple has been recently demolished by the villagers, and the only portion of it that survives is a sculptured stone which bears the figure of a kneeling elephant, above the elephant a *hauda* with a stout male person reclining in it, and the single word *śrī-Kalinârai* in Pallava-Grantha characters (No. 376 of 1902). It may perhaps be concluded from this, that the demolished temple of Îsvara (Śiva) was built by a Pallava king named Kalinârai, and that the man riding on the elephant is meant to represent this king.

According to the subjoined Tamil inscriptions, the ancient name of Tirunâmanallûr was Tirunâvalûr. The Śaiva saint Sundaramûrti, who was born at Tirunâvalûr and was the protégé of a chief of that place,¹ derived from it the surname Nâvalûraṇ, which he applies to himself in some of his hymns. Tirunâvalûr belonged to the district of Munaippâḍi (C. below) or Tirumunaippâḍi (A. and B. below). In the time of Râjendra-Chôla I. it bore the surname Râjâdittadêvapuram,² which is due to the fact that its temple had been founded by Râjâditya, and was included in Mêlûr-nâḍu, a subdivision of Tirumunaippâḍi, a district of Jayaṅgoḍa-Chôla-maṇḍalam (F. below).

The subjoined inscriptions contain the names of a few other villages in the neighbourhood of Tirunâmanallûr. Of these, Śevalai in Veṇṇainallûr-nâḍu (C. below) survives in the two villages Periyaśevalai and Śiṇṇaśevalai³ (i.e. 'great and small Śevalai') close to Tiruveṇṇainallûr.⁴ Êkadhîra-chaturvêdimangalam (D. below) cannot be identified, as it is not the name, but the surname of some village. Arumbâkkam⁵ (E. below) is situated 2 miles south of Tirukoilur.

A.—INSCRIPTION OF PARANTAKA I.

This inscription (No. 335 of 1902) is dated in the 28th year of "Parakêsarivarman who took Madirai (Madhurâ)," i.e. of the Chôla king Parântaka I.⁶ who ruled from about A.D. 900 to about 940.⁷ It records the gift of two lamps by a servant of Kôkkaḷāṇaḍi, the queen of Parântaka I. and the mother of his son Râjâdityadêva. The latter is the Râjâditya who, according to the large Leyden grant⁸ and the Âtakûr inscription of A.D. 949-50,⁹ was killed in battle by the Râshtrakûṭa king Krishṇa III.

TEXT.

- 1 Svasti [ś]r[î] [l] [Madi]r[ai] ko[n]ḍa kô=Pparakêśa-
- 2 ripa[n]ma[r*]kk-i[yāṇ]ḍu irubattettâvadu [T]irumu-
- 3 paippâḍi-Ttirunâvalûr Tiruttonḍi(nḍi)svara[n]
- 4 tiru-kkaṇ-ṇaḷi śe[y*]vitta Râjâdittadêvar tã[y]âr na[m]-birattiyâr
- 5 Kô[k]kiḷā[ṇa]ḍigal pari[b]â(vâ)rattâl Śittirakômaḷam va(vai)tta n[o]ndâ-viḷak-

¹ See page 136 below.

² Other inscriptions have the shorter form Râjâdittapuram.

³ Nos. 267 and 265 on the *Madras Survey Map* of the Tirukoilur tāluka.

⁴ No. 273 on the same map.

⁵ No. 97 on the same map.

⁶ *South-Ind. Inscr.* Vol. II. p. 379 f.

⁷ See *ibid.* p. 381. If Professor Kielhorn's calculation of the date of the Kûram inscription (p. 1 above) should be corroborated by the discovery of a similarly dated record of the same reign, it would follow that Parântaka I. reigned from about A.D. 906 to about 946.

⁸ *Arch. Survey of S. India*, Vol. IV. p. 206 f.

⁹ Above, Vol. VI. p. 51.

- 6 k=[o]ṇṇukku va(vai)[tta s]āṇvā m[ū]vā=ppēr-ād[u] tonṇūṇṇu īlā¹-viḷa-
 7 kk=onṇu [i*] idu paṇ-[M]āyē(hē)śvarar irakshai ||—
 8 mēppaḍiyā! Śittirak[ō]maḷam vaitta viḷakk=onṇu īlā¹.
 9 viḷakku.||—

TRANSLATION.

(Line 1.) Hail! Prosperity! In the twenty-eighth year of king Parakēsarivarman who took Madirai, Chitrakōmaḷam,—a female attendant of our lady Kōkkilāṇaḍigaḷ, the mother of Rājādityadēva who caused to be made the sacred stone temple of Tiruttonḍiśvara at Tirunāvalūr in Tirumūnaippāḍi,—gave one perpetual lamp. For (*this lamp she*) gave ninety undying (*and*) unaging big sheep³ (*and*) one *īlā* lamp.³ This (*gift is placed under*) the protection of all Māhēśvaras.

(L. 8.) The same Chitrakōmaḷam gave one (*other*) lamp (*and*) an *īlā* lamp(-stand).

B.—INSCRIPTION OF PARANTAKA I.

This inscription (No. 363 of 1902) is dated in the 39th year of the same king as A. and records the gift of a lamp by Mahādēvaḍi, the queen of prince Rājādityadēva and the daughter of Ilāḍarāyar, for the merit of her elder brother Rājādittan Pugaḷvippavargaṇḍa. Rājāditya was already mentioned in the preceding inscription (A.). Ilāḍarāyar means 'the chief of Lāṭa (Gujarāt).' This title was borne by a family of local chiefs, one of whom, named Vira-Chōḷa, is known to have been a feudatory of Rājārāja I.⁴ Vira-Chōḷa was the son of Pugaḷvippavargaṇḍa. This chief is probably identical with Rājādittan⁵ Pugaḷvippavargaṇḍa, the elder brother of Rājāditya's queen Mahādēvaḍi.

TEXT.

- 1 ||[a-] Śva(sva)sti śrī [i*] Madiraiyum īlammum⁶ koṇḍa kō=Pparakēsaripa-
 2 ṇ[ma][r*]kk-iyāṇḍu muppattu-onḍadāṇḍu Tirumūnaippāḍi=Ttirunā-
 3 valūr Tiruttonḍiśvarattu⁷ Māhadēvarkku=ppillaiyār Rā-
 4 jādittadēvar dēviyār⁸ [I]lāḍarāyar magalār⁹ Māhadēvaḍigaḷ tamai-
 5 yaṇṇār¹⁰ Araiyar Rā[jā*]dittan Pugaḷiprargaṇḍaṇai¹¹ sārtti va(vai)chcha nōttā¹²-
 6 viḷakk=[o]ṇṇukku [va](vai)[ch]cha śā[v]ā mu(mū)vā=ppēr-[ā]ḍu¹³ nū[rū]
 ni[lai-v]iḷakku
 7 nīrai eḷu[ba]ḍiṇ palam śa[n]d[irā*]dittaval eri[p]padakku¹⁴ [i*] i[du] pan-Māhē[śva]-
 rar irakshai ||

TRANSLATION.

Hail! Prosperity! In the thirty-ninth year of king Parakēsarivarman who took Madirai and Ilam,—Mahādēvaḍigaḷ, the queen of prince Rājādityadēva (*and*) the daughter of

¹ Read *īlā*.

² The meaning of the two terms 'undying' and 'unaging' is, that those sheep which died or ceased to supply milk had to be replaced from among the lambs that had grown up in the meantime.

³ I.e., apparently, a lamp-stand after the fashion of Ilam (Ceylon). According to the dictionaries, the word *īlam* means also 'gold;' but, if this meaning were intended here, the writer would have probably used the common word *poṇ*.

⁴ See above, Vol. IV. p. 139.

⁵ This word is here prefixed to the name of the Lāṭa chief Pugaḷvippavargaṇḍa in honour of his brother-in-law, the Chōḷa prince Rājāditya.

⁶ Read *īlammum*.

⁷ Read *Tiruttonḍiśvarattu Mahādēva*.

⁸ The secondary form of *i* is engraved above the initial *i*.

⁹ Read *Māhādēva*.

¹⁰ Read *yaṇḍr*.

¹¹ Read *Pugaḷvippavargaṇḍaṇai*.

¹² Read *nōttā*.

¹³ The *d* of *rd* seems to be corrected from *ḍu*.

¹⁴ Read *ḍaṇḍu*.

Ilāḍarāyar, gave one perpetual lamp to (*the god*) Mahādēva of the Tiruttonḍiśvara (*temple*) at Tirunāvalūr in Tirumunaiappāḍi for the merit of¹ (*her*) elder brother Araiyaṛ Rājādittan Puḡaḷvippavargaṇḍan. For (*this lamp she*) gave one hundred undying (*and*) unaging big sheep² (*and*) a lamp-stand weighing seventy *palam*, to burn as long as the moon and the sun shall last. This (*gift is placed under*) the protection of all Māhēśvaras.

C.—INSCRIPTION OF KRISHNA III.

This inscription (No. 362 of 1902) is dated in the 17th year of Kannaradēva, *i.e.* of the Rāshtrakūṭa king Kṛishṇa III., the conqueror of the Pallava and Chōḷa countries.³ It records the gift of a lamp by a chief of Milāḍu, named Narasimhavarman and surnamed Śaktinātha and Siddhavaḍava. He claims to belong to the lineage of Śukra and to the Malaiyakula, *i.e.* the family of the rulers of Malaiyanāḍu or Malaināḍu, of which Milāḍu and Malāḍu are contracted forms. According to the *Periyapurāṇam*, the capital of this district was Tirukkōvalūr (Tirukoilur), the head-quarters of the present Tirukoilur tāluka.⁴ The chiefs of Malaināḍu claimed connection with the Chēdi family.⁵ They had the custom of prefixing the name of the reigning Chōḷa king to their title. Thus, six inscriptions of Rājendra-Chōḷa I., Kulōttuṅga-Chōḷa and Vikrama-Chōḷa at Kīlūr near Tirukoilur (Nos. 241, 260, 284, 285, 286 and 290 of 1902) mention Milāḍuḍaiyāṇ Irāmaṇ Mummaḍi-Chōḷaṇ *alias* Rājendra-Chōḷa-Milāḍuḍaiyāṇ, Kīlīyūr⁶ Malaiyamāṇ Kulōttuṅga-Chōḷa-Chēdiyarāyaṇ, and Kīlīyūr Malaiyamāṇ Vikrama-Chōḷa-Chēdiyarāyaṇ, the father of Vikrama-Chōḷa-Kōvalarāyaṇ; and in two inscriptions of *Tribhuvanaśakravartin* Rājarājadēva and Kulōttuṅga-Chōḷadēva (Nos. 288 and 293 of 1902) we find Kīlīyūr Malaiyamāṇ Rā[ja]rāja-Chēdiyarāyaṇ.

The Trivikrama-Perumāl temple at Tirukoilur bears an inscription of the sixth year of Parakēsarivarman *alias* Rājendradēva, *i.e.* A.D. 1057-58⁷ or about a century after the present record. It belongs to a later chief of Milāḍu, whose name was likewise Narasimhavarman. He resided at Tirukkōvalūr (Tirukoilur), was a descendant of the lineage of Bhārgava (*i.e.* Śukra), and bore the surname Rapakēsari-Rāma.

TEXT.

- 1 Svasti śrī || 6. Śrī-Kannaradēvarkku yāṇḍu padinēḷāvaḍu Mupaippāḍi-Ttirunāvalūr-Tti[rut]tonḍi(nḍi)śvarattu Mā(ma)hādēvarkku svasti Śukrānma(nva)y-ōdayāchal-āditya Śa[k]tinātha simha-ddhvaja śikhi-makara-la(lā)ñchhana Malaiyakul-ō-
- 2 tbha(dbha)va Malaiyakula-sū(chū)ḷamaṇi śrīmat(n)-Narasimhava[r*]mmā Milāḍ-udaiya nāṭṭān Śittavaḍavan-āgiya Narasimhava[n]man vaitta noṇḍā-viḷakk-onṇinukku vaitta poṇ padin kaḷaṇju [*] i-ppoṇ padin kaḷaṇju[ñ]=goṇḍu Veṇ-
- 3 painallūr-nāṭṭu-Chechevalai sabhaiyōmum ūrōmum āṭṭu nūṟu nāḷi ney [k]oḍu vaṇḍu māḍēviyāḷēy *śantrādityaval aṭṭuvōm=ānōm Śevalai sabhai ūrōm [*] Ūḷa-viḷakku onṇu ||— idu pan-Māh[ē]śvara[r*]
- 4 irakshai || 6.

¹ This seems to be the meaning of the gerund *īrtti*, which occurs frequently in the same connection.

² See above, p. 134, note 2.

³ See above, Vol. III. p. 282 ff. and Vol. IV. p. 81 f. and p. 280 f.; *South-Ind. Inscr.* Vol. III. pp. 11 and 22.

⁴ *South-Ind. Inscr.* Vol. II. p. 167.

⁵ See *loc. cit.* and *Ind. Ant.* Vol. XXII. p. 143.

⁶ Kīlīyūr is a village in the Tirukoilur tāluka, No. 128 on the *Madras Survey Map*.

⁷ See page 7 above.

⁸ Read *chandra*.

TRANSLATION.

(Line 1.) Hail! Prosperity! In the seventeenth year of the glorious **Kannaradēva**,—Hail! the glorious **Narasimhavarman**, the sun of the eastern mountain— the lineage of **Śakra**, **Śaktinātha**,¹ whose banner bore a lion, whose crest were a peacock and a *makara*, who was born in the **Malaiyakula**, the crest-jewel of the **Malaiyakula**, the lord of the country of **Milāḍu**,—(this) **Narasimhavarman** who was called **Siddhavaḍava**² gave one perpetual lamp to (the god) **Mahādēva** of the **Tiruttonḍiśvara** (temple) at **Tirunāvalūr** in **Muṇaippāḍi**. For (this lamp he) gave ten *kaḷaṇḍu* of gold.

(L 2.) Having received these ten *kaḷaṇḍu* of gold, we, the members of the assembly and the inhabitants of the village of **Sevalai** in **Vennainallūr-nāḍu**, shall have to bring every year one hundred *nāḷi* of ghee and shall have to pour (it) out (i.e. measure it) by the *māddēvi*³ as long as the moon and the sun shall last.

(L 3.) One *īḷa* lamp-(stand)⁴ (was also given). This (gift is placed under) the protection of all **Māhēśvaras**.

D.—INSCRIPTION OF SAKA-SAMVAT 875.

This inscription (No. 356 of 1902) and the next one (E.) are remarkable for being dated according to the Śaka era, which is employed in very few of the earlier Tamil inscriptions.⁵ The inscription D records the gift of a lamp by a **Muṇaiyadiyaraiyaṇ**, i.e. a chief of the district of **Muṇai** or **Muṇaippāḍi**, in which **Tirunāmanallūr** was included.⁶ 'The chief of the people of **Muṇai**' (*Muṇaiyar kōṇ*) is mentioned as a vassal of **Vikrama-Chōḷa** in the *Vīḷkaiama-Śōḷa-Uḷ*.⁷ According to the *Periyapurāṇam*, the Śaiva saint **Sundaramūrti** was the protégé of another chief of **Tirumuṇaippāḍi** (*Muṇaiyadiyar*), named **Narasimha**, who resided at **Tirunāvalūr** (**Tirunāmanallūr**), and who is himself considered one of the sixty-three **Tiruttonḍar** or devotees of Śiva.

TEXT.

- 1 || Svasti śrī || ௨. Śagar[ai] yā[ṇ]ḍu
- 2 875āvaḍu Tirunāvalūr Ti-
- 3 ruttonḍi-īśvara-⁸garattu
- 4 dēvarkku Muṇai[ya]ldiyarai[ya]-
- 5 ṇ Kulamānikkaṇ [I]rāma-
- 6 dēvaṇ vaitta nottā(ndā)-viḷak-
- 7 ku onru śāvā mu(mū)vā=ppēr-āḍu 100 [*]
- 8 ivv-āḍu [nū]ṇu=goṇḍu śan-
- 9 dirā[d]ittavalu[m] erikka ṇ[e]y at[ṭu]-
- 10 vār=[ā]ṇār dēvaḍāṇam [Ē]kadi(dhi)ra-śa(cha)[ṭu]-
- 11 [rvvē]dimāṅgalattu sabhai[yār] [||*]

TRANSLATION.

(Line 1.) Hail! Prosperity! In the Śaka year 875, **Muṇaiyadiyaraiyaṇ** **Kulamānikkaṇ** **Irāmadēvaṇ** gave to the god of the **Tiruttonḍiśvara** temple at **Tirunāvalūr** one perpetual lamp (and) 100 undying (and) unaging big sheep.⁹

¹ I.e. 'the lord of the spear' or 'the lord of power.' The same word is an epithet of the two gods Skanda and Śiva.

² I.e. '(the owner) of renowned mares.'

³ I.e. a measure called after the chief queen (*mahādēvi*).

⁴ An inscription of the Śaka year 810 was published in *South-Ind. Inscr.* Vol. III, p. 95.

⁵ See page 133 above.

⁶ Read *Tiruttonḍiśvara*.

⁷ See above, p. 134, note 3.

⁸ *Ind. Ant.* Vol. III, p. 95.

⁹ *Ind. Ant.* Vol. XXII, p. 143.

¹⁰ See above, p. 134, note 2.

(L. 8.) Having received these hundred sheep, the members of the assembly of **Ēkadhira-chaturvêdimangalam**, (*a village*) granted to the temple, shall have to pour out ghee,¹ to burn as long as the moon and the sun shall last.

E.—INSCRIPTION OF SAKA-SAMVAT 876.

This inscription (No. 338 of 1902) records the gift of a lamp by the queen of a chief of **Munai**, whose name resembles that of the other chief mentioned in the preceding inscription (D.).

TEXT.

- 1 Svasti śrī [||*] Śagarai yāṇḍu 87[8]-
- 2 āvadu Tirunāvalūr Tirutṭoṇḍiśva-
- 3 rattu Mahādēvaṅku Munaiyadiyaraiyar Kulamā-
- 4 ṇikkerumāṇār dēv[i]yā[r=A]kkināṅ[aiyār] vaytta²
- 5 noṇḍā-vilakkiṇukku va(vai)tta śāvā m[ā]vā pār-āḍu
- 6 nūru³ nūruṇ=[g]oṇḍu nū⁴ ni[śa]da[m*] uḷakku māḍēviyāl⁵
- 7 n[ey] aṭṭuv[ō]m=āṇōm Arumbākkā[t*]t=ūr[ō]m [i*] idu [paṇ]-M[ā]y[ā](hē)-
[śvarar irakshai ||*]

TRANSLATION.

(Line 1.) Hail! Prosperity! In the Śaka year 876, [A]kkināṅaiyār, the queen of **Munaiyadiyaraiyar Kulamāṇikkerumāṇār**, gave a perpetual lamp to (*the god*) Mahādēva of the **Tirutṭoṇḍiśvara** (*temple*) at **Tirunāvalūr**. For (*this lamp she*) gave one hundred undying (*and*) unaging big sheep.⁶

(L. 6.) Having received (*these*) hundred (*sheep*), we, the villagers of **Arumbākkam**, shall have to pour out daily one *uḷakku* of ghee by the *māḍēvi*.⁷ This (*gift is placed under*) the protection of all Māhēśvaras.

F.—INSCRIPTION OF RAJENDRA-CHOLA I.

This inscription (No. 360 of 1902) belongs to the reign of **Parakēsarivarman** *alias* **Rājendra-Chōḷadēva**, *i.e.* the Chōḷa king **Rājendra-Chōḷa I.** who ascended the throne in A.D. 1011-12.⁸ The figure denoting the year of his reign is lost. A regiment of the king gave to the god a necklace of gold and jewels, and the commander of the regiment gave another necklace of pearls and a bracelet of gold.

TEXT.

- 1 Svasti śrī[i] [||*] K[ō]=Pparakēsaripa[r*]mar-ā[ṇa] śrī-Rājēndhi(ṇdi)ra-
Śōḷadēvaṅku yā[ṇḍu] . . [va]ḍu Jayaṅgoṇḍa-Śōḷa-ma[ṇḍa]lattu-Ttiru-
- 2 munaippā[ḍi] M[ē]lūr-nāṭṭu-Ttirunāvalūr-āṇa Rājādittadēvapurattu
[Tirutṭon]ḍi(ṇḍi)śvarattu Āḍavalāṅku ṇḍaiyār paḍai Vi(vi)raṇārāya[ṇa]-
tte[r]i[ṇḍa-vil]ligal
- 3 śeyd=iṭṭa mālai lṇāl poṇ mu-kkaḷaṇj=arai [i*] idil taḍavi kaṭṭiṇa
spa(spha)ṭika[m] nāyagaṇ uṭpaḍa uru paṇiṇṇu ni(ni)lam iraṇḍam [i*]
[mu]ttōḍu mālai o-

¹ Compare the preceding inscription (C.)

² Read *vaitta*.

³ This sign of punctuation is expressed by a dot above the line.

⁴ Cancel this syllable.

⁵ The syllable *mā* is entered below the line.

⁶ See above, p. 134, note 2.

⁷ See above, p. 136, note 3.

⁸ See page 7 above.

4 nru [i*] idu še[y]vitt-iduvittāṅ i-ppaḍaikkku nāyagam seyda Mārāyan
 Paḷuvūr Nakkan [i*] ivanē tiru-kaiyckku sātṭi aruḷa taḍavi kaṭṭina
 sphatikam onṇu mutt=¹ēṇṇa kâ-
 5 rai onṇu po[n kaḷa]ñju [i*] ivai pan-Māhahēśva[ra*]-²ra[kshai] [i*]

TRANSLATION.

(Line 1.) Hail! Prosperity! In the . . th year of king Parakēsarivarman *alias* the glorious Rājendra-Chōḷadēva,—the chosen bowmen of Vīranārāyaṇa,³ a regiment of the king, made and gave 1 necklace, consisting of three and a half *kaḷaṇṇu* of gold, to (*the god*) Āḍavalār of the Tiruttoṇḍiśvara (*temple*) at Tirunāvalūr *alias* Rājādittadēvapuram in Mēlūr-nāḍu, (*a subdivision*) of Tirumunaiṇṇāḍi, (*a district*) of Jayanṅonda-Śōḷa-maṇḍalam. In this (*necklace*) were fixed eighteen pieces of crystal, including the central gem, and two sapphires.

(L. 3.) One necklace of pearls. This was caused to be made and to be given by Mārāyan Paḷuvūr Nakkan,⁵ who commanded this regiment.

(L. 4.) The same person (*gave*) one bracelet, to be placed on the arm of the god (*and consisting of*) one *kaḷaṇṇu* of gold, in which one crystal was fixed (*and*) on which pearls were mounted.

(L. 5.) These (*gifts are placed under*) the protection of all Māhēśvaras.

No. 20.—FOURTEEN INSCRIPTIONS AT TIRUKKOVALUR.

By E. HULTZSCH, PH.D.

Tirukkōvalūr is the head-quarters of a tāluca of the South Arcot district. It contains a Viṣṇu temple named Trivikrama-Perumāl, and the suburb of Kīlūr a Śiva temple named Virattāṇēśvara. Of the subjoined inscriptions, ten (A. to J.) are in the Śiva temple and four (K. to N.) in the Viṣṇu temple.

The sacred writings of the Śaivas and Vaishṇavas of the Tamiḷ country mention both of the Tirukkōvalūr temples. Tiruñāṇasambandar refers to the Śiva temple as 'Virattāṇam at Kōvalūr,'⁶ and Tirumaṅgai-Āḷvār to the Viṣṇu temple as 'Idaikaḷi at Kōvalūr.' The subjoined inscriptions have the forms Tiruvirattāṇam (A. to J.) and Tiruviḍaikaḷi (K.) or Idaikaḷi (L.). Tirukkōvalūr (A. to C., E. to K.) or Kōval (L.) bore in the time of the Chōḷa dynasty the surname Madurāntaka-chaturvēdimāṅalam (K.). It was included in Kuṟukkai-kūṟram, a subdivision of Malāḍu or Milāḍu,⁷ a district of 2,000 (villages), which in the time of the Chōḷas was surnamed Jananātha-vaḷanāḍu (K.).

The subjoined inscriptions incidentally mention three villages, *viz.* Uṇṅalpūṇḍi (G.), Neṇmali and Śiṟṇinjūr (H.). Of these, I can only identify the second, which is the modern Nemali.⁸

¹ The first *t* of *mutt*= is entered below the line.

² Read -Māhēśvara-.

³ This regiment was probably named after Parāntaka I., who had the surname Vīranārāyaṇa; see *South-Ind. Inscr.* Vol. II. p. 379. Two Tanjore inscriptions mention another regiment, entitled Paṇḍita-Śōḷa-terinda-villigal, which was named after a surname of Rājendra-Chōḷa I. himself; see *ibid.* Vol. III. p. 127 and note 17.

⁴ Āḍavalār or Āḍavallār is a Tamiḷ synonym of Natēśa, a form of Śiva.

⁵ This person may have been a native of Kīḷappaluvūr, which is mentioned in the *Dēḍram* under the name of Paḷuvūr; see *South-Ind. Inscr.* Vol. III. p. 152.

⁶ One of the sixty-three devotees of Śiva, Maypporuṇāyaṇār, is supposed to have resided at Tirukkōvalūr; see *South-Ind. Inscr.* Vol. II. p. 167.

⁷ See page 135 above.

⁸ No. 159 on the *Madras Survey Map* of the Tirukoilur tāluca.

A.—INSCRIPTION OF VIJAYA-NANDIVIKRAMA.

This Tamil inscription (No. 278 of 1902) is dated in the 17th year of Vijaya-Nandivikrama, i.e. of the Gaṅga-Pallava king Vijaya-Nandivikramavarman.¹ It records the gift of a lamp by a concubine of Vāṇakōvaraiyar. This was probably the title of the chief of Vāṇakōppādi or Vāṇagappādi, a district which according to other inscriptions (No. 40 of 1887-88 and No. 126 of 1900) included Tiruvannāmalai on the northern bank of the Pennai.² A later Vāṇakōvaraiyar is referred to in an inscription of Kulōttuṅga I.³ and another Vāṇakōvaraiyar in one of Kulōttuṅga III. (No. 72 of 1890).

TEXT.

- 1 Svasti śrī [||*] Kō Vijaiya-vikrama-⁴Nandivi[k*]kiramarkku yāṇḍu 17āvaḍu(du)
Malāṭṭu
2 Kuṛukkai-kkūṟṟattu Tirukkōvalūr Tiruvi(vi)[ra]ṭṭāṇattu-Pperumāḷukku oru-no-
3 ndā-viḷakku Māṇikka[t*]tār magaḷār Kōṇakkaṇār Vāṇakōvaraiyar bōgi-
4 yār vaitta poṇ paḷaṇ-gāṣiṇḍu uraiy=oppadu 15 la⁵ [||*] i-ppoṇ
5 paḍiṇḍ-gaḷaṇḍu=gonḍu kaḍavōm ivv-ār nagarattōm [||*] i-ppoṇ
6 ṇiṇ paḷisaiyālēy niśadam uḷakk=enṇai ā(a)ṭṭuvōm=ānōm nagarattōm [||*] idu pan-
Māhēśvara-rakshai [||]

TRANSLATION.

(Line 1.) Hail! Prosperity! In the 17th year of king Vijaya-Nandivikrama,—
Kōṇakkaṇār, the daughter of Māṇikkattār (and) the concubine⁷ of Vāṇakōvaraiyar, gave 15
kaḷaṇḍu of gold, which was equal in fineness to the old kaḷu,⁸ (for) one perpetual lamp to (the
god) Perumāḷ⁹ of the Tiruviraṭṭāṇam (temple) at Tirukkōvalūr in Kuṛukkai-kūṟṟam, (a
subdivision) of Malāḍu.

(L. 4.) We, the citizens of this place, have received these fifteen kaḷaṇḍu of gold.

(L. 5.) Out of the interest of this gold, we, the citizens, shall have to pour out daily one
uḷakku of oil.

(L. 6.) This (gift is placed under) the protection of all Māhēśvaras.

B.—INSCRIPTION OF VIJAYA-NRIPATUNGAVIKRAMA.

This Tamil inscription (No. 277 of 1902) is dated in the 21st year of Vijaya-Nripatunḡa-
vikrama,— the son and successor¹⁰ of Vijaya-Nandivikrama whose name we have found in the
preceding inscription (A.). It records the gift of a lamp by a servant of Veṭṭuvadaraiyar,—
apparently a local chief.

TEXT.

- 1 Svasti śrī [||*] Kō Vijaiya-Nirupatoṅgavikramarkku yāṇḍu 21āvaḍu Milā-
2 ṭṭu-Kkuṛukkai-kkūṟṟattu Tirukkōvalūr Tiruvi(vi)raṭṭāṇattu Mahādēvarkku
natnā(ndā)-viḷa-
3 kkiṇukku Veṭṭuvadaraiyarkku aṟāmuppuṇṇ Nannan Korraṇ kuḍutta poṇ
4 12 la¹¹ [||*] paṇṇiru-kaḷaṇḍu paḷisaiyālēy iravum pa[ga*]lum oru-nondā-viḷak-

¹ See above, Vol. VI. p. 321.

² I.e. the Southern Pennaiyāru; see above, Vol. VI. p. 333.

³ South-Ind. Inscr. Vol. III. p. 152.

⁴ Cancel -vikrama-.

⁵ This letter slants towards the right; it is evidently an abbreviation for kaḷaṇḍu. In an inscription of Kulōttuṅga I. (above, Vol. V. p. 105, text line 5) I have misread this symbol as pa.

⁶ Read paḍiṇḍu.

⁷ Bōgi is used in the sense of bōgiṇi (bhōgiṇi in Sanskrit).

⁸ This must be the designation of some gold coin; compare above, Vol. V. p. 106 and note 3.

This is one of the Tamil names of Viṣṇu, but is here applied to Śiva.

¹⁰ See above, Vol. VI. p. 321.

¹¹ See note 5 above.

5 k=erippôm=ânôm Tirukkôvalûr nagarattôm śandrâdittaval [*] idu pan-Mā.
6 hēśvara-rakshai||

TRANSLATION.

(Line 1.) Hail! Prosperity! In the 21st year of king Vijaya-Nripatungavikrama,—Nanṇaṇ Korraṇ, a servant¹ of Veṭṭuvadaraiyar, gave 12 *kaḷaṇṇu* of gold for a perpetual lamp to (*the god*) Mahādēva of the Tiruvirattāṇam (*temple*) at Tirukkôvalûr in Kuṟukkai-kūṟṟam, (*a subdivision*) of Milāḍu.

(L. 4.) Out of the interest of (*these*) twelve *kaḷaṇṇu*, we, the citizens of Tirukkôvalûr, shall have to burn one perpetual lamp night and day, as long as the moon and the sun shall last.

(L. 5.) This (*gift is placed under*) the protection of all Māhēśvaras.

C.—INSCRIPTION OF VIJAYA-NRIPATUNGAVIKRAMAVARMAN.

This Tamil inscription (No. 303 of 1902) belongs to the same king and year as the preceding one (B.) and records the gift of a lamp by the same servant of Veṭṭuvadiyara²iyar. This form of the title occurs also in an inscription of the 22nd year of Vijaya-Nripatungavarman at Tiruchcheṇṇambūṇḍi (No. 301 of 1901), while the preceding inscription (B.) has the slightly different form Veṭṭuvadaraiyar.

TEXT.

1 Svasti śrī [*] Kô Viśaiya-Niru[patōṅga]vikkira-
2 maparumaṟku yāṇḍu [21]āvaḍu T[i]rukkô-
3 valûr Tiruvi(vi)ratṭ[ā]ṇattu Mahādēvarkku [na]-
4 ndā-viḷak[k]iṇṇukku Veṭṭuvadiyara²iyar a-
5 ṟāmunaṇṇu=Nanṇaṇ Korraṇ kuḍutta po-
6 [ṇ] paṇṇiru-kaḷaṇṇu [*] idāṇ paḷiśaiyā[ḷ]
7 nandā-viḷakku iravum pagalum erippô-
8 mm=ânôm Tirukkôvalûr nagarattôm [*] i-
9 [du paṇ-Māhēśvara-ra*]kshai [||]

TRANSLATION.

(Line 1.) Hail! Prosperity! In the 21st year of king Vijaya-Nripatungavikrama-varman,—Nanṇaṇ Korraṇ, a servant of Veṭṭuvadiyara²iyar, gave twelve *kaḷaṇṇu* of gold for a perpetual lamp to (*the god*) Mahādēva of the Tiruvirattāṇam (*temple*) at Tirukkôvalûr.

(L. 6.) Out of the interest of this (*gold*), we, the citizens of Tirukkôvalûr, shall have to burn a perpetual lamp night and day.

(L. 8.) This (*gift is placed under*) the protection of all Māhēśvaras.

D.—INSCRIPTION OF PARAKESARIVARMAN.

This Tamil inscription (No. 299 of 1902) is dated in the 5th year of the Chōḷa king Parakeśarivarman³ and records the gift of a lamp by a queen of Vāṇakôvaraiyar.³

TEXT.

1 Svasti śrī [*] Kô=Ppara[kē]śaripaṇ[ma]ṟku yāṇḍu aiṇjāvaḍu Tiruvi(vi)-
ratṭāṇattu perumāṇadigaḷukku na-

¹ In *arḍmuṇṇum*, *arḍm* is perhaps a poetical form of *aram*, 'charity'; compare *paḍam* and *kaḍam* for *paḍam* and *kaḍam*. *Uṇṇum* is the relative participle of *uṇ*, 'to eat.'

² See above, Vol. V. p. 42.

³ On this title see p. 139 above.

- 2 nd[ā]-viḷakk[i]ṇukku Vāṇakōvaraiyar dēviyār=[I]lāḍaigaḷ magaḷā[r*] Naṅgai
Kulamāṇ[ī]kka-
3 ttār vaitta poṇ paḍiṇaiñ(ā)-gaḷaṇju [i*] i-ppoṇṇukku kaḷaṇṇi-vaṅ=ttiṅgaḷ uri-
4 ppaḍiyāl iravura pagalum nandā-viḷakk=erippippōm=āṇḍ=naga[ra*]ttōm [i*]
5 idu paṇ-Māhēśvara-rak[sh]ai [i*]

TRANSLATION.

(Line 1.) Hail! Prosperity! In the fifth year of king Parakēsarivarman,— Naṅgai Kulamāṇikkattār, the queen of Vāṇakōvaraiyar (*and*) the daughter of Ilāḍaigaḷ,¹ gave fifteen *kaḷaṇju* of gold for a perpetual lamp to the god of the Tiruviraṭṭāṇam (*temple*).

(L. 3.) For this gold, we, the citizens, shall cause to burn a perpetual lamp night and day, at the rate of one *uri* (of oil) per month for each *kaḷaṇju*.

(L. 5.) This (*gift is placed under*) the protection of all Māhēśvaras.

E. and F.—INSCRIPTIONS OF PARANTAKA I.

These two Tamil inscriptions (Nos. 279 and 280 of 1902) belong to the reign of "Parakēsarivarman who took Madirai (Madhurā)," i.e. of the Chōla king Parāntaka I.² The first is dated in his 28th and the second, which follows it in line 4, in his 33rd year.

The inscription E. records the gift of a lamp by a daughter of Kayiṇṇ Perumāṇār, a chief of Milāḍu, and the inscription F. refers to a similar gift by the regiment of prince Arikulakēśarin. The same prince is mentioned as 'the royal son of the Chōla king' in an inscription of the 24th year of Parāntaka I. at Tirupandurutti near Tanjore.³ He is perhaps identical with Arimajaya, the third son of Parāntaka I.⁴

TEXT OF E. AND F.

- 1 Svasti śrī [i*] Madirai koṇḍa kō=Pparakēsaripanma[r*]kk-iyāṇḍu 28āvadu
Malāṭṭu-Kkuṇukkai-
2 kūrattu Tirukkōvalūr Tiruvi(vi)raṭṭāṇattu=Pperumāḷukku oru-nondā-
viḷakku[k*]ku Mi[l]āḍ-ndaiyār
3 Kayiṇṇ=Pperumāṇār magaḷār Rājadēviyār Tēṣaḍakki Perumāṇār vaitta
śāvā m[ā]vā=ppēr-āḍu nū-
4 ru [i*] ivai pan-Māhēśvara-rakshai || 6 Svasti śrī [i*] Madirai koṇḍa
kō=Pparakēsaripanma[r*]kk-iyāṇḍu [3]3āvadu Tiruk-
5 kōvalūr Tiruvi(vi)raṭṭāṇattu Mah[ā*]dēvarkku piḷaiyār Arikulakēśariyār
paḍaiyār Malaiyāṇa-orraichohēvagar oru-
6 nondā-viḷakkukku śandirāḍittavall=eriya vaitta śāvā mu(mū)vā=ppēr-āḍu nūru [i*]
ivai pan-Māhēśvara-rakshai || 6-]

TRANSLATION OF E.

Hail! Prosperity! In the 28th year of king Parakēsarivarman who took Madirai,— Rājadēviyār Tēṣaḍakki⁵ Perumāṇār, the daughter of the lord of Milāḍu, Kayiṇṇ

¹ The name of this person suggests that she may have been connected with the Lāṭa chiefs of the North Arcot district; see above, p. 134 and note 4.

² See above, p. 133 and note 6.

³ Published by Mr. Venkayya in the *Madras Christian College Magazine* of August 1890.

⁴ No. 6 of the Table in *South-Ind. Inscri.* Vol. I. p. 112.

⁵ This word means 'the subduer of the lustre (of enemies).' Both this surname and the following title *Perumāṇār* would be more appropriate for a prince, than for a princess.

Perumāṇār, gave one hundred undying (*and*) unaging big sheep¹ for one perpetual lamp to (*the god*) Perumāḷ² of the Tiruvirattāṇam (*temple*) at Tirukkōvalūr in Kuṟukkai-kūṟram, (*a subdivision*) of Malāḍu. These (*sheep are placed under*) the protection of all Māhēśvaras.

TRANSLATION OF F.

Hail! Prosperity! In the 33rd year of king Parakēsarivarman who took Madirai,—the Malaiyāṇa-ōṟraichchēvagar,³ the regiment of prince Arikulakēsarīyār, gave one hundred undying (*and*) unaging big sheep for one perpetual lamp, (*which was*) to burn as long as the moon and the sun shall last, to (*the god*) Mahādēva of the Tiruvirattāṇam (*temple*) at Tirukkōvalūr. These (*sheep are placed under*) the protection of all Māhēśvaras.

G.—INSCRIPTION OF KRISHNA III.

This Tamil inscription (No. 268 of 1902) is dated in the 21st year of Kaṇṇaradēva, *i.e.* of the Rāshtrakūṭa king Kṛṣṇa III.⁴ It records a grant of land by the Vaidumba-mahārāja Śandayaṇ Tiruvayaṇ and (his queen) Śūttiradēvi.⁵

The Vaidumbas appear to have been local chiefs. One of them is stated to have been defeated by Parāntaka I.⁶ 'Śandayaṇ Tiruvayaṇ,' *i.e.* Tiruvayaṇ, the son of Śandayaṇ, has to be identified with Tiruvaiyaṇ, the father of Śaṅkaradēva who was a contemporary of Rājārāja I.⁷ and who is called a Vaidumba in an inscription of Rājendra-Chōḷa I.⁸

The subjoined grant of Tiruvayaṇ is quoted, and the names and measurements of the fields are repeated, in an inscription of Rājārāja I. (No. 236 of 1902), which has been utilized for the translation of the present record.

TEXT.

- 1 Svasti śrī [||*] Kaṇṇaradēvaṅk-iyāṇḍu irubattoṇṇāvadu Malāṭṭu-Kkuṟukkai-kkūṟrattu Tirukkōvalūr-Ttiruvi(vi)ratṭāṇam=uḍaiya perumāṇa-
- 2 ḍigaḷukku Vaidumba-mahārājar Śandayaṇ Tiruvayaṇ Tirukkōvalūr sabhaiyār-
idai yāṇ vilai-koṇḍa bhūmi Uṇāṅalpūṇḍi.⁹
- 3 yīṟ-paḍu=nilam naṇṣeyum puṇṣeyum Bagavanda-kkaḷaṇi irubattettum Kāḍēṟu kālū=
Marattuḷāṅ-vēli eṭṭum Kaḷarmēḍu ki(ki)ḷiṇa
- 4 pattum mēlaṇa iraṇḍu māvum Kaḷiya-kkaḷaṇi Kōṟpāḍu eṭṭu māvum [||*] ittaṇai
nilamum poṇ kuḍuttu irai iḷichchi āḷvār-
- 5 kku=ttiruvamudu [i]ratṭikku nivandañ=jeydu kuḍuttēṇ Tiruvayaṇ-ēṇ [||*]
ivaiyīṟḷ Kaḍambaṇum=Uttiraṇ-idai=Chchūttiradēvi koṇ-
- 6 ḍu kuḍuttaṇa pattu=chcheṟuvum Uvachcha-kaḷaṇ [||*] idu pan-Māhēśvarar=irakshai ||—

TRANSLATION.

(Line 1.) Hail! Prosperity! In the twenty-first year of Kaṇṇaradēva,—I, the Vaidumba-mahārāja Śandayaṇ Tiruvayaṇ, purchased from the members of the assembly of Tirukkōvalūr (*the following*) wet land and dry land, situated in Uṇāṅalpūṇḍi:— the

¹ See above, p. 134, note 2.

² See above, p. 139, note 9.

³ *I.e.* 'the unrivalled warriors of Malayālam.' This was perhaps a regiment of Nairs.

⁴ See above, p. 135 and note 3.

⁵ This name may correspond in Sanskrit either to Śūttiradēvi or to Śūdradēvi.

⁶ *South-Ind. Inscr.* Vol. II. p. 387, verse 9.

⁷ *South-Ind. Inscr.* Vol. III. p. 104.

⁸ *Ibid.* p. 108. For other references to the Vaidumbas see *ibid.* p. 106.

⁹ The *i* of *ḍi* is expressed twice.

Bhagavanta field, (containing) twenty-eight (*mā*);¹ (the field called) *Kāḍēru*, (containing) a quarter (*vēli*);² the *Marattulāṇ* field, (containing) eight (*mā*); ten (*mā*) below the *Kāḷarmēḍu*; two *mā* above (the same); and eight *mā* (called) *Kōrpāḍu* (in) the *Kāḷiya* field. Having paid gold and having exempted this land from taxes, I, *Tiruvayaṇ*, gave (*it*) to the god of the *Tiruviraṭṭāṇam* (temple) at *Tirukkōvalūr* in *Kuṟukkai-kūṟṟam*, (a subdivision) of *Malāḍu*, for the requirements of a double (daily) offering to the god.

(L. 5.) Out of this (land) *Śūttiradēvi* gave a field of ten (*mā*), which (*she*) had purchased from *Kaḍambaṇ* and *Uttiraṇ*, (as) a field for the *Uvaḥchas*.³

(L. 6.) This (gift is placed under) the protection of all *Māhēśvaras*.

H.—INSCRIPTION OF KRISHNA III.

This Tamil inscription (No. 235 of 1902) belongs to the same king as the preceding one (G.). The year of the reign is obliterated, but may have been the 22nd. The inscription records a gift of gold by a female relative of the *Vaidumba-mahārāja Tiruvayaṇ*, whose name has been already met with in G.

TEXT.

- 1 Svasti śrī [||*] Kannaradēvaṟku yā[ṇ]ḍu⁴ [Mal*][āṭ]ṭu=
Kkuṟukkai-kkūṟṟattu=Ttirukkōvalūr-Ttiruvi(vi)raṭṭāṇatt=ālvārkkū sam-
- 2 [kr]ānti-tōṟum snapaṇāṇ=jeyvadaṟku Vaidum[ba]-mahārājar Tiruvayaṇār dēviyār
mu(mū)tta-dēviyār Virattāṇ Vi(vi)ranāraṇiyār vaitta
- 3 [po]ṇ irubadiṇ kalaṇḍu [i*] i-ppon irubadiṇ kalaṇḍu=gonḍu kalaṇḍiṇ-vāy=kkala-
ppoliyūṭṭ=āga=ppēriḷama(mai)[y]āl irubadiṇ
- 4 kala=nellum tūyav=ākki kūli-pparam paṭṭu tiru-muṟṟattukkē koḍu ēṇṇ=alaṇḍu
kuḍuppōm=āṇōm Milāḍamāṇikkam=āgiyā(ya) Neṇmali sa[bb]aiyōm [i*] i-nne-
- 5 1 taṇḍuvārkkū me[y*]=kkaṇḍu sōṟu kuḍuppōm=āṇōm Neṇmali sabhaiyōm [i*]
Neṇmali sabhaiyārum Śirriṇḍūr sabhaiyārum pēriḷa-
- 6 ma(mai)yāl=alakk[u]=nelli aṟubadiṇ kalam=ivai eṇṇāli-kkālāl eḷuba[t]taiṇ-
[ga]lamu[n=d]iṅgaḷ-obādi aṟu-kalaṇē m[u]-kkuṟu[ṇi]yūn=gonḍu kalaṣam iruba . . .
.

TRANSLATION.

(Line 1.) Hail! Prosperity! In the [22nd ?] year of *Kannaradēva*,—queen *Virattāṇ Viranāraṇiyār* (i.e. *Viranāraṇiyāṇi*), the elder sister of the queen of the *Vaidumba-mahārāja Tiruvayaṇār*, gave twenty *kalaṇḍu* of gold to the god of the *Tiruviraṭṭāṇam* (temple) at *Tirukkōvalūr* in *Kuṟukkai-kūṟṟam*, (a subdivision) of *[Mal]āḍu*, for bathing (the god) at every *saṁkrānti*.

(L. 3.) Having received these twenty *kalaṇḍu* of gold, we, the members of the assembly of *Milāḍamāṇikkam* alias *Neṇmali*, shall have to supply — at the rate of interest of one *kalam* per *kalaṇḍu* — twenty *kalam* of paddy by the *pēriḷamai* (measure), cleaning (*it*), defraying the cooly charge, conveying (the paddy) to the very court-yard of the temple, going (there) and measuring (*it*).

(L. 4.) To those (temple officials) who shall call for this paddy, we, the members of the assembly of *Neṇmali*, shall have to supply boiled rice after having identified (their) persons.

¹ The *mā* is $\frac{1}{16}$ of a *vēli*.

² This is equal to five *mā*, the measurement of this field given in No. 236 of 1902.

³ I. e. the temple drummers; see *South-Ind. Inscr.* Vol. II. p. 299, note 2.

⁴ The existing traces of letters suggest the reading *22davadu*.

(L. 5.) The members of the assembly of Neṇṇmali and the members of the assembly of Śirriṇjūr have to measure sixty *kalam* of paddy by the *pēriḷamai*.

(L. 6.) Having received these (sixty *kalam*), (which are equal to) seventy-five *kalam* by the *kāl*¹ of eight *nāli*, and to six *kalam* and three *kuṟuṇi* per month,
 . . twenty (?) pots²

I.—INSCRIPTION OF KRISHNA III.

This Tamil inscription (No. 267 of 1902) is dated in the 24th year of the same king as the two preceding inscriptions (G. and H.) and records a gift of 24 lamps by the Vaidumba-mahārāja Tiruvayan, the donor of G.

TEXT.

- 1 Svasti śrī [||*] Kaṇṇaradēvaṛk=iyāṇḍu(ṇḍu) irubattu-nālāvaḍu Malāṭṭu-Kkuṟukkai-kūṟṟattu=
- 2 Ttirukkōval[ū]r-Ttiruv[i]raṭṭāṇatt=ālvārku Vaidumba-mahārājar Tiruvayanār
- 3 ālvārku [cha]ndrādittaval tiru-viḷakku 24kku vaitta āḍu sāvā mu(mū)vā=ppē-
- 4 r-āḍu iraṇḍāyirattu-munnūṟṟu-nāliṇālum nondā-viḷakku pan-Māhēśvara-rakshai ||—

TRANSLATION.

Hail ! Prosperity ! In the twenty-fourth year of Kaṇṇaradēva,— the Vaidumba-mahārāja Tiruvayanār gave to the god of the Tiruvirattāṇam (*temple*) at Tirukkōvalūr in Kuṟukkai-kūṟṟam, (*a subdivision*) of Malāḍu, two thousand three hundred and four undying (*and*) unaging big sheep³ for 24 sacred lamps (*which shall burn*) before the god as long as the moon and the sun shall last. The perpetual lamps (*fed*) by (*the ghee prepared from the milk of these sheep are placed under*) the protection of all Māhēśvaras.

J.—INSCRIPTION OF RAJARAJA I.

This Tamil inscription (No. 239 of 1902) is dated in the 9th year of Rājarājakēśari-varman, *i.e.* of the Chōḷa king Rājarāja I., and records the gift of a lamp by Amitravalli, (*the daughter of*) Kundan and the mother of queen Lōkamahādēvi. The same queen of Rājarāja I. is mentioned in inscriptions at Tanjore and Tiruvaiyāru.⁴

TEXT.

- 1 Svasti śrī [||*] Kō Rājarājakēśarivanma[r*]ku yāṇḍu onppadā-⁵
- 2 vadu Mi[l]āṭṭu-Kkuṟukkai-kkūṟṟattu=[T]tirukkōvalūr=Ttida(ru)-
- 3 vi(vi)raṭṭāṇam uḍe(ḍai)yār[k*]ku nam-birāṭṭiyār Ulōgamahādēviyā[rai]=
- 4 ttiru-vayiyu-vāytta Kundan [A]mittirava[l]li ālvārku-
- 5 ku chaṇḍrādittavat vaichecha nondā-viḷakku onṟu [||*] tiruvuṇ[n]ā[ḷi*]-
- 6 gaiyār i-[v*]viḷakkāl pon [k]onḍu chandr[ā]dittavala(lu)m⁶ viḷak[k]=eri-
- 7 [p]pōm=āṇōm tiruvuṇṇāḷig[ai]-sabhaiyōm [||*] iraṇḍu kāsū
- 8 perṟa ũa-viḷakku on[ru] [||*] idu pan-Māhēśvara-rakshai ||—

¹ *Kāl* is a shorter form of *marakkāl* or *kuṟuṇi*, a measure which consists of 8 *nāli* and is equal to $\frac{1}{12}$ *kalam* compare *South-Ind. Inscr.* Vol. II. p. 48, note 5.

² These pots were evidently required for the bathing of the god, which was the purpose of the grant according to L. 2 of the inscription.


³ See above, p. 134, note 2.

⁴ *South-Ind. Inscr.* Vol. II. pp. 90, 142, 148, 152, and 278, note 7; above, p. 25, note 8.


⁵ Read *onpaddavadu*.

⁶ The secondary sign for *i* stands above *tava* of *ṭavalam*.


B.




E. AND F.



G.



1.



TRANSLATION.

(Line 1.) Hail! Prosperity! In the ninth year of king Rājarājakēsarivarmā,—Kundaṇaṇ **Amitravalli**, who gave birth to our lady Lōkamahādēviyār, gave to the god of the Tiruvirāṭṭāṇṇam (temple) at Tirukkōvalūr in Kuṟukkai-kūṟṟam, (a subdivision) of Milāḍu, one perpetual lamp (which shall burn) before the god as long as the moon and the sun shall last.

(L. 5.) Having received gold for this lamp, we, the members of the assembly (in charge) of the store-room of the temple,¹ shall have to burn the lamp as long as the moon and the sun shall last.

(L. 7.) One *līla* lamp(-stand),² worth two *kāṣu*, (was also given).

(L. 8.) This (gift is placed under) the protection of all Māhēśvaras.

K.—INSCRIPTION OF RAJENDRADEVĀ.

This inscription (No. 123 of 1900) opens with a Sanskrit verse in the Grantha alphabet; the remainder is written in Tamil. It is dated in the 6th year of the Chōḷa king Parakēsarivarmā alias Rājēndradēva, i.e. A.D. 1057-58.³ As in other inscriptions,⁴ Rājēndradēva is stated to have conquered Raṭṭapāḍi, to have set up a pillar of victory at Kollāpuram, and to have defeated Ābavamallā at Koppam.

The object of the inscription is to commemorate the rebuilding of the Tiruviḍaikaḷi temple at Tirukkōvalūr by a chief of Milāḍu, named Narasiṃhavarman, who had the surname Raṇakēsari-Rāma, belonged to the family of Bhārgava,⁵ and resided at Tirukkōvalūr.

TEXT.

- 1 || Svasti śrī-Narasimhavanma(rma)-nripatiḥ Śr[ī]kōvalūrē bhajan vāsaṁ viśva-jagan-nivāsa-vapushaḥ śrī-Vāmanasy=[ā]kar[ō]t [i*] śailam śumbhita-sātakumbha-vilasat-kumbham ma-
- 2 hā-maṇḍa[pa]m prākāraṁ para-mālikā-vilasita[in*] muktāmāyī(yi)ñ=cha prapā(bhā)m ||—
Kōyil śrī-Vaiyishnavar rakshai || Svasti śrī [i*] Tirumagaḷ maruviya ſēngōl
vaḷara=ttan tiru-ttam[ai]yan[ō]ḍum [pō]-
- 3 y Irattapāḍi ā-arai ilakkamuñ=goṇḍu Kollāpurattu jayasta[m]bha=naṭṭi mīṇḍu pōṇḍu
pēr-āṟṟaṇ-garai Koppattu Āhavamallānai aṇjuvittu āṅgavaṇ āṇaiyum
kudiraiyum [p]e-
- 4 nḍir-paṇḍāramuñ=gaiy-kkoṇḍu vijaiya[r=a]bhishēkañ=jeydu vi(vi)ra-simhāsanattu [vi]r-
iruud=aruliya kō=Pparakēsaripanmar=āṇa nḍaiyār śrī-Rājēndradēvaṟku
yāṇḍu āṟvadu Milāḍ=āna Ja[nan]āda-[va]ṇ[ā]ṭṭu=Kkuru-
- 5 kkai-kūṟṟattu brahmadēyam Tirukkōvalūr=āṇa śrī-Maḍurāntaka-śadurvēdi-
maṇḍalattu=Tiruviḍaikaḷi [ā]lvār śrī-vi[m]ānam muṇbu [i]śhṭagai-ppaḍaiy=āy=
ppaḷagi=ppiḷandamai kaṇḍu Bhārggava-vaṁśattu Mi[ḷ]āḍu [u]ḍai-
- 6 yār Irāṇakēsari-Irāmar=āṇa Narasiṅgava[nma]r kōyilai iḷich[chi=kka]ruḷ[ga]llē
koṇḍu śrī-vimānamum [ma]ṇḍapamu[m] e[ḍu]ppittu pūra[ṇa]-poṟ-kuḍam ai[ṇ]ju
vai[p]pittu tiruchchurumāligaiyum [mu]nbi[ḷ] maṇḍapa-
- 7 mum eḍu[p]pittu mu[t]tu-ppandaluñ=guḍuttu munbu kal-v[e]ṭṭu-ppaḍiy-uḷḷa
nima[nda]ṅgaḷ=ellām inda śrī-vim[āna]ttē kallum veṭṭuvittār Narasiṅgavanmar
eṇṇu abishēgam paṇ-

¹ Compare *South-Ind. Inscr.* Vol. III. p. 20, note 5. The word *tiruvuṇḍigai* is repeated in a clumsy manner (l. 5 f. and l. 7).

² See above, p. 134, note 3.

³ See page 7 above.

⁴ *South-Ind. Inscr.* Vol. II. p. 303; Vol. III. pp. 39 and 111.

⁵ I.e. *Sukra*, the planet Venus; compare p. 135 above.

⁶ Read *-chaturvēdi*.

- 8 ni muḍi kavittu Milāḍu iraṇḍā[yi]ra[m] pūmiyum āṇḍa Milāḍ-ūḍaiyār
 Narasi[n]gava[nma]r ||— Narasiṅgavanmar śandrādittaval erikkaḥ vaitta
 tiru-nundā-ṇṇakku iraṇ[ḍu] [*] [i]v[ai]-
 9 [oh]chukku ṇṇakku=erikka kuḍutta śāṇḍā mu(mū)ṇḍā=ppera[m]-baṣu [aru]baṣu=ūḍu [*]
 iṇṇaichchāl niṣadam ṇṇakku ira[n]ḍin[i]ṇku ney urī [*] i-ppaṇḍu=ka[ṇ]-
 kko[nḍu*]

TRANSLATION.

(Line 1.) Hail! The glorious prince **Narasimhavarman**, residing in **Śrīkōvalūra**,¹ made for the god **Vāmana**, in whose body the whole world abides, a great *maṇḍapa* of stone, resplendent with pitchers of shining gold, a surrounding wall, adorned with excellent buildings, and a canopy of pearls. (*These buildings are placed under*) the protection of the *śrī*-*Vaiṣṇava*s of the temple.

(L. 2.) Hail! Prosperity! In the sixth year of king **Parakēsarivarman** *alias* the lord *śrī* **Rājendradēva**, who, while (*his*) sceptre, embraced by the goddess of Fortune, was prospering, went with his royal elder brother,² conquered the seven and a half *lakṣas* of **Raṭṭapāḍi**, set up a pillar of victory at **Kollāpuram**, started again, terrified **Āhavamalla** at **Koppam** (*on*) the bank of the great river, seized his elephants, horses, women and treasures, performed the *harmantment* of victors, and was pleased to take his seat on the throne of heroes,—

(L. 4.) Having perceived that the central shrine of the god of the **Tiruvīḍaikaḷi** (*temple*) at **Tirukkōvalūr** *alias* *śrī*-**Madurāntaka-chaturvēdimangalam**, a *brahmanḍiṇa* in **Kurukkai-kūṇṇam**, (*a subdivision*) of **Milāḍu** *alias* **Jananātha-vaṇanāḍu**, which formerly consisted of layers of bricks, had become old and cracked,—the lord of **Milāḍu** of the **Bhārgava** lineage, **Raṇakēsari-Rāma** *alias* **Narasimhavarman**, pulled down the temple, rebuilt the central shrine and the *maṇḍapa* of granite, placed (*on the shrine*) five solid pitchers of gold, built a surrounding wall and a *maṇḍapa* in front, and gave a canopy of pearls.

(L. 7.) The lord of **Milāḍu**, **Narasimhavarman**, who, having been anointed and crowned under the name **Narasimhavarman**, ruled the two thousand country of **Milāḍu**, caused to be re-engraved (*on*) the stones of this central shrine all endowments from copies of the former engraving on stone.

(L. 8.) **Narasimhavarman** gave two perpetual lamps, to burn as long as the moon and the sun shall last. For feeding these lamps, (*he*) gave sixty-four undying (*and*) unaging big cows.³ From these, one *urī* of ghee (*has to be supplied*) daily to (*these*) two lamps. Having received these cows,

L.—INSCRIPTION OF RAMA NARASIMHA.

This inscription (No. 118 of 1900) consists of a single Tamil verse. It is a short poetical version of the preceding inscription (K.) and refers to the rebuilding of the **Idaikaḷi** temple at **Kōval**, i.e. **Tirukkōvalūr**, by **Rāma Narasimha**.

TEXT.

- 1 Svasti śrī [||*] Naṇ-gōṇ=Irāman=ēḷi-chenḍō=
 2 Naraśi[n]gaṇ eṇ-gōṇ-ṇaṇ Kōval Idaikaḷiyi-
 3 1 aṇḍēy karuṇḍaṇ-paḍai . ai[n]ḍu sem-boṇ-
 4 kuḍan=dā=ṇeruṇḍa=ppayilvittā=ṇiṇṇu ||—

¹ This is a Sanskritized form of **Tirukkōvalūr**.

² *Viz.* **Rājādhirāja** I.; see *South-Ind. Inscr.* Vol. III. p. 89.

³ Compare above, p. 184, note 2.

U 2

No. 21.—TWO FURTHER INSCRIPTIONS OF TAMMUSIDDHI.

By H. LÜDEB, Ph.D.; GÖTTINGEN.

A.—TIRUVORRIYUR INSCRIPTION OF SAKA-SAMVAT 1120.

The subjoined inscription is engraved on the east wall of the second *prākāra* of the *Ādhipurīśvara* temple at *Tiruvorriyūr* in the *Saidāpēt* taluka of the *Chingleput* district.¹ The excellent inked estampages from which it is edited here were supplied to me by Dr. Hultsch.

The inscription consists of 26 lines in *Grantha* characters which vary in size from $\frac{3}{8}$ " to $1\frac{1}{4}$ ". The language is *Sanskrit*, and the whole text is in verse. With regard to orthography it may be noted that the engraver has followed the common practice of the time in this part of the country, in writing a surd consonant instead of a sonant before a sonant, in *patma* (ll. 1, 2, 3), *drīkibhyām* (l. 3), *utbhavati* (l. 8), *ushatbudha* (l. 13), and *bhavatbhir* (l. 25). Instead of *ushadbudha* lexicographers teach *usharbudha*, and this form is actually found in the *Uttararāmacharita* (6, 4^o). Nevertheless I do not venture to alter *ushatbudha* into *usharbudha*, as the word occurs again in exactly the same shape in line 15 of the *Arulāla-Perumāl* inscription of *Tammusiddhi* (B. below), and under these circumstances a mere clerical error seems to be out of the question.²

The inscription is one of king *Tammusiddhi* or *Tammusiddha*, and in every respect closely resembles the two inscriptions of that chief which I have edited above, p. 119 ff. I have pointed out already on that occasion that the present inscription is of some importance as settling the question of the relationship of *Dāyabhimā* and *Nallasiddhi*, which was left undetermined by the other two records.³ Besides, the genealogical portion of the inscription contains seven new verses, three of which, however, are of no interest for the historian as they are merely in praise of some well-known heroes of the solar line from which *Tammusiddhi* claimed descent, *viz.* *Raghu* (v. 8), *Daśaratha* (v. 9), and *Rāma* (v. 10). Verse 12 also, which alludes to the feats of the ancient *Chōla* king *Kalikāla*, adds nothing to our knowledge as it is an almost literal equivalent of the corresponding verse in the other two inscriptions. The verses 26 and 27 are eulogies of *Tammusiddhi* after the usual fashion.

The only new verse of historical value is verse 15, which introduces a king *Betta* as a descendant of *Madhurāntaka* *Pottappi-Chōla* and an ancestor of *Tilungavidya* or, as he is called here (v. 16), *Tilungabijja*. Literally translated, the verse runs thus: "In this family was born (a king) called *Betta*, who was the crusher of the thunderbolt whose flight was impelled by *Śakra*; if he with his fiery splendour had risen before, the cutting of the wings of the mountains also would not have taken place." *Betta* is here compared to *Agni*, the fire or the fire-god, who has the reputation of being able to split diamonds and thunderbolts.⁴ As *Betta*,

¹ No. 104 of the Government Epigraphist's collection for the year 1892.

² The writing *ushadbudha* is perhaps due to the influence of *Tamil* phonology. As in *Tamil* a *Sanskrit* dental generally assumes the sound of *r* before a labial (compare *e.g.* *Tamil urpatti* = *Sanskrit utpatti* and *Tamil arpuḍam* = *Sanskrit adbhutam*), I think it not unlikely that the *r* of *usharbudha* also was looked at as a secondary sound and therefore erroneously converted into *ḍ* or *t*.

³ It will be noticed that the term *tad-vamānjah* in verse 11 of the *Tiruppāśūr* inscription is replaced here (v. 20) by the words *asy=amūjah*.

⁴ See especially a passage in the *Uttararāmacharita* (6, 4^o), pointed out to me by Prof. Kielhorn: *uchhaṇḍa-vajra-khaṇḍ-āvarphōṭa-paṭah . . . usharbudhaḥ*, 'the fire . . . which is able to split into pieces the exceedingly hard *vajras*.' In this case, it is true, *vajra* would naturally suggest the meaning of diamond; but as *vajra* has also the meaning of thunderbolt, and as the thunderbolt is thought to be of the same substance with the diamond, it is easy to understand how later writers came to credit the fire also with the faculty of destroying thunderbolts.

however, is not a legendary person to whom purely fictitious exploits such as a fight with Indra might be ascribed, it is evident that the words *Śakra-chôdita-gatêr āsanêḥ praharîd* must be understood in a double sense and as referring to some historical event. We are thus led to take Āsani as a proper name and to translate 'who defeated Āsani whose march had been ordered by Śakra.' In this case Āsani would seem to have been the general of a king called Śakra or Indra; but it is perhaps even more probable, as suggested to me by Prof. Kielhorn, that *Śakra-chôdita-gatî* is the Sanskrit rendering of some Tamil or Telugu *biruda* of Āsani, just as Āsani itself may be the Sanskrit equivalent of some Dravidian name. Who this Āsani was, I am unable to tell; but it can be shown, at any rate, that proper names or *birudas* with the meaning of 'thunderbolt' are by no means uncommon in Southern India. Pagāppidugu, 'the thunderbolt which cannot be split,' was the surname of the Pallava Mahēndravarmān I.¹ Among the ancestors of the Chôla chief Śrīkaṇṭha appears an Agraṇipidugu, 'the thunderbolt to the foremost (of his enemies),'² and in the inscriptions of the Perumāḷ temple at Poygai we find four times a certain Śambuvarāyaṇ who bore the *biruda* Vīrāsani, 'the thunderbolt to heroes.'³ To these may be added Piḍuvarāḍitya, the *biruda* of Malla II., one of the chiefs of Velanāṇḍu, as the first member of the compound seems to be connected with *pidugu*.⁴

The object of the grant is to record that in the Śaka year denoted by the chronogram *Dhirayāyin*, i.e. 1120 (= A.D. 1207-8), Tammusiddhi allotted to the god, the lord of Ādhipurī, all the revenue due to the king in the villages belonging to the temple. Ādhipurī is an attempt of Sanskritizing Tiruvorriyūr, the name of the village where the temple is situated.⁵

TEXT.⁶

- 1 Svasti śrī-Tammusiddhāya tasmai yat-sainya-rēṇavaḥ [1*] Brahma-patma(dma)-
spraśas=śamkê bhāvi-bhū-srishti-hêtavaḥ || [1*] Jayati vijayi-chāpaḥ kshālit-
āśēsha-pāpas=satata-madhura-lāpaḥ prā-
- 2 pta-vidyā-kalāpaḥ [1*] vitata-vitarāṇ-āpaś=śatru-māyā-durāpaḥ praśamita-kali-tāpas=
Tammusiddhi-kshamāpaḥ || [2*] Udadhi-śayana-bhājaḥ Patma(dma)nābhasya
nābhêḥ kim=api nikhila-hêtur=jā-
- 3 tam=āscharyya-patma(dma)m [1*] yad=abhajad=api srishtêḥ pūrvvam=ētasya
drikbhya(ghbyā)m=mrīdu-kathina-mahôbhyām=mlān-ônmlānāni || [3*] Tasmād=
Viriñchir=udabhūt=suchiran=tad-antar=vvāsād=iva prakāṭayan=rajasah
- 4 pravṛttim [1*] ya[h*] Śrīśa-talpa-phaṇi-mauli-maṇi-praviṣṭa-bimbās=srijaṇn=iva
babhau sadpraśas=sahāyān || [4*] Marichir-udagāt=tasmād=uday-ādrêr=iv=āmśumān [1*]
tataḥ Kaśyapa ētasmāt
- 5 prakāśa iva nirggataḥ || [5*] Tasmāj=jaga[t*]-tritaya-maṅgala-ratnadīpaś=chhandas-
tanus=timira-kānana-dāva-vahnîḥ [1*] dik-kālayôḥ kim=aparam vyavahāra-hêtuh
kô=py=āvirāsa vasudhādhipa-varṇsa-kandah || [6*] Asmā-
- 6 d=idam prathama-sambhṛita-rāja-sabdah pūrnô guṇair=nnikhila-nīti-patha-prayôktā
[1*] dēvô Manus=sapadi gôptum=iv=āvatīrṇas=tan-maṇḍal-antara-gataḥ purushah
purāṇah || [7*] Tasy=ānvayê Raghur=abhū-

¹ *South-Ind. Inscr.* Vol. II. p. 341. This and the following two references were kindly communicated to me by Prof. Kielhorn from his forthcoming *List of Inscriptions of Southern India*.

² Above, Vol. V. p. 123, note. I assume that Agraṇipidugu stands for Agraṇipidugu.

³ *South-Ind. Inscr.* Vol. I. p. 87 ff.

⁴ See verse 14 of the Piṭhāpuram pillar inscription of Prithivīvara and Dr. Hultzsch's note on that passage, above, Vol. IV. p. 49. In this verse Malla II. Piḍuvarāḍitya is described as *nija-khadga-khāḍita-mahôchāḍ-dīsoniḥ*, 'he who broke by his own sword very fierce thunderbolts,' which almost looks like an imitation of the passage from the *Uttararāmacharita* cited above.—[Compare also Viḍēlviḍugu, 'the crashing thunderbolt,' in *South-Ind. Inscr.* Vol. III. p. 93.—E. H.]

⁵ [See above, Vol. V. p. 106 and note 5.—E. H.]

⁶ From inked estampages supplied by Dr. Hultzsch.

- 7 t Surabhêḥ payôbbhir=yyaḥ pôshitaḥ prakṛiti-kāraṇatām upêtaiḥ [1*] āharttur=
addhvaram=amushya¹ kim=atra chitraṁ sarvasva-dānam=api viśva-diśām
vijêtuh || [8*] Ath=ābhavat Pañktirathas=tad-anvayê bhuj-âpadâ-
8 nêna chirāya raksh[i]tâ [1*] adānavâ yêna krit=Âmarâvatī sa-dāna-vâ[h*]² svairam=
iyañ=cha mēdinî || [9*] Tasmād=utbha(dḥbha)vati sma vikrama-dhanô Rām-
ābhidhānô Harir=yyas=samkh[y*]³ê vinihatya rākshasa-patiṁ svar-gga-
9 rva-sarvvaṅkasham [1*] dēvīm svām śasinaḥ kṛisām=iva kalām=arkkam
praviśy=ānalam śuddhim prāpya vinirggatām punar=api svīkritya yātaḥ
purīm || [10*] Babbhūvur=ullāsita-kīrtti-nirjīharâ Raghôḥ kulô=smin bahavaḥ
10 kshamābhṛitaḥ [1*] divas-prithivyôr=api yair=nniyanṭṛibhir=nnirāṅkuśô nīti-pathaḥ
pravarttitaḥ || [11*] Tasmin kulê samabhavat Kalikāla-Chôlô vīraḥ Kavēra-
tanayān=tatīnīm vidhātâ [1*] yat-kêḷi-yashtī-
11 parighattita-mātra ēva Mēruś=chalan=vyatikaram haritān=chakāra || [12*] Jātô=sya
vāmśē Madhurām vijitya paśchād=udañchan-Madhurāntak-ākhyāḥ [1*] nitānta-
mukt-ābharaṇāḥ prachandaḥ Pāṇdy-āṅganāḥ prāg=iva ya-
12 ś=chakāra || [13*] Jishnur=Andhrēshu yaḥ kṛitvā purīm Pottappi-samjñitām [1*]
tatas=tat-pūrvva-Chôl-ākhyāḥ prakhyāta-bhujā-vikramaḥ || [14*] Tasmin kulê
samudapadyata Betta-nāmā yaś=Śakra-³chôdita-gatêr=a[śa]-
13 nêḥ praharttâ [1*] prāg=ēva yady=aradagamishyad=⁴ushatbu(dḥbu)dh-ārochih
paksha-kshayaḥ kshītībhṛitām=api n=ābhavishyat || [15*] Tad=vāmśē sa
Tilumgabijja-nṛipatir=yyên=Ôjjapuryyām=asau chañchat-
14 kīrtti-patākayâ tilakita-stambhaḥ pratishṭhāpitaḥ [1*] yasy=āgrê Garuḍan=nirīkshya
sahaja-snêhēna sūtê sthitê maddhyê-vyôma vīlambatê dinapatīḥ prāyas=tad-ādi
kshaṇam || [16*] Tat-ku-
15 lē⁵ Siddhi-bhūpālāḥ pālayām=āsa mēdinīm [1*] yadiya-dôḥ-pad-āyattam=artthi-
pratyarthi-jīvitam || [17*] Anujanm=ābhavat=tasya Betta-bhūpāḥ pratāpavān [1*]
tasy=āpi jajūirê putrās=trātāras=śaraṇ-ārtthi-
16 nām || [18*] Dāyabhimô nṛipas=têshān=jyêshṭhaḥ kshôṇīm=apālayat [1*] yat-
pāpīs=sātrava-śrīpām kēś-ākṛishtī-kashāyitaḥ || [19*] Asy=ānujas=sahaja-jitvara-
satva(ttva)-rāsīs=sātru-kshītīśvara-yaśas=śisīrāmśu-rāhuḥ [1*]
17 śrī-Nallasiddhi-nṛipatir=yyam=upētya kāntan=dig=dakṣiṇâ galita-kāñchi-guṇâ
babhūva || [20*] Tasy=Aīrasiddhi-nṛipatis=sahajaḥ kañyān=dūran=nirasya kalim=
asya punaḥ-pravêsam [1*] rôddhum pravṛitta iva yaḥ prachuram ya-
18 śa[h*] svan=dik-sīmasu sphaṭika-sāla-nibham babanddha⁶ || [21*] Asy=ābhavann=
avani-maṇḍala-rakshītāraḥ putrās=traya[h*] sphurita-paurusha-bh-ūshapās=tê [1*]
yair=anvitaḥ prasavitâ suchiram vyarājat=têjōmayair=iva nijai-
19 r=nnayanais=Triṇêtraḥ || [22*] Jyāyām=ēshām=Manmasiddh-īśvaraḥ kshamām
kshār-āmbhōdhi-śyāma-sīmām śasāsa [1*] nity-ôdañchad-yad-yaśaḥ-pañjar-āntar-
vvyôma dḍhyāmām kōkilatvam bibharti || [23*] Tan-maddhyamas=tad=anu
Betta-nṛip-ābhīdhāna-
20 ś=sāntas=tapôbbhir=avadhīrita-bhōga-vāñchhaḥ [1*] jyêshṭhê gatê divam=anākulam=ēva
rājyan=nikshiptavān=api kañyasi Tammusiddhau || [24*] Jayati vipula-
bhūbhṛid-vamśa-janmā suvṛittaḥ parichita-guṇa-gumpha-

¹ The m of *mu* has a peculiar form; it looks as if it had not been finished by the engraver.

² The length of the *ā* of *sadda* is expressed by two signs.

³ The *akshara* *ka* looks like *ta*, but apparently only owing to a fissure in the stone.

⁴ Read *aradagamishyad*.

⁵ The sign for *ś* stands at the end of the preceding line.

⁶ Read *babanddha*.

- 21 s=sambhavan-nāyaka-śrīḥ [*] suchiram=avani-bhūśā Tammusiddh-ābhidhānas-
sarasa-madhura-mūrttiś=chētanah kō=pi hārah || [25*] Yaśaś=śubhram yasya
śravaya-subhagam sarasadi muhus=Sahasrākshaś=śrinvan-madhura-vachasaḥ kinna-
22 ra-mukhāt [*] sva-chakshus-saṁkhyāka-śruti-vibhava-kautūhala-vaśāt kalatrāya
prāya[h*] śprīhayati punar=Ggantama-munēḥ || [26*] Daḥita-ripu-karindra-śrēṇi-
vistīrṇa-kumbha-sthala-vigalita-śumbhan-mauktika-vyāpta-
23 mūrttiḥ [*] jayati ghaṭita-lakshmīḥ kshira-vās-chūṛṇa-kīṛṇaḥ puruṣa iya
purāṇa[h*] śyāmaḥ yat-kṛpāṇaḥ || [27*] Sa Śrīdēvyām=Ērasiddhi-kshītīśāj-
jāta[h*] śrīmān=Manmasiddh-ānujanmā [*] dhātrīn=ētān=trāyamāṇas=sa-
24 mastām=ast-ārātis=Tammusiddhi-kshamāpāḥ || [28*] Dēvāy=Ādhipurīśāya Śak-
ābdē dhīrayāyini [*] grāmēśhv=asya nṛpa-grāhyam prādād=āyam=aśēshataḥ
|| [29*] Yatnēna dharmma-sarapīḥ parirakshaṇīyā s=ēya-
25 m bhavatbhi(dhbi)r=akhilair=iti Tammusiddhaḥ [*] āgāminah prapayātē
nṛpatīn=ajasran=dūran=natēna śirasā na śarāsanēna || [30*] ८ || Ētat
kshōṇibhṛitām=amśu-jaṭālair=mmakutair=ddhṛitam [*] jaga[t*]-
26 traya-prasiddhasya Tammusiddhasya śāsanam || [31*]

TRANSLATION.¹

(Verse 8.) In his (*i.e.* Mann's) family was Raghu who was fed by the milk of Surabhi which had become the cause of procreation. Is it surprising, under these circumstances, that he should have performed a sacrifice at which (*his*) whole property was given away, (*and*) that he should have conquered also all the quarters?²

(V. 9.) Then there was in his family Pañktiratha,³ who, by the exploits of (*his*) arm protecting for a long time (*both*) Amarāvati and this earth, kept, of his own accord, (*the one*) free from demons (*and the other sprinkled*) with the water of donations.

(V. 10.) From him was born, under the name of Rāma, Hari full of valour,⁴ who, having killed in battle the lord of the Rākshasas who was injuring all (*beings*) through (*his*) arrogance (*awakened by the conquest*) of (*Indra's*) heaven,⁵ took back his queen, after she had emerged in purity from the fire which she had entered, as the narrow digit of the moon (*emerges again in old splendour*) from the sun after it has entered it,⁶ and went to (*his*) capital.

(V. 12.) In this family was born Kalikāla-Chōḷa, the hero who supplied with banks the daughter of Kāvēra,⁷ When (*Mount*) Mēru had been merely touched by his play-staff, it began to shake and (*thereby*) caused a confusion among the quarters.

(V. 15.) In this family was born (*a king*) called Betta, who was the crusher of the thunder-bolt whose flight was impelled by Śakra;⁸ if he with his fiery splendour had risen before, the cutting of the wings of the mountains also would not have taken place.

¹ Only the verses which are not found in the Tiruvālaṅgāḍu and Tiruppāsūr inscriptions have been translated here. Verse 29 also has been omitted, because, apart from the name of the god, it is identical with verse 21 of the Tiruvālaṅgāḍu inscription.

² According to the *Raghuvamśa* (II. 69 ff.) Raghu was conceived by Sudakṣiṇā, after her husband Dilīpa had drunk from the milk of the cow Nandini, the daughter of Surabhi, and not of Surabhi herself as implied by the verse of the inscription. Raghu's *digvijaya* and his performance of the Viśvajit sacrifice are narrated in the fourth *sarga* of the *Raghuvamśa*; compare with our verse especially IV. 86 :— *sa Viśvajitam dīkṛt yajñam sarvasa-dakṣiṇam*.

³ *i.e.* Daśaratha.

⁴ The term *vīkrama* is used with reference also to the three strides of Viṣṇu.

⁵ Rāvaṇa's conquest of Indra's heaven is told in the *Rāmāyaṇa*, VII. 27 ff.

⁶ According to the *Purāṇas*, the moon, when reduced by the draughts of the gods, enters the orbit of the sun and is replenished by it; see *e.g.* *Viṣṇupurāṇa* II. 12, 4 ff.

⁷ *i.e.* the Kāvērī; see above, Vol. VI. p. 132, note 5.

⁸ Or 'of Aśani Śakrachōditagati.' Regarding this verse see my remarks above, p. 148 f.

(V. 26.) When the thousand-eyed (Indra) in (*his*) court constantly hears of his (*i.e.* Tammusiddhi's) brilliant fame, pleasant to the ear, from the sweet-voiced mouth of the *Kinnaras*, I am sure, he will covet again the wife of the sage Gautama¹ out of desire for the development of ears equal in number to his eyes.²

(V. 27.) Victorious is his sword, which is decked with shining pearls that have dropped from the cleft large frontal globes of the numerous princely elephants of (*his*) enemies, (*and*) which resembles the primeval spirit (*Vishnu*), because it is dark-blue (*and*) covered with dust as (*Vishnu* is sprinkled) with the water of the milk-ocean, (*and*) because it has established (*his*) royal power (*as Vishnu* is united with *Lakshmi*).

B.—ARULALA-PERUMAL INSCRIPTION OF SAKA-SAMVAT 1127.

This inscription, which I edit from inked estampages supplied to me by Dr. Hultzsch, is engraved at the base of the north wall of the stone platform called 'the mountain' (*malai*) in the Arulāḷa-Perumāḷ temple at Conjeeveram.³

It is written in Grantha characters which vary in height from $\frac{1}{3}$ " to $1\frac{3}{4}$ ". Up to line 15, medial *ai* is expressed in the usual manner by putting the two spirals side by side; see *tasmai* (l. 1), *saṁya* (l. 1), *gunair* (l. 7), *sambhavair* (l. 8), *kirttyai* (l. 9), *svairam* (l. 10), *yair* (l. 12). But in the second half of the inscription the two signs are put one above the other; see *asy*=*Aṅgasiḍḍhi*- (l. 16), *yair* (l. 17), *tējōmayair* (l. 17), *nijair*=*niyānair* (l. 17), *-āsmāi* *Hastisailēśvarāya* (l. 20), *akḥilair* (l. 20), *jaṭāḷair*=*mamakūṭair* (l. 21). The language is Sanskrit, and, with the exception of a short passage in ll. 19 and 20, the whole text is in verse. The spelling of the words *patma* (ll. 1, 3, 4), *Vālmikivāt bhānu-* (l. 9), *abhūt bhuj-āpadānēna* (l. 9), *uibhavati* (l. 10), *ushatbudha*⁴ (l. 15), *sphāyat-bhāmnē* (l. 20), *prādāt grāmam* (l. 20), *bhavatbhir* (l. 20) is in agreement with the practice followed in similar Grantha inscriptions. The group *ddh* is written *dhḍh* in *Aṅgasiḍḍhi* and *rōḍḍhum* in line 16.

This is another record of king Tammusiddhi. It enriches our knowledge by incidentally mentioning the surname of Tammusiddhi's father, *Āṅgasiḍḍhi*, and the time and place of Tammusiddhi's inauguration. This information is found in l. 19 f. where it is recorded that in the Śaka year 1127 (=A.D. 1205-6) king Tammusiddhi, the son of Gaṇḍagōpāla and Śrīdēvī, the younger brother of the great king Maṇmasiddhi, having performed his anointment in the town of Nellūr, presented the village of Muṭṭiyampākka, the head-quarters of Paṇṭarāshṭra, to the god, the lord of Hastisaila. Nellūr is the modern Nellore, the chief town of the district of that name. Muṭṭiyampākka and the district of Paṇṭarāshṭra I am unable to identify. The temple of the lord of Hastisaila, *i.e.* 'the elephant mountain,' is the Arulāḷa-Perumāḷ temple⁵ where the inscription is engraved.

Except these data, the inscription contains nothing of historical value which is not known to us from the previously published records of Tammusiddhi, the four verses (4, 8, 9, 12) which here appear for the first time being merely eulogies of the king's mythical ancestors: Brahman, Sagara, Bhagīratha and Kuśa. Perhaps it is worth mentioning that Tiluṅgavidya and Nallasiddhi are omitted in the genealogy, and that the name Betta is here constantly spelt Vetta (vv. 17, 19, 24).

¹ *I.e.* Ahalyā, whom Indra tried to seduce. When Gautama became aware of his intention, he cursed the god, in consequence of which Indra's body was covered with a thousand eyes.

² The idea which forms the theme of this verse is rather far-fetched. Indra, being eager to listen to Tammusiddhi's praise, wants to have a thousand ears. He therefore looks again for Gautama's wife, hoping that by a new curse of the sage he will get as many ears as he has got eyes.

³ No. 35 of the Government Epigraphist's collection for the year 1893.

⁴ With respect to this word I refer to my remarks above, p. 148.

⁵ [Compare above, Vol. III. p. 71, and Vol. IV. p. 145.—E. H.]

TEXT.¹

- 1 Svasti śrī-Tammusiddhāya tasmai yat-sainya-rēpavaḥ [*] Brahma-patma(dma)-
spriśās=śaṅkē bhāvi-bhū-spriṣṭi-hētavaḥ [|| 1*] Jayati vijayi-chāpāḥ kṣhālīt-
āśēśha-
- 2 pāpas=satata-madhura-lāpāḥ prāpta-vidyā-kalāpāḥ [*] vitata-vitarap-āpas=śatru-māyā-
durāpāḥ praśamita-kali-tāpas=Tammusiddhi-kṣhamāpāḥ [|| 2*] Udadhi-śaya[na]-
bhājāḥ
- 3 [Pa]tma(dma)nābhāsyā nābhēḥ kim=api nikhila-hētur=jjātam=āścharyya-patma(dma)n
[*] yad=abhajād=api spriṣṭēḥ pūrvvam=ētasya dṛigbhyām=mrīdu-kāṭhina-
mahōbhyām=mīlan-ōnmīlanāni [||] [3*] Tasmād=ā-
- 4 virabhūch=charāchara-ja[ga]n-nirmāṇa-nirvāṇakas=tasy=āntas=chira-vāsa-sambhṛita-rajō
vṛttis=sa Patmā(dmā)śanaḥ [*] yēna Śrīpati-talpa-pannaga-phauṇa-ratnēśhṭha-
bimba-spriśā sraṣṭā-
- 5 rō bahavas=sahāya-vidha[y]ē sampādyamānā iva [|| 4*] Marīchir=udagāt=tasmād=
uday-ādrēr=iv=āmśumān [*] tataḥ Kaśyapa ētasmāt prakāśa iva nirgataḥ
[|| 5*] Tasmāj=jagat-tritaya-mamga-
- 6 la-ratna-dīpas=chandas-tanus=timira-kānana-dāva-vahniḥ [*] dik-kālayōḥ kim=aparam
vyavahāra-lētup kō=py=āvirāsa vasudhādhipa-vamśa-kandaḥ [|| 6*] Tasmād=idam
prathama-sambhṛita-rāja-
- 7 śabdaḥ pūrṇō gupair=akhila-nīti-patha-prayōktā [*] dēvō Manus=sapadi gōptum=
iv=āvatīrṇas=tan-maṇḍal-āntara-gataḥ puruṣaḥ purāṇaḥ [|| 7*] Ath=ānvayē
tasya
- 8 babhūva rakṣitā kṣhitēr=udāras=Sagarō narēśvaraḥ [*] chakāra yas=sāgaram=
ātma-sambhavaiv=yā[śas]-sama[ṣṭ]ēr=nnirapāyam=āśrayam [|| 8*] Bhagīrathas=tatra
babhūva divyām Sarasvatīm yaḥ kṣhi-
- 9 tim=ānināya [*] Vālmīkivat(vad) bhānu-kulasya kīrttyai sampādayitrīm² kavi-
kautukāni [||] [9*] Tad-anvayē Paṅktirataḥ kramād=abhūt(bhūd) bhuj-āpadānēna
chirāya rakṣ[i]tā [*] adānavā yēna kṛit=Āmarāva-
- 10 tī sa-dāna-vā[h*] svairam=iyāñ=cha mēdini [||] [10*] Tasmād=utbha(dbha)vati sma
vikrama-dhanō Rām-ābhīdhānō Harir=yyas=samkḥ[y*]ē vinihatya rākṣhasa-patiṁ
svar-ggarvva-sarvvamkasham [*] dēvīm sv-
- 11 ān śāśinaḥ kṛiśām=iva kalām=arkkam praviśy=ānalām śuddhim prāpya
vinirggaṭām punar=api svikṛitya yātaḥ purīm [||11*] Abhūt sutas=tasya Kuś-
ābhīdh[ā*]nō rājñāḥ kara-sparśam=avāpya ya-
- 12 sya [*] Kumudva[tī] sā sarasaḥ prarūdhā vikasvar-āngi suchira[n=na]nanda [||
[12*] Babhūvur=ullāsiti(ta)-kīrtti-nirjjharā Raghōḥ kulē=smin babavaḥ
kṣhamābhṛitaḥ [*] divas-prithivyōr=api yair=nniyantri-
- 13 bhi[r=nni]ramkuśō nīti-pathaḥ pravarttitaḥ [||] [13*] Tat-kulē Kalikālō=bhūt
Kāvērī-tīra-kṛin=nrīpāḥ [*] yat-kēli-yashṭi-tulitē Mērau vyatikṛitā disaḥ [|| 14*]
Jātō=sya va[m]śē Madhurā[m] vijitya paśchād=udañchan-Ma-
- 14 dhurāntak-ākhyāḥ [*] [ni]tānta-mukt-ābharanāḥ prachandaḥ Pāṇḍy-āṅganāḥ
prāg=iva yās=chakāra [|| 15*] Jishṇur=Andhrēshu yaḥ kṛitvā purīm Pottappi-
samjñitām [*] tatas=tat-pūrvva-Chōl-ākhyāḥ prakhyāta-bhujā-vikramaḥ [|| 16*]
- 15 Tasmin kulē samudapadyata Vetta-nāmā yaś=Śakra-chōdita-gatēr=aśanēḥ praharttā
[*] prāg=ēva yady=udagam[i]shyad=ushatbu(dbu)dh-ārchchi[h] paksha-kshayaḥ
kṣhitibhṛitām=api n=ābhavishyat [||] [17*] Tad=va[m]śē Siddhi-bhūpālāḥ pālayām=ā-

¹ From inked estampages supplied by Dr. Hultsch.² The syllable *mpd* has been added below the line.

- 16 sa médinâm [*] yadīya-dôḥ-pad-āyattam=artthi-pratyartthi-jīvitam || 18*] Anujanm=ābhavat=tasya Vetta-bhūpaḥ pratāpavān [*] tasy=āpi jajñirē putrās=trātāras=śarap-ārtthinām || 19*] Dāyabhimō nripas=tēshā[m] jyēsthah kshōṇim=apālayat [*] yat-pāp[i]ś=sātrava-śr[i]nām kēs-ākṛishṭi-kashāyitaḥ || 20*] Asy=Aīrasiddhi(ddhi)-nripat[i]s=sahajaḥ kaṇiyan=dūran=nirasya kal[i]m=asya punaḥ-pravēśam [*] rōdhdu(ddhu)m pravṛitta iḥ yaḥ prachuraṁ yaśa[h*] svan=d[i]k-sīmasu sphaṭika-sāla-nibham babandha || 21*]
- 17 Asy=ābhavann=avani-maṇḍala-ra[kshi]tāra[h pu]trā[s=traya][h*] sphuri[ta]-pauruṣa-bhū[sha]nās=tē [*] yair=anvitaḥ prasavitā suchiraṁ vyarājat=tējōmayair=iva nijair=nnayanais=Triṇētraḥ || 22*] Jyāyān=ēshām=Manmasiddh-iśvaraḥ kshāmāḥ kshārāmbhōdhi-śyāma-sīmāḥ śāsāsa [*] nity-ōdañchad-yad-yaśaḥ-paūjar-āntar=vyōma ddhyamāḥ kōkilatvam bibharti || 23*] Tan-madhyamas=tad=anu Vetta-nrip-ābhichānās=sāntas=tapōbhir=avadhīrita-bhōga-vāñchah [*]
- 18 jyēsthē gatē divam=anākulam=ēva rājyan=nikshiptavān=api kaṇiyasi Tammusiddhau || 24*] Jayati vipula-bhūbhṛid-va[m]śa-janmā suvṛittaḥ parichita-guṇa-guṇphaḥ=sambhava[n*]-nāyaka-śrīḥ [*] suchiram=avani-bhūshā Tammusiddh-ābhichānās=sarasa-madhura-mūrttiś=chētana[h*] kō=pi h[āraḥ] || 25*] [Ya]śās=śubhram yasya śravaṇa-subhagaṁ saṁsadi muḥus=Sahasrākshaś=śrīvan=madhura-vachasaḥ kinnara-mukhāt [*] sva-chakshus-samkhyāka-
- 19 śruti-vibhava-kautūhala-vaśāt kaṭatrāya prāya[h*] sprihayati punar=Ggautama-munēḥ || 26*] Daṇṭa-ripu-karīndra-śrēṇi-vistira[n]a-kumbha-sthala-vigaṇita-śumbhan-mauktika-vyāpta-mūrttiḥ [*] jayati ghaṭita-lakshmiḥ kshīra-vās-chūṛṇa-kṛṇaḥ puru[sha iḥ] pu[rāṇa][h*] śyāmaḥ yat-kṛipāḥ || 27*] Sa khalu samasta-sāmrājya Nallūr-nagarē kṛit-ābhishēka[h*] śrī-Gaṇḍagōpāla-Śrī-
- 20 dēvi-vīra-sūtir=Mmanmasiddhi-mahārāj-ānujanmā Tammusiddhi-mahāpālāḥ pālāya[nn=a]khilāni=arṇav-āmbarām [*] Dēvāy=āsmā Hast[i]śailēśvarāya sphāyat(yad)-bhūmnē sāravō[gyē Śa]k-ā[bd]ē [*] . . . ddhim³ Paṇṭa-rāshṭra-pradhānam prādāt(dād) grāmam=Muṭṭiyampāka-samjñam || 28*] Yatnēna dharmma-saraṇiḥ parirakshaḥ[i]yā s=ēyam bhavat(vad)bhir=akhilair=iti Tammusiddhaḥ [*] āgāmināḥ prapayātē nripatīn=ajasran=dūran=natēna śira-
- 21 sā na sārāsanaḥ || 29*] Ēta[t] kshōṇibhṛitām=amśu-jatālair=mmakutair=ddhritam [*] jaga[t*]-traya-prasiddhasya Tammusiddhasya śāsanam || 30*]

TRANSLATION.⁴

(Verse 4.) From this (*lotus*) arose that Padmāsana,⁵ who, having accumulated the power of *rajas*, because he had dwelt long in its interior,⁶ accomplished the creation of the animate and inanimate world, (*and*) who, in order to create companions, seemed to produce many creators, when he touched the images reflected in the jewels of the hoods of the snake (*which formed*) the couch of the husband of Śrī.⁷

(V. 8.) Then there was in his (*i.e.* Mann's) family an illustrious ruler of the earth, king Sagara, who by his own sons made the ocean an everlasting receptacle of the aggregate of (*his*) fame.

(V. 9.) In this (*family*) was Bhagīratha, who led to the earth the heavenly Sarasvatī⁸ that produced wonders of poets like Vālmiki for the glorification of the solar race.

¹ The *la* has been added below the line.

² The *visarga* has been added below the line.

³ Three *akṣaras* before *ddhim* are illegible.

⁴ The translation comprises only those verses which are not found in the inscriptions of Tammusiddhi published until now.

⁵ *I.e.* Brahman.

⁶ See above, p. 124, note 5.

⁷ *I.e.* Vishṇu.

⁸ *I.e.* the Gaṅgā, and, at the same time, the goddess of eloquence.

(V. 12.) His (*i.e.* Râma's) son was he who bore the name of Kuśa. Having obtained the touch of the hand of this king, that Kumudvatî, who had emerged from the tank, expanding her body, enjoyed pleasures for a very long time.¹

(Line 19.) Now, this king Tammusiddhi, the heroic offspring of the glorious Gaṇḍa-gôpâla and Śrīdēvi, the younger brother of the great king Manmasiddhi, having performed his anointment to universal sovereignty in the town of Nellûr, while protecting the whole (*earth*) girt with the oceans,—

(V. 28.) Presented, in the Śaka year (*denoted by the chronogram*) Sârayôgya (*i.e.* 1127), the village called Muṭṭiyampâkka, . . . the head-quarters of Paṇṭarâshṭra, to this god, the lord of Hastîśaila, whose wealth is increasing.

No. 22.—MADHUBAN PLATE OF HARSHA;

THE YEAR 25.

By F. KIELHORN, PH.D., D. LITT., LL.D., C.I.E.; GÖTTINGEN.

This plate was discovered, in January 1888, in a field near the village of Madhuban² in the pargana Nathûpûr of the tahsil Sagrî, in the Azamgarh district of the Benares division of the United Provinces, and is now in the Provincial Museum of Lucknow. The inscription which it contains has been already edited, by the late Professor Bühler,³ in *Ep. Ind.* Vol. I. p. 67 ff. As it is desirable to issue a facsimile of the plate, I re-edit the inscription from impressions that were furnished to Dr. Hultzsch by the late Mr. E. W. Smith.

This is a single copper-plate, about 1' 8" broad by 1' $\frac{3}{4}$ " high, and inscribed on one side only. Judging from the impressions, a seal was soldered on to the middle of the proper right side of the plate, just as is the case with the Banskhêra plate of Harsha and the three plates of the *Mahârâjas* of Mahôdaya,⁴ but it must have got detached from the plate⁵ and has not been discovered. In the upper part and on the proper left side the plate has suffered somewhat from corrosion, but the writing throughout is so deeply engraved that on the back of the impressions every letter of the 18 lines which the plate contains may be read with absolute certainty. The size of the letters is about $\frac{5}{16}$ ". The characters belong to the north-western class of alphabets;⁶ in general, they closely resemble those given (from the Lakkhâ Maṇḍal inscription, *North. Inscr.* No. 600) in columns xv. and xvi. of Table IV. of Professor Bühler's *Ind. Palæographie*. Of initial vowels the text only contains *a* (*e.g.* in *anayôr=*, l. 15); *i* (*e.g.* in *iva*, l. 6), the form of which, employed here, in Professor Bühler's Table occurs only in much later inscriptions; *u* (in

¹ The words used of Kumudvatî are selected with reference to the original meaning of that name. Kumudvatî is likened to a group of lotuses (*kumudvatî*) growing in a pond (*sarasaḥ prarūḍhā*), which open their blossoms (*vikasav-āṅgā*) when touched by the beams (*kara-sparśam avāpya*) of the moon. The marriage of Kuśa and Kumudvatî, the sister of the serpent Kumuda, is told in the sixteenth *sarga* of the *Raghuvamśa*.

² According to Dr. Führer, *Monumental Antiquities and Inscriptions in the N.-W. Provinces and Oudh*, p. 189, where the above information is given, the village of Madhuban is 32 miles north-east of Azamgarh; but I have not found the name in the *Indian Atlas*, sheet No. 108.

³ Some of the errors which Prof. Bühler's text contains were corrected by him, when editing the Banskhêra plate of Harsha, above, Vol. IV. p. 208 ff.

⁴ See above, Vol. IV. p. 208, and Vol. V. p. 208.

⁵ Compare the Sômpat seal of Harshavardhana, *Gupta Inscr.* p. 281, and Plate.

⁶ The apparently more antique manner in which essentially the same alphabet was written in Eastern India may be seen from the plates of the time of Śaśāṅkarâja (above, Vol. VI. p. 144, Plate) which are only about ten years older than this Madhuban plate.

utkhāya, l. 7); and *ē* (in *ēkachakkra*°, l. 3). Of the consonants, *gh*, *ḍh* and *b* do not occur; and *chh*, *jh*, *ñ* and *ṭh* are only found as subscript letters, e.g. in *tach=chhāsanaṃ*, l. 10, *ujjhātavin*, l. 7, *ājñā*, l. 15, and *jyāsthā*, l. 13. Regarding the other signs it may be noted that five of them—*k*, *g*, *ḍ*, *r* and *ś*—when they have no subscript letters, have a small hook at the bottom (see e.g. *bhāgākara*, l. 15, *taḍit*, l. 16, and *samādēśāch*, l. 18); and attention may also be drawn to the forms of *k* (e.g. in *kara*, l. 15), *ñ* (e.g. in *sōdraṅgaḥ*, l. 11), *ch* (e.g. in *chamchalāyāḥ*, l. 16), *t* (e.g. in *paṭalā*°, l. 17), *d* (e.g. in *dānaṃ*, l. 16), *ph* (in *phalaṃ*, l. 16), and *v* (e.g. in *Śivadēva*°, l. 14). The superscript sign for *r* is sometimes written above, and sometimes on, the line; *y*, where it follows upon another consonant, is always denoted by the secondary, subscript form, even in the conjunct *ry* (e.g. in *paryantaḥ*, l. 11). The ordinary form of the subscript *ṭh* may be seen from the *sthā* of *rājasthānīya*, l. 9; the same form is used in the conjunct *rṭh*, in *samprīṭārthi*, l. 5, but the full form of *ṭhā* is exceptionally employed in the *sthā* of *śrō-pasthānaṃ*, l. 15. The subscript form of *n* does not differ from the sign for *na*; see e.g. *Sāvarṇi*, l. 13, and *Vishnavriḍha*, l. 14. Apparently in order to distinguish clearly between the subscript *dh* and *v*, the latter is denoted by a peculiar triangular sign; compare e.g. the *ddh* of *bhivriḍhayā*, l. 13, with the *tv* of *āgruhāratvēna*, l. 14. The only final consonant which occurs is the *t* of the word *samvat* in line 18; it is denoted by the lower part of the sign for *ta*, with a separate horizontal line above it.—As regards medial vowels, only the signs for *ā*, *u* and *ī* call for remarks. The ordinary sign for *ā* (and for the *ā* of *jā*) may be seen e.g. in *mahārājādhi-rāja*, l. 12. When *ā* follows upon *ñ*, *t* or *n*, or a conjunct beginning with one of these consonants, it is denoted by a wavy line placed vertically above the sign for *ñ*, *t* or *n*; see e.g. *bhāñktvā*, l. 10, *Uhaṭṭāraka*, l. 13, and *°karaṇādhi*, at the end of line 17. In the same way *ī* is denoted in the *khyā* of *samākhyaṭam*, l. 17 (compare with it the *khi* of *vimukhāḥ*, l. 7), and in the *jñā* at the commencement of line 10 (compare with it the *jñā* of *ājñā*, l. 15).¹ Excepting in the syllable *ru* (for which see *Varuṇ*, l. 5), the vowel *u* is either denoted by a subscript vertical line—or prolongation of the vertical line of the consonant-sign—ending with a small hook, or by a sign which resembles the subscript *u* of the modern Nāgarī alphabet. The former way of denoting *u* is followed in writing the *aksharas* *chokhu*, *shṇu*, *du*, *nu*, *pu*, *mu*, *yu*, *vu*, *du* and *su*, the latter in *ku*, *tku*, *gu*, *tu*, *śtu* and *bhu*; compare *vichchurita*, l. 4, *dushṭa*, l. 6, *samuchita*, l. 15, and *tulya*, l. 15, *Skandaguptaḥ*, l. 17, etc. For two ways of writing the medial *ī*—the one followed only in *dī*, and the other in *kī*, *pī* and *bhī*—compare *dūtakā*, l. 17, and *kāṭa*, l. 10.—The inscription does not contain the signs of the *jihvāmālīya*, *upadhmanīya* and *avagraha*; but in line 18 it has three numerical symbols, for 20, 5 and 6. The symbol for 20 is like the *akshara* *tha*; that for 5 looks like *tri*, with the sign of the medial *ā* attached to it; and the symbol for 6 resembles the *akshara* *dā* with a subscript *u*. Signs of punctuation are used in the text three times, in lines 16 and 17. Throughout the writer has formed the letters with great care and skill.—The language of the inscription is Sanskrit.² Any unusual or rare words and technical terms which it contains will be drawn attention to in the notes on the translation. The text generally is in prose, but it contains a verse in lines 6 and 7, and two benedictive and imprecatory verses—in one of which the king Harsha himself is referred to as an authority for the sentiment expressed—in lines 16 and 17. In respect of orthography it need only be stated that the sign for *v* denotes both *v* and *b*, that *k* and *t* are generally doubled before *r* (e.g. in *puttras*, l. 1, and *ātīkhrānta*, l. 3, but not in *-pravṛtta-chakra*, l. 3), and that now and then the rules of *sandhi* have not been observed.

The inscription is a charter of the well-known king Harsha—or Harshavardhana, the hero of Bāṇa's *Harshacharita*, who ruled part of Northern India at the commencement of the 7th

¹ In the Banskhera plate of Harsha the same superscript sign for *ā* is more frequently employed.

² According to Prof. Bühler the language of the Banskhera plate is better than that of this plate; but I cannot find any difference.

century A.D.—by which the village of **Sômakunḍakâ** in the **Kuṇḍadhâni** vishaya of the **Śrāvastī** bhukti, which had been previously held by a Brâhmaṇ on the strength of a forged charter, was granted to two other Brâhmaṇs. The king's order was issued from the royal residence or camp of **Kapitthikâ** (l. 1), and is dated on the 6th of the dark half of the month **Mârgaśīrsha** of the year 25 (apparently of the king's reign¹). The actual order is preceded by the genealogy of Harsha, in the course of which it is stated that his immediate predecessor, his elder brother **Râjyavardhana**, after defeating **Dêvagupta** and other kings, was treacherously slain in his enemy's quarters. On this event and on the genealogy generally it is now unnecessary to comment.

Of the localities mentioned in the inscription, **Kapitthikâ** apparently is the Kie-pi-tha (**Kapittha**) of Hiuen-Tsiang,² which, again, is the same as **Sâmkâśya**, identified by the late Sir A. Cunningham³ with the modern Sankisa,⁴ on the **Kâlnadī** river, about 40 miles north-west of Kanauj. And **Śrāvastī**, after which the **Śrāvastī**-bhukti was called, is the modern **Sahet-Mahet**⁵ in the Gonda district of Oudh. **Kuṇḍadhâni**, from which the **Kuṇḍadhâni**-vishaya received its name, and the village of **Sômakunḍakâ** have not been identified.

TEXT.⁶

- 1 Om⁷ svasti [||*] Mahâ-nau-hasty-asva-jayaskandhâvânât=**Kapitthikâyâh**⁸ mahârâja-
śrî-Naravarddhanas=tasya puttras=tatpâdânudhyâtaḥ śrî-Vajripidêvyâm=utpannaḥ
paramâdityabhaktô
- 2 mahârâja-śrî-Râjyavarddhanas=tasya puttras=tatpâdânudhyâtaḥ śrî-⁹**Apsarôdêvyâm**=
utpannaḥ paramâdityabhaktô mahârâja-śrîmad-A(â)dityavarddhanas=tasya puttras=
tatpâdânudhyâtaḥ śrî-Mahâ-
- 3 **sênaguptadêvyâm**=utpannaḥ=¹⁰chatussamudr-âtikkrânta-kirttiḥ pratâp-ânurâg-ôpanat-
ânyarâjâ¹¹ varṇ-âśrama-vyavasthâpana-pravṛtta-chakra êkachakkraratha iva
prajânâm=ârtti-haraḥ
- 4 paramâdityabhaktaḥ paramabhaṭṭâraka-mahârâjâdhirâja-śrî-**Prabhâkaravarddhanas**=
tasya puttras=tatpâdânudhyâtaḥ sitayasâhpratâna-vichchhurita-sakalabhuvanamaṇḍalâḥ
parigrhîta-
- 5 **Dhanada**-Varuṇ-Êndia-prabhṛiti-lôkapâla-têjâḥ satpath-ôpârjhit-ânêka-dravina-bhûmi-
pradâna-samprîpit-ârthihridayô-tisayita-pûrvvarâja-charitô dêvyâm=amalayaśômatyâm
- 6 śrî-Yasômatyâm=utpannaḥ paramasaugataḥ Sugata iva parahit-aikarataḥ
paramabhaṭṭâraka-mahârâjâdhirâja-śrî-Râjyavarddhanâḥ Râjânô¹² yudhi dushṭa-vâjina
iva śrî-Dêvagupt-â-
- 7 dayaḥ kṛtvâ yēna kaśâprahâra-vimukhâḥ sarvvê samam samyatâḥ [||*] utkhâya
dvishatô vijitya vasudhâm kṛtvâ prajânâm priyam prânân=ujjhitavân=arâti-bhavanê
saty-ânurôdhēna yaḥ [||*] Tasy=ânuja-

¹ If the Harsha era dates from the commencement of Harsha's reign, the date must fall in A.D. 630-81.

² See Beal's *Si-yu-ki*, Vol. I. p. 202; compare also *Jour. Roy. As. Soc.* 1897, p. 421.

³ *Archæol. Survey of India*, Vol. I. p. 271.

⁴ See the *Imperial Gazetteer of India*, 2nd ed., Vol. XII. p. 223.

⁵ See *ibid.* p. 126. Compare also Dr. Bloch in *Jour. As. Soc. of Bengal*, Vol. LXVII. Part. I. pp. 289 and 290; to the inscriptions there enumerated as mentioning Śrāvastī may now be added the Lucknow Museum plate of Kirtipâla, above, p. 96, l. 12 of the text.

⁶ From impressions supplied by the Curator of the Provincial Museum, Lucknow.

⁷ Denoted by a symbol.

⁸ Here and in other places below the rules of *sandhi* have not been observed; read °kâdyâ.

⁹ Read sry-.

¹⁰ Originally °tpannaḥ and °chataḥ was engraved.

¹¹ Read °râjô.

¹² Metre: Śârdûlavikṛdita.


- 8 s=tatpādānudhyātāḥ paramamāhēśvarō Mahēśvara iva sarvvasat[^{t*}]v-ānukampi
paramabhaṭṭāraka-mahārājādhirāja-śrī-Harshaḥ Śrāvasti-bhuktau Kuṇḍadhāni-
vaishayika-Sōmakunḍakā-¹grāmē
- 9 samupagatām² mahāsāmanta-mahārāja-daussādhasādhanika-pramātāra-rājasthāniya-
kumārāmāty-ōparika-vishayapati-bhaṭa-chāṭa-sēvak-ādīn=prativāsi-janapadās=cha³ samā-
- 10 jñāpayaty=astu vaḥ samviditām⁴āyam Sōmakunḍakā-grāmō vrā(bra)hmaṇa-
Vamarathyēna kūṭa-sāsanaṇa bhuktaka iti vichārya yatas=tach=chhāsanaḥ
bhaṅktvā tasmād=ākshipya cha svasimā-
- 11 paryantaḥ s-ōdraṅgaḥ sarva-rājakulābhavya-pratyāya-samētaḥ sarva-parihṛita-
parihārō vishayād=uddhṛita-piṇḍaḥ⁵ putra-pautra-ānugaḥ⁶ chandrārkkakshita-
samakālīnō
- 12 bhūmichchhidra-nyāyēna mayā pituḥ paramabhaṭṭāraka-mahārājādhirāja-śrī-
Prabhākaravarddhanadēvasya mātuh paramabhaṭṭāraka-mahādēvī-rājñī-śrī-
Yasōmatidēvyāḥ⁷
- 13 jyēsthabhṛātri-paramabhaṭṭāraka-mahārājādhirāja-śrī-Rājyavarddhanadēvapādānām cha
puṇya-yaśō-bhividdhayē Śāvarṇpisagōttra-chchhandōgasavra(bra)hmachāri-bhaṭṭa-
Vārasvāmī-
- 14 Vishuvyūddhasagōttra-va(ba)hvirichasavra(bra)hmachāri-bhaṭṭa-Sivadēvasvā m i b h y ā m
pratigraha-dharmmaṇ⁸=āgrahāratvēna pratipāditāḥ⁹ viditvā bhavadbhiḥ samanū-
mantavyaḥ prati-
- 15 vāsi-janapadair=apy=ājñāsraṇa-vidhēyair=bhūtvā yathāsamuchita-tulyamēya
bhāgubhōgakara-hirany-ādi-pratyāyāḥ¹⁰ anayōr=ēv=ōpanēyāḥ sēv-ōpasthānam cha
karaṇīyam=ity-a-¹¹
- 16 pi cha || ¹²Asmat-kula-kkramam=udāram=udāharadbhir=anyais=cha dānam=idam=
abhyānumōdanīyam [¹³] lakshmyās=taḍit-salila-vndvuda-chamchalāyāḥ¹³ dānam
phalaṁ purayaśaḥ-paripālanam cha || Karmmaṇā¹⁴
- 17 manasā vāchā kartavyam prāpinē hitam [¹⁵] Harshēṇ=aita¹⁶ samākhyātām dharm-
ārjjanam=anuttamam || Dūtako=ttra mahāpramātāra-mahāsāmanta-śrī-Skanda-
guptaḥ [¹⁷] mahākshapaṭalādhikaraṇādhi-
- 18 kṛita-sāmanta-mahārāj-Ēśvaragupta-samādēśāch=ch=ōtkirṇam Garjjarōṇa¹⁸ [¹⁹]
Samvat¹⁷ 20 5 Mārggaśirsha-vadi 6 [²⁰];

TRANSLATION.

(Line 1.) Ōm. Hail!

From the great royal residence¹⁸ of victory, (*furnished*) with boats, elephants and horses—
from Kapitthikā:¹⁹—(There was) the Mahārāja Naravardhana.²⁰ Begotten on Vajripidevi, his son, who medi-
tated on his feet, (*was*) the devout worshipper of the Sun, the Mahārāja Rājyavardhana [I.].¹ Originally Sōmakunḍikā— was engraved, but the vowel i of the akshara ṇi has been struck out; see the name below, in line 10.² Read °gatān=.³ Read °paddmt=cha.⁴ Read samviditam=.⁵ The akshara du of vishayāduddhṛita is quite clear in the impressions.⁶ Read °nuga=.⁷ Read °dēvyā.⁸ Read °dharmmēṇ=; see my note on the translation.⁹ Read °tydyā.¹⁰ Metre: Vasantatilakā.¹¹ Metre: Ślōka (Anuṣṭubh).¹² The first akshara of this word is undoubtedly ga.¹³ Or 'from the great camp.'¹⁴ The sentence is continued below, in the words 'his younger brother . . .'¹⁵ In the original the names of the kings and queens— including the name Dēvagupta in line 6, but excluding the name Harsha in line 17— have the word śrī or śrīmāt, 'the illustrious' or 'glorious,' prefixed to them.

Harsha issues this command.



F. KIELHORN.

SCALE '43

FROM AN IMPRESSION SUPPLIED BY THE LATE E. W. SMITH.

W. GRIGGS, COLLOTYPE.

Begotten on *Apsarôdêvi*, his son, who meditated on his feet, (*was*) the devout worshipper of the Sun, the *Mahârāja Âdityavardhana*. Begotten on *Mahâsênaguptâdêvi*, his son, who meditated on his feet, (*was*) the devout worshipper of the Sun, the *Paramabhattachâraka Mahârâjâdhirâja Prabhâkaravardhana*, whose¹ fame crossed the four oceans; before whom other kings bowed down on account of his prowess and out of affection for him; who wielded his power for the due maintenance of the castes and orders of life, (*and*) who, like the sun,² relieved the distress of the people. Begotten on the queen of spotless fame *Yasômati*, his son, who meditated on his feet, (*was*) the devout worshipper of Sugata (Buddha)—like Sugata solely delighting in the welfare of others—the *Paramabhattachâraka Mahârâjâdhirâja Râjyavardhana* [II.], the tendrils of whose bright fame overspread the whole orb of the earth; who appropriated the glory of Dhanada. Varuṇa, Indra and the other guardian (deities) of the world; who gladdened the hearts of suppliants by many donations of wealth and land acquired in righteous ways, (*and*) who surpassed the conduct of former kings.

He in battle curbed *Dévagupta* and all the other kings together, like vicious horses made³ to turn away from the lashes of the whip. Having uprooted his adversaries, having conquered the earth, having acted kindly towards the people, he through his trust in promises⁴ lost his life in the enemy's quarters.

(L. 7.) His younger brother, who meditates on his feet, the devout worshipper of Mahêśvara (Śiva)—like Mahêśvara taking compassion on all beings—the *Paramabhattachâraka Mahârâjâdhirâja Harsha* issues this command to the *Mahâsûmantas*, *Mahârâjas*, *Dmihâdhîsâdhanikas*, *Pramâtâras*,⁵ *Râjasthânyas*, *Kumârâmâtyas*, *Uparikas*, *Vishayapatis*, regular and irregular soldiers, servants and others, assembled at the village of *Sômakunḍakâ* which belongs to the *Kunḍadhânî* *vishaya*⁶ in the *Śrâvasti bhukti*, and to the resident people:—

(L. 10.) Be it known to you! Having ascertained that this village of *Sômakunḍakâ* was held⁷ by the Brâhman *Vâmarathya* on the strength of a forged charter,⁸ I therefore have broken that charter and taken (the village) away from him, and, for the increase of the spiritual merit and fame of my father, the *Paramabhattachâraka Mahârâjâdhirâja Prabhâkaravardhanadêva*, of my mother, the *Paramabhattachârîkâ Mahâdêvi*, the queen *Yasômatidêvi*, and of my revered eldest brother, the *Paramabhattachâraka Mahârâjâdhirâja Râjyavardhanadêva*, have given it to the nation

¹ Compare *Gupta Inscr.* p. 220, lines 1 and 2 of the text.

² The word for 'sun,' employed in the original on account of the preceding *-pravritta-chakra*, is *âkashakra-ratha*, 'whose chariot has only one wheel'; compare for it *e.g.* in the third act of the *Ratnâvali* the verse commencing with *adhvânâṁ n=âikachakraḥ prabhavati*, and *Mayûra's Sûryasata* a, v. 59 (where the Sun says: *na hi rathô yâti mē n=âikachakraḥ*). For the idea that the sun relieves distress, compare *e.g.* *Gupta Inscr.* p. 162, text, l. 2.

³ The Gerund *kṛitô* of the original text is employed, in an unusual way, to convey a passive sense; 'like vicious horses (curbed) after they have been made to turn away from the lashes of the whip.' In Prâkrit we do find passive Gerunds; compare *e.g.* *bhājju janti* (= *bhâṅktô yânti*), 'they run away after having been broken,' in Prof. Pischel's *Materialien zur Kenntnis des Apabhram̐sa*, p. 23. For Sanskrit I can only quote, from the *Dâśakumâra-charita*, *kim upakṛitya pratyupakṛitavatt bhavēyam*, where the Gerund *upakṛitya* must mean 'after having been favoured.'

⁴ According to the *Harshacharita*, 'allured to confidence by false civilities on the part of the king of Gauda;' see Prof. Cowell and Mr. Thomas's Translation, p. 178.

⁵ On *pramâtâra* and *mahâpramâtâra*, which occurs in line 17 of the text, see *Ind. Ant.* Vol. XXV. p. 182, note 70; *pramâtâri* also apparently occurs in *Gupta Inscr.* p. 216, l. 9.

⁶ With *Kunḍadhânîvaishayika* compare *Ângadyavaishayika*, above, Vol. IV. p. 211, l. 7, *Vâlâkîvaishayika*, *Gupta Inscr.* p. 216, l. 6, *Gaydvaishayika*, *ibid.* p. 256, l. 7 of the text, . . . *vaishayika*, *ibid.* p. 50, l. 25, etc.

⁷ In *bhuktaka* the suffix *ka* has been added to *bhukta*—as noted already by Prof. Bühler, through the influence of the Prâkrit—without altering the meaning of *bhukta* (*svârthâ*); compare Prof. Pischel's *Grammatik der Prâkrit-Sprachen*, § 598. In *Gupta Inscr.* we similarly find *atisishtaka*, *kâritaka*, *datikaka*, *pravishtaka*, *pratishṭhâpitaka*, *utpannaka*, *utpadyamânaka*.

⁸ On the subject of forged copper-plates see now Dr. Fleet in *Ind. Ant.* Vol. XXX. p. 201 ff.

of a donation¹ (to Brāhmanas), as an *agrahāra* — extending to its proper boundaries, with the *udranga*, together with all income that might be claimed by the king's family,² exempt from all obligations,³ as a piece taken out of the district⁴ (*to which it belongs*), to follow the succession of⁵ sons and sons' sons, for as long as the moon, the sun and the earth endure, according to the maxim of *bhāmichchhidra* — to the *Bhaṭṭa* Vātasvāmin who is of the *gōtra* of *Sāvarṇi* and a fellow-student of the *Chhandogas*,⁶ and the *Bhaṭṭa* Śivadēvasvāmin who is of the *gōtra* of *Vishṇuvriddha* and a fellow-student of the *Bahvrichas*.⁷ Knowing this, you should assent to this, and the resident people, being ready to obey my commands, should make over only to these two⁸ the *tulya-mēya*,⁹ the share of the produce, payments in money and other kinds of income, as they may be due, and should render service to them. Moreover:—

(L. 16.) Those who profess (*to belong to*) the noble line of our family and others should approve of this donation. Of fortune, unstable as lightning and a bubble of water, donations and the preservation of others' fame¹⁰ are the (real) fruit.

By deeds, thoughts and words one should do good to the living. This Harsha has declared to be the very best way of earning religious merit.

(L. 17.) The *dātaka* in this matter is the *Mahāpramātāra Mahāsāmanta*, the illustrious Skandagupta. And by order of the great officer in charge of the office of records, the *Sāmanta Mahārāja* Īśvaragupta, (*this was*) engraved by Garjara.

The year 20 5 Mārgaśirsha-vadi 6.

No. 23.—TIRUVENDIPURAM INSCRIPTION OF THE TIME OF
RAJARAJA III., NARASIMHA II. AND KOPPERUNJINGA.

By E. HULTZSCH, PH.D.

This inscription (No. 142 of 1902) is engraved on the west wall of the *prākāra* of the Dēvanāyaka-Perumāḷ temple at Tiruvēndipuram, a village $4\frac{1}{2}$ miles west-north-west of

¹ Since *pratigraha-dharmaṇḍa*, which would be a Bahuvrīhi compound, could not be taken to qualify *agrahāra* in the abstract noun *agrahāratvēna*, I have altered it to *pratigraha-dharmēṇa*. With the whole passage compare e.g. above, Vol. VI. p. 139, l. 34, *akṣa yantvī-dharmēṇa-dharmatvēna pratipāditāḥ*. Compare also phrases like *pratigraheṇa pratipāditāḥ*, *Ind. Ant.* Vol. XV. p. 113, l. 12 of the text; *agrahāratvēna pratipāditāḥ*, *ibid.* Vol. XX. p. 124, l. 9 of the text; *dēvagrahāratvēna pratipādayati sma*, *Gupta Inscr.* p. 289, l. 10; etc.

² With *rājakulābhāvya* compare *rājābhāvya* in the plates of the *Mahārājās* of Uchchakalpa, *Gupta Inscr.* p. 118, l. 11; p. 122, l. 13; p. 127, l. 20; etc.

³ With *sarva-parihṛita-parihāra* compare *sarvaviśṭi-parihāra-parihṛita* in the plates of the *Vākātaka Mahārājās*, e.g. above, Vol. III. p. 262, l. 20. The meaning intended is more correctly expressed by *parihṛita-sarvaprāda*, e.g. above, Vol. IV. p. 250, l. 53, and by *sarvakara-parihāram kṛitva*, above, Vol. III. p. 223, l. 16. Compare also *sarva-bādhā-parihāra* (e.g. *Ind. Ant.* Vol. IX. p. 123, l. 35), and for similar expressions see above, Vol. VI. p. 13, note 3.

⁴ The expression *viśayād=uddhṛita-piṇḍa* I have found again only in the Pāṇḍukēśvar plate of Lalitāsūradēva, *Ind. Ant.* Vol. XXV. p. 180, l. 21. I am not quite certain about the exact meaning of it.

⁵ I.e. 'to be inherited in turn by'; compare *putra-pautr-ānugāmin*, e.g. above, Vol. III. p. 262, l. 21.

⁶ I.e. a student of the Sāmaveda.

⁷ I.e. a student of the Rīgvēda.

⁸ Instead of *anayōr=eva* one would have expected *abhyām=eva*.

⁹ I do not know the exact technical meaning of *tulya-mēya* which might be translated by 'things to be weighed and to be measured'; *mēya* by itself we find, in *grāma-pratyādyā mēya-hiranyādayaḥ*, in *Gupta Inscr.* p. 257, l. 12; and *tulya* occurs *ibid.* p. 70, l. 10, apparently in a technical sense. See also above, p. 62.

¹⁰ Viz. by not resuming the grants made by them.—The verse occurs with different readings in *Ind. Ant.* Vol. XIX. p. 349, l. 9 of the text, and Vol. XXV. p. 181, l. 28.

Cuddalore (Kūḍalūr), the head-quarters of the South Arcot district.¹ It consists of 9 lines in the Tamil alphabet and language and forms a single big sentence, which can, however, be dissolved into several distinct periods with the help of the gerunds *kēṭṭu*, 'having heard,' in line 2, and *eṇṇu*, 'having said,' in lines 3 and 4. The pronoun *namakkum*, 'to us,' in line 9 shows that the subject of the passage beginning in line 4 is the plural of the pronoun of the first person.

The language exhibits a few peculiarities. The letters *ḍ* and *ḍ* are doubled after a nasal in *yāṇḍḍu* (l. 1), *Ṣēṇḍḍa*² (l. 2) and *eḷṇḍḍu* (l. 9). Instead of the gerund *koṇḍu* (twice in l. 6, and l. 8), the poetical form *koḍu* occurs four times (ll. 2, 3, 4 and 9). *Arulivittu* (ll. 4 and 9), *arulivikkā* (l. 9) and *veṭṭivittu* (l. 7) are vulgar forms of *aruluvittu*, etc.

This inscription is distinguished from most other South-Indian inscriptions, as it does not record a donation or similar transaction, but is of a purely historical character. It is dated in the 16th year of *Triḷḷuvanaḥakravarṭin* Rājarājadēva (l. 1) and must have been engraved at the instance of two military officers (*daṇḍāḥka*³), named Appaṇa and Samudra-Goppaya⁴ (l. 5), in the service of the Hoysaṇa (or Hoysala) king Vira-Nārasimhadēva (l. 1). This king had heard that Kōpperuñjīṅga had captured the Chōḷa emperor at Śēṇḍamaṅgalam. Anxious to vindicate his title 'the establisher of the Chōḷa country,' he started from Dōrasamudra and conquered the Maha[ra] kingdom. When at Pāchchūr, he ordered the two above-mentioned officers to continue the campaign. They advanced through the enemy's country until they reached Śēṇḍamaṅgalam, forced Kōpperuñjīṅga to release the Chōḷa emperor, and accompanied the latter into his dominions.

The title 'establisher of the Chōḷa country,' which the inscription applies to Vira-Nārasimhadēva (l. 3), and the statement that he conquered the Mahara kingdom, show that this king is identical with the Hoysala Narasimha II., who in several inscriptions is styled 'the establisher of the Chōḷa kingdom' and 'the uprooter of the Makara or Magara kingdom.'⁵ As the inscriptions of Narasimha II. are dated between A.D. 1222 and 1234, it follows that the king Rājarāja, to whose 16th year the subjoined inscription belongs (l. 1), is the Chōḷa king Rājarāja III., who ascended the throne in A.D. 1216,⁶ and whose 16th year accordingly corresponded to A.D. 1231-32. He is no doubt identical with the 'Chōḷa emperor' who was captured and released at Śēṇḍamaṅgalam. The dates of other inscriptions of Rājarāja III. show that he continued to reign after his re-installation. His latest known date is A.D. 1243-44 in an inscription at Poygai.⁷

The subjoined inscription mentions a considerable number of geographical names. Dōrasamudra, the capital of Narasimha II., is the modern Halēbiḍ in the Bēlūr tāluka of the Hassan district in the Mysore State. Pāchchūr, where he halted on his expedition against Kōpperuñjīṅga (l. 4), is perhaps identical with a village of that name in the Trichinopoly tāluka, opposite to the island of Śrīraṅgam, 2 miles north of the Coleroon river, and 9½ miles west by south of Kannaṇūr, the southern capital of Narasimha's successor Sōmēśvara.⁷ If this identification of Pāchchūr is correct, it would follow that Narasimha II. left his dominions by way of the Gajalhaṭṭi pass, and that the Mahara (Makara or Magara) kingdom (l. 3) has to be looked for in the Coimbatore or Salem district. In the course of the expedition which Appaṇa and Samudra-Goppaya undertook against Kōpperuñjīṅga, they first destroyed the villages of Eḷḷeri, Kalliyūrmūlai and Toludagaiyūr (l. 5). Then they worshipped the god at Poṇṇambalam

¹ See Mr. Sewell's *Lists of Antiquities*, Vol. I. p. 212, where the name is spelt 'Tiruvandipuram.' The same erroneous form is found on the *Madras Survey Map* of the Cuddalore tāluka. The *Postal Directory of the Madras Circle*, p. 1350, has correctly 'Tiruvendipuram.'

² *Daṇḍāḥka* and *daṇḍyaka* are *taḍbhavas* of the Sanskrit *daṇḍāṇḍyaka*; see *Ind. Ant.* Vol. XX. p. 304 and note 7.


³ The first part of this name is apparently derived from Dōrasamudra.

⁴ Dr. Fleet's *Dyn. Kan. Distr.* p. 507; Mr. Rice's *Ep. Carn.* Vol. IV., Ng. 98, and Vol. VI., Kd. 12a.

⁵ See page 9 above.

⁶ *South-Ind. Inscr.* Vol. I. No. 64.

⁷ Above, Vol. III. p. 8 f.



(l. 6 f.), destroyed *Tonḍaimāṇallūr*, and halted at *Tiruppādirippuliyūr* (l. 7). Next they destroyed *Tiruvadigai* and *Tiruvekkarai* (l. 7) and the country between the *Vāraṇavāsi* river in the north, *Śēndamaṅgalam* in the west, and the sea in the east (l. 8). As far as the route of Narasiṃha's two officers can be followed on the map, it appears that they crossed the present South Arcot district from south to north. *Elḷēri* and *Kalliyūrmūlai* (now *Kaliyamalai*) are in the southern portion of the *Chidambaram tāluka*.¹ *Ponṇambalam* is one of the Tamil names of *Chidambaram* itself. *Tonḍaimāṇallūr* is perhaps the modern *Tonḍamānattam* in the *Cuddalore tāluka*,² and *Tiruppādirippuliyūr* is the well-known ancient name of *Tirupāpuliyūr*,³ a railway station north of *Cuddalore*. *Tiruvadigai* is *Tiruvadi*⁴ near *Paṇṇuṭṭi*,⁵ and *Tiruvekkarai* is *Tiruvakkarai* in the *Villupuram (Viḷuppuram) tāluka*.⁶ As regards *Śēndamaṅgalam*,⁷ where *Kōpperuṇḷiṅga* kept the *Chōḷa* king prisoner, and at the gates of which the war seems to have ended,—the *Postal Directory of the Madras Circle* mentions no less than eighteen villages of this name, three of which belong to the South Arcot district. The *Śēndamaṅgalam* which is intended here is probably the one in the *Tirukoilur (Tirukkōvalūr) tāluka*.⁸ I am unable to identify the *Vāraṇavāsi* river, which has to be looked for to the north of *Śēndamaṅgalam*,⁹ and the village of *Toḷudagaiyūr*, which must have been situated south of *Chidambaram*. It is not clear why *Appana* and *Samudra-Goppaya* selected the temple of *Tiruvēndipuram* for engraving this account of their achievements. Perhaps it was at this village that they took leave of the *Chōḷa* king *Rājārāja III.*, whom they had rescued from the hands of *Kōpperuṇḷiṅga* at *Śēndamaṅgalam*.

As far as we know at present, *Narasimha II.* was the first among the *Hoysala* kings who possessed a portion of the *Trichinopoly* district. In an inscription on a *vīṇakal*, dated in A.D. 1222,¹⁰ he is stated to be "marching against the *Raṅga* in the South," i.e. the island of *Śrīraṅgam*, and in the *Harihar* inscription of A.D. 1224¹¹ he is already called 'the uprooter of the *Makara* kingdom' and 'the establisher of the *Chōḷa* kingdom.' Hence his conquest of *Śrīraṅgam* seems to have taken place between A.D. 1222 and 1224. This first invasion of the *Makara* and *Chōḷa* kingdoms was distinct from and prior to the conquest of the same two kingdoms which is related in the *Tiruvēndipuram* inscription, and it is presupposed by the wording of the latter, which implies that the king started on his new campaign in order to vindicate his previously earned title 'establisher of the *Chōḷa* country.' A further testimony to *Narasimha's* influence in the *Chōḷa* country is supplied by an inscription in the *Gōkarnēśvara* temple at *Tirugōkarnam* near *Pudukkōṭṭai* (No. 410 of 1902), which is dated in the [1]0th year of *Tribhuvanachakravartin Rājārājādēva*, i.e. A.D. 1225-26, and records a grant of land by a servant of *Sōmaladēvi*,¹² the wife of *Sōmēśvaradēva*, the son of the *Pōsala* king *Vīra-Nārasimhadēva* of

¹ Nos. 274 and 280 on the *Madras Survey Map* of this tāluka.

² No. 229 on the *Madras Survey Map* of this tāluka.

³ No. 204 on the *Madras Survey Map* of the *Cuddalore tāluka*.

⁴ See above, Vol. VI. p. 331 and note 8.

⁵ No. 79 on the *Madras Survey Map* of the *Cuddalore tāluka*.

⁶ 'Tiruvakarai,' No. 239 on the *Madras Survey Map* of this tāluka.

⁷ This word is derived from *Sēndaṇ*, 'the red one,' a name of the god *Skanda*.

⁸ No. 288 on the *Madras Survey Map* of this tāluka.

⁹ The nearest river on the north of *Śēndamaṅgalam* is the *Gedilam*.

¹⁰ Mr. Rice's *Ep. Carn.* Vol. VI, Cm. 56:—*Saka-varusa 1144 Chitrabhānu-sam | rada Aśvja-sudda 10 [da*]sami Maṅgalavādrad-aṁdu*. On this date Professor Kielhorn remarks as follows:—"For *Āśvina-sudi 10* of *Saka-Samvat 1144* expired=*Chitrabhānu* this date is wrong; it would correspond to Friday, the 16th September A.D. 1222. If we could read *sudda 7 sa[pta*]mi*, it would regularly correspond to Tuesday, the 13th September A.D. 1222."

¹¹ Dr. Fleet's *Dyn. Kan. Distr.* p. 607.

¹² See above, Vol. III. p. 9, note 6. Another princess of the same name is mentioned in Mr. Rice's *Ep. Carn.* Vol. IV., Kp. 63. She is there compared to *Lakshmi*, and *Narasimha II.* to the Moon. Hence she must have been his sister, and not his wife as Mr. Rice thinks (*ibid.*, Introduction, p. 21). According to other inscriptions, the wife of *Narasimha II.* and the mother of *Sōmēśvara* was *Kāḷadēvi*; see *ibid.* Vol. III., Md. 122; Vol. IV., Ng. 98; and Vol. VI., Kd. 125.

Dōrasamudra.¹ Finally, a mutilated inscription in the Raṅganātha temple at Śrīraṅgam (No. 54 of 1892), dated in A.D. 1233,² records a grant by a female relation of Bhujabala-Bhimakēśava-Daṇḍanāyaka, the great minister (*mahāpradhāna*) of *Pratāpachakravartin* Pōśala-śrī-Vīra-Nārasimhadēva.

Among the opponents of Nārasimha II., the Harihar inscription of A.D. 1224 and the Basarālu inscription of A.D. 1234 mention the Kādava king and the Pāṇḍya king,³ and three inscriptions state that "his valour caused the reduction of the Pāṇḍya sovereignty."⁴ As will appear below (p. 164 and note 3), Kōpperuñjīṅga claimed to belong to the Kādava or Pallava family. If he is meant by the expression 'Kādava king' in the Harihar inscription, it would follow that he had come into hostile contact with Nārasimha II. before the time of the Tiruvēndipuram inscription, perhaps on the occasion of Nārasimha's first attack on Śrīraṅgam between A.D. 1222 and 1224. The Pāṇḍya contemporary of Nārasimha II. was Māravarman *alias* Sundara-Pāṇḍya I., who, as shown by Professor Kielhorn,⁵ ascended the throne in A.D. 1216. This king boasts on his part to have conquered the Chōla country and to have restored it to the Chōla king; and an inscription of his 9th year, i.e. A.D. 1225, is actually found in the Raṅganātha temple at Śrīraṅgam,⁶ while we have seen that Nārasimha II. was marching against Śrīraṅgam in A.D. 1222.

Among the partisans of Kōpperuñjīṅga, the inscription mentions two chiefs named Śōlakōṇ⁷ (l. 5) and Kōlḷi-Śōlakōṇ (l. 6). Viragaṅganādālvāṇ and Chinattarayaṇ are stated to have been killed and are called 'officers of the king.' Apparently, they were originally in the service of Rājarāja III. and had gone over to Kōpperuñjīṅga. Of special interest is the statement that "four officers including Parākramabāhu, the king of Īlam," were killed. What the author wants to say is perhaps "Parākramabāhu and three of his officers." Īlam is the Tamil name of Ceylon. According to Wijesinha's Translation of the *Mahāvamsa* (page xxiv. ff.), Parākramabāhu I. died in A.D. 1197 and Parākramabāhu II. in A.D. 1275, and neither of them fell in battle. Hence the Parākramabāhu of this inscription must be different from both; perhaps he was not a king, but a prince of Ceylon.

Kōpperuñjīṅga, the person who was responsible for Nārasimha's interference in the affairs of the Chōla kingdom, is first mentioned in an inscription of the Vīddhagiriśvara temple at Vīddhāschalam (No. 136 of 1900), the head-quarters of a tāluḱa in the South Arcot district. This record opens as follows:—

- 1 ॐ Svasti śrīḥ [||*] Tribhuvanachchakravatti-
- 2 gaḷ śrī-Rājarājadēvaṅku yāṇ-
- 3 ḍu lāḷvadu uḍaiyār Tiru-
- 4 mudugunṇam-uḍaiya nāyaṇāṅku Pal-
- 5 lavan Kōpperuñjīṅgan agam-
- 6 baḍi-mudaligaḷil Edirigaṇāyan Po-
- 7 ttappi-Chchōḷan i-nṇāyan-

¹ *Tōraḷsamuttirattu śrī-Pōśala-Vīra-śrī-Nārasīṅgadēvar maganār Śōmīśvaradēvar māḍar Śōmaladēvi[y]ār.*

² *Vijaya-samma(samva)tsarattu Kāttigai sūddha-pañchami* Adidra=mudal; "from Sunday, the fifth *nīḱi* of the bright (fortnight) of Kāttigai in the Vijaya year." Professor Kielhorn kindly informs me that, "for the month Kārttika of Śaka-Samvat 1155 expired=Vijaya, this date regularly corresponds to Sunday, the 9th October A.D. 1233."

³ Dr. Fleet's *Dyn. Kan. Distr.* p. 507.

⁴ Mr. Rice's *Ep. Carn.* Vol. III., Md. 121; Vol. IV., Ng. 98; and Vol. VI., Kd. 12a.

⁵ Above, Vol. VI. p. 814.

⁶ See *Ind. Ant.* Vol. XXI. p. 344, and above, Vol. VI. p. 303, No. 5. The Tirupparaṅguṇṇam cave-inscription and the smaller Tiruppuvaṇam grant belong to the reign of the same king.

⁷ A different person of the same name is mentioned among the officers of Vikrama-Chōla in the *Vikīrama-śōḷaṅ-Uḷ*; *Ind. Ant.* Vol. XXII. pp. 143 and 149.

8 āṅku vaitta tirunundāṇṭa-

9 kku onṅukku

"In the 14th year of the emperor of the three worlds, the glorious Rājarājādēva,—Edirigaṇṭayan Pottappi-Chōḷa, (one) among the chiefs of the body-guard¹ of the Pallava Kōpperuñjīṅga, gave to the lord, the god of Tirumudugunṇam,² one perpetual lamp," etc.

From this inscription we learn that Kōpperuñjīṅga claimed to belong to the Pallava family,³ and that in A.D. 1229-30, i.e. two years before the Tiruvēdipuram inscription, he still acknowledged Rājarāja III. as his sovereign. The defeat which Narasimha II. inflicted on Kōpperuñjīṅga enabled Rājarāja III. to remain in power until at least A.D. 1243-44.⁴ About this time he was either ousted or succeeded by his former enemy; for, an inscription of Kōpperuñjīṅga, who had assumed the titles *dēva*, 'king,' and *Sakalabhuvanachakravartin*, in the Arulāla-Perumāḷ temple at Conjeeveram shows that the 18th year of his reign corresponded to Śaka-Samvat 1182. I subjoin the date-portion of this inscription, and that of three other inscriptions at Tiruveṇṇainallūr, Tiruviḍaimarudūr and Tirukkālukkunṇam.

A.—In the Arulāla-Perumāḷ temple at Conjeeveram.⁵

1 Svasti śrī [||*] Śakābdam āyiratt-orunūṇṇu-en[ba]tt-irapḍiṇ mēl śellāniṇṇa
Śagalabuvanaḥ[cha]kkaṇavattigaḷ śrī-Kōpperuñjīṅga[dé]vaṅku yāṇḍu
[18āvadu] Vṛśchika-nāyaṅṇu apara-pakshattu daśamiyum Nāyaṅṇu-
kkiḷamaiyu[m*]⁶

"In the [18th] year of the emperor of the whole world, the glorious Kōpperuñjīṅgadēva which was current after the Śaka year one thousand one hundred and eighty-two,—
.⁷ a Sunday and the tenth *tithi* of the second fortnight of the month Vṛśchika."

B.—In the Vaikuṇṭha-Perumāḷ temple at Tiruveṇṇainallūr.⁸

1 [Svasti*] [śrī ||] Sakalabhuvanaḥchakravartigaḷ śrī-Kōpperuñjīṅga[dé]var[k*]k
yāṇḍu [7ā]vadu Sim[ha]-nāyaṅṇu apara-pakshattu chatuṛthiyum Velli-
kkiḷamaiyum peṇṇa Rēvati-nāl.

"In the [7]th year of the emperor of the whole world, the glorious Kōpperuñjīṅgadēva,—on the day of Rēvati, which corresponded to a Friday and to the fourth *tithi* of the second fortnight of the month Simha."

C.—In the Mahālingasvāmin temple at Tiruviḍaimarudūr.⁹

1 Svasti[ī] śrī [||*] Śagalabuvanaḥsakkaṇavattigaḷ śrī-Kōpperuñjīṅga[dé]vaṅku yāṇḍu
18vadu Kaṇ[ṇ]i-nāyaṅṇu pūrvva-pakshattu pañchadaśiyum Nāyaṅṇu-kiḷam[ai]
peṇṇa Śadayattu [n]āl.

"In the 18th year of the emperor of the whole world, the glorious Kōpperuñjīṅgadēva,—on the day of Śatabhishaj, which corresponded to a Sunday and to the fifteenth *tithi* of the first fortnight of the month Kanyā."

¹ See Dr. Gundert's *Malayālam Dictionary*, p. 2, s.v. *agambāḍi*.

² This is the Tamil name of Vṛddhachalam; compare *South-Ind. Inscr.* Vol. I. p. 123, and Vol. III. p. 152.

³ In the *Madras Christian College Magazine* of March 1892, Mr. Venkayya states that two inscriptions at Tiruvannāmalai also call Kōpperuñjīṅga a Pallava or Kāḍava. Regarding Kāḍava as a synonym of Pallava, see above, p. 25, and *South-Ind. Inscr.* Vol. III. p. 68.

⁴ See above, p. 161 and note 6.

⁵ No. 38 of 1890; see *South-Ind. Inscr.* Vol. II. p. 340, note 5.

⁶ The remainder of the line is built in.

⁷ A portion of the date, which probably contained the name of the *nakṣatra*, is lost.

⁸ No. 320 of 1902.

⁹ No. 135 of 1895.

D.— In the Vēdagiriśvara temple at Tirukkalukkunram.¹

- 1 Svasti śrī [||*] Śāgalabuvanachchakkaravatt[i]gaḷ Avaniy-āḷa-ppiṇḍār Kōpperuñ-
j[i]ṅgadēvarkku yāṇḍu [3]lvaḍu Kumba-nāyaru pūrvva-pakshattu d[v]it[i]yayum
Śa-
2 ni-kkīlamaiyum perṟa Uttirattādi-nāl.

"In the [3]1st year of the emperor of the whole world, him who was born to rule the earth, Kōpperuñjīngadēva,— on the day of Uttarabhadrapadā, which corresponded to a Saturday and to the second *tithi* of the first fortnight of the month Kumbha."

According to Professor Kielhorn, who has kindly examined these four dates, "the first date (A.), of Śaka-Samvat 1182 expired and the 18th year current, regularly corresponds to **Sunday**, the 31st October A.D. 1260, which was the 4th day of the month Vṛiśchika, and on which the tenth *tithi* of the dark half (of the month Kārttika) ended 6 h. 31 m. after mean sunrise. The second date (B.), of the 7th year, corresponds to **Friday**, the 30th July A.D. 1249, which was the 3rd day of the month Simha, and on which the fourth *tithi* of the dark half (of the month Śrāvaṇa) ended 9 h. 38 m., and the *nakshatra* was Rēvati from 3 h. 56 m., after mean sunrise. The third date (C.) is incorrect. The fourth date (D.), of the 31st year, corresponds to **Saturday**, the 10th February A.D. 1274, which was the 18th day of the month Kumbha, and on which the second *tithi* of the bright half (of the month Phālguna) ended 10 h. 46 m., and the *nakshatra* was Uttara-Bhadrapadā for 21 h. 1 m., after mean sunrise. The three dates A., B. and D. show that Sakalabhuvanachakravartin Kōpperuñjīngadēva must have ascended the throne in A.D. 1243 between, approximately, the 11th February and 30th July." His reign extended to at least A.D. 1278-79; for, as the subjoined list of his inscriptions shows, two of them at Chidambaram are dated in his 36th year. In this list the inscriptions are arranged under different heads according to the manner in which they quote the king's name and titles.

I. Kōpperuñjīngadēva.

1. 20th year: Tiruvottūr, No. 83 of 1900.
2. 22nd year: do. No. 95 of 1900.

II. Sakalabhuvanachakravartigaḷ śrī-Kōpperuñjīngadēva.

1. 5th year: Vṛiddhāchalam, No. 134 of 1900.
2. [7]th year: Tiruveṇṇainallūr, No. 320 of 1902.
3. 8th year: Vṛiddhāchalam, No. 135 of 1900.
4. 14th year: Vallam, No. 186 of 1892.²
5. 16th year: Chidambaram, No. 467 of 1902.
6. Do. do. No. 468 of 1902.
7. 18th year: Tiruvidaimarudūr, No. 135 of 1895.
8. [18th] year: Conjeeveram, No. 38 of 1890.
9. 26th year: Tirukkōvalūr, No. 308 of 1902.
10. 36th year: Chidambaram, No. 455 of 1902.

III. Sakalabhuvanachakravartigaḷ Avaniy-āḷa-ppiṇḍār Kōpperuñjīngadēva.

[3]1st year: Tirukkalukkunram, No. 181 of 1894.

¹ No. 181 of 1894. The inscription records the gift of a lamp by the wife of Pañchanedi-Vāṇar alias Nilagaṅgarayar (l. 3). The same person or a relation of his is mentioned in an inscription of the 26th year of Kulōttuṅga III.; *South-Ind. Inscr.* Vol. III. p. 84.

² See *South-Ind. Inscr.* Vol. II. p. 340, note 4.

IV. Sakalabhuvanachakravartigaḷ Avaniy-āla-ppiṇḍār *alias* śrī-Kōpperuñjiṅgadēva.

- | | | | |
|----|------------|--------------|------------------|
| 1. | 3rd year : | Chidambaram, | No. 462 of 1902. |
| 2. | Do. | do. | No. 465 of 1902. |
| 3. | Do. | do. | No. 466 of 1902. |
| 4. | 5th year : | do. | No. 459 of 1902. |
| 5. | Do. | do. | No. 464 of 1902. |

V. Sakalabhuvanachakravartigaḷ śrī-Avaniy-āla-ppiṇḍār *alias* Kōpperuñjiṅgadēva.

- | | | | |
|----|-------------|--------------|------------------|
| 1. | 5th year : | Chidambaram, | No. 463 of 1902. |
| 2. | 8th year : | do. | No. 460 of 1902. |
| 3. | 34th year : | do. | No. 461 of 1902. |
| 4. | 36th year : | do. | No. 456 of 1902. |

The Vallam inscription of the 14th year¹ mentions 'prince (*pillaiyār*) **Nilagaṅgaraiyar**,' apparently a son of Kōpperuñjiṅgadēva. An inscription in the Arulāla-Perumāl temple at Conjeeveram (No. 41 of 1893), which is dated in the 22nd year of *Tribhuvanachakravartin* Vijaya-Gaṇḍagōpālādēva,² records the gift of a flower-garden by Nilagaṅga of **Āmūr**, who bore the surname **Bhū-pālan-ōḍbhava** (in Sanskrit) or **Puvi-āla-ppiṇḍa** (in Tamil), *i.e.* 'who was born to rule the earth.' This person is no doubt identical with the prince **Nilagaṅgaraiyar** of the Vallam inscription, and his surname is a slight modification of *Avaniy-āla-ppiṇḍār*, the title of his father Kōpperuñjiṅgadēva.

As stated on page 163 above, the Tiruvēndipuram inscription mentions among the partisans of Kōpperuñjiṅga a certain **Śōlakōṇ**. This person is probably identical with an officer whose name occurs in most of the Chidambaram inscriptions of Kōpperuñjiṅgadēva. In one inscription he is called "Perumālppillai *alias* Śōlakōṇār, (one) among his (*viz.* Kōpperuñjiṅgadēva's) officers,"³ and in another (No. 462 of 1902) "the lord of Araśūr, Śēgaṇivāyar *alias* Pillai Śōlakōṇār Āliyar." The grant portion of the Chidambaram inscriptions of the 3rd to 16th years opens with the words *Śōlakōṇ ōlai*, *i.e.* "the order of Śōlakōṇ," and ends with the words *ivai Śōlakōṇ eḷuttu*, *i.e.* "this (is) the signature of Śōlakōṇ." Accordingly, Śōlakōṇ must have been the representative of Kōpperuñjiṅgadēva at Chidambaram until at least A.D. 1258-59.

A short undated inscription at Tiruvēndipuram supplies the name of Śōlakōṇ's younger brother. This inscription (No. 146 of 1902) runs as follows :—

- | | | | |
|---|-------------------------|----|----------------------|
| 1 | Svasti śrī [*] Avani- | 7 | Śōlakōṇ ta[m]- |
| 2 | āla-ppiṇḍā- | 8 | bi Perumāl Vē- |
| 3 | ṇ Kōpperuñ- | 9 | [n]āḍuḍaiyāṇ ēe[y*]- |
| 4 | jiṅgadēvar ti- | 10 | vitta tirukkōpura- |
| 5 | rumēṇikkū naṇṇā- | 11 | m a- |
| 6 | ga Śēgaṇivāyaṇ | | |

"Hail! Prosperity! For the benefit of the royal body of him who was born to rule the earth, **Kōpperuñjiṅgadēva**,— Perumāl **Vēṇāḍuḍaiyāṇ**, the younger brother of Śēgaṇivāyaṇ Śōlakōṇ, caused to be made (*this*) sacred *gōpura*."

Vēṇāḍuḍaiyāṇ seems to have succeeded his elder brother as officer in charge of Chidambaram. For, in two Chidambaram inscriptions of the 34th and 36th years of Kōpperuñjiṅgadēva (Nos. 461 and 456 of 1902), the grant portion opens with the words *Vēṇāḍuḍaiyāṇ ōlai* and ends with the words *ivai Vēṇāḍuḍaiyāṇ eḷuttu*.

¹ Above, p. 165, clause II. No. 4.

² As the 15th and 16th years of this king corresponded to A.D. 1265 (*Ind. Ant.* Vol. XXII. p. 220), the date of this inscription must fall in A.D. 1271-72.

³ No. 460 of 1902 :— *ivar mudaligaḷil Perumālppillai dṇa Śōlakōṇār*.

A solitary Sanskrit record of Kōpperuñjīgadēva is found as far north as Drākshārāma in the Gōdāvari district. Unfortunately this inscription (No. 419 of 1893) is so much mutilated that no connected transcript of it can be given. It is dated in the Śaka year 1184 and records gifts to the temple of Bhīmanātha by the king, who is called *Sakalabhūvanachakravartin*, *Avany-avan-ōdbhava* or *Avany-avana-sambhava*, and *Mahārājasimha*. The two names beginning with *avani* are Sanskrit translations of his surname *Avanyī-dīa-ppirandār*.¹ *Mahārājasimha* means 'the lion among great kings,' while Kōpperuñjīga would mean 'the great lion among kings.' The Drākshārāma inscription calls him 'the ornament of the Kāthaka family'² and 'a worshipper of Kanakasabhādhinātha.'³ He is stated to have defeated the Karpāṭa⁴ and Chōḷa kings and to have established the Pāṇḍya country.⁵ The Kākati king and Ganapati-mahārāja are also referred to in the Drākshārāma inscription. The first three lines contain two verses in the Śārdūlavikrīḍita metre, and the sixth line states that certain verses were composed by the king himself and inscribed on his gifts to the temple.

It was stated in the preceding paragraph that Kōpperuñjīgadēva claims to have established the Pāṇḍya country. On the other hand, an inscription of the Pāṇḍya king Jaṭāvarman *alias* *Tribhūvanachakravartin* Sundara-Pāṇḍyadēva at Tiruppanduruttī⁶ asserts that this king "besieged the prosperous city of Śēdamangalam and fought several battles to frighten the Pallava."⁷ This Pallava is evidently Kōpperuñjīgadēva, and Śēdamangalam seems to have been his capital, as we might already conclude from the Tiruvēndipuram inscription, according to which Kōpperuñjīga was besieged in Śēdamangalam.

TEXT.

- 1 Svasti śrī [||*] Tiribu[vaṇa]ch[cha]kka[ra]vattigaḥ śrī-Rājarājadē[va]r[k]ku yāṇ[ḍ]ḍu⁸
15[vad]il edirā[m]-āṇḍu Pratā[pa]chchakkaravatti Hoy[sa]ṇa-śrī-Vi(vi)ra-
Nārasi[m*]hadēvaṇ Śōḷa-chchakkaravattiyai=
- 2 Kkō[pp]eruñjīgaṇ ⁹[Ś]ēpddamañ[ga*]lattē [p]idi[t]tu koḍu iru[ndu] taṇ
[pa]ḍaiyai iṭṭu rāyattai alittu dēv-ā[la]iyāṅga[lu]m ¹⁰Vishṇu-stāṇṅaḷum
aligaiyālē ippaḍi dēvaṇ kēṭ[t=a]ru-
- 3 ḷi Śōḷa-maṇḍala-pratishṭ-āsāriyaṇ¹¹ eṇṇu[m] ki(ki)r[t*]t[i] ni[lai]-ni[r]u[tti] a[l]ladu
i-k[k]ālam=ntuvad[i]llai¹² eṇṇu Dōra[samuttiratti[ni*]]n[r]u[m] eḍuttu vandu
[Ma]ha[ra*]-rājya=nirmamālam=āḍi ivaṇaiyum [i]vaṇ penḍu-paṇḍāra[mu]m kai-
kkoḍu
- 4 Pāchchūrilē vittu=Kkōp[pp]eruñjīgaṇ dē[sa]mu[m] alittu=Chchōḷa-chchakka-
vattiyaiyum eḷund=aruḷi(lu)vittu=tke(kko)ḍuv=an[r]u¹³ dēvaṇ tiruv-uḷlam=āy ēva
viḍai koṇḍu eḷunda svasti śrīmaṇu-¹⁴mahāpradhāni paramaviśvāsi
- 5 daṇḍinagōpaṇ Jagago(do)bbagaṇḍaṇ Appaṇa-dann[ā]kkaṇum Śa[mu]tt[ī]ra-
Gop[pa]ya-dannākkaṇum Kōpperuñjī[ḷ]gaṇ iru[n]da E[ḷ]ḷi[ḷ]riyu[m]
Kalliyūrmu(mū)laiyum Śōḷakōp iru[nda] Toludagaiyūrum alit[tn] vē-
- 6 [nda]ṇ mudaligali[||*] Viragaṅga[n]ā[ḍ]ḍā[va]ṇ J[i](chi)ṇa[t]taraya[n] ḷattu rājā
Parāk[k]i[ḍa](ra)maḥāh=ū[ḷ]i[t]ṭa [mu]dali [ḷ] pēraiye . . . ko[ḷ]ru

¹ See above, p. 165 f.

² Here 'Kāthaka' can hardly refer to the kings of Cuttack, but must be taken as a Sanskrit equivalent of 'Kāḍava,' see above, p. 164, note 3.

³ *I.e.* of the god at Chidambaram.

I.e. the Hoysala king Narasimha II.

⁴ *Pāṇḍya-maṇḍala-sthāpand-sātradhārāṇa.*

⁵ No. 166 of 1894. According to Professor Kielhorn, the date of this record corresponds to the 7th October A.D. 1257; see above, Vol. VI. p. 307 f.

⁶ Line 10 f.:—*Śēdamangala-chchēḷum-baḍi murri=Pallava=ṇaḍ* ¹⁵*ppala pōr-āḍi.*

⁷ Read *yāṇḍu.*

⁸ Read *Śēnda.*

⁹ Read *Vishṇu-stāṇḍa.*

¹⁰ Read *pratishṭh-dohdyaṇ.*

¹¹ Read *āḍuvadill*

¹² Read *eṇṇu.*

¹³ Read *śrīmaṇu.*

- i[va][r*]gaḷ kudiraiyu[m] kai-konḍu Kolli-Chchōlakōṇ kudiraigaṇai(lai)yum
kai-kkonḍu Po[ṇ]-
- 7 ṇa[mba]la-dēvaṇaiyum kumbiṭṭu eḍuttu vandu Toṇḍaimāṇallūr ulliḍa tamukk-
u[rga]lum aḷit[ṭu] aḷi . . [kkā]ḍum veṭṭi(ṭṭu)vittu Tiruppā[dī][r][i][p]-
puliṭṭu[ṭi]lē viṭṭu irundu Tiruvadigai Tiruvekkarai ulliṭṭa ūr-
- 8 gaḷum aḷittu Vāraṇavāsi āṇṇukku=tterku Śēn[da*]maṅgalattukkum ku² kḷakku
kaḍalilē [aḷi]-ūrgaḷum kuḍi-k[kāl]ga[ḷu]m sūṭṭum aḷidudum³ peṇḍu[ga]lai
piḍittum kolḷai-konḍum Śēndamaṅgalattilē eḍuttu vi-
- 9 ḍa=ppū(ppō)giṇa aḷaḍi(vi)lē Kōpperuṇṇi[ṭi][n*]gaṇ kulaindu Śōḷa-chchakka[ra*]-
vattiyai e[ḷu]nd=a[ru*]ḷi(lu)[vi]kka=[kka*]ḍavadāga dēvaṇukku vinnappa[m*]
śēya ivar viṭṭu namakkum aḷi vara=kkāṭṭugaiyālē Śōḷa-chchakka[ra*]vattiyai
eḷund[ḍa*]ruḷi(lu)vittu=kkoḍu vō(pō)ndu rāṇyattē puga viṭṭadu ௨-

TRANSLATION.

(Line 1.) Hail! Prosperity! In the year which was opposite to the 15th year (*i.e.* in the 16th year)⁵ of the emperor of the three worlds, the glorious Rājarājadēva,— when king⁶ Pratāpachakravartin, the Hoysāṇa, the glorious Vira-Nārasimhadēva, heard that Kōpperuṇṇiṅga had captured the Chōḷa emperor at Śēndamaṅgalam, that he destroyed the kingdom with his army, and that the temples of the god (Śiva) and the places (*sacred to*) Viṣṇu were destroyed, he exclaimed:— “This trumpet shall not be blown⁷ unless (*I shall*) have maintained (*my*) reputation of being ‘the establisher of the Chōḷa country.’⁸ ”

(L. 3.) He started from Dōrasamudra, uprooted the Maha[ra] kingdom, seized him,⁹ his women and treasures, and halted at Pāchchūr.

(L. 4.) Then the king was pleased to order:— “Destroy the country of Kōpperuṇṇiṅga and liberate the Chōḷa emperor.”— Hail! (*We*), the glorious great minister, the very confidential servant, Daṇḍinagōpa¹⁰ Jagadobbagaṇḍa¹¹ Appaṇa-Daṇṇākka and Samudra-Goppaya-Daṇṇākka, took leave (*from the king*) and started.

(L. 5.) (*We*) destroyed (*the villages of*) Elḷēri and Kalliṭṭuṇṇiṅga where Kōpperuṇṇiṅga was staying, and Toḷudagaiyūr where Śōḷakōṇ was staying; killed . . . among the king’s officers Viragaṇaṇḍāḷvāṇ (*and*) Chiṇattarayaṇ, and 4 officers including Parākrama-bāhu, the king of Iṇam; seized their horses; and seized the horses of Kolli-Śōḷakōṇ.

(L. 6.) Having worshipped the god of Poṇṇambalam, (*we*) started (*again*), destroyed rich (?) villages including Toṇḍaimāṇallūr, caused the . . . forest to be cut down, and halted at Tiruppādirippuliṭṭu.

(L. 7.) (*We*) destroyed Tiruvadigai, Tiruvekkarai and other villages; burnt and destroyed the port-towns¹² on the sea and the drinking-channels to the south of the Vāraṇavāsi river and to the east of Śēndamaṅgalam; and seized and plundered the women.

¹ Read *tamakk-ār* (P).

² Read *aḷittum*.

³ See *South-Ind. Insor.* Vol. III. p. 33, note 3.

⁴ The trumpet (*kāḍam*) was one of the five instruments used in producing the *pañcha-mahāśabda*; see above, Vol. V. p. 216, note 3, and p. 260, note 3. The king here makes a vow that he will dispense with his right of using this instrument, until he will have defeated Kōpperuṇṇiṅga and re-established the Chōḷa king.

⁵ Literally, ‘the architect (causing) the stability of the Chōḷa country.’ The parallel term *Pāṇḍya-maṇḍolū-siddhānta-sūtradhāra* (see above, p. 167, note 5) proves that the word *dhārya* is here used in its Tamil meaning: ‘a master-carpenter, an architect.’

⁶ *Viz.* the Mahara king.

⁷ This word is not Tamil, but Kanarese, and means ‘the commander of an army.’

⁸ On this *śiruda*, which is also Kanarese, see above, Vol. III. p. 64, note 9.

⁹ See Dr. Gundert’s *Malayāḷam Dictionary*, s. v. *aḷi* and *aḷi-mukham*.

¹⁰ Cancel this syllable.

¹¹ Read *eḷund*.

¹² This word (*dēva*) occurs at the end of line 2.

(L. 8.) When (*we*) advanced against Śēndamaṅgalam and were going to encamp (*there*), Kōpperuñjiṅga became afraid and submitted to the king that (*he*) would release the Chōla emperor.

(L. 9.) As he (*viz.* the king) agreed and despatched a messenger to us, (*we*) liberated the Chōla emperor, went (*with him*), and let (*him*) enter (*his*) kingdom.

No. 24.— DATES OF CHOLA KINGS.

By F. KIELHORN, PH.D., D.LITT., LL.D., C.I.E.; GÖTTINGEN.

(Continued from page 10.)

Dr. Hultzsch again has sent me a large number of dates of Chōla kings, of which I now publish twenty-three, with the results of my calculations. Of these, the dates Nos. 61-74 show that the times previously found for the commencements of the reigns of the five kings to whom they belong—Rājarāja I., Rājendra-Chōla I., Kulōttuṅga-Chōla I., Vikrama-Chōla, and Kulōttuṅga-Chōla III.—are correct. The dates of Rājarāja III., Nos. 75-78, reduce the time during which this king must have commenced to reign, to the period from (approximately) the 23rd June to the 13th August A.D. 1216. And the dates Nos. 79-83, belonging to Rājendra-Chōla III., of whom no dates had yet been examined, prove that this king commenced to reign between (approximately) the 21st March and the 8th May A.D. 1246. The remaining dates sent to me are very difficult to deal with;¹ their publication will probably have to be deferred to the time when more dates of the kings to whom they belong have been discovered.

A.—RAJARAJA I.

61.—In the Mūlēsvara temple at Bāhūr.²

- 1 Svasti śrī [||*] Kānda[||]ūr-Chch[ā]l[ai] ka[lam-aṇu]tta kō I[rā]jarāja-
k[ē]sar[ipa]nmaṅku yā[p]-
2 ḍu lla(ā)vadu ivv-āṭṭai Midhu(thu)na-nāyaṇṇu
3 apara-pakshattu Nāyaṇṇu-kkilamai perṇa Kātti[g]ai-nāṇṇu³ pagal.

"In the 11th year (*of the reign*) of king Rājarājakēsarivarman who destroyed the ships (*at*) Kāndaḷūr-Śālai,—in daytime on the day of Kṛittikā, which corresponded to a Sunday of the second fortnight of the month of Mithuna in this year."

The date corresponds to Sunday, the 14th June A.D. 996, which was the 22nd day of the month of Mithuna, and on which the 11th *tithi* of the dark half (of Jyāishṭha) ended 12 h. 58 m., while the *nakṣatra* was Kṛittikā, by the Brahma-siddhānta for 13 h. 47 m., according to Garga for 15 h. 6 m., and by the equal space system from 2 h. 38 m., after mean sunrise.

B.—RAJENDRA-CHOLA I.

62.—In the Karavandiśvara temple at Uḍaiyārkōyil.⁴

- 1 Sva[st]i śrī [||*] Tiru manni valara
17 kō=Ppararē(kē)śaripaṇ[ma] . . . [v=U]ḍaiyār śrī-Rājendra-Śōḷadēva[r]ku
yāṇḍu 3lā[vadu]

¹ They apparently belong to three kings of whom no dates have yet been published in this list.
² No. 178 of the Government Epigraphist's collection for 1902.
³ Read *-nāṇṇu*.
⁴ No. 433 of the Government Epigraphist's collection for 1902.

- 19 i[vv-āṇḍu] Kaṇ[kadaga-nāya]ṛṛu pū[rvva-pakshat]tu chatu[r]tth[iy]um Vell[i]-
kk[i]lamaiyum [pe]ṛṛa Pu[ṇarbū]-
20 śatti-nā].

"In the 31st year (of the reign) of king Parakēsarivarman [*alias*] the lord, the glorious Rājendra-Chōḷadēva,—on the day of Punarvasu, which corresponded to a Friday and to the fourth *tithi* of the first fortnight of the month of Karkāṭaka in this year."

The date is intrinsically wrong because the *nakshatra* on the fourth *tithi* of a bright half in the month of Karkāṭaka cannot be Punarvasu. The equivalent of the date apparently is Friday, the 23rd July A.D. 1042, which was the 28th day of the month of Karkāṭaka and which was entirely occupied¹ by the fourth *tithi* of the bright half (of Śrāvāṇa). The *nakshatra* on this day was Uttara-Phalgunī, by the equal space system and according to Garga for 13 h. 8 m., and by the Brahma-siddhānta for 9 h. 51 m., after mean sunrise.

C.—KULOTTUNGA-CHOLA I.

63.—In the Karavandiśvara temple at Uḍaiyārkōyil.²

- 1 Svasti śrī || Puḡaḷ śūḷṇḍa puṇari
8 [kōv-Irāja]kēsaripat[ma]r=āna Tribhuva-
9 nachchakkaravattigaḷ śrī-Ko[l]ō[t]tuṅga-Śōḷadēvar[k*]ku yāṇḍu 16āvadu . . .
Mina-nāyaṛṛu [apara-pakshattu V]i[y]āḷa-kkīlamai[y]um
dacha(śa)miyu[m] peṛṛa Utirāḍa[ttu nā].

"In the 16th year (of the reign) of king Rājakēsarivarman *alias* the emperor of the three worlds, the glorious Kulōttuṅga-Chōḷadēva,—on the day of Uttarāśhāḍhā, which corresponded to a Thursday and to the tenth *tithi* of the second fortnight of the month of Mina."

A date of the month of Mina of the 16th year of Kulōttuṅga-Chōḷa I. would be expected to fall in A.D. 1086,³ and in my opinion this date undoubtedly corresponds to Thursday, the 12th March A.D. 1086, which was the 19th day of the month of Mina, and on which the *nakshatra* was Uttarāśhāḍhā, by the equal space system and according to Garga for 16 h. 25 m., and by the Brahma-siddhānta for 9 h. 51 m., after mean sunrise. But the *tithi* which ended on this day, 10 h. 50 m. after mean sunrise, was the 9th, not the 10th *tithi*, of the dark half (of, Phālguna).—This result shows that the word *dachamiyum* of the original date should be altered to *navamiyum*.⁴

D.—VIKRAMA-CHOLA.

64.—In the Vāmanapurīśvara temple at Tirumānikuḷi.⁵

- 1 [S]va[s]ti śrī [i] [i*] Pū-māḍu puṇara
2 kō=P[arakē]śar[i]pa[n]mar=ā[ṇa] Ti[r]ibuvāṇachcha[k*]karavattigaḷ
śrī-Vikkirama-Śōḷadēvaṛku yāṇḍu paḍiṇ-o[ṇṇāvadu] . . . [nāya]ṛṛu
apa[ra-pakshattu ēkādaśiyum Budāṇ-kiḷamaiyum peṛṛa Viśāgattu nā].

"In the eleventh year (of the reign) of king Parakēsarivarman *alias* the emperor of the three worlds, the glorious Vikrama-Chōḷadēva,—on the day of Viśākhā, which corresponded to a Wednesday and to the eleventh *tithi* of the second fortnight of the month of"

¹ The *tithi* was a *prathama-chaturtithi*.

² No. 399 of the Government Epigraphist's collection for 1902.

³ See above, p. 7, note 5.

⁴ [It is not absolutely excluded that the writer wanted to write *navamiyum*, and that the two Grantha letters *da* and *cha* are in reality a badly shaped *na* and *va*, respectively.—E. H.]

⁵ No. 148 of the Government Epigraphist's collection for 1902.

My calculation shows that the name of the month of this date was **Dhanus**. For this month the date corresponds to **Wednesday, the 19th December A.D. 1128**,¹ which was the 25th day of the month of **Dhanus**, and on which the 11th *tithi* of the dark half (of *Mārgaśīrsha*) ended 22 h. 1 m. after mean sunrise, while the *nakṣatra* was *Viśākhā*, by the equal space system and according to Garga for 16 h. 25 m., and by the *Brahma-siddhānta* for 11 h. 50 m., after mean sunrise.

65.—In the Karavandiśvara temple at Udaiyarkōyil.²

- 1 [Sva]sti [ś]r[i] [||*] Pū-mādu p[unara]
 2 kō= pan[ma*]r-āna
 Tir[i*]bu[va*]na[cha][k*]karavattigaḷ śrī-Vik[kira*]ma-Śōḷadēvark[ku yāṇ]ḍu
 1[5]āva[du Si]mha-nāyaṟṟu apara-[pa]³ [m]
 V[iyā]la-kkiḷa[m]ai[yum pe]ṟṟa⁴

“In the 15th year (of the reign) of king [Parakēsa]rivarman *alias* the emperor of the three worlds, the glorious **Vikrama-Chōḷadēva**,— [on the day of], which corresponded to a Thursday and to the [*tithi*] of the second fortnight of the month of **Simha**.”

This date does not admit of verification.

E.—KULOTTUNGA-CHOLA III.

66.—In the Vāmanapurīśvara temple at Tirumāṇikuḷi.⁵

- 1 Svasti śrī [||*] Puyal peruga
 3 kō=Pparakēsariparmanar-āṇa Tribhū(bhu)vaṇaśakra[va]ttigaḷ śrī-
 Kulōttuṅga-Śōḷadēvaṟṟku y[ā]ṇḍu ṇu(mū)[n]ṟāvadu Simha-nāyaṟṟu
 apara-bha(pa)kshattu pañchamiyum Tīṅgaḷ-kiḷamaiya(yu)m peṟṟa Aśvati-nāḷ.

“In the third year (of the reign) of king **Parakēsarivarman** *alias* the emperor of the three worlds, the glorious **Kulōttuṅga-Chōḷadēva**,— on the day of **Aśvini**, which corresponded to a Monday and to the fifth *tithi* of the second fortnight of the month of **Simha**.”

A date of the month of **Simha** of the third year of **Kulōttuṅga-Chōḷa III.** would be expected to fall in A.D. 1180, and in my opinion this date undoubtedly corresponds to the 12th August A.D. 1180, which was the 16th day of the month of **Simha**, and on which the 5th *tithi* of the dark half (of *Śrāvaṇa*) ended 9 h. 34 m., while the *nakṣatra* was **Aśvini** for 3 h. 17 m., after mean sunrise. But the day was a Tuesday, not a Monday.⁶

67.—In the Bhaktaparādhiśvara temple at Gidaṅgil.⁷

- 1 Svasti śrī [||*] Kō=Pparakēsarivanmar-āṇa Tribhuvanaśakravarttigaḷ śrī-Kulōttuṅga-
 Śōḷadēvaṟṟku
 2 yāṇḍu 3vadu Simha-nāyaṟṟu irubattē[ān=di[yadi*]y=āṇa Budan-kiḷamai peṟṟa
 Aśvati-nāḷ.

“In the 3rd year (of the reign) of king **Parakēsarivarman** *alias* the emperor of the three worlds, the glorious **Kulōttuṅga-Chōḷadēva**,— on the day of **Aśvini**, which corresponded to a Wednesday which was the twenty-seventh solar day of the month of **Simha**.”

¹ The year A.D. 1118 would yield no satisfactory equivalent for this date.

² No. 404 of the Government Epigraphist's collection for 1902.

³ Read *-pakshattu*; the *tithi* is lost.

⁴ The *nakṣatra* is lost.

⁵ No. 165 of the Government Epigraphist's collection for 1903; *South-Ind. Inscr.* Vol. III. No. 85.

⁶ On Monday, the 11th August A.D. 1180, the 5th *tithi* of the dark half commenced 8 h., and the *nakṣatra* was **Aśvini** from 3 h. 56 m., after mean sunrise.

⁷ No. 226 of the Government Epigraphist's collection for 1903.

Under the preceding date it has been stated that the *nakshatra* was *Āśvinī* on the 16th day of the month of *Simha* of the third year of the king's reign; *Āśvinī* therefore cannot have been the *nakshatra* on the 27th day of the same month. Nor would the weekday be correct; for the 27th day of *Simha* of the third year would be Saturday, the 23rd August A.D. 1180 (when the *nakshatra* was *Uttara-Phalgunī*).—I have not found any year of the reign of *Kulōttuṅga-Chōla III.* for which the date would be correct.

68.—In the *Vāmanapurīśvara* temple at *Tirumāṇikūḷi*.¹

- 1 Svasti śrī [||*] Tiribuvāṇachchakravattigaḷ śrī-Vīrarājēndira-Śōḷadēvaṅku yāṇḍu
ēḷāvadu *Simha*-[nāyaṅ]ṇu irubattāṇ=diyadi āṇa Budan-kiḷamaiyum
pūrvha(rvva)-pakshattu chchatu[r*]daśiyum=āṇa² Śadaiya-
2 tu nāḷ.

“In the seventh year (*of the reign*) of the emperor of the three worlds, the glorious *Virarājendra-Chōḷadēva*,³—on the day of *Śatabhishaj*, which was the fourteenth *tithi* of the first fortnight and a **Wednesday**, which was the twenty-sixth solar day of the month of *Simha*.”

The 26th day of the month of *Simha* of the 7th year of *Kulōttuṅga-Chōla III.* corresponds to **Wednesday**, the 22nd August A.D. 1184.⁴ On this day the 14th *tithi* of the bright half (of *Bhādrapada*) ended 13 h. 19 m., and the *nakshatra* was *Śatabhishaj*, by the equal space system and according to *Garga* from 1 h. 19 m., and by the *Brahma-siddhānta* from 1 h. 58 m., after mean sunrise.

If this were a date of *Rājendra-Chōla III.*, it would be quite incorrect.

69.—In the *Darbhāraṇyōśvara* temple at *Tirunaḷḷār*.⁵

- 1 Svasti śrī [||*] Tiribuvāṇachchakravattigaḷ Madurai koṇḍu Pāṇḍiyan muḍi-
ttalaiyum koṇḍ-arūḷiya śi-Kulōttuṅga-Śōḷadēvarkku [y]āṇḍu 17vadu Kumba-
[n]āyāṅṇu pūrvā-pattisattu⁶ ti[tā]yaiyum⁷ Tiṅgaṭ-kiḷamaiyum peṇṇa Uttiraṭṭādi-
nāḷ.

“In the 17th year (*of the reign*) of the emperor of the three worlds, the glorious *Kulōttuṅga-Chōḷadēva*, who, having taken *Madurai*, was pleased to take also the crowned head of the *Pāṇḍya*,—on the day of *Uttara-Bhādrapadā*, which corresponded to a **Monday** and to the second *tithi* of the first fortnight of the month of *Kumbha*.”

The date corresponds to **Monday**, the 13th February A.D. 1195, which was the 21st day of the month of *Kumbha*, and on which the second *tithi* of the bright half (of *Phālguna*) commenced 1 h. 55 m. after mean sunrise, while the *nakshatra* was *Uttara-Bhādrapadā*, by the *Brahma-siddhānta* and according to *Garga* the whole day, and by the equal space system from 3 h. 17 m. after mean sunrise.

70.—In the *Kṛipāpurīśvara* temple at *Tiruveṇṇainallūr*.⁸

- 1 Svasti śrī [||*] Pū maruviya diśaimugattōn
Tiribuvāṇachchakravartigaḷ Maduraiyum Pāṇḍiyan muḍi-ttalaiyūn=goṇḍ-arūḷina

¹ No. 164 of the Government Epigraphist's collection for 1902.

² The *du* of “*daśi*” is entered below the *śi*.

³ The name *Virarājendradēva* (II.) is applied to *Kulōttuṅga III.* in two inscriptions of the 5th year at *Chidambaram* (Nos. 121 and 122 of 1887-88).

⁴ The *Simha-samkrānti* took place 16 h. 48 m. after mean sunrise of the 27th July A.D. 1184.

⁵ No. 395 of the Government Epigraphist's collection for 1902.

⁶ Read *-pakshattu*.

⁷ Read *dvitīyayum*.

⁸ No. 313 of the Government Epigraphist's collection for 1902.

śrī-Kulōttuṅga-Śōḷadēva[ṛ]ku yāṇḍu 17āvadu Miduna-nāyaṛ[ṛu] apara-pakshattu
traī(trā)yōdasiyum Viyāḷa-kkiḷamaiyum peṛṛa Urōṣaṇi-[nā].

“In the 17th year (*of the reign*) of the emperor of the three worlds, the glorious Kulōttuṅga-Chōḷadēva, who was pleased to take Madurai and the crowned head of the Pāṇḍya,—on the day of Rōhiṇī, which corresponded to a **Thursday** and to the thirteenth *tithi* of the second fortnight of the month of **Mithuna**.”

The date undoubtedly corresponds to **Thursday, the 8th June A.D. 1195**, which was the 13th day of the month of **Mithuna**, and on which the *nakshatra* was **Rōhiṇī** for 9 h. 51 m. (or 9 h. 12 m.) after mean sunrise. As the 13th *tithi* of the dark half (of **Jyāishṭha**) ended on this day only a minute or two after true sunrise, I should have expected the writer to quote the 14th *tithi* instead of the 13th.

71.—In the Ikshupuriśvara temple at Kōvilvenni.¹

1 T[i]r[i]buvānāchchakkaravatt[i]gaḷ Ma-
2 duraiyum Paṇḍiyan muḍi-ttalaiyūṇ-go[n]ḍ-aruliya [ś]i-[Ku]-
3 lōttuṅga-Śōḷadēvaṛkku yā[n]ḍu pattonbadabadu=Kkani-²nā-
4 yaṛṛu=ppūṛ[va*]-pakshattu navamiyum Tiṅga[ḷ]-kiḷamaiyum peṛṛa At[ta]-
5 nā.

“In the nineteenth year (*of the reign*) of the emperor of the three worlds, the glorious Kulōttuṅga-Chōḷadēva, who was pleased to take Madurai and the crowned head of the Pāṇḍya,—on the day of **Hasta**, which corresponded to a **Monday** and to the ninth *tithi* of the first fortnight of the month of **Kanyā**.”

The date is intrinsically wrong because the *nakshatra* on the 9th *tithi* of a bright half in the month of **Kanyā** cannot be **Hasta**. The equivalent of the date apparently is **Monday, the 2nd September A.D. 1196**, which was the 6th day of the month of **Kanyā**, and on which the 9th *tithi* of the bright half (of **Bhādrapada**) ended 22 h. 22 m. after mean sunrise. The *nakshatras* on this day were **Mūla** and **Pūrvāṣāḍhā**.

72.—In the Vāmanapuriśvara temple at Tirumāṇikulī.³

1 S[va]sti śrī [ḷ]* T[iribu]vānāchchakkarā[va]ttiṅga[ḷ] Ma[d]urai koṇḍu Pāṇ[ḍiya]ṇ
muḍi-ttalai-
2 yūṇ-goṇḍ-aruliṇa śrī-Kulōttuṅga-Śōḷadēvaṛku y[ā]ṇḍu pattonbadā-
3 vadu Rishabha-nāyaṛṛu āṇ=diyadiy-āṇa pūrvva-pakshattu dvādasīyum Budāṇ-
kiḷam[ai]yum peṛṛa [A]-
4 ttattu nā.

“In the nineteenth year (*of the reign*) of the emperor of the three worlds, the glorious Kulōttuṅga-Chōḷadēva, who, having taken Madurai, was pleased to take also the crowned head of the Pāṇḍya,—on the day of **Hasta**, which corresponded to a **Wednesday** and to the twelfth *tithi* of the first fortnight, which was the sixth solar day of the month of **Rishabha**.”

The date corresponds to **Wednesday, the 30th April A.D. 1197**, which was the 6th day of the month of **Rishabha**,⁴ and on which the 12th *tithi* of the bright half (of **Vaiśākha**) ended 19 h. 37 m., while the *nakshatra* was **Hasta**, by the equal space system and according to Garga for 7 h. 13 m., and by the **Brahma-siddhānta** for 3 h. 56 m., after mean sunrise.

¹ No. 397 of the Government Epigraphist's collection for 1902.

² Read *pattonbadāvadu=Kkani*.

³ No. 161 of the Government Epigraphist's collection for 1902.

⁴ The **Rishabha-samkrānti** took place 14 h. 4 m. after mean sunrise of the 24th April A.D. 1197.

73.—In the Vāmanapurīśvara temple at Tirumāṇikuḷi.¹

- 1 Svasti śrī [||*] Tiribuvanachchakkaravarttiḡa[!] Maduraiyum Ūlamum Pāṇḍiyan
muḍi-ttalaiyūṅ=gonḍ-arul[i]ya śrī-Kulōttuṅga-Śōḷadēva[r*]kku yāṇḍu 21vadu
Mēsha-n[ā]yaṅṅu pūrvva-[pa*]kshattu daśamiyum Budan-kiḷamaiyu[m] peṇṇa
[Ma]gattu nāḷ.

"In the 21st year (*of the reign*) of the emperor of the three worlds, the glorious Kulōttuṅga-Chōḷadēva, who was pleased to take Madurai, Ūlam and the crowned head of the Pāṇḍya,—on the day of Maghā, which corresponded to a Wednesday and to the tenth *tithi* of the first fortnight of the month of Mēsha."

The date corresponds to Wednesday, the 7th April A.D. 1199, which was the 14th day of the month of Mēsha, and on which the 10th *tithi* of the bright half (of Vaiśākha) ended 23 h. 39 m., while the *nakshatra* was Maghā, by the equal space system for 22 h. 20 m., by the Brahma-siddhānta for 7 h. 53 m., and according to Garga for 10 h. 30 m., after mean sunrise.

74.—In the Vāmanapurīśvara temple at Tirumāṇikuḷi.²

- 1 Svast[i] śr[ī] [||*] Pu[ya]l vāyttu
4 kō=Pparakēśaripaṇmar=āṇa Tiribuvanachchakkaravarttiḡa[!]
Maduraiyum=Ūlamuṅ=gonḍu Pāṇḍiyan muḍi-ttalaiyūṅ=gonḍ-arul[i]ya śrī-Kulōt-
5 tuṅ[ga]-Śōḷadēvarkku yāṇḍu 21vadu Rishabha-nāyaṅṅu pūrvva-pakshattu tri(tra)yō-
daśiyum Śani-kiḷamaiyum peṇṇa Attatti=nāḷ.

"In the 21st year (*of the reign*) of king Parakēśarivarman *alias* the emperor of the three worlds, the glorious Kulōttuṅga-Chōḷadēva, who, having taken Madurai and Ūlam, was pleased to take also the crowned head of the Pāṇḍya,—on the day of Hasta, which corresponded to a Saturday and to the thirteenth *tithi* of the first fortnight of the month of Rishabha."

A date of the month of Rishabha of the 21st year of the reign of Kulōttuṅga-Chōḷa III. would be expected to fall in A.D. 1199, but for that year this date is incorrect, and I have not found any other year of the king's reign for which it would be correct. Such being the case, I feel certain that the month of Rishabha has been quoted erroneously instead of Mēsha. For this month the date regularly corresponds to Saturday, the 10th April A.D. 1199, which was the 17th day of the month of Mēsha, and on which the 13th *tithi* of the bright half (of Vaiśākha) ended 22 h. 48 m. after mean sunrise, while the *nakshatra* was Hasta, by the equal space system and according to Garga the whole day, and by the Brahma-siddhānta for 21 h. 40 m. after mean sunrise.

F.—RAJARAJA III.

75.—In the Tirumālīśvara temple at Māgaral.³

- 1 i-ttē[varkku] yāṇḍu nālāvadu Mid[u]ṇa-[nāya]r[ru] apara-
pakshat[t]u=ppaṇchamiyun=D[i]ṅga[t-ki]lamaiyum peṇṇa Śadaiyattu nāḷ.

"In the fourth year (*of the reign*) of this king,⁴—on the day of Śatabhishaj, which corresponded to a Monday and to the fifth *tithi* of the second fortnight of the month of Mithuna."

The date corresponds to Monday, the 22nd June A.D. 1220, which was the 29th day of the month of Mithuna, and on which the 5th *tithi* of the dark half (of Āshāḍha) ended 15 h.

¹ No. 169 of the Government Epigraphist's collection for 1902.

² No. 170 of the Government Epigraphist's collection for 1902.

³ This is an earlier date of the same reign which is quoted in No. 76 below.

⁴ Viz. Rājārāja III.

56 m., while the *nakshatra* by the equal space system was *Satabhishaj* for 4 h. 36 m., after mean sunrise.

76.—In the Tirumālīśvara temple at Māgaral.¹

1 T[i]r[i]buvaṇachchak[ka]ravatt[i]ga[l] śrī-Rāśarāśadēvaṅku yāṇ[du]
5[va]ḍu Simha-nāyaṅgu a[pa]ra-[pa]kshattu pañchamiyum Buda[ṇ]-
k[i]lāmaiyum [p]eṅga Aśvat[i]-nāl.

“In the 5th year (of the reign) of the emperor of the three worlds, the glorious Rājarājadēva,—on the day of Aśvinī, which corresponded to a Wednesday and to the fifth *tithi* of the second fortnight of the month of Simha.”

The date corresponds to Wednesday, the 19th August A.D. 1220, which was the 24th day of the month of Simha, and on which the 5th *tithi* of the dark half (of Bhādrapada) commenced 10 h. 38 m., while the *nakshatra* was Aśvinī for 18 h. 24 m., after mean sunrise.—As the 5th *tithi* commenced very late in the day, I consider it probable that it has been quoted erroneously instead of the 4th.

77.—In the Ikshupurīśvara temple at Kōvilveṇṇi.²

1 [Sva]sti śrī [l*] Tiribuvaṇachchakkara-
2 vattigal śrī-I[r]ājarājadēvaṅku
3 yāṇḍu 6ā[vad]u edir=ām=ā[n]-
4 ḍu Tulā-nā[ya]ṅ[ru] pūrva-[pa*]kshat-
5 tu saptamiyum Viyāla-[k]k[ila]mai-
6 [y]um peṅga Uttirāḍattu [n]ā[l*].

“In the year which was opposite the 6th year (of the reign) of the emperor of the three worlds, the glorious Rājarājadēva,—on the day of Uttarāśhāḍhā, which corresponded to a Thursday and to the seventh *tithi* of the first fortnight of the month of Tulā.”

The date corresponds to Thursday, the 13th October A.D. 1222, which was the 16th day of the month of Tulā, and on which the 7th *tithi* of the bright half (of Kārttika) ended 11 h. 33 m., while the *nakshatra* was Uttarāśhāḍhā, by the equal space system and according to Garga for 13 h. 8 m., and by the Brahma-siddhānta for 6 h. 34 m., after mean sunrise.

78.—In the Ādiyappaṇ temple at Kil-Kāśākūḍi.³

1 Rājarājadēvaṅku yāṇḍu pattāvadu Mēsha-nāyaṅgu apara-pakshattu
aṣṭamiyum Śevvāy-kkīlāmaiyum peṅga Avittattu nāl.

“In the tenth year (of the reign) of Rājarājadēva,—on the day of Śravishṭhā, which corresponded to a Tuesday and to the eighth *tithi* of the second fortnight of the month of Mēsha.”

The date corresponds to Tuesday, the 21st April A.D. 1226, which was the 28th day of the month of Mēsha, and on which the 8th *tithi* of the dark half (of Vaiśākha) ended 10 h. 16 m., while the *nakshatra* was Śravishṭhā, by the equal space system and according to Garga for 19 h. 3 m., and by the Brahma-siddhānta for 19 h. 42 m., after mean sunrise.

G.—RAJENDRA-CHOLA III.

79.—In the Karavandīśvara temple at Uḍaiyārkkōyil.⁴

1 Svasti śr[i] [l*] T[i]r[i]bu[va*]ṇach[chakkaravatt[i]ga] śr[i]-Irājēndira-Śōla-
dēvaṅku⁵ yāṇḍu 3vadū Miṇa-nā-

¹ No. 217 of the Government Epigraphist's collection for 1901.

² No. 396 of the Government Epigraphist's collection for 1902.

³ No. 392 of the Government Epigraphist's collection for 1902.

⁴ No. 406 of the Government Epigraphist's collection for 1902.

⁵ Read **ḍevarka*.

2 [ya]rru pū[rva]-pakshattu pañ[cha]m[i]yum Śaṇi-kkiḷamaiyu[m] p]erra [U]rōṣaṇi-nāḷ.

"In the 3rd year (of the reign) of the emperor of the three worlds, the glorious Rājendra-Chōḷadēva,— on the day of Rōhiṇi, which corresponded to a Saturday and to the fifth *tithi* of the first fortnight of the month of Mina."

My examination of the four dates Nos. 79-83 has yielded the result that the reign of Rājendra-Chōḷa III. commenced between (approximately) the 21st March and the 8th May A.D. 1246.

This date, No. 79, corresponds to Saturday, the 20th March A.D. 1249, which was the 26th day of the month of Mina, and on which the 5th *tithi* of the bright half (of Chaitra) commenced 0 h. 30 m., while the *nakshatra* was Rōhiṇi for 18 h. 24 m. (or 17 h. 44 m.), after mean sunrise.

80.— In the Raṅganātha temple at Śrīraṅgam.¹

1 Kannarigarāja-pa[ti]kūḷa-kāladanḍa makarālaya-majjita-[Kali]-bala
Vi(vi)ra-Sōmi(mā)śvara-kar-āmukta-pāda-[vi]rābharāṇa
2 Tiribuva[ṇa]chchakkaravattigaḷ śrī-Rāṣēṇḍira-Śōḷadēvarkku yāṇḍu
7āvadu Magara-nāyaṛru apara-pakshattu aṣṭami[y]um Budan-k[i]ḷamaiyum
perṛa Śittirai-nāḷ.

"In the 7th year (of the reign) of the emperor of the three worlds, the glorious Rājendra-Chōḷadēva, the hostile rod of death to the Kannariga (*i.e.* Kar-ṇāṭaka) king, he who had drowned the power of the Kali (age) in the ocean, the hero's anklets² on whose feet were put on by the hands of Vira-Sōmēśvara,³ — on the day of Chitrā, which corresponded to a Wednesday and to the eighth *tithi* of the second fortnight of the month of Makara."

The date corresponds to Wednesday, the 25th December A.D. 1252. On this day the Makara-(Uttarāyaṇa)-saṁkrānti took place 13 h. 3 m.,⁴ the 8th *tithi* of the dark half (of Pausa) commenced 0 h. 17 m., and the *nakshatra* was Chitrā, by the equal space system and according to Garga the whole day, and by the Brahma-siddhānta for 21 h. 1 m. after mean sunrise.

81.— In the Rājagōpāla-Perumāḷ temple at Maṇṇārguḍi.⁵

Svasti śrī [||*] Tribuvaṇachchakkaravattigaḷ śrī-Rāja[jē]ndra-⁶[Śōḷa]dēvaṛku yāṇḍu
2lvadu Kaṛkaḍaga-ṇā[yaṛru] a[para-pakshattu ēk]ādaṣiyum Budhaṇ-
kiḷamaiyum perṛa Rōhi[ṇi]-nāḷ.

"In the 21st year (of the reign) of the emperor of the three worlds, the glorious Rājendra-Chōḷadēva,— on the day of Rōhiṇi, which corresponded to a Wednesday and to the eleventh *tithi* of the second fortnight of the month of Karkāṭaka."

The date corresponds to Wednesday, the 30th June A.D. 1266, which was the fourth day of the month of Karkāṭaka, and on which the 11th *tithi* of the dark half (of Āshāḍha) ended

¹ No. 64 of the Government Epigraphist's collection for 1892.

² *Vīr-ābharāṇa* is used in the sense of the Tamil *vīra-kkaḷal*.

³ This implies that the Chōḷa king had defeated the Hoysala king Sōmēśvara and employed him as a servant.

⁴ Ordinarily, therefore, the 25th December A.D. 1252, here described as a day of the month of Makara, would be considered to be the last day of the month of Dhanu.

⁵ No. 105 of the Government Epigraphist's collection for 1867.

⁶ Read -Rājendra-.

10 h. 21 m. after mean sunrise, while the *nakshatra* was *Rôhîṇi*, by the Brahma-siddhânta and according to Garga the whole day, and by the equal space system from 2 h. 38 m. after mean sunrise.

82.—In the Anṇāmalainātha temple at Maṇṇārgudi.¹

- 1 Ti[ru](ri)buvaṇachchak[ka]ravattigaḷ śrī-Rāj[é*]n[di]ra-Śōḷa[d]ēvarkku yāṇḍu 22vada Rishabha-nāyar[ru] [pū]rvva-pakshattu śadurtesiyum Nā[ya]r[ru]-kkīḷamaiyum peṇṇa Viśāgattu nāl.

“In the 22nd year (of the reign) of the emperor of the three worlds, the glorious Rājendra-Chōḷadēva,—on the day of Viśākhā, which corresponded to a Sunday and to the fourteenth *tithi* of the first fortnight of the month of Rishabha.”

The date corresponds to Sunday, the 8th May A.D. 1267, which was the 14th day of the month of Rishabha, and on which the 14th *tithi* of the bright half (of the first *Jyāishṭha*) ended 21 h. 40 m. after mean sunrise, while the *nakshatra* was Viśākhā, according to Garga the whole day, by the Brahma-siddhânta for 22 h. 20 m., and by the equal space system from 3 h. 17 m., after mean sunrise.

83.—In the Raṅganātha temple at Śrīraṅgam.²

- 1 Svasti śrīḥ [||*] Māma-Sōmī(mē)śvara-pratikūla-kāladanḍa [T]iribuvaṇachchakkaravattigaḷ śrī-Rājendra-Śōḷadēvarkku yāṇḍu ēḷavad[iṇ] edir=ām=āṇḍu Vṛīschika-nāyar[ru] pūrvva-[pa]ksha[t]tu pañchamiyum Tiṅgaṭ-kīḷamaiyum peṇṇa Aśvati-nāl.

“In the year which was opposite the seventh year (of the reign) of the emperor of the three worlds, the glorious Rājendra-Chōḷadēva, the hostile rod of death to (his) uncle Sōmēśvara,—on the day of Aśvini, which corresponded to a Monday and to the fifth *tithi* of the first fortnight of the month of Vṛīschika.”

The date is intrinsically wrong because the *nakshatra* cannot be Aśvini on the 5th *tithi* of a bright half in the month of Vṛīschika.—A date of the month of Vṛīschika of the year opposite the 7th, i.e. of the 8th year, of the king's reign would be expected to fall in A.D. 1253; but for that year this date would correspond to Tuesday, the 28th October, when the *nakshatras* were Pūrvāshāḍhā and Uttarāshāḍhā. If the date were one of the 9th year of the king's reign, it would correspond to Monday, the 6th November A.D. 1254, when the *nakshatras* were Uttarāshāḍhā and Śravana.—I am unable confidently to suggest any correction of the original date with which the date would yield a satisfactory equivalent.

No. 25.—KALUCHUMBARRU GRANT OF VIJAYADITYA-AMMA II.

By J. F. FLEET, I.C.S. (RETD.), PH.D., C.I.E.

This record is the one which I have entered as U. in *Ind. Ant.* Vol. XX. p. 271, in one of my papers on the Eastern Chalukya chronology, and from which I have given a short extract (verse 8, line 35 ff.) in the same Journal, Vol. XII. p. 249. I edit it from the original plates, which belonged to Sir Walter Elliot and are now in the British Museum. There is no information as to where they were obtained.

The plates are five in number, each measuring about $8\frac{1}{2}$ " by $4\frac{3}{8}$ ". The first of them is inscribed on one side only; the others are inscribed on both sides. The edges of the inscribed

¹ No. 91 of the Government Epigraphist's collection for 1897.

² No. 65 of the Government Epigraphist's collection for 1892.

surfaces, except the last, were raised into rims, to protect the writing. The outer side of the last plate, having no such rims, is somewhat worn; and a few letters there are more or less illegible. But the rest of the record is in a state of very excellent preservation; and the text of it is quite clear and certain, throughout, except in one place in line 36.—The ring, on which the plates are strung, is about $\frac{1}{8}$ " thick and $4\frac{5}{8}$ " in diameter. It has been cut; but it seems to be the same ring which was attached to the plates, and which had not then been cut, when the record first came under my observation, in 1877 or 1878. The seal, in which the ends of the ring are secured, is circular, about 3" in diameter. It has, in relief on a countersunk surface,—across the centre, a boar, standing to the right (proper left), and the legend *śrī-Tribhuvan[ā*]mku[śa]h*, which presents a motto of the kings of the dynasty and means "the glorious elephant-goad of the three worlds:" the *śa*, which is considerably damaged, stands behind the boar, and the *visarga* is in front of the boar; the rest of the legend is in one line above the boar. Above these, there is an elephant-goad, with the sun and moon above it. And, below the boar, there is a floral device, apparently an expanded water-lily shewing seven or eight petals.—The characters belong to the southern class of alphabets, and are of the regular type of the locality and period to which the record belongs. They range in size from a little more than $\frac{1}{8}$ " to nearly $\frac{1}{4}$ ". The engraving, though good, is not very deep; and, the plates being substantial, the letters do not shew through on the reverse sides. Marks of the working of the engraver's tool can be seen in many places, both in the interiors of the letters, and in the copper which was pushed up by the tool at the sides of them; such marks on the sides of the letters, caused in the same way, can be seen very clearly in the lithograph of the Korumelli plates of Rājarāja I.¹ The lingual *ç* is distinguished from the dental *d* by a slight but marked prolongation upwards of the end of the character. The record presents final forms of *k* in line 17, of *t* in lines 8, 29, 31, 32, 42, 60, and 73, of *n* in lines 11 and 31, and of *m* in lines 10, 12, 13, 14 (twice), 15, 35, and 71. In line 15 it presents a peculiar mark of punctuation, regarding which reference may be made to the foot-note to that passage. As regards palaeography,—the guttural *ñ* does not occur. The *kh*, *j*, *b*, and *l*, all present the later cursive forms, throughout. The initial short *i* occurs three times; once in line 43, and twice in line 66. In each instance, it is of the old square type, but the actual form of it presents the following abnormal feature. The full form of the old square initial short *i* of the alphabet with which we are concerned, consisted of an upper component which may be likened to the outstretched wings of a hovering bird, and of a separate bottom part which consisted sometimes of two circles, as may be seen very clearly in *iti*, the last word of the Haidarābād plates of Pulakēśin II. of A.D. 612;² and sometimes of two points or dots, as may be seen in *iva*, line 15, No. 15, and in *iv=*, line 40, the last *akshara* but four, of the Diggubarru grant of Chālukya-Bhīma II. of the period A.D. 934 to 945.³ The peculiarity in the present record is, that the ends of the upper component have been brought right down to the lower line of the writing, and the bottom components have been omitted. The form of the letter thus presented is not a transitional form, but is a variety of the old square type. It may be characterised as more or less of a freak. But it cannot be stamped as a mistake. I have found one similar instance, in the word *iti* in line 23 of the Kolavennu plates of the period A.D. 934 to 945;⁴ and there it might perhaps be treated as a mistake, because the two bottom components are duly shewn in that record, as points, in *indur*, line 19, and *itham*, line 22. In the present record, however, there is no such contrast: the abnormal form only is presented; and it was plainly intended.—In lines 73, 74, there is a Telugu passage, for the translation of which I am indebted to Dr. Hultzsch; and lines 65, 66 present some Telugu words, including the genitive *Idiyūri*. But, with those exceptions, the language is Sanskrit throughout. There are two of the customary benedictive and imprecatory verses in

¹ *Ind. Ant.* Vol. XIV. p. 62, Plate iv. a, the last four or five lines, and Plate v.

² *Id.* Vol. VI. p. 73, Plate.

³ *Id.* Vol. XIII. p. 214, Plate.

⁴ *South-Ind. Inscri.* Vol. I. p. 45. A lithograph, however, has not been given there; and I am quoting from ink-impressions.

lines 68 to 70, and seventeen ordinary verses in the body of the record, with one more, in line 72 f., which refers to the *ājñapti*, the writer, and the composer of the record.—In respect of orthography, we need note only (1) the incorrect *saṁdhi*, made by the use of an epenthetic *m*, in *brahmanyam=Attili*, for *brahmanya Attili*, or more correctly *brahmanyō=Ṭṭili*, in line 49;¹ (2) the omission to combine the *t* and *s* in *saṁdhi* in *sat-saraṇam*, line 39, and *śrīmat śrī*, line 59-60; (3) the omission of the *visarga* in *chāru-śrī*, for *chāru-śrīḥ*, line 55-56, in accordance with an optional rule of Southern India,—taught, Professor Kielhorn tells me, in the *Vyāsāśikshā*,—which permits the omission of a *visarga* before a sibilant that is followed by any consonant, hard or soft;² (4) the doubling of *s* before *y*, once, in *tassya*, line 65; and (5) the use of *s* for *ś* three times, in *aśau*, lines 17, 41, and *vitrāśa*, line 18.

The inscription is a record of the Eastern Chalukya king Amma II., otherwise called Vijayāditya VI. It is not dated. But we know, from other sources,³ that he was anointed to the sovereignty on Friday, 5th December, A.D. 945, and reigned for twenty-five years. It registers the grant of a village named Kaluchumbarru, in the Attilināṇḍu province (*vishaya*),⁴ to a Jain teacher named Arhanandin, belonging to the Valahāri gaṇa and the Aḍḍakali gachchha, for the purpose of providing for repairs to the charitable dining-hall of a Jain temple called Sarvalōkāśraya-Jinabhavana. The grant was evidently made by Amma II. himself; but it was “caused to be given” by a certain lady named Chāmekāmbā, who belonged to the Paṭṭavardhika lineage and was a pupil of Arhanandin: on this point, see page 182 below. The Telugu passage at the end of the record mentions a present made by Arhanandin himself to the writer of the record.

To the identification of the places referred to in this record, we are led by the mention of the Attilināṇḍu vishaya in line 49. This province evidently took its appellation from a town named Attili, which still exists in the Tanuku tāluka of the Gōdāvarī district, Madras Presidency; in the Indian Atlas sheet No. 94 (1899), it is shewn as ‘Uttellee,’ in lat. 16° 41', long. 81° 39', seven miles south-west-half-west from Tanuku. The name of the village that was granted, is presented as Kaluchumbarru in line 61, and in line 73 as Pedda-Kaluchuvubarru; this latter appellation marks it as being then the larger or older of two villages bearing the same name. It is the ‘Kunsamurroo’ of the map, the village-site of which is about three miles south-by-west from Attili; the modern form of the name is to be explained by the not infrequent interchange of *l* and *n*, and by a transition of *ch* into *s*. Of the other places, mentioned in specifying the boundaries of Kaluchumbarru, Āruvilli, on the east, is the ‘Arraveelee’ of the map, the village-site of which is one mile towards the south-east from that of ‘Kunsamurroo;’ and Korukolanu, on the south, is ‘Corecolloo,’ one mile and a half south-west from ‘Kunsamurroo;’ and the Yidiyūru of line 64, on the west, mentioned again as Idiyūru in line 66, is ‘Eedooroo,’ one mile and a half west-north-west from ‘Kunsamurroo.’ The other names cannot be identified,

¹ With this instance, compare the similar use of *m* in *Sāryyasutam=iva* and *Vṛikōdaram=iva*, in Vol. III. above, p. 4, lines 4, 5; and that passage presents also an epenthetic *v*, in *niravadya-vuddāra*, for *niravady-ōddāra*. We have a somewhat similar use of *m* in *Kalpalu(dru)mam=iv* and *Jandṛddanam=iv* in *Ind. Ant.* Vol. XVIII. p. 267, lines 7, 8; line 7 of that record, however, presents also *savitāram=iv=ōdayavantam* for *savit=śv=ōdayavdn*, which indicates the use, in the other two instances, of the accusative for the nominative, rather than of an epenthetic *m*.—Originally, not knowing of the existence of the modern Attili, I thought that the present reading ought to be corrected into *brahmany[ō*] Mattili*. And that was how I came to present the name of the district as Mattilināṇḍu, in *Ind. Ant.* Vol. XX. p. 271.

² In his *South-Ind. Palaeo.* p. 81, Dr. Burnell said:—“In S. India the alternative allowed by the grammarians ‘of assimilating visarga to a following sibilant is almost universally accepted, and the reduplication of the sibilant ‘then omitted.’ This remark covers the case in question, but also includes more; it would justify the omission of a *visarga* before a sibilant which is not followed by a consonant.”

³ See *Ind. Ant.* Vol. XX. p. 271.

⁴ Regarding my having previously taken the name of this province as Mattilināṇḍu (*Ind. Ant.* Vol. XX. p. 271), see note 1 above.

unless Yullikodamaṇḍru, on the north, is 'Komera,' about two and a half miles north-west-by-north from 'Kunsamurroo.'

The Attili country is mentioned again, as the Attili dēśa, in the Chellūr plates of A.D. 1143, where, we can now see, the correct reading is, — dēśe-sāv=Attil-iti kshītitala-viditā prādād Kāṭa-daṇḍādhināthah,¹— "this same Kāṭa, the leader of the forces, gave to learned Brāhmaṇas the Maṇḍadoṛṇu *agrahāra*, together with the village of Pondaṇḍu, in the district known on the earth by the name of Attili." The Maṇḍadoṛṇu *agrahāra*, it may be added, seems to be the 'Mamdooroo' of the Atlas sheet, about four miles south-east from Attili, and two miles on the east of 'Kunsamurroo.'

* * * * *

Differing from all the records of the Western Chalukyas of Bādāmi, and from some of the other records of the series to which it itself belongs,² this record presents the family-name, in line 5-6, in prose, as Chālukya, with the long *ā* in the first syllable. It does the same, again, in prose, in line 30, in mentioning the king Chālukya-Bhīma I. But in line 52 it presents the family-name as Chalukya, with the short *a*; this instance is in verse.

In order to introduce a play upon words in connection with the incarnation of the god Vishṇu as a dwarf, the composer has presented the name of the founder of the dynasty as Kubja-Vishṇu (line 7), instead of using the full form Kubja-Vishṇuvardhana.

In connection with Vijayāditya III., it may be noted that this record, following some others, presents in line 15, in verse, in the form of Guṇaga, a *biruda*, belonging to him, which in the Masulipatam(?) plates of Chālukya-Bhīma II., of the period A.D. 934 to 945, is presented as Guṇaka.³ And in the same verse, just after that, it describes him as *aṅkakāras-sākshāt*. As *guṇaka* means 'a calculator, reckoner,' and *aṅka* means 'a numerical figure,' I originally took the expression *aṅkakāras-sākshāt* as meaning "a thorough arithmetician," and as explaining the *biruda*.⁴ And it is, in fact, difficult to avoid thinking that the composer of this record may have had in view some kind of an explanation of the *biruda* as presented here. The full form of the *biruda*, however, was Guṇakenallāta, "he who is good, excellent, or beautiful on account of his virtues," as given in the Kolavennu plates which also were issued in the time of Chālukya-Bhīma II.⁵ And, though *aṅkakāra* may have to be here invested with a secondary meaning, there is no doubt that it also stands for the word which in the southern records is usually written *aṅkakāra*, with the Drāviḍian *r*, and that the expression used by the composer is properly and primarily to be translated by "a veritable champion."⁶ Like all the other records, with one exception, this record states that Vijayāditya III. reigned for forty-four years, and does not, in reality, add an alternative statement of forty-eight years; see note 8 on page 189 below. The sole exception is the Piṭhāpuram plates of Vīra-Chōḍadēva of A.D. 1092-93, which specify forty years;⁷ this is to be attributed to a careless omission of the syllables *tuścha* or *śchatu*.

¹ *Ind. Ant.* Vol. XIV. p. 58, line 49 f. For the point that the real date of this record is the 24th March, A.D. 1143,—not the 23rd March, A.D. 1132, as suggested by me in *id.* Vol. XX. p. 285,—see page 9 f. above, where Prof. Kielhorn has shewn that the record presents *rasa-vīśikha* by mistake for *vīśikha-rasa*.

² Regarding the variants of the family-name in, respectively, the Western and the Eastern records, see my *Dynasties of the Kanarese Districts* (in the *Gazetteer of the Bombay Presidency*, Vol. I. Part II.), p. 336, note 2, and *Ind. Ant.* Vol. XX. p. 95, note 10.

³ Vol. V. above, p. 136, line 12-13.

⁴ *Ind. Ant.* Vol. XX. p. 102.

⁵ *South-Ind. Inscre.* Vol. I. p. 44, line 12.—I have already made some remarks on this *biruda* in Vol. VI. above, p. 179, note 2.

⁶ For the meaning of *aṅkakāra*, see Vol. VI. above, p. 56, note 1. To what has been said there, it may be added that Monier-Williams' Sanskrit Dictionary, revised edition, gives *aṅkakāra* as used in the *Bālarāmdyāya* to mean 'a champion chosen by each side to decide a battle.'

⁷ Vol. V. above, p. 76, line 26. For the exact year of this record, see Vol. VI. above, p. 336.

Differing from all the other records, this one says, in line 30 f., that Vikramāditya II. reigned for nine months. Of the other records, some say eleven months, and some say one year.¹

If taken as it actually stands in line 31 f., in prose, this record would represent Yuddhamalla II. as *Tālapa-rāj-āgrajajanman*, "born from an elder brother of king Tālapa." This statement, however, is not borne out by the other records which mention the parentage of Yuddhamalla II. There is, indeed, one record, the Diggubayru grant of the period A.D. 931 to 945, which, in verse, speaks of him as Malla, and describes him as *Tāha-jyēshtha-suta*;² and this expression, while ordinarily and most naturally meaning "eldest son of Tāha," might also be rendered as meaning "son of an elder brother of Tāha." The other records, however, are more explicit; and, it may be added, they all speak of him by his full name of Yuddhamalla. The Paḍamkalūru grant, of the period A.D. 945 to 970, describes him, in verse, as *Tālapa-rājasya sūnu*,³ "son of king Tālapa." The Masulipatam plates, of the same period, describe him, in prose, as *Tāl-ādhipa-sūnu*,⁴ "son of the lord Tāla." The 'Yelivarru' plates, also of the same period, describe him, in prose, as *Tālapa-rājasya suta*,⁵ "son of king Tālapa." And the Korumelli plates, of the period A.D. 1022 to 1063, the Chellūr plates of A.D. 1090-91, and the Piṭhāpuram plates two years later in date, describe him, in prose, as *tat-Tāḍapa-rājasya suta*,⁶ "son of that same king Tāḍapa." And, in view of those statements, we may safely decide that there is a mistake of some kind in the present record; the explanation perhaps is that the composer used the word *agrajanman*, 'first-born,' in the sense, whether correctly or not, of 'eldest son,' instead of in its usual meaning of 'elder brother,' and that either he, or the writer of the record, carelessly repeated the *ja* and so produced the reading which is actually presented but is certainly wrong.

In connection with Chālukya-Bhīma II. (A.D. 934 to 945), whom it calls in line 33-34 simply Bhīma, and in line 41 Rāja-Bhīma, this record mentions, in line 35 ff., the following enemies overthrown by him, namely, Rājamayya, Dhalaga, Tātabikki, Bijja, Ayyapa, Gōvinda, a ruler of the Chōḷas named Lōvabikki, and Yuddhamalla. Yuddhamalla is undoubtedly the Eastern Chālukya king Yuddhamalla II., the immediate predecessor of Chālukya-Bhīma II.; a specific mention of his overthrow and expulsion by Bhīma II. is made in the Paḍamkalūru grant of the period A.D. 945 to 970.⁷ Gōvinda is the Rāshtrakūṭa king Gōvinda IV., for whom we have dates ranging from A.D. 918 to 933-34. Ayyapa is very possibly the Ayyapadeva, doubtless a Nolamba prince of the Nolambavāḍi territory in Mysore, to whom the Western Gaṅga prince, Eṇṇeyappa, lent a force for the purpose of fighting against a certain Vīramahēndra;⁸ and, if so, it probably follows that Vīramahēndra was another *biruda* of Chālukya-Bhīma II., or, rather, was a variant of his *biruda* Gaṇḍamahēndra. Bijja seems to be identical with the Dantivarman, also named Bijja, who is mentioned in the spurious Sūḍi plates, apparently in connection with Banavāṇi, as one of the foes against whom, it says, the Western Gaṅga prince Bātuga II. (A.D. 940 and 953) fought and prevailed.⁹ And Rājamayya is perhaps the Rājavarman who, also, is mentioned in that record, but without any indication as to where his territory lay. Lōvabikki, the ruler of the Chōḷas, is not as yet known from any other sources. To Dhalaga and Tātabikki reference is made in the Kolavennu plates of Chālukya-Bhīma II. himself, in a verse which,

¹ See *Ind. Ant.* Vol. XX. p. 269. And, for the statement of eleven months, add now the Futhapattana plates, see Vol. V. above, p. 76, line 28.

² *Ind. Ant.* Vol. XIII. p. 214, line 30 f.

³ *Id.* Vol. VII. p. 16, line 19.

⁴ Vol. V. above, p. 140, line 15 f.

⁵ *Ind. Ant.* Vol. XII. p. 92, line 21.

⁶ See, respectively, *Ind. Ant.* Vol. XIV. p. 52, line 45; *id.* Vol. XIX. p. 429, line 42; and Vol. V. above, p. 76, line 28.—In line 17 of the Chellūr plates of A.D. 1143 (*Ind. Ant.* Vol. XIV. p. 56; for the correct date of this record, now given, see note 1 on page 180 above), the composer or writer used only the expression *tat-Tāḍapa*, omitting *Tāḍapa-rāja*; with the result that that record practically represents Yuddhamalla II. as a son of Vikramāditya II.

⁷ *Ind. Ant.* Vol. VII. p. 18.

⁸ See Vol. VI. above, p. 47.

⁹ See Vol. III. above, p. 147.

presenting their names in the somewhat different forms of Dhaladi and Tatabikyana, appears to say:—"He, this Rājamārtanḍa (a very sun among kings), piercing (*everything*) in front (of him), having conquered in battle, with his arm, him who was named Tatabikyana, (and also) Dhaladi, causes his fame to be sung by people."¹ We have, however, no information as yet as to the part of the country to which they belonged.

It may be remarked, incidentally, that a *biruda* of Chālukya-Bhima II., not mentioned in this record, which is presented in the Guṇḍugolanu grant of the period A.D. 945 to 970 as, apparently, Kaṛayilladāta,² would have been given more correctly as Kaṛeyilladāta: it means "he in whom there is no spot or blemish" (*kaṛey-illad-āta*); and it answers exactly to the Sanskrit appellation Akalanka.

✓ Chāmekāmbā, who caused the grant to be made, seems to be clearly marked by line 53 as a courtesan. It would appear, therefore, that she was a favourite mistress of the king. And, for a case analogous to this one, we may quote that of the courtesan Vināpōṭi, the *prāṇavallabhā* or "mistress as dear as life" of the Western Chalukya king Vijayāditya, who is mentioned in one of the Mahākūṭa inscriptions as making certain grants to a temple, and whom that record has treated with such respect as to name also her mother and grandmother.³ So, also, the spurious Sūṭi plates claim a grant of some land at that village by the Western Gaṅga prince Bātuga II. for the purposes of a Jain temple founded by his mistress Divalāmbā.⁴

The Paṭṭavardhika lineage (*anvaya*),—to which, as is indicated in line 52 f. of this record, Chāmekāmbā belonged by birth, and in respect of which we are told that the members of it belonged to the retinue of the Chalukya kings,—is mentioned as the Paṭṭavardhini race (*vaṁśa*) in a record of Amma I. (A.D. 918 to 925). That record specifies, as members of it, Kālakampa, who had been a follower of Kubja-Vishṇuvardhana I., and, with his permission, had killed in battle (*a king*) Daddara and seized his insignia; a descendant of Kālakampa, named Sōmāditya; Sōmāditya's son Pritivīyarāja; and Pritivīyarāja's son Bhaṇḍanāditya, also called Kuntāditya, who had been a servant of Vijayāditya IV. (A.D. 918), and to whom the grant of a village, registered in the record, was made.⁵ And another reference to it is to be found in a record of Amma II. (A.D. 945 to 970), which registers the grant of some fields to the Yuvarāja Ballalādēva-Vaḷābhata, also called Boḍḍiya, son of (the lady) Pammavā (of the Paṭṭavardhini family).⁶

¹ *South-Ind. Inscri.* Vol. I. p. 45, line 17 ff. I read the first two *pādas*, from an ink-impression, thus:—Yas-Tatabikyan-ākhyānn=Dhaladi munn-iṛiva Rājamārtanḍau. The verse is in the Āryāgiti metre. At the end of the first *pāda*, *ākhyānn* has of course to be corrected into *ākhyān*. In the second *pāda*, three syllabic instants are wanting; the metre may be set right by reading:—Dhaladim munn-iṛiva Rājamārtanḍōsau. The words *munniṛiva* are Kanarese.

² *Ind. Ant.* Vol. XIII. p. 249, line 17-18.

³ *Id.* Vol. X. p. 103.

⁴ Vol. III. above, p. 184; and see *Ind. Ant.* Vol. XXX. p. 217, No. 81. The expression *svakṛtya-priyā*, in line 70 of the text, should be rendered by "his mistress;" not by "his wife," as was done by me in editing the record. This should perhaps have been recognised by me at the time, from the description of Divalāmbā in line 84 as "the one Rambhā of the world;" and also because, the passage being in prose, the word *paṇṭ* or *hṛdyā* might have been used just as readily as *priyā*, if a wife was really intended. But there are, I think, a few cases in which quite respectable women were likened to Rambhā in respect of their beauty and general charms; and the name itself occurs as the name of Rambhā, the *sādhvī* or "virtuous wife" of the poet Ratnasimha, in the Ratnapur inscription of Prithivīdēva (*Ep. Ind.* Vol. I. p. 50, verse 12). However, we know now that the wife of Bātuga II. was Rāvakanimmaḍi; see Vol. VI. above, p. 71.

⁵ *South-Ind. Inscri.* Vol. I. p. 43

⁶ Vol. V. above, p. 140.

In addition to conveying the village itself, the record recites, in line 70 f., the grant in perpetuity, to a certain Kusumâyudha, son of Kaṭṭalāmbā, of the *grāmakūṭa* or office of *Grāmakūṭa* or headman of the village. The post was evidently that of the village official who is known in Marāṭhi as the Pāṭēl or Pāṭil, and in Kanarese as the Gavuda or Gauḍa.

Of the Kanarese word gavuda or gauḍa, we have various earlier forms, — *gauḍa*,¹ *gavunḍa*,² *gāvunḍa*,³ *gavunḍu*,⁴ *gāvunḍu*,⁵ *gāmunḍa*,⁶ and *gāmunḍu*.⁷ And we can now see that it was derived from the word *grāmakūṭa* itself, through a corruption of *grāma* into some such form as the *gāmvu* which occurs as the termination of certain village-names in the Paiṭhap plates of A.D. 1272,⁸ coupled with, in *kūṭa*, a disappearance of the *k* and a softening of the *t* into *ḍ*, and accompanied by a shifting of the nasality of the first component of the word. It may be added that, in colloquial usage, the modern form *gauḍa* is often nasalised and pronounced *gauṇḍa*; also, that Professor Fischel tells me that the *Dēśinūmamālā*, ii. 69, gives *gāmaūḍa* as the Prākṛit form of *grāmakūṭa*.

It may be remarked here that the Marāṭhi word pāṭēl, pāṭil, can now be distinctly traced back to the earlier word paṭṭakila, which we have in, for instance, the Ujjain plates of A.D. 975 and 1023⁹ and the Bhōpāl plates of A.D. 1200,¹⁰ through an intermediate form paṭṭēla which I have found in a Sanskrit Nāgarī inscription, of about the thirteenth century A.D., at Mañchar in the Poona district, in which a certain person is described, in verse, as *paṭṭēla-varya*, "best or chief of the *paṭṭēlas*." In this case, again, there has been an elision of a medial *k*.

* * * * *

In line 72, the record presents the expression ājñaptiḥ kaṭakādhisaḥ. The word ājñapti means literally 'a command.' But, as has been indicated before now, in such passages as the present one it was employed to denote the Dūtaka or messenger, whose duty it was to communicate the fact and details of a grant to the local authorities.¹¹ What was intended by the word *kaṭakādhisa*, has not been so obvious. But it can now be made clear by a comparison of passages.

¹ Vol. V. above, p. 232, and p. 247, line 34.

² *Ibid.* p. 232.

³ *Ibid.* pp. 214, 261; and *Ind. Ant.* Vol. XII. p. 219, the last line of the text: this last instance is of A.D. 866.

⁴ *Jour. Bo. Br. R. As. Soc.* Vol. X. p. 245, line 48.

⁵ *Ibid.* p. 204, line 1, and p. 245, line 46; the first of these two instances is of A.D. 980.

⁶ *Ind. Ant.* Vol. XI. p. 70, line 17, of about A.D. 750; and *id.* Vol. XIX. p. 144, line 8 ff., of about A.D. 690.

⁷ *Id.* Vol. XII. p. 271, lines 12, 13; this instance is of A.D. 978.

⁸ See *id.* Vol. XXX. p. 517.

⁹ *Id.* Vol. VI. p. 51, line 10, and p. 53, line 7-8. Mr. N. J. Kirtane, who edited those records, recognised the meaning of *paṭṭakila*, and translated it by *pāṭil*.

¹⁰ *Id.* Vol. XVI. p. 254, line 10.

¹¹ See, for instance, *id.* Vol. XX. pp. 18, 96, and Vol. V. above, p. 119.—The word has, indeed, been otherwise rendered, by 'executor'; see *South-Ind. Insere.* Vol. I. pp. 36, 62, and Vol. V. above, p. 71. But that is opposed by such expressions as *ājñā svayam* and *sva-mukh-ājñāyā* in two of the records of the Eastern Gaṅgas of Kalinganagara; see *Ind. Ant.* Vol. XIII. p. 121, line 19, and Vol. III. above, p. 129, line 24. The word *ājñā*, also, means 'a command.' It was, indeed, sometimes used in the same technical sense with *ājñapti*: for instance, another Eastern Gaṅga record says *ājñā mahāmahattara-Gaurīarmm[ā*]*, "the *ājñā* is the *Mahāmahattara Gaurīarman*;" see *Ind. Ant.* Vol. XIII. p. 123, line 24. But in the expression *sva-mukh-ājñāyā* it is to be translated by its ordinary meaning of 'command'; the passage tells us that "this charter of Rājasiṃha has been written, at the command of his (*the king's*) own mouth, by Vinayachandra, son of Bhānuachandra." In the expression *ājñā svayam*, it may have a more technical meaning. But it cannot there mean 'executor'; for, a king would certainly not attend in person to the administration of an endowment made by him. On the other hand, neither would he act as a *Dūtaka*; and Prof. Kielhorn has reminded me of two cases in which the expression *ājñā svayam*, in the transposed form *svayam-ājñā*, "the *ājñā* is Ourselves," is followed by the words *dūtakaś=ch=ātra*, "and the *Dūtaka* in this matter is, etc.," introducing the name of a person who was not the king who is designated by the words *svayam-ājñā*; see *Ind. Ant.* Vol. IX. p. 170, line 21, and p. 175, line 22-23.

We must set aside one instance of an anomalous nature, occurring in the record of the second year of Vishṇuvardhana II. It presents the expression *sva-mukh-ājñāptā*.¹ Here, we have to emend the text, and read either *ājñāptā*, or *ājñāpitā*, or more probably *ājñāptyā*, "by the command of (Our) own mouth," on the analogy of the *sva-mukh-ājñayā* which occurs elsewhere.² And, irrespective of the necessity for emendation, this instance is not to the point. The other instances, in chronological order, are:—

(1) The record of the eighteenth year of Vishṇuvardhana I. recites,—
ājñāptir=Aṭavidurjjayaḥ,³—"the ājñāpti is Aṭavidurjaya, born in the illustrious Matsya family, who has bowed down his enemies by the strength and prowess of his arm."—(2) The record which purports to be of the eighteenth year of Jayasimha I. but is of somewhat doubtful authenticity, recites,—a(ā)jñāptir=Siyaśarman=āśya,⁴—"the ājñāpti of this (*grant*) is Siyaśarman."—(3) A record of the time of Maṅgi-Yuvarāja (A.D. 672 to 696) recites,—ājñāpti Nissaramiji (?),⁵—"the ājñāpti is Nissaramiji (?)."—(4) A record of the time of Vijayāditya II. (A.D. 799 to 843) recites, in verse, ājñāptir=asya dharmmasya Nripārudrô,⁶—"the ājñāpti of this act of religion is the most excellent prince Nripārudra, brother of Narēndramrigarāja-(Vijayāditya II.), born of the Haihaya race."—(5) A record which purports to be of the same period (A.D. 799 to 843) but is of somewhat doubtful authenticity, recites, in verse,—a(ā)jñāptir=asya dharmmasya Boḷama-nām[ā*],⁷—"the ājñāpti of this act of religion is that spotless best of men named Boḷama, a very store of religion, who devotes his thoughts to meritorious actions in this world."—(6) A record of the time of Vijayāditya III. (A.D. 844 to 888) recites, in verse,—ājñāptir=asya dharmmasya Pāṇḍarāṅgaḥ,⁸—"the ājñāpti of this act of religion is the majestic Pāṇḍarāṅga, who like a second Bibhatsu (Arjuna) has overcome all hostility by his valour."—(7) A record of the time of Chālukya-Bhīma I. (A. D. 888 to 918) recites, in verse,—ājñā(jña)ptir=asya dharmmasya Kaḍeyarājaḥ,⁹—"the ājñāpti of this act of religion is the majestic Kaḍeyarāja, whose father's father was Pāṇḍarāṅga who vexed his foes."

(8) A record of the time of Amma I. (A.D. 918 to 925) recites,—ājñāpti[h*] kaṭakarājaḥ,¹⁰—"the ājñāpti is the Kaṭakarāja."—(9) A record of the time of Amma II. (A.D. 945 to 970) similarly recites,—ājñāptiḥ kaṭakarājaḥ,¹¹—"the ājñāpti is the Kaṭakarāja."—(10) Another record of the same period (A.D. 945 to 970) similarly recites,—ājñāptiḥ kaṭakarājaḥ,¹²—"the ājñāpti is the Kaṭakarāja."—(11) Another record of the same period (A.D. 945 to 970) similarly recites,—ājñā(jña)ptiḥ kaṭakarājaḥ,¹³—"the ājñāpti is the Kaṭakarāja."

(12) The present record, also of the time of Amma II. (A.D. 945 to 970) recites, in verse,—ājñāptiḥ kaṭakādhīś[ā*],¹⁴—"the ājñāpti is the Kaṭakādhīśa."—(13) A record of the time of Rājārāja I. (A.D. 1022 to 1063) recites, in prose,—ājñāptiḥ kaṭi(ṭa)kēśo,¹⁵—"the ājñāpti is the Kaṭakēśa."

¹ *Ind. Ant.* Vol. VII. p. 189, line 67, and Vol. VIII. p. 320, Plate.

² See p. 183, above, note 11.

³ *Ind. Ant.* Vol. XX. p. 17, line 20.

⁴ *Id.* Vol. XIII. p. 138, line 28.

⁵ *Id.* Vol. XX. p. 106, line 28. For *ājñāpti*, read *ājñāptiḥ*.

⁶ *Id.* Vol. XX. p. 417, line 51 f. The actual reading of the name, presented in the original, is *nripārudra*.

⁷ Vol. V. above, p. 121, line 25.

⁸ *Ibid.* p. 125, line 34 f.

⁹ *Ibid.* p. 130, line 45 f.

¹⁰ *Ibid.* p. 133, line 36.

¹¹ *Ind. Ant.* Vol. VII. p. 17, line 63. For *ājñāptiḥ*, read *ājñāpti*.

¹² *Id.* Vol. XII. p. 93, line 60.

¹³ *Id.* Vol. XIII. p. 250, line 35.

¹⁴ Page 188 below, line 72.

¹⁵ *Ind. Ant.* Vol. XIV. p. 55, line 113 f. I have previously taken this passage as meaning—"the *ājñāpti* is Kaṭakēśa, son of Rāchiya-Peddēri-Bhīma;" see *id.* Vol. XX. p. 275. But the last words have to be connected with the name of the composer, Chētanabhaṭṭa.

(14) A record of A.D. 1090-91 recites,— dattasy=āśya śāsanasy=ājñaptih pañcha pradhānāḥ,¹—“the ājñapti of this charter, given in the twenty-first year of the glorious and victorious reign, is the five ministers.”—And similarly (15) A record of the same reign, two years later in date, recites,— dattasy=āśya śāsanasy=ājñaptih pañcha pradhānāḥ,²—“the ājñapti of this charter, given in the twenty-third year of the glorious and victorious reign, is the five ministers.”

Now, in the instances Nos. 1, 2, 4, 5, 6, and 7, the word ājñapti unmistakably introduces certain individual persons mentioned by name; and probably also in No. 3, where, however, a continuation of the text may have been lost. And, *rāja* being a frequent enough ending of proper names, it was, therefore, not unnatural that the word *kaṭakarāja* should have been originally taken as, similarly, a personal appellation.

On the other hand, in the instances Nos. 14 and 15, no individual is mentioned by name, and the word ājñapti introduces a body of officials known as the five ministers.

The word *kaṭakēśa*, in No. 13, is a mere variant of the *kaṭakādhiśa* of No. 12; and both these words are fairly capable of being taken as only synonyms of *kaṭakarāja*. We can recognise a decided objection to interpreting *kaṭakarāja* as a proper name, in the fact that it could at least not denote one and the same individual through so long a period as that which is covered by the instances Nos. 8, 9, 10, and 11. And, from a comparison of all the passages, we may finally decide that, as has been suggested as possible some time ago,³ the word *kaṭakarāja*, and, with it, *kaṭakādhiśa* and *kaṭakēśa*, should be taken as denoting an official post, that of the governor or superintendent (*adhīśa*, *īśa*, *rājan*) of the royal camp (*kaṭaka*).

In earlier records, the word *ājñapti* occurs in the Prākṛit forms, used in the same way. of *ānatti* in the ‘Gunapadeya’ plates of Vijaya-Buddhavarman,⁴ and of *ānati* in the Mayidavolu plates of Śiva-Skandavarman.⁵

TEXT.⁶

First plate.

- 1 Om⁷ Svasti Śrīmatām sakala-bhuvana-sa mstūyamāna-Mānavya-sagôtrā-
 - 2 nām Hāriti-putrānām Kauśiki-vara-prasāda-labdha-rājyānām-Mātrigaṇa-pari-
 - 3 pālītānām Svāmi-Mahāsena-pād-ānudyātānām⁸ bhagavan-Nārāyaṇa-prasā-
 - 4 da-samāsādita-vara-varāhalāchchha(c h h a) n-ê kshaṇa-kshaṇa-vasīkṛit-ārāti-
 - 5 maṇḍalānām⁹=aśvamēdh-ava bhṛitā¹⁰nāna-pavitrikṛita-vapushām Chā-
 - 6 lukyānām kulam=alamkarishnōs=Satyāśrayavallabhēndrasya bhrātā [*] Śri(śrī)¹¹-
- patir=vvi-

¹ *Ind. Ant.* Vol. XIX. p. 433, line 113 f. For the exact year of this record, see Vol. VI. above, p. 335.

² *Ind. Ant.* Vol. XX. p. 267, note 5.

³ Vol. V. above, p. 94, line 280.

⁴ *Id.* Vol. IX. p. 102, line 16.—[Compare above, p. 69, note 1. The same Prākṛit form occurs in the Kāśākuḍi plates, *South-Ind. Inscr.* Vol. II. No. 73, l. 106 f.; in the Rāyakōṭa plates, above, Vol. V. No. 8, l. 13; in the Madras Museum plates of Jaṭilavarman, *Ind. Ant.* Vol. XXII. p. 71, l. 75; and in a Tiruvallam inscription, *South-Ind. Inscr.* Vol. III. No. 43, l. 16.—E. H.]

⁵ Vol. VI. above, p. 88, line 27.

⁶ From the original plates.

⁷ Represented by an ornate symbol.

⁸ In the syllable *nām*, the *d* was formed by a direct continuation, upwards, of the last stroke of the *n*, instead of being attached, in the usual way, as a projection to the right of that stroke. This form of the *d* occurs again in the *tyā* of *Satyāśraya*, line 6. It is met with in other places also. But it is not, on the whole, common. And the explanation probably is that, in all such cases, the vowel was at first omitted by the writer and then was inserted on a revision of his work, and that it was formed in this exceptional manner because there was no space in which to make it in the usual way.

⁹ Read *maṇḍalāndm*.

¹⁰ Read *dvabṛitha*.

¹¹ Metre, Śloka (Anuṣṭubh). There are two syllables too many in the fourth *pāda*. An omission of the two syllables *laya* would make the metre correct.

- 7 kramên(n)=âdyô durjjayâd=Balitô hritâm ashtâdaśa samâh Kubja-Vishṇu-
jjishṇu-
8 r=mmahim=apâlayat |(l) Tad-âtma-jô Jayasimhas=trayas-trimśatah [l*] tad-a-

Second plate; first side.

- 9 nuj-Ēndrarâja-nandanô Vishṇuvarddhanô nava | tat-sûnur=Mmaṅgi-Yuvarâjah pa-
10 mcha-vimśa[ti*]m | tat-putrô Jayasimhas=trayôdaśa || Tasya dvaimâtur-
ânujah Ko-
11 kkili[h*] shaṇ=mâsân [l*] tasya j[y*]êshthô bhrâtâ Vishṇuvarddhanas=tam=
uchchâtya sapta-trimśa-
12 tam | tat-sutô Vijayâditya-Bhaṭṭarakô=shtâdaśa | tat-sutô Vishṇu-
13 varddhanah shaṭ-trimśatam | tat-sutô Narêndramṛigarâjas=s-âshṭa-chatvârimśa-
14 tam | tat-putrah Kali-Vishṇuvarddhanô=dhy-arddha-varsham [l*] Tat-sutô
Gunaga-Vijayâditya-
15 s=chatuś-chatvâri[m*]śatam | athavâ¹ Sutas²=tasya jyêshthô Gunaga-
Vijayâditya-patir=a-
16 mkakâras=sâksh[â*]d=Vallabhanripa-samabhyarchchita-bhujah pradhâna[h*] sûrâ-
nâ(nâ)m=api subhata-

Second plate; second side.

- 17 chûḍâmani(ni)r=aśau(sau) chatasras=chatvârimśatim³=api samâ bhûmim=abhunak ||
Tad⁴-bhrâtu-
18 r=yyuvarâjasya Vikramâditya-bhûpatê[h*] śatru-vitrâśa(sa)-krit=putrô dâni
19 Kânina-sannibhah || Jitvâ⁵ samyati Krishṇavallabha-mahâ-daṇḍam sa-dâyâ-
20 dakan=datvâ dēva-muni-dvijâti-tanayô dharmm-ârttham=arttarm⁶=muhuh kri-
21 tvâ râjyam=a[ka*]ṇṭakan=nirupamañ sa[m*]vridham=viddha-praja[m*] Bhimô
bhûpati-
22 r=anvabhū[m*]kta bhuvana[m*] nyâyât=samâs=trimśatam || Tad⁷=anu Vijayâdityas=ta-
23 aya priya-tanayô⁸ mahân=adhika-Dhanadas=s a t y a-t y â g a-p r a t â p a-s a m a-
24 nvitah para-hridaya-ni[r*]bhêdi nâmn=aiva Kollabiganḍa-b h ū p a t i r=a k r i-

Third plate; first side.

- 25 ta shaṇ=mâsân(n) râjyan=naya-sti(sthi)ti²-samyantah || Tasy¹⁰=âgra-sunûr=aparâji-
26 ta-śaktir=Amma-râjah parâjita-par-âvanirâja-râjî(ji)h râj=[â*]bhavad=vidita.¹¹
27 Râjamahendra-nâm[â*] varahâpi sapta saraṇih karuṇâ-rasasya || Tasy=a-
28 tmaja-Vijayâditya-bâlam¹²=uchchâtya s r i-Y u d d h a m a l l-â t m a j a s-T â-
29 lapa-râjô mâsam=âkamm(m)=arakshît || Tam=âhavê vinirjitya
30 Châlukya-Bhima-tanayô Vikramâdityô vikramêp=âkramê

¹ This mark of punctuation, which may be taken either as a single mark or as a double mark, is represented by what is substantially a final s. But it occurs elsewhere, also; for instance, in lines 51 and 53 of the Diggubærru grant, *Ind. Ant.* Vol. XIII, p. 214, and Plate. And it seems to be a recognised variant, not a mistake.

² Metre, Śikharinî.

³ See note 8 on page 189 below.

⁴ Metre, Ślôka (Anushtubh).

⁵ Metre, Śârdûlavikrîdita.

⁶ Read *arttham*.

⁷ Metre, Harinî.

⁸ Read *priyas=tanayô*, as required by the metre. The correction of *nibhêdi* into *nirbhêdi*, in the next line, is required in the same way.

⁹ This *ti* was at first omitted, and then was inserted below the line.


¹⁰ Metre, Vasantatîlaka.

¹¹ The syllable *di* was at first omitted, and then was inserted below the line.


¹² Read *tasya=tmajah Vijayâdityah bâlam*.

Kaluchumbarru Grant of Vijayaditya-Amma II.

i.



iii b.




FLEET.


SCALE 80

W GRIGGS, COLLOTYPE.

iv a. iv a.



v a. v a.



- 31 nikshipya nava māsān pālayat¹ || Tatō Yuddhamallas=Tālapa-rā-
32 j-āgrajajanmā² sapta varshāni grihi(hi)tv=ātishṭhat || Tat³=āntarē vidita-

Third plate ; second side.

- 33 Kollabigaṇḍa-sutō⁴ dvaimāturō vinuta-Rājamahēndra-nāmnah Bhi-
34 m-ādhipō vijita-Bhi(bhi)ma-bala-pratāpaḥ prāchin=disarṇ vimalayann=udī-
35 tō vijētum [[*] Śrīmantam⁵ Rājamayyan=Dhalagam=urutaran=Tātabikkim
pracha-
36 ṇḍa[m*] Bijjam sa[[jam cha]⁶ yuddhē balinam=atitā(ta)rām=Ayyapaṁ bhīmam=
ugraṁ
37 daṇḍam Gōvinda-rāja-pranīhitam=adhikam Chōla-paṁ Lōvabikkim⁷ vi-
38 krānta[m*] Yuddhamallam ghaṭita-gaja-ghaṭan=sannihaty=aika ēva || Bhītān=
āsvā-
39 sayan=sat-saraṇam⁸=upagat[ā*]n=pālayan=kaṇṭakān=utsa n n ā n=k u r v v a n=s u g r i h a-
40 n=karam=apara-bhuvō raṁjayana(n) svañ=jan-augham tanvan=kīrtti[m*] narēndr-
ōchchayam=avana-
41 mayann=arjjayan=vastu-rāśin=ēva śrī-Rāja-Bhimō jagad=akhilam=aśau(sau) dvādaś=ā-

Fourth plate ; first side.

- 42 bdāny=arakshat |(l)| Tasya⁹ Mahēśvara-mū[r*]ttēr=Umā-samān-ākṛitēḥ Kumāra-
samāna[h*] Lō-
43 kamahādēvyāḥ khala yas=samabhavad=Amma-rāja iti vikhyātō(taḥ) |(l)| Yō
rūpēṇa
44 Manōjam vibhavēna Mahēndram=ahimakaram=uru-mahā(ha)sā Haram¹⁰=ari-pura-
daha-
45 nēna nyak-kurvan=bhāti vidita-nirmala-kīrttiḥ [[*] Yad¹¹-bāhu-daṇḍa-karavāla-
vidārit-āri-
46 matt-ēbha-kumbha-galitāni vibhānti yuddhē muktāpa(pha)lāni subhaṭa-ksha-
47 taj-ōkshitāni bijāni kīrtti-vitatēr=iva rūpitāni¹² |(l)| Sa samasta-
48 bhuvanāśraya-śrī-Vijayāditya-mahārājādhīrāja-paramēśvara-paramabhā-
49 ṭṭārakaḥ parama-brahmanyam=Attilināṇḍu¹³-vishaya-nivāsinō rāshṭrakūṭa-pramu-
50 khān=kuṭumbinas=samāhūy=ēttham=ājñāpayati¹⁴ || Adḍakali¹⁵-gachchha-nāmā | Vala-

Fourth plate ; second side.

- 51 hāri-gaṇa-pratīta-vikhyāta-yaśā[h*] | chāturvvarnnā(rṇya)-śramana(ṇa)-viśēṣ-āna-
śrāṇan-ābhi-

¹ Read *māsdn=apōlayat*.

² Read *āgrajanmā*; and see the remarks on page 181 above.

³ Metre, Vasantatilaka.

⁴ Read *putrō*, or *sūnur*, to suit the metre.

⁵ Metre, Sragdharā; and in the next verse.

⁶ I give what appears to be the reading. But the letters are so filled in with rust here, that it is not quite certain.

⁷ The first syllable of this name is probably *lō*, with the ordinary *l*. But it might possibly be taken as *lō*, with the Dravidian *l*.

⁸ Read *sach-ōhharanam*.

⁹ Metre, Āryāgiti; and in the next verse.

¹⁰ The *ra* was at first omitted, and then was inserted below the line.

¹¹ Metre, Vasantatilaka.

¹² Read *rōpiti*. A *visarga* has in the same way been mistakenly inserted in *ājñāpayati*, line 50, and *bhāvatī*, line 68.

¹³ Read, either *brahmanya Attilināṇḍu*, with hiatus, or, more correctly, *brahmanyō=Attilināṇḍu*, with *samāhi*. See note 1 on page 179 above.

¹⁴ Read *ājñāpayati*.

¹⁵ Metre, Āryāgiti; and in the next three verses.

- 52 lashita-manaskah || Śrī-rāja-Chaluky-ānvaya- | -parivārita¹-Paṭṭavaraddhik-ānvaya-ti-
 53 lakā | gaṇikājana-mukha-kamu(ma)la-dyumani-dyutir=iha hi Chāmekā-
 54 m̄b=ābhūt=sā || Jina-dharmma-jala-vivarddhana- | -śaśi²-ruchira-samā-
 55 na-kīrtti-lābha-vilōlā | dāna-dayā-si(śi)la-yutā |³ chāru-
 56 śrī⁴ śrāvaki budha-śruta-niratā || Yasyā⁵ guru-pamktir=uchya-
 57 tē || Siddhānta-pāradīśvā prakāṣita-guṇa-Sakalachandrasiddhānta-muni[h*] |
 58 tach-chhishy[ō*] guṇavān=prabhura=amita-yasā=samātir=Ayapōṭi-mu-
 59 nindraḥ || Tach⁶-chhishyāy=Ārhanandy-ā(a)m̄kita-vara-munayē Chāmekāmbā su-
 bhaktyā śrī-

Fifth plate; first side.

- 60 mat śrī⁷-Sarvvalōkāśraya-Jinabhavana-khyāta-satr-ātta(rttha)m=uchchair=Vveṃgināth-
 Āmma-
 61 rāj[ō*] kshatibhṛiti Kaluchumbārū-su-grāmam=ishṭam |⁸ cha(sa)ntuṣṭā
 dāpayitvā hu-
 62 dha-jana-vinutām yatra jā(ja)grāha kīrttim || Uttarāyana-nimittēna ka(kha)ṇḍa-
 sphuṭi-
 63 ka(ta)-navakarm-ārttha[m*] sarvva-kara-parihāram śāsanikṛitya dattam=Asy=
 āvadhayaḥ [i*] pūrvva-
 64 taḥ Āruvillī⁹ [i*] dakṣhiṇataḥ Korukolanu | paśchimataḥ Yidiyūru |
 65 uttarataḥ Yullikodamaṇḍru || Tasya kshētr-āvadhayaḥ [i*] pūrvvataḥ
 Śarkarakuṅḡru [i*]
 66 dakṣhiṇataḥ Iṅṅulakoḷu [i*] paśchimataḥ Iḍiyūri pola-garusu | uttarataḥ
 Kāṇcharigu-
 67 ṇḍu || Asy=ōpari na kēnachid=bādhā kartavyā yaḥ karōti sa pañcha-
 mahāpātaka-sa[m*]yu-
 68 kṭō bhavati¹⁰ || Bahubhir¹¹=vvasudhā dattām¹² bahubhiś=ch=ānupālita yasya
 yasya ya-
 69 dā bhūmis=tasya tasya tadā phalam || Sva-dattā[m*] para-dattā[m*] vā yō
 harēta vasu-

Fifth plate; second side.

- 70 [ndha]rā[m] shasṭi-varsha-sahasrāṇi viśṭhāyā[m*] [jāya*]tē krimiḥ || Asya
 grāmasya¹³ grāmaku(kū)ṭa-
 71 tva[m] Ka]ṭṭalāmb-ātmaja¹⁴ Kusumāyudhāya dattam śāśvatam || Asya grāmasya
 72 [ka?]pp-ābhidhānam kara-varjjitaḥ(m) || Ājñaptiḥ¹⁵ kṭākādhis[ō*] Bhaṭṭadēvaś=
 cha lēkhakaḥ kaviḥ Ka-

¹ Read *ānvaya-parivārita*, omitting the mark of punctuation.² Read *vivarddhana-śaśi*, omitting the mark of punctuation.³ This mark of punctuation, at the end of a third *pāda*, is superfluous.⁴ This stands for *chāru-śrī*. See page 179 above.⁵ Read *yasyā*.⁶ Metre, *Sragdharā*.⁷ Read *śrīmach-chhīr*.⁸ This mark of punctuation, at the end of a third *pāda*, is superfluous.⁹ The *llī* was first written in the place of the *vi*. Then the *akṣhara* was corrected into *vi* and the *llī* was added, before the writer went any further.¹⁰ Read *bhavati*.¹¹ Metre, *Ślōka* (Anuṣṭubh); and in the next verse.¹² Read *dattā*.¹³ The *ma* was at first omitted, and then was inserted below the line.¹⁴ Read *ātmaja*.¹⁵ Metre, *Ślōka* (Anuṣṭubh).

- 73 vichakravarttī śāsanassāśyukṛit¹ || Peddha(dda)-Kaluchuvubariti śāsana[m*]bu
śāsina Bha-
74 tṭadēvanik=Arahanandi-bhaṭṭar[u*]lu Gumsimiya r[e*]tṭeḍlu-gāmpulunnunḍi paru
. . ṇḍa² tūmuna ne(? ni)³ vuṭṭu vittu-paṭṭu vrasāḍaṇ-chēsiri [||*]

TRANSLATION.

Om ! Hail ! Of Satyāśrayavallabhēndra-(Pulakēśin II.),— who adorned the family of the Chālukyas, who are glorious; who belong to the Mānavya gōtra which is being praised throughout the whole world; who are Hārītiputras; who acquired sovereignty by the favour of a boon from the goddess Kauśikī; who are protected by the assemblage of the Mothers (of the world); who meditate on the feet of the god Svāmi-Mahāsēna; who have made the territories of their enemies subject to themselves on the instant at the mere sight of the excellent boar-crest which they acquired through the favour of the divine Nārāyaṇa; and whose bodies have been purified by ablutions performed after celebrating *asvamedha*-sacrifices.— the (younger) brother :—

(Verse 1 ; line 6.) The victorious Kubja-Vishṇu (that is, Vishṇuvardhana I.), the first husband of Fortune,⁴ protected for eighteen years the earth, taken by his valour from a mighty (foe)⁵ hard to be conquered, just as the dwarf Vishṇu, the first husband of Śrī (Lakshmi), protected the earth, taken by his stride from the demon Bali hard to be conquered.

(Line 8.) His son Jayasīmha (I.) (reigned) for thirty-three (years). Vishṇuvardhana (II.), son of his younger brother Indrarāja, for nine (years). His son Maṅgi-Yuvarāja, for twenty-five (years). His son Jayasīmha (II.), for thirteen (years).

(L. 10.) His younger brother Kokkili, born from a different mother, (reigned) for six months. His elder brother Vishṇuvardhana (III.), having expelled him, (reigned) for thirty-seven (years). His son Vijayāditya (I.)-Bhaṭṭāraka, for eighteen (years). His son Vishṇuvardhana (IV.), for thirty-six (years). His son Narēndramrigarāja-(Vijayāditya II.), for forty-eight (years). His son Kali-Vishṇuvardhana (V.), for one year and a half.

(L. 14.) His son Gunaga-Vijayāditya (III.) (reigned) for forty-four (years); or (in other words) :—(V. 2; l. 15.) His eldest son, the lord Gunaga-Vijayāditya (III.), a veritable champion,⁶ to whose arm great honour was paid by the Vallabha king,⁷ and who, in addition to being a chief of heroes, was a crest-jewel of great warriors, enjoyed the earth for four and forty years.⁸

(Vv. 3, 4; ll. 17, 19.) The son of his brother the Yuvarāja king Vikramāditya (I.), namely, the king Bhima (I.),⁹ who caused alarm to his foes, and who was (so) liberal (that) he

¹ Read, probably, *śāsanasy-āśya kavya-kṛit*.

² Read, perhaps, *paṇṇeḍu*.

³ It seems either that *ni* was engraved and was corrected into *ne*, or else that the reverse was done. Further, the *akshara* is perhaps a mistake for the figure 9.

⁴ That is to say, the first king in his dynasty.

⁵ There is, perhaps, an intimation that the territory first acquired by the Eastern Chalukyas had belonged to a ruler named Bali. But we have no facts as yet, in support of such an interpretation.

⁶ *Aṅgakāra*; for *aṅgakāra*: see page 180 above.

⁷ That is, the contemporaneous Rāshtrakūṭa king of Mālkḥēd, either Amoghavarsha I. or Krishna II.; see Vol. VI. above, pp. 174, 175.

⁸ When I originally saw this record, many years ago, I read, in line 17, *asvachata avatadrimsatim*, and thought that it should be emended into *asvabhat-dakṣat[cha*]tadrimsatim*; and that is how I came to say (*Ind. Ant.* Vol. XX. p. 102) that this record adds an alternative statement that the duration of the reign of Vijayāditya III. was forty-eight years. The real reading, however, — *asau(sau) chatastrat=chataadrimsatim*, — is quite certain; and my mistake was due to the great similarity between the initial *a* and the *akshara* era, and between the subscript *v* and *ch*, in the period to which this record belongs.

⁹ This king is mentioned again in line 30 as Chālukya-Bhīma (I.), by his more usual appellation.

resembled Kânina (Karna), conquered in fight the great army of **Krishnavallabha**,¹ together with kinsmen of his own, and,—being a very son to gods and saints and Brâhmanas,—repeatedly gave away wealth for religious purposes, and made his kingdom free from troubles and unequalled and very thriving and possessed of prosperous subjects, and enjoyed the earth righteously for thirty years.

(V. 5 ; 1. 22.) After that, his dear son **Vijayāditya (IV.)**,—who was great ; who bestowed so much wealth that he surpassed the god Dhanada (Kubêra) ; who was endowed with truthfulness and liberality and majesty ; who cleft open the hearts of his enemies ; and who by name indeed was (*known as*) the king **Kollabigaṇḍa**,—reigned for six months, possessed of prudent behaviour and steadfastness.—(V. 6 ; 1. 25.) His eldest son king **Amma (I.)**,—whose power was unconquered ; who conquered whole rows of hostile kings ; who had the famous name of **Râjamahendra** ; and who was the straight path of the sentiment of compassion,—was king for seven years.

(I. 27.) Having expelled his son **Vijayāditya (V.)** (*while he was*) a child, king **Tâlapa**, son of the glorious **Yuddhamalla (I.)**,² guarded (*the earth*) for one month. Having completely conquered him in battle, **Vikramāditya (II.)**, son of **Châlukya-Bhima (I.)**,³ having overthrown him by prowess in attack, protected (*the earth*) for nine months. Then **Yuddhamalla (II.)**, the eldest son⁴ of king **Tâlapa**, took (*the sovereignty*) and continued for seven years.

(V. 7 ; 1. 32.) At that juncture, the lord **Bhima (II.)**,—who was a son of the famous **Kollabigaṇḍa-(Vijayāditya IV.)** ; who was a brother, born from a different mother, of him (**Amma I.**) who had the extolled name of **Râjamahendra** ; and who surpassed the epic hero Bhima in strength and majesty,—rose up to conquer, purifying the eastern region.—(V. 8 ; 1. 35.) Having unaided, indeed, slain the glorious **Râjamayya**, and **Dhalaga** who excelled far and wide, and the fierce **Tâtabikki**, and **Bijja** who was (*always*) ready for war, and the excessively powerful **Ayyapa**, terrible and savage, and the extremely great army sent by king **Gôvinda**, and **Lôvabikki** the ruler of the **Chôlas**, and the valorous **Yuddhamalla**,—(*all of them*) possessed of marshalled arrays of elephants :—(V. 9 ; 1. 38.) Verily, this glorious **Râja-Bhima (II.)**,—giving encouragement to those who were frightened, and protecting those who came to the excellent refuge (*which he afforded*), and removing troublesome people, and justly levying taxes from the lands of his enemies, and giving pleasure to the mass of his own people, and spreading his fame abroad, and making the multitude of kings bow down, and accumulating stores of wealth,—guarded the whole world for twelve years.

(V. 10 ; 1. 42.) He who, resembling Kumâra, was born of him, an embodiment of the god **Mahêśvara**, from **Lôkamahâdêvi** whose form resembled that of **Umâ**, is he who is famous under the appellation of king **Amma (II.)** :—(V. 11 ; 1. 43.) Who, putting to shame **Manôja** (**Kâmadêva**) by his beauty, and **Mahendra** (**Indra**) by his might, and the hot-rayed sun by his great glory, and **Hara** (**Śiva**) by burning up the cities of his enemies, is resplendent, his spotless fame being well known.—(V. 12 ; 1. 45.) The pearls, dropping down in battle from the temples of rutting elephants cleft open by the scimitar which is his long arm, shine out as the planted seeds, moistened by the blood of great warriors, of the clump (*of trees*) which is his fame.

(I. 47.) He, the asylum of the universe, the glorious **Vijayāditya-(Amma II.)**, the **Mahârâjâdhirâja**, **Paramêśvara**, and **Paramabhakṭâraka**, who is most kind to Brâhmanas, having

¹ That is, the Râshtrakûṭa king **Krishna II.**

² From other sources, we know that **Yuddhamalla I.** was a (younger) brother of the **Vikramāditya I.** who is mentioned in line 18 of this record.

³ That is, of the **Bhima** who is mentioned in line 21 of this record.

⁴ See page 181 above.

called together the householders, headed by the *Rāshtrakūṭa*,¹ who dwell in the Attilināṇḍu district, thus issues his commands:—

(V. 13 ; 1. 50.) “(There is) the sect which has the name of the *Adḍakali gachohha*, which has established its renowned fame in the *Valahāri gaṇa*, and the minds of the members of which have their desires bent on granting excellent food to ascetics of the four castes.

(V. 14 ; 1. 52.) “Here (on earth), indeed, there came into being she, *Chāmekā*, who is an ornament of the *Paṭṭavardhika* lineage which belongs to the retinue of the lineage of the glorious royal *Chalukyas*, and who possesses the lustre of a sun to the water-lilies (blooming in the daytime) which are the faces of courtesans:— (V. 15 ; 1. 54.) And who agitates herself in acquiring fame as radiant as that of a moon to bring to full tide the waters of the religion of *Jina*, and is endowed with charity and tenderness and good character, and is beautiful, and is a disciple who delights in the teachings of learned people.

(L. 56.) “The line (of succession) of her teacher is declared:— (V. 16 ; 1. 57.) (There was) the saint *Sakalachandrasiddhānta*, possessed of virtues which were very manifest, who was thoroughly well versed in the *Siddhānta*-writings; and his disciple was the great saint *Ayyapōṭi*, virtuous and masterful and possessed of unmeasured fame and very intelligent.

[(V. 17 ; 1. 59.) “To his disciple, the excellent saint who is marked by (the name of) *Arhanandin*, *Chāmekāmbā*, through her great devotion to him,—while king *Amma* (II.), the high lord of *Veṅgi*, is reigning,—has, with great pleasure, caused to be given the excellent village of *Kaluchumbarru*, wished for by him, for the purposes of the renowned dining-hall of the holy and famous Jain temple called *Sarvalōkāśraya-Jinabhavana*; whereby she has acquired a reputation praised by learned people.]

(L. 62.) “On account of the winter solstice, (this village) has been given, conveyed by (this) charter, with exemption from all taxes, for the purpose of the restoration of whatever may become broken or torn. Its boundaries are:— On the east, *Āruvilli*; on the south, *Korukolanu*; on the west, *Yiḍiyūru*; and, on the north, *Yullikodamaṇḍru*. The boundaries of its fields are:— On the east, *Śarkarakuṇṇu*;² on the south, *Iṇṇulakoḷu*; on the west, the waste land of *Idiyūru*; and, on the north, the rock (?) called *Kaṇchariguṇḍu*.

(L. 67.) “No one should cause any molestation (to the enjoyment) of this (village); he who does so, incurs (the guilt of) the five great sins!— (V. 18 ; 1. 68.) Land has been given by many people, and has been protected (in enjoyment) by many; whosoever at any time possesses the earth, to him belongs, at that time, the reward (of making or protecting this grant)!— (V. 19 ; 1. 69.) He who confiscates land that has been given, whether by himself or by another, is born as a worm in ordure for the duration of sixty thousand years!

(L. 70.) “The office of *Grāmakūṭa*³ of this village has been given in perpetuity to *Kusumāyudha*, son of [Ka]ṭṭalāmbā. That, belonging to this village, which is named *kappa*,⁴ is exempt from taxes.

(V. 20 ; 1. 72.) “The *ājñapti* is the *Kaṭakādhīta*;⁵ and the writer is *Bhaṭṭadēva*; the composer of the poetical parts of this charter is the poet *Kavichakravartin*.”

¹ That is, the head official or governor of the *rāṣṭra* or *vishaya* or province.

² This was perhaps the name of a hamlet. The *Madras Manual of Administration*, Vol. III. p. 229, gives ‘*corroo*,’ = Telugu *kurru*, in the sense of ‘a small hamlet.’ Dr. Hultzsch tells me that the word is a frequent ending of village-names.

³ That is, the office of village-headman,— the post of *Gauḍa* or *Pāṭi*. See page 183 above.

⁴ This seems to be the word which in Kanarese means ‘tribute,’ but the exact bearing of the passage is not apparent.

⁵ That is, the governor of the royal camp; see page 185 above.

(L. 73.) To Bhaṭṭadēva,¹ who has drawn up the charter concerning **Pedda-Kaluchuvubarru**, the venerable Arahānandi has given, as a present, land requiring as seed 9(?) *puṭṭis* of twelve *ūmus* (each), (which he received) from the cultivators, (possessing) two bullocks, at **Gūmsimi** (?).

No. 26.—FOUR INSCRIPTIONS AT SOLAPURAM.

Br E. HULTZSCH, PH.D.

Mr. G. Venkoba Rao, one of my assistants, lately visited **Śōlapuram**,² a village about 8 miles south of Vellore, and copied a number of inscriptions, of which I am now publishing the four most interesting ones.

The ancient name of **Śōlapuram** was **Kāṭṭuttumbūr** (B. and D. below), which was included in **Paṅgaḷa-nāḍu**,³ a subdivision of the district of **Paḍuvūr-kōṭṭam**⁴ (B. below). In inscriptions of the Chōḷa kings Rājarāja I. (No. 421 of 1902) and Kulōttuṅga I. (Nos. 422 and 425 of 1902), the village is called **Uyyakkonḍāṇ-Śōlapuram** and is stated to have belonged to **Mugai-nāḍu**, a subdivision in the north of **Paṅgaḷa-nāḍu**, a district of **Jayaṅgonḍa-Śōḷa-maṇḍalam**. From other inscriptions we know that **Paṅgaḷa-nāḍu** included **Vēlūrppāḍi**, a suburb of Vellore,⁵ and that Tirumalai near **Pōlūr** belonged to **Mugai-nāḍu**.⁶

Vol. I. of *South-Indian Inscriptions* contains one inscription from **Śōlapuram** (No. 53), which I now republish (B. below) because my former transcript of it was not quite correct. A fresh copy (No. 422 of 1902) of another **Śōlapuram** inscription which was noticed in *South-Indian Inscriptions*, Vol. I. (No. 96), enables me to add that this record opens with the words *Pugaḷ-māḍu viḷaṅga* and hence belongs to **Kulōttuṅga I.**⁷ and that it mentions the temple of **Rājarājēśvara** at **Uyyakkonḍāṇ-Śōlapuram**, which, as well as **Rājendra-Chōḷēśvara**,⁸ is perhaps a later designation of the **Nandikampīśvara** temple.⁹

A.—INSCRIPTION OF VIJAYA-KAMPA.

This inscription (No. 429 of 1902) is engraved on a long stone broken in three pieces, which were dug up by Mr. G. Venkoba Rao in a tope of trees opposite the ruined **Īśvara** temple at **Śōlapuram**.

The inscription consists of 2½ mutilated Sanskrit verses in the Grantha character, and a passage in Tamil prose which is incomplete at the end. The Tamil portion is dated in the 8th year of king **Vijaya-Kampa**. The archaic alphabet of the inscription makes it probable that this king is identical with **Kampavarman**, whose inscriptions at **Ukkal** are dated in the 10th and 15th years.¹⁰ As I shall show further on (p. 196 below), he was perhaps a son of the **Gaṅga-Pallava** king **Vijaya-Nandivikramavarman** and hence belonged to the ninth century of the Christian era.

The Tamil portion records that a chief named **Rājāditya** built a temple of **Śiva** and a tomb in memory of his deceased father **Prithivigaṅgaraiyar** and apparently made a grant to a **Brāhmaṇa**. The mutilated Sanskrit portion contained a genealogical account of this **Rājāditya**. His earliest ancestor was **Mādhava** of the **Gāṅgēya** family, whose son was "he who was renowned as the splitter of even a stone-pillar." In the inscriptions of the Western **Gaṅgas**, this

¹ This passage is in Telugu. I am indebted to Dr. Hultzsch for the translation of it.

² No. 95 on the *Madras Survey Map* of the Vellore taluka.

³ An inscription of **Parāntaka I.** (No. 423 of 1902) mentions **Śōlapuram** as 'Kāṭṭuttumbūr in **Paṅgaḷa-nāḍu**' and Vellore as 'Vēlūr *alias* **Paramēśvaramaṇḍalam**;' compare *South-Ind. Inscr.* Vol. I. No. 110.

⁴ For other divisions of **Paḍuvūr-kōṭṭam** see *ibid.* Vol. III. p. 89.

⁵ Above, Vol. IV. n. 83.

⁷ See *ibid.* Vol. III. p. 126.

⁹ See p. 186 below.

⁶ *South-Ind. Inscr.* Vol. I. Nos. 67 and 68.

⁸ See *ibid.* Vol. I. No. 97.

¹⁰ *South-Ind. Inscr.* Vol. III. Nos. 8 and 5.

feat is ascribed to the mythical king **Koṅgaṇivarman**,¹ who is, however, there represented as the father and not as the son of Mādhava. The Śōlapuram inscription then states that in his (*viz.* Koṅgaṇivarman's) family was born a king whose name is given in the corrupt form of **Atvivarman**, which may be meant for Atrivarman, Agnivarman, Arivarman, *etc.* Verse 2 praises a king whose name is lost; but the Tamil portion suggests that this is the person who is there called **Prithivigaṅgaraiyar**. Verse 3, of which only the first and last words are preserved, opens with the name of **Rājāditya**, who is described in the Tamil portion as the son of **Prithivigaṅgaraiyar** and the contemporary of Vijaya-Kampa. As regards **Prithivigaṅgaraiyar**, he must be different from the Gaṅga chief **Prithivīpati I.**, because the latter was the father of **Mārasimha** and the son of **Śivamāra**,² while the former was the father of **Rājāditya** and apparently the son of the king whose name is hidden in the corrupt form **Atvivarman**.

TEXT.

- 1 Svasti śrī [||*] Gaṅgēya-vamśyō vijai(ja)y-ābhirāma[h] śrī-Mādhava[s=*] tasya
 sutō va(ba)bhūva [3] chhēttā śilā-sta[m]bham=api pri(pra)siddha[s=*] tat(d)-
 varṇsa-jō=bhu(bhūt=) pri(pra)[thi]tō=tvī[varmā]* [|| 1*]
 gō
 2 nripati[h*] parantapa[h |*] nrip-āpi(bhi)vandya[h*] Śiva-bhaktimān kavi[r=*]
 vikalpa-kallōla-padārtuha-tatpara[h*] || [2*] Rājāditya-ākhyā-bhūpa[h*] sura[ta]ru-
 sa[d]riśō Narga[ti-nāma] ram=asan
 3 dāpayām=āsa v[i]ra[h*] || [3*]⁵ Kō Viśaiya-Kamparkku yāṇḍu eṭṭāvaḍu
 Prithiviga[n]ga[r]aiyar at[i]tar=āyina pirpāḍu tat-putra-Rājāditya[n] ma[hā-
 dē]van para-nripati-makuṭa-ghaṭṭita-chara-
 4 [na]n. tam=appaṇār[ai]=ppalli-paḍuttav=iḍattu Īśvar-ālayamum atiyta-⁶garamum
 eḍu[p]pittu kaṇḍu(ṇḍu) śevviytān⁷ [i*] Prāvaśa(cha)na-sūttirattu Kauśika-
 gōtrattu perum-bā[r*]ppāṇ Tiṭṭaiśarmma.⁸

TRANSLATION OF THE TAMIL PORTION.

(Line 3.) (*In*) the eighth year of king **Vijaya-Kampa**,— after **Prithivigaṅgaraiyar** had died, his son, the great king **Rājāditya**, whose feet were rubbed by the diadems of hostile kings, caused to be built, constructed, and caused to be made a temple of **Īśvara** (**Śiva**) and a house for the deceased (*i.e.* a tomb) on the spot where his father had been buried.

(L. 4.) [*To*] **Tiṭṭaiśarman**, a great **Brāhmaṇa** of the **Prāvachana-sūtra**⁹ (*and*) of the **Kauśika-gōtra**

B.—INSCRIPTION OF VIJAYA-KAMPAVIKRAMAVARMAN.

This Tamil inscription is engraved on the north wall of the **Perumāl** temple at **Śōlapuram**. It has been edited before in *South-Indian Inscriptions*, Vol. I. No. 53, but is now republished from a better impression prepared in 1902.

The inscription is dated in the 23rd year of king **Vijaya-Kampavikramavarman**¹⁰— who is probably the same as the **Vijaya-Kampa** of A.— and records the building of a temple of **Nārāyaṇa**

¹ Above, Vol. III. p. 164 f. and p. 186; *South-Ind. Inscr.* Vol. II. p. 380.

² *South-Ind. Inscr.* Vol. II. p. 380.

³ This sign of punctuation is expressed by a *visarga*.

⁴ I am unable to correct with confidence this corrupt name.

⁵ Read *attita*.

⁶ The remainder of the inscription is lost.

⁷ This is only half a verse.

⁸ Read *śevvittāṇ*.

⁹ See above, Vol. V. p. 52, note 11.

¹⁰ The same form of the king's name is found in an inscription at **Dāśi**; *South-Ind. Inscr.* Vol. III. p. 8 and note 5. Twelve further inscriptions of **Vijaya-Kampavarman** and **Vijaya-Kampavikramavarman** have been copied at **Uttaramallūr**, and two of **Kampavarman** at **Kāvāntaṇḍalam**; see my *Annual Reports* for 1897-98 and 1900-01, pp. 18-20 and p. 23, respectively.

(Vishṇu) at Kāṭṭuttumbūr (*i.e.* Śōlapuram), which must be identical with the temple of Perumāḷ (Vishṇu) on which the inscription is engraved. The temple was named **Kanakavalli-Vishṇu-griha** after the village of **Kanakavalli**, in which some land was granted to it. The name of the person who built the temple and granted land to it is lost.

TEXT.

- 1 Svasti śr[i] [i]* Kō V[i]śaiya-[Ka]mpavikkiramaparumarkk-iyāṇḍu
irubattu-mu(mū)ṇṇāvadu [Pa]ḍuv[ū]r-kkōṭṭattu=Ppa[ṇ]-
- 2 gaḷa-nāṭṭu=Kkāṭṭuttumbūr Nārāyaṇa-bhaṭṭāragarkku śrī-kōy[i]l eḍuppittu
Ka[ṇa]kava[ḷi]-Vishṇu-griham eṇṇu-
- 3 m nāmāthē(dhē)yattāl amaippittu idaṇṇukku [tri]kālam ārādhippadaṇṇam
tri[kā]lam tiru-amurdukkum na-
- 4 ndā-viḷakkum ārādhippaṇṇukku jīvitamum āga i-kkōṭṭattu i-nāṭṭu Kanakavalli
ēri ki(ki) bhūmi i-¹

TRANSLATION.

Hail! Prosperity! (*In*) the twenty-third year of king Vijaya-Kampavikramavarman a sacred temple was caused to be built to the god Nārāyaṇa (*at*) Kāṭṭuttumbūr in Paṇḡala-nāḍu, (*a subdivision*) of Paḍuvūr-kōṭṭam; (*it*) was endowed with the name **Kanakavalli-Vishṇu-griha**; and, for the worship at the three times (*of the day*), for offerings at the three times (*of the day*), (*for*) a perpetual lamp, and as a living for the worshipper, [there was granted] to it land below the tank of **Kanakavalli** in the same *kōṭṭam* (and) in the same *nāḍu*.

C.—INSCRIPTION OF SAKA-SAMVAT 871.

This Tamil inscription (No. 428 of 1902) is engraved on a rock near a pond called Kaḷḷaṇḡuttai, south-west of Śōlapuram.

The date of this inscription is expressed in three different ways, *viz.* (a) “the year two;” (b) the Śaka year 871 (in words); and (c) “the year in which the emperor Kannaradēva-Vallabha, having pierced Rājāditya, entered the Toṇḍai-maṇḍalam.” The second and third portions of the date furnish an interesting confirmation of the Ātakūr inscription, according to which the Rāshtrakūṭa king Kṛishṇa III. had killed the Chōḷa king Rājāditya at Takkōlam in Śaka-Samvat 872 current, the Saumya-samvatsara = A.D. 949-50.² As the date of the Śōlapuram inscription does not contain a cyclic year, it is impossible to say if its Śaka year has to be taken as expired or current. In the former case the date would be the same as that of the Ātakūr inscription, and in the second case it would be A.D. 948-49. The “year two” with which the Śōlapuram inscription opens cannot refer to the reign of Kṛishṇa III., because we know from the Dēḷi plates that Amoghavarsha, the father of Kṛishṇa III., had died and that the latter was reigning³ in A.D. 940.⁴ Hence, as far as I can see, the “year two” can only refer to the reign of the Chōḷa king Rājāditya. This would indirectly confirm Professor Kielhorn’s calculation of the date of an inscription at Kūram, according to which the 40th year of Parāntaka I., the father and immediate predecessor of Rājāditya, corresponded to A.D. 946.⁵ It may now be provisionally assumed that Parāntaka I. reigned from about A.D. 907 to at least 946, and that Rājāditya was crowned in about A.D. 948 and was killed by Kṛishṇa III. in about A.D. 949.

The purpose for which the subjoined inscription was engraved was to record the construction of the pond near which it is found, and which was called the **Kaḷḷinaṅgai pond**

¹ The remainder of the inscription is lost.

² Above, Vol. V. p. 195, vv. 27 and 28.

³ See p. 1 above.

⁴ See above, Vol. VI. p. 51.

⁵ Dr. Fleet’s *Dyn. Kan. Distr.* p. 420.

Scale One-fifteenth.




No. 26A.—Solapuram Inscription of Vijaya-Kampa.

Scale One-fifteenth.



No. 26B.—Solapuram Inscription of Vijaya-Kampavikramavarman.

Scale Three-tenths.



No. 27.—Vaishnava Inscription at Pagan.

E. HULTZSCH.

WILEY & SONS, LTD., LONDON, E.C. 4.

in memory of a woman named Kaḷḷinaṅgai. The present name Kaḷḷaṅguṭṭai, i.e. 'the robber's pond,' is evidently a popular corruption of the original one. Kaḷḷinaṅgai had died at Aruṅguṇṇam, a village in the modern Arcot taluka.¹ She was the daughter of the Gaṅga chief Attimallar (i.e. Hastimalla) alias Kannaradēva-Prithvigāṅgaraiyar. This chief was the son of Vayiri-Adiyaṇ, the lord of Paṅḡala-nāḍu.² Hence he seems to be different from the Gaṅga-Bāṇa chief Hastimalla alias Prithivīpati II., who was the son of Mārasimha.³ The word Kannaradēva, which is prefixed to the name of Prithvigāṅgaraiyar, characterises the latter as a subordinate of the conqueror Kṛishṇa III. His wife Kāmakkāṇār bore the title Gaṅgamādēvi and was the daughter of Vāṇakōvaraiyar Orriyūr-Adiyaṇ. Vāṇakōvaraiyar is known to have been the title of certain chiefs.⁴ Orriyūr-Adiyaṇ means 'the devotee of the temple at Tiruvorriyūr.'⁵

TEXT.

- 1 Svasti śrī [||*] Yāṇḍu iraṇḍu Śaka-varsham eṇṇūṟṟ-eḷubatt-onṟu
- 2 śa(cha)kravartti Kannaradēva-Vallabhan⁶ Rājādittarai eṇṇu Tonḍai-maṇḍalam
pugun[da]-
- 3 [v=ā]ṇḍu Paṅḡala-nāḍ-uḍaiya Vayiri-Adiyaṇ maganār Attimallar=āgiya
Kannaradēva-Pri[thvi]gaṅga-
- 4 [rai]yark[ku] [Vāṇa]kōvaraiyar Orriyūr-Adiyaṇ magalār Kā[mak]kaṇār=āṇa
Gaṅgamādēviyār vayiṟru[ṭ=pi]ṇandu Aruṅguṇṇattir=[svargga]-
- 5 r=āyiṇa Kaḷḷinaṅgaiyārkkku-kka[n]ḍa Kaḷ[ḷi]naṅgai-kuḷam [||]

TRANSLATION.

Hail! Prosperity! (In) the year two, the Śaka year eight-hundred and seventy-one, the year in which the emperor Kannaradēva-Vallabha, having pierced Rājāditya, entered the Tonḍai-maṇḍalam,—the Kaḷḷinaṅgai pond was constructed for (the merit of) Kaḷḷinaṅgaiyār, who died at Aruṅguṇṇam, having been born by Kāmakkāṇār alias Gaṅgamādēviyār, the daughter of Vāṇakōvaraiyar Orriyūr-Adiyaṇ, to Attimallar alias Kannaradēva-Prithvigāṅgaraiyar, the son of Vayiri-Adiyaṇ, the lord of Paṅḡala-nāḍu.

D.—INSCRIPTION OF SAKA-SAMVAT 875.

This Tamil inscription (No. 346 of 1901) is engraved on the base of the ruined Śvara temple at Śōlapuram. It is dated in Śaka-Samvat 875 (in words), while Hastimalla alias Kannaradēva-Prithvigāṅgaraiyar⁷—the same chief who was mentioned in C.—was ruling the Kalleḍuppūr-maryādā. This may have been a subdivision of Paṅḡala-nāḍu, the lord of which his father is stated to have been (C. line 3); but I cannot find Kalleḍuppūr on the map.⁸

The inscription records grants to the two temples of Nandikampīśvara and Guṇamālai at Kāṭṭuttumbūr (i.e. Śōlapuram) by Hastimalla's minister Puttaḍigaḷ alias Alivīṇa-Kaḷakaṇḍa-Prithvigāṅgaraiyaṇ. The last portion of this name is evidently derived from that of his master; kaḷakaṇḍa is the Tamil form of kalakaṇṭha, 'a kōkila'; alivīṇa means 'devoid

¹ See above, Vol. IV. p. 271.

² South-Ind. Inscr. Vol. II. p. 380 f., and above, Vol. IV. p. 222 f.

³ See p. 189 above.

⁴ Above, Vol. V. p. 106; South-Ind. Inscr. Vol. II. p. 290, note 1, and Vol. III. p. 132.

⁵ The engraver seems to have written at first -Vallabhar, and then to have cancelled the r and added an a after it.

⁷ In line 9 he is called simply Prithvigāṅgaraiyar.

⁸ A village of the same name is referred to in South-Ind. Inscr. Vol. I. No. 83, line 5. No. 85 mentions a village of a slightly different name, viz. Kalleḍuppūr, which must be different from Kalleḍuppūr, because it belonged to Virpēḍu-nāḍu (see above, Vol. VI. p. 228 and note 5), a subdivision of Kāliyūr-kōṭṭam.

of destruction; and Puttaḍigaḷ means 'a devotee of Buddha.' Hence the donor seems to have been a Buddhist.¹

Nandikampiśvara must have been the ancient name of the temple of Īśvara (Śiva) in which this inscription is engraved. As no other Śiva temple exists at Śōḷapuram, it may be also identified with the Īśvara temple that was founded during the reign of Vijaya-Kampa according to the inscription A., and the Nandi-Kampa, after whom the Nandikampiśvara temple was called, may be identical with Vijaya-Kampa. As the alphabet of the inscriptions of Vijaya-Kampa, Kampavarman or Vijaya-Kampavikramavarman resembles that of the inscriptions of Vijaya-Dantivikramavarman, Vijaya-Nandivikramavarman and Vijaya-Nripatuṅgavikramavarman,² I feel tempted to explain Nandi-Kampa by 'Kampa, the son of Nandi,' and to assume that Kampavarman was a son of Nandivikramavarman and a brother of Nripatuṅgavikramavarman. The temple of Guṇamālai may have been a shrine in the Nandikampiśvara temple or another name of the Viṣṇu temple referred to in B. above.

TEXT.

- 1 Svasti śrī ||— Śagar yā[ṇḍu] [luba]tt-³aiñjāvadu śr[i].
Att[i]mallar-āg[i]ya [Kaṇṇara]d[ēva-P]ri[thivi]gaṅga[rai]yar Kall[e]ḍu-
- 2 ppūr-majjādi ālav-irukka [i]var=adigāri Puttaḍigaḷ=āgiya Aḷivi(vi)ṇa-Kaḷakaṇḍa-
Ppiridigaṅgaraiyaṇ-ēṇ Kāṭṭuttumbūr Nandi-
- 3 kampiśvara-dēvarkk=oru-nandā-vi[la]kku [cha]nd[r]āditya-prisiddham=⁴erippadāga=
chohāvā mu(mū)vā=ppār-āḍu toṇṇūṇ-āḍum Guṇamālai-
- 4 pperumāṇukk=oru-nandā-vilakk=erippadaṅkku=ttōṇṇūṇ-āḍum=ivv-ār nagarattār=vaḷi=
kkāṭṭi=kkuḍuttēṇ
- 5 Aḷivi(vi)ṇa-Kaḷakaṇḍa-Ppiridigaṅgaraiyaṇ-ēṇ[*] i-Nnandikampi(mpi)śvara-dēvarkku
niśada[m*] [u]lakku=ttumbai-ppūvum Guṇa[m]ā-
- 6 l[ai]-pperumāṇukku [u]lakku=ttumbai-ppūv=attuvadāga chandrāditya-pramāṇam
kaḷaṇḍu poṇ kuḍuttēṇ=i-dēvar ti-
- 7 [ru*][vū]ṇāḷigai-pperumakkaḷē [a]ṭṭuvippadāga [kuḍuttēṇ] [*] Guṇamālai-
pperumāṇukku [mū]ṇu sandhi[y]um tirumavidu⁵ kāṭṭuvadāga Amalaṅga[vaḷ]-
- 8 li-Attimalla-chchaturvēdimāṅgalam=ēṇ[ru nā]l=ūraiym=ēka-grāma[m]-āga=
chocheyya [A]ḷivi(vi)ṇa-Kaḷakaṇḍa-Prithvigaṅga[ṇ]garaiyaṇ-⁶ē-
- 9 ṇ [|| u]ḍaiyār Prithviga[m]garaiyarkku viṇṇappaṇ=jeyya [u]ḍaiyārum=ēka-
grāmaṇ=jeygiṇa [pō]ḷdu i[ṇa]-7Kkuṇamālai-pperumāṇu-⁸

TRANSLATION.

(Line 1.) Hail! Prosperity! (In) the [eight-hundred-and-]seventy-fifth year of the Śaka (king), while the glorious Attimallar alias Kaṇṇaradēva-Prithivigaṅgaraiyar was ruling the Kalleḍuppūr-majjādi,⁹—I, his minister (adhikārin) Puttaḍigaḷ alias Aḷiviṇa-Kaḷakaṇḍa-Ppiridigaṅgaraiyaṇ, exhibited and gave to the citizens of this town ninety undying (and) unaging big sheep¹⁰ for burning (with ghee prepared from their milk) one perpetual lamp in the Nandikampiśvara temple (at) Kāṭṭuttumbūr as long as the moon and the sun shall last, and ninety sheep for burning one perpetual lamp in the Guṇamālai temple.

¹ For another instance in which the same person worshipped both Śiva and Buddha, see above, Vol. VI. p. 143.

² See above, Vol. VI. p. 321, and Vol. VII. p. 139 f.

³ Read -pramāṇam= as in line 6.

⁴ Read -Prithvigaṅgaraiyaṇ-.

⁵ The remainder of the inscription is lost.

⁶ This word is a corruption of the Sanskrit *maryadda*.

⁷ See above, p. 134 and note 2.

⁸ Restore *enṇāṇṇ-ēḷḷabatti*.

⁹ Read *tiruvamidu*.

¹⁰ Cancel the *ṇa*.

(L. 5.) For supplying daily, as long as the moon and the sun shall last, one *uḷakku* of *tumbai* flowers to this Nandikampiśvara temple and one *uḷakku* of *tumbai* flowers to the Guṇamālai temple, I gave one *kaḷañju* of gold; I gave (it) in order that the great men (in charge) of the store-room of the temple¹ of this god² should cause (the flowers) to be supplied.

(L. 7.) When I, Aliviṇa-Kaḷakaṇḍa-Prithvigaṅgaraiyaṇ, requested the lord Prithvigaṅgaraiyar to combine four villages into one village called Amaṇḡavalli-Attimalla-chaturvêdimāṅgalaṃ (which should provide) for offerings to be made at the three times (of the day) in the Guṇamālai temple, and when (accordingly) the lord combined (them) into one village, . . . [to] this Guṇamālai temple

No. 27.—A VAISHNAVA INSCRIPTION AT PAGAN.

By E. HULTZSCH, Ph.D.

This inscription was noticed at Pagan by the Honourable Mr. A. T. Arundel, C.S.I., in the course of his tour through Burma. At his instance, Mr. Taw Sein Ko furnished me with an ink-impression of it in December 1902. After I had sent him a copy of the subjoined text and translation, he was good enough to supply me in February 1903 with three further ink-impressions and with the following additional information:—The inscription “is engraved on sandstone and was found at Myinpagan, which is situated about a mile to the south of Pagan. At Myinpagan lived Manôhari, the last of the Talaing kings, who was led into captivity by Anawrata, king of Pagan, in 1057 A.D. The captive king was surrounded by his fellow countrymen, who must have extended their friendship to colonists from Southern India. A Vaishnava temple has been found at Pagan, but none at Myinpagan. The inscription may belong to that temple, or to some other building which has since been demolished.”

The inscription consists of one verse in the Sanskrit language and Grantha alphabet, and a prose passage in the Tamil language and alphabet. The Tamil characters are those of the thirteenth century of the Christian era.

The Sanskrit verse is taken from the *Mukundamālā*³ (verse 6), a short poem by the Vaishnava saint Kulaśekhara, who, as shown by Mr. Venkayya, must have lived before the eleventh century.⁴

The Tamil prose passage records gifts by a native of Magôdayarpatṭaṇam in Malaimaṇḍalam, i.e. Cranganore⁵ in Malabar. His name, Śrī-Kulaśekhara-Nambi, stamps him as a devotee of the Vaishnava saint Kulaśekhara, from whose *Mukundamālā* the opening verse is derived. The recipient of the gifts was the Vishṇu temple of Nāṇādēsi-Viṇṇagar at Pukkam alias Arivattapuram, i.e. at Pagan, which in the Kalyāṇi inscriptions is styled ‘Arimaddanapura alias Pugāma.’⁶ Nāṇādēsi-Viṇṇagar means ‘the Vishṇu temple’ of those coming from various countries.’ This name shows that the temple, which was situated in the heart of the Buddhist country of Burma, had been founded and was resorted to by Vaishnavas from various parts of the Indian Peninsula.

¹ See above, p. 145 and note 1.

² The word *dēva* refers to Nandikampiśvara-dēva. Evidently the authorities of this temple had to make over one *uḷakku* of flowers per day to the temple of Guṇamālai-perumāṇ.

³ Printed in the *Kāvyamālā*, No. 1.

⁴ Above, Vol. IV. p. 294.

⁵ On Viṇṇagar, ‘a Vishṇu temple,’ see above, Vol. V. p. 47, note 4.

⁶ See *South-Ind. Insor.* Vol. III. p. 148.

⁷ *Ind. Ant.* Vol. XXII. p. 17.

TEXT.

- 1 Svasti śrī [||*] N=āsthā dhanmē(rmé) na vasu-nichayē n=aiva kām-ōpa-
 2 bhōgē yat jat¹ bhavyam bhavatu [bha*]gavan pūrvva-kaum(rm)-ānurūpam [!*]
 eta-
 3 t prāthyām(rthyam) mama bahutama² janma-janm-āntatarē=³pi tvat-pād-
 āmbhōrū(ru)-
 4 hai(ha)-yuga-gatā nischalā bhaktir=astu || o || Svasti śrī [||*] Tiru-ohchel[va][m*]
 peruga [!*]
 5 Pukkam-āṇa Arivattanapurattu Nāṇādēsi-Viṇṇagar-Ālvār kō-
 6 yil tiru-maṇḍapamuñ=jeṇḍu tiru-k[ka]davum=iṭṭu inda maṇḍapa-
 7 ttukku niṇṇ=erigaikku nilai-vilakk=onṇum=iṭṭēṇ Malai-
 8 maṇḍala[nu]ttu Magōdayarpaṭṭaṇa[tt]u I(ī)rāyiraṇ Śiṇṇān=āṇa Śi(śi)-
 9 Kulasēgara-Ra(na)mbiy-ēṇ [!*] idu śrī [!*] i-daṇmam Malaimaṇḍalattāṇ [!*]

TRANSLATION.

(Line 1.) Hail! Prosperity! (*I have*) no regard for merit, none for a heap of wealth, none at all for the enjoyment of lust. Whatever is to happen, let it happen, O God! in accordance with previous actions. This (*alone*) is to be prayed for (*and*) highly valued by me:—In every other birth also let (*me*) possess unswerving devotion to the pair of Thy lotus-feet!

(L. 4.) Hail! Prosperity! Let the wealth of (*this*) temple increase! (*In*) the temple of Nāṇādēsi-Viṇṇagar-Ālvār at Pukkam *alias* Arivattanapuram, I, Irāyiraṇ Śiṇṇān *alias* Śrī Kulasēkhara-Nambi of Magōdayarpaṭṭaṇam in Malaimaṇḍalam, made a sacred maṇḍapa, gave a sacred door, and gave one fixed lamp to burn constantly in this maṇḍapa. (*Let*) this prosper! This meritorious gift (*was made by*) a native of Malaimaṇḍalam.

No. 28.—SOME RECORDS OF THE RĀSHTRAKUTA KINGS OF MALKHED.

By J. F. FLEET, I.C.S. (RETD.), PH.D., C.I.E.

(Continued from Vol. VI. page 198.)

D.—Mantrawāḍi inscription of the time of Amoghavarsha I.—A.D. 805.

This inscription has been mentioned by me in Vol. III. above, p. 163, note 1. It was originally brought to my notice by Mr. Govind Gangadhar Deshpande. And I obtained ink-impressions of it in 1882. It is now edited for the first time. The colotype is from an ink-impression received in 1886 from Mr. Cousens, Superintendent of the Archaeological Survey of the Bombay Presidency.

Mantrawāḍi is a village about five miles towards the east-by-north from Shiggaon, the head-quarters of the Bankapur taluka of the Dhārwar district. The Indian Atlas sheet No. 42 (1827) shews it as 'Munturrehdee.' The Map of the Dhārwar Collectorate (1874) shews it as 'Muntruwudee.' The present record seems to indicate that its original name was Elpunuse, or else Elamvalli.⁴ And the purport of it places both Elpunuse and Elamvalli in the Purigere district,—the Purigere three-hundred of other records. The inscription is on a

¹ Read *yad-yad*; the *Mukundamāli* reads *yad-bhāgayaṁ tad-bhāvata*.

² The *Mukundamāli* reads *bahumataḥ*.

³ Read *-Antarā-*.

⁴ The maps do not shew, in the neighbourhood of Mantrawāḍi, any villages with names resembling these two.

stone tablet, which was found near a temple of Hanumat at Mantrawâdi and is now stored in the kachêri at Shiggaon.

At the top of the stone, there are sculptures representing the goddess Lakshmî, squatting and facing full-front, with an elephant on each side, standing towards her; the tips of the trunks of the elephants, which are uplifted, meet above her head; and each of them holds, apparently, a flower over her.—The writing covers an area about 2' 0½" broad by 3' 9½" high, and is mostly in a state of very good preservation. In addition to the record edited and shewn in the collotype, there is one line of writing below the sculptures, which are, as usual, on a surface which projects somewhat in front of that part of the stone which bears the body of the record. It is in characters of the same type with those of the body of the record; and it gave the name of the writer: but the greater part of it is damaged and illegible; we can only recognise, at the beginning of the line *Śrī-Rē(?)vayyana*, and at the end *likhitam*, with perhaps a cross-mark below the *m*, as if to shew that something is to be supplied here,—namely, possibly, the *aksharas*, standing before the *Svasti* of line 1 of the body of the record, which are not wanted there and seem to be meaningless.—The characters are Kanarese, boldly formed and well executed. The size of them ranges from about ¾" in the *dha* of *dharmadol*, line 22, to about 1½" in the *va* of *goravarum*, line 8; the *lchi* of *pelchisal*, line 15, and the *ṭṭa* of *koṭṭar*, line 17, are each about 2½" high. The lingual *ḍ* is not very clearly, if at all, distinguished from the dental *d*. As regards the palæography,—the *ṛ* does not occur. The *j* occurs four times, in lines 2, 3, and 8, and is, in each case, of the old square type: the exact form aimed at in this record, is illustrated best in the *jā* of *rājādhi*, line 2, No. 2; it is a closed form, of that particular shape from which there may have been derived, quite directly, the back-to-back *j* and the open *j* which we have in the Doddahundi inscription of Nītimārga and Satyavākya.¹ The *kh* occurs three times, in lines 6, 17, and 20, and again in *likhitam* in the line below the sculptures: in each case, it is of the later cursive type; and the form of it is practically identical with the modern form of the present day: it is seen best in the *kha* of *akhaṇḍita*, at the end of line 17. The *b* occurs more often, and is of the later cursive type, throughout; the intended form of it is seen very clearly in the *bā* of *bādhdā*, line 16, No. 11, and is to be recognised as almost identical with the modern form of the present day. The *l* occurs still more freely, and is, also, of the later cursive type, throughout, including the *l* in *likhitam* in the line below the sculptures; the particular form of it aimed at in this record, is perhaps exhibited most clearly in the *la* of *kālam*, line 17, No. 2. Except in the *l* of *rakshisal*, line 15, where it is hardly to be detected, in the *l*, as presented in this record, we can recognise a feature which played an important part in the process by which the later cursive type of this character was evolved from the old square type, namely, the miniature representation, of the principal part of the old square character, which stands here in the centre of the later cursive character. In the development of the later character, the first step was the prolongation, with a sweep to the right, of the downstroke with which the formation of the original character ended,—a feature which is well illustrated in the Hattī-Mattār inscription of the time of Kṛishṇa I.;² that was eventually followed by a continuation of that stroke up to the top line of the writing; and, meanwhile, the principal part of the original character was diminished, rounded off, and raised, until the original leading characteristic of the old square letter was almost entirely lost. In some Kanarese fonts of the present day, it has disappeared altogether,—for instance, in the font used, in accordance with the general custom, in the Rev. Dr. F. Kittel's *Kanada-English Dictionary*; on the other hand, the miniature of the principal part of the old square character is distinctly recognisable in the font used for the words presented in Kanarese characters in the compilation entitled *Bombay Places and Common Official Words*. In lines 7, 8, 14, 20 (twice), 21, and 22 of this record, we have a peculiar form of the *m*, for which at present the earliest limit is fixed by its occurrence in *para-dattam=bā* in line 14 of the Kanarese grant of

¹ See Vol. VI. above, p. 42, and Plate.

² Vol. VI. above, p. 160, and Plate.

Gôvinda III. of A.D. 804;¹ it is here seen best in the *mā* of *nelamum=Āditya*, line 14, No. 7: it occurs again in *likhitam*, in the line below the sculptures, where it is formed somewhat smaller than usual, so as to mark it as a final form; it is a character which may often be confused with one form of *re*, *rē*. The corresponding form of the *v* occurs, but not very clearly, in the upper *v* of *sarvva*, line 16, No. 10.—The language is Kanarese, of the archaic type, in prose. In *sāsanamum*, line 9-10, the copulative ending *um* is attached to the usual archaic ending of the nominative singular neuter in *m*, *m*; on the other hand, in line 8 it is doubtful whether the *m* has been retained,—*mahājanamum*, or whether it has been softened into *v*,—*mahājanavum*. In line 20 we seem to have the accusative singular neuter in *v*,—*dharmavam*; while, on the other hand, in line 17 we have clearly the more archaic form in *m*,—*sthānaman*. In line 14, in *sthānamuvam* or *sthānavuvam*, the *m*, *m*, of the copulative suffix, with the accusative ending after it, seems distinctly to have been softened into *v*; but, whether the *m* of *sthānam*, *sthānam*, has been retained before it, or has been softened into *v*, is doubtful. Line 10 gives us—(unless we assume a mistake of *s* for *ś*)—*dise*, as another variant of *dise*, *dese*, ‘a quarter or point of the compass, direction, region, side;’ line 12 gives *niru-gal*, which seems clearly to mean ‘a set-up stone,’ *niru* being, no doubt, connected with *niri*, *l*, ‘to be properly arranged or prepared, to be ready,’ from which we have *nirisu*, ‘to put down, place, arrange, adjust, prepare,’ which occurs in line 20 in respect of the setting up of the stone itself that bears the record; ² line 15 gives *peḷchisu*, as a variant of *perchisu*, *pechchisu*, ‘to cause to increase, to multiply;’ ³ and line 21-22 gives *brahmāti*, as a variant of *brahmāti*, *brahmāti*, = *brahmahatyā*, ‘the killing of a Brāhman.’—The orthography does not present anything calling for comment.

The inscription refers itself to the reign of the Rāshtrakūṭa king Amôghavarsha I.,—son and successor of Gôvinda III.,—who was on the throne from A.D. 814 or 815 to A.D. 877 or 878. And it mentions a feudatory of his, named Kuppēya,⁴ who was governing the Purigere district. The object of it was to record the grant of some lands to a priest named Gôkarpa-papditabhāṭāra. The sculptures at the top of the stone mark the record as a Vaishnava record, and thus shew that the donee was a Vaishnava. And it seems worth noting that one of the donors was a Gorava or Śaiva priest.

The record is dated on the full-moon day of Vaiśākha of the Pārthiva *saṃvatsara*, coupled with Śaka-Saṃvat 787. Whatever system of the cycle is applied, the Śaka year is the expired year.⁵


¹ *Ind. Ant.* Vol. XI, p. 127, and Plate.

² Compare *i sāsanaman=nirīsidar*, “they placed, adjusted, or set up, this charter,” in the Daṇḍāpur inscription (*Ind. Ant.* Vol. XII, p. 223, text line 12).—Compare, also, *nirīśida kinnari-galla guḍḍe nālku* in an inscription at Naregal in the Rōp tāluks, Dhārwar (*Jour. Bo. Br. R. As. Soc.* Vol. XI, p. 229, text lines 51, 53, 55), and *nirīśida guḍḍe nālku* (*ibid.* p. 230, line 57). As regards the first of these passages, the occurrence of the combination *kinnarigal* (line 51) or *kinnarigal* (lines 53, 55) in a record at a place named Naregal,—which is mentioned as Hiriya-Nareyaṅgal in a neighbouring record (*ibid.* p. 248, line 20-21), and the name of which would often be written Narigal in the present day,—led me to think that the text referred to a smaller or later Naregal, distinguished from Hiriya-Nareyaṅgal; but I now see that we should interpret the text as meaning, not “four heaps of stones, above graves of Kin-Narigal,” etc., but “four set-up heaps of stones (bearing representations) of female Kinnaras together with a *liṅga* and ascetics and a cow.”

³ Compare *peḷ-dore*, ‘the great river,’ for the more usual *per-dore* in the Mulgund inscription of A.D. 975; Vol. VI, above, p. 259, text line 5.

⁴ The vowel of the penultimate syllable is apparently to be taken as the long *ē*, on the analogy of the *ē* in Baṅkēya, which is marked as long by the metre in line 53 of the inscription at Konnūr (Vol. VI, above, p. 33); but it is not quite certain that the long *ē* is not used there simply to suit the metre. The name of Baṅkēya or Baṅkeya appears also as Baṅka, in Baṅkēśa (Vol. VI, above, p. 30, text line 19). So, also, the name Kuppēya or Kuppeya appears—(but in the case of another person)—as Kuppa, and Kuppappa, in the Nīḍagundi inscription; F. below, page 214.

⁵ By the luni-solar system of the cycle, northern or southern, the Pārthiva *saṃvatsara* was Śaka-Saṃvat 788, current, = A.D. 655-66. By the mean-sign system, it began on the 27th September, A.D. 864, Ś.-S. 786 expired, and ended on the 23rd September, A.D. 865, Ś.-S. 787 expired.



J. F. FLEET.

SCALE .20

W. GRIGGS, COLLOTYPE.

FROM AN IMPRESSION SUPPLIED BY MR COUSENS.

And the corresponding English date is the 14th April, A.D. 865, on which day the full-moon conjunction occurred at about 20 hrs. 54 min. after mean sunrise (for Ujjain).

TEXT.¹

- 1 [Om]² Svasty=Amôghavarsha śrīprithivīvallabha mahâ-
 2 rājādhirāja paramēśvara bhaṭārara r[ā]-
 3 [jy]-ābhivṛddhiyo[=Śaka-n r i p a - k ā l - ā t i t a - s a m v a -
 4 tsara-śataṅga[=ēl-nūr=enbhatt-ēlaneya Pārtthi-
 5 va-saṁvatsaram pravarttise Purigere-nāda[m] Ku-
 6 ppēyan³=āle Vaisākha-māsada paurṇa-
 7 māse(si)y-and=Elpūṇuseya nālvadimba-
 8 r=mmahājanamu(?vu)m⁴ Moni-goravarum Mūlasthā-
 9 nada Mahādēvar=ālv=Elamvalliya śāsa[na]-
 10 mum=ā dēvara mūda-diseyo[=mūda vadḍava . .⁵
 11 ya pola mēreye temka dēvam-geyye mēre
 12 paḍuva niṇ-gal=mēre baḍaga Kālabe(?)ya pola
 13 m[ā]reya mēre-māḍi enbhattay-vattar=kk[e]yyum=āru
 14 tōṇṭada nelanum=Āditya-bhaṭārara sthānamu(?vu)vaṁ⁶
 15 rakshisal=pe[ḥ]chisal=ivarē samarthar=endu Gōka-
 16 rṇa-paṇḍita-bhaṭārargge sarvva-bādhā-parihāram
 17 kālām ka[ḥ]chi koṭṭar=ī sthānaman=ālv goravar=akha-
 18 ṇḍita-brahmachāriy=apudu brahmacharyya-hīnaran=i
 sama-
 19 yada goravarkka[=ka]evor=ī paddhatiyam silā-lē-
 20 khe-māḍi niṇsidar=ppaṇḍita-bhaṭārar=ī dharmmavaṁ⁷ kā-
 21 domg=aśvamēdhada phala[m] aḷiyal-baṅgevoṁge⁸ bra-
 22 hmātiya pāpam=akkum [||*] Nāgadēvan=i dharmmadol=
 gōshṭi(shṭhi) ā(?)dom⁹ [||*]

TRANSLATION.

[Om]! Hail! In the increase of the sovereignty of Amôghavarsha (I.), the favourite of Fortune and of the Earth, the Mahārājādhirāja, the Paramēśvara, the Bhaṭāra,—while the Pārthiva saṁvatsara, the seven hundred and eighty-seventh (year of) the centuries of years that have gone by from the time of the Śaka king, was current,—while Kuppēya¹⁰

¹ From the ink-impressions.

² There seems to have stood here, originally, a plain symbol for the word *Om*, on which there were afterwards overlaid two *akṣaras*, which seem to be *māgi*, apparently belonging to the line of writing below the sculptures above the body of the record (see page 199 above).

³ Regarding this name, see note 4 on page 200 above.

⁴ There is a small mark between the consonant and the vowel, half-way down the consonant, which makes it probable that *m* was written but was not fully engraved; so, also, in *sthānamu(?vu)vaṁ*, line 14, and perhaps, but not so probably, in *dharmmavaṁ*, line 20.

⁵ One *akṣara* is lost here. The consonant must, apparently, be either *ṇ* or *n*. The vowel must be either *i* or *e*. There is a word *odḍavane*, 'array, preparation,' which, however, does not seem suitable here. Otherwise, I can only think of *vadḍavane*, for *odḍa-mane*; but I do not know whether the *m* of *mane* ever changes into *v*; and this word also, meaning "the house or abode of the Odḍas," does not seem altogether suitable.

⁶ See note 4 above.

⁷ See note 4 above.

⁸ Read *baṅgevoṁge*.

⁹ The *akṣara* before the *dom* is doubtful. And the dictionaries do not give any such word as *gōshṭhi* or *gōshṭhīn* in the sense of 'president of an assembly,' which clearly seems to be implied. Perhaps what was intended was *gōshṭhikan=ddom*.

¹⁰ See note 4 on page 200 above.

was governing the Purigere district,—on the day of the full-moon of the month Vaisākha :—

(Line 7) The forty *Mahājanas* of Elpupuse, and the *Gorava* Moni, and the managers¹ of Elamvalli which belongs to the god Mahādēva (Śiva) of the Mūlasthāna,²—saying “He, indeed, is able³ to protect (*the property*), and to increase it,”—gave to the honourable Gōkarnapaṇḍita, free from all molestation, having laved his feet, eighty-five *mattars* of cultivable land, and six plots of garden-land, and the property of Ādityabhaṭāra, on the east side of that same god, making the boundaries to be on the east, the field; on the south, the cultivable land of the god; on the west, a stone that was (*then*) set up; and, on the north, the field of Kālabe(?).

(L. 17) Let the *Goravas* who manage this property be such as keep unbroken the vow of continence; the *Goravas* of this community shall reject those who are wanting in continence. The honourable paṇḍit⁴ put this precept into (*the form of*) a writing on stone, and set it up.

(L. 20) To him who protects this religious grant, there shall accrue the reward of performing an *aśvamēdha*-sacrifice; to him who (*even*) thinks of destroying it, there shall attach the guilt of slaying a Brāhmaṇ !

(L. 21) Nāgadēva was the president of the meeting in the matter of this religious grant.

E.—Sirūr inscription of the time of Amōghavarsha I.—A.D. 866.

This inscription was brought to notice and edited by me in 1883, in the *Ind. Ant.* Vol. XII. p. 215 ff., from an ink-impression obtained in 1882. A lithograph of it was not given then. And, for that and other reasons, it is now re-edited. The collotype which accompanies the present revised version of the record, is from an ink-impression which Mr. Cousens was good enough to obtain for me in 1898, the original impression having suffered some damage and become unsuitable for reproduction.⁵

Sirūr is a village about sixteen miles west-by-north from Nawalgund, the head-quarters of the Nawalgund tāluka of the Dhārwar district. The Indian Atlas sheet No. 41 (1852) shews it as ‘Serroor.’ And the Map of the Dhārwar Collectorate (1874) shews it as ‘Siroor.’ The record gives its name in the older form of Śrīvūra, which may possibly be a mistake for Śrīvūra, with the long ī. And the purport of it places Sirūr in the Belvola three-hundred district. The inscription is on a stone tablet somewhere on the south of the *hūḍe* or village-bastion at Sirūr.

I have no information as to whether there are any sculptures at the top of the stone.—The writing covers an area about 3' 7" broad by 3' 3" high. The extant portion of it is in a fairly good state of preservation, and can be read without any uncertainty, throughout. But, before it came to notice at all, a portion of it had been broken away and lost at the upper left-hand corner, in consequence of which there is missing a part of the text ranging from fifteen or sixteen *aksharas* in line 1, to one *akshara* in line 7. And, since the time when the original impression was obtained by me, some damage has been done to the lower left-hand corner, whereby we have lost one complete *akshara* at the beginning of lines 22, 23, and 24.—The characters are Kanarese, boldly formed and well executed. They contrast rather curiously with those of the Nīlgund inscription, edited in Vol. VI. above, p. 98 ff., which are of a much more square and upright

¹ *Śāsana* seems to be used here in the sense of ‘the act of governing, ruling, government,’ and to be, like *mahājana*, a neuter employed with a collective meaning.

² This probably implies that the temple of Mahādēva was the earliest and principal temple of the village.

³ The original uses the honorific plural,—‘these, indeed, are able.’

⁴ I.e., doubtless, the grantee, Gōkarnapaṇḍitabhaṭāra.

⁵ Owing to the paper used in making the ink-impressions having stretched somewhat unevenly, marks of joining are observable below the end of line 12, and from between the syllables *ta* and *cha* of *ghaṭṭita-charaṇas*, line 5, down to the bottom.

style suggestive, at first sight, of their belonging to a period considerably earlier than the time of the present inscription, though the two records are, in reality, of precisely the same date; this difference is to be attributed, of course, to the facts, that the two records were written by different persons, and that the *Bhaṭṭa* who wrote the Nīlgund record for the engraver to transfer it to the stone, or who painted it on the stone for the engraver to reproduce it there, was a better writer or draughtsman than Mādhavayya who wrote or painted the present record, and also was more guided, in some details, by a prepossession in favour of the older types and style. The writing of the present record is fairly uniform, the size of the letters ranging mostly between about $\frac{7}{8}$ " and $1\frac{1}{8}$ "; the *r*, however, in *Annigereyal*, line 19, and the *ya* in *vijaya*, line 16, are only $\frac{4}{8}$ " high, and the *l* in *iṇḍarvorum*, line 20, is somewhat less: the *rjju* in *Nāgarjjunam*, line 23, is $2\frac{7}{8}$ " high. The record presents final forms, of *l* in *rājyaṁ-bol*, line 14, and of *l* in *Bāraṇḍisvadoḷ*, line 21; there ought to have been a final *t*, of *abhāt*, in line 3, but it was omitted. The distinct form of the lingual *ḍ* is, curiously enough, presented in *puḍidudu*, line 24, where, however, it is a mistake for the dental *d*; whereas it is not shewn in the *ḍu* of *eraḍum* at the end of line 16: a remark, which might have been made earlier, may be made here, namely that it was seldom, if ever, the early practice to use the distinct form of the *ḍ* in the combination *ṇḍ*; we must suppose that the *ṇ* was considered sufficient to mark the nature of the subscript consonant. As regards palæography,—this record presents all the five principal test-letters. The *kh* occurs twice, in *śamkha*, line 9, and in *likhītam*, for *likhitam*, line 23; and, in both places, it is distinctly of the old square type, though there are no actually straight lines in it: it is exhibited best in the *khī* of *likhītam*, line 23, No. 18. The *j* occurs freely, and is of the old square type throughout: we have an open form of it in the *jō* of *dhvajōru*, line 9, No. 29, and again in the *ja* of *paṁkaja*, line 18: in some other cases, illustrated very well by the *ja* of *mahājanāda*, line 20, No. 19, there is a clear space between the centre stroke and the upright part of the letter; but, in other cases, that stroke is joined to the upright stroke, according to the original practice, and we have the fully closed form of the character, as is illustrated very well by the upper *j* of the *rjju* in *Nāgarjjunam*, line 22, No. 22. The *ṇ* occurs ten times, and, following the *j* in the usual manner, is of the old square type, throughout: in some cases, it presents the open form, as in the *ṇa* of *ttuṇga*, line 11, No. 2; in the other cases, it presents the fully closed form, which is illustrated very well in the *ṇa* of *Nripatwāga*, line 13, the last *akshara*. The *b* occurs eleven times: in nine cases, it is of the old square type, sometimes in the closed form illustrated in the *be* of *Beḷvōla*, line 13, No. 26, and sometimes in the open form exhibited in the *bī* of *bīṭṭom*, for *bīṭṭom*, line 20, the last *akshara* but one: but in the *bda* of *śabda*, line 7, No. 4, we can recognise clearly, though the *akshara* is somewhat damaged, the later cursive form, the occurrence of which here is made doubly peculiar by the fact that the old square type was presented in the same word, of the same passage, in line 9 of the Nīlgund record; evidently the writer of this official record, familiar with both types but more accustomed to the later type for ordinary purposes, intended to use the older type of the *b* throughout, but made an involuntary slip in the word *śabda* and inadvertently used the later type there; and it would seem that he began to do the same in the subscript *b* in *nba*, the last *akshara* of line 4, but recognised the mistake almost directly after beginning the letter, and turned it into a *b* of the old square type with a very abnormal dip down in the top stroke.¹ The *l* occurs freely, and is here of the later cursive type throughout, though the Nīlgund record presents the old square *l* much more frequently than the later character: the exact form aimed at, as a rule, in this record, is perhaps exhibited in the *la* of *kālam*, line 20, No. 23, as well as anywhere else: but the *li* of *likhītam*, line 23, No. 17, exhibits very markedly the preservation in

¹ It may be remarked that lines 4 and 7 present the first instances of the occurrence of the letter *b* in this record; and that may account for the peculiarity pointed out. After the first use of the old square *b*, in *bāḍa*, line 12, there is no relapse of any kind into the later cursive type. In the *bā* of *Bāraṇḍisya*, line 22, there is a stroke in the centre, which seems to be due to a slip of the engraver's tool; through some mishap in the final printing, some of the copies of the collotype shew a break, which does not really exist, in the top stroke of this *akshara*.

miniature, in the centre of the later cursive letter, of the principal part of the old square character, to which attention has already been drawn on page 199 above, in the remarks on the Mantravāḍi inscription of A.D. 865; and the same feature is recognisable, though not so pointedly, in *alamkṛitam*, line 1, *kavileyam*, line 21, and *kavileyu*, line 22. There seem to be three abnormal vowel-marks in this record: the stroke projecting downwards from the bottom of the *k* of *ganikā*, near the end of line 8, appears to be intended to supply the *ā*, which was omitted in its proper place on the top line of the writing; in the superscript *i* of *śrīmad*, near the beginning of line 16, the long vowel appears to be marked by a curve on the right, instead of the left in the usual manner; and in *śrīmad*, line 18, it appears that, *i* having been written instead of *ī*, an upward stroke to the right was added, on revision, by way of marking the vowel as long.—As regards the language, we have ordinary Sanskrit verses in lines 1 to 6: and the remainder of the record is in Kanarese, of the archaic style, in prose. As far as the words *Annigereyaḥ=ire*, in line 19, this record follows the same draft on which there was based the corresponding part of the Nīlgund inscription. But this record does not seem¹ to have included the verse *Jayati bhuvana-kīraṇam*, etc., which we have in the beginning of the Nīlgund inscription; and it presents a few various readings, of which, however, only *Sauṭān*, instead of *Gauṭān*, in line 4, is of any particular interest. Like the Nīlgund inscription, this record presents, in line 8, the word *prātīrājya*, employed in the sense of *pratīrāja*, 'a hostile king,' or rather, perhaps, 'a collection of hostile kings.' In *Bāraṇāsivaduḥ*, line 21, we have a curious substitute for the usual locative *Bāraṇāsīyoh*, with which we have to compare the locative *Vāraṇāsivaduh* in an inscription at Baḷagāmi,² and *Bāraṇāsivada*, in the place of the usual genitive *Bāraṇāsīya*, in an inscription at Paṭṭadakal;³ these forms suggest, of course, the existence and occasional use of a base *Bāraṇāsiva* (with such variants as *Bāraṇāsiva* and *Vāraṇāsiva*), for which, however, it is difficult to account.—In respect of orthography, the only points to be noted are (1) the use of *ri* for *ṛi* in the word *sriṣṭi*, line 10, just as in lines 12 and 33 of the Nīlgund record, and again in *vriḍḍhi*, line 15; and (2) the occurrence of *lāñchanam*, instead of *lāñchhanam*, in line 13, just as in line 16 of the Nīlgund record.

This inscription is another record of the reign of the Rāshtrakūṭa king Amōghavarsha I.; and it is distinctly dated in such a way as to shew that he commenced to reign in A.D. 814 or 815.⁴ It mentions, like the Nīlgund inscription, an officer of his, named Dēvaṇṇayya, who, residing at Annigere,⁵ was governing the Beḷvola three-hundred district. And, devoted to the same end with the Nīlgund inscription, it records that Dēvaṇṇayya assigned the tax on clarified butter to the two-hundred *Mahājanas* of Śrīvūra,—doubtless in order to make the proceeds of the tax available for expenditure by them on communal purposes, instead of being credited to the state revenues.⁶

The record is dated at the time of an eclipse of the sun on Sunday the new-moon day of the (*amānta*) month Jyāishṭha of the Vyāsa *samvatsara*, Śaka-Samvat 788 (expired), in the fifty-second year of the reign of Amōghavarsha I. And the corresponding English date is Sunday, 16th June, A.D. 866, when there was a total eclipse of the sun, visible in India, at 9 hrs. 4 min. after mean sunrise.⁷

The date presented in this record fixes, as I have pointed out before now,⁸ the commencement of the reign of Amōghavarsha I. in A.D. 814 or 815, in the following manner. The record places the new-moon day of the *amānta* month Jyāishṭha, on which day the assignment

¹ See page 205 below, note 2.

² *Ind. Ant.* Vol. X. p. 167, No. 105, text line 6.

³ *Ind. Ant.* Vol. XIX. p. 145, text line 13.

⁴ See the next paragraph but one.

⁵ Regarding the use of this form of the name, instead of Annigere with the lingual *ṇ*, see Vol. VI. above, p. 100, note 2.

⁶ See Vol. VI. above, p. 107, note 4.

⁷ See Vol. VI. above, p. 102, note 3.

⁸ In *Ind. Ant.* Vol. XII. p. 216 a, and more fully and clearly in my *Dynasties of the Kanarese Districts*, in the Gazetteer of the Bombay Presidency, Vol. I. Part II., p. 401, note 2.

registered in it was made, in the Vyaya *saṃvatsara*, Śaka-Saṃvat 788 (expired), and in the fifty-second year of his reign. But it does not say that the fifty-second year of his reign coincided either with the *saṃvatsara* or with the Śaka year. The new-moon day of the *amānta* Jyaishṭha, Ś.-S. 788 expired, being in his fifty-second year, it follows that the new-moon day of the *amānta* Jyaishṭha, Ś.-S. 737 expired, fell in the first year of his reign. And the first year of his reign began on some day from Āshāḍha śukla 1 of the Vijaya *saṃvatsara*, Ś.-S. 736 expired, falling in May or June, A.D. 814, to the *amānta* Jyaishṭha kṛishṇa 30 of the Jaya *saṃvatsara*, Ś.-S. 787 expired, falling in June, A.D. 815.

TEXT.¹

- 1 [Ōm || Sa² vò=vyād=Védhasā dhāma yan-nābhi-kamalaṃ kṛi]taṃ Haraś=cha yasya kānt-[é]ndu-kalayā kam=alaṃkṛita[m] ||
- 2 [Labdha³-pratishṭham=achirāya Kalim su]-dā[ra]m⁴=utsāryya śuddha-charitair=ddharanī-talasya kṛitvā punaḥ Kṛitayuga-śrī(śrī)-
- 3 [yam=apy=aśēshām chi]tra[m] katha[m] Nirupama[h*] Kalivallabhō=bhū[t*] ||*
- 4 [jivā jagat=sama]st[am] [yō*] Jagat[t*]jūṅga iti śruta[h] ||* Kēraḷa⁵-Mālava-Śaṭān⁶=sa-Gujjarā¹⁰ Chitraku(kū)ṭa-giridurgga-sthān=ba-
- 5 [ddhvā Kāñch-īśā]n=ā(a)tha sa Kīrttinārāyaṇ[ō*] jagati¹¹ ||* Anī¹²-nripati-makūṭa-ghaṭṭita-charaṇas=sakala-bhuvana-va-
- 6 [ndita]-ś[au]ryya[h*] Vaṅg-Āṅga-Magadha-Mālava-Vemg-īśair=archchitō=Tiśaya-dhavalah ||* Svasti Samadhigartō(ta)pañcha-
- 7 mā(ma)hāśabda-mahārājādhirāja-paramēśvara-bhaṭṭāraka . chatur-udadhi-valaya-va(Pvā)layu(yi)ta¹³-sakala-dharātala-
- 8 prātirājy-ānēka-maṇḍalikarkkalā kaṭaka-kā(ka)ṭis[ū]tra-kunḍala-kēyūra-h[ā]rābharan-ālaṃkṛita-gaṇikā¹⁴-sahasra-

¹ From the ink-impression.— In the footnotes to the text of the Nilgund inscription, Vol. VI. above, p. 102 ff., such differences of reading in the two records, as seem to present anything at all of interest, have been exhibited. It does not seem necessary to shew them all here again.

² Metre, Ślōka (Anuṣṭubh).— Before the verse, there was doubtless an Ōm, represented by a plain symbol, as at the beginning of the Nilgund inscription. There seems to be not room enough for the word *Svasti* to have stood after the Ōm.— From the ink-impressions, it cannot be decided whether there was, or was not, any writing above the first extant line of the present record. But the verse *Jayati dhuvana-kṛāṇam, etc.*, which we have in the beginning of the Nilgund inscription, would fill about a line and a half in the writing of the present record; and the first *pāda* of the verse *Sa vò=vyād, etc.*, preceded by Ōm, quite suffices to fill the lacuna in the first part of line 1. And it seems, therefore, that the verse *Jayati dhuvana-kṛāṇam, etc.*, was not used here, and that no writing is missing above the first extant line; because it would be contrary to custom to leave a blank space of half a line or so between two such verses.

³ Metre, Vasantatilaka.

⁴ The *dā* was at first omitted by the writer, and then was inserted below the line, over the *pa* of *Nirupama* of the next line.

⁵ Metre, Ślōka (Anuṣṭubh).

⁶ See Vol. VI. above, p. 102, note 10.

⁷ Read, probably, *śauryyēṇa-vikramaiḥ*; but see Vol. VI. above, p. 102, note 11. In the *akṣara ryyē*, the vowel *ē* was at first omitted, and then was added on revision.—An inscription at Chīñchli in the Gadag tāluka, of the time of Kṛishṇa II., dated in the Pīṅgala *saṃvatsara*, Śaka-Saṃvat 819 (expired), = A.D. 897-98, seems to present the reading *śauryy-[dṛhka]-vikramaḥ*, "possessed of prowess characterised by heroism."

⁸ Metre; see Vol. VI. above, p. 102, note 13.

⁹ Nilgund, line 6, has *Gauḍān*; see page 207 below, note 9.

¹⁰ Read *Gurjjardn*; or, if *saṃdhi* is observed, *Gurjjardn=Chitra*; and see Vol. VI. above, p. 102, note 15.

¹¹ In the first syllable of this word, *ji* was formed and then was corrected into *ja*.

¹² Metre; see Vol. VI. above, p. 103, note 2.

¹³ See Vol. VI. above, p. 103, note 4.

¹⁴ The *d*, omitted in its proper place, seems to have been supplied, in a very unusual manner, by the stroke projecting downwards from the bottom of the *ka*.

- 9 chāmar-āndhakāra-vādiyya-viyya-māna¹-śvêt-ātapatra-traya-kālaha-sāmk h a-p ā l i d h v a j -
ōru²kētu-patāk-āchchhādita-
- 10 digantar-ella³ sri(sri)sh[*t*]i-sēnāpati puravara-taḷavargga-daṇḍanāyaka-sāmant-ādy-
ānēka-vishaya-vināma⁴-ō-
- 11 ttaṅga-kirīṭa-makūṭa-ghṛishṭa-pādāravinda-yugma nirjjita-vairi ripu-nivaha-Kāla-daṇḍa
dushṭa-mada-bhajjana-
- 12 na⁵ amōgha-Rāma[m] para-chakra-pañch[ā*]nanam sur-āsura-marddanam vairi-
bhaya-karam badde-manōharam abhimāna-mandiram
- 13 Raṭṭa-varṇs-ōḍbhava[m] Garuḍa⁶-lāñcha[ñchha]nam tivilī-paṇeghōshapam
Lattalūra-pura-paramēśvaram śrī-Nripatuṅga-
- 14 nām-ānkita-Lakshmivallabhēndram⁷ chandr-ādityara kalam-varegam mahā-Vishṇuva
rājyam-bol uttar-ōttaram rājy-ābhi-
- 15 vri(vri)ddhi salutt-ire Śaka-nripa-kāl-ātita-samvatsaraṅga[-ē]-nūr-enbhatt-
enṭaneyā Vyayam-emba sa[m*]vatsaram prava-
- 16 rtise śrīmad⁸-Amōghavarsha-Nripatuṅga-nām-ānkitanā vijaya-rājya-
pravardda(rddha)māna-samvatsaraṅga[-ayvatt-eraḍu-
- 17 m-uttar-ōttaram⁹ rājy-ā¹⁰bhivṛiddhi¹¹ salutt-ire Atiśayadhavaḷa-narēndra-
pras[ā*]dadind-Amōghavarsha-
- 18 dēva-pādapaṅkaja-bhramara viśiṣṭa-jan-āśrayan=appa śrīmad¹²=Dēvaṇṇayya[m*]
Beḷvola-mūnūṭuma-
- 19 n=ā¹³uttum=Annigereya¹⁴-ire Jēshṭa¹⁴-māsad-amaseyum-Ādityavāra[mu*]m-āge
sūryya-grahanad-andu
- 20 Śrīvārada Ravikayyam modal-āgi iṇnūrvorum mahājanada kalam kaḷchi tuppā-
deṇeyam bi(bi)ṭṭor [||*]
- 21 ī sti(sthi)tiyam kād-ātā(ta)ṅge Bāraṇāsivadol¹⁵ s[ā*]sira kavileyam koṭṭa
phalam=akkum

¹ See Vol. VI. above, p. 103, note 7; and for *vādiyya-viyya-māna* read either *dādīpyamāna*, 'very brightly shining,' or *dādīyāmāna*, 'being waved to and fro like fans.' In favour of *dādīpyamāna*, it may be noted that a Tamil song presents the expression "O king, whose white umbrella shines resplendent;" see *Ind. Ant.* Vol. XXVIII. p. 29.

² After the *jē*, the writer or engraver first formed a *k*, and then, without properly correcting the *k* into *r*, added the *u* rather imperfectly.

³ In the *akshara re*, the superscript *e* is formed very anomalously.

⁴ Read, probably, *vishay-adhindh*; see Vol. VI. above, p. 103, note 11.

⁵ Apparently *bhañjanam* was intended, without *samdh* with the following word. As remarked in Vol. VI. above, p. 103, note 12, from this point more attention was paid, both in this record and in the Nilgund record, to the case-endings of the nominatives.

⁶ First *ṭa* was written; and then it was corrected into *ḍa*.

⁷ Read *vallabhēndra* or *vallabhēndraṇḍ*. Nilgund, line 17, has the same mistake, except that the *anusvāra* was omitted.

⁸ In the *śrī*, the long *ī* seems to be marked here by a curve on the right, instead of the left as, for instance, in *śrī*, line 13; so, also, in *śrīmad* in line 18 below, it seems to be abnormally marked by a stroke upwards to the right.

⁹ The *anusvāra* is quite clear in the impression, though not in the collotype.

¹⁰ The original had *rājyayj*; and then the *jya* was cancelled.

¹¹ Read *abhiṛiddhi*; see Vol. VI. above, p. 104, note 7.

¹² Regarding the way in which the superscript *t* is formed, see note 8 above.

¹³ Read *Annigereya*, as in Nilgund, line 22; or else *Annigereyal*. As regards the *nni*, which is probably a mistake for *ṇi*, see Vol. VI. above, p. 100, note 3. From the collotype, it might be thought that we have here the long *ī*. But that is only due to a fault in the impression. My impression of 1882 shews distinctly that the vowel-mark is quite closed down on to the top stroke of the consonant, and that the vowel is therefore the short *i*.

¹⁴ Read *Jyēshṭha*; or, more correctly, *Jyāishṭha*.

¹⁵ Regarding this word, see some remarks on page 204 above.

2
 4
 6
 8
 10
 12
 14
 16
 18
 20
 22

- 22 [i]dan¹=alidu tuppam²-uṇṭ-ātā(ta)m Bāraṇṣiyu³ sāsira kavileyu[īh*] sāsirvvar=
pp[ā*]rvvaruman=alidon=akku[m] [||*]
23 [Ni]mbichchara⁴-Bam[m*]ayya besa-geysido Mādhavayyana likhī(khi)taṁ
Nāg[ā*]rjjunam bhe(be)sa-geydo
24 [Si]ri-gāvundana eṭtu⁵-puḍi(di)dudu [||*]

TRANSLATION.

[Ōm!]— (Verse 1 ; line 1) [May he (Vishṇu) protect you, the water-lily (*growing*) in whose
vel is made a habitation by Vēdhas (Brahman)]; and Hara (Śiva), whose head is adorned
a lovely digit of the moon!

(V. 2 ; 1. 2) Since, with his pure actions, he [in no long time] drove far away from the
face of the earth [Kali who had secured a footing there], and made again [complete even]
the splendour of the Krita age, [it is wonderful] how Nirupama-(Dhruva) became (*also*
known as) Kalivallabha.⁶

(V. 3 ; 1. 3) (*There was his son*)⁷ Prabhūtavārsha-Gōvindarāja (III.), who, [having
conquered the whole world] by his heroism and deeds of prowess(?),⁸ was known as Jagat-
ūga.— (V. 4 ; 1. 4) Having [fettered] the people of Kēraḷa and Mālava and Śaṭṭa,⁹ and,
together with the Gurjaras, those who dwell in the hill-fort of Chitrakūṭa,¹⁰ and then [the lords
of Kāñchi], he (*became known as*) Kirtinārāyaṇa on the earth.¹¹

(V. 5 ; 1. 5) (*And then there came his son*) Atiśayadhavaḷa-(Amōghavarsha I.), whose
feet are rubbed by the diadems of hostile kings (*bowing down before him*), and whose heroism
is [praised] throughout the whole world, and who is worshipped by the lords of Vaṅga, Āṅga,
Magadha, Mālava, and Vēṅgi.

(Line 6)— Hail! While, to an extent ever greater and greater, the increase of the
sovereignty of him, Lakshmīvallabhēndra,¹² who is distinguished by the name of the glorious

¹ Read *idan*, with the short *i*. The *ḥ*, of which only a small part is now extant, is supplied from the original ink-impression of 1882, which was made before the stone suffered injury at this place; so, also, the *Ni* at the beginning of the next line, and the *Si* at the beginning of line 24.

² Read *tappum*.

³ Read, probably, *Bāraṇṣiyuṁ*. We might, of course, supply *ḷ*, and, reading *Bāraṇṣiyuḷ*, obtain here another instance of the comparatively rare locative in *uḷ*, regarding which see Vol. VI. above, p. 99, and note 1 on page 100. But it seems more likely that the copulative nominative (*Bāraṇṣiyuṁ*), standing for the accusative (*Bāraṇṣiyuman*), was intended here, as was certainly the case in the next word but one, *kavileyu*, which is a mistake for *kavileyuṁ*, standing for *kavileyuman*. For the justification of the use of the accusative of *Bāraṇṣi* in this and similar passages, see Vol. VI. above, p. 107, note 5.

⁴ This *ra* was evidently at first omitted, and was then inserted on revision.

⁵ The original impression of 1882 shews, between this *akshara* and the *ḥe* which is above it, a thin horizontal line, seven-eighths of an inch long, which seems to have been intended to turn the *ḷ* into a *ḥ*—*eṭtu*. In Mr. Cousens' impression, also, this line is visible; but more faintly, because of a little too much ink having been used. In the collotype, it is hardly discernible at all.

⁶ See Vol. VI. above, p. 105, note 9.

⁷ See Vol. VI. above, p. 105, note 10.

⁸ See Vol. VI. above, p. 102, note 11.

⁹ The Nāgund inscription gives Gauda. Śaṭṭa may perhaps be accepted as another form of Śaṭṭa, the name of a country mentioned in the *Rājatarāṅgi*, vi. 300, which speaks of a *maṭha* founded at Diddāpura for the accommodation of people from the Madhyadēśa or middle country, and from Lāṭa, Śaṭṭa, and Uḍra (?). Or, as in line 13 the writer first wrote *Garuṭa* and then corrected the *ṭa* into *ḍa*, *Śaṭṭan* may be treated as an uncorrected mistake for *Śaṭṭan*. Or, again, we might assume that the *ḥ*, also, is a mistake for *g*, which would not be at all impossible; and, on that view, the *Śaṭṭan* of this record would be simply a mistake for *Gauḍan* in the original draft.

¹⁰ The allusion here seems to be to 'Ohitor' and 'Chitorgarh,' in Rājputāna, rather than, as previously thought by me, to Chitrakōṭ or Chatarkōṭ in Bundēlkhaṇḍ.

¹¹ See Vol. VI. above, p. 106, note 1.

¹² See Vol. VI. above, p. 106, note 2.

Nripatuṅga,— the *Mahārājādhirāja* and *Paramēśvara* and *Bhaṭṭāraka* who has attained the *pañchamahāsabha*;¹ he who has covered all the territories of the numerous chieftains of the hostile kings, over the whole surface of the earth which is girdled by the belt of the four oceans, with his thousands of female elephants² decorated with rings on their tusks and lines on their cheeks and pendants from their ears and bracelets and strings of pearls, and with the darkness (*caused by the multitude*) of his *chauris*, and with his very brightly shining (?)³ three white umbrellas, and with his battle-conches, and with his broad standard of the *pāṇidhvaja* banner and his (*other*) flags; he who is a born leader of armies; he whose feet, resembling water-lilies, are rubbed by the lofty tiaras and diadems (*bowed down before him*) of *Dāyaka* *nāyakas* (*in charge*) of capitals and groups of places, and of chieftains and other lords of districts (?); he who has conquered his foes; he who is a very staff of Death to the host of his enemies; he who breaks down the pride of wicked people; he who is a very unfailing Rāma; he who is a very lion to the army of his enemies; he who subdues gods and demons; he who causes fear to his foes; he who captivates the minds of truthful women; he who is the habitation of haughtiness; he who has been born in the race of the *Raṭṭas*; he who has the *Garuda* crest; he who is heralded in public with the sounds of the musical instrument called *ṭivīḷi*; (*he who has the hereditary title of*) supreme lord of the town of *Lattalūra*, — was continuing, like the sovereignty of the great *Vishṇu*, so as to endure as long as the moon and sun might last;—

(L. 15)—While the *samvatsara* named *Vyaya*, the seven hundred and eighty-eighth of the years elapsed of the era of the *Śaka* kings, was current; and while the fifty-second of the augmenting years of the victorious reign of him who is distinguished by the name of the glorious *Amôghavarsha-Nripatuṅga* was continuing (with) an increase of sovereignty to an extent ever greater and greater:—

(L. 17)—While, by the favour of the king *Atiśayadhavaḷa*, the illustrious *Dēvaṇṇayya*, a very bee on the water-lilies that are the feet of *Amôghavarshadēva* and a very asylum for excellent people, was dwelling at *Annigere*, governing the *Beḷvola* three-hundred:—

(L. 19)—When it was the new-moon day of the month *Jyēṣṭha* and a Sunday, at the time of an eclipse of the sun, he (*Dēvaṇṇayya*) laved the feet of the two-hundred *Mahajanas*, headed by *Ravikayya*, of *Śrīvūra*, and relinquished (*to them*) the tax on clarified butter.

(L. 21)—To him who protects this ordinance, there shall accrue the reward of giving a thousand brown cows at *Bāraṇāsi*; he who, having destroyed it, is (*thereby*) guilty of a misdeemeanour, shall be (*as*) one who destroys *Bāraṇāsi*⁴ or a thousand brown cows or a thousand *Brāhmans*!

(L. 23)—Written by *Mādhavayya*, at the command of *Nimbichhara-Bammayya*; set up and fixed in its place by *Sirigāvunḍa*, at the command of *Nāgārjuna*.

F.—*Niḍagundi* inscription of the time of *Amôghavarsha I.*—About A.D. 874-75.

This inscription has been mentioned by me in Vol. III. above, p. 163, note 1. It is now edited for the first time. I originally obtained ink-impressions of it in 1882. The accompanying colotype, however, is from an ink-impression received from Mr. Cousens in 1886.

Niḍagundi is a village about four miles towards the south-south-west from *Shiggaon*, the head-quarters of the *Baṅkāpur tāluka* of the *Dhārwar* district. The Indian Atlas sheet No. 42

¹ See Vol. VI. above, p. 106, note 3.

² Using another meaning of *ganikā*, which is given in *Monier-Williams' Sanskrit Dictionary*, revised edition, namely 'female elephant' instead of 'courtesan,' I give here a translation which seems more appropriate than that put forward for the same passage in the *Niḷgund* inscription.

³ See above, p. 206, note 1.

⁴ See Vol. VI. above, p. 107, note 5. An inscription at *Āraṇi* in *Mysore* (*Ep. Carn.* Vol. IV., Ng. 51) speaks in the same connection, of the destruction of *Prayāga* as well as of *Bāraṇāsi*.

(1827) shews it as 'Neergoondée.' And the Map of the Dhārwar Collectorate (1874) shews it as 'Needgoondée.' The present record gives its name in the older form of *Niḍugundage*, and marks it as the chief town of a group of villages known as the *Niḍugundage twelve*. And the purport of the record has the effect of placing it and its attached villages in the *Kundarage seventy*, and perhaps in also the *Belgali three-hundred*. The inscription is on a stone tablet, which was found in a field, Survey No. 64, at *Niḍagundi*, and is now stored in the *kachēri* at *Shiggaon*.

The top of the stone, about $7\frac{1}{2}$ " high, shews the sculptures of a *līṅga* on its *abhishēka*-stand, with the bull *Nandin*, recumbent, and facing towards it. These sculptures cover about two-thirds of the top part of the stone. The rest of it, on the proper right side, is occupied by six short lines of writing, in characters of the same type and period, which contain a short supplementary record; they have been numbered 20 to 25, and are given after the text of the body of the record. — The writing of the body of the record covers an area about $1' 9\frac{1}{2}"$ broad by $2' 4\frac{1}{4}"$ high, and is mostly in a state of very good preservation. — The characters are Kanarese, boldly formed and well executed. They are fairly uniform in size, ranging mostly between about $\frac{1}{8}"$ and $\frac{1}{6}"$; but the *yo* of *Vāraṇāsiyoḷ*, in line 17, is only a little more than $\frac{1}{8}"$ high: the *ī* in line 1 is about $2"$ high. The record itself presents final forms, of *t* in *śrīmat*, line 5, and of *m* in *koṭṭam*, line 13, and *paḍedoṃm*, line 16; and we have the final *m* again in the supplementary record at the top of the stone, in *bhaṭṭāram*, line 22. The *anusvāra* is formed between the lines of writing, instead of above the top line, in *idaṃ*, line 16, and apparently also in *kavileyuṃ*, line 18. The distinct form of the lingual *ḍ* can be recognised clearly in *panneraḍuṃṃ*, line 9, and still more so in *perggede*, for *perggaḍe*, line 11; it is also marked, though not so plainly, in *Niḍugundage*, line 9, *Gāḍiyammaṃ*, line 15, and *paḍedoṃm*, line 16: and it is exhibited again in *paḍeda[ṇa]*, line 24. As regards palæography, — the *kh* does not occur. The *j* occurs four times: in the *jya* of *rājyaṃ*, line 3, No. 8, and in the *ja* of *vijaya*, line 4, No. 8, it is of the old square type, closed; but in *jā* twice in *mahārājādhirājā*, line 2, Nos. 6 and 9, it is the later cursive character. The *ñ* occurs twice, in lines 16, 17: in both places, it is of the old square type, closed; it is presented most clearly in the *ñge* of *kādoṅge*, line 16, the last *akshara* but one: it occurs again in the supplementary record, in *anugrahaṇ-geydu*, line 23-24; and there, also, it is of the old square type, closed. The *b* occurs nine times: in the *bḍha* of *ōpalabḍha*, line 4, No. 6, we have the later cursive form; but, in all the other instances, we have the old square type, in the closed form, and the intended exact form of it is perhaps best illustrated by the *ba* of *Baṃ-kēyaṃge*, line 10, No. 4: it occurs again in the supplementary record, in *sabbā*, line 22; and there also, it is of the old square type, but, apparently, in the open rather than the closed form: the solitary instance of the use of the later cursive form in *ōpalabḍha*, line 4, No. 6, must, as in the case of the *Sirūr* record, be explained as a slip on the part of the writer. The *l* occurs more freely still: it is, throughout, of the later cursive type, as also in the supplementary record, in *choḷege* or *volege*, line 23: the *la* of *lakshmī*, line 4, exhibits very markedly the preservation, in miniature, of the principal part of the old square character, to which attention has already been drawn on page 199; but the *la* of *dēgulamaṃ*, line 14, No. 8, probably illustrates best the exact form that was aimed at in this record. — The language is Kanarese, of the archaic type, in prose. In line 23, we have a word *chole* or *vole*, the meaning of which is not apparent. — The orthography does not present anything calling for comment, except (1) the insertion of an unnecessary *anusvāra* in *Rāpanuṃm*, line 10-11, *Gāḍiyammaṃ*, line 15, and *paḍedoṃm*, for *paḍedon* or *paḍedoṃ*, line 16; and (2) perhaps the use of *v* for *b*, in *vaṭṭāra*, line 14, for *baṭṭāra* as a possible *tadbhava*-corruption of *bhaṭṭāra*; here, however, the *v* is possibly simply a writer's mistake for *bh*.

This inscription is another record of the reign of the Rāshtrakūṭa king Amōghavarsha I. It mentions an official of his, named *Baṅkēya* or *Baṅkēyarasa*, who was governing the *Banavāsi twelve-thousand* province, and the districts known as the *Belgali three-hundred*, the

Kundarage seventy, the Kundûr five-hundred, and the Purigere three-hundred. And it mentions also a son of Bañkôya, named Kundatte, who was governing the group of villages known as the Nidugundage twelve. The primary object of it was to record the grant of some lands to a temple of the god Mahâdêva (Śiva). The short supplementary record at the top of the stone, indicates a certain Viṇakadêva as the person on whose instigation the grant was made.

The date of this record is expressed in a very exceptional and peculiar manner. The Śaka year is not mentioned. Nor is the name of the *saṃvatsara* given. And the record only refers itself to the time,—Amôghavarsha ond-uttaram rājyam-geyyutt-ire, —“while Amôghavarsha was reigning increased by one.” Evidently, there was here an omission of some kind or another, whether intentional or accidental. And we have to consider whether we can supply that omission.

Now, from the Sirûr inscription, which quite clearly and unmistakably places the new-moon day of the *amânta* month Jyaishṭha of the Vyaya *saṃvatsara*, Śaka-Saṃvat 788 expired, in the fifty-second year of his reign, we know, as shewn on page 204 f., that Amôghavarsha I. began to reign in A.D. 814 or 815. One of the Kanheri inscriptions supplies for him the date, without full details, of Ś.-S. 799 (expired), = A.D. 877-78.¹ Though he had then been reigning for at least sixty-two full years, we might, if we should like, as there is nothing as yet in the dates of his successor to oppose it, add another two years to his reign. And it might thus be thought possible to take the date of the present record as equivalent to “(the Śaka year 800) increased by one,” that is to say, Śaka-Saṃvat 801 (expired), = A.D. 879-80. We have, however, not any proved instance of Indian historical dates having been expressed in that elliptical manner, with omission of the centuries, except in connection with the Laukika reckoning of Kashmîr and of some adjacent parts of Northern India. That reckoning was devised in only the tenth, or possibly the ninth, century A.D. There is not anything that can give us a reasonable cause for believing in the existence of any Indian custom of recording historical dates with “omitted hundreds,” except in those parts and in connection with that particular reckoning. And I do not for a moment think it possible that the present date is to be explained in that way.

Some other explanation must be found. Now, we know that the reign of Amôghavarsha I. lasted for at least sixty-two full years, and that it thus included one complete revolution of the sixty-years cycle of the planet Jupiter. We know, also, that the use of that cycle, in the Kanarese country, was definitely established by the Râshtrakûṭas, and that it was already being freely used there in the time of Amôghavarsha I. There is, indeed, one epigraphic instance of its use in those parts before the Râshtrakûṭa period; namely, in the Mahâkûṭa pillar inscription of the Western Chalukya king Maṅgalêsa, which is dated in the fifth year of his reign and in the Siddhârtha *saṃvatsara*, with other details which place it on exactly the 12th April, A.D. 602.² That, however, is at present only an isolated epigraphic instance of earlier times. But the use of the cycle was definitely established by the Râshtrakûṭas. Amongst the records of Gôvinda III., the father and predecessor of Amôghavarsha I., we have it in the plates from the Kanarese country of A.D. 804, in the Wanî plates of A.D. 807, in the Râdhanpur plates of A.D. 808, and in the Tôrkhêdê plates of A.D. 813.³ Amongst the records of Amôghavarsha I., we have already found it used in the Kanheri inscription of A.D. 851,⁴ in the Mantrawâḍi inscription of A.D. 865,⁵ in the Nîlgund inscription of A.D. 866,⁶ and in the Sirûr inscription of

¹ *Ind. Ant.* Vol. XIII. p. 135, No. 48 A.

² See a note on this subject, which I am giving in the *Indian Antiquary*, Vol. XXXII.

³ See Prof. Kielhorn's List of Inscriptions of Southern India, in the Appendix to this volume, p. 10, No. 62, p. 11, Nos. 63, 64, and p. 12, No. 67.

⁴ See Prof. Kielhorn's Southern List, p. 13, No. 73.

⁵ Page 201 above.

⁶ See Prof. Kielhorn's Southern List, p. 13, No. 75.

the same date.¹ I have found it used in various other records of his time in the Kanarese country. It was used very freely in the Rāshtrakūṭa records of subsequent reigns, in all parts of their dominions. And I do not hesitate to decide that the explanation of the present date is to be found in connection with that system of reckoning, and that the expression *ond-uttaram*, presented in this record, is the abbreviation of a full expression which would be *ond-uttaram=aruwattaneya varsham*, "the sixtieth year increased by one." I have not overlooked the possibility of the eleventh, twenty-first, thirty-first, forty-first, or fifty-first year being intended. But it is difficult to recognise anything rational in an elliptical expression being used for any of those years. On the other hand, with a cycle of sixty years actually in use, an elliptical method of designating years in excess of the number of sixty, in such a case as this one, is perfectly intelligible and admissible. And I entertain no doubt that that is the method which was adopted in recording the date of the present record. This record is, therefore, to be placed roughly about A.D. 874-75. The palæography of the record is quite in agreement with this result. And the result is also thoroughly in accordance with the date in A.D. 897, which is established by the *prasasti* of the *Uttarapurāṇa* for Lōkāditya, son of the Baṅkēya who is mentioned in this record.²

The question remains, whether this explanation places the record in actually the sixty-first year of Amōghavarsha I., or whether it places it in the sixty-first *saṃvatsara* counted from, and including, the *saṃvatsara* in which his reign commenced. The two things are not exactly the same; because it happens that, in the period A.D. 814-15 to 877-78 covered by the reign of Amōghavarsha I., there was an apparent or an actual omission of a *saṃvatsara*. If the *saṃvatsaras* were taken according to the so-called northern luni-solar system, then the year Ś.-S. 745 expired was the Subhakrit *saṃvatsara*, No. 36, and the year Ś.-S. 746 expired was the Krōdhin *saṃvatsara*, No. 38, and there was an actual omission of the Śōbhana *saṃvatsara*, No. 37.³ If, on the other hand, they were taken according to the actual mean-sign system which underlay and governed the other system, then there was not an actual omission of that or any other *saṃvatsara*; but each of the sixty *saṃvatsaras* ran its full course, and there was only an apparent omission of Śōbhana, No. 37, presenting itself in the fact that the first day of the year Ś.-S. 745 expired fell in Śubhakrit, No. 36, while the first day of the year Ś.-S. 746 expired fell in Krōdhin, No. 38. It does not seem necessary to make calculations for the period A.D. 873 to 876, to determine the *saṃvatsaras* for those years according to the actual mean-sign system; especially, as Professor Kielhorn has arrived at the conclusion that the system then in use was the so-called northern luni-solar system.⁴ It seems sufficient to state the following results.

We have seen, on page 205, that Amōghavarsha I. began to reign at some time from Āshāḍha śukla 1 of the Vijaya *saṃvatsara*, Śaka-Saṃvat 736 expired, falling in May or June, A.D. 814, to Jyaishṭha kṛishṇa 30 of the Jaya *saṃvatsara*, Ś.-S. 737 expired, falling in June, A.D. 815. The first *saṃvatsara* after a complete round of the *saṃvatsaras* would be, again, either Vijaya, Ś.-S. 795 expired, beginning, according to the so-called northern luni-solar system, in A.D. 873 and ending in A.D. 874, or else Jaya, Ś.-S. 796 expired, beginning in A.D. 874 and ending in A.D. 875; and the record is to be placed in A.D. 873, 874, or 875.

On the other hand, the actual sixty-first year of Amōghavarsha I. would commence on some day from Āshāḍha śukla 1 of the Jaya *saṃvatsara*, Śaka-Saṃvat 796 expired, in A.D. 874, to Jyaishṭha kṛishṇa 30 of the Manmatha *saṃvatsara*, Ś.-S. 797 expired, in A.D. 875; and the record is to be placed in A.D. 874, 875, or 876. A more exact result cannot be arrived at, because the month and *tithi*, with the week-day or any other detail, are not specified.

¹ Page 205 above.

² See a note on the Mukula or Chellakētana family, which I am giving in the *Indian Antiquary*, Vol. XXXII.

³ See Sewell and Dikshit's *Indian Calendar*, Table I., p. 34.

⁴ See *Ind. Ant.* Vol. XXV, p. 269.

Of the territorial divisions mentioned in this record, the **Banavāsi twelve-thousand** and the **Purigeṛe three-hundred** are already well known. The **Niḍugundage twelve** was, of course, a group of villages headed by the modern **Niḍagundi** itself. The position of the **Kundarage seventy** is probably marked by a village in the North Kanara district, the name of which is not given in the Indian Atlas sheet No. 42 (1827) but is shewn in the Map of the **Dhārwar** Collectorate (1874), perhaps as a hamlet or deserted village, as '**Koondurgee**,' one mile and a half east-by-south from **Mundagōḍ** in the **Yellāpur tāluka** and nine miles west-by-north from **Niḍagundi**. The **Belgali three-hundred** may be connected either with a village in the **Baṅkāpur tāluka**, which is shewn as '**Belgulle**' in the Indian Atlas sheet No. 41 (1852), and as '**Belugulle**' in the Collectorate Map, four miles on the north of **Shiggaon**, and about eight miles north-by-east from **Niḍagundi**, or with a village in the **Hubli tāluka**, which is shewn as '**Belgulle**' in the Collectorate Map, but as '**Bellaguttee**' — (no doubt, by mistake for '**Bellagulle**') — in the Atlas sheet No. 41, about seven and a half miles on the south of **Hubli**, and twenty-two miles towards the north-by-west from **Niḍagundi**. The position of the **Kundūr five-hundred** is a more difficult question. There is a village in the **Baṅkāpur tāluka**, which is shewn in both the Atlas sheet No. 42 and the Collectorate Map as '**Koondoor**,' seven miles south-south-east-half-south from **Shiggaon**, and five miles south-east from **Niḍagundi**; but the close proximity of the **Pānuṅgal** or **Hānuṅgal five-hundred** and the **Purigeṛe three-hundred** districts, renders it difficult, if not impossible, to find room for a five-hundred district there. And there is also a '**Kundur**' somewhere in the **Sirsi tāluka** of North Kanara; but, if the **Kundūr five-hundred** lay there, **Baṅkēyarasa** must have been governing also the **Pānuṅgal five-hundred**, intervening directly between that locality and the **Purigeṛe three-hundred**; whereas, the record does not mention the **Pānuṅgal five-hundred**. A **Kundūr five-hundred**, however, appears to be mentioned elsewhere, in the passage in the **Amīnbhāvi** inscription of A.D. 1113,¹ which, according to the transcription given in Sir Walter Elliot's Manuscript Collection, mentions the place as **Ammāiyyanabhāvi**, and claims that, in the time of the Western Chalukya king **Pulakēśin II.**, and in A.D. 566 or 567 (an altogether incorrect date), certain grants were made to the god **Kalidēva** of **Ammāiyyanabhāvi**, which was an *agrahāra* in the **Kundūr five-hundred** of the **Palasige** province (*viśhaya*). **Amīnbhāvi** is about six miles north-north-east from **Dhārwar**, and about thirty miles on the east of **Halsi**, the ancient **Palasige**, in the **Khānāpur tāluka**. The position is a thoroughly suitable one for the **Kundūr five-hundred** district. And I think that we may safely take it that the **Kundūr five-hundred** of the present record is localised by the **Amīnbhāvi** record and included that village, though I cannot at present identify the town, **Kundūr**, from which the district took its appellation.

TEXT.²

- 1 Svasty³-Amōghavarsha śrīprithiviva-
- 2 llabha mahārājādhirājā(ja) ' paramēśvara bhaṭ[ā]-
- 3 rara(r) ond-uttaram rājyam-geyyuti-ire satya-samara-
- sam-
- 4 ghaṭṭan(n)-ōpalabdha-vijaya lakshmi-nivāsita-⁴
- 5 chellakētana śrīmat [Baṅkēy⁵-arasara(r) Banavāsi-⁶

¹ Regarding this record, see *Dyn. Kan. Distrs.* p. 358, note 1, and *Ind. Ant.* Vol. XXX. p. 209.


² From the ink-impressions.

³ The marks before this word do not seem well enough defined to be taken for the remnants of a damaged symbol for the word *Om*.

⁴ The second syllable of this word is an anomalous character, neither exactly *va* nor exactly *ma*. It occurs again in *Banavāsi*, in the next line.

⁵ Regarding the quantity of the vowel of the second syllable of this name, see note 4 on page 200 above.

⁶ Regarding the third syllable of this word, which is neither exactly *va* nor exactly *ma*, see note 4 above.



J. F. FLEET.

SCALE .80

W. GRIGGS, COLLOTYPE.

FROM AN IMPRESSION SUPPLIED BY MR. COUSINS.

- 6 pannirchchāsiramumân=Belgali-mûnûrumâm Kundara-
 7 ge-elpattumâm Kundûr-aynûrumâ[m] Purigere-
 8 mûnûrumâm Bankêy-arasar¹=âutt-ire Bankêya-
 9 na maga[m] Kundaṭṭe Niḍugundage-panneraḍumân=â-
 10 ḷutt-īḍu Bankêyamge dharmmam=akk=endu Kundaṭ-
 ṭeyum Râ-
 11 panuim²=īḍu Niḍugundage-panneraḍara pergge-
 (rgga)ḍe
 12 Kuppappana dēgulada Mahādēvargge or-mmattar=
 ttōṭṭamu[m]
 13 ay-mattar=kkeyyu koṭṭam³ [||*] Maḷdam tanna
 bhāgamam kuḍe ā
 14 vaṭṭāra⁴ Kupa[m] dēgulamam māḍisi sarvva-bādha-pa-
 15 riḥāram Śamkaram nāl-gāmu[nḍu*]-geye Gāḍiyam-
 mam⁵=ā bā-
 16 la[m] paripālisi nile paḍedomm⁶ [||*] Idam kādoṅge
 Vā-
 17 raṇāsiyol=aśvamēdhada phalam idan=aḷidoṅge
 18 sāsira kavileyum sāsirvvar=pārvvarumân=aḷida ma-
 19 hā-pātakam=akku [||*] Ōm⁷ [||*] I(i) kallam Durgga-
 d[ā]sam samedo[m] [||*]

At the top of the stone.

- 20 Namāstē⁸ Śrī(śrī)-
 21 Viṇa kadēvā(v a)-
 22 bhaṭṭāram⁹ sabbā(bba)-
 23 cho(?vo)lege¹⁰ anugra-
 24 haṇ-geydu paḍeda[m]
 25 i(i) tāṇama[m] [||*]

TRANSLATION.

Hail! While Amôghavarsha, the favourite of Fortune and of the Earth, the Mahārāja-dhīrāja, the Paramēśvara, the Bhaṭṭa, was reigning (for the sixtieth year) increased by one;¹¹ and while the illustrious Bankēyarasa, whose javelin-banner has been taken as an abode by the goddess of victory won by encounterings in genuine battle, was governing the whole of

¹ This is an unnecessary repetition of the nominative which we have already in line 5.

² Read *Kāpanum*.

³ Read *kkeyyum koṭṭar*.—The use of the final *m* in *koṭṭam* is rather peculiar; *koṭṭam* (or *koṭṭan*) would have been more correct. Compare *paḍedomm* for *paḍedom* (or *paḍedon*), line 16, and *bhaṭṭāram* for *bhaṭṭāram* (or *bhaṭṭāran*), line 22.

⁴ In the second syllable of this word, the subscript *ṭ* has not been properly joined to the upper *ṭ*; and it has also been carried so low as to be overrun by the top stroke of the *h* of *riḥāram* in the next line. The word itself, *vaṭṭāra*, either is a mistake for *bhaṭṭāra*, or else stands for *bhaṭṭāra* as a possible *taddhava*-corruption of *bhaṭṭāra*.

⁵ Read *Gāḍiyamman*.

⁶ Read *paḍedom*; see note 3 above.

⁷ Represented by an ornate symbol, much damaged.

⁸ Read *namō=stu*.

⁹ Read *bhaṭṭāram*; see note 3 above.

¹⁰ It is just possible that, before the *o* or *vo*, there may be a cramped and imperfectly formed *akshara*,—perhaps *ra* or *ka*,—on the edge of the stone.

¹¹ See page 210 f.

the Banavāsi twelve-thousand, the Belgai three-hundred, the Kundarage seventy, the Kundūr five-hundred, and the Purigere three-hundred :—

(Line 8) Kundaṭṭe, the son of Baṅkēya, while governing the Niḍugundage twelve, said to Baṅkēya—"Let there be a religious grant;" and Kundaṭṭe and Rāpa, being convened,¹ gave one *mattar* of garden-land and five *mattars* of cultivable land to the god Mahādēva of the temple of Kuppappa the *Perage* of the Niḍugundage twelve.

(L. 13) On Maḷda giving his own share, that same honourable Kappa caused the temple to be made; and, while Śaṅkara was holding office as *Nālgāmunḍu*, Gāḍiyamma, protecting that property, acquired it so that it continued unimpaired, free from all molestation.²

(L. 16) To him who protects this, there shall accrue the reward of performing an *astu-mēḷhu*-sacrifice at Vāraṇāsi; to him who destroys it, there shall attach the guilt of the great sin of destroying a thousand brown cows or a thousand Brāhmaṇas!

(L. 19) Durgadāsa prepared this stone.

At the top of the stone.

(L. 20) Let there be reverence! The honourable one, the saintly Viṇakadēva, did a kindness to the whole . . . ,³ and obtained this property.

* * * * *

The family-name of the Rāshtrakūṭas of Māḷkhēḍ.

To my previous paper on some of the records of the Rāshtrakūṭa kings of Māḷkhēḍ, in Vol. VI. above, p. 160 ff., I attached some notes on a few special points, chiefly in connection with the names, *birudas*, and other appellations of the various members of that family. Eventually, we shall consider some wider questions, such as the antiquity that may be assigned to the Rāshtrakūṭa stock, the extraction of the Rāshtrakūṭas, the period and localities in which they first came to the front as a ruling power, and the distribution of them in later times as indicated in the first place by epigraphic records, and in the second place by the existence of tribes and clans who now claim to be of Rāshtrakūṭa descent. Meanwhile, I deal now with some more preliminary points.

In line 13 of the Sirūr inscription of A.D. 866,⁴ as also in the corresponding passage in line 16 of the Nilgund inscription of the same date,⁵ the family-name of the Māḷkhēḍ dynasty is presented to us, in the formal *prasaṣti* or eulogy in Kanarese prose which introduces the practical details of the record, as Raṭṭa, in the description of Amōghavarsha I. as *Raṭṭa-vāṁś-ōḍbhava*, "born in the race of the Raṭṭas, or in the Raṭṭa race."⁶ And these two passages are the earliest known passages which present the name Raṭṭa.

¹ *Idu* is equivalent to *oḍan=idu*; see Vol. VI. above, page 68, note 6.

² This passage, the construction of which is not quite grammatical, seems to recite the previous founding of the temple, and the original endowment of it.—The meaning of *nile* is not quite certain; but the word seems to be a form of the infinitive of *nil*, *nilu*, in the sense of 'to stand or last, to continue unimpaired.' A very similar expression, *nīla māḍisidom*, occurs in line 46 of the Hebbāl inscription of A.D. 975 (Vol. IV. above, p. 354); *nīla*, also, is a form of the infinitive of *nil*, *nilu*.

³ The meaning of the word at the beginning of line 23 is not known.

⁴ Page 206 above.

⁵ Vol. VI. above, p. 108.

⁶ It is convenient to speak of "the Raṭṭa or Rāshtrakūṭa race, lineage, or family," and of "the Raṭṭa or Rāshtrakūṭa kingdom, rule, or sovereignty." And we meet with the actual expression *Raṭṭa-āhvayō vāṁśah*, "the race which has the appellation Raṭṭa;" see page 218 f. But the exact analysis of all such compounds as *Raṭṭa-vāṁśa*, *Rāshtrakūṭa-kula*, and *Raṭṭa-rājya*, etc., seems to be *Raṭṭāndm vāṁśa*, "the race of the Raṭṭas," *Rāshtrakūṭāndm kula*, "the family of the Rāshtrakūṭas," and *Raṭṭāndm rājya*, "the kingdom, rule, or sovereignty of the Raṭṭas," and so on; compare the expressions *vāṁśō . . . Yadūndm* and *Yadu-kula* on page 37 above, text lines 8, 9, and 9-10, and *Yadōr-anvayah* and *Yadu-vāṁśa* in *Ind. Ant.* Vol. XII. p. 264, text lines 4 and 6-7.

In the records of the Mālkhēḍ dynasty, the only other known instances in which the name occurs in the same form, *Raṭṭa*, are the following. The two sets of Bagumrā plates of A.D. 915 speak, in a Sanskrit verse, of *Raṭṭa-rājya*, "the kingdom, rule, or sovereignty of the *Raṭṭas*;"¹ and the same expression occurs again in the Dêlî plates of A.D. 940, in two Sanskrit verses,² and again in the same two verses in the Karhâḍ plates of A.D. 959.³ The Bagumrā plates of A.D. 915 further apply to Indra III., again in a Sanskrit verse, the *biruda* *Raṭṭakandarpa*, "a Kandarpa, Kâma, or Love of the *Raṭṭas*;"⁴ and the same *biruda* is applied to Gôvinda IV. in a Kanarese verse in the Kaḷas inscription of A.D. 930,⁵ and to Khotṭiga in Kanarese prose in the Adaraguñchi inscription of A.D. 971,⁶ and to Indra IV. in Kanarese verses in the Śravaṇa-Belgoḷa inscription of A.D. 982.⁷ The Kaḷas inscription of A.D. 930, in the Kanarese prose passage which leads up to the date and other details of the record, further applies to Gôvinda IV. the *biruda* *Raṭṭavidyādhara*, "a *Vidyādhara* or demigod of the *Raṭṭas*."⁸ And the Dêlî plates of A.D. 940 introduce, in a Sanskrit verse, the eponym *Raṭṭa*, as the name of the imaginary person whom that record puts forward as the original ancestor of the family;⁹ and the same verse occurs in the Karhâḍ plates of A.D. 959.¹⁰

In those of the other records of the Mālkhēḍ dynasty which put forward the proper name of the family and do not refer to it as simply the race, family, or lineage of Yadu or of the Yadus,¹¹ the name is always given as *Rāshṭrakūṭa*. The Sāmāṅgaḍ plates of A.D. 754 liken Indra II., in a Sanskrit verse, to *sad-Rāshṭrakūṭa-kanakāūrī*, "a golden mountain (Mêru) of the good *Rāshṭrakūṭas*;"¹² and we have the same verse in the Paithan plates of A.D. 794,¹³ in the Nausârî plates of A.D. 817,¹⁴ in the Kāvî plates of A.D. 827,¹⁵ in the Bagumrā plates of A.D. 867,¹⁶ in the Chokkhakuṭi grant of A.D. 867,¹⁷ and in the Bagumrā plates, of doubtful authenticity, of A.D. 888.¹⁸ The Nausârî plates of A.D. 817, in another Sanskrit verse, describe Dhruva as *Rāshṭrakūṭa-tilaka*, "an ornament of the *Rāshṭrakūṭas*;"¹⁹ and this verse occurs again in the Kāvî plates of A.D. 827,²⁰ in the Bagumrā plates of A.D. 867,²¹ in the Chokkhakuṭi grant of A.D. 867,²² and in the Bagumrā plates, of doubtful authenticity, of A.D. 888.²³ The Baroda plates of A.D. 835 speak, in a Sanskrit verse, of *śulūkika-Rāshṭrakūṭa*, "tributary *Rāshṭrakūṭas*;"²⁴ and the same verse is presented in the Bagumrā plates of A.D. 867,²⁵ in the

When *śrī* is prefixed, as, for instance, in *śrī-Rāshṭrakūṭa-ānvaya*, the proper analysis seems to be *śrīmatām Rāshṭrakūṭānam=ānvaya*; compare, for instance, *śrīmatām . . . Chalukyānam kulam* in *Ind. Ant.* Vol. VI. p. 76, text lines 2, 6.

¹ *Jour. Bo. Br. R. As. Soc.* Vol. XIII. p. 258, B., plate ii. a, text line 5, and p. 262, A., plate ii. a, line 3.—In my previous paper, these two records have been referred to as "the Nausârî plates of A.D. 915." I have already indicated the reason for which they are to be properly known as "the Bagumrā plates of A.D. 915;" see Vol. VI. above, Additions and Corrections, p. vi.

² Vol. V. above, p. 194, text lines 29, 32.

³ Vol. IV. above, p. 234, text lines 31, 39.

⁴ *Loc. cit.* (note 1 above), p. 259, B., plate ii. b, text line 5, and p. 263, A., plate ii. b, line 2.

⁵ This record has not been published yet. I quote it from an ink-impression.

⁶ *Ind. Ant.* Vol. XII. p. 256, text line 4-5.

⁷ *Inscr. at Śrav.-Bel.* No. 57, verses 2, 17.

⁸ See note 5 above.

⁹ Vol. V. above, p. 193, text line 11.

¹⁰ Vol. IV. above, p. 232, text line 10-11.

¹¹ Two verses presented in the Cambay plates of A.D. 930 (p. 37 above, text lines 8 f. and 9 f.), and again in the Sāngli plates of A.D. 933 (*Ind. Ant.* Vol. XII. p. 249, text lines 4 f. and 5 ff.), simply place the members of the family in the *Yadūnām vamsā* or *Yadu-kula*. The Kharda plates of A.D. 972 similarly place them in the *Yadōr=ānvaya* or *Yadu-vamsā* (*Ind. Ant.* Vol. XII. p. 264, text lines 4, 6-7).

¹² *Ind. Ant.* Vol. XI. p. 112, text line 14.

¹³ Vol. III. above, p. 106, text line 9.

¹⁴ *Jour. Bo. Br. R. As. Soc.* Vol. XX. p. 136, text line 9.

¹⁵ *Ind. Ant.* Vol. V. p. 146, verse 6.

¹⁶ *Ind. Ant.* Vol. XII. p. 182, verse 6.

¹⁷ Vol. VI. above, p. 288, text line 7.

¹⁸ *Ind. Ant.* Vol. XIII. p. 66, verse 4.

¹⁹ *Jour. Bo. Br. R. As. Soc.* Vol. XX. p. 137, text line 31.

²⁰ *Ind. Ant.* Vol. V. p. 146, verse 20.

²¹ *Ind. Ant.* Vol. XII. p. 182, verse 17.

²² Vol. VI. above, p. 289, text line 20.

²³ *Ind. Ant.* Vol. XIII. p. 67, verse 11.

²⁴ *Ind. Ant.* Vol. XIV. p. 149, text line 17.

²⁵ *Ind. Ant.* Vol. XII. p. 183, verse 29.

Chokkhakuṭi grant of A.D. 867,¹ and in the Bagumrā plates, of doubtful authenticity, of A.D. 888.² And the Kaḷas inscription of A.D. 930³ describes Gōvinda IV., in a Kanarese verse, as *Rāshtrakūṭ-ōttama*, "a best of the *Rāshtrakūṭas*." The Wanī plates of A.D. 807 mention the family, in a Sanskrit verse, as *śrī-Rāshtrakūṭ-ānvaya*, "the lineage of the glorious *Rāshtrakūṭas*;"⁴ we have the same verse in the Rādhampur plates of A.D. 808;⁵ and the inscription of probably the period A.D. 814-15 to 877-78 at the Daśavatāra cave at Ellōrā, speaks, in another Sanskrit verse, of *prakāṣa-Rāshtrakūṭ-ānvaya*, "the manifest, public, or well-known lineage of the *Rāshtrakūṭas*." The Baroda plates of A.D. 812 speak, in a Sanskrit verse, of *śrī-Rāshtrakūṭ-āmala-vamśa*, "the spotless race of the glorious *Rāshtrakūṭas*;"⁷ the Dēoli plates of A.D. 940, and, following the same draft, the Karhād plates of A.D. 959, again in a Sanskrit verse, speak of *Rāshtrakūṭa-vamśa*, "the race of the *Rāshtrakūṭas*, or of *Rāshtrakūṭa*," and propose to account for the name by saying that the family derived it from the name of a certain (imaginary) *Rāshtrakūṭa* whom these records put forward as the son of the eponymous *Raṭṭa*.⁸ Finally, the Bagumrā plates of A.D. 915 introduce the family, again in a Sanskrit verse, as *śrī-Rāshtrakūṭa-kula*, "the family of the glorious *Rāshtrakūṭas*;"⁹ and the same expression *Rāshtrakūṭa-kula*, "the family of the *Rāshtrakūṭas*," is put forward, in ornate prose, in the Kaḍaba plates,¹⁰ which purport to have been issued in A.D. 813, but which are not of unquestionable authenticity.

In the records of some other early branches of the same general stock, but only distantly connected, if actually connected at all, with the Mālkḥēḍ family, we find used only the form *Rāshtrakūṭa*. Thus, in Sanskrit prose, the Uṇṭikavāṭikā grant of Abhimanyu describes his first ancestor Mānāṅka as *Rāshtrakūṭānām tilaka*, "an ornament of the *Rāshtrakūṭas*."¹¹ A Sanskrit verse in the Multāi plates of A.D. 709 places Durgarāja, the first ancestor of Yuddhāsura-Nandarāja, *śrī-Rāshtrakūṭ-ānvayē*, "in the lineage of the glorious *Rāshtrakūṭas*."¹² And a Sanskrit verse in the Āntrōli-Chhārōli plates of A.D. 757 describes Kakkarāja I., the first ancestor of Kakkarāja II., as *śrī-Rāshtrakūṭa-kula-pankaja-shaṇḍa-sūrya*, "a sun of the group of water-lilies (blooming in the daytime) which is the family of the glorious *Rāshtrakūṭas*."¹³

In later extraneous records which mention the Mālkḥēḍ family, we find the following usage. A Sanskrit verse in an Eastern Chalukya copper-plate record of the period A.D. 918 to 925 describes Vijayāditya II. (A.D. 799 to 843) as fighting during twelve years, by day and by night, a hundred and eight battles with the armies of the Gaṅgas and the *Raṭṭas*; and a subsequent Sanskrit verse in the same record says that Vijayāditya III. (A.D. 844 to 888), prompted by the lord of the *Raṭṭas*, conquered the Gaṅgas, and cut off the head of Maṅgi in battle, and frightened Kṛishṇa and Saṅkila, and completely burnt their city.¹⁴ In the Chōḷa

¹ Vol. VI. above, p. 290, text line 36.

² *Ind. Ant.* Vol. XIII. p. 67, verse 18.

³ See note 5 on page 215 above.

⁴ *Ind. Ant.* Vol. XI. p. 158, text line 17.

⁵ Vol. VI. above, p. 243, text line 18.

⁶ *Archaeol. Surv. West. Ind.* Vol. V. p. 82, text line 3.

⁷ *Ind. Ant.* Vol. XII. p. 169, text line 2.

⁸ Vol. V. above, p. 193, text lines 11, 12; and Vol. IV. p. 262, text lines 10, 11.

⁹ *Jour. Bo. Br. R. As. Soc.* Vol. XVIII. p. 258, B., plate ii. a, text line 1, and p. 262, A., plate i. text line 15.

¹⁰ Vol. IV. above, p. 340, text line 6.

¹¹ *Jour. Bo. Br. R. As. Soc.* Vol. XVI. p. 90, text line 2.

¹² *Ind. Ant.* Vol. XVIII. p. 234, text lines 1, 2.

¹³ *Jour. Bo. Br. R. As. Soc.* Vol. XVI. p. 107, text lines 2, 3.—I am of opinion, now, that the members of this family did not belong to what can be properly treated as a branch of the Mālkḥēḍ family, but were only *vamśyas* or "kinsmen" of the *Rāshtrakūṭas* of Mālkḥēḍ; that is to say, that they belonged to a separate line of the same *vamśa* or race, stock, or clan. See, also, Vol. VI. above, p. 170.

¹⁴ *South-Ind. Inscri.* Vol. I. p. 39, text lines 12, 24; and, regarding the second verse, see also Vol. IV. above, p. 226.

records, the Rāshtrakūṭa territory, which, however, had by that time passed into the hands of the Western Chālukyas of Kalyāṇi, is called, in Tamil prose, the *Ṛaṭṭapāḍi* and *Irattapāḍi* seven-and-a-half-lākh (country), in which appellation the name stands for *Raṭṭapāḍi*, "the country of the *Raṭṭas*,"¹ and *Irattamaṇḍala*, "the territory of the *Raṭṭas*."² The Bhādāna Śilāhāra grant of A.D. 997 speaks, in a Sanskrit verse, of the once flourishing *Raṭṭa-rājya* or "sovereignty of the *Raṭṭas*" as then existing only in memory, and further on, in Sanskrit prose, uses the same word in mentioning the downfall and destruction of the family, consequent on the overthrow of Kakka II.³ The Khārēpāṭaṇ Śilāhāra plates of A.D. 1008 speak, in a Sanskrit verse, of *Rāshtrakūṭ-śvarādām vaiśa*, "the race of the Rāshtrakūṭa lords," and further on, in Sanskrit prose, describe the Western Chālukya king Ṛivabedaṅga-Satyāśraya as ruling over *Raṭṭapāṭi* or "the country of the *Raṭṭas*."⁴ And the Kauthēm Western Chālukya plates of A.D. 1009, in Sanskrit verses, speak five times of the *Rāshtrakūṭas*, and *Rāshtrakūṭa-kula* or "the family of the *Rāshtrakūṭas*," and also present once the other form *Raṭṭa*, in referring to Bhammaha-Raṭṭa or "the *Raṭṭa* Bhammaha," whose daughter Jākavvā became the wife of Taila II.⁵

In the later extraneous records, there are many other references to the *Rāshtrakūṭas* of Mālkhēḍ, of which some speak of them as *Rāshtrakūṭas*, but the majority call them *Raṭṭas*. We need not pursue those references any further. But we must note the usage in respect of the family-name, in connection both with the *Rāshtrakūṭas* of Mālkhēḍ and with the *Raṭṭas* of Saundatti, in the records of the feudatory *Raṭṭa* princes of Saundatti, who ruled over the Kūṇḍi three-thousand province which lay in the territory that had belonged to the *Rāshtrakūṭa* kings of Mālkhēḍ, and who, in their later records, are represented as belonging to the same lineage with those kings.⁶ In these *Raṭṭa* records, as far as they have been explored, the name *Rāshtrakūṭa* is but rarely met with. An inscription at Bail-Hongal, probably referable to the period A.D. 1044 to 1068 but perhaps to be placed about a century later, presents the name of the family of apparently the *Raṭṭa* princes as *Rāshtrakūṭa*.⁷ An inscription at Saundatti, put together in A.D. 1096 or soon after, speaks, in Kanarese prose, in a passage which presents wrongly the date of A.D. 875-76, of a king Kṛishnarājadēva, by whom it means Kṛishṇa III., and describes him as *Rāshtrakūṭa-kula-tīlaka*, "an ornament of the family of the *Rāshtrakūṭas*."⁸ The Tērdāl inscription, which was put together in A.D. 1187, includes a passage dated in A.D. 1122 which applies to the prince Kārtavīrya II., in Kanarese prose, the epithet *Rāshtrakūṭ-ānvaya-śirāḥ-śikhāmani*, "a crest-jewel on the head that was the lineage of the *Rāshtrakūṭas*."⁹ And the Saundatti inscription of A.D. 1228 describes the prince Lakshmidēva II., in a Kanarese verse, as *Rāshtrakūṭ-ānvaya*, "belonging to the lineage of the *Rāshtrakūṭas*."¹⁰ But, with the above exceptions, the *Raṭṭa* records, including even the records of A.D. 1096, 1187, and 1228 mentioned above, always present the name as *Raṭṭa*, or, using a variant of the name written with the Drāviḍian *r*, as *Raṭṭa*. The earliest certain record of the *Raṭṭa* princes, the Sogal inscription

¹ See, for instance, *South-Ind. Insers.* Vol. III. p. 15, a record of A.D. 1008; and *ibid.* p. 112, a record of A.D. 1054-55.

² See *ibid.* p. 63, a record of A.D. 1053-54.

³ Vol. III. above, p. 272, text line 20, and p. 273, line 43.

⁴ Vol. III. above, p. 293, text line 6-7, and p. 299, line 21.—There can hardly be any doubt that the same word *Raṭṭapāṭi* is the real reading in the passage in the *Navasahasāṅkacharita*, XI. 89, 90, in which Dr. Bühler (see *Ep. Ind.* Vol. I. p. 225) found a mention of "*Raṭṭapāṭi*."

⁵ *Ind. Ant.* Vol. XVI. p. 21, text lines 10, 15, and p. 23, lines 39, 40-41, 43, 44.

⁶ See a note on references to Kṛishṇa III. in the records of the *Raṭṭas* of Saundatti, which I am giving in the *Indian Antiquary*, Vol. XXXII.

⁷ See *Ind. Ant.* Vol. IV. p. 115. The language of the record is Kanarese. But I did not note whether the particular passage is in prose or in verse.

⁸ See the article referred to in note 6 above.

⁹ *Ind. Ant.* Vol. XIV. p. 18, text line 47.

¹⁰ *Archaeol. Surv. West. Ind.* Vol. III. p. 110, text line 5.

dated in July, A.D. 980,¹ speaks of the prince Kārtavīrya I., in a Kanarese verse, as *Raṭṭa-kūḷa-bhūṣhaṇa*, "an ornament of the family of the Raṭṭas." The Saundatti inscription, dated in December of the same year, of the Baisa prince Śāntivarman, speaks in Kanarese verses, with reference it may be to the Rāshtrakūṭas of Mālkhēḍ, or it may be to some earlier members of the Raṭṭa family of Saundatti,² of *Raṭṭa-kūḷa-ānvaya-nrīpar*, "the kings of the lineage of the family of the Raṭṭas," and, with the Drāviḍian *r*, of *Raṭṭar*, "the Raṭṭas."³ The Maṇṭū inscription of A.D. 1040 presents a formal *praśasti* of the usual kind in Kanarese prose, introductory to the practical details of the record, in which it applies to the prince Eṇṇa-Eṇṇammarasa the epithet *Raṭṭa-vaṃś-ōḍbhava*, "born in the race of the Raṭṭas," and the *biruda* *Raṭṭamārtanḍa*, "a sun of the Raṭṭas;" and, in Kanarese verses, it gives him the *biruda* *Raṭṭanārāyaṇa*, "a Nārāyaṇa of the Raṭṭas," in addition to repeating the *biruda* *Raṭṭamārtanḍa*; and it further speaks, in Kanarese prose, of a tank called *Raṭṭasamudra*.⁴ The Kanarese inscription in the temple of Aṅkalēśvara or Aṅkuśēśvara, at Saundatti,⁵ in the passage of A.D. 1048 describes Nanna, the father of Kārtavīrya I., in verse as *Raṭṭa-kūḷa-āmbara-tigmarōḷhi*, "a sun of the sky which is the family of the Raṭṭas," and speaks of Ḍāyima in verse as *Raṭṭara Mēru Ḍāyima*, "Ḍāyima, a Mēru of the Raṭṭas;"⁶ and it uses the same form of the name twice more, in verse and prose, in connection with Aṅka in that passage, and once again in the passage of A.D. 1087, in which it describes Kārtavīrya II., in a formal prose *praśasti*, as *Raṭṭa-kūḷa-kamaḷa-mārtanḍa*, "a sun of the water-lily (*blooming in the daytime*) which is the family of the Raṭṭas." Another inscription at Saundatti, of the period A.D. 1069 to 1076, describes the prince Kārtavīrya II., in the formal *praśasti* in Kanarese prose, as *Raṭṭa-kūḷa-ranaja-vana-mārtanḍa*, "a sun of the group of water-lilies (*blooming in the daytime*) which is the family of the Raṭṭas," and, in giving his pedigree, uses the same verse that stands in the record of A.D. 1048, and styles his ancestor Ḍāyima, in a Kanarese verse, *Raṭṭara Mēru Ḍāyima*, "Ḍāyima, a Mēru of the Raṭṭas."⁷ The Saundatti inscription, put together in A.D. 1096 or thereabouts, which has been quoted above as presenting the name Rāshtrakūṭa in connection with Kṛishṇa III., describes the prince Kārtavīrya II., in the formal *praśasti* in Kanarese prose, as *Raṭṭa-kūḷa-bhūṣhaṇa*, "an ornament of the family of the Raṭṭas," and, in tracing his descent, describes his ancestor Kārtavīrya I., in a Sanskrit verse, as *Raṭṭa-vaṃś-ōḍbhava*, "born in the race of the Raṭṭas."⁸ The Tērdāl inscription, put together in A.D. 1187, which has been quoted above as presenting, in a passage dated in A.D. 1122, the name Rāshtrakūṭa in connection with the prince Kārtavīrya II., styles him, in the formal *praśasti* in Kanarese prose, *Raṭṭa-kūḷa-bhūṣhaṇa*, "an ornament of the family of the Raṭṭas."⁹ The Kalhole inscription of A.D. 1204 describes the prince Sēna II., in a Kanarese verse, as *Raṭṭa-ānvaya-Śrī-nētra*, "the eye of Fortune in the shape of the lineage of the Raṭṭas," and applies the *biruda* *Raṭṭanārāyaṇa*, "a Nārāyaṇa of the Raṭṭas," to Kārtavīrya IV., again in a Kanarese verse, and then, in the formal *praśasti* in Kanarese prose, styles him, as usual, *Raṭṭa-kūḷa-bhūṣhaṇa* "an ornament of the family of the Raṭṭas."¹⁰ The Bhōj plates of A.D. 1208 speak of the family of the princes, in a Sanskrit verse, as *Raṭṭa-ānvaya*

¹ Noticed in *Dyn. Kan. Distrs.* pp. 423, 553. I quote it from an ink-impression.

² On this point, see page 223 below, note 5.

³ *Jour. Bo. Br. R. As. Soc.* Vol. X. p. 104, text lines 1, 2.

⁴ *Ind. Ant.* Vol. XIX. p. 164, text lines 9, 10, 17, 24, and p. 165, line 27.

⁵ Not yet published, but mentioned in *Jour. Bo. Br. R. As. Soc.* Vol. X. p. 172 f., and *Dyn. Kan. Distrs.* pp. 553, 554. I quote it from an ink-impression.

⁶ With the epithet thus applied to Ḍāyima, compare the likening of Iudra II. to "a golden mountain (Mēru) of the good Rāshtrakūṭas," see page 215. It would also seem that Nāgavarman, somewhere in his *Kōṣṭhaśāstra*, uses the expression *Raṭṭara Mēru Dantiga*. "Dantiga, a Mēru of the Raṭṭas," with reference probably to the Rāshtrakūṭa king Dantidurga-Dantivarman II.; see *Jour. Bo. Br. R. As. Soc.* Vol. XX. p. 25.

⁷ *Jour. Bo. Br. R. As. Soc.* Vol. X. p. 213, text line 6, and p. 214, line 12.

⁸ *Ibid.* p. 196, text lines 24, 26.

⁹ *Ind. Ant.* Vol. XIV. p. 18, text line 43.

¹⁰ *Jour. Bo. Br. R. As. Soc.* Vol. X. p. 220, text line 5, and p. 221, lines 12, 16.

vaṁśa, "the race that has the appellation Raṭṭa," and in the formal *praśasti*, given in this case in Sanskrit prose, style Kārtavīrya IV., as usual, *Raṭṭa-kūḷa-bhūṣhaṇa*, "an ornament of the family of the Raṭṭas."¹ The Nēsargi inscription of A.D. 1218 uses, throughout, the variant of the name which presents the Drāviḍian *r*; in Kanarese verses, it speaks of the Māḷkhēḍ kings as *Raṭṭ-āṇvayar*, "those who were of the lineage of the Raṭṭas," and of their family as *Raṭṭa-vaṁśa*, "the race of the Raṭṭas," and *Raṭṭa-kūḷa*, "the family of the Raṭṭas," and of the family of the princes of Saundatti as *Raṭṭa-vaṁśa*, "the race of the Raṭṭas."² The Saundatti inscription of A.D. 1228, which has been quoted above as presenting the name Rāshtrakūṭa in connection with the prince Lakshmidēva II., further speaks of him, in a preceding Kanarese verse, as *Raṭṭa-vaṁś-ōḷbhava*, "born in the race of the Raṭṭas," and uses, also in Kanarese verses, and in connection with the prince s, the expressions *Raṭṭa-rājya*, "the rule of the Raṭṭas," and *Raṭṭa-rāja* and *Raṭṭ-ōṇvīpa*, "the Raṭṭa kings;" and in the formal *praśasti*, in Kanarese prose, it styles Lakshmidēva II., as usual, *Raṭṭa-kūḷa-bhūṣhaṇa*, "an ornament of the family of the Raṭṭas."³ And an inscription at Hannikere or Hannikēri, put together in A.D. 1257,⁴ uses, throughout, the variant of the name with the Drāviḍian *r*, and presents the name of the family of the kings of Māḷkhēḍ as *Raṭṭa-vaṁśa*, "the race of the Raṭṭas," in a Kanarese verse, and as *Raṭṭ-āṇvaya*, "the lineage of the Raṭṭas," in Kanarese prose, and describes the prince Kārtavīrya III., in Kanarese prose, as *Raṭṭa-kūḷa-bhūṣhaṇa*, "an ornament of the family of the Raṭṭas," and his son Lakshmidēva II., in a Kanarese verse, as *Raṭṭa-kūḷ-āgrani*, "a leader of the family of the Raṭṭas."

The form Raṭṭa, with the Drāviḍian *r*, has not as yet been found in any records of the Rāshtrakūṭa kings of Māḷkhēḍ. It is met with, first, in the Saundatti record of A.D. 980. But, from the other instances given above, it does not seem to have been used at all freely until about the beginning of the thirteenth century A.D. It was not always used even then. It became, however, so well established and well known a form of the name, that we find it used also in extraneous records, and in the Nāgarī characters, though a special device had to be adopted to represent it in that alphabet. That device was the doubling of the ordinary Nāgarī *r*, with the result of presenting the name as Rraṭṭa, without, however, producing a double consonant strong enough to lengthen a preceding short vowel.⁵ And we have the name in this form in a Sanskrit verse in the Haralahaḷḷi plates of A.D. 1238, which contain a Dēvagiri-Yādava record,⁶ and again

¹ *Ind. Ant.* Vol. XIX. p. 245, text line 6-7, and p. 247, line 87-88.

² *Jour. Bo. Br. R. As. Soc.* Vol. X. p. 240, text lines 4, 10, and p. 241, lines 11-12, 14.

³ *Archæol. Surv. West. Ind.* Vol. III. p. 110, text lines 5, 6, 7, 10, and p. 112, line 52, and p. 113, line 62.

⁴ See the article referred to in note 6 on p. 217 above.

⁵ To the same expedient, the doubling of the ordinary *r*, recourse was had even in Reeve and Sanderson's Kanarese Dictionary (1858), in the comparatively few instances in which an attempt was made to indicate the Drāviḍian *r* in that work.

⁶ *Jour. Bo. Br. R. As. Soc.* Vol. XV. p. 387, text line 27.—The doubling of the *r* was effected here by placing a superscript *r* over the ordinary *r*. The same means was also used in the Kanarese part of this record, written in Nāgarī characters, in *Kuṁbārragerrey=olage*, for *Kuṁbāragerey=olage*, line 93, and in *Kuṁbārragoḷana keḷage* for *Kuṁbāragoḷana keḷage*, line 97. And the same means was used in the word Rraṭṭa, quoted above from the Bēhaṭṭi plates of A.D. 1253, and again in *mārra-kāṇḍu*, for *māra-kōṇḍu*, in the Kanarese passage, given in Nāgarī characters, at the end of the Bēhaṭṭi Kalachurya plates of A.D. 1183 (*Ind. Ant.* Vol. IV. p. 276, text line 87). The same means was used in also *Kirru-Valasig-ākhyam*, for *Kiru-Valasig-ākhyam*, in the Halst Kādamba plates of A.D. 1199 (*Jour. Bo. Br. R. As. Soc.* Vol. IX. p. 244, line 13).—Another means of representing the Drāviḍian *r* in Nāgarī characters, was, to double the Nāgarī *r* by making from the bottom of it an upstroke to the right similar to the upstroke to the left in the ordinary *r*. This device was used in the spurious plates in the Bangalore Museum which purport to have been issued in A.D. 445 (No. 49 in my list of Spurious Indian Records in *Ind. Ant.* Vol. XXX. p. 221); here we have *Hemjarra* for *Hemjēra* (*Ind. Ant.* Vol. VIII. p. 94, text line 12), and *Hemjerra* . . . *irridu* for *Hemjēra* . . . *iridu* (*ibid.* p. 95, text line 17).—We have the double *rr* in Nāgarī, for the Drāviḍian *r*, again in *arrravaṇa*, = *aruvana*, in the Bhōj Raṭṭa plates of A.D. 1203 (*Ind. Ant.* Vol. XIX. p. 217, text line 103). But I have not kept a note as to how the *rr* is formed there.

in the same verse in the Bêhatti plates of A.D. 1253, which contain another Dêvagiri-Yâdava record.¹

That the family-name of the princes of Saundatti, who ruled the Kûndi three-thousand province, was Raṭṭa, not Râshṭrakûṭa, is unmistakable. And it is also quite plain that, while Râshṭrakûṭa was the formal appellation which it was customary to apply to the kings of Mâlkḥêḍ in ornate language, the real practical form of their family-name was Raṭṭa. This is made clear, in one way, by the fact that Raṭṭa is the name that was used in forming those *birudas*, or secondary appellations of the kings, of which the family-name was a component, and of which we have at present instances dating from A.D. 915 and onwards; namely, Raṭṭakandarpa in the cases of Indra III., Gôvinda IV., Khotṭiga, and Indra IV., and Raṭṭavidyâdhara in the case of Gôvinda IV. But it is made clear in other ways also. In the records of the Mâlkḥêḍ family, except in the case of the Kaḍaba plates which are not of unquestionable authenticity, the appellation Râshṭrakûṭa is found only in Sanskrit verses, in those parts of the records which were introductory to the passages containing the practical details of the records, and were devoted to exhibiting the pedigree, reciting the achievements, and generally magnifying the importance of the kings, in the principal literary language of the time. And even in the record put forward in the Kaḍaba plates, where the appellation occurs in prose, the passage is in ornate prose of an elaborate and stilted kind, or, as Dr. Lüders has styled it, in "exceedingly rich and flowery language."² The name Raṭṭa appears first in the Sirûr and Nîlgund inscriptions of A.D. 866. And in them it is presented, not in a Sanskrit verse, but in the Kanarese prose *prasasti* which introduces the practical details of the records. At about that time, there arose a practice of presenting compositions, which did not even include excerpts from the early standard drafts such as we have in the case of verses 1 and 2 in the Sirûr record and verses 2 and 3 in the Nîlgund record, but which departed altogether from the early standard drafts, and were also liable to be independent even of each other. The composers of those later records indulged in various liberties, which had not been allowed to the composers of the earlier records. And, in the drafts presented in the Cambay plates of A.D. 930 and the Sângli plates of A.D. 933 and the Kharḍa plates of A.D. 972, the real name of the family, in either form, was actually suppressed altogether, and the members of the dynasty were simply allotted, in connection with their then recently elaborated Purâṇic pedigree, to "the race of the Yadus" or "the lineage of Yadu."³ It was only in those later compositions that the habit crept in, of using the name Raṭṭa in Sanskrit verses. And, even then, a kind of apology was made for using the more practical form of the name in the more ornate parts of the records. That the *biruda* Raṭṭakandarpa, in the case of Indra III., should be used in a Sanskrit verse, in the Bagumrâ records of A.D. 915, in that practical form and without being metamorphosed into Râshṭrakûṭakandarpa, is natural enough. But it is found rather far on in the record. And the composer of the draft presented in those two sets of plates was careful to introduce the dynasty by its more stately appellation of "the family of the Râshṭrakûṭas," before he proceeded to speak of "the kingdom or sovereignty of the Raṭṭas" and to bring the *biruda* Raṭṭakandarpa into one of his verses. So, also, the draft presented in the Dêoli plates of A.D. 940 and the Karhâḍ plates of A.D. 959 introduces the dynasty as "the race of the Râshṭrakûṭas," before it, again, speaks of "the kingdom or sovereignty of the Raṭṭas." And these two drafts, presented to us first in records of A.D. 915 and 940, emphasise the point that Raṭṭa was the real and practical form, and Râshṭrakûṭa was the ornamental or stately form, of the family-name. Such are the facts. But the Raṭṭas of Mâlkḥêḍ have come to be familiarly known as the Râshṭrakûṭas of Mâlkḥêḍ, because that form only of their name is presented at all prominently in

¹ *Jour. Bo. Br. E. As. Soc.* Vol. XII. p. 43, text line 17. As stated in the preceding note, the doubling of the *r* was effected here, also, by placing a superscript *r* over the ordinary *r*.

² Vol. IV. above, p. 333.

³ See note 11 on page 215 above.

their various records which were published before the time when the Sirūr inscription came to notice. And, for purposes of easy discrimination, it will be desirable to continue the use of that appellation, and to speak still, as hitherto, of the Rāshtrakūṭa kings of Mālkhed and the Raṭṭa princes of Saundatti.

We have now to consider which of the two names, Raṭṭa and Rāshtrakūṭa, was evolved from the other name, and how it was done.

And, in the first place, it is to be remarked that we have been told by Mr. Pathak that "the word *raṭṭa*, according to Trivikrama, is a Prākṛit form of the Sanskrit *rāshṭra*."¹ I have, however, been assured, by the very best authority, that Trivikrama does not give in his grammar any rule at all about the word *rāshṭra*, and that the word *raṭṭa* has not been found in Prākṛit literature. And, as far as our actual knowledge goes, the forms which the Sanskrit word *rāshṭra*, 'a country,' would assume in the Prākṛits, are *raṭṭha*, *raṭha* and *raṭa*. We have the form *raṭṭha* in Surāṭṭha, = Surāshṭra, and Sōraṭṭha, = Saurāshṭra, which instances Professor Pischel has given me from, respectively, *Hemachandra*, 2, 34, and *Trivikrama*, 1, 4, 14; and the use of it evidently underlies the Jaina-Mahārāshṭri, Śaurasēni, and Apabhraṃsa word Marahāṭṭha, for Mahārāṭṭha, = Mahārāshṭra, and the Mahārāshṭri word Marahāṭṭhi, for Mahārāṭṭhi, = Mahārāshṭri.² In Pāli, we have the independent word *raṭṭha* itself, = *rāshṭra*, in the sense of 'kingdom, realm, country, land, district.'³ And, in epigraphy, we have *Sātāhani-raṭṭhē*, "in the province of Sātāhani."⁴ We have the form *raṭha*, in epigraphy, in Surāṭha, = Surāshṭra, in one of the Nāsik inscriptions of Puṣumāyi.⁵ And we have the form *raṭa*, attributable no doubt to the tendency to avoid aspirates in the Drāviḍian languages, in Sorāṭa, = Saurāshṭra, which is given as an instance of the changes of *au* to *o* and of *shṭ* to *t* in the illustrations of Kēśirāja's Kanarese *Śabdamanidarpana*, sūtras 270, 283.⁶ So far, no authority can be obtained for saying that the form *raṭṭa*, = *rāshṭra*, 'country,' actually occurs. However, according to the *Śabdamanidarpana*, sūtra 283, the Sanskrit *shṭ* may become *ṭṭ*, as well as *t*, in Kanarese; and there are cases, such as *duṭṭa*, = *dushṭa*, *siṭṭi*, = *śiṣṭi*, and *iṭṭige*, = *iṣṭaka*, in which that change has occurred. And so, also, in the Prākṛit languages technically so called, while the Sanskrit *shṭ* usually becomes *ṭṭh*,⁷ there are some cases in which it has become *ṭṭ*; as, for instance, in *uṭṭa*, = *ushṭra*, and a few other words.⁸ And we are, therefore, not prepared to say that the form *raṭṭa*, = *rāshṭra*, may not be found to occur, though it was not taught by Trivikrama, and though we cannot at present quote any instance of it.

But the name Raṭṭa was certainly not obtained from the word *rāshṭra*, or from the name Rāshtrakūṭa. The family-name, in its Sanskrit form, was, not Rāshṭra, but Rāshtrakūṭa. There was no name Rāshṭra, from which to obtain the name Raṭṭa. From the name Rāshtrakūṭa we obtain, by corruption, in the most natural manner, Rāshṭrōḍa, actually presented in a Verāwal inscription of A.D. 1384, which speaks of *Rāshṭrōḍa-vamśa*, "the race of the Rāshṭrōḍas," and describes it as a third race famous like the Solar and Lunar Races;⁹ and we shall not be

¹ *Ind. Ant.* Vol. XIV. p. 14 a.

² See Prof. Pischel's Prākṛit Grammar, § 354.

³ Childers' Pāli Dictionary, p. 403. The word figures in also *raṭṭhaviśinō*, 'inhabitants,' *raṭṭhādhipō*, 'a king,' and *raṭṭhikō*, *raṭṭhiyō*, 'an inhabitant.'

⁴ *Ep. Ind.* Vol. I. p. 6, text line 27. And, evidently, the same word figures in the fiscal term *a-raṭṭha-samvi-nayikam* in line 32 of the record, and is the basis of the official title *raṭṭhika* in line 4. As variants of this fiscal term, connected with the other form *raṭha*, we have *a-raṭha-savinayika* in *Archæol. Surv. West. Ind.* Vol. IV. p. 104, No. 13, line 4, and p. 106, No. 14, line 10, and *a-raṭha-samviindyika* in Vol. VI. above, p. 87, line 14.

⁵ *Archæol. Surv. West. Ind.* Vol. IV. p. 108, text line 2. For other instances of this form, in a certain fiscal expression, see the preceding note.

⁶ Dr. Kittel's edition, pp. 356, 370. So, also, Sorāṭa is given as the corruption of Saurāshṭra in the illustrations of sūtra 160 of Bhaṭṭakalaṅkādeva's *Karmātakalabdhanūśāna*, Bangalore, 1890.

⁷ See Prof. Pischel's Prākṛit Grammar, § 303.

⁸ See *id.* § 304.

⁹ *Antiquarian Remains in the Bombay Presidency*, 1897, p. 253.

surprised, if we meet hereafter with epigraphic instances of further corruptions such as Raṭṭhōḍa and Rāṭhōḍa, of which forms the last is actually the modern name which in gazetteers, etc., is presented as 'Rāthor' and 'Rāhtor'.¹ But, in the name Rāshṭrōḍa, the second component, *kūṭa*, of Rāshtrakūṭa, is duly represented.² Whereas, in the name Raṭṭa there is nothing whatever to represent that second component of the other name. And, for that reason we cannot admit Raṭṭa as a corruption of, or in any way obtained from, the name Rāshtrakūṭa.

It can only be the case that the name Rāshtrakūṭa was evolved out of the name Raṭṭa. And, that that was the case, is unconsciously disclosed by the draft presented in the Dēōlī plates of A.D. 940 and the Karhād plates of A.D. 959, in the verse which puts forward the eponymous person Raṭṭa as the imaginary original ancestor of the Mālkḥēḍ family, and asserts that he had a son named Rāshtrakūṭa, and says that it was from the name of that son that the family became known as the Rāshtrakūṭa race, or the race of Rāshtrakūṭa or of the Rāshtrakūṭas.³ But the name Rāshtrakūṭa is certainly not merely a Sanskritised form of nothing but the name Raṭṭa; for the simple reason that in Raṭṭa there is nothing to account for the component *kūṭa* in the other form of the name. The name Raṭṭa does account for the first component, *rāshṭra*. It does not, however, account for it in the way of having been literally translated by the word *rāshṭra*. The explanation is that, in devising an ornamental form of a name, Raṭṭa, which, whatever may have been the origin of it, did not mean a 'country,' there was used, not unnaturally, a Sanskrit word, *rāshṭra*, which was the actual representative and origin of words of very similar sound, such as *raṭṭha*, *raṭṭa*, and *raṭa*,—possibly even *raṭṭa* itself, if the existence of that form should be established hereafter,—which did possess that meaning. There was thus obtained, as the first step, a name Rāshṭra. But it seems to have been then recognised that the appellation thus obtained was not sufficiently high-sounding, and that something more was needed to adapt it better to the purposes for which it was wanted. Now, the word *kūṭa* has the meaning, among others, of 'the highest, most excellent, first,' derived no doubt from its meanings of 'any prominence, a peak or summit of a mountain.' In literature, it occurs in that meaning in the *Bhāgavatapurāṇa*, 2, 9, 19, where Bhagavat (Vishnu-Krishna) is represented as addressing Brahman as *kūṭa yōginām*, "O chief of ascetics!" In the epigraphic records, it is used in the same meaning in the official title *grāmakūṭa*, 'a chief or headman of a village,'⁴ and also actually in the word *rāshtrakūṭa* as an official title meaning 'the headman of a territorial division technically known as a *rāshṭra*.'⁵ The word *kūṭa*, in that same meaning, was plainly employed in making up the full family-name Rāshtrakūṭa. And the use of it, to fill out and give sufficient pomp to that form of the name, was very probably suggested by the actual existence of the word *rāshtrakūṭa* as an official title. But we need not think, any longer, that the name

¹ Dr. Bühler has told us that "the bards of Rājputānā," inverting the process, "have invented Rāshṭraṇḍa as an etymon for Rāṭhōḍ," in order to explain a difficult Prākṛit word; see *Ind. Ant.* Vol. XVII. p. 192, note 34.

² Namely, by the *uḍa* in *Rāshṭra-uḍa*, from which we have eventually *Rāshṭrōḍa*. Compare *grāmakūṭa*, *gāma-uḍa*, and eventually *gaṇḍa*, etc.; see page 183 above.

³ Vol. V. above, p. 193, text lines 11, 12; and Vol. IV. p. 287, verse 7, and p. 282, text lines 10, 11.

⁴ For instance, in the Sāmāṅgaḍ plates of A.D. 754; see *Ind. Ant.* Vol. XI. p. 112, text line 29. Another form of this title was *grāmakūṭaka*, which we have, for instance, in the Kauṭhēm plates of A.D. 1009; see *id.* Vol. XVI. p. 24, text line 60.—Regarding the fact that the word *grāmakūṭa* was the origin of the Kanarese title *Gauḍa*, answering to the Marāṭhī *Pāṭil*, *Pāṭel*, see page 183 above.

⁵ For instance, in an Eastern Chalukya record of the period A.D. 799 to 843; see *Ind. Ant.* Vol. XX. p. 416, text line 17. Another Eastern Chalukya record, belonging or purporting to belong to the same period, presents the simple word *kūṭaka*, which we may take as standing either for *rāshtrakūṭaka* or for *grāmakūṭaka*, as we like; see Vol. V. above, p. 120, text line 15. The records of Western India usually present, instead of *rāshtrakūṭa*, either *rāshṭramahattara*, as in the Sarsavṇī plates of the Kaṭachchuri king Buddharāja of A.D. 610 (see Vol. VI. above, p. 298, text line 18), or *rāshṭrapati*, as in the Sāmāṅgaḍ plates of the Rāshtrakūṭa king Dantidurga of A.D. 754 (see *Ind. Ant.* Vol. XI. p. 112, text line 28), and in the Kauṭhēm plates of the Western Chalukya king Vikramāditya V. of A.D. 1009 (see *id.* Vol. XVI. p. 24, text line 60).

is itself the official title, or that, like the official title, it means 'a headman of a *rāshṭra*.'¹ It was plainly intended to mean 'highest, most excellent, chiefs, or leaders, of the Raṭṭas.'

It may be added that both the original family-name Raṭṭa, and its ornate form Rāshṭrakūṭa, came to be afterwards used as personal names. Thus, the Khārēpāṭa plates of A.D. 1008 mention a Śilāhāra prince named Raṭṭa and Raṭṭarāja;² and Hānachandra mentions in his *Parīśiṣṭapāraṇa* a man named Rāshṭrakūṭa.³ It may also be remarked that Kāhāṇa has asserted the existence of a queen of the Dekkan, of Karpāṭa extraction, named Raṭṭā, alleged to have been a contemporary of Lalitāditya of the Kārkōṭa dynasty of Kashmir; but there can be no doubt that Dr. Stein has rightly explained the passage, not as establishing the real existence of any such queen, but as presenting a personification of the dynasty of the Rāshṭrakūṭas of Mālkhed.⁴

* * * * *

The original home of the Rāshṭrakūṭas of Mālkhed.

In line 13 of the Sirūr inscription of A.D. 866, and in line 16 of the Nīlgund inscription of the same date, Amōghavarsha I. is described as *Lattalūra-pura-paramēśvara*, "supreme lord of the town of Lattalūra." The same town is mentioned, sometimes as Lattalūr and sometimes as Lattanūr, in also the records of the Raṭṭa princes of Saundatti; for instance, the Maṇṭūr inscription of A.D. 1040 describes Eṛaga-Eṛeyammarasa as *Lattalūr-puravar-ēśvara*, "lord of Lattalūr, a best of towns, an excellent town, a chief town," and the Bhōj plates of A.D. 1208 describe Kārtavīrya IV., and the Saundatti inscription of A.D. 1228 describes Lakshmidēva II., as *Lattanūr-puravar-ādihāśvara*, "supreme lord of Lattanūr, a best of towns."⁵ And in these epithets we have, in various forms, a hereditary title commemorative of the place which the Rāshṭrakūṭa kings of Mālkhed,—and, after them, the Raṭṭa princes of Saundatti, who, according to some of their later records, belonged to the same lineage with those kings,—claimed as their original home. The name of the town is further presented to us in a transitional form in the Sītābaldī inscription of A.D. 1087, which applies the epithet *Latalaura-vinirgata*, "come forth or emigrated from Latalaura," to a feudatory of the Western Chālukya king Vikramāditya VI., namely to the *Mahāśānta* Dhāḍibhaṇḍaka or Dhāḍibhaṇḍaka, also called the *Rānaka* Dhāḍiadēva, whom it further describes as *mahā-Rāshṭrakūṭa-āṇḍaya-prasūta*, "born in the great lineage of the Rāshṭrakūṭas, or in the lineage of the great Rāshṭrakūṭas;" and the record applies

¹ There would, however, not have been anything derogatory even in that derivation of the name. The name of the well known Andhrabhṛitya kings is explained, as having taken its origin from the fact that the first of them had been a servant (*bhṛitya*) of the Andhras. And there was a family of kings who referred themselves to a lineage known as the Gurjarapratihāra lineage (see Vol. III. above, p. 263), evidently because their ancestors had been doorkeepers of the Gurjaras.

² Vol. III. above, p. 300, text lines 32, 34.

³ See Monier-Williams' Sanskrit Dictionary, under *rāshṭra*.

⁴ See his translation of the *Rājatarāṅgī*, Vol. I. p. 185, note on verse 152 of the fourth book.

⁵ See, respectively, *Ind. Ant.* Vol. XIX. p. 165, and p. 248, and *Archaeol. Surv. West. Ind.* Vol. III. p. 113, text line 62, and Plate 73 in Vol. II. p. 224.—By a printer's mistake, not noticed at the time, the published text of the Bhōj record gives the name of the town, in line 86-87, as Lāttanūr, with the long *ā*, instead of the short *a*, in the first syllable. The necessary correction should be made.—At present, I cannot trace back the use of this title to any date before A.D. 1040 in records which belong unquestionably to the Raṭṭas of Saundatti. The Kalasāpur inscription of A.D. 933, of the time of the Rāshṭrakūṭa king Gōvinda IV., does, indeed, mention a *Mahāśānta* whom it describes as *Lattalūr-pura-paramēśvara* and as *trivālī-pareghōshana*; and it is practically certain that he was a Raṭṭa: but the original record is greatly damaged, and I cannot recognise, in the ink-impression, either his name, or any epithet which specifically refers him to the lineage of the Raṭṭas. The Sogal inscription of the Raṭṭa prince Kārtavīrya I., of July, A.D. 980, does not seem to make any mention of Lattalūr. And it may be added that the town is certainly not mentioned in the Saundatti inscription, of December of that same year, of the *Mahāśānta* Śāntivarman (*Jour. Bo. Br. R. As. Soc.* Vol. X. p. 204); but, for various reasons, it is very questionable whether that is really a Raṭṭa record at all.

the same epithet, "come forth or emigrated from Latalaura," to Dhādibhadaka's officer, the *Danḍanāyaka* Vāsudēva.¹

The town Lattalūr or Lattanūr may, or may not, have been in the territory of the Rāshtrakūṭas of Mālkhed. By a similar title, the Western Gaṅga princes of Talakād were styled *Kovaḷāla-puravar-ēśvara*, "lord of Kovaḷāla, the best of towns."² Here, the allusion is to the town now known as Kōlār, the chief town of the Kōlār district in the east of Mysore. And that town certainly was in the Western Gaṅga territory. So, also, the Kādamba princes of Hāṅgal had the hereditary title of *Banavāsi-puravar-ādhiśvara*, "supreme lord of Banavāsi, the best of towns."³ And they sometimes had the administration of the Banavāsi province. But their hereditary authority was confined to the Pānuṅgal five-hundred province: the Banavāsi province proper was a crown property, administered from time to time by whomsoever the paramount sovereign might appoint; it was only by special appointment that it, with also some neighbouring districts, was occasionally held by the Kādambas of Hāṅgal; and they used the title simply because they claimed descent from the early Kadamba kings, whose capital was Banavāsi. These are the only two instances, that I can recall, in which a hereditary title of the kind that we are considering was more or less connected with actual territorial authority. The same title, "supreme lord of Banavāsi, the best of towns," was used by the Kādamba princes of Goa,⁴ who had no authority whatever at Banavāsi, and simply derived the title in the same way as did the Kādambas of Hāṅgal. The Kaḷachurya kings of Kalyāṇi in the Nizam's Dominions had the hereditary title of *Kālāñjara*-(for *Kālañjara*)-*puravar-ādhiśvara*, "supreme lord of Kālāñjara, the best of towns,"⁵ simply in connection with the legend that referred the origin of their family to Kālāñjar in Bundēlkhand, Central India, a long way outside their own territory. The Gutta princes of Guttal, whose power was usually limited to quite a small part of the Dhārwar district, used the title *Ujjayanī-puravar-ādhiśvara*, "supreme lord of Ujjayanī, the best of towns,"—for which in one passage there is substituted "supreme lord of Pāṭālī, the best of towns,"⁶—simply because their traditions or legends connected them with the Early Guptas and the mythical king Vikramāditya, and consequently with the far distant Ujjain in Mālwa and Pāṭaliputra-Pāṭṇa in Behar. By similar titles, the Śilāhāra princes of the Northern Konkan styled themselves *Tagara-pura-paramēśvara*, "supreme lord of the town of Tagara,"⁷ and their relatives who ruled at Karḷād styled themselves *Tagara-puravar-ādhiśvara*, "supreme lord of Tagara, the best of towns,"⁸ though Tagara, which is the modern Tār in the Naldurg district of the Nizam's Dominions,⁹ was at a very appreciable distance, a hundred miles at least, from any part of the provinces to which their authority was confined. And the Yādava princes of the Sēṇa country, which was the territory of which the chief town was Dēvagiri-Daulatābād, used the title *Dvāravati-pura-paramēśvara*, "supreme lord of the town of Dvāravati,"¹⁰ which, in the form *Dvārāvati-puravar-ādhiśvara*, "supreme lord of Dvārāvati, the best of towns," was taken over

¹ Vol. III. above, p. 305, and text lines 4-5 and 7. It seems clear that, in line 5 of the text, *maḥa* was prefixed to *Rāshtrakūṭa-ānvaya-prasūta* in order to indicate that Dhādibhadaka claimed descent from the great Rāshtrakūṭa kings of Mālkhed, and not from one of the minor branches of the Rāshtrakūṭa or Raṭṭa stock which existed in other parts of India.

² See, for instance, Vol. VI. above, p. 44, and text line 2.

³ See, for instance, *Ind. Ant.* Vol. X. p. 254 a, and text line 24-25.

⁴ See, for instance, *Jour. Bo. Br. R. As. Soc.* Vol. IX. p. 300, and p. 296, text line 6.

⁵ See Vol. V. above, p. 24, and text line 5, and p. 257, and text line 55.

⁶ See *Dyn. Kan. Distrs.* p. 578 ff.

⁷ See, for instance, Vol. III. above, p. 269, and p. 273, text line 43-44.

⁸ See, for instance, *Cave-Temple Inscriptions* (No. 10 of the brochures of the Archæological Survey of Western India), p. 109, text line 26-27.

⁹ See *Jour. R. As. Soc.*, 1901, p. 537 ff., and 1902, p. 230 ff.

¹⁰ It appears first in the case of Bhīllama II., in the Saṅgamnēr plates of A.D. 1000; see *Ep. Ind.* Vol. II. p. 215 and text line 48.

from them by their descendants, the Yādava kings of Dēvagiri-Daulatābād.¹ But, whereas the allusion here is to Dvāravatī, Dvārāvati, or Dvārakā, which is the modern Dwārakā at the western extremity of Kāthiāwār, the Yādava princes of the Sēuna country certainly never ruled at Dwārakā or over any part of Kāthiāwār. The title was only set up by them in connection with their claim to belong to the Lunar Race, and to be descended from the god Viṣṇu, who, in his incarnation as Kṛishṇa, made Dwārakā his capital. And, that they simply claimed Dwārakā as their traditional place of origin, is explicitly shewn by a passage in the Bassein plates of A.D. 1069 which says in respect of Dṛiḍhaprahāra, whom it puts forward as the original founder of the family, that "he, in the beginning, came from the city (*pattana*) of Dvārāvati" to the territory, in the Nāsik district and the Nizam's Dominions, which his descendants were ruling at the time when the record was drawn up, "and made famous in the world the town of Chandrādityapura, which had already sprung into existence."² From all these facts, we can see plainly that these hereditary titles, presenting the names of ancient towns, put forward only assertions as to places of origin, and not claims to actual local authority; and that, to take a specific instance, the title *Lattalūra-pura-paramēśvara*, "supreme lord of the town of Lattalūra," which we have in the Sīrūr and Nīlgund records, is nothing but a more dignified and ostentatious method of conveying the exact idea which is expressed by the *Latalaura-vinirgata*, "come forth or emigrated from Latalaura," of the Sītābaldī inscription.³

An identification of the town Lattalūr, Lattanūr, or Latalaura, has not yet been established.⁴ I have, indeed, suggested that it might not impossibly be found in the town known as Ratanpur, in the Bilāspur district, Central Provinces;⁵ because the letters *l* and *r* are often interchanged, and so it would not be difficult to derive the name Ratanpur from the full form Lattanūrpura. That suggestion, however, was based chiefly on the fact that we find traces of rulers calling themselves Rāshtrakūṭas in various parts of India far to the north of the territory of the Rāshtrakūṭas of Mālkḥēd. And it is not, really, in any way sustainable; because the name Ratanpur has been simply obtained by transposition from Ratnapura, as is shewn by a record of A.D. 1114 at Ratanpur itself.⁶ I cannot at present quote any epigraphic references to Lattalūr, except from the records of the Rāshtrakūṭas of Mālkḥēd and the Raṭṭas of Saundatti, and from the Sītābaldī inscription. Nor can I find it mentioned by any ancient geographer or traveller, or in any *Purāṇa* or other work. But we are certainly concerned with a southern locality. And, while not asserting a final identification of Lattalūr, I would indicate a place in respect of which it seems worth while that some precise inquiries should be made. That place is a town in the Bidar district of the Nizam's Dominions, which is shewn as 'Latur' in the Indian Atlas sheet No. 56 (1845), in lat. 18° 24', long. 76° 38', and in Thacker's Reduced Survey Map of India by Bartholomew (1891). In Philip's Gazetteer of India by Ravenstein (1900), it is treated as 'Lathur, or Latur,' and is credited with a population of 9,063. It seems to have been, not long ago, of more importance than at present; for, Murray's *Encyclopædia of Geography* (1844)

¹ It is applied to the first king, Bhīllama, in an inscription of his time, dated in A.D. 1189, at Muttagi in the Bijāpur district. I quote from an ink-impression.

² *Ind. Ant.* Vol. XII. p. 121, and text lines 3 to 5. Regarding Chandrādityapura, see *id.* Vol. XXX. p. 518.

³ On the technical use of *vinirgata* in such expressions as this, see *Ind. Ant.* Vol. XXXI. p. 331 ff.

⁴ Major Graham's suggestion, put forward in 1854 (*Statistical Report on the Principality of Kolhapoor*, p. 418), that it is Athnī, the head-quarters of the Athnī tāluka in the Belgaum district, was only based on the mistaken reading of 'Atunpoor,' and is, of course, altogether unsustainable.—Pandit Bhagwanlal Indraji seems to have entertained the idea (see the *Gazetteer of the Bombay Presidency*, Vol. I. Part I. p. 7) that the name of the Lāṭa country, in Gujarāt, was derived from the name of some local tribe, "perhaps the Lattas" (read, obviously, Raṭṭas), who might possibly, through the interchange of *l* and *r*, be identified with the Raṭṭas or Rāshtrakūṭas, and that Lattalūra (*sic*) may have been in Lāṭa and may have given its name to both the country and the dynasty. It is difficult, however, to look on this as anything except an early crude speculation, which the Pandit himself would not have incorporated in any final presentation of his more mature views.

⁵ *Dyn. Kan. Distrs.* p. 384.

⁶ *Ep. Ind.* Vol. I. p. 33, and text lines 12 (twice) and 17.

shows 'Lattoor' as the name of a territorial subdivision ranking on equal terms with Bidar, Kalburga, Shôlâpur, Vairâg, and Pañdharpur.¹ Along with Pratishtâna-Paithan and Tagara-Têr, 'Latur' is in that part of the Dekkan, watered by the Gôdâvarî and its tributaries, which has been indicated by Dr. Bhandarkar as a favourite region of early Âryan settlement;² and it is, in fact, only about twenty-eight miles east-by-north from Têr, and three miles south of the 'Manjera,' which is an important feeder of the Gôdâvarî. And I strongly suspect that local inquiries would result in finding that 'Latur' is the ancient Lattalûr, Lattanûr. If so, there will, perhaps, be found at 'Latur' some notable temple or remains of such a temple, either of the goddess Durgâ in the form of Châmunḍâ, or of Vishṇu in the form of the man-lion, or possibly temples of both those deities; since the Sîtâbaldî inscription further describes Dhâḍi-bhâḍaka as "he who obtained favour by a boon of (the goddess) Châmunḍâ," and Vâsudeva as "he who obtained favour by a boon of (the god) Nârasimha."³

The matter must, of course, depend a good deal upon what is the actual spelling of the modern name which the maps and gazetteers present as 'Latur, Lathur, and Lattoor.' We need not trouble ourselves about the *h* which appears in one of these forms; it is as easily accounted for here, as in some other instances referred to by me elsewhere.⁴ For the rest, I feel no doubt that inquiries on the spot would shew that the real name is Lâtûr, with a long *â* followed by a single dental *t*. And, if that is so, the modern name is distinctly derivable from the ancient name, through steps the rules for some of which have been given to me by Professor Pischel. We start with the form Lattalûra, of A.D. 866, of which Lattanûr, appearing first at present in A.D. 1208, is plainly only an optional variant attributable to the interchangeability of *l* and *n*.⁵ The first step would be the dropping of one *t* in the second syllable, which would give us Latalûra, and eventually the Lataisura which we actually have in the Sîtâbaldî inscription. The next step would be the omission of the short *a* of the second and final syllables,⁶ which would give us Latlûr. The next step would be the assimilation of the *l* to the preceding *t*,⁷ which would give us Lattûr. And, finally, the nexus *tt* would be dissolved into the simple *t*, and the preceding short *a* would be lengthened by way of compensation;⁸ and this would give us the ultimate form Lâtûr.

* * * * *

¹ See the skeleton map on p. 951, and the key to it on p. 953, sub-divisions Nos. 66 to 71.

² See the *Gazetteer of the Bombay Presidency*, Vol. XIII, Thana, Part II., p. 423, note 4, and *Early History of the Dekkan* (id. Vol. I. Part II.), p. 135 ff.

³ Compare another epithet of the Kâdambas of Hângal, namely *Jayanti-Madhukêśvaradêva-labḍha-va-prasâda*, "he who obtained the excellent favour of the god Madhukêśvara of Jayanti (Banawâsi)" (*Ind. Ant.* Vol. X. p. 252, text line 25); also, another epithet of the Guttas of Guttal, namely *Ujjenti-Mahâkêḍadêvalabḍha-va-prasâda*, "he who obtained the excellent favour of the god Mahâkêḍa of Ujjayani" (*P. S. O.-C. Insers.* No. 109, line 10). But the records do not always present a title of this kind, in connection with the title commemorating the place of origin. And in some cases the epithet indicating a family-god, refers to a god who was not the god of the alleged place of origin; for instance, though, like the Kâdambas of Hângal, the Kâdambas of Goa were styled "supreme lord of Banavâsi, the best of towns," their other title was *śrî-Saptakôṭîśvaradêvalabḍha-va-prasâda*, "he who obtained the excellent favour of the holy god Saptakôṭîśvara" (*Jour. Bo. Br. B. As. Soc.* Vol. IX. p. 804, text line 11-12, and compare *Ind. Ant.* Vol. XIV. p. 290, text line 27), and Saptakôṭîśvara appears to have been a god at 'Narven' in Goa (see *Dyn. Kan. Distre.* p. 566, note 7).

⁴ See *Jour. B. As. Soc.*, 1901, p. 543 ff.

⁵ See Prof. Pischel's *Prâkrit Grammar*, § 260. As instances of the interchange of *l* and *n*, we may quote the place-names *Lañjigêśara-Nandikêśwar* (see *Ind. Ant.* Vol. XIX. p. 317 *a*) and *Balisa-Wanasa* (see id. Vol. XVIII. p. 266, and Vol. XXXI. p. 397), and the proper name *Lingapa-Ningapa*, well known in the Kanarese country, and the ordinary words *nâḥan* for *lahân* in Gujarâti (see id. Vol. XVIII. p. 266, note 5) and *jalam-asṭhâmi* for *janm-dâṣṭhâmi* in Northern India (see id. Vol. XX. p. 69, note 2).

⁶ See id. § 148.

⁷ See id. §§ 279, 296, and Beames' *Comparative Grammar of the Modern Âryan Languages of India*, p. 282 (2).

⁸ See Beames' *Comparative Grammar*, Vol. I. p. 152, § 41, and p. 281, § 78 (1).

The banners and crests of the Rāshtrakūṭas of Mālkhēḍ and of the Raṭṭas of Saundatti.

The difference between the *lāñchhana* or crest, which was the device used on the seals of copper-plate charters,¹ occasionally at the tops of inscriptions on stone, and on coins, and the *dhvaja* or banner, has been explained, with instances, in my *Dynasties of the Kanarese Districts*, in the *Gazetteer of the Bombay Presidency*, Vol. I. Part II., p. 299, note 4.

The Rāshtrakūṭas of Mālkhēḍ had the *pālidhvaja* banner and the *Garuḍalāñchhana* or *Garuḍa* crest, which are mentioned in, for instance, lines 9 and 13 of the Sirūr inscription of A.D. 866, E., page 206. And it would appear, from a passage in the *Ādipurāṇa* of Jinasēna, that the *pālidhvaja* was a particular arrangement, in rows, of a thousand and eighty flags,—a hundred and eighty flags of each of ten kinds of flags bearing, as there specified, the devices of garlands, cloths (P), peacocks, water-lilies, geese, eagles, lions, bulls, elephants, and wheels; see *Ind. Ant.* Vol. XIV. p. 104 f.

The Raṭṭas of Saundatti, on the other hand, had the *suvarṇaGaruḍadhvaja*, or banner of a golden *Garuḍa*, and the *śindūralāñchhana* or *sendūralāñchhana*, the red-lead crest.

Their *lāñchhana* is mentioned in the records edited by me in the *Jour. Bo. Br. R. As. Soc.* Vol. X. pp. 194 to 286, in my translations of which I treated it as the mark of vermilion. Subsequently, however, the expression *śindūra-lāñchhanam*, for *śindūra-lāñchhanam*, in line 43 of the inscription at Têrdāl, was translated by Mr. Pathak as meaning “who has the device of an elephant.” To this there was attached a note, telling us vaguely that, “according to Kêśirāja, *śindhura* is changed into *śindūra*.”² And, accepting that statement, I translated *śindūra-lā[ñ]chhanam* in the Maṇṭūr inscription of A.D. 1040,³ and *śindūra-lāñchchhanas* in the Bhôj plates of A.D. 1208,⁴ by “who has the crest of an elephant;” and I have taken it as established, that the Raṭṭas of Saundatti had the elephant crest.⁵ Since that time, however, I have gradually learnt that, even apart from his habit of often not stating chapter and verse for his assertions, so that it is sometimes difficult or impossible to test them, the person who made that statement about the meaning of *śindūra* in this combination, is by no means to be accepted implicitly. He has misled us in this matter. And, as happens not infrequently, the process of setting things right cannot be made as brief as the enunciation of the assertion which has led us astray.

On re-examining the Raṭṭa records themselves,⁶ I find that they mention the crest by two words, *śindūra* and *sendūra*.⁷ I find the word *śindūra* in the following cases:—My ink-impression of the fragmentary inscription of Kārtavīrya II. at Saundatti, of the period A.D. 1069 to 1076, shews distinctly *śindūra-lāñchchhanam*, as given by me in *Jour. Bo. Br. R. As. Soc.* Vol. X. p. 213, text line 5. My photograph of the Kalhoḷe inscription of Kārtavīrya IV. of A.D. 1204 shews distinctly *śindūra-lāñchchhanam*, as given by me *ibid.* p. 221, text line 16. And the published facsimile lithograph⁸ of the Saundatti inscription of Lakshmidêva II. of A.D. 1228 shews distinctly *śindūra-lāñchchhanam*, as given by me, *ibid.* p. 268, text line 62. And I have the

¹ There were, however, exceptions to the rule. And, notably, the seal of the only Raṭṭa copper-plate record which has come to light, the Bhôj plates of A.D. 1208, appears to present, not their crest, but the *Garuḍa* which was the device on their banner; see *Ind. Ant.* Vol. XIX. p. 243.

² *Ind. Ant.* Vol. XIV. p. 24, note 24.—I may remark that the editing of that record was done under strict supervision by me; and there can be little doubt, if any, that the original does present *śindūra* and not *sendūra*.

³ *Ind. Ant.* Vol. XIX. p. 164, text line 9-10.

⁴ *Ibid.* p. 247, text line 88.

⁵ See *Dyn. Kan. Distrs.* p. 552.

⁶ I have not got either ink-impressions or photographs of the Maṇṭūr inscription and the Bhôj plates.

⁷ In the first syllable of this word, the vowel may be either the short *e* or the long *ē*. The following conjunct consonant indicates, preferentially, the short *e*.

⁸ *Archæol. Surv. West. Ind.* Vol. II. p. 224, Plate 73.

word *sendūra* in the following cases:—My ink-impression of the Saundatti inscription of A.D. 1096 or thereabouts shews that in line 24, where my published text, *Jour. Bo. Br. R. As. Soc.* Vol. X. p. 196, gives *sindhūra-lāñchhanam*, the original has *sendūra-lāñchhanam*: the vowel of the first syllable is unmistakably *e*, *ē*, not *i*; and in the second syllable the *n* and the *ḍ* are unmistakable, and the subscript consonant, somewhat blurred, either is an original *ḍ*, or else is an original *dh* corrected into *ḍ*. And my ink-impression of the inscription at the temple of Aṅkalēśvara or Aṅkuśēśvara at Saundatti, which, though not published, has been mentioned by me elsewhere,¹ shews distinctly *sendūra-lāñchhanam* in line 24, in the description of Anka in the passage of A.D. 1048, and again in line 59, in the description of Kārtavīrya II. in the passage of A.D. 1087.

We thus have, well established, the two forms *sindhūra* and *sendūra* or *sēndūra*, both used in the Raṭṭa records. And we have now to determine the meaning of the word.

Now, we have in Sanskrit two words, *sindhura*, with the aspirated *dh* and the short *u*, meaning 'an elephant,' and *sindūra*, with the unaspirated *d* and the long *ū*, meaning 'red lead, minium, vermilion,' and 'a particular kind of tree or plant.'

Dr. Kittel's Kannaḍa-English Dictionary (1894) gives *sindhūra*, with the long *ū* but still with the aspirated *dh*, as a variant of *sindhura*, and only with the meaning of 'an elephant.' His authority for it is the *Nāmārtharatnākara*, 26. I am not able to examine that work. But I notice that Gangadhar Madiwaleshwar Turmari's Kanarese Vocabulary (1869) gives *sindhūra*, with the long *ū* and the aspirated *dh*, with the meanings both of 'elephant' and of *kuñkuma*, 'saffron,' the use of which for certain purposes was much the same as the use of *sindūra*; and, further, it brackets *sindhura*, with the short *u*, in such a way as to attribute to it, also, the meaning of *kuñkuma*, for which, however, I cannot trace any other authority. And so, also, Reeve and Sanderson's Canarese Dictionary (1858) gives *sindhura* and *sindhūra*, with both the short *u* and the long *ū* and with the aspirated *dh*, as meaning both 'red lead' and 'an elephant.'

In addition to giving *sindhūra* as another form of *sindhura*, Dr. Kittel's Dictionary further presents *sindura*, with the short *u* and the unaspirated *d*, as a *tadbhava*-corruption of *sindhura*. The authority quoted for this is the *Śabdamanidarpana* of Kēśirāja, Dr. Kittel's own edition (1872), p. 339. And there, under the illustrations of sūtra 255, which teaches amongst other things the change of *dh* to *d*, we certainly have "*sindhuram* = *sinduram*." Here, however, the short *u* is preserved; and the corruption of *sindhura*, thus presented, is not *sindūra* with the long *ū*. This corruption, *sindura*, is not given in Gangadhar Madiwaleshwar's Vocabulary, or in Reeve and Sanderson's Dictionary.

To the other word, *sindūra*, Dr. Kittel's Dictionary assigns only the meaning of 'red lead, minium.' And, as *tadbhava*-corruptions of this word, it gives *chandra* (2), with *chandra*, *chendara* (1) and *chendira* (1), and also *sendura*, with the short *e* and *u*, and *sēndūra*, with the long *ē* and *ū*, and both with the unaspirated *d*. Reeve and Sanderson's Dictionary does not include *sendura* or *sēndūra*. Gangadhar Madiwaleshwar's Vocabulary does not present *sendura* or *sēndūra*; but it does present *sēndhūra*, with the long *ē* and *ū* and with the aspirated *dh*, as another form of *sindūra*. I do not find this last form anywhere else.

For *sēndūra*, as a corruption of *sindūra*, Dr. Kittel has quoted only Gangadhar Madiwaleshwar's Vocabulary. But, as I have just said, that Vocabulary presents, not *sēndūra* with the unaspirated *d*, but *sēndhūra* with the aspirated *dh*.

For *sendura*, as a corruption of *sindūra*, Dr. Kittel has quoted, with another authority which I am not able to examine, the *Śabdamanidarpana* of Kēśirāja, his own edition (1872), p. 357. There, however, under the illustrations to sūtra 271 which teaches amongst other things that *i* becomes *e*, we have "*sindhuram* = *sēndhuram*." In respect of this, I can only say that

¹ *Jour. Bo. Br. R. As. Soc.* Vol. X. p. 172 f., and *Dyn. Kan. Distrs.* pp. 553, 554.

either it establishes *sendhura* (for which, however, I cannot find any other authority) as a corruption of *sindhura*, for *sindhura*, 'elephant,' or else, and more probably, it is a mistake for "*sindhuram* = *senduram*," based on a habit which, Dr. Kittel has told me, the manuscripts have of not unfrequently presenting an aspirated instead of an unaspirated letter and *vice versa*. Beyond that, I can only say that Mr. Rice's *Karṇāṭakaśabdānuśāsanam* of Bhaṭṭakalaṅkadēva (1890), p. 108, under the illustrations of sūtra 160, does give *sendura* as the corruption of *sindūra*.

So far, no authority has been found for the assertion that *sindhura*, 'an elephant,' becomes *sindūra*. We have only obtained *sindura*, with the unaspirated *d* but retaining the short *u*, as a corruption of that word, and *sindhūra*, with the long *ū* but retaining the aspirated *dh*, as another form of it.

But, also, we have not found any conclusive authority for *sendūra* or *sēndūra* as a corruption of *sindūra*, 'red lead.' We have only obtained, more or less certainly *sendura* with the short *u*, and doubtfully *sēndhūra* with the aspirated *dh*, and *sēndūra* apparently deduced by inference from it. Turning, however, to other sources of information, we there obtain something quite definite. In a language closely allied to Kanarese, Mr. C. P. Brown's Telugu-English Dictionary (1852) does not give *sindura*, *sendura*, *sendūra*, or *sēndūra*. It does give *sindhuramu*, with the meaning of only 'an elephant,' and *sindhūramu*, with the meanings of only 'red lead, minium,' and 'a sort of tree.' And, while it does mention *sindhūramu* with the aspirated *dh* and the long *ū*, it specifies it as an "error" for *sindhūramu*. But, in a language of which the vocabulary is very much mixed up with that of the Kanarese of the southern districts of the Bombay Presidency, Molesworth and Candy's Marāṭhī-English Dictionary (1857), while not presenting *sindhura*, 'an elephant,' or *sindura*, does give *sindhūra*, with the meaning of only 'red lead, minium,' and gives *sēndūra* (with the palatal *ś*) as a popular form of it, and also *sēndūra* (with the dental *s*) with the indication that it is commonly written *sēndūra*. And Professor Pischel, in § 119 of his *Prākṛit Grammar* (1900), Vol. I., Part 8, of the *Grundriss der Indo-arischen Philologie und Altertumskunde*, has given *sendūra*, with the short *e* and the long *ū*, as the corruption of *sindūra*. On the other hand, the *Pāyālaśchhīnāmamālā* of Dhanapāla, according to Dr. Bühler's edition (1879), does not seem to deal with *sindhūra*, but indicates, in verse 9, that *sindhura*, 'an elephant,' retains the *tatsama*-form *sindhura*, and does not present any corruption of that word.

It would thus seem that, among the Kanarese authorities, there has been some confusion between *sindhura*, 'an elephant,' and *sindūra*, 'red lead, minium, vermilion,' which confusion, however, is in all probability confined to mistakes by copyists. But I cannot discover any authority of any kind for the assertion that *sindhura*, 'an elephant,' takes the form *sindūra*, or any indication that the word *sindūra* has the meaning of 'an elephant.' And there are no reasonable grounds for imputing any confusion between the two words to the writers of the ancient records. On the other hand, *sendūra*, *sēndūra*, and *sēndūra* are given as corruptions of *sindūra* by authorities of an unquestionable kind. We may, therefore, safely discard any idea that *sindūralāñchhana* and *sendūralāñchhana* can mean 'an elephant crest.' And we may safely revert to my original rendering of it as the mark of vermilion, for which, however, there is now to be substituted, in more technical terms, the red-lead crest.

The only point that remains, is, to determine exactly what we are to understand by a red-lead crest. Now, Monier-Williams' Sanskrit Dictionary, revised edition, gives *sindūra-tilaka* as meaning 'a mark on the forehead made with red lead.'¹ And, similarly, Dr. Kittel's

¹ Also, we may remark, it gives *sindūra-tilaka* as meaning 'marked with red lead, an elephant,' and *sindūra-tilaka* as denoting 'a woman whose forehead is marked with red lead (and therefore whose husband is living).' And H. H. Wilson has mentioned a particular use of the *sindūra-tilaka* by women, in telling us that a widow, about to commit *suttee*, "in making preparations for ascending the funeral pile, used to mark her forehead with *sindūra*, and to deck herself sumptuously with all the symbols of a *sadhavī*," or woman whose husband is still alive; see his *Works*, Vol. II. p. 300.

Kannaḍa-English Dictionary gives *sindūra-boṭṭu* as meaning 'a round mark (on the forehead) made with red lead.' That, therefore, was one of the uses of red-lead; namely, for making the *tilaka* or 'mark on the forehead, made with coloured earths, sandal-wood, or unguents, either as an ornament or as a sectarian distinction.' But a special use of the *sindūra* as a royal prerogative is established by the *Rājatarāṅgiṇī*, 8, 2010. We are there told, in respect of a certain confidential official named Kōshthēśvara, a councillor of king Jayasinha of Kashmir, that,—*baddhv-ādihikāriṇaḥ śulkaṁ grāhṇat-ākāri rāja-vat tēna sva-nāmnā bhāpḍēshu draṅgē sindūra-mudrapam*,—"imprisoning the officials, he collected the customs at the watch-station, and had his own name stamped in red-lead on the wares as if he were the king."¹ To this, Dr. Stein has attached the comment that "it is still customary in Jammu territory, and 'probably elsewhere too in India, to mark goods for which octroi-duty has been paid, with seal-impressions in red-lead (*sindūra*).'" That comment is apposite enough. But we further learn from the text that, in ancient times, there was a certain royal privilege of stamping with red-lead. The word *mudrapa* means the act of making the *mudra* or stamp or impression of a *lāñchhana* or device on a seal or crest. And we thus see that the possession of the *sindūralāñchhana* or *sendūralāñchhana* entitled an owner of it to stamp his name, crest, or other symbol, in red-lead.

* * * * *

Gōvinda II., and the Alās plates which purport to have been issued in A.D. 770.

In Vol. VI. above, p. 170 ff., I examined again, in the light of only the most nearly synchronous records, a question which had engaged my attention once before.² And I arrived at the same conclusion; namely, that the successor of Kṛishṇa I. was his younger son Dhruva. I indicated that the pointed expression used in the Wanī record of A.D. 807 (and repeated in the Rādhānpur record of A.D. 808), that Dhruva obtained the sovereignty by "leaping over his elder brother (*jyēshṭh-ōlāṅghana*)," would not be incompatible with the possibility that Gōvinda II., the elder son, was the intended successor of Kṛishṇa I., and in fact is rather suggestive that, not only was that the case, but also an appointment of him as *Yuvarāja* was actually made. And I found, in the Paṭṭaṇ record of A.D. 794, a possible intimation that Gōvinda II. established himself in the northern parts of the Rāshṭrakūṭa territories, while Dhruva set himself up as his rival in the south, and that time elapsed before Dhruva made himself master of the whole kingdom. But I found it to be plain that, at the best, Gōvinda II. made a stand for only a short time. And I arrived at the conclusion, from the early authoritative records, that Dhruva set himself up as king immediately on the death of Kṛishṇa I., and that Gōvinda II. had no real part in the succession at all.

Since then, there has been published, in Vol. VI. above, p. 208 ff., the record contained in the Alās plates. This record mentions Dantidurga, son of Indra II., by a name, Dadrivarman, which is of course nothing but a mistake, made by the writer, for Dantivarman. It introduces Gōvinda II. as "the dear son" of the favourite of Fortune and the Earth, the *Mahārājādhirāja*, *Paramēśvara*, and *Bhaṭṭāraka* Akālavārsha-(Kṛishṇa I.), and describes him as the *Yuvarāja* Gōvindarāja, with the *birudas* or secondary appellations of *Prabhūtavārsha* and *Vikramāvalōka*, "whose head was purified by an anointment to the position of *Yuvarāja* which was greeted with acclamation by the whole world, and who had attained the *pañchamahāśabda*." It brings forward a certain Vijayāditya, with the *birudas* of *Mānāvalōka* (*sic*) and *Ratnavārsha*, who is described as a son of (another) Dantivarman, and as a son's son of a Dhruvarāja (who seems to be Dhruva, the younger brother of Gōvinda II.). And it recites that, at the request of Vijayāditya, and on a specified day of the month *Āshāḍha* in the *Saumya saṁvatsara*, Śaka-Saṁvat 692 (expired), falling in June, A.D. 770, Gōvinda II., as *Yuvarāja*, being

¹ Dr. Stein's Text; and Translation, Vol. II. p. 156.

² *Dyn. Kan. Distrs.* p. 393.

then at the confluence of the rivers Krishṇavernā and Musī after his victorious camp had invaded the province of Veṅgi and the lord of Veṅgi had humbly ceded his treasures, his forces, and his country, granted to a Brāhmaṇa a certain village in the Alaktakā *viśhaya*, which¹ was a territory close on the east of Kōlhāpur, between the rivers Vārṇā, Krishṇā, and Dādghaṅgā.

Now, the bad formation of the characters, and the occasional very marked irregularity of the lines of the writing, suffice to shew that these Alās plates do not contain the original and synchronous official record of the matters recited in them. And they are, therefore, a *spurious record*. Whether, however, the matter set forth in the record is unauthentic, is another question. But it seems hardly likely that the composer of it could have invented the *birudas* ending in *avalōka*.² There is nothing discordant in the date, A.D. 770, which applies, of course, to Krishṇa I. as well as to Gōvinda II., and fits in perfectly well between the dates of A.D. 754, which we have for Dantidurga-Dantivarman II., and A.D. 783-84, which we have for Dhruva.³ And I think that, pending the production of any distinct evidence to the contrary, we may look upon this record as based upon something genuine, and as being a more or less accurate reproduction, from probably a manuscript copy, of an original record which had been lost, and may accept it as establishing, provisionally, that Gōvinda II. was actually installed as Yuvarāja, and was holding office as such, under his father Krishṇa I., in A.D. 770. While, however, it may be provisionally accepted to that extent, this Alās record does not prove that Gōvinda II. succeeded to the throne and reigned as king.⁴

¹ See *Ind. Ant.* Vol. XXIX. p. 277 f.

² On the subject of the *avalōka*-appellations of the Rāshtrakūṭas of Mālkhēḍ, see Vol. VI. above, p. 168 f.

³ See Vol. VI. above, pp. 167, 197.

⁴ There is nothing more that can be said about that question, to any practical purpose, until we obtain further definite facts to go upon. But I am compelled to notice some remarks made by Mr. D. R. Bhandarkar, on page 28 above, in connection with the Sāṅglī record of A.D. 933 and an alleged utilisation of it by me, in respect of the point in question, on the occasion indicated above, namely, in Vol. VI. above, p. 170 ff., when, he has said, I was meeting objections brought by him against the views previously expressed by me. So far from basing any argument on the Sāṅglī record, so completely did I set it aside as being a late record of no authority on the point in question, that it was only after twice reading through my remarks that I discovered that Mr. Bhandarkar's allusion is to my inclusion of it in a foot-note in which I merely put together all the cases in which Gōvinda II. is, or is not, mentioned in the Rāshtrakūṭa records. And, so far from rightly understanding and applying the meaning of what I wrote, Mr. Bhandarkar has simply himself made from the Sāṅglī record an objectless deduction, about Jagattuṅga-Gōvinda III. and Amoghavarsha I., which could not serve any practical purpose, and in respect of which there is not any basis for his suggestion that it follows from anything said by me.—To the cases, put together by me in Vol. VI. above, p. 172, note 2, in which Gōvinda II. is, or is not, mentioned in the Rāshtrakūṭa records, we have now to add two more. The Chokkhakūṭi grant of A.D. 867 (Vol. VI. above, p. 239, verses 15, 16, text lines 17 to 20) repeats the two verses about Gōvinda II. and Dhruva which are presented in the Paṭṭhaṇ record of A.D. 794. And the Cambay plates of A.D. 930 (page 37 above, verses 8, 9, 10, text lines 10 to 14) present the three verses about Krishṇa I., Gōvinda II., and Nirupama-(Dhruva) which we have in the Sāṅglī plates of A.D. 933.

INDEX.¹

By V. VENKATYA, M.A.

A		PAGE	PAGE
Abhidhānachintāmaṇi, <i>quoted</i> ,	30n	Abalyā, <i>f.</i> ,	152n
Abhimanyu, <i>Rāshṭrakūṭa ch.</i> ,	216	Āhavamalla, <i>sur. of</i> Sōmēśvara I.,	145, 146
abhiśhēka-maṇḍapa,	132	Ahmad Shāh, <i>Bahmanī k.</i> ,	78
abhyūsha, <i>a cake</i> ,	43n	Abōbala, <i>vi.</i> ,	84
Abulāmā, <i>vi.</i> ,	72	Airāvata, <i>the elephant of</i> Indra,	42n
āchārya, <i>an architect</i> ,	168n	Aivaraganda, <i>sur. of</i> Nṛsiṃharāya,	84
Achocharapākkam, <i>vi.</i> ,	11	Ajanṭā, <i>vi.</i> ,	49
Achyutarāya, <i>Vijayanagara k.</i> ,	18n	Ajilaru, <i>sur. of</i> Vira-Timmarāja-Odeyaru,	114
Adaragunṇi, <i>vi.</i> ,	215	Ajmere, <i>vi.</i> ,	58
Āḍavallār or Āḍavallār, <i>s. a.</i> Natēsa,	138	ājñā, <i>s. a.</i> ājñapti,	163n
Āḍavi-Mushṭūru, <i>s. a.</i> Kōna,	75, 85	ājñapti,	69n, 183, 184, 185, 191
Āḍḍakali gachchha,	179, 191	Akālavarsha, <i>sur. of</i> Rāshṭrakūṭa kings, 28,	29, 43, 230
ādēsa-naibandhika,	87	akhasālin, <i>s. a.</i> akkasāle,	107n
Āḍēya,	62	akkasāle or akkasāliga, <i>a goldsmith</i> ,	107n
Ādhikārika,	45	Akkinangaiyār, <i>queen of</i> Kulamānikkeru-	
adhikārin, <i>a minister</i> ,	196	maṇār,	137
Ādhipurī, <i>s. a.</i> Tiruvorriyūr,	149	akshapatālika or ākshapatālika,	69, 107n
Ādhipurīśvara, <i>te.</i> ,	148	ākshasālika or akshasālin, <i>s. a.</i> akkasāle,	107n
adhvaryu,	46	akshaya-nivī,	101n
aḍi, <i>His Majesty</i> ,	24n	akshaya-tritīyā, <i>tīlhi</i> ,	98
Āḍijina, <i>s. a.</i> Rishabhavātha,	108, 114, 115	Akshēśvara, <i>te.</i> ,	11
Āḍipurāṇa, <i>quoted</i> ,	227	Alagan-Perumāl, <i>sur. of</i> Jaṭilavarman Śrī-	
Āḍityabhaṭāra, <i>m.</i> ,	202	vallabha Ativīrarāma,	16
Āḍityasēna, <i>Gupta k.</i> ,	59	Alaktakā-vishaya, <i>di.</i> ,	231
Āḍityavardhana, <i>Kanauj k.</i> ,	159	Ālaṅguḍi, <i>vi.</i> ,	5n
Āḍivarāha, <i>sur. of</i> Bhōja,	82n	alai, <i>flower</i> ,	132
Āḍiyappaṇ, <i>te.</i> ,	175	Alās, <i>vi.</i> ,	230, 231
Āḍiyār, <i>m.</i> ,	25	Albuquerque, <i>Portuguese viceroy</i> ,	18, 19
agambāḍi, <i>a body-guard</i> ,	164	ali-mukham, <i>a port-town</i> ,	168
Agastyēśvara, <i>te.</i> ,	133	Alinā, <i>vi.</i> ,	62n, 68n
Āgimita (Agnimitra), <i>m.</i> ,	50	Alivīṇa-Kalakanda-Prithvigāngaraiyaṇ, <i>sur.</i>	
Agimitranaka (Agnimitra), <i>m.</i> ,	49, 50	of Puttaḍigaḷ,	195, 196, 197
agnidh,	46	aliya-santāna,	112
agnibōtrin,	87	alopakhādaka,	67
Agnipurāṇa, <i>quoted</i> ,	120n	alphabets :—	
agnishṭōma,	46	box-headed,	103
agrahāra,	20, 27, 45, 75, 84, 160, 180, 212	Brāhmī,	117, 118, 119
Āgranipidugu, <i>Chōḷa ch.</i> ,	149	Grantha,	22, 25, 76n, 108, 109, 115, 116,
āgrayana,	46		120, 121, 123, 145, 148, 152, 192, 197

The figures refer to pages; 'n' after a figure, to foot-notes; and 'add.' to the *Additions and Corrections* on pp. v. and vi. The following other abbreviations are used :— *ch.* = chief; *co.* = country; *di.* = district or division; *do.* = ditto; *dy.* = dynasty; *E.* = Eastern; *f.* = female; *k.* = king; *m.* = male; *mo.* = mountain; *ri.* = river; *s. a.* = same as; *sur.* = surname; *te.* = temple; *vi.* = village or town; *W.* = Western.

	PAGE		PAGE
Kannarese, 108, 109, 111, 112, 113, 199,	202, 209	Ânûka, m.,	95
Kharoṣṭhî,	117, 118, 119	anusvâra,	86, 103, 202
Nâgarî, 75, 85, 94, 98, 102, 109, 111, 156,	188, 219	Âpadevanaka, m.,	50
Pallava-Grantha,	133	apahnuti, <i>alamkâra</i> ,	43n
Telugu,	17, 75, 83n	Aphsaḍ, vi.,	53
Vatteluttu,	23, 24, 108	Appaṇa, ch.,	161, 162, 163
Âlvâr, s. a. Vishnu,	193	Apsarôdêvi, <i>queen of Râjyavardhana I.</i> ,	159
Amûlângavalli-Attimallachaturvêdimangalam,		araiyar, <i>title</i> ,	135
vi.,	197	aṣâm (aṣam), <i>charity</i> ,	140n
Amarakôṣa, <i>quoted</i> ,	43n, 46n	Âraṇi, vi.,	203n
Amarâvati, vi.,	17	Araṣûr, vi.,	164
Amarêṣa, s. a. Amarêṣvara,	20	aratṭhasamvinayika,	67, 68, 221n
Amarêṣvara, <i>te.</i> ,	17	ardha-samvṛitta,	27
amâṭya,	71	Arhanandin, <i>Jaina teacher</i> ,	179, 191, 192
Âmbûr, vi.,	79n	Arihararâja, s. a. Haribara II.,	115
Âmbûrudurga (Gid-Âmûru), vi.,	78n	Arikêśarin II., <i>Chalukya ch.</i> ,	34
Aminbhâvi, vi.,	212	Arikulakêśarin or Kêśariyâr, s. a. Arimjaya,	141, 142
Amitravalli, f.,	144, 145	Arimaddanapura, <i>sur. of</i> Pugâma,	197
Amua I., <i>E. Chalukya k.</i> ,	182, 184, 190	Arimjaya, <i>Chôla k.</i> ,	141
Amma II., <i>do.</i> ,	179, 182, 184, 190, 191	Arivattagapuram, <i>sur. of</i> Pukkam,	197, 198
Ammaiyyasabhâvi, s. a. Aminbhâvi,	212	Arjuna, <i>Chôla k.</i> ,	29, 38, 43, 44
Ammapadêva, <i>Chôla k.</i> ,	33, 44	arka, <i>metal</i> ,	107n
Amôghavarsha, <i>sur. of</i> Vaddiga,	33, 34, 194	ârkasâlîka, s. a. akkasâlîga,	107n
Amôghavarsha I., <i>Râshtrakûṭa k.</i> ,	28, 29,	Arkôḍam, vi.,	25
36, 43, 189n, 198, 200, 201, 202, 204,		Arraveelee, vi.,	179
207, 208, 209, 210, 211, 213, 214,		Aruḷâlanâtha, s. a. Aruḷâla-Perumâl,	132
Amôghavarsha II., <i>do.</i> ,	223, 231n	Aruḷâla-Perumâl, <i>te.</i> ,	128, 129, 130, 148,
Âmûr, vi.,	34		152, 164, 166
Âmûru, s. a. Ambûrudurga,	166	Arumbâkkam, vi.,	133, 137
âṇata,	78	Araṇa, <i>god</i> ,	125n
âṇati, s. a. âjñâpti,	69	Aruṅguṇam, vi.,	195
âṇatti, <i>do.</i> ,	185	Âruvilli, s. a. Arraveelee,	179, 191
Anawrata, k.,	185	Ârya-siddhânta,	15
Andhra, <i>dy.</i> ,	197	Âśâdhamitâ, f.,	57
Andhrabhṛitya, <i>dy.</i> ,	51, 121, 125, 223n	Aśani, ch.,	149, 151n
Âṅga, co.,	223n	Asathipâtaka, vi.,	87
Âṅka, <i>Raṭṭa prince</i> ,	77, 207	ashtakâ,	46
âṅkakâra or âṅkakâra, a <i>champion</i> ,	218, 223	âshṭavargika,	95
Âṅkalêṣvara, s. a. Âṅkusêṣvara,	180, 189	Âśôka, <i>Maurya k.</i> ,	66, 118
Âṅkusêṣvara, <i>te.</i> ,	218, 228	Âśvalâyana Gṛihyasûtra, <i>quoted</i> ,	46n
Annadâttabhaṭṭa, m.,	218, 228	asvamedha, <i>sacrifice</i> ,	189, 202, 214
Annâḍha, vi.,	85	Âtakûr, vi.,	133, 194
Annâmalainâtha, <i>te.</i> ,	87	Aṭavidurjaya, <i>Matsya ch.</i> ,	184
Annaveṇa, <i>Reddî k.</i> ,	177	Athpi, vi.,	225n
Annigere or Appigere, vi.,	58	Atisayadhavaḷa, <i>sur. of</i> Amôghavarsha I.,	207, 208
anomasa,	204, 208	atithitarpana,	45, 46
Ântrôli-Chhârôli, vi.,	67	Atri, <i>risâi</i> ,	86
	216	Attili, s. a. Uttellee,	179, 180
		Attilidêṣa, s. a. Attilinâṇḍu,	160

	PAGE		PAGE
Attilināṇḍu, <i>di.</i> ,	179, 191	Baṇās, <i>vi.</i> ,	58
Attimallar, <i>s. a.</i> Hastimalla,	195, 196	Baṇāsā, <i>s. a.</i> Baṇās,	58
Atvivarman (?), <i>W. Gaṅga k.</i> ,	193	Banavāsi, <i>vi.</i> ,	49, 70, 224, 226n
Avāḍachapa, <i>vi.</i> ,	87	Banavāsi twelve-thousand, <i>di.</i> ,	181, 209, 212, 214, 224
avagraha,	85	Baner, <i>vi.</i> ,	116
āvali, <i>a lineage</i> ,	110	Bangalore, <i>vi.</i> ,	51, 76n, 219n
avalōka appellation,	231	Baṅgavādi, <i>vi.</i> ,	22
Avanīyāḷappirandār, <i>sur. of</i> Kōpperuñ- jīṅga,	165, 166, 167	Baṅkēśa, <i>s. a.</i> Baṅkeya,	200n
Avanti, <i>co.</i> ,	31	Baṅkeya, Baṅkēya or Baṅkēyasa, <i>ch.</i> ,	200n, 209, 210, 211, 212, 213, 214
Avanyavanassambhava or Avanyavanōdbhava, <i>s. a.</i> Avanīyāḷappirandār,	167	Baṅkhēra, <i>vi.</i> ,	155, 156n
aviyena,	69	Bārapāsi, <i>s. a.</i> Vārapāsi,	208
Āyirachchēri, <i>vi.</i> ,	129, 131	Barabarāha, <i>sur. of</i> Nṛisimharāya,	84
Ayitilu, <i>m.</i> ,	52	Bargāon, <i>vi.</i> ,	100
Āyōmukha, <i>demon</i> ,	86	Bārṇāsā, <i>s. a.</i> Bārṇāsā,	58
Ayyapa, <i>s. a.</i> Āyyapadēva,	181, 190	Baroda, <i>vi.</i> ,	35, 215, 216
Āyyapadēva, <i>Noḷamba ch.</i> ,	181	Bārṇakūr, <i>vi.</i> ,	79, 80
Āyyapōṭi, <i>Jaina teacher</i> ,	191	Basarājū, <i>vi.</i> ,	163
Azamgarh, <i>vi.</i> ,	155n	Bassein, <i>vi.</i> ,	225
Azilizes, <i>k.</i> ,	52	Beḍada, <i>s. a.</i> Bidar,	76n
		Beḍadakōṭa or Beḍandakōṭa, <i>s. a.</i> Bidar,	78
		Beḍāsā, <i>vi.</i> ,	49, 50, 51
		Beggulūru, <i>s. a.</i> Bangalore,	78
		Bēhaṭṭi, <i>vi.</i> ,	219n, 220
		Beḷali three-hundred, <i>di.</i> ,	209, 212, 214
		Beḷgola or Beḷgula, <i>s. a.</i> Śravaṇa-Belgola,	108, 109, 112, 113, 114n
		Belgulee, <i>vi.</i> ,	212
		Bellaguttee, <i>s. a.</i> Belgulee,	212
		Bellakonḍa, <i>s. a.</i> Bellamkonḍa,	18, 19
		Bellamkonḍa, <i>fort</i> ,	19
		Belugulee, <i>vi.</i> ,	212
		Beḷvola three-hundred, <i>di.</i> ,	202, 204, 208
		Benares, <i>vi.</i> ,	29, 98n
		Betta, <i>Telugu-Chōḍa ch.</i> ,	148, 151, 152
		Betta I., <i>do.</i> ,	121, 122, 125
		Betta II., <i>do.</i> ,	121, 122, 126, 128
		Bezvāḍa, <i>vi.</i> ,	129
		Bhādāna, <i>vi.</i> ,	34, 217
		Bhadasama, <i>m.</i> ,	63
		Bhādāyaniya,	59
		bhāgabdhōgakara,	98, 160
		Bhāgalpur, <i>vi.</i> ,	31, 32, 33n
		Bhagavanta, <i>field</i> ,	143
		Bhāgavatapurāṇa, <i>quoted</i> ,	222
		Bhāgiratha, <i>mythical k.</i> ,	152, 154
		Bhairava or Bhairavēndra, <i>ch.</i> ,	109, 111, 112
		Bhājā, <i>vi.</i> ,	49, 50, 51
		Bhaktajunēśvara, <i>te.</i> ,	132
			2 H 2

B

Bādāmi, <i>vi.</i> ,	180
Baddega, <i>s. a.</i> Vaddiga,	34
Bagumrā, <i>vi.</i> ,	215, 216, 220
Bāgūru, <i>vi.</i> ,	78
Bahmanī, <i>dy.</i> ,	76, 77, 78
Bāhubalin, <i>Jaina saint</i> ,	108, 109, 111, 112n
Bāhūr, <i>vi.</i> ,	169
Baicha or Baichapa, <i>ch.</i> ,	115 and add.
Bail-Hongal, <i>vi.</i> ,	217
Baisa, <i>family</i> ,	218
bakula, <i>flower</i> ,	132
Bajagāmi, <i>vi.</i> ,	204
Bālarāmāyaṇa, <i>drama</i> ,	31n, 180n
Balavarman, <i>Prāgyōtisha k.</i> ,	100
bali,	45, 46
Bali, <i>demon</i> ,	31, 32n, 189
Bali, <i>k.</i> ,	189n
Balisa, <i>s. a.</i> Wanasa,	226n
Ballāladēva-Vēlābhata, <i>ch.</i> ,	182
Baloda, <i>vi.</i> ,	102, 103n
Bāpa, <i>dy.</i> ,	22, 24, 25
Bāpa, <i>post</i> ,	124n, 156
Bāpādhirāja, <i>title</i> ,	22n, 23
Bāpamahārāja, <i>s. a.</i> Bāpādhirāja,	23
Bāparāja, <i>s. a.</i> Bāparasa,	23
Bāparasa, <i>ch.</i> ,	23

	PAGE		PAGE
Bhaktaparādhiśvara, <i>te.</i> ,	171	Bisnaga, <i>s. a.</i> Vijayanagara,	19
Bhāmāna, <i>sur. of</i> Śivarāja II.,	86	Biṭraguṇṭa, <i>vi.</i> ,	17
Bhāmānadēva, <i>Kalachuri k.</i> ,	86	boar crest,	74, 178, 189
Bhāmaha, <i>Raṭṭa ch.</i> ,	217	Boḍḍiya, <i>sur. of</i> Ballāladēva-Vēlābhata,	182
Bhaṇḍanāditya, <i>ch.</i> ,	182	Pōdhi-tree,	51
Bhānuchandra, <i>m.</i> ,	183n	bōgi, <i>a concubine</i> ,	139
Bhārgava, <i>s. a.</i> Śukra,	135, 145, 146	Boḷama, <i>m.</i> ,	184
Bharhut Stūpa,	50n	Bollapini or Gollapini, <i>family name</i> ,	75
bhaṭāra,	201, 213	Bomma, <i>sur. of</i> Guṇḍa II.,	83
Bhatpar, <i>vi.</i> ,	93	Bonagiri, <i>vi.</i> ,	77
bhaṭṭa,	87, 160, 203	Boppa, <i>Sāḷva ch.</i> ,	76
Bhaṭṭadēva, <i>m.</i> ,	191, 192	Boppaṇāga, <i>m.</i> ,	107
bhaṭṭagrāma,	94	Brahmadēvastambha, <i>pillar</i> ,	111
Bhaṭṭākalāṇkadēva, <i>author</i> ,	221n, 229	brahmaḍēya,	66, 146
bhaṭṭāmākutika,	87	Brahman, <i>god</i> , 36, 41, 45, 111, 112, 120, 124,	152, 154n, 207, 222
bhaṭṭāraka,	208, 230	Brāhmaṇa,	58, 87
Bhaṭṭāraka, <i>sur. of</i> Vijayāditya I.,	189	brāhmaṇāchchhamsin,	46
Bhavabhūti, <i>poet</i> ,	30	brahmāṇḍa,	84
Bhāyilā (Bhrājilā), <i>f.</i> ,	52	Brāhmaṇi,	52
bhikhuhala,	66, 67	Brahma-siddhānta, 2, 3, 4, 5, 6, 9n, 10, 12,	13, 14, 15, 28, 169, 170, 171, 172, 173, 174,
bhikshu,	63		175, 176, 177
bhikshupī,	64	brahmāti (brahmahatyā),	200
Bhīllama I., <i>Yādava k.</i> ,	225n	bṛīhadratha,	49
Bhīllama II., <i>do.</i> ,	224n	Bṛīhaspati, <i>planet</i> ,	95
Bhīma, <i>Kalachuri k.</i> ,	86	Bṛīhaspati-sava,	46n
Bhīma, <i>s. a.</i> Chālukya-Bhīma I.,	189, 190n	British Museum plates,	129, 177
Bhīma, <i>s. a.</i> Chālukya-Bhīma II.,	181, 190	Bubhnowlee, <i>vi.</i> ,	99n
Bhīmanātha, <i>te.</i> ,	167	Buddha,	159, 196
Bhōgū, <i>m.</i> ,	87	Buddharāja, <i>Kaṭachchuri k.</i> ,	222n
Bhōj, <i>vi.</i> ,	218, 219n, 223, 227	Buddhist, 50, 51, 55, 56, 60, 66, 69, 119, 196, 197	72, 73, 74
Bhōja, <i>co.</i> ,	31	Bugūḍa, <i>vi.</i> ,	100
Bhōja, <i>Kanauj k.</i> ,	30, 32n, 86	Bukka, <i>ch.</i> ,	79n
Bhōjadēva, <i>k.</i> ,	29	Bukka I., <i>Vijayanagara k.</i> ,	115, 116
Bhōpāl, <i>vi.</i> ,	183	Bukka II., <i>do.</i> ,	115, 116
Bhujabala, <i>sur. of</i> Hoysala kings,	79n	Bukkarāja, <i>s. a.</i> Bukka II.,	115
Bhujabala-Bhīmakēśava-Daṇḍanāyaka, <i>ch.</i> ,	163	Bukkarāya, <i>s. a.</i> Bukka I.,	115
Bhujabala-māḍai, <i>coin</i> ,	130n	bull crest,	51, 85
Bhujabalin, <i>s. a.</i> Bāhubalin,	108, 112, 113	Bundēlkhāṇḍ, <i>co.</i> ,	224
bhūmichchhidra,	160	Burhān-i Ma'āsir, <i>name of a work</i> ,	77
Bhūpālanōdbhava, <i>sur. of</i> Nīlagaṇḍa,	166	Burma, <i>co.</i> ,	197
Bhūtapāla, <i>m.</i> ,	49	Busbal Rao, <i>sur. of</i> Vīra-Narasimha,	79
Bhuvanapāla, <i>k.</i> ,	94	Būtuga II., <i>W. Gaṅga k.</i> ,	181, 182
Bībhatu, <i>s. a.</i> Arjuna,	184		
Bidar, <i>vi.</i> ,	78		
Bijja, <i>s. a.</i> Bijja-Dantivarman,	181, 190		
Bijja-Dantivarman, <i>k.</i> ,	181		
Bilhari, <i>vi.</i> ,	29		
Bilvapedraka, <i>vi.</i> ,	104, 107		
Binnāpi, <i>queen of</i> Vīra-Timmarāja-Oḍeyaru,	114		
Birudu-māḍa, <i>coin</i> ,	180n		

C

Calicut, <i>vi.</i> ,	18
Cambay, <i>vi.</i> ,	26, 215n, 220, 231n

	PAGE		PAGE
Ceylon, island,	163	Chikkarāja-Oḍeyar, Ummatūr ch.,	19
Chaitra-pavitra, ceremony,	128, 132	Chippattarayana, ch.,	163, 168
chaitya,	51	Chiñchli, vi.,	205n
chaityālaya,	114	Chinnamapēt, vi.,	119
Chakrāyudha, sur. of Kshitipāla,	31, 32, 33n	Chitaldroog, vi.,	50, 51
Chalukya, family,	28, 34, 35n, 42, 180, 182, 191	Chitor or Chitorgarh, vi.,	207n
Chalukya, Eastern, dy.,	28, 29, 43, 177, 179, 180n, 181, 189n, 216, 222n	Chitrakōmalam, f.,	134
Chalukya, Western, dy.,	35, 130n, 180, 182, 210, 212, 217, 222n, 223	Chitrakōt or Chatrakōt, vi.,	207n
Chāluka, family,	28, 180, 189	Chitrakūṭa, s. a. Chitor,	207
Chāluka-Bhīma I., E. Chalukya k., 180, 184,	189n, 190	Chokkhakuṭi, vi.,	215, 216, 231n
Chāluka-Bhīma II., do.,	178, 180, 181, 182	Chōla, co.,	6, 25, 84n, 120, 129, 130, 133, 134n, 135, 137, 138, 140, 141, 144, 145, 147, 148, 149, 151, 161, 162, 163, 167, 168, 169, 176n, 181, 190, 192, 194, 216
Chāluka-Nārāyaṇa, sur. of Nṛsiṃharāja,	84	Chōlapuram, vi.,	12
Chāmara-māda, coin,	130n	Chōlasundara-Māvēndavarājan, sur. of Śemban- gudaiyan Nārāyaṇa Āditya,	147
Chambal, ri.,	58	Chōla-Tikka, Telugu-Chōḍa ch.,	121, 129
Chāmekā or Chāmekāmbā, f.,	179, 182, 191	chole or vole,	209
champaka, flower,	132	Chōlēśvara, te.,	12
Chāmunḍa, s. a. Chāmunḍarāja,	112, 113	Chōra, s. a. Chōla,	84
Chāmunḍā, goddess,	226	Cochin, vi.,	23
Chāmunḍarāja, ch.,	108, 109, 112	Coleroon, ri.,	161
Chāpakya, m.,	36	Comdepallyr, s. a. Koṇḍapalle,	19
Chāpakya-Chaturmukha, sur. of Gōvinda IV.,	36, 45	Conadolgī, s. a. Koṇḍaviḍu,	19n
Chandēlla, family,	31, 32, 86n	Corecolloo, vi.,	179
Chandrādityapura, vi.,	225	Cranganore, vi.,	197
Chandragupta II., Gupta k.,	60n	Cuddalore, vi.,	161, 162
Chandranātha, Jaina saint,	114	Cuddapah, vi.,	75n
Chanduliā, vi.,	87	Cuttack, vi.,	167n
Chāra, s. a. Chēra,	84		
charu,	45, 46	D	
Chārukīrti, title of Jaina teachers, 110n, 112,	113, 114	Daddara, k.,	182
chāturmāsya,	46	Dādā, vi.,	116
Chaturmukhabastī, te.,	110	Dādiga, s. a. Dadiya,	23
Chaturvargachintāmani, quoted,	59n	Dādīgavādi, co.,	22
Chaubattamalla, sur. of Nṛsiṃharāja,	84	Dādiga, ch.,	22, 23
Chāvunḍarāja, s. a. Chāmunḍarāja,	109	Dadrivarman, s. a. Dantivarman,	230
Chēdi, co.,	29, 33, 86n, 88, 135	Dāhāla, s. a. Chēdi,	86n
Chellakētana, family,	211n	daivagārika,	95
Chellūr, vi.,	9, 180, 181	Daivahāpāra, di.,	88n
Chenji, s. a. Gingee,	77	daivajña,	97
Chēra, co.,	84n	Dakhmitrā, f.,	56
Chētanabhaṭṭa, m.,	184n	Damayantikathā, quoted,	125n
Chhāñchi, m.,	87	Dambaṭṭil or Dēvaṭṭil, vi.,	94
chhata,	69, 70, 71n	Damōraka, m.,	49
Chhiḍāḍāṭēmbhā, vi.,	87	dānamukha, s. a. dēyadharmā,	55
Chicacole, vi.,	101	danāyaka, s. a. danḍanāyaka,	161n
Chidambaram, vi.,	5, 162, 165, 166, 167n, 172n	danḍa,	46
		danḍanāyaka,	161n, 208, 224

	PAGE		PAGE
Danḍapur, <i>vi.</i> ,	200n	fifth,	13, 128, 131n, 171, 174, 175
Danḍimahādēvi, <i>queen</i> ,	101	sixth,	3, 87, 88, 157, 160
danḍinagōpa,	168	seventh,	10, 11
Dāndū, <i>m.</i> ,	87	eighth,	2, 3, 175, 176
dannāka, <i>s. a.</i> danḍanāyaka,	161, 168	ninth,	1, 11, 12, 170
danta, <i>a pin</i> ,	89n	tenth,	164, 165, 170
Dantidurga, <i>Rāshtrakūṭa k.</i> ,	28, 42, 222n	eleventh, 2, 3, 15, 129, 131, 169, 170, 171, 176	
Dantidurga, <i>sur. of</i> Dantivarman II., 218n, 230, 231		thirteenth,	7n, 173
Dantiga, <i>s. a.</i> Dantidurga,	218n	fourteenth,	9n
Dantisakti-Viṭaṅki, <i>queen of</i> Rājaraṅga I.,	25n	new-moon,	204, 205, 208, 210
Dantivarman, <i>ch.</i> ,	230	days, solar :—	
Dantivarman II., <i>Rāshtrakūṭa k.</i> , 218n, 230, 231		third,	16
Daradagaṇḍaki, <i>di.</i> ,	94	sixth,	173
Darbhāraṇyāśvara, <i>te.</i> ,	172	thirteenth,	10
darśapūrnāmāsa,	46	fifteenth,	14, 15
Daśakumāracharita, <i>quoted</i> ,	159n	twentieth,	13
daśāparādha,	46, 68n	twenty-first,	13, 14, 129, 131
Daśavatāra, <i>cave temple</i> ,	216	twenty-second,	16
dates :—		twenty-third,	14
recorded by a chronogram, 76n, 126, 149, 155		twenty-sixth,	172
recorded in numerical symbols, 61, 66, 72,		twenty-seventh,	171, 172
74, 103, 107, 156, 160		twenty-eighth,	12
recorded in numerical words, 9, 20, 85, 110,		twenty-ninth,	15
112, 113		days of the week :—	
danḥśādhāsādhānika,	159	Sunday, 2, 4, 5, 6, 7, 8, 9, 11, 75, 85, 87,	
Daulatābād, <i>vi.</i> ,	224, 225	88, 163n, 164, 165, 169, 177, 204, 208	
Davirāmakula, <i>vi.</i> ,	94, 95	Monday, 2, 3, 7, 8, 9, 12, 13, 28, 45, 86,	
Dāyabhīma, <i>Telugu-Chōḍa ch.</i> ,	121, 122,	88, 98, 115, 171, 172, 173, 174, 177	
125, 148		Tuesday,	6, 8, 9, 162n, 171, 175, 177
Dāyima, <i>Raṭṭa prince</i> ,	218	Wednesday, 6, 7, 8, 9, 11, 13, 14, 15, 110,	
days, lunar :—		111, 129, 131, 170, 171, 172, 173, 174, 175, 176	
bright fortnight :—		Thursday, 2, 3, 4, 5, 6, 7, 8, 10, 13, 14, 15,	
first,	6	112, 113, 114, 170, 171, 173, 175	
second,	95, 165, 172	Friday, 7, 8, 9, 11, 12, 16, 128, 131, 162n,	
third,	5, 12, 98	164, 165, 170, 179	
fourth,	170	Saturday, 1, 4, 6, 8, 9, 16, 19, 95, 165, 172,	
fifth,	3, 4, 163n, 176, 177	174, 176	
sixth,	2, 12	Dēhātādēvi, <i>queen of</i> Bhāmānadēva,	86
seventh,	2, 4, 10, 87, 88, 175	Dekkan,	33n, 35n, 223
eighth,	4, 86, 88	Dēo-Baranārk, <i>vi.</i> ,	68n
ninth,	173	Deoha (Daivahā); <i>s. a.</i> Gogra,	88
tenth, 14, 28, 45, 112, 113, 114, 162n, 174		Dēōli, <i>vi.</i> ,	27n, 33, 34, 194, 215, 216, 220, 222
twelfth, 11, 14, 15, 16, 20, 111, 112, 173		Dēśigana or Dēśigana,	110, 112, 113, 114
thirteenth,	4, 5, 6, 174	Dēśināmamālā, <i>quoted</i> ,	183
fourteenth,	13, 172, 177	dēva, <i>a king</i> ,	164
fifteenth,	164	dēvabhōgahala,	66
full-moon,	75, 85, 115, 200, 201, 202	dēvadāya,	66
dark fortnight :—		Dēvagiri, <i>s. a.</i> Daulatābād,	219, 220, 224, 225
third,	16	Dēvagupta, <i>k.</i> ,	157, 159
fourth,	164, 165, 175	dēvakuṭikāshṭha, <i>measure of land</i> ,	87

	PAGE		PAGE
F		G	
Perishta, <i>author</i> ,	77	Gaḍiyamma, <i>m.</i> ,	214
		gahapati,	53
		Gaharwara, <i>family</i> ,	30n
		gahata (grihastha),	52n
		Gajalhatṭi pass,	161
		Gajapati, <i>dy.</i> ,	18, 19
		Gajapati-varāha, <i>coin</i> ,	130n
		gāmaūḍa, <i>s. a.</i> grāmakūṭa,	183, 222n
		gāmunḍa or gāmunḍu, <i>s. a.</i> gaṇḍa,	183
		Gaṇapati, <i>god</i> ,	27
		Gaṇapati, <i>Kākatīya k.</i> ,	167
		Gaṇḍagopāla, <i>biruda</i> ,	128, 130, 131
		Gaṇḍagopāla, <i>sur. of</i> Śrasiddhi,	162, 155
		Gandak, <i>ri.</i> ,	88, 94, 95
		Gaṇḍakī, <i>s. a.</i> Gandak,	87, 88, 94
		Gaṇḍa-māḍa, <i>coin</i> ,	130n
		Gaṇḍamahendra, <i>sur. of</i> Chālukya-Bhima II.,	181
		Gandahasti- or Gandhavāra-māḍa, <i>s. a.</i>	
		Gajapati-varāha,	130n
		Gandhāra, <i>co.</i> ,	31
		Gaṇḍikōṭa, <i>vi.</i> ,	78
		Gaṇḍēśvara, <i>m.</i> ,	95
		Gaṇḍa, <i>dy.</i> ,	23, 216
		Gaṇḍa, <i>Eastern, dy.</i> ,	107n, 183n
		Gaṇḍa, <i>Western, dy.</i> , 108, 181, 182, 192, 193,	195, 224
		Gaṇḍā (Ganges), <i>ri.</i> ,	35, 42, 44, 98, 154n
		Gaṇḍa-Bāṇa, <i>family</i> ,	195
		Gaṇḍādhārāya, <i>m.</i> ,	47
		Gaṇḍa Hale Sambā Rāya, <i>ch.</i> ,	77
		Gaṇḍaikondāṇ, <i>vi.</i> ,	15
		Gaṇḍamahādevī, <i>sur. of</i> Kāmakkāṇār,	195
		Gaṇḍa-Pallava, <i>family</i> , 22, 23, 24, 25n, 189, 192	
		Gaṇḍarāja, <i>ch.</i> ,	108, 109
		Gaṇḍa Rāja, <i>Ummatūr ch.</i> ,	18
		Gāṇḍāya, <i>family</i> ,	192
		gaṇikā, <i>a female elephant</i> ,	208
		Gaṇjām, <i>di.</i> ,	101
		Garga, <i>astronomer</i> , 2, 3, 4, 5, 6, 9n, 10, 12,	13, 14, 15, 28, 169, 170, 171, 172, 173,
			174, 175, 176, 177
		Garjara, <i>m.</i> ,	160
		Garuḍa, <i>god</i> ,	106
		aruḍa crest,	27, 98, 103, 121, 125, 208, 227
		Gauḍa, <i>co.</i> ,	86, 159n, 207n
		gauḍa or gavuḍa,	183, 191n, 222n
		Gauhaṭṭi, <i>vi.</i> ,	100
		gaulmika,	91
		gaṇḍa or gavuḍa, <i>s. a.</i> gaṇḍa,	183, 222n
		Gaṇḍīputra,	50
		Gaurisārman, <i>ch.</i> ,	183n
		Gauta I., <i>Sāluva ch.</i> ,	83
		Gauta II., <i>do.</i> ,	76, 84
		Gautama, <i>rishi</i> ,	143
		Geḍilam, <i>ri.</i> ,	162n and add.
		gerund,	147n
		ghara (griha), <i>a chaitya cave</i> ,	40
		ghaṭṭapati,	91
		Ghupika, <i>m.</i> ,	64
		Gidāṅgil, <i>vi.</i> ,	171
		Gingee, <i>vi.</i> ,	77n
		Goa, <i>vi.</i> ,	19, 224, 226n
		Gōḍāvari, <i>ri.</i> ,	27 and add., 45 and add., 226
		Goḍuguchinta, <i>vi.</i> ,	78
		Gogra or Ghogra, <i>ri.</i> ,	88, 96
		Gojjiga, <i>s. a.</i> Gōvinda IV.,	34
		Gōkarnapaṇḍitabhaṭṭāra, <i>teacher</i> ,	200, 203
		Gōkarnēśvara, <i>te.</i> ,	183
		Gōkulaghaṭṭa, <i>vi.</i> ,	86
		Golden Garuḍa banner,	227
		Gommaṭa or Gommaṭēśvara, <i>s. a.</i> Bāhubalin,	108
		Gōpālakrishṇa, <i>te.</i> ,	34
		Gōparāja, <i>Sāluva ch.</i> ,	76, 77
		Gōpa-Timma, <i>do.</i> ,	77n
		Gōpa-Tippa, <i>ch.</i> ,	76n
		Goppa-Tippa, <i>ch.</i> ,	76
		Gōrākhpur, <i>vi.</i> ,	98n, 99n
		gorava, <i>a Śaiva priest</i> ,	200, 203
		gōshṭhi,	201
		Gotamīputa Sātakaṇi (Gautamīputra Sāta-	
		karṇi), <i>Andhra k.</i> ,	60, 66, 70
		Goti (Gaupṭi), <i>f.</i> ,	46
		Gotiputra, <i>s. a.</i> Gaupṭīputra,	50
		gōtras :—	
		Bhāradvāja,	87
		Dhaumra,	87
		Gautama,	94
		Kāśyapa,	87, 98
		Kātyāyana,	87
		Kaundinya,	87
		Kausika,	198
		Kṛishṇātra (Kṛishṇātrōya),	87
		Kusika,	87
		Mānavya,	198

	PAGE		PAGE
Māthara,	28, 45		
Parāsara or Pārāsara,	87		
Rāhula,	87		
Śāṇḍilya,	87		
Sāvarṇa or Sāvārṇi,	87, 160		
Śrīvatsa,	85		
Vishṇuvṛiddha,	160		
Gōvinda II., <i>Rāshtrakūṭa k.</i> ,	28, 42, 230, 231		
Gōvinda III., <i>do.</i> ,	28, 29, 32n, 35, 200, 207, 210, 231n		
Gōvinda IV., <i>do.</i> ,	27, 28, 33, 34, 35, 36, 44, 47, 181, 190, 215, 216, 220, 223n		
Gōvindachandra, <i>Kanauj k.</i> ,	67, 85, 87, 98, 99		
Gōvindāyichcha, <i>m.</i> ,	87		
Gōviśālaka, <i>vi.</i> ,	98		
grāmakūṭa or grāmakūṭaka, <i>a village headman</i> ,	45, 183, 191, 222		
grāvastut,	46		
grīhapati,	50n		
grīhastha,	52		
Gujarāt, <i>co.</i> ,	29n, 35, 36, 58, 134, 225n		
Gummaṭa or Gummaṭṭṣa, <i>s. a. Bāhubalin</i> ,	108, 111, 114, 115		
Gummidippūṇḍi, <i>s. a. Gummidipūṇḍi</i> ,	129, 131		
Gummidipūṇḍi, <i>vi.</i> ,	129n		
Gumṣimi(P), <i>vi.</i> ,	192		
Gumsūr, <i>vi.</i> ,	100, 101		
Gupaga or Gupaka, <i>sur. of Vijayāditya III.</i> ,	29, 180, 189		
Gupakala-vishaya, <i>di.</i> ,	87, 88		
Gupakenallāta, <i>sur. of Vijayāditya III.</i> ,	180		
Gupamālai, <i>te.</i> ,	195, 196, 197		
Gupāmbhōḥidēva, <i>s. a. Gupasāgara I.</i> ,	86		
Gupapadeya, <i>vi.</i> ,	185		
Gupasāgara I., <i>Kalachuri k.</i> ,	86		
Gupasāgara II., <i>do.</i> ,	86, 87		
Gupḍa I., <i>Sāluva ch.</i> ,	76, 83		
Gupḍa II., <i>do.</i> ,	83		
Gupḍa III., <i>do.</i> ,	76, 77, 84		
Gupḍlūru, <i>vi.</i> ,	75, 85		
Gupḍugolana, <i>vi.</i> ,	132		
Gupta, <i>dy.</i> ,	35n, 46n, 50, 224		
Gurjara, <i>co.</i> ,	207		
Gurjara, <i>dy.</i> ,	223n		
Gurjarapratihāra, <i>family</i> ,	223n		
Gurmha, <i>vi.</i> ,	93n, 96n		
Gurupaṇḍitadēva, <i>s. a. Chārukīrti</i> ,	114		
Gutta, <i>family</i> ,	224, 226n		
Guttal, <i>vi.</i> ,	224, 226n		
Gwalior, <i>vi.</i> ,	30		
		H	
		Haidarābād, <i>vi.</i> ,	178
		Haihaya, <i>family</i> ,	33, 43, 184
		Haihaya, <i>mythical k.</i> ,	86
		hala, <i>measure of land</i> ,	66
		Halēbbī, <i>vi.</i> ,	161
		Halai, <i>vi.</i> ,	212, 219n
		Hampe, <i>vi.</i> ,	18
		Hanasōge, <i>vi.</i> ,	110
		Hanṣhe, <i>vi.</i> ,	80n
		Hāngal, <i>vi.</i> ,	224, 226n
		Hannikere, <i>vi.</i> ,	219
		Hannikēri, <i>s. a. Hannikere</i> ,	219
		Hanumantapuram, <i>vi.</i> ,	23
		Hanumat, <i>god</i> ,	199
		Hānūngul five-hundred, <i>di.</i> ,	212
		Hara, <i>s. a. Śiva</i> ,	41, 45, 190, 207
		Haralāhalli, <i>vi.</i> ,	219
		Harapharapa, <i>m.</i> ,	72
		Hari, <i>s. a. Vishṇu</i> ,	84, 151
		Harihar, <i>vi.</i> ,	162, 163
		Harihara II., <i>Vijayanagara k.</i> ,	115
		Hāritasmṛiti, <i>quoted</i> ,	66
		Hāritiputra,	189
		Harivamśapurāṇa, <i>quoted</i> ,	32n
		Hari-vāsara,	19, 20
		Harsha, <i>hill</i> ,	66
		Harsha, <i>Kanauj k.</i> ,	155, 156, 157, 159n, 159, 160
		Harsha, <i>Kāśmīr k.</i> ,	130n
		Harshacharita, <i>quoted</i> ,	156, 159n
		Harshadēva, <i>Chandēlla k.</i> ,	31, 32
		Harshavardhana, <i>s. a. Harsha</i> ,	155n, 156
		hasta, <i>measure of land</i> ,	87
		Hastigrāma, <i>vi.</i> ,	87
		Hastimalla, <i>sur. of Prithivipati II.</i> ,	193
		Hastimalla, <i>W. Gaṅga ch.</i> ,	195
		Hastisaila, <i>s. a. Arajāla-Perumā</i> ,	152, 155
		Hattī-Mattūr, <i>vi.</i> ,	199
		Hebbāl, <i>vi.</i> ,	214n
		Hebbipi, <i>vi.</i> ,	24
		Hēlārāja, <i>author</i> ,	44n
		Hēmachandra, <i>do.</i> ,	30, 69, 221, 223
		Hēmādri, <i>do.</i> ,	69n
		Hēmakūṭa, <i>hill</i> ,	80n, 84
		Hēmanta, <i>season</i> ,	46n
		Himavat, <i>mo.</i> ,	44
		Hindū,	77, 119
		hiranyāya,	46
			2 1

Jagaddhara, <i>commentator</i> ,	30n
Jagadobbagaṇḍa, <i>biruda</i> ,	168
Jagattuṅga, <i>sur. of</i> Gōvinda III., 28, 29, 42,	207, 231n
Jagattuṅga II., <i>Rāshtrakūṭa k.</i> ,	29, 33, 43
Jagattuṅga-sindhu, <i>tank</i> ,	29, 43
Jāgūka, <i>m.</i> ,	95
Jaimini-Bhāratam, <i>Telugu poem</i> ,	75, 76, 77
Jaina, 32n, 36, 74, 108, 109, 110, 112, 115,	116, 179, 182, 191, 221
Jākavvā, <i>queen of</i> Taila II.,	217
Jākhū, <i>m.</i> ,	87
jalam-ashtamī, <i>s. a.</i> janm-āshṭamī,	226n
Jālū, <i>m.</i> ,	87
Jambudvīpa,	49
Jambukēśvara, <i>te.</i> ,	129
Jammu, <i>di.</i> ,	230
Janaka, <i>m.</i> ,	87
Jananātha-vaṇanāḍu, <i>sur. of</i> Milāḍu two-	thousand, 138, 146
Jātaka, <i>quoted</i> ,	50n, 56n
Jaṭavarman Parākrama-Pāṇḍya, <i>Pāṇḍya k.</i> , 12, 17	
Jaṭavarman Sundara-Pāṇḍya I., <i>do.</i> ,	167
Jaṭavarman, <i>do.</i> ,	23, 185n
Jaṭavarman Parākrama-Pāṇḍya Arikēsa-	dēva, <i>do.</i> ,
	12, 13, 14, 17
Jaṭavarman Parākrama-Pāṇḍya Kulasēkhara,	<i>do.</i> ,
	14, 15, 17
Jaṭavarman Śrīvallabha, <i>do.</i> ,	15, 17
Jaṭavarman Śrīvallabha Ativīrārāma, <i>do.</i> ,	16, 17
javelin banner,	213
javvandi (śevvandi), <i>flower</i> ,	132
Jayachobandra, <i>Kanauj k.</i> ,	85, 88n
Jayāditya II., <i>k.</i> ,	93n, 96n
Jaya-māḍa, <i>coin</i> ,	130n
Jayanātha, <i>k.</i> ,	62n
Jayaṅgaṇḍa-Chōḷa-maṇḍalam, <i>co.</i> ,	133, 138, 192
Jayanti, <i>s. a.</i> Banavāsi,	49, 226n
Jayasimha, <i>Kaśmīr k.</i> ,	230
Jayasimha I., <i>E. Chalukya k.</i> ,	184, 189
Jayasimha II., <i>do.</i> ,	189
jihvāmūliya,	103
Jina, 108, 111, 112, 113, 114, 115, 116, 191	

	PAGE		PAGE
Jinadatta, <i>mythical k.</i>	110, 111, 112	kalakanda (kalakaptha),	195
Jinasena, <i>Jaina author,</i>	227	Kalalaya, <i>k.</i>	51
Jola, <i>co.</i>	34	Kalaledēvi, <i>queen of Narasimha II.,</i>	162n
Junnar, <i>vi.</i>	50, 55, 56	kalam, <i>measure,</i>	143, 144
Jupiter, <i>planet,</i>	95, 210	kalam, <i>a trumpet,</i>	168n
jyōtishōma,	46n	Kalanjara (Kalanjar), <i>vi.,</i>	86, 224
K			
Kachchi or Kachchiyūr, <i>s. a. Kachchūr,</i>	129	Kalanjarādhipati, <i>sur. of Chandēlla kings,</i>	86n
Kachchi-, Kachchiyūr- or Kachchūr-nādu, <i>di.,</i>	129, 132	kalanju, <i>weight,</i>	136, 138, 139, 140, 141, 143, 197
Kachchipan, <i>s. a. Kāsyapa,</i>	120	Kalapriya, <i>s. a. Mahākāla,</i>	29, 30, 43
Kachchūr, <i>vi.,</i>	129	Kalapriyanātha, <i>te.,</i>	30n
Kadaba, <i>vi.,</i>	216, 220	Kalarmōdu, <i>field,</i>	143
Kādadi Kapakkaṇ, <i>ch.,</i>	24	Kalas, <i>vi.,</i>	215, 216
Kadamba, <i>dy.,</i>	224	Kalasāpur, <i>vi.,</i>	223n
Kādamba, <i>family,</i>	219n, 224, 226n	Kalapa, <i>poet,</i>	223
Kādamba, <i>m.,</i>	143	Kalhole, <i>vi.,</i>	213, 227
Kādambari, <i>quoted,</i>	124n	Kali, <i>sur. of Vishṇuvardhana V.,</i>	189
Kādapaṭṭi, Kādupaṭṭi or Kādupaṭṭi, <i>s. a.</i>	25n	Kali age,	124, 125, 176, 207
Kādava, <i>s. a. Pallava,</i>	23, 24, 25, 26, 163, 164n, 167n	Kalidēva, <i>te.,</i>	212
Kādavan-Perundēvi, <i>sur. of Śālavai,</i>	25	Kalikāla, <i>s. a. Karikāla,</i>	120, 121, 122, 125, 148, 151
Kādēru, <i>field,</i>	143	Kālinadi, <i>ri.,</i>	157
Kādēyarāja, <i>ch.,</i>	184	Kalinārai, <i>Pallava k.,</i>	133
Kādaviṭṭēśvara, <i>te.,</i>	25n	Kalinārlēvara, <i>te.,</i>	133
Kahalli, <i>vi.,</i>	87	Kalinganagara, <i>vi.,</i>	183n
Kahla, <i>vi.,</i>	85	Kalingattu-Parani, <i>quoted,</i>	120
Kailāsa, <i>mo.,</i>	42	Kalivallabha, <i>sur. of Dhruva,</i>	207
Kailāsanātha, <i>te.,</i>	11	Kaliya, <i>field,</i>	143
Kailāsapati, <i>te.,</i>	10, 15	Kaliyamalai, <i>vi.,</i>	162
Kaira, <i>vi.,</i>	29n, 36	Kāliyūr-kōṭṭam, <i>di.,</i>	195n
Kaivandūr, <i>vi.,</i>	123	Kallaḍuppūr, <i>vi.,</i>	195n
Kaivandūr, <i>s. a. Kaivandūr,</i>	123, 128	Kallaḍuppūr, <i>vi.,</i>	194, 195
Kākati or Kākatiya, <i>family,</i>	128, 129, 131, 167	Kallaṅguṭṭai, <i>pond,</i>	195
Kakka II., <i>Rāshtrakūṭa k.,</i>	217	Kalleḍuppūr, <i>vi.,</i>	195, 196
Kākkalūr, <i>vi.,</i>	129	Kalleḍuppūr-maryādā, <i>di.,</i>	194, 195
Kākkalūr-nādu, <i>di.,</i>	129	Kallināgai, <i>f.,</i>	161, 162, 168
Kakkarāja I., <i>Gujarāt Rāshtrakūṭa ch.,</i>	216	Kalliyūrmālai, <i>s. a. Kaliyamalai,</i>	179, 191
Kakkarāja II., <i>do.,</i>	216	Kaluchumbayru, <i>s. a. Kunsamurroo,</i>	130n, 217, 224
kāl, <i>s. a. marakkāl,</i>	144	Kalyānapura or Kalyāni, <i>vi.,</i>	197
Kalabe, <i>f.,</i>	202	Kalyāni, <i>ri.,</i>	44, 45, 190, 215
Kalachuri, <i>dy.,</i>	86, 88	Kāma, <i>god,</i>	195
Kalachurya, <i>dy.,</i>	86n, 219n, 224	Kamakkaṇār, <i>f.,</i>	99n
Kālahasti, <i>vi.,</i>	77, 129	Kamauli, <i>vi.,</i>	192, 193n, 196
Kālakampa, <i>ch.,</i>	182	Kampa or Kampavarman, <i>s. a. Vijaya-Kampa-</i>	24
		vikramavarman,	167
		Kaṇaiyūr, <i>vi.,</i>	194
		Kanakasabhādhinātha, <i>te.,</i>	194
		Kanakavalli, <i>vi.,</i>	194
		Kanakavalli-Vishṇugriha, <i>te.,</i>	30, 31, 32, 33n, 85, 86n, 87, 88n,
		Kanauj, <i>vi.,</i>	95, 98, 157
		Kāñchanadēvi, <i>queen of Guṇasāgara I.,</i>	86
		Kāñcharigunḍu, <i>rock,</i>	191
			2 r 2

	PAGE		PAGE
Kāññi or Kāññhipura (Conjeeveram), vi., 18,		Kārtavīrya I., <i>Raṭṭa ch.</i> ,	218, 223n
25n, 77, 80, 115, 116, 121, 122, 128,		Kārtavīrya II., <i>do.</i> ,	217, 218, 227, 228
129, 130, 131, 152, 164, 165, 166, 207		Kārtavīrya III., <i>do.</i> ,	219
Kāññāṭṭh-Sālai. vi.,	169	Kārtavīrya IV., <i>do.</i> ,	218, 219, 223, 227
Kāññāṭṭh. vi.,	78	Kārtavīrya Arjuna, <i>mythical k.</i> ,	86
Kāññāṭṭh. <i>Gaṅga k.</i> ,	23	Kārtikēya, s. a. Skanda,	106
Kāññāṭṭh. vi.,	117, 118	Kāśāknḍi, vi.,	23n and add., 185n
Kāññāṭṭh. vi.,	210	Kāśilli, vi.,	94
Kāññāṭṭh. vi.,	116, 117, 118, 119	Kāśmīr, co.,	130n, 210, 223, 230
Kāññāṭṭh. s. a. Kṛishṇa.	117	kāśu, coin,	139, 145
Kāññāṭṭh. co.,	76	kāṭa,	69
Kāññāṭṭh. s. a. Kāññāṭṭhaka,	23	Kāṭa, ch.,	180
Kāññāṭṭh. vi.,	161	Kāṭachchuri, <i>dy.</i> ,	222n
Kāññāṭṭh. s. a. Kṛishṇa III., 135, 136, 143,		kāṭakādhīśa, kāṭakarāja or kāṭakēśa, a super-	
194, 195		intendent of the royal camp, 183, 184, 185, 191	
Kāññāṭṭh. <i>do.</i> ,	25, 142, 144	Kāṭaughanagrāma, vi.,	87
Kāññāṭṭh. Pṛithivī (or Pṛithivī)gaṅgaraiyar,		Kāṭhaka, s. a. Kādava,	167
sur. of Attimallar,	195, 196	Kāṭhāri or Kāṭṭāri, <i>viruda</i> , 76, 77n, 79, 83n, 84	
Kāññāṭṭh. s. a. Kāññāṭṭhaka,	176	Kāṭṭalāmbā, <i>f.</i> ,	193, 191
kāññāṭṭh.	59n	Kāṭṭirai, ch.,	23, 24
Kāññāṭṭh. s. a. Kāññāṭṭh.	30, 31, 32	Kāṭṭuttumbūr, s. a. Śōlapuram, 192, 194, 195, 196	
Kāññāṭṭh. <i>fort</i> ,	77	Kāṭṭikī, goddess,	189
Kāññāṭṭh. s. a. Kāññāṭṭh.	36	Kāṭṭikīputra,	50 and add.
Kāññāṭṭh. vi.,	27, 45	Kāṭṭhēm, vi.,	217, 222n
Kāññāṭṭh. s. a. Kie-pi-tha,	157, 158	Kāṭṭāṇḍalam, vi.,	1, 193n
kappa,	191	Kāvēra, <i>mythical k.</i> ,	151
Kāññāṭṭh. or Kāññāṭṭh. vi.,	58, 60, 65, 67, 71	Kāvēri, vi.,	18, 120, 121, 125, 151n
karapa,	100	Kāvi, vi.,	32n, 36, 215
karapa:—		Kāvichakravartin, m.,	191
Vāñij,	16	Kāvikā, s. a. Kāvi,	27, 28, 36, 45, 46
karapaṇāyastha,	97	Kāvyaṇḍaloka, <i>quoted</i> ,	218n
karapaṇa,	98	Kayirūr Perumāṇār, <i>Milādū ch.</i> ,	141, 142
Karavandīśvara, te.,	169, 170, 171, 175	Kāzā, vi.,	19
Karavilladāta or Karavilladāta, sur. of		Kēmajju, s. a. Kimōj,	36
Chālukya-Bhīma II.,	182	Kēraja, co.,	130, 207
Karhād, vi.,	33, 34, 215, 216, 220, 222, 224	Kēsarivarman, sur. of Rājārāja I.,	6n
Karikāla, <i>Chōla k.</i> ,	120	Kēsava, m.,	94
Kariya-Perumāl Periyāṇāyan, sur. of Nara-		Kēsavapadumā, m.,	95
siṃha,	147	Kēsava-Perumāl, te.,	1
Karka II., <i>Gujarāt Rāshtrakūṭa ch.</i> ,	35	Kēsirāja, author,	221, 227, 228
Kārkaṇa, vi.,	108, 109, 110, 111, 112n	Kēvañja, s. a. Kimōj,	27, 36, 45, 46
Kārkoṭa, <i>dy.</i> ,	223	Khabarāta, <i>dy.</i> ,	56, 58, 60
Kārlō, vi.,	47, 48, 49, 50, 51, 57, 58, 59, 60,	Khajurāhō, vi.,	30 and add., 32 and add.
62, 66, 68, 69, 70, 71n		Khālimpur, vi.,	31, 32
karmānta,	46n	Khālsi, vi.,	66
Karṇadēva, <i>Chēdi k.</i> ,	29	Khambāyat, s. a. Cambay,	26
Karṇāṭa or Karṇāṭaka, co., 75, 77, 78, 79, 84n,		khaṇḍaraksha,	87n
130n, 167, 176, 223		khaṇḍavāla,	87
Karṇāṭakasābdānūsāsana, <i>quoted</i> ,	221n, 229	Kharḍa, vi.,	215n, 220
Kārōniri, <i>Bāṇa ch.</i> ,	24, 25	Khārēpāṭan, vi.,	33, 34, 217, 223

	PAGE		PAGE
Khêṭaka, <i>s. a.</i> Kaira,	28, 29n, 36, 45	Kovāḷāla, <i>s. a.</i> Kōlār,	224
Khêṭaka, <i>s. a.</i> Mānyakhêṭa,	29, 43	Kōvalār, <i>s. a.</i> Tirukkōvalār,	133
Khottiga, <i>Rāshtrakūṭa k.</i> ,	215, 220	Kōvela-Nellūru, <i>vi.</i> ,	78
Kie-pi-tha (Kapittha), <i>s. a.</i> Sāmkāśya,	157	Kōvilāḍi, <i>vi.</i> ,	1
Kilappaluvūr, <i>vi.</i> ,	138n	Kōvilvenni, <i>vi.</i> ,	173, 175
Kilijūr, <i>vi.</i> ,	135	Kratha, <i>co.</i> ,	86
Kil-Kāśākuḍi, <i>vi.</i> ,	175	Kripāpurīśvara, <i>te.</i> ,	172
Kil-Muṭṭugūr, <i>vi.</i> ,	22n	Krishṇa, <i>god.</i> ,	45n, 59, 222, 225
Kilūr, <i>vi.</i> ,	135, 138	Krishṇa, <i>k.</i> ,	216
Kimnara,	152, 200n	Krishṇa I., <i>Rāshtrakūṭa k.</i> ,	28, 42, 199, 230, 231
Kimōj or Kīmaj, <i>vi.</i> ,	36	Krishṇa II., <i>do.</i> ,	28, 29, 33, 189n, 190n, 205n
Kīra, <i>co.</i> ,	31	Krishṇa III., <i>do.</i> ,	133, 135, 142, 194, 195, 217, 218
Kirīṭin, <i>s. a.</i> Arjuna,	86	Krishṇā, <i>vi.</i> ,	231
Kīrti-Nārāyaṇa, <i>sur. of</i> Gōvinda III.,	207	Krishṇarājadēva, <i>s. a.</i> Krishṇa III.,	217
Kīrti-Nārāyaṇa, <i>sur. of</i> Indra III.,	36	Krishṇarāya or Krishṇadēvarāya, <i>Vijaya-</i> <i>nagara k.</i> ,	18, 19, 20, 74
Kīrtipāla or Kīrtipālādēva, <i>Uttarasamudra</i> <i>ch.</i> ,	94, 157n	Krishṇavallabha, <i>s. a.</i> Krishṇa II.,	190
Kōkkala or Kōkkalla I., <i>Chēdi k.</i> ,	29, 33, 43, 88n	Krishṇavēṇī, <i>s. a.</i> Krishṇā,	20
Kōkkilāṇḍi, <i>queen of</i> Parāntaka I.,	133, 134	Krishṇavērṇā, <i>do.</i> ,	231
Kokkili, <i>E. Chalukya k.</i> ,	189	Krishṇayaśas, <i>m.</i> ,	117, 118, 119
Kōlār, <i>vi.</i> ,	224	Kṛta age,	207
Kolavennu, <i>vi.</i> ,	178, 180, 181	Kṛtavīrya, <i>mythical k.</i> ,	86
Kōlhāpur, <i>vi.</i> ,	231	Kṣhatrapa, <i>a Satrap.</i> ,	53
Kollabigaṇḍa, <i>sur. of</i> Vijayāditya IV.,	190	Kshatriya,	78
Kollāpuram, <i>vi.</i> ,	145, 146	Kshīrasvāmin, <i>author.</i> ,	44n
Kollēgāl, <i>vi.</i> ,	18, 121	Kshitipāla, <i>Kanauj k.</i> ,	30, 31, 32
Kolji-Sōlakōṇ, <i>ch.</i> ,	163, 168	Kubja-Vishṇu or -Vishṇuvardhana, <i>s. a.</i> Vish- ṇuvardhana I.,	180, 182, 189
Komera, <i>vi.</i> ,	180	Kuḍā, <i>vi.</i> ,	49, 50, 52, 55n, 57, 73
Kommadhārāpura, <i>vi.</i> ,	77	Kūḍalār (Cuddalore), <i>vi.</i> ,	161
Kōṇa or Kōṇa-Muṣṭūru, <i>vi.</i> ,	75	Kudopali, <i>vi.</i> ,	101
Kōṇakkaṇār, <i>f.</i> ,	139	Kulamāpikkaṇ Irāmadēvaṇ, <i>Munai ch.</i> ,	136
Koṇḍamudi, <i>vi.</i> ,	71n	Kulamāpikkerumāṇār, <i>do.</i> ,	137
Koṇḍapalle, <i>vi.</i> ,	19	Kulāndhī, <i>vi.</i> ,	87
Koṇḍaviṭṭu, <i>vi.</i> ,	18, 19, 20, 77	Kulāśēkhara, <i>Vaishṇava saint.</i> ,	197
Kōṇērmaikōṇḍāṇ, <i>biruda.</i> ,	15, 16	Kulāśēkharamuḍaiyār, <i>te.</i> ,	16
Koṇḍaṇivarman, <i>W. Gaṅga k.</i> ,	193	Kulbarga, <i>vi.</i> ,	73
Koṇkaṇ, <i>co.</i> ,	36, 224	Kullūka, <i>commentator.</i> ,	66
Konnūr, <i>vi.</i> ,	200n	Kulōttuṅga-Chōḍa II., <i>Chālukya-Chōḷa k.</i> ,	9
Koondurgee, <i>vi.</i> ,	212	Kulōttuṅga-Chōḷa I., <i>Chōḷa k.</i> ,	1, 4n, 7, 135, 139, 169, 170, 192
Koppam, <i>vi.</i> ,	145, 146	Kulōttuṅga-Chōḷa III., <i>do.</i> ,	6, 8, 139, 165n, 169, 171, 172, 173, 174
Kōpperuñjiṅga, <i>Pallava ch.</i> ,	161, 162, 163, 164, 165, 166, 167, 168, 169	Kulōttuṅga-Chōḷa-Chēdiyarāyaṇ, <i>Mīlāḍu ch.</i> ,	135
Kōrpāḍu, <i>field.</i> ,	143	Kulōttuṅga-Chōḷadēva, <i>Chōḷa k.</i> ,	135
Korukolannu, <i>s. a.</i> Corecolloo,	179, 191	Kulōttuṅga-māḍa, <i>coin.</i> ,	130n
Korumelli, <i>vi.</i> ,	178, 181	Kumāra, <i>s. a.</i> Skanda,	190
Kōsala, <i>co.</i> ,	103, 107		
Kōshthēśvara, <i>ch.</i> ,	230		
Kosiki, <i>f.</i> ,	61		
Koṭṭi, <i>f.</i> ,	64		
Kōval, <i>s. a.</i> Tirukkōvalār,	133, 146, 147		

	PAGE		PAGE
kumārāmātya,	159	Lalitaśūradēva, k.,	160n
Kumuda, <i>serpent</i> ,	155n	lāñchhita,	101
Kumudvatī, <i>do.</i> ,	155	languages :—	
Kuṇḍadhāni, <i>vi.</i> ,	157	Apabhraṃśa,	221
Kuṇḍadhāni-vishaya, <i>di.</i> ,	157, 159	Gujarāṭī,	226n
Kundaṇa, <i>m.</i> ,	144, 145	Kanarese,	23, 107n, 108, 111, 113, 124n, 168n, 182n, 183, 191n, 199, 200, 204, 209, 210, 211, 214, 215, 216, 217n, 218, 219n, 221, 226n
Kundāni, <i>vi.</i> ,	78	Māgadhi,	119
Kundaraga seventy, <i>di.</i> ,	209, 210, 212, 214	Mahārāshṭrī,	119, 221
Kundaṭṭe, <i>m.</i> ,	210, 214	Marāṭhī,	109
Kūṇḍi three-thousand, <i>co.</i> ,	217, 220	Pāli,	50n, 69, 221
Kundūr, <i>vi.</i> ,	212	Prākṛit,	22, 52, 56, 67, 107n, 119, 159n, 183, 185, 221
Kundūr five-hundred, <i>di.</i> ,	210, 212, 214	Sanskrit,	18, 27, 69, 75, 77n, 85, 94, 98, 103, 109, 111, 112, 116, 120, 122, 128, 145, 148, 152, 156, 159n, 167, 178, 183, 192, 197, 204, 215, 216, 221
Kunsamurroo, <i>vi.</i> ,	179, 180	Śaurasēni,	119, 221
Kuntāditya, <i>sur. of</i> Bhaṇḍanāditya,	182	Tamil,	22, 23, 24, 25, 26, 77, 108, 115, 128, 133, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148n, 161, 168n, 192, 193, 194, 195, 197
Kuppa or Kuppanṇa, <i>ch.</i> ,	200n, 214	Telugu,	75, 178, 191n, 192n
Kuppēlūr, <i>vi.</i> ,	18n	Lañjigēsara, <i>s. a.</i> Nandikēshwar,	226n
Kuppeya or Kuppēya, <i>ch.</i> ,	200, 201	Lār, <i>vi.</i> ,	98
Kura, <i>vi.</i> ,	60, 72	Lāṭa, <i>co.</i> ,	28, 36, 45, 134, 141n, 207n, 225n
Kūram, <i>vi.</i> ,	1, 133n, 194	Latalaura, <i>s. a.</i> Lattalūra,	223, 224, 225, 226
kurru, <i>a hamlet</i> ,	191n	Lāṭēśvara-maṇḍala, <i>co.</i> ,	32n
Kuru, <i>co.</i> ,	81	Lathur or Latur, <i>vi.</i> ,	225, 226
Kurukkai-kūram, <i>di.</i> ,	138, 139, 140, 142, 143, 144, 145, 146	Latta or Lāṭṭa, <i>tribe</i> ,	225n
kurupi, <i>s. a.</i> marakkāl,	144	Lattalūr or Lattalūra, <i>vi.</i> ,	208, 223, 224, 225, 226
Kuśa, <i>mythical prince</i> ,	152, 155	Lattanūr, <i>s. a.</i> Lattalūr,	223, 224, 225, 226
Kuśasthala, <i>s. a.</i> Kanauj,	30, 43	Lattoor, <i>s. a.</i> Lathur,	226
Kushana, <i>tribe</i> ,	118	Laukika reckoning,	210
Kusumāyudha, <i>m.</i> ,	183, 191	Lāvanyavatī, <i>queen of</i> Guṇasāgara II.,	86
kūṭaka,	222n	Leyden grant,	120, 193
kūṭa-sāsana, <i>a forged charter</i> ,	157, 158	liṅga,	200n, 209
Kuttālam, <i>vi.</i> ,	12, 13	lion banner,	136
Kuttalanātha, <i>te.</i> ,	13, 13	Lōkāditya, <i>ch.</i> ,	211
		Lōkamahādēvi, <i>queen of</i> Chālukya-Bhīma II.,	190
		Lōkamahādēvi, <i>sur. of</i> Dantiśakti-Viṭaṅki,	25n, 144, 145
		Lōvabikki, <i>Chōḷa prince</i> ,	181, 190
		Lucknow Museum,	98, 98, 155, 157n
		Luiz, <i>Franciscan friar</i> ,	18, 19
		Lunsadi, <i>vi.</i> ,	62n

L

Iagna :—

Mithuna,	112, 113
Lakkhā Maṇḍal, <i>te.</i> ,	155
Lakshmaṇarāja, <i>Kalachuri k.</i> ,	86
Lakshmi, <i>goddess</i> ,	28, 44, 152, 162n, 199
Lakshmi, <i>queen of</i> Jagattunga II.,	29, 43
Lakshmidēva II., <i>Raṭṭa ch.</i> ,	217, 219, 223, 227
Lakshminārāyana, <i>te.</i> ,	1
Lakshmivallabha, <i>sur. of</i> Amoghavarsha I.,	207
Lalitāditya, <i>Kārkōṭa k.</i> ,	223
Lalitakirti, <i>title of</i> Jaina teachers,	110

	PAGE		PAGE
M			
mā, <i>measure of land</i> ,	143	Mahākāla, <i>te.</i> ,	30, 226n
Māchanabhaṭṭa, <i>m.</i> ,	85	mahākshapatalika,	91, 97
māḍa, <i>a half pagoda</i> ,	76, 130n	Mahākūṭa, <i>vi.</i> ,	182, 210
māḍai, <i>s. a. māḍa</i> ,	128, 130, 131, 132	Mahālingasvāmin, <i>te.</i> ,	164
mādam,	15n, 16n	mahāmahantaka,	87
Madanādēvi, <i>queen of Guṇasāgara I.</i> ,	86	mahāmahattara,	183n
Madanapāla, <i>Pāla k.</i> ,	70	mahāmapāḍalēśvara,	76, 77, 79, 115
mādēvi, <i>measure</i> ,	136, 137	mahāpāndhākulika,	87
Māḍha, <i>m.</i> ,	87	mahāpradhāna,	163
Mādhava, <i>m.</i> ,	98	mahāpramātara,	159n, 160
Mādhava, <i>W. Gaṅga k.</i> ,	192, 193	mahāpratihāra,	91
Mādhavavarman, <i>Kaliṅga ch.</i> ,	100	mahāpurōhita,	97
Mādhavayya, <i>m.</i> ,	203, 208	mahāpurusha,	119
Madhuban, <i>vi.</i> ,	155	Mahara, <i>s. a. Makara</i> ,	161, 163
Madhukēśvara, <i>te.</i> ,	226n	mahārāja or mahārāya, 23, 85, 142, 143, 144, 155, 158, 159, 160, 167	
Madhurā (Madura), <i>vi.</i> ,	76, 121, 125, 133, 141	mahārājādhirāja, 27, 45, 80, 86, 88, 94, 98, 159, 190, 201, 208, 213, 230	
Madhurāntaka, <i>sur. of Pottapi-Chōḷa</i> ,	121, 122, 125, 143	mahārājaputra,	87
Madhurāntaka-Pottapi-Chōḍasiddhi, <i>Telugu- Chōḍa ch.</i> ,	121n	Mahārāja-Śarva, <i>sur. of Amoghavarsha I.</i> ,	36
Madhurāntaka-Pottapi-Chōḷa, <i>ch.</i> ,	121	Mahārājasimha, <i>s. a. Kōpperuñjīga</i> ,	167
Madhyadēsa, <i>co.</i> ,	94n, 207n	mahārājūi,	87
Madirai, <i>s. a. Madhurā</i> ,	1, 133, 134, 141, 142	mahārātha, <i>title</i> ,	49, 50
Mādirāja, <i>Sāḷva ch.</i> ,	83	mahārāthi, <i>do.</i> ,	49, 50
Madra, <i>co.</i> ,	31	mahārāthi, <i>do.</i> ,	49, 50, 51, 61
Madras Museum plates,	23, 166n	mahārāthini, <i>do.</i> ,	50
Madurai, <i>s. a. Madhurā</i> ,	6, 172, 173, 174	mahārthasāsānika,	95
Madurāntakachaturvēdimangalam, <i>sur. of Tirukkōvalūr</i> ,	138, 146	mahāsādhanika,	91, 97
Madurāntakan-māḍai, <i>coin</i> ,	130n	mahāsāmanta,	50, 159, 160, 223
maga (mārga),	66	Mahāsāṅghika,	59, 60, 61, 65, 72
Magadha, <i>co.</i> ,	207	mahāsāndhivigrahika,	37
Māgaral, <i>vi.</i> ,	174, 175	Mahāsēnaguptādēvi, <i>queen of Ādityavardhana</i> ,	159
Magōdayarpaṭṭanam, <i>s. a. Oranganore</i> ,	197, 198	Mahāsiva-Tīvararāja, <i>Kōśala ch.</i> ,	103, 107
Mahābhārata, <i>quoted</i> ,	125n	mahāśrēsthin,	91
Mahābhavagupta II., <i>Trikaliṅga k.</i> ,	101	mahāsthāna, <i>a holy place</i> ,	36
mahābhōja,	50	mahattama,	91
Mahābōdhi, <i>te.</i> ,	33n	mahattara,	45
mahādāna,	84n	Mahāvali-Bāparasa, <i>Bāṇa k.</i> ,	23
mahādānika,	87	Mahāvamsa, <i>quoted</i> ,	163
Mahādēva, <i>s. a. Śiva</i> , 135, 136, 137, 140, 142, 202, 210, 214		Mahāvastu, <i>do.</i> ,	69
Mahādēvaḍi, <i>queen of Rājāditya</i> ,	134	Mahāyāna, <i>sect</i> ,	119
Mahādēvapaka (Mahādēva), <i>m.</i> ,	52	Mahēndra, <i>s. a. Indra</i> ,	83, 190
Mahādēvayya, <i>m.</i> ,	23, 45	Mahēndramangalam, <i>vi.</i> ,	115, 116
mahādēvi,	159	Mahēndrapāla, <i>Kanauj k.</i> ,	30
mahājana,	202, 204, 208	Mahēndravarmān I., <i>Pallava k.</i> ,	149
mahājaya, <i>titihī</i> ,		Mahēndravikrama, <i>ch.</i> ,	22, 23
		Mahēśvara, <i>commentator</i> ,	46n
		Mahēśvara, <i>s. a. Śiva</i> ,	86, 94, 159, 190
		Mahēśvara, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144,	

	PAGE		PAGE
Mahi, <i>ri.</i> ,	36	Maṅgalagiri, <i>vi.</i> ,	17, 19
Mahārīpātaka, <i>vi.</i> ,	87	Maṅgalēsa, <i>W. Chalukya k.</i> ,	210
Mahichanda, <i>m.</i> ,	95	Maṅgi, <i>k.</i> ,	218
Mahika, <i>m.</i> ,	95	Maṅgi-Yuvarāja, <i>E. Chalukya k.</i> ,	184, 189
Mahipāla, <i>s. a. Kshitipāla</i> ,	30, 32	Maṅgu, <i>s. a. Śāluva-Maṅgu</i> ,	76
Mahīśāsaka,	60	Māpikkattār, <i>m.</i> ,	139
Mahōdaya, <i>s. a. Kanauj</i> ,	30, 31, 32, 43, 155	Manjera, <i>ri.</i> ,	226
Mahuāli, <i>vi.</i> ,	87	Māñji, <i>ri.</i> ,	116
Maisūr (Mysore), <i>co.</i> ,	18	Manma-Gaṇḍagōpāla, <i>Telugu-Chōḍa ch.</i> ,	120, 130
maitravarupa,	46	Manmasiddha or Manmasiddhi, <i>do.</i> ,	121, 122, 125, 126, 152, 155
majjādi, <i>s. a. maryādā</i> ,	196	Maṇṇārguḍi, <i>vi.</i> ,	11, 176, 177
Makara or Magara, <i>co.</i> ,	161, 162	Manōhari, <i>Talaing k.</i> ,	197
makara crest,	136	Mantrawāḍi, <i>vi.</i> ,	198, 199, 204, 210
makāḷa-santāna,	112	Maṇṭūr, <i>vi.</i> ,	218, 223, 227
Malabar, <i>co.</i> ,	15, 197	Manu, <i>rishi</i> ,	66, 120, 122, 125, 151, 164
Malāḍu, <i>s. a. Milāḍu</i> ,	135, 138, 139, 142, 143, 144, 147	Manuma-Gaṇḍagōpālādēva-Chōḍamahārāja, <i>s. a. Manma-Gaṇḍagōpāla</i> ,	129
Malaimaṇḍalam, <i>s. a. Malabar</i> ,	197, 198	Mānyakhēṭa, <i>s. a. Mālkhēḍ</i> ,	27, 28, 29, 45
Malaināḍu or Malaiyanāḍu, <i>s. a. Milāḍu</i> ,	135	marakkāl, <i>measure</i> ,	144n
Malaiyakula, <i>family</i> ,	135, 136	Mārasimha I., <i>W. Gaṅga k.</i> ,	193, 195
Malaiyamān, <i>sur. of Milāḍu chiefs</i> ,	135	Mārasimha II., <i>do.</i> ,	108
Malaiyāpa-orraichohēvaga, <i>regiment</i> ,	142	Marāṭha, <i>co.</i> ,	50, 109
Mālatimādhava, <i>drama</i> ,	30n	Marattulān, <i>field</i> ,	143
Mālava, <i>co.</i> ,	77, 207	Mārarvarman Parākrama-Pāṇḍya, <i>Pāṇḍya k.</i> ,	11, 12, 17
Malayālam (Malabar),	142n	Mārarvarman Sundara-Pāṇḍya I., <i>do.</i> ,	163
Malaya-nāḍu, <i>di.</i> ,	129	Mārarvarman Sundara-Pāṇḍya III., <i>do.</i> ,	15, 16, 17
Malda, <i>m.</i> ,	214	Mārāyaṇ Paluvūr Nakkaṇ, <i>ch.</i> ,	138
Mālhē, <i>m.</i> ,	87	Mārjavāḍa, <i>di.</i> ,	75, 85
Māliya, <i>vi.</i> ,	62n, 66	Mārkaṇḍēyapurāṇa, <i>quoted</i> ,	125n
Mālkhēḍ, <i>vi.</i> ,	189n, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224, 225, 227, 231n	Māryādāsāgaradēva, <i>sur. of Vyāsa</i> ,	86, 87
Malla, <i>s. a. Yuddhamalla II.</i> ,	161	Masulipatam, <i>vi.</i> ,	77, 180, 181
Malla II., <i>Velanāḍu ch.</i> ,	149	maṭha,	207n
Mallāmbā or Mallāmbikā, <i>queen of Guṇḍa III.</i> ,	77, 84	Mathurā, <i>vi.</i> ,	52n, 57
Mallidēvi, <i>queen of Vira-Tiṇmarāja-Oḍeyaru</i> ,	114	Matsya, <i>co.</i> ,	31, 184
Mallikārjuna, <i>Vijayanagara k.</i> ,	79n	mattar, <i>measure of land</i> ,	202, 214
Mālūr, <i>vi.</i> ,	77	Mattilināḍu, <i>di.</i> ,	179n
Māmāḍa, <i>s. a. Māmāla</i> ,	65	Mauṛya, <i>family</i> ,	118
Māmāla or Māmāla, <i>s. a. Māwal</i> ,	65, 66	Māvaṇḍūr, <i>s. a. Māmaṇḍūr</i> ,	115, 116
Māmaṇḍūr, <i>vi.</i> ,	115n	Māwal or Māul, <i>di.</i> ,	61, 63
Mamdooroo, <i>vi.</i> ,	180	Mayidavōlu, <i>vi.</i> ,	185
Mānāṅka, <i>Rāshtrakūṭa ch.</i> ,	216	Mayindāḍiya, <i>s. a. Mahēndravikrama</i> ,	23
Mānāvalōka, <i>sur. of Vijayāditya</i> ,	230	Mayūra, <i>poet</i> ,	150n
Mānavira, <i>Telugu-Chōḍa ch.</i> ,	128, 129, 130, 131	Medegulla, <i>s. a. Mudkal</i> ,	19
Mañchar, <i>vi.</i> ,	183	Mēdinimisara ^o or Mēdinimisavaragṇḍa, <i>biruda</i> ,	77n, 79 and add.
Maṇḍadoṛṛu, <i>s. a. Mamdooroo</i> ,	180	Mēlūr-nāḍu, <i>di.</i> ,	133, 138
maṇḍala, <i>a district</i> ,	29n, 44, 45	Meṅkiḍḍaka, <i>vi.</i> ,	104, 107
Mandara, <i>mo.</i> ,	42, 84	Mōru, <i>mo.</i> ,	42, 84, 120, 125, 151, 215, 218
Mandava (Māṇḍavya),	50n		

	PAGE
Meypporupāyānār, <i>Śaiva devotee</i> , . . .	138n
Milādāmānikkam, <i>sur. of Nepwālī</i> , . . .	143
Milāḍuḍaiyān, <i>a lord of Milāḍu</i> , . . .	135
Milāḍu two-thousand, <i>di.</i> , 135, 136, 138, 140,	
141, 145, 146, 147	
Misaragāṇḍa, <i>biruda</i> ,	76, 84
Mitadeva, <i>ch.</i> ,	50, 61
Mitadevanaka (Mitradēva), <i>ch.</i> ,	56
Mōhana-Murāri, <i>sur. of Nṛsiṃharāya</i> ,	84
Monghyr, <i>vi.</i> ,	98
Moni, <i>Śaiva teacher</i> ,	202
months, lunar :—	
Āshāḍha,	19, 20, 230
Āsvina,	162n
Bhādrapada,	75, 85
Chaitra,	7n, 10, 87, 88
Jyāishṭha or Jyēshṭha, 2, 28, 45, 104, 107,	
204, 205, 208, 210	
Jyāishṭha, the second,	86, 88
Māgha,	7n
Mārgaśīrsha,	157, 160
Pauṣa,	87, 88
Phālguna,	7n, 95, 111, 112, 113, 114
Vaiśākha,	2, 5, 98, 200, 202
months, solar :—	
Āṇi,	16, 129, 131
Āvāṇi,	16
Kārttigai or Kāttigai,	10, 115, 163n
Sittirai,	5
Moon, race of the, 28, 42, 83, 86, 103, 109, 111, 114, 225	
Mūḍabidure, <i>vi.</i> ,	110n
Mudgagiri, <i>s. a. Monghyr</i> ,	98
Muḍivalaṅgiṇān, <i>god</i> ,	132
Mudkal, <i>vi.</i> ,	19
Mugai-nāḍu, <i>di.</i> ,	192
Mugdhatunga, <i>sur. of Śaṅkaragana II.</i> ,	86
Muḥammad II., <i>Bahmanī k.</i> ,	77
Mukula, <i>s. a. Chellakōtana</i> ,	211n
Mukundamālā, <i>poem</i> ,	197, 198n
Mūlasthāna, <i>te.</i> ,	202
Mūlāsvara, <i>te.</i> ,	169
Mulgund, <i>vi.</i> ,	200n
Multāi, <i>vi.</i> ,	216
Mupai or Mupaiṇṇādi, <i>di.</i> ,	133, 136, 137
Mupaiyayariyān, <i>a chief of Mupai</i> ,	136, 137
Mundagōḍi, <i>vi.</i> ,	212
Mungir, <i>vi.</i> ,	33
muni=7,	20
Muppiḍi or Muppiḍi-Nāyaka, <i>ch.</i> , 128, 129,	
130, 131, 132	

	PAGE
Mūruṇāyaraṅḍa, <i>biruda</i> ,	84
Mushṭūru, <i>vi.</i> ,	75
Musi, <i>vi.</i> ,	231
Muttagi, <i>vi.</i> ,	225n
Muṭṭiyampākka, <i>vi.</i> ,	152, 155
Myinpagān, <i>vi.</i> ,	197

N

Nāḍupūru, <i>vi.</i> ,	56
Nāgadēva, <i>m.</i> ,	202
Nāgalā, <i>s. a. Nāgamāmbā</i> ,	13
Nāgamāmbā or Nāgāmbikā, <i>Tuḷuva queen</i> ,	18
Nāgamārya, <i>m.</i> ,	23, 45, 46
Nagara, <i>vi.</i> ,	87
Nāgarjuna, <i>m.</i> ,	208
Nāgavarman, <i>Kanarese poet</i> ,	213n
Nāgavarman, <i>m.</i> ,	47
Nagercoil, <i>vi.</i> ,	12
Nāgpur, <i>vi.</i> ,	103
nabān (lahān),	226n
Nahapāna, <i>Kshatrapa</i> ,	56, 58, 60
Nair, <i>tribe</i> ,	142n
nakshatras :—	
Anurādhā,	13
Ārdrā,	2, 3, 9, 10
Āsvini,	11, 171, 172, 175, 177
Chitrā,	5, 176
Hasta,	2, 4, 5, 6, 11, 12, 28, 45, 173, 174
Kṛttikā,	14, 115, 169
Maghā,	3, 4, 10, 174
Mṛigaśīrsha,	12
Māla,	173
Punarvasu,	4, 170
Pūrvāshāḍhā,	173, 177
Pushya or Pushyaka,	6, 112, 113, 114
Rōvati,	14, 15, 164, 165
Rōhiṇī,	1, 173, 176, 177
Śatabhishaj,	2, 3, 12, 164, 172, 174, 175
Śravaṇa,	2, 177
Śravishṭhā,	175
Svāti,	14, 15, 16
Uttarā,	2
Uttarābhadrapadā,	9n, 11, 16, 165, 172
Uttaraphalgunī,	9n, 170
Uttarāshāḍhā,	3, 13, 170, 175, 177
Viśākha,	170, 171, 177
nal-babā,	77
nālgāmupḍu,	214
nāli, <i>measure</i> ,	136, 144

	PAGE		PAGE
Nālasiddhi, <i>Telugu-Chōḷa</i> ch.,	122, 127, 129, 148, 152	Narsenaque, s. a. Narasa-Nāyaka,	78, 81
Nālasiddhi, <i>do.</i> ,	129	Narsinga, Narsymga or Narsymgna, s. a.	
nālu or nāluka, <i>measure of land</i> ,	87	Nṛsiṃharāya,	19, 73, 79
nalva, <i>do.</i> ,	87	Narven, <i>vi.</i> ,	226n
Nāpādēśi-Viṇṇagar, <i>te.</i> ,	197, 198	Nāsik, <i>vi.</i> ,	46n, 47, 49, 56, 57, 58, 59, 60, 63, 66 and add., 67, 68, 69, 70, 71, 72, 221
Nānārtharatnākara, <i>Kanarese lexicon</i> ,	228	Natarāja, s. a. Śiva,	119
Nanda, <i>m.</i> ,	54	Naṭeśa, <i>do.</i> ,	138a
Nandupaka (Nanda), <i>m.</i> ,	50	Nausārī, <i>vi.</i> ,	32, 215
Nandaprabhāñjanavarman, <i>Kalinga k.</i> ,	101	Nāvalūra, <i>sur. of</i> Sundaramūrti,	133
Nandi, s. a. Nandivikramavarman,	196	Navasāhasāṅkacarita, <i>quoted</i> ,	217n
Nandika, <i>m.</i> ,	64	Nawalgund, <i>vi.</i> ,	202
Nandi-Kampa, s. a. Vijaya-Kampe,	196	nāyaka, a <i>general</i> ,	123, 131
Nandikampisvara, <i>te.</i> ,	192, 195, 196, 197	Nellore, <i>vi.</i> ,	130, 152
Nandikēśwari, <i>vi.</i> ,	226n	Nellūr, s. a. Nellore,	152, 155
Nandin, <i>Śiva's bull</i> ,	209	Nemali, <i>vi.</i> ,	138
Nandini, <i>the celestial con.</i> ,	151n	Nemali, s. a. Nemali,	138, 143, 144
Nāṅgai-Kulamāpikkattār, <i>quest.</i> ,	141	Nepāl, <i>co.</i> ,	65
Nanna, <i>Boṭṭa ch.</i> ,	218	Nerūr, <i>vi.</i> ,	35
Nannadēva, <i>ch.</i> ,	103, 107	Nēsargi, <i>vi.</i> ,	219
Nannan Korraṇ, <i>m.</i> ,	140	Nēṭṭibhāṭṭa, <i>ch.</i> ,	100, 101
Nannarāja, <i>ch.</i> ,	104, 107	nibandha, an <i>endowment</i> ,	63
Nārada, <i>ṛishi</i> ,	120	Niḍagundi, <i>vi.</i> ,	200n, 208, 209, 212
Naragalla, <i>vi.</i> ,	78n	Niḍagundage, s. a. Niḍagundi,	207
Naragoṇḍa, <i>vi.</i> ,	78	Niḍagundage twelve, <i>di.</i> ,	209, 210, 212, 214
Narasa, s. a. Narasiṃha,	18, 19	nigamaśabhā,	50
Narasa- or Narasappa-Nāyaka, s. a. Nara-		nikāya, a <i>religious corporation</i> ,	65
siṃha,	78, 79, 80	Nikhatigrāma, <i>vi.</i> ,	87
Narasarārupēṭa, <i>vi.</i> ,	129	Nilagaṅga or Nilagaṅgaraiyai, <i>Pallava ch.</i> ,	166
Narasiṃha, <i>m.</i> ,	85	Nilagaṅgarayar, <i>ch.</i> ,	165n
Narasiṃha, <i>Milādū ch.</i> ,	147	Niḷgund, <i>vi.</i> ,	202, 203, 204, 205n, 206n, 207n, 208n, 210, 214, 220, 223, 225
Narasiṃha, <i>Muṇai ch.</i> ,	136	Nimbichhara-Bammayya, <i>m.</i> ,	203
Narasiṃha, <i>Tuluva ch.</i> ,	19, 75, 76n, 78, 79, 80	Nimbō, <i>m.</i> ,	37
Narasiṃha II., <i>Hoysaḷa k.</i> ,	24, 161, 162, 163, 164, 167n	niru-gal, a <i>set-up stone</i> ,	200
Nārasimha, s. a. Viṣṇu,	226	Nirupama, <i>sur. of</i> Dhruva,	28, 42, 207, 231n
Narasiṃharāya, s. a. Immaḍi-Nṛsiṃharāya,	80n	Nissaramiji (P), <i>m.</i> ,	184
Narasiṃhavarman I., <i>Milādū ch.</i> ,	135, 136	Nitimarga, <i>sur. of</i> W. Gaṅga kings,	199
Narasiṃhavarman II., <i>do.</i> ,	135, 145, 146, 147	Nitya-Kandarpa, <i>sur. of</i> Gōvinda IV.,	36, 45
Narasīṅgaiyadēva, s. a. Nṛsiṃharāya,	79n and add.	Nityavarsha, <i>sur. of</i> Indra III.,	27, 34, 45
Narasīṅgarāya or Narasiṃha, s. a. Nṛsiṃha-		niyama,	43
rāya,	75, 77, 80	Nolamba, s. a. Pallava,	151
Naravardhana, <i>Kanauj k.</i> ,	158	Nolamba, s. a. Nolamba	23
Nārāyaṇa, s. a. Viṣṇu,	45, 94, 189, 193, 194, 218	Nolambavādī, <i>di.</i> ,	24, 181
Nārāyaṇapāla, <i>Pāla k.</i> ,	31	Nowgong, <i>vi.</i> ,	100
Naregal or Narigal, <i>vi.</i> ,	200n	Nṛparudra, <i>prince</i> ,	184
Narēndramrigarāja, <i>sur. of</i> Vijayāditya II.,	184, 189	Nṛpati-Trinētra, <i>sur. of</i> Gōvinda IV.,	36, 45
Narēndrēśvara, <i>te.</i> ,	103n	Nṛpatuṅga, <i>sur. of</i> Amoghavarsha I.,	203
		Nṛsiṃha, <i>god</i> ,	84
		Nṛsiṃharāya, <i>Sōḷuva ch.</i> ,	75, 76, 77, 78, 79, 80, 84

	PAGE	PAGE
Nunes or Nuniz, Fernão.	19, 20, 78, 79, 80	panam, coin, 128, 132
O		Panasôge, s. a. Hanasôge, 110
Odâ, 201n		Pañchaghantânâda, <i>biruda</i> , 76, 84
Odâi, s. a. Orissa, 77		Pañchâla or Pâñchâla, co., 31, 32, 77
Odigair or Odegary, s. a. Udayagiri, 19 and add.		pañcha-mahâsabda, 84n, 106, 107, 168n, 208, 220
Okhañakiya, 50, 61		Pañchanadêśvara, <i>te</i> , 25n
Ôpavala, s. a. Unavala, 99		Pañchanedi-Vâpar, <i>sur. of Nîlagangarayar</i> , 165n
Ôpavala-pathaka, <i>di</i> , 99		pañcha pradhânâh, <i>the five ministers</i> , 185
Oonowlee, <i>vi</i> , 99n		Pândala-pattalâ, <i>di</i> , 98
Orissa, co., 19, 20, 77		Pâñdarânga, <i>ch</i> , 184
Orriyûr-Âdiyan, <i>ch</i> , 195		Pâñdava, <i>family</i> , 108
ottasâmam (ardhayâma), 132n		Pâñdavas, the five, 84
ottu, 17		pañdita, 87, 94, 95
P		Pañdita-Śôla, <i>sur. of Râjendra-Chôla I.</i> , 138n
Pabhâsa, s. a. Prabhâsa, 58		Pañdita-Śôla-terinda-villigal, <i>regiment</i> , 138n
Pâchobûr, <i>vi</i> , 161, 168		Pâñdu, <i>mythical k.</i> , 103, 107
Paçmâkalûru, <i>vi</i> , 181		Pâñdukêśvar, <i>vi</i> , 160n
Padea Rao, <i>Vijayanagara k.</i> , 78		Pâñdya, <i>ch</i> , 112, 113, 114, 115
Padmapura, <i>vi</i> , 30n		Pâñdya, co., 10, 76, 84, 121, 125, 163,
Padumê, <i>m</i> , 95n		167, 172, 173, 174
Paduminikâ, <i>f</i> , 57		Pâñdyaka or Pâñdyakadêvi, <i>queen</i> , 112, 113, 114
Paduvûr-kôttam, <i>di</i> , 192, 194		Pâñdyakadêvi, <i>queen of Vira-Timmarâja</i> -
Paes, Domingos, 19		Odeyaru, 114
Pagân, <i>vi</i> , 197		Pâñdyarâya, s. a. Vira-Pâñdya, 109, 111
Pagâppidûgu, <i>sur. of Mahêndravarmân I.</i> , 149		Pañgala-nâdu, <i>di</i> , 192, 194, 195
Paithan, <i>vi</i> , 183, 215, 226, 230, 231n		Pâñiui, <i>quoted</i> , 125n
Pâiyalachohhinâmamâlâ, <i>quoted</i> , 229		Pañrutti, <i>vi</i> , 162
Paiyyûr, <i>vi</i> , 120, 131, 132n		Pañra-râshtra, <i>di</i> , 152, 155
Paiyyûr-kôttam, <i>di</i> , 129, 131		Pânumgal, s. a. Hânumgal, 212
Pâla, <i>dy</i> , 31		Pânumgal five-hundred, <i>di</i> , 224
palam, <i>weight</i> , 135		Parakêsarivarmân, <i>Chôla k.</i> , 25, 140, 141
Pâlampur, <i>vi</i> , 58		Parakêsarivarmân, <i>sur. of Chôla kings</i> , 1, 5,
Palasiga, s. a. Halst, 213		7, 8, 133, 134, 135, 137, 138, 141, 142,
Palasiga-vishaya, <i>di</i> , 212		145, 146, 170, 171, 174
Palee, <i>vi</i> , 99		Parâkramabâhu, <i>Ceylon prince</i> , 163, 168
Pâli, s. a. Palee, 99		Parâkramabâhu I., <i>Ceylon k.</i> , 163
pâlidhvaja, <i>banner</i> , 44, 208, 227		Parâkramabâhu II., <i>do</i> , 163
Palivela, <i>vi</i> , 129		paramabhattâraka, 27, 45, 86, 94, 98, 159, 190
Pallava, <i>dy</i> , 24, 25, 68, 133, 135, 149, 163, 164, 167		paramabhattârikâ, 159
Pallavamârâyan (Pallavamahârâja), s. a. Śatti, 25, 26		paramêśvara, 27, 45, 86, 94, 98, 190, 201,
Pallava-Perkadaiyâr, <i>ch</i> , 25		208, 213, 230
pallichchandam, 116		Paramêśvaramahâgalam, <i>sur. of Vâlûr</i> , 192n
Paļuvûr, <i>vi</i> , 138n		Parântaka I., <i>Chôla k.</i> , 1, 6, 133, 138n,
Pammavâ, <i>f</i> , 132		141, 142, 192n, 194
Pampa, <i>Kanarese poet</i> , 33, 34		parihâra, a <i>privilege</i> , 66, 67
		pârijâta, <i>tree</i> , 83
		Pârijâtâpaharânam, <i>Telugu poem</i> , 78
		Parishîtaparvan, <i>quoted</i> , 223
		Parmâñi or Parmâñi, s. a. Vikramâditya
		VI., 130n
		2 x 2

	PAGE		PAGE
parru, <i>a division</i> ,	116	Piṭhāpuram, <i>vi.</i> ,	149n, 180, 181
Pāṣipura, <i>s. a.</i> Tiruppāṣūr,	122, 123, 128	Podavākkam, <i>s. a.</i> Pondavākkam,	129
Paśupati, <i>s. a.</i> Śiva,	94	Pōliyūr-nādu, <i>di.</i> ,	25, 26
Pāṭaḷi, <i>s. a.</i> Pāṭṇa,	224	Pōlūr, <i>vi.</i> ,	25, 192
Pāṭaliputra, <i>do.</i> ,	224	Pondaipākkam, <i>s. a.</i> Pondavākkam,	129, 132
pāṭal <i>or</i> pāṭil,	183, 191n, 222n	Pondavākkam, <i>vi.</i> ,	129
pathaka, <i>a district</i> ,	66	Ponduva, <i>vi.</i> ,	160
Pathāri, <i>vi.</i> ,	94n	Ponṇambalam, <i>s. a.</i> Chidambaram,	161, 162, 163
Paṭhyār, <i>vi.</i> ,	116, 117, 118	Ponṇēri, <i>vi.</i> ,	129
pāṭikū,	87	Ponṇi, <i>s. a.</i> Kāvēri,	120
Pāṭṇa, <i>vi.</i> ,	224	Poona, <i>vi.</i> ,	61
paṭṭa, <i>a pontificate</i> ,	113n	Portuguese,	19
paṭṭabandha,	27, 131	Pāṣala, <i>s. a.</i> Hoysala,	162, 163
Paṭṭadakal, <i>vi.</i> ,	204	Pōtāchavaḍa, <i>vi.</i> ,	63
paṭṭakila,	183	Potapi, <i>vi.</i> ,	121n
Paṭṭavarḍlika <i>or</i> Paṭṭavardhini, <i>family</i> , 179, 182, 191		Pottapi <i>or</i> Pottappi, <i>s. a.</i> Potapi,	121, 122n, 123
paṭṭāla, <i>s. a.</i> paṭṭakila,	183	Pottapi-Chōla, <i>Telugu-Chōḍa ch.</i> ,	121, 122, 125, 143
peacock crest,	136	Poygai, <i>vi.</i> ,	149, 161
Pedda-Kaluchuvubarru, <i>s. a.</i> Kaluchumbarru, 179, 192		Prabhākaravardhana, <i>Kanauj k.</i> ,	169
Pehoa, <i>vi.</i> ,	30	Prabhāsa, <i>vi.</i> ,	68
peḷ-ḍore, <i>a great river</i> ,	200n	Prābhava, <i>s. a.</i> Prabhava,	116
Penakoṇḍa, <i>vi.</i> ,	19	Prabhūta-varsha, <i>sur. of Rāshṭrakūṭa kings</i> , 35, 44, 207, 230	
Penugaram, <i>vi.</i> ,	23, 24	Prāgjyōtiṣa, <i>co.</i> ,	77
Pennai, <i>s. a.</i> Southern Pennaiyāru,	189	Prahasitaśarman, <i>m.</i> ,	94
Penugonḍa <i>or</i> Penugonḍa, <i>s. a.</i> Penakoṇḍa, 75n, 77, 78, 80		pramātāra,	169
Penugonḍa-chakrēśvara, <i>Virūda</i> ,	19	prapā, <i>a trough, a cistern</i> ,	46
Penugonḍa-mahārāja, <i>co.</i> ,	75, 85	prāpti, <i>revenue</i> ,	132
pergaḍa, <i>s. a.</i> preggāḍa,	25n, 214	praśasti,	211, 214, 218, 219, 220
Pergunda, <i>s. a.</i> Penakoṇḍa,	19	praśāstri, <i>s. a.</i> maitravaruna,	46n
pēriḷamai, <i>measure</i> ,	143, 144	Pratāpachakravartin, <i>sur. of Hoysala kings</i> , 163, 163	
Periyapurāṇam, <i>quoted</i> ,	24, 132, 135, 136	Pratāparudra, <i>Kākatya k.</i> ,	128, 129, 130, 131
Periyaśevalai, <i>vi.</i> ,	133	prathama-tṛitīyā, <i>tiṭhi</i> ,	98n
perkaḍai, <i>s. a.</i> preggāḍa,	25n	prātirāja (pratirāja),	204
Perumāḷ, <i>s. a.</i> Śiva,	139, 142	Pratishṭhāna, <i>s. a.</i> Paṭṭhaṇ,	226
Perumāḷ, <i>s. a.</i> Viṣṇu,	149, 193, 194	pratiśraya,	46
Perumāḷ, <i>sur. of Pāṇḍya kings</i> ,	15, 16	pratyāya,	62
Perumāḷ, <i>sur. of Vēṇāḍudaiyān</i> ,	166	pravaṇikara,	98
Perumāḷ-Arulāṇātha, <i>s. a.</i> Arulāḷa-Perumāḷ,	131	pravaras :—	
Perumāḷpillai, <i>sur. of Śōlakōṇ</i> ,	166	Āvatsāra,	98
Perumāḷtādar, <i>s. a.</i> Viṣṇudāsa,	128, 132	Kāśyapa,	98
Petlad, <i>vi.</i> ,	26	Naidhruva,	98
piechi, <i>flower</i> ,	132	Prayāga (Allahabad), <i>vi.</i> ,	208n
pidugu, <i>a thunderbolt</i> ,	149	preggaḍa, <i>a minister</i> ,	25n
Piḍuvārāditya, <i>sur. of Malla II.</i> ,	149	Prithivigaṅgaraiyar, <i>W. Gaṅga ch.</i> ,	192, 193
Piḷḷai Śōlakōṇār Āḷiyār, <i>s. a.</i> Śōlakōṇ,	166	Prithivipati I., <i>W. Gaṅga k.</i> ,	193
Piṇayārya, <i>m.</i> ,	85	Prithivipati II., <i>do.</i> ,	120, 195
Piṇḍigaṅgaraiyan, <i>s. a.</i> Prithivigaṅgaraiyan,	196	Prithivivarmadēva, <i>E. Gaṅga k.</i> ,	101

	PAGE		PAGE
Prithvidēva III., <i>Ratnapura k.</i> ,	182n	Rājādityēśvara, <i>s. a.</i> Bhaktajanēśvara,	133
Prithvigaṅgaraiyar, <i>s. a.</i> Kannaradēva-Prith-		Rāja- or Rāya-Gaṇḍagōpāla, <i>sur. of</i> Maṇma-	
vigaṅgaraiyar,	197	Gaṇḍagōpāla,	123, 130
Prithviśvara, <i>Telandāṇḍu ch.</i> ,	149n	Rājagōpāla-Perumāḷ, <i>te.</i> ,	176
Prithvirallabha, <i>biruda</i> ,	27, 45	Rājakesarivarman, <i>sur. of Chōla kings</i> , 2, 6, 7,	
Pritivīyarāja, <i>ch.</i> ,	182		9, 170
Pudukkōṭṭai, <i>vi.</i> ,	162	Rājakesarivarman, <i>sur. of Rājēndradēva</i> ,	7n
Pūddūr, <i>vi.</i> ,	24	Rājamahēndra, <i>sur. of</i> Amma I.,	190
Pugalvippavarganḍa, <i>s. a.</i> Rājādittan Pugal-		Rājamahēndri (Rajahundry), <i>vi.</i> ,	77
vippavarganḍa,	134	Rājamalla, <i>W. Gaṅga k.</i> ,	23
Pugāma, <i>s. a.</i> Paḡan,	197	Rājamārtanḍa, <i>sur. of</i> Chālukya-Bhīma II.,	182
Pūtipa, <i>vi.</i> ,	100	Rājamārtanḍa, <i>sur. of</i> Indra III.,	43n
Pukkam, <i>s. a.</i> Paḡan,	187, 198	Rājamayya, <i>s. a.</i> Rājavarman,	181, 190
Pulakēsin II., <i>W. Chalukya k.</i> ,	178, 189, 212	rājaparamēśvara,	50
puḷḷi,	109n	Rājaputra, <i>Kalachuri k.</i> ,	86, 88
Puḷamāyi, <i>Andhra k.</i> ,	51, 221	Rājarāja I., <i>Chōla k.</i> , 6, 25n, 134, 142, 144, 169, 192	
Puñjaḷi or Puñjāḷike, <i>di.</i> ,	114, 115	Rājarāja II., <i>do.</i> ,	147
Puri, <i>vi.</i> ,	101	Rājarāja III., <i>do.</i> , 9, 121, 161, 162, 163, 164,	
Purigere three-hundred, <i>di.</i> ,	198, 200, 202,		163, 169, 174, 175
	210, 212, 214	Rājarāja I., <i>E. Chalukya k.</i> ,	178, 184
pnrdāsa,	46	Rājarāja-Chēdiyarāyan, <i>Milādū ch.</i> ,	135
Pushkar, <i>lake</i> ,	58	Rājarājadēva, <i>Chōla k.</i> ,	135
Pushpasēna, <i>Jaina teacher</i> ,	116	Rājarājakesarivarman, <i>sur. of</i> Rājarāja I., 144,	
Puttaḍigal, <i>ch.</i> ,	195, 196		145, 169
puṭṭi, <i>measure</i> ,	76, 192	Rājarāja-māḍa, <i>coin</i> ,	130n
Puttūr, <i>vi.</i> ,	78n	Rājarājēśvara, <i>s. a.</i> Nandikampīśvara,	192
Puvāḷappiranda, <i>s. a.</i> Bhūpālanōdbhava,	166	Rājasēkhara, <i>poet</i> ,	31
		Rājasēkhara, <i>Vijayanagara k.</i> ,	79n
		Rājasiriba, <i>sur. of</i> Indravarman I.,	183n
		rājasthāniya,	159
		rājastya, <i>sacrifice</i> ,	46
		Rājatarangini, <i>quoted</i> ,	130n, 207n, 223n, 230
		Rājavā, <i>queen of</i> Guṇasāgara II.,	86
		Rājavarman, <i>k.</i> ,	181
		Rājēndra-Chōla I., <i>Chōla k.</i> , 7, 133, 135, 137,	
			138, 142, 169, 170
		Rājēndra-Chōla II., <i>s. a.</i> Kulōttuṅga-Chōla I.,	2
		Rājēndra-Chōla III., <i>Chōla k.</i> , 169, 172, 175,	
			176, 177
		Rājēndra-Chōla-Milādudaiyaṅ, <i>sur. of</i> Irāmaṇ	
		Mummaḍi-Chōḷaṅ,	135
		Rājēndra-Chōlēśvara, <i>s. a.</i> Nandikampīśvara,	192
		Rājēndradēva, <i>Chōla k.</i> ,	7, 135, 145, 146, 147
		Rājim, <i>vi.</i> ,	103, 104, 106n
		Rājputānā, <i>co.</i> ,	58, 222n
		Rājyapāla, <i>Kanauj k.</i> ,	30n
		Rājyavardhana I., <i>do.</i> ,	153
		Rājyavardhana II., <i>do.</i> ,	157, 159
		Ramā, <i>s. a.</i> Lakshmi,	84
		Rāma, <i>saint</i> ,	148, 151, 155, 203

R

Rāchamalla, <i>W. Gaṅga k.</i> ,	23
Rāchamalla II., <i>do.</i> ,	109
Rāchiya-Peddēri-Bhīma, <i>m.</i> ,	184n
Rādhanpur, <i>vi.</i> ,	210, 216, 230
Rādūpāṭi, <i>s. a.</i> Raṭṭapāṭi,	217n
Raghu, <i>mythical k.</i> ,	148, 151
Raghuvārśa, <i>quoted</i> ,	151n, 155n
Rāhu, <i>demon</i> ,	127
Raichūr, <i>vi.</i> ,	19
rainy season,	66
Rāja-Bhīma, <i>s. a.</i> Chālukya-Bhīma II.,	181, 190
Rājadēviyār, <i>queen</i> ,	141
Rājādhirāja I., <i>Chōla k.</i> ,	7, 146n
Rājādittadēvapuram or Rājādittapuram, <i>s. a.</i>	
Tirunāvalūr,	133, 138
Rājādittan Pugalvippavarganḍa, <i>ch.</i> ,	134, 135
Rājāditya, <i>Chōla k.</i> ,	133, 134, 194, 195
Rājāditya, <i>W. Gaṅga ch.</i> ,	192, 193

	PAGE		PAGE
Rāma Narasimha, s. a. Narasimhavarman II.,	146, 147	Rattānārāyaṇa, sur. of Kārtavīrya IV.,	218
Rāmāyaṇa, quoted,	120n, 151n	Rattapādi, co.,	145, 146, 217
Rambhā, f.,	182n	Rattapādi, s. a. Rattapādi,	217
Rāmēśvaram, island,	76n	Rattasamudra, tank,	218
Ramkola, vi.,	95	Rattavidyādharma, sur. of Gōvinda IV.,	215, 220
rāṇaka,	223	ratthika,	50n, 221n
Rānakēsari-Rāma, sur. of Narasimhavarman II.,	135, 145, 146, 147	Rāvaṇa, demon,	43, 151n
Rāpavīgraha, Chēdi k.,	29, 43	Ravikayya, m.,	208
Rāndhūka, m.,	95	Ravivarman, Kēraḷa k.,	130
Raṅga, s. a. Śrīraṅgam,	162	Rāyakōṭa, vi.,	155n
Raṅganātha, te.,	77n, 163, 176, 177	Rāyakumāra or Rāyakuvara, ch.,	112, 113, 114
Rāṇṇādēvi, queen of Dharmapāla,	33	Rāvakaninmaḍi, queen of Būtuga II.,	162n
Rāpa, m.,	214	Rishabhadatta, ch.,	56, 58, 59, 60, 71
Rāshtrakūṭa, dy., 27, 28, 29, 30, 32, 33, 34, 35, 36, 42n, 133, 135, 142, 181, 189n, 190n, 194, 200, 204, 209, 210, 211, 214, 215, 216, 217, 218, 219 and add., 220, 221, 222, 223, 224, 225, 227, 230, 231n		Rishabhanātha, Jaina saint,	168
Rāshtrakūṭa, m.,	223	Rishabhēśvara, te.,	11
Rāshtrakūṭa, mythical k.,	216, 222	Rohanigutta, s. a. Rōhinīgupta,	69
rāshtrakūṭa, the headman of a village,	191, 222	Rōhinīgupta, m.,	69n
rāshṭramahattara,	222n	Rracholl or Rachol, s. a. Raichūr,	19
rāshtrapati,	45, 222n	Rraṭṭa, s. a. Raṭṭa,	219
Rāshṭraudha, s. a. Rāthōr,	222n	rūpaka, alamkāra,	43n
rāshṭrin,	50n		
Rāshṭrōḍa, s. a. Rāshtrakūṭa,	221, 222		
Rāthi, caste,	117, 118		
rathitara,	117		
Rāthōḍa, s. a. Rāthōr,	222		
Rāthōr, family,	30n		
Ratikara, m.,	97		
Ratnapālavarman, Prāgyōtisha k.,	100		
Ratnapur or Ratnapura, vi.,	182n, 225		
Ratnasimha, poet,	182n		
Ratnāvali, drama,	159n		
Ratnavarsha, sur. of Vijayāditya,	230		
Raṭṭa, mythical k.,	215, 216, 222		
Raṭṭa or Raṭṭa, s. a. Rāshtrakūṭa, 33, 208, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224n, 225, 227, 228			
Raṭṭa or Raṭṭarāja, Śilādhara prince,	223		
Raṭṭa, queen,	223		
Raṭṭakandarpa, sur. of Gōvinda IV.,	215, 220		
Raṭṭakandarpa, sur. of Indra III.,	36, 215, 220		
Raṭṭakandarpa, sur. of Indra IV.,	215, 220		
Raṭṭakandarpa, sur. of Khoṭṭiga,	215, 220		
Raṭṭamārtanḍa, sur. of Eṇeyammarasa,	218		
Rattānārāyaṇa, do.,	218		

	PAGE		PAGE
Sāluvasāluva, <i>biruḍa</i> ,	77n, 79n	Śarvanātha, <i>k.</i> ,	62n
Sāluva-Timma, <i>ch.</i> ,	79n	sarva-niyōga, <i>exclusive property</i> ,	131
Sāmaṇinikā, <i>f.</i> ,	50	śāsana, <i>governing</i> ,	202n
Sāmagam, <i>vi.</i> ,	46	Śaśāṅkarāja, <i>k.</i> ,	101, 102, 155n
Sāmāṅgaḍ, <i>vi.</i> ,	215, 222n	Sashō[ravi]śā, <i>di.</i> ,	94
sāmanta,	78, 160	Sasva(?), <i>m.</i> ,	86n
Śāmarai, <i>queen of Śattiviḍaṅgaṇ</i> ,	25	Sātāhani, <i>co.</i> ,	221
sama-vpitta,	114n	Sātakaṇi, <i>Andhra k.</i> ,	51
Samburāya, <i>s. a. Sāmparāya</i> ,	76	Śatapatha-Brāhmaṇa, <i>quoted</i> ,	50n
Sambuvārāyaṇ, <i>ch.</i> ,	149	Sātārā, <i>vi.</i> ,	70
saṅgha,	59, 60, 62, 72	Sātimita, <i>m.</i> ,	54, 55
Śāmi (Śyāmila or Svāmin), <i>m.</i> ,	53	Śāttaṇ, <i>m.</i> ,	24
Śāmkara, <i>m.</i> ,	214	Śatti, <i>Pallava k.</i> ,	25, 26
Śāmkaradēva, <i>Vaidumba ch.</i> ,	142	Śattiviḍaṅgaṇ (Śakti-Viḷaṅka), <i>do.</i> ,	25
Śāmkaragāṇa I., <i>Kaluchuri k.</i> ,	86, 88n	sattra,	46, 104, 107
Śāmkaragāṇa II., <i>do.</i> ,	86	Satyāśraya-Vallabhēndra, <i>s. a. Pulakēśin II.</i> ,	189
Śāmkaragāṇa III., <i>do.</i> ,	86	Satyavākya, <i>sur. of W. Gaṅga kings</i> ,	199
Śāmkāśya, <i>s. a. Sankisa</i> ,	157	Śauḍa, <i>co.</i> ,	207n
saṁkrāntis :—	95, 143	śaulkika,	91
Mēsha-saṁkrānti,	7n, 9	Saumyasindhu, <i>s. a. Uttarasamudra</i> ,	94
Uttarāyaṇa-saṁkrānti,	87, 88, 176, 191	Saundatti, <i>vi.</i> ,	217, 218, 219, 220, 221, 223, 225, 227, 228
Sāmparāya, <i>Sāluva ch.</i> ,	76	Śauṇa, <i>co.</i> ,	207
Samudra-Goppaya, <i>ch.</i> ,	161, 162, 168	Sāvarpi (Manu), <i>family</i> ,	94
Sāñchi, <i>vi.</i> ,	60n	sāvikā,	74
Śāṇḍayaṇ, <i>Vaidumba ch.</i> ,	142	Sāvitrī-Maṅgi, <i>Sāluva ch.</i> ,	83
Saṅgamnēr, <i>vi.</i> ,	224n	Sēlhaṇa, <i>m.</i> ,	98
Sāṅglī, <i>vi.</i> ,	27, 28, 34, 36n, 38n, 215n, 220, 231n	Sēligar, <i>m.</i> ,	23
Saṅkalāpura, <i>vi.</i> ,	18	Śēmbaṅḍaiyāṇ Nārāyaṇa Āditya, <i>m.</i> ,	147
Śāṅkaragāṇa, <i>Chēdi k.</i> ,	20	Sēna II., <i>Raṭṭa ch.</i> ,	218
Śāṅkasasthāna, <i>vi.</i> ,	87	śēṇbagam, <i>s. a. champaka</i> ,	132n
śāṅkadhārīn,	95	Śēndalai, <i>vi.</i> ,	76n
Śāṅkhāka, <i>m.</i> ,	95	Śēndamaṅgalam, <i>vi.</i> ,	161, 162, 167, 168, 169
Saṅkila, <i>k.</i> ,	216	Śēṇḍaṇ, <i>s. a. Skanda</i> ,	162n
Sankisa, <i>vi.</i> ,	157	sendūra, sēndūra or sēndūra, <i>s. a. sindūra</i> , 228, 229	
Santarāvūru, <i>vi.</i> ,	76	Śēṅgama, <i>vi.</i> ,	11
Śāntiśvara, <i>Jaina saint</i> ,	114	Śēṅgaṇivāyar, <i>sur. of Piḷḷai Śōlakōṇār Āḷiyār</i> , 166	
Śāntivarman, <i>Baisa prince</i> ,	213, 223n	serpents, day of the,	131
Śaptakōṭiśvara, <i>te.</i> ,	226n	Śēsha, <i>god</i> ,	28, 45
Sarasvatī, <i>goddess</i> ,	41, 154	Setapharaṇa, <i>m.</i> ,	72
śarayōgya, <i>chronogram</i> ,	155	seṭṭhi,	49
Sarayū, <i>s. a. Gogra</i> ,	86, 88	Sēuṇa, <i>co.</i> ,	224, 225
Sarayūpāra, <i>co.</i> ,	86, 88	Śēvalai, <i>vi.</i> ,	133, 136
Śārkarakuṇṇu, <i>vi.</i> ,	191	Shēri (Shēdhi), <i>vi.</i> ,	36 and add.
Sāraṇṇī, <i>vi.</i> ,	222n	Shiggaon, <i>vi.</i> ,	198, 199, 208, 209, 212
śārtti,	135	Shō[thā]visā, <i>di.</i> ,	94
Saruvāra, <i>di.</i> ,	98, 99	Siddhānta,	191
Śarva, <i>s. a. Śiva</i> ,	36n	Siddhavaḍava, <i>sur. of Narasiṁhavarman I.</i> , 135, 136	
śārvabhauma,	79, 84	Siddhi, <i>Telugu-Chōḍa ch.</i> ,	121, 122, 125, 127
Sarvalōkāśraya-Jinabhavana, <i>te.</i> ,	179, 191	Sīdhū, <i>m.</i> ,	87
sarvāmānya,	85		

	PAGE		PAGE
Sigām or Śigām, <i>vi.</i> ,	36	Sōmāditya, <i>ch.</i> ,	182
Sibaḍa, <i>m.</i> ,	95	Sōmakunḍakā, <i>vi.</i> ,	157, 159
Sibaḍa, <i>m.</i> ,	95n	Sōmaladēvi, <i>queen of Sōmēśvara</i> ,	162
Sibadhaya, <i>m.</i> ,	54	Sōmanātha, <i>s. a. Śiva</i> ,	132
Sibugrāma or Śihukagrāma, <i>s. a. Sigām</i> ,	36, 46	Sōmanāthapaṭṭaṇa, <i>s. a. Prabhāsa</i> ,	58
Śilāhāra, <i>family</i> ,	217, 223, 224	Sōmanāthēśvara, <i>te.</i> ,	6
śīman, <i>a district</i> ,	75, 85	Sōmaṅgalam, <i>vi.</i> ,	6
Śimbāchalam, <i>vi.</i> ,	76	Sōmēśvara, <i>Hoysala k.</i> ,	161, 162, 176, 177
Simhadata, <i>m.</i> ,	52	Sōmēśvarasvāmin, <i>te.</i> ,	18
sindūra or sendūra crest,	227, 228, 229, 230	Sōnpat, <i>vi.</i> ,	155n
Śīnṇaśevalai, <i>vi.</i> ,	133	Soparaka, <i>vi.</i> ,	54, 55
Śīraiṇūr, <i>vi.</i> ,	24, 25	Soraṭa (Saurāshṭra), <i>co.</i> ,	221
Sīrasi, <i>s. a. Sīrsi</i> ,	99	Sottraṇāga, <i>m.</i> ,	107
Sīrasī-pattalā, <i>di.</i> ,	99	Southern Pennaiyāru, <i>vi.</i> ,	139n
Sīrigāvunḍa, <i>m.</i> ,	208	Sovasaka,	72
Siri-Puḷumāvi or Siri-Puḷumāyi, <i>s. a. Vāsiṭhi-</i> <i>puta Puḷumāyi</i> ,	61, 72	śrāddha,	40
Sīrpur, <i>vi.</i> ,	103, 104	śrāvaka,	112
Śīrriṇjūr, <i>vi.</i> ,	138, 144	Śravana-Belgoḷa, <i>vi.</i> ,	108, 109, 110n, 112, 115, 215
Sīrsi, <i>vi.</i> ,	99	Śrāvastī, <i>s. a. Sahet-Mahet</i> ,	157
Sīrūr, <i>vi.</i> ,	202, 209, 210, 214, 220, 221, 223, 225, 227	Śrāvastī-bhukti, <i>di.</i> ,	157, 159
Śīsīra, <i>season</i> ,	46n	Śrāvastī-maṇḍala, <i>s. a. Śrāvastīya-vishaya</i> ,	94
Śītābaldī, <i>vi.</i> ,	223, 225, 226	Śrāvastīya-vishaya, <i>di.</i> ,	94
Śiva, <i>god</i> ,	22, 27n, 28, 42, 45, 83, 107, 132, 133, 136, 138, 139n, 168, 192, 196	Śrī, <i>s. a. Lakshmi</i> ,	42, 124, 154, 189
Śivadēvasvāmin, <i>m.</i> ,	160	Śrīdēvi, <i>queen of Śrīśiddhi</i> ,	121, 122, 126, 152, 155
Śivagupta, <i>m.</i> ,	71	Śrīdhara, <i>m.</i> ,	98
Sivakhadaguta, <i>s. a. Śivaskandagupta</i> ,	66	Śrī-Harsha, <i>Chandella k.</i> ,	39
Śivamāra II., <i>W. Ganga k.</i> ,	193	Śrī-Kāḍapaṭṭigaḷ, <i>sur. of Śattiviḍaṅgaṇ</i> ,	25
Śivanasamudra, <i>vi.</i> ,	18, 19	Śrīkaṇṭha, <i>Chōḷa ch.</i> ,	149
Śivarāja I., <i>Kalachuri k.</i> ,	86	Śrīkōvalūra, <i>s. a. Tirukkōvalūr</i> ,	146
Śivarāja II., <i>do.</i> ,	86	Śrī-Kulaśōkhara-Nambi, <i>sur. of Irāyiraṇ</i> <i>Śīriyāṇ</i> ,	197, 198
Śivaskanda, <i>ch.</i> ,	71	śrīmad-Gōvindhachandradēvaḥ, <i>legend on seal</i> ,	98
Śivaskandagupta, <i>m.</i> ,	66, 71	śrīmat-Sōḍhadēvasya, <i>do.</i> ,	85
Śivaskandavarman, <i>Pallava k.</i> ,	67, 68, 69, 185	Śrīnātha, <i>Telugu poet</i> ,	78
Śiyadōṇi, <i>vi.</i> ,	30	Śrīnivāsa, <i>sur. of Mādhavarman</i> ,	100
Śiyasārman, <i>m.</i> ,	184	Śrī-Paravala, <i>s. a. Śrī-Vallabha</i> ,	33
Si-yu-ki,	157n	Śrīpura, <i>s. a. Sīrpur</i> ,	104, 106
Skanda, <i>Bāṇa ch.</i> ,	22, 23	Śrīraṅga, <i>god</i> ,	76
Skanda, <i>god</i> ,	136n, 162n	Śrīraṅgam, <i>vi.</i> ,	77n, 161, 162, 163, 176, 177
Skandagupta, <i>ch.</i> ,	160	Śrīraṅgamāmbā, <i>queen of Nṛsiṃharāya</i> ,	77, 84
Smpiti,	103	Śrīraṅgapaṭṭaṇa, <i>vi.</i> ,	18, 76, 78
Sōḍhadēva, <i>Kalachuri k.</i> ,	86, 87, 88	śrī-Tribhuvanāṃkusaḥ, <i>legend on seal</i> ,	178
Sogal, <i>vi.</i> ,	217, 223n	Śrīvaikunṭham, <i>vi.</i> ,	10
Śōlakōṇ or Śōlakōṇār, <i>ch.</i> ,	163, 166, 168	Śrīvallabha, <i>biruda</i> ,	33
Śōlapuram, <i>vi.</i> ,	192, 193, 194, 195, 196	Śrīvūra or Śrīvūra, <i>s. a. Sīrūr</i> ,	202, 204, 203
sōma,	46	sthālipāka,	48
Sōmadēva, <i>ch.</i> ,	61	sthavira,	50, 51, 54
		Śūchi, <i>s. a. Mithuna</i> ,	128, 131
		Sūḍi, <i>vi.</i> ,	181, 182
		Sūgalladēvi, <i>queen of Śivarāja II.</i> ,	86

INDEX.

257

	PAGE		PAGE
Sugata, <i>s. a.</i> Buddha,	159	Tapti, <i>vi.</i> ,	36
Śukra, <i>planet</i> ,	135, 136, 145n	taram, <i>revenue</i> ,	131
Śūlapāṇi, <i>s. a.</i> Śiva,	20	tarapati,	91
śulka,	29n, 215	Tātabikki, <i>ch.</i> ,	181, 190
Sulān,	76, 77	Tātabikyana, <i>s. a.</i> Tātabikki,	182
summer,	61	tēdi,	15n, 1fr
Sun, <i>god</i> ,	158, 159	Tēkal, <i>vi.</i> ,	76, 77
Sun, <i>race of the</i> ,	94, 120, 125n	Teliṅgāna, <i>co.</i> ,	77
Sundaramūrti, <i>Śaiva saint</i> ,	133, 136	Telugu-Chōḍa or -Chōḷa, <i>family</i> ,	120, 121
Sundarikāmārga, <i>di.</i> ,	104, 107	Telūnga, <i>s. a.</i> Teluṅgurāya,	76
Śuṅga, <i>dy.</i> ,	50n	Telūṅgabijjana or Tiluṅgabijja, <i>s. a.</i> Tilunga- vidya,	121n, 148
Surāṭha (Surāshṭra), <i>co.</i> ,	221	Telūṅgurāya, <i>Sāḷuva ch.</i> ,	76
Sūrayōjha, <i>m.</i> ,	85	Teṇkāsi, <i>vi.</i> ,	13, 14, 15, 16
Sūrināyani-Muṣhṭāru, <i>s. a.</i> Muṣhṭāru,	75, 85	Tēr, <i>vi.</i> ,	224, 226
Surjoo, <i>s. a.</i> Sarayū,	88	Tērdāl, <i>vi.</i> ,	217, 218, 227
Sūryasātaka, <i>quoted</i> ,	159n	Tēśadakkī Perumāṇār, <i>sur. of</i> Rājadēviyār,	141
Sūrya-siddhānta,	15, 95	ṭhakkura,	94, 98
sūtra:—		Thiulapāṭaka, <i>vi.</i> ,	87
Prāvachana,	193	tiger banner,	120
suttee,	229	Tigula or Tigula, <i>s. a.</i> Tamil,	77
Śūttiradēvi, <i>queen of</i> Tiruvayaṇ,	143, 143	Tihuyasāṭha, <i>m.</i> ,	87
suvarṇa, <i>coin</i> ,	27, 35, 45	ṭikari, <i>vi.</i> ,	87
Suvarṇavarsha, <i>sur. of</i> Gōvinda IV.,	27, 35, 41, 45	ṭikarikā, <i>di.</i> ,	87, 88
svādhyāya,	46	Tiluṅgavidya, <i>Telugu-Chōḍa ch.</i> ,	121, 122, 125, 148, 152
Svāmi-Mahāśeṇa, <i>s. a.</i> Skanda,	189	Timma, <i>Sāḷuva ch.</i> ,	77
Svāmin, <i>do.</i> ,	106	Timma or Timmarāja, <i>ch.</i> ,	108, 112, 113, 114
svastika,	27, 117, 119	Tippa, <i>Sāḷuva ch.</i> ,	76, 77
Śvētapada, <i>co.</i> ,	86	Tipparāja-Oḍeyar, <i>do.</i> ,	76
symbols, numerical,	85, 86	tīrtha,	58
		Tiruchchennambūṇḍi, <i>vi.</i> ,	140
		Tirugōkarpam, <i>vi.</i> ,	162
		Tirukkalukkunram, <i>vi.</i> ,	164, 165
		Tirukkāṭṭuppalī, <i>vi.</i> ,	77n
		Tirukkōvalūr, <i>s. a.</i> Tirukoilur,	135, 138, 139, 140, 142, 143, 144, 145, 146, 165
		Tirukoilur, <i>vi.</i> ,	133, 135, 162
		Tirumalai near Pōḷūr, <i>vi.</i> ,	192
		Tirumalaidēva-mahārāja, <i>s. a.</i> Gōpa-Timma,	77n
		Tirumalavāḍi, <i>vi.</i> ,	5
		Tirumālīśvara, <i>te.</i> ,	174, 175
		Tirumaṅgai-Ālvār, <i>Vaiṣṇava saint</i> ,	138
		Tirumāṇikuḷi, <i>vi.</i> ,	170, 171, 172, 173, 174
		Tirumudugunram, <i>s. a.</i> Vṛiddhāchalām,	164
		Tirumūpaippāḍi, <i>s. a.</i> Mūṇaippāḍi,	133, 134, 135, 136, 138
		Tirunallār, <i>vi.</i> ,	172
		Tirumānanallūr, <i>vi.</i> ,	132, 133, 136
		Tirumāṇasambandar, <i>Śaiva saint</i> ,	138
			2 q
T			
Tāḍapa, <i>E. Chalukya k.</i> ,	181		
Tagara, <i>s. a.</i> Tēr,	224, 226		
Tāha, <i>s. a.</i> Tāḍapa,	181		
Taila II., <i>W. Chalukya k.</i> ,	217		
ṭakkārikā, <i>vi.</i> ,	94n		
Takkōlam, <i>vi.</i> ,	194		
Tāla or Tālapa, <i>s. a.</i> Tāḍapa,	181, 190		
Talaing, <i>co.</i> ,	197		
Talākāḍ, <i>vi.</i> ,	224		
tala-simā,	46n		
Tālī, <i>vi.</i> ,	87		
Tammasiddha or Tammasiddhi, <i>Telugu-Chōḍa</i> <i>ch.</i> ,	120, 121, 122, 124, 126, 140, 152, 154n, 155		
tānira-paṭṭa or -paṭṭaka,	87, 95, 98		
Taṇḍalam, <i>vi.</i> ,	25, 26		
Tanjore, <i>vi.</i> ,	77n, 138n, 141, 144		
Tapuku, <i>vi.</i> ,	179		

	PAGE		PAGE
Upēnda, <i>sur. of Kshitipāla</i> ,	32	Vāpakōppādi, <i>di.</i> ,	139
uri, <i>measure</i> ,	141, 146	Vāpakōvaraiyaṇ or Vāpakōvaraiyar, <i>biruda</i> ,	139, 140, 141, 195
Uravupalli, <i>vi.</i> ,	66	Vānapalli, <i>vi.</i> ,	17
Urvarāditya, <i>sur. of Nṛsimharāya</i> ,	84	Vaṅga, <i>co.</i> ,	207
Usabhadata or Usabhadāta, <i>s. a. Rishabhadatta</i> ,	56, 58	Vaṇīpātaka, <i>vi.</i> ,	87
ushatbudha (usharbudha),	148	Vaṇkidēva, <i>Sāḷva ch.</i> ,	76
Ushavadāta, <i>s. a. Rishabhadatta</i> ,	46n	Varāha, <i>s. a. Vishṇu</i> ,	132
Uttamagaṇḍa-māda, <i>coin</i> ,	130n	Varāhapurāṇam, <i>Telugu poem</i> ,	75, 76, 78, 79
Uttaramallūr, <i>vi.</i> ,	193n	Vārāṇāsi, <i>s. a. Benares</i> ,	214
Uttarapurāṇa, <i>quoted</i> ,	211	Vārāṇāsi, <i>vi.</i> ,	162, 168
Uttarāramacharita, <i>drama</i> ,	30n, 148, 149n	Vardhamāna, <i>Jaina saint</i> ,	115, 116
Uttarasamudra, <i>co.</i> ,	94, 95	Vardhamānaka, <i>sur. of Pāṇḍyakadēvi</i> ,	114
Uttelle, <i>vi.</i> ,	179	Vārṇā, <i>vi.</i> ,	231
Uttirā, <i>m.</i> ,	143	varsha,	58, 60
uvachcha, <i>a temple drummer</i> ,	143	Varuṇa, <i>god</i> ,	159
Uyyakkōṇḍāṇ-Sōlapuram, <i>s. a. Sōlapuram</i> ,	192	varusham,	16n
V		Vāsīthī, <i>Andhra queen</i> ,	61, 73
Vāchīśvara, <i>te.</i> ,	119	Vāsīthī, <i>f.</i> ,	61
Vaḍḍadi, <i>vi.</i> ,	76	Vāsīthīputa (Vāsīsthīputra) Pūḷmāyi,	60, 66, 70
vaḍḍavane,	201n	Andhra k.,	224, 226
Vaddiga, <i>Rāshtrakūṭa k.</i> ,	34	Vāsudēva, <i>ch.</i> ,	224, 226
Vāhali or Bāhali, <i>k.</i> ,	86	Vaṭṭaranyēśvara, <i>te.</i> ,	119
Vāhmaṭa, <i>m.</i> ,	87	Vātasvāmin, <i>m.</i> ,	160
Vaichaya, <i>s. a. Baicha</i> ,	115, 116	Vaṭṭavi or Vaṭṭaranya, <i>s. a. Tiruvālaṅgādu</i> ,	121, 126
Vaidumba, <i>family</i> ,	142, 143, 144	Vāyalpādu, <i>vi.</i> ,	75n, 85n
Vaidyanātha, <i>te.</i> ,	5	Vayiri-Aḍiyā, <i>W. Gaṅga ch.</i> ,	195
Vaijayanṭi, <i>s. a. Banavāsi</i> ,	49, 70	Vāyula, <i>m.</i> ,	117, 118
Vaikunṭha-Perumāḷ, <i>te.</i> ,	164	ve (drau),	63
vaishayika,	159n	Vēdagiriśvara, <i>te.</i> ,	165
Vaishṇava,	138, 146, 197, 200	Vēdas and śākhās :—	
vaiśvadēva,	45, 46	Bahvīśha,	87, 160
Vaiśya, <i>caste</i> ,	50n, 53	Sāman,	23, 41
vājapēya,	46	Chhandōga,	87, 180
Vajrinidēvi, <i>queen of Naravardhana</i> ,	158	Yajus,	85, 87
Vakāṭaka, <i>family</i> ,	160n	Kārva,	28, 45
valādhīra or balādhīra,	87	Mādhyamādhina,	87
Velahāri-gaṇa,	179, 181	Vājasanēya,	87
Vallabha, <i>sur. of Rāshtrakūṭa kings</i> , 27, 28,	29, 45, 189, 194, 195	Vājīn,	28, 45
Vallam, <i>vi.</i> ,	79n, 165, 166	Vēgavati, <i>vi.</i> ,	129
Vallūru, <i>vi.</i> ,	75n	Vēḷkā, <i>s. a. Vēgavati</i> ,	129
Vālmiki, <i>poet</i> ,	164	Velanāḍu, <i>co.</i> ,	149
Valūraka, <i>s. a. Kārlē</i> ,	53, 59, 60, 61, 62, 65	Vēlapātipura, <i>s. a. Vāyalpādu</i> ,	75n, 85
Vāmana, <i>god</i> ,	146	vēli, <i>measure of land</i> ,	143
Vāmanapurīśvara, <i>te.</i> ,	170, 171, 172, 173, 174	Vēḷkā, <i>s. a. Vēgavati</i> ,	128, 129, 132
Vāmarathya, <i>m.</i> ,	159	Vellore, <i>vi.</i> ,	192
Vāṇagappādi, <i>s. a. Vāpakōppādi</i> ,	139	Vēlūr, <i>s. a. Vellore</i> ,	25, 192n
		Vēlūrpādi, <i>vi.</i> ,	192
		Vēpāṇḍaiyaṇ, <i>ch.</i> ,	166

	PAGE		PAGE
Vēṅgi, <i>co.</i> ,	28, 191, 207, 231	Vijaya-Nripatūṅgavikrama or Vikramavarman, <i>Gaṅga-Pallava k.</i> ,	139, 140, 161
Veṅkaṭa, <i>s. a.</i> Tirupati,	77	Vijayapāla, <i>Kanauj k.</i> ,	30n
Veṅkaṭapati, <i>Vijayanagara k.</i> ,	129	Vikara, <i>vi.</i> ,	94
Veṅkaṭaramaṇappa, <i>m.</i> ,	75	Vikkirama-Śōlaṅ-ulā, <i>quoted</i> ,	120, 136, 163n
Veṅkaṭēsa-Perumāḷ, <i>te.</i> ,	25	Vikrama-Chōḷa, <i>Chōḷa k.</i> ,	2, 3, 4, 5, 6, 8, 135, 136, 163n, 169, 170, 171
Veṅṇainallūr-nāḍu, <i>di.</i> ,	133, 136	Vikrama-Chōḷa-Chēdiyarāyaṇ, <i>Milāḍu ch.</i> ,	135
Vēṇṭr, <i>vi.</i> ,	108, 112, 113, 114	Vikrama-Chōḷa-Kōvalarāyaṇ, <i>do.</i> ,	135
Vēṇuvāsa, <i>m.</i> ,	53	Vikramāditya, <i>mythical k.</i> ,	224
Verāwal, <i>vi.</i> ,	221	Vikramāditya I., <i>E. Chalukya k.</i> ,	189, 190n
Vetta, <i>s. a.</i> Betta,	152	Vikramāditya II., <i>do.</i> ,	181, 190
Vēṭṭuvadaraiyar, <i>ch.</i> ,	139, 140	Vikramāditya V., <i>W. Chōḷukya k.</i> ,	222n
Vēṭṭuvadiyaraiyar, <i>s. a.</i> Vēṭṭuvadaraiyar,	140	Vikramāditya VI., <i>do.</i> ,	130n, 223
veṅkā,	52	Vikramapāla or Vikramapālādēva, <i>Uttara-samudra ch.</i> ,	94
Vidarbha, <i>co.</i> ,	30n	Vikramāṇjunavijaya, <i>Kanarese poem</i> ,	33, 34n
Viḍēlviḍugu, <i>hiruda</i> ,	149n	Vikramāvalōka, <i>sur. of Gōvinda II.</i> ,	230
Vidyā, <i>queen of Śaṅkaragapa II.</i> ,	86	Vikrānta-Nārāyaṇa, <i>sur. of Gōvinda IV.</i> ,	36, 45
Vidyādharaḥaṇṇa, <i>ch.</i> ,	101	Vipakadēva, <i>m.</i> ,	210, 211
Vighnēśvara, <i>s. a.</i> Gaṇapati,	83	Vināpōṭi, <i>f.</i> ,	152
viḥāra,	60, 117	Vinayachandra, <i>m.</i> ,	163n
Vijāmbā, <i>queen of Indra III.</i> ,	33, 44	Vinayāditya, <i>W. Chalukya k.</i> ,	45
Vijaya-Buddhavarman, <i>Pallava k.</i> ,	67, 69, 185	Viṅgavallī, <i>vi.</i> ,	28, 45
Vijaya-Dantivikramavarman, <i>Gaṅga-Pal-lava k.</i> ,	196	Vinikōṇḍa, <i>s. a.</i> Vinukōṇḍa,	16, 19
Vijayāditya, <i>ch.</i> ,	230	vinigata,	235c
Vijayāditya, <i>W. Chalukya k.</i> ,	35, 182	Vinṇagar, <i>a Viṣṇu temple</i> ,	197n
Vijayāditya I., <i>E. Chalukya k.</i> ,	189	Vinukōṇḍa, <i>vi.</i> ,	16
Vijayāditya II., <i>do.</i> ,	184, 189, 216	Vīrabhadra, <i>Gajapati prince</i> ,	18, 19, 20
Vijayāditya III., <i>do.</i> ,	20, 180, 184, 189, 216	Vīra-Chōḷa, <i>E. Chalukya k.</i> ,	140
Vijayāditya IV., <i>do.</i> ,	182, 190	Vīra-Chōḷa, <i>ch.</i> ,	124
Vijayāditya V., <i>do.</i> ,	190	Vīra-Chōḷa, <i>sur. of Prithivīpati II.</i> ,	130
Vijayāditya VI., <i>sur. of Amma II.</i> ,	179, 190	Vīraganṇanāḍālvāṇ, <i>ch.</i> ,	163, 168
Vijaya-Gaṇḍagōpālādēva, <i>Telugu-Chōḷa ch.</i> ,	129, 166	Vīrahōbala, <i>Sāḷuva ch.</i> ,	63
Vijaya-Īśavaravarman, <i>Gaṅga-Pallava k.</i> , 23, 24, 25		vīrakal or vīrakkaḷ,	23, 169
Vijaya-Kampa, <i>s. a.</i> Vijaya-Kampavikrama-varman,	192, 193, 196	vīrakalāl,	176n
Vijaya-Kampavarman, <i>do.</i> ,	193n	virāma,	75n
Vijaya-Kampavikramavarman, <i>Gaṅga-Pal-lava k.</i> ,	193, 194, 196	Vīramahēndra, <i>sur. of Chāḷukya-Bhima II.</i> ,	181
Vijayanagara, <i>vi.</i> ,	18, 19, 75, 77, 78, 79, 80, 84n, 115	Vīra-Narasimha, <i>Vijayanagara k.</i> ,	79, 80
Vijaya-Nandivikrama or -Nandivikramavarman, <i>Gaṅga-Pallava k.</i> ,	139, 192, 196	Vīra-Narasimhadēva, <i>s. a.</i> Narasimha II.,	161, 162, 163, 168
Vijaya-Narasimhavarman, <i>s. a.</i> Vijaya-Narasimhavikramavarman,	22n	Vīra-Narasimhadēva-Yādavarāya, <i>k.</i> ,	25
Vijaya-Narasimhavikramavarman, <i>Gaṅga-Pallava k.</i> ,	22, 23	Vīra-Nārāyaṇa, <i>sur. of Amōghavarsha I.</i> ,	36
Vijaya-Nripatūṅgavarman, <i>s. a.</i> Vijaya-Nripatūṅgavikramavarman,	140	Vīra-Nārāyaṇa, <i>sur. of Parāntaka I.</i> ,	133n
		Vīranārāyaṇa-terinda-villigal, <i>regiment</i> ,	133
		Vīra-Pāṇḍya, <i>ch.</i> ,	108, 109, 110, 111, 112
		Vīra-Pāṇḍya, <i>Pāṇḍya k.</i> ,	10, 11, 17
		Vīrapratāpa, <i>sur. of Vijayanagara kings</i> ,	80
		Vīrarājendra, <i>Chōḷa k.</i> ,	9

327
262
65

APPENDIX.

A LIST OF INSCRIPTIONS OF SOUTHERN INDIA FROM ABOUT A.D. 500.

By PROFESSOR F. KIELHORN, C.I.B.; GÜTTINGEN.

IN continuation of my List of the Inscriptions of Northern India¹ I now publish a similar list of inscriptions of Southern India, which also was originally compiled solely for my own use. It contains all southern inscriptions from about A.D. 500 which I have found in the various publications accessible to me, excepting, as a rule, those in Dr. Burgess and Pandit Natesa Sastri's *Archæol. Survey of Southern India*, Vol. IV., and in Mr. Rizzo's *Epigraphia Carnatica*, Vol. III. ff. The inscriptions of any importance, other than reprints, in the former publication may be expected to be soon republished critically, and those in the *Epigraphia Carnatica* will, I have no doubt, receive a general index of their own, when all the texts have been published.

While I am writing these lines,² my list contains 1,020 numbers which treat of about 1,100 separate inscriptions. Of this total about 210 are on copper-plates, and 890 on stone. Taken as a whole, the inscriptions of the South in some respects differ essentially from the northern inscriptions. The latter with insignificant exceptions are all in Sanskrit; of the 1,100 inscriptions in the present list not more than about 290 are in Sanskrit only.³ About 340 are in Tamil, 320 in Kanarese, 10 in Telugu, 90 in Sanskrit and Kanarese, 30 in Sanskrit and Telugu, and 20 in Sanskrit and Tamil; the language of four is an ancient Prākṛit, and a few are composed or contain remarks in a dialect which apparently is an old form of Marāṭhī. On the other hand, while the inscriptions of the North are dated in about ten different eras the chief of which is the Vikrama era, Southern India generally uses the Śaka era. Of about 510 of these inscriptions dated according to eras,⁴ 450 quote the Śaka and 20 from the southernmost part of India the Kōlamba (or Kollam) era; six quite exceptionally use the era of the Kaliyuga (marked Ky.), and 34 are dated according to the Chālukya-Vikrama era (marked Chā. Vi.), i.e., really, in regnal years of the Western Chālukya Vikramāditya VI. The Vikrama era is foreign to the South; it is quoted only once, in the most modern inscription of this list (of A.D. 1830), which also gives the number of years elapsed since Vardhamāna's Nirvāṇa. This list, moreover, will show that in large tracts of Southern India it was the custom — more rarely observed in Northern India — to date documents only in the regnal years of the reigning kings. Of the prominent part which the Jovian years play in the dates of southern inscriptions I have had occasion to speak elsewhere.

Differently from the course followed in the Northern List, I have arranged the inscriptions here given mainly according to the dynasties to which they belong. Dated and undated miscellaneous inscriptions which I cannot assign to any particular dynasty will be given under separate headings at the end of the list. Any inconvenience which my arrangement may cause I hope to

¹ See above, Vol. V. Appendix.

² Any inscriptions that may be published while this list is being printed will as far as possible be inserted in their proper places.

³ When the language of an inscription is not stated in this list, it should be understood to be Sanskrit.

⁴ Current years will be denoted in this list by an asterisk placed after the numerals for the year.

lessen by an index which will give all dated inscriptions arranged in the order of the Śaka years. Another index is to contain most of the proper names which occur in this list.

While doing this work, I often have found cause to regret that I know so little of the vernaculars of Southern India, and I fear that this list must suffer through this want of knowledge on my part. I nevertheless venture to hope that what I offer now will at least save some trouble to others who are interested in Indian Epigraphy.

A.—The Western Chalukyas of Bādāmi.¹

1.—Ś. 310.—*Ind. Ant.* Vol. IX. p. 294. Pimpalñēr (spurious²) plates³ of the W. Chalukya⁴ *Mahārājādhirāja Satyāśraya* (Pulakēśin I. ?) :—

(L. 1).—Śakanripakāl-ātita-samvatsara-satēshu tri(tri)shu daś-ōttarēshv=asyā[m*] samvatsara-māsa-paksha-divasa-pūrvvāyān=tithau.

(L. 35).—sūryagrahaṇa-parvvapi.

2.—Ś. 411*.—*Ind. Ant.* Vol. VII. p. 211, and Plates in Vol. VIII. p. 340. Altēm⁵ (formerly Captain T. B. Jervis's, now British Museum, spurious⁶) plates of the W. Chalukya *Mahārājādhirāja Pulakēśin I. Satyāśraya*, the son of Raṇarāga who was the son of Jayasimha I.; and of his feudatory *Sāmiyāra*, the son of Sivāra who was the son of the *Rājā* Goṇḍa, of the Rundranīla-Saindraka family (or Rundranīla and Saindraka families) :—

(L. 28).—Śakanrip-ābdēshv=ākādaś-ōttarēshu chatuś-satēshu vyatītēshu Vibhava-samvatsarē pravarttamānē . . . Vaisākh-ōdita-pūrṇa-punya-divasē Rāhō(hau) vidhau(dhōr=) maṇḍalaṁ ślāsbhē (?).

(L. 35).—Vaisākha-paurṇamāsyām Rāhau vidhu-maṇḍala[m*] pravishṭavati.

12th April A.D. 488; a lunar eclipse, not visible in India; but see *ibid.* Vol. XXIV. p. 10, No. 164.

The inscription records the building of a Jaina temple and the allotment of certain grants to it, and gives the line of Jaina teachers Siddhanandin, Chitakāchārya, Nāgadēva, and Jinanandin.

3.—Ś. 500.—*Ind. Ant.* Vol. III. p. 305, and Plate; Vol. VI. p. 363, and Plate in Vol. X. p. 58; *PSOCI.* No. 39. Bādāmi cave inscription of the W. Chalukya⁷ *Maṅgalēśvara Raṇavikrānta*, of the 12th year of the reign (of his elder brother Kīrtivarman I.) :—

(L. 6).—pravarddhamāna-rājya-samvatsarē dvādaśē Śakanripati-rājyābhishēka-samvatsarēshv=atikrāntēshu pañchasa satēshu . . .

(L. 11).—mahā-Kārttika-paurṇamāsyām.

4.—*Ind. Ant.* Vol. X. p. 60, and Plate; *PSOCI.* No. 40. Bādāmi Kanarese rock inscription of the W. Chalukya⁴ *Maṅgalēśa*.

¹ For the W. Chalukyas of Gujārāt see my *List of North. Inscr.* Nos. 398, 400, 401 and 404. Of the (unpublished) Balsār plates, dated in Ś. 653, of the Jayāśraya-Maṅgalarasārāja (also called Vinayāditya and Yuddhamalla) who is mentioned *ibid.* No. 404, an account is given in *Jour. Bo. As. Soc.* Vol. XVI. p. 5, and *Ind. Ant.* Vol. XIII. p. 75.—In *Jour. Bo. As. Soc.* Vol. XX. p. 42 is published a Sanjān copper-plate inscription which professes to be of the time of the W. Chalukya Vikramāditya I. and to record a grant by his paternal uncle Buddhavarasa, the younger brother of Satyāśraya (Pulakēśin II.). I hope that this inscription may be re-edited with a facsimile. (For the name Buddhavarasa see below, No. 67.)

² See *Ind. Ant.* Vol. XXX. p. 218, No. 25.

³ The third plate is numbered with the numeral figure 3.

⁴ The name Chalukya or Chālukya does not occur in the inscription.

⁵ See *ibid.* Vol. XXX. p. 218, No. 35.

⁶ See *Ind. Ant.* Vol. XXIX. p. 273.

⁷ The original has *Chalukya*.

5.—*Ind. Ant.* Vol. XIX. p. 16, and Plate. Bādāmi (Mahākūṭa) pillar inscription¹ of the 5th year of the reign of the W. Chalukya² Maṅgalēśa Raṇavikrānta :—

(L. 14).—uttarōttara-pravaraddhamāna-rājya-pañchama-śrī-varshē pravarttamānē Siddhārthē Vaisākha-paurṇamāsyām.

The Jovian year Siddhārtha, if it is really intended here,³ by the mean-sign system lasted from the 25th October A.D. 601 to the 21st October A.D. 602 (in Ś. 523-524).

In the lineage of the Chalukyas, Jayasiṅha (Jayasimha I.); his son Raṇarāga; his son Satyāśraya Raṇavikrama [Pulakēśin I.]; his son Puru-Raṇaparākrama [Kirtivarman I.] (defeated the kings of Vaṅga, Aṅga, Kalinga, Vaṭṭūra, Magadha, Madraka, Kēraḷa, Gaṅga, Mūshaka, Pāṇḍya, Dramiḷa, Chōḷiya, Āḷuka, Vaijayantī); his younger brother Uru-Raṇavikrānta Maṅgalēśa (conquered the [Kalatsūri] king Buddha).⁴—The inscription mentions Maṅgalēśa's father's wife Durlabhadēvi, of the Batpūra family.

6.—*Ind. Ant.* Vol. VII. p. 161, and Plate; *PSOOL*. No. 11. Nerūr (now India Office) plates of the W. Chalukya⁵ Maṅgalārāja (Maṅgalēśa, who put to flight Śaṅkaragapa's son Buddharāja,⁴ and killed Svāmīrāja of the Chālikya family), the son of Vallabha (Pulakēśin I.) :—

(L. 14).—samvatsara-pūjyatamāyām Kārttika-dvādaśyām.

7.—Ś. 532.—*Jour. Bo. As. Soc.* Vol. X. p. 365, and Plates. Goa plates, recording a grant by Satyāśraya Dhruvarāja Indravarman of the Bappūra family, who was staying at Rāvatīdvīpa⁶ and acting with the permission of the Mahārāja Śrīprithivī-vallabha; of the 20th year of the reign (according to Dr. Bhandarkar, of the W. Chalukya Maṅgalēśa, but according to Dr. Fleet of the 20th year of his own administration) :—

(L. 6).—Māgha-paurṇamāsyām.

(L. 17).—pravarddhamāna-vijayarājya-samvatsaram viṃśatimam⁷ Śaka-kālāḥ=pañcha varsha-śatāni dvātriṃśāni.⁸

8.—Ś. 532 (?).—Kurtakōṭi (spurious) plates of the W. Chālukya Vikramāditya I. Satyāśraya; see below, No. 21.

9.—Ś. 534.—*Ind. Ant.* Vol. VI. p. 73, and Plate; *PSOOL*. No. 12. Haidarābād plates of the third year of the reign of the W. Chalukya⁵ Mahārāja Satyāśraya (Pulakēśin II.), son of the Mahārāja Kirtivarman I., and son's son of the Mahārāja Satyāśraya Polekēśivallabha (Pulakēśin I.); issued from Vātāpīnagarī :—

(L. 11).—ātmanah pravarddhamāna-rājyābhishēka-samvatsarē tṛtīyē Śakanripati-samvatsara-śatēshu chatustrimś-ādhikēshu pañchasy-atītēshu Bhādrapad-āmāvāsyāyām sūryyagrahapa-nimittam.

2nd August A.D. 612;⁹ a solar eclipse, not visible in India; see *ibid.* Vol. XXIII. p. 130, No. 106.

10.—Ś. 556 (Ky. 3735¹⁰).—*Ep. Ind.* Vol. VI. p. 4, and Plate; *PSOOL*. No. 73. Aihole inscription, recording the construction of a temple of Jinēndra by a certain Ravikīrti, during

¹ The inscription is read from the bottom upwards; compare below, No. 641.

² The original has *Chālikya*.

³ The earliest inscription in this *List*, in which a Jovian year undoubtedly is quoted, is No. 56 of Ś. 692.

⁴ Compare *Ep. Ind.* Vol. VI. p. 294. ⁵ The original has *Chālikya*.

⁶ See below, No. 10.

⁷ Read *viṃśatimam*.

⁸ Read *dvātriṃśāni*.

⁹ This was the new-moon day of the *pūrṇimānta* Bhādrapada.—On the 23rd July A.D. 613, which was the new-moon day of the *pūrṇimānta* Bhādrapada of Ś. 535 expired, there was a total eclipse of the sun that was fully visible at Bādāmi.

¹⁰ Described as the year 3735 since the Bhārata war.

the reign of the W. Chalukya **Pulakēśin II. Satyāśraya**; (composed by Ravikīrti himself, whose fame is compared to that of Kālidāsa and Bhāravi):—

(L. 16).—Triṃśatsu tri-sahasrēshu Bhāratād=āhavād=itaḥ [*] sapt-ābdaśata-yuktēshu śa(ga)tēshv=abdeśhu pañchasu [!]* Pañchāśatsu Kalau kâlê shatsu pañcha-śatāsu cha [*] samāsu samatītāsu Śakānām=api bhūbhujām ||

In the Chalukya lineage, Jayasimhavallabha [I.]; his son Raṇarāga; his son Polekēśin [I.] (acquired Vātāpipurī); his son Kīrtivarman [I.] (defeated the Naḷas, Mauryas and Kadambas); his younger brother Maṅgalēśa (defeated the Kaṭachchuris and took Rēvatīdvīpa); Kīrtivarman's son Polekēśin [II.] Satyāśraya (was at war with Āpāyika and Gōvinda; besieged Vanavāsi; subdued the Gaṅgas, Ālupas, and the Mauryas in the Koṅkaṇas; besieged Purī; subdued the Lāṭas, Mālavas and Gūrjaras; defeated Harsha [of Kanauj]; conquered the three Mahārāshṭras; was at war with the Kālīngas and Kōśaḷas; took Pishṭapura; fought at the Kaunāla, i.e. Kolleru lake; defeated the Pallavas of Kāñchīpura; crossed the river Kāvērī and caused prosperity to the Chōḷas, Kēraḷas and Pāṇḍyas).

11.—*Ep. Ind.* Vol. V. p. 7, and Plate. Yekkēri rock inscription¹ of the reign of the W. Chalukya² **Mahārāja Satyāśraya Polekēśivallabha (Pulakēśin II.)**:—

(L. 8).—Kārttikasya pūnnimāsām³ likhitā prasast=īti || samvatsarā . . 6(?) rājya iti.

12.—*Ind. Ant.* Vol. VIII. p. 43, and Plate; *PSOCI.* No. 266. Nerūr (now India Office) fragmentary plates of the [W. Chalukya] **Mahārāja Satyāśraya Polekēśivallabha⁴ (Pulakēśin II.)**, the son of Kīrtirāja (Kīrtivarman I.).

13.—*Ep. Ind.* Vol. III. p. 51, and Plate. Chiplūp (now Bombay As. Soc.'s) plates of the W. Chalukya **Satyāśraya (Pulakēśin II.)**, the son of Kīrtivarman I.; recording a grant by his maternal uncle Śrīvallabha Sēnānandarāja of the Sēndraka family.

14.—*Ind. Ant.* Vol. XIV. p. 330, and Plate. Kāndalgaon (spurious⁵) plates of the 5th year of the reign of the W. Chalukya **Mahārājādhirāja Satyāśraya Pulakēśivallabha (Pulakēśin II.)**:—

(L. 14).—vijayarājya-samva[t*]sarē pañchamē Māghamāsa-saptamyām.

15.—*Ind. Ant.* Vol. VIII. p. 96, and Plate in Vol. IX. p. 304; *Mysore Inscr.* No. 159, p. 298. Hosūr (spurious⁶) plates of the W. Chalukya **Satyāśraya (Pulakēśin II.)**, recording a grant made at the request of his son or daughter (?) **Ambēra** or **Ambērā**:—

(L. 8).—mahā-Māgha-paurṇamāsyāyā . . . sōma-grahanē.

16.—*Ind. Ant.* Vol. VII. p. 106, lines 51-61 of the text. Lakshmēshwar (spurious⁷) inscription⁸ of **Durgasakti**, the son of Kundaśakti who was the son of Vijayaśakti, of the family of the Sēndra kings who belonged to the Bhujagēndra lineage; contemporary (or feudatory) of the W. Chalukya **Mahārāja Ereyya Satyāśraya (Pulakēśin II.)**, the son of the **Mahārāja Raṇaparākramānka**.

17.—*Ind. Ant.* Vol. IX. p. 124, and Plate. Nirpaṇ (spurious⁹) plates of the W. Chalukya **Tribhuvanāśraya Nāgavardhanarāja**, recording a grant made at the request of a certain Balāmma-Thakkura.

¹ The inscription contains numerical symbols for 4, 5, 6(?), 8, and 50.

² The name Chalukya or Chālukya does not occur in the inscription.

³ Read *paurṇamāsyām likhitā prasastir=iti*.

⁴ See *Ind. Ant.* Vol. XXX. p. 217, No. 27.

⁵ In verse apparently called simply Vallabha.

⁶ See *ibid.* p. 222, No. 53.

⁷ See *ibid.* p. 218, No. 37.

⁸ Put on the stone in about the second half of the 11th century A.D.

⁹ See *Ind. Ant.* Vol. XXX. p. 216, No. 28.

In the family of the Chalukyas, Satyāśraya Kīrtivarmanarāja [I.]; his son Pulakēśivallabha (Pulakēśin II., defeated Harsha [of Kanauj]); his younger brother Dharāśraya Jayasimhavarmanarāja; his son Tribhuvanāśraya Nāgavardhanarāja (Jayāśraya?).

18.—*Jour. Bo. As. Soc.* Vol. XVI. p. 235, and Plate. Karnūl district plates of the third year of the reign of the W. Chalukya¹ *Mahārājādhirāja Vikramāditya I. Satyāśraya*, son of the *Mahārāja* Satyāśraya (Pulakēśin II., who defeated Harshavardhana [of Kanauj]), grandson of the *Mahārāja* Kīrtivarman I. (who defeated the kings of Vanavāsi, etc.), and great-grandson of the *Mahārāja* Polekēśivallabha (Pulakēśin I.) :—

(L. 20).—pravarddhamāna-vijayar[ā*]jya-tṛtīya-samvatsarē . . . saṅgama-mahāyātrāyām paurṇamāsyām.

19.—*Jour. Bo. As. Soc.* Vol. XVI. p. 238, and Plate. Karnūl district plates of the 10th year of the reign of the W. Chalukya² *Mahārājādhirāja Vikramāditya I. Satyāśraya* (described as in No. 18); recording a grant made at the request of Dēvasaktirāja of the Sēndraka family :—

(L. 18).—pravarddhamāna-vijayarāja-daśama-samvatsarē Āshāḍa(ḍha)-paurṇamāsyām.

20.—*Ind. Ant.* Vol. VI. p. 76, and Plate; *PSOCI.* No. 13. Haidarābād (spurious³?) plates of the W. Chalukya *Mahārājādhirāja Vikramāditya I. Satyāśraya* (who defeated Narasimha, Mahēndra, and Īśvara or Īśvarapōtarāja⁴ of Kāñchi), the son of the *Mahārājādhirāja* Satyāśraya (Pulakēśin II., who defeated Harshavardhana [of Kanauj]), grandson of the *Mahārāja* Kīrtivarman I., and great-grandson of the *Mahārāja* Pulakēśivallabha (Pulakēśin I.).

21.—*S.* 532 (?).—*Ind. Ant.* Vol. VII. p. 219, and Plate. Kurtakōṭi (now Royal As. Soc.'s, spurious⁵) first and second plates⁶ only of the 16th year of the reign of the W. Chalukya *Mahārājādhirāja Vikramāditya I. Satyāśraya* (described much as in No. 20); issued from Kisuvolal :—

(L. 20).—batrimśōttara-paṁchaśatēshu Saka-varshēshv-ātītēshu vijayarāja-sambachchara-shōsha(ḍa)śa-varshē pravarttamāna . . . tasya Vaiśākha-Jēshthā-māsa-madhyam-amavāsya Bhāskara-dīnē Rōhiṇya-pikshē madhyāhna-kālē . . . Vṛishabha-rāṣau sūryyagrāhaṇa-sarvvamā(gṛā)si(st)bhūtē.

The date is irregular; see *ibid.* Vol. XVIII. p. 285.

22.—*Jour. Bo. As. Soc.* Vol. XVI. p. 240, and Plate. Karnūl district (spurious⁷) plates of the W. Chalukya⁸ *Mahārājādhirāja Vikramāditya I. Satyāśraya* (described much as in No. 18) :—

(L. 12).— . . . p[au*]rṇamāsyā[m*].

23.—*Ind. Ant.* Vol. VII. p. 163, and Plate. Nerūr (now India Office) plates of *Vijaya-bhaṭṭārikā*, the queen of the *Mahārāja* [Chandrāditya], who was the eldest brother of the W. Chalukya Vikramāditya I., son of the *Mahārājādhirāja* Satyāśraya (Pulakēśin II.), etc.; of the 5th year of the reign (of Chandrāditya?) :—

(L. 15).—svarāja-pañchama-ssam(sam)vatsara A(ā)śvayuja-paurṇamāśasya dvitīyāyām vishuvē.

[S. 581]: 23rd September A.D. 659.⁹

¹ The original has *Chale(li)kya*.

² The original has *Chalikya*.

³ See *Ind. Ant.* Vol. XXX. p. 219, No. 39; compare also *Nachrichten Ges. d. Wiss. Göttingen*, 1900, p. 345 ff.

⁴ I.e. the Pallavas Narasimhavarman I., Mahēndravarmān II., and Paramēśvaravarman I.; compare below, Nos. 628 and 634.—In the verses which give the above information, Vikramāditya I. himself is referred to, or described by the epithets or *śirūdas* Anivārta, Vallabha, Śrīvallabha, Raṇarasika and Rājamalla; and the Pallava family is called the Mahāmalla *kula*; compare below, Nos. 627, 629 and 632.

⁵ See *Ind. Ant.* Vol. XXX. p. 217, No. 30.

⁶ Not earlier than the ninth or tenth century A.D.

⁷ The original has *Chalikya*.

⁸ See *ibid.* p. 214, No. 8.

⁹ On this day the second *tithi* of the bright half of Āśvina commenced 4 h. 19 m., and the Tulā-vishuvā-sankrānti took place 9 h. 26 m., after mean sunrise. Compare Dr. Fleet's *Dynasties*, p. 385, note 3.

24.—*Ind. Ant.* Vol. VIII. p. 45, and Plate. Kôchrên plates of Vijayamahâdêvi, the queen of the *Mahârâjâdhirâja Chandrâditya*, who was the eldest brother of the W. Chalukya Vikramâditya I., son of the *Mahârâjâdhirâja Satyâsraya* (Pulakêsin II.), etc. :—

(L. 18).—Vaisâkha-śukla-dvâdasîyâm.

25.—*Ind. Ant.* Vol. XI. p. 67 ; *Jour. Bo. As. Soc.* Vol. XVI. p. 233, and Plate. Karṇûl district plates of the first year of the reign of the W. Chalukya *Mahârâjâdhirâja Âdityavarman*,¹ a son of the *Mahârâjâdhirâja Satyâsraya* (Pulakêsin II., who defeated Harshavardhana [of Kanauj]), grandson of the *Mahârâja Kirtivarman I.*, and great-grandson of the *Mahârâja Satyâsraya* (Pulakêsin I.) :—

(L. 15).—pravardhamâna-vijayarâjya-prathama-samvatsarê Kârttika-paurṇamâsyâm Paitâ-mahî-Hiraṇyagarbha-mahôtsava-samayê.

26.—*Ś. 608.*—*Ind. Ant.* Vol. VII. p. 112. Notice of a Lakshmêshwar (spurious²) inscription³ (fourth part of the record) of the 5th year of the reign of the W. Chalukya *Vinayâditya Satyâsraya*; issued from Raktapura :—

Ashtôttara-shatçhatêshu Śaka-varshêshv=atîtêshu pravarttamâna-vijayarâjya-paṇchama-samvatsarê . . . Mâgha-mâsê paurṇamâsyâm.

27.—*Ś. 611.*—*Ind. Ant.* Vol. VI. p. 86, and Plate; *PSOOL* No. 14; *Jour. Bo. As. Soc.* Vol. XVI. p. 242, and Plate. Togarchêḍu plates of the 10th year of the reign of the W. Chalukya *Mahârâjâdhirâja Vinayâditya Satyâsraya*; issued from Pampâtîrtha :—

(L. 24).—êkâdasôttara-shatçhatêshu Śaka-varshêshv=atîtêshu pravarddhamâna-vijayarâjya-samvatsarê dasamê varttamânê . . . Kârttika-paurṇamâsyâm.

In the family of the Chalukyas, the *Mahârâja Pulakêsinivallabha* (Pulakêsin I.); his son, the *Mahârâja Kirtivarman I.*; his son, the *Mahârâjâdhirâja Satyâsraya* (Pulakêsin II., defeated Harshavardhana [of Kanauj]); his son *Vikramâditya I.* (took Kânchîpura); his son, the *Mahârâjâdhirâja Vinayâditya Satyâsraya*.

28.—*Ś. 613.*—*Ind. Ant.* Vol. VI. p. 89, and Plate; *PSOOL* No. 15. Karṇûl district plates of the 11th year of the reign of the W. Chalukya *Mahârâjâdhirâja Vinayâditya Satyâsraya*, recording a grant made at the request of the *Ywarâja Vijayâditya*; issued from Elumpundale :—

(L. 24).—trayôdasôttara-shatçhatêshu Śaka-varshêshv=atîtêshu pravarddhamâna-vijayarâjya-samvatsarê êkâdasê varttamânê . . . Mâgha-paurṇamâsyâm.

Genealogy as in No. 27.

29.—*Ś. 614.*—*Ind. Ant.* Vol. XIX. p. 149; *PSOOL* No. 16. Sorab plates of the [11th] year of the reign of the W. Chalukya *Mahârâjâdhirâja Vinayâditya Satyâsraya*, recording a grant made at the request of the *Mahârâja Chitravâha*, the son of the Âlupa king Gunasâgara;⁴ issued from Ohitrasedu :—

(L. 18).—[cha]turddasôttara-shatçhatêshu Śaka-varshêshv=atîtêshu pravarddhamâna-vijayarâjya-samvatsarê [êkâ]dasê varttamânê . . . dakshîṇâyan-âbhimukhê bhagavati bhâskarê Rôhîṇî(pî)-nakshatrê Śanaischaravârê.

Savurday, 22nd June A.D. 692; but the *nakshatra* on this day was Âślêshâ or Maghâ, not Rôhîṇî; see *Ind. Ant.* Vol. XXIV. p. 9, No. 160.

Genealogy as in No. 27; but the name of *Satyâsraya* (Pulakêsin II.) is omitted through carelessness.

¹ Compare below, No. 150.

² See *Ind. Ant.* Vol. XXX. p. 218, No. 88.

³ Put on the stone in about the second half of the 11th century A.D.

⁴ See Dr. Hultzsch's *Report* for 1901, p. 5, where we find the names of the Âlupa kings *Rajasâgara*, *Pṛithuvîsâgara*, *Vijayâditya*, etc.

30.—**Ś. 616.**—*Ind. Ant.* Vol. VII. p. 301, and Plate; *PSOOL*. No. 17. Harihar plates of the 14th year of the reign of the W. Chalukya *Mahārājādhirāja Vinayāditya Satyāśraya*, recording a grant made at the request of an Āḷva king; issued from Karañjapetra:—

(L. 23).—shōḍaśōttara-shachchha(ṭchha)tēshu Śaka-varshēshv=atitēshu pravarddhamāna-vijayarājya-samvatsarē chaturddasē varttamānē . . . Kārttikē paurṇamāsyām.
Genealogy as in No. 27.

31.—*Ind. Ant.* Vol. XIX. p. 144, and Plate; *PSOOL*. No. 152. Baḷagāmve Kanarese inscription of the reign of the W. Chalukya¹ *Mahārājādhirāja Vinayāditya Rājāśraya*, and his feudatory, the *Mahārāja* Pogilli of the Sēndraka family.

32.—**Ś. 621.**—*Ind. Ant.* Vol. X. p. 60. Bādāmi Sanskrit and Kanarese² inscription of the third year of the reign of the W. Chalukya¹ *Mahārājādhirāja Vijayāditya Satyāśraya*:—

(L. 5).—pravarddhamāna-vijayarājya-samvatsarē tṛtīyē varttamānē ēkaviṃśōttara-shaṭchhatēshu Śaka-varshēshv=atitēshu Jyē(jyai)shṭhyām paurṇamāsyām.

33.—**Ś. 622.**—*Ind. Ant.* Vol. IX. p. 126. Nerūr (now India Office) plates of the 4th year of the reign of the W. Chalukya³ *Mahārājādhirāja Vijayāditya Satyāśraya*, recording a grant made at the request of a certain Nandēya; issued from Rāsenanagara:—

(L. 30).—dvāviṃśatyuttara-shaṭchhatēshu Śaka-varshēshv=atitēshu pravarddhamāna-vijayarājya-samvatsarē chaturthē varttamānē . . . Āshāḍa(ḍha)-paurṇamāsyām.

Genealogy as far as Vinayāditya Satyāśraya as in No. 27;⁴ his son, the *Mahārājādhirāja Vijayāditya Satyāśraya*.

34.—**Ś. 627.**—*Ind. Ant.* Vol. IX. p. 130. Nerūr (now India Office) plates of the 10th year of the reign of the W. Chalukya³ *Mahārājādhirāja Vijayāditya Satyāśraya*, recording a grant made at the request of a certain Upēndra:—

(L. 29).—saptaviṃśatyuttara-shaṭchhatēshu Śaka-varshēshv=atitēshu pravarddhamāna-vijayarājya-samvatsarē daśamē varttamānē . . . mahā-saptamē(myām ?).⁵

Genealogy as in No. 33.

35.—*Ind. Ant.* Vol. VIII. p. 285, and Plate; *PSOOL*. No. 76. Aihole Kanarese inscription of the third month of the 13th year of the reign of the W. Chalukya¹ *Mahārājādhirāja Vijayāditya Satyāśraya*:—

(L. 2).—trayōdaśa-varshamuṃ mu(mū)ṇu-tīṅgaḷuḷ . . . Āsvayuja-pū[r]ṇamāsaduḷ vishupaduḷ.

[**Ś. 631**]: 23rd September A.D. 709; see *ibid.* Vol. XIX. p. 188.⁶

36.—**Ś. 645.**—*Ind. Ant.* Vol. VII. p. 112. Notice of a Lakshmēshwar (spurious⁷) inscription⁸ (first part of the record) of the 28th year of the reign of the W. Chalukya *Vijayāditya Satyāśraya*; issued from Raktapura:—

⁹ Pañchachatvarīṃśaduttara-shaṭchhatēshu Sa(sa)ka-varshēshv=atitēshu pravarddhamāna-vijayarājya-samvatsarē aṣṭāviṃśē varttamānē . . . Bhādrapada-paurṇamāsyām sarvvagrāsī-chandragrahaṇ-ōpalakshitāyām.

20th August A.D. 723; a total eclipse of the moon, visible in India.

¹ The name Chalukya or Chālukya does not occur in the inscription.

² But the Kanarese part of the inscription is almost entirely illegible.

³ The original has *Chalukya*.

⁴ But Vikramāditya I. is described as the *Mahārājādhirāja* Vikramāditya Satyāśraya.

⁵ Dr. Fleet takes *mahā-saptama* to denote one of the divisions of the seven Koṅkaṇas; see his *Dynasties*, p. 372.

⁶ Dr. Fleet now takes the equivalent of the date to be the 23rd September A.D. 708; see his *Dynasties*, p. 370, note 5, and p. 372.

⁷ See *Ind. Ant.* Vol. XXX. p. 218, No. 38.

⁸ Put on the stone in about the second half of the 11th century A.D.

⁹ From an impression supplied by Dr. Fleet.

37.—**Ś. 651.**—*Ind. Ant.* Vol. VII. p. 112. Notice of a Lakshmêshwar (spurious¹) inscription² (second part of the record) of the 34th year of the reign of the W. Chalukya **Vijayāditya Satyāśraya**, recording a grant to his father's priest Udayadêva-panḍita, also called Niravadya-panḍita, who was the house-pupil of Pūjyapāda; issued from Raktapura:—

Ēkapamchāsāduttara-shaṭchhatêshu Śaka-varshêshv=atitêshu pravartta(rddha)māna-vijayarāja-samvatsarê chatustrimśê varttamânê . . . Phālguna(na)-māsê paurṇamāsyām.

38.—*Ind. Ant.* Vol. X. p. 103, and Plate; *PSOCI.* No. 50. Bādāmi (Mahākūṭa) Kanarese inscription of Vināpoṭi, 'the heart's darling' of the W. Chalukya³ **Mahārājādhirāja Vijayāditya Satyāśraya**.

39.—*Ind. Ant.* Vol. X. p. 165, and Plate; *PSOCI.* No. 53. Paṭṭadakal Kanarese inscription of the W. Chalukya³ **Mahārājādhirājas Vijayāditya and Vikramāditya II.**

40.—*Ind. Ant.* Vol. IX. p. 133. Nerūr (now India Office) plates⁴ of the W. Chalukya **Mahārājādhirāja Vijayāditya Satyāśraya**, apparently recording a grant made by his son, the **Mahārājādhirāja Vikramāditya II. Satyāśraya**.

Genealogy as in No. 33.

41.—**Ś. 656.**—*Ind. Ant.* Vol. VII. p. 106, lines 61-82. Lakshmêshwar (spurious⁵) inscription² of the second year of the reign of the W. Chalukya **Mahārājādhirāja Vikramāditya II. Satyāśraya**, the son of Vijayāditya Satyāśraya, etc.; issued from Raktapura:—

(L. 72).—shaṭpamchāsāduttara-shaṭchhatêshu Śaka-varshêshv=atitêshu pravarddhamāna-vijayarāja-samvatsarê dvitīyê varttamânê Māgha-paurṇamāsyām.⁶

42.—*Ind. Ant.* Vol. VIII. p. 286, and Plate; *PSOCI.* No. 77. Aihole Kanarese inscription of the reign of the W. Chalukya⁷ **Mahārājādhirāja Vikramāditya II. Satyāśraya**.

43.—*Ep. Ind.* Vol. III. p. 360, and Plate. Conjeeveram Kanarese inscription of the W. Chalukya **Mahārājādhirāja Vikramāditya II. Satyāśraya**.

44.—*Ind. Ant.* Vol. X. p. 166, and Plate; *PSOCI.* No. 54. Paṭṭadakal Kanarese inscription; records that **Lōkamahādēvi**, the queen of the W. Chalukya **Vikramāditya II.**, confirmed a grant made by the **Mahārājādhirāja Vijayāditya Satyāśraya**.⁸

45.—*Ind. Ant.* Vol. X. p. 167, and Plate; *PSOCI.* No. 57. Paṭṭadakal Kanarese inscription; mentions **Lōkamahādēvi**, the queen of the W. Chalukya **Vikramāditya II.**

46.—*Ind. Ant.* Vol. X. p. 164, and Plate; *PSOCI.* No. 59. Paṭṭadakal Kanarese inscription; mentions **Lōkamahādēvi**, the queen of the W. Chalukya **Vikramāditya II.**

47.—*Ind. Ant.* Vol. X. p. 164, and Plate; *PSOCI.* No. 58. Paṭṭadakal Kanarese inscription; mentions the queen of the W. Chalukya **Vikramāditya II.**

48.—*Ep. Ind.* Vol. III. p. 4, and Plate. Paṭṭadakal duplicate⁹ pillar inscription of the reign of the W. Chalukya **Mahārājādhirāja Kirtivarman II. Satyāśraya**:—

(L. 22).—Śrāvana-māsê amāvāsyāyām sarvva-grāsê sūryya-grahanê.

¹ See *Ind. Ant.* Vol. XXX. p. 218, No. 38.

² Put on the stone in about the second half of the 11th century A.D.

³ The name Chalukya or Chālukya does not occur in the inscription.

⁴ The authenticity of this grant is doubtful.

⁵ See *Ind. Ant.* Vol. XXX. p. 218, No. 37.

⁶ The date would correspond to the 13th January A.D. 735, when there was a lunar eclipse, visible in India.

⁷ In Nos. 42-47 the name Chalukya or Chālukya does not occur.

⁸ Below the above inscription, on the same pillar, is a short inscription, the language of which appears to be Kanarese, and which seems to record the name of a certain Dhuliprabhu, perhaps a visitor to the temple; see *Ind. Ant.* Vol. X. p. 166, and *PSOCI.* No. 55.

⁹ In northern and in southern characters; compare below, No. 254.

[**Ś. 676**] : 25th June A.D. 754;¹ a total eclipse of the sun, visible in India; see *ibid.* p. 3.

The inscription mentions the *Mahārājādhirāja* Vijayāditya Satyāśraya;² his son, the *Mahārājādhirāja* Vikramāditya [II.] Satyāśraya;³ and his queens (of the Haihaya family) Lōkamahādēvī and her younger sister Trailōkyamahādēvī (the mother of Kīrtivarman II.).

49.—**Ś. 679**.—*Ep. Ind.* Vol. V. p. 202, and Plates. Vakkalēri plates of the 11th year of the reign of the W. Chalukya *Mahārājādhirāja* Kīrtivarman II. Satyāśraya, recording a grant made at the request of a certain Dōsirāja;⁴ issued from Bhaṇḍāragaviṭṭage:—

(L. 61).—ga(na)vasaptatyuttara-shaṭchhatēshu Śaka-varshēshv-atītēshu pravardhamāna-vijayarājya-samvatsarē ēkādaśē varttamānē . . . Bhādrapada-paurṇamāsyām.

Genealogy as far as Vijayāditya Satyāśraya as in No. 33; his son, the *Mahārājādhirāja* Vikramāditya [II.] Satyāśraya (defeated the Pallava Nandipōtavarman⁵); his son, the *Mahārājādhirāja* Kīrtivarman [II.] Satyāśraya.—The inscription mentions [the Pallava] Narasimhapōtavarman.⁶

50.—*Ind. Ant.* Vol. XI. p. 69. Āḍṭr Sanskrit and Kanarese damaged inscription of the reign of the W. Chalukya⁷ *Rājādhirāja* Kīrtivarman II.;⁸ mentions a king Sinda of Pāṇḍipura, and a king Mādhavatti.

51.—*Ep. Ind.* Vol. VI. p. 253, and Plate. Didgūr Kanarese inscription⁹ of the reign of a [W. Chalukya ?] king Kattiyara,¹⁰ under whom a certain Dōsi¹¹ was governing the Banavāsi twelve-thousand province:—

(L. 4).—grahaṇa[do].

52.—*Ind. Ant.* Vol. XX. p. 69, and Plate. Kōṭṭr Kanarese inscription¹² of the time of a Chalukya prince named Parahitarāja; records the ceremony of walking through fire and the death of a Śaiva ascetic named Sambu (Śambhu).

B.—The Rāshtrakūṭas of Mālkhēḍ and Gujarāt (Lāṭa).

53.—**Ś. 675**.—*Ind. Ant.* Vol. XI. p. 111, and Plates. Sāmāgaḍ (now Royal As. Soc.'s) plates of the Rāshtrakūṭa *Mahārājādhirāja* Dantidurgarāja (Dantivarman II.) **Khaḍgavalōka**:—

(L. 30).—paṁchasaptatyadhika-Śakakālasamvatsara-śatashaṭkē vyatītē samvata(t) 675 pai (? pō or pau)hachchhikāyā Māghamāsa-rathasaptamya[m*] tulāpurusha-sthitē . . .

Gōvindarāja [I.]; his son Kakkarāja [I.]; his son Indrarāja [II.]; his son Dantidurgarāja,¹³ conquered Vallabha (*i.e.* the W. Chalukya Kīrtivarman II.), and defeated the Karṇāṭaka army which had defeated Harsha [of Kanauj], Vajraṭa and others.

54.—**Ś. 679**.—*Jour. Bo. As. Soc.* Vol. XVI. p. 106, and Plates. Āntrōli-Chhārōli (in Surat district) plates of the Rāshtrakūṭa *Mahārājādhirāja* Kakkarāja II. of Gujarāt:—

(L. 29).—vishuva-samkrāntau . . .

(L. 36).—Śakanri(nri)pakāl-ātita-samvatsara-śatashaṭkē ēkū(kō)nāsīty-adhikē Āśvayuja-śuddhā(ddhē=n)katē(tō)=pi sam 600 70 9 tithi 7.

¹ This was the new-moon day of the first *pūrṇimānta* Śrāvāṇa (or, by the system of mean intercalation, of the *pūrṇimānta* Śrāvāṇa).

² With the epithet or *viruda* Niravadya (?).

³ He has the epithets or *virudas* Anivārita and Nṛipasimha.

⁴ See below, No. 51.

⁵ *I.e.* Nandivarman; see below, No. 633 ff.

⁶ *I.e.* Narasimhavarman; see below, No. 634.

⁷ The name Chalukya or Chālukya does not occur in the inscription.

⁸ See Dr. Fleet's *Dynasties*, p. 377.

⁹ According to Dr. Fleet "the characters of it are fairly referable to closely about A.D. 800."

¹⁰ Compare below, No. 232.

¹¹ See above, No. 49.

¹² Of about the ninth century A.D.

¹³ In the concluding verse called Dantivarman.

24th September A.D. 757; see *Ind. Ant.* Vol. XXIII. p. 113, No. 2.

Kakkarāja [I.]; his son Dhruvarāja; his son Gōvindarāja, married a daughter of Nāgarman; their son Kakkarāja [II.].—The grant mentions, as *dātuka*, Ādityavarmanarāja.

55.—*Ep. Ind.* Vol. VI. p. 161, and Plate. Hattī-Mattūr Kanarese memorial tablet¹ of the reign of Akālavarsha (Kṛishṇarāja I.).

56.—*Ś. 692.*—*Ep. Ind.* Vol. VI. p. 209, and Plate. Alās plates of the Rāshtrakūṭa Yuvarāja Gōvindarāja II. Prabhūtavarsha Vikramāvalōka, recording a grant made at the request of Vijayāditya Māpāvalōka Ratnavarsha (son of Dantivarman and grandson of Dhruvarāja); issued at the confluence of the rivers Kṛishṇaverṇā and Musī:—

(L. 29).—*shaṭchhatē dvinavaty-adhikē Śaka-varshē Saumya-samva[tsa]rē Āshāḍha-śukla-pakshē saptamyām.*²

Gōvindarāja [I.]; his son Kakkarāja [I.]; his son Indrarāja [II.]; his son Dantivarman [II.],³ vanquished the Karmāṭaka army which had defeated Harsha [of Kanauj], Vajraṭa and others; and conquered Vallabha (*i.e.* the W. Chalukya Kirtivarman II.); after him, Kakkarāja's son Kṛishṇarāja [I.] Śubhatuṅga Akālavarsha; his son Gōvindarāja [II.] (defeated the lord of Vēṅgi).

57.—*Ind. Ant.* Vol. XI. p. 125, and Plate; *PSOCI.* No. 60. Paṭṭadakal Kanarese inscription of the reign of the Rāshtrakūṭa⁴ *Mahārājādhirāja Dhāravarsha Kaliballaha (Kalivallabha Dhruvarāja).*

58.—*Ep. Ind.* Vol. VI. p. 163, and Plate. Naregal Kanarese memorial tablet⁵ of the reign of Dōra (*i.e.* Dhōra, Dhruvarāja), and of his feudatory Mārakkarasa.

59.—*Ep. Ind.* Vol. VI. p. 166, and Plate. Lakshmēshwar Kanarese inscription⁶ of the reign of Śrīballaha (Śrīvallabha, according to Dr. Fleet in all probability Dhruvarāja).

60.—*Inscr. at Śravaṇa-Belgoḷa*, No. 24, p. 3. Fragmentary Kanarese inscription of the *Mahāśāmantādhipati Kambayya (Stambha?) Raṇāvalōka*, a son of [the *Mahārājādhirāja*] Śrīvallabha (Dhruvarāja ?).⁷

61.—*Ś. 716.*—*Ep. Ind.* Vol. III. p. 105, and Plate. Paiṭhaṇ plates⁸ of the Rāshtrakūṭa *Mahārājādhirāja Gōvindarāja III. Prabhūtavarsha*, issued from outside Pratiśṭhāna.—

(L. 60).—*Śakanripakāl-ātita-samvatsara-sa(śa)tēshu saptamu(su) jē(shō)ḍaś-ōttarēshu Vaisākha-va(ba)hul-āmāvāsyaṁ=ādityagrahaṇa-parvvaṇi.*

4th May A.D. 794; a solar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 131, No. 107.

Genealogy from Gōvindarāja [I.] to Dantidurgarāja as in No. 53;¹⁰ after him, Kakkarāja's son Kṛishṇarāja [I.] Śubhatuṅga Akālavarsha (defeated Rāhappa); his son Gōvindarāja [II.] Vallabha; his younger brother Dhruvarāja Nirupama Dhāravarsha; his son Gōvindarāja [III.] Prabhūtavarsha.

62.—*Ś. 726.*—*Ind. Ant.* Vol. XI. p. 126, and Plate. Kanarese country (formerly Sir W. Elliot's, now British Museum) Kanarese plates of the Rāshtrakūṭa⁴ *Mahārājādhirāja Gōyinda (Gōvindarāja III.) Prabhūtavarsha*:—

(L. 1).—*Śakanripakāl-ātita-samvatsaramga[ḷ]=ēl-nūṛ-i(i)rpatt-āṇaneyā Subhānu embhā(mbā) varshadā Vaisā(śā)khamāsa-kṛishṇapaksha-pañohamē(mi)-Bṛihaspatī(ti)vāram=āgi(gi).*

¹ By Dr. Fleet assigned to about A.D. 765.

² Also called Vallabharāja.

³ By Dr. Fleet assigned to about A.D. 78

⁴ By Dr. Fleet assigned to about A.D. 7

⁵ See Mr. Rice in *Ep. Carn.* Vol. IV. Introduction, p. 5; Dr. Fleet in *Ep. Ind.* Vol. VI p. 195.

⁶ Compare *Ind. Ant.* Vol. XXX. p. 515.

⁷ But the name of Kakkarāja is spelt here *Karkarāja*, and Dantidurgarāja is also called Vallabharāja.

⁸ This date fell in A.D. 770, not in 769.

⁹ The name Rāshtrakūṭa does not occur in the inscription.

¹⁰ Compare below, No. 68.

Thursday, 4th April A.D. 804; see *ibid.* Vol. XXIII. p. 122, No. 55.

The grant gives the name of Gōvinda's queen, Gāmuṇḍabbe; states that he had conquered Dantiga¹ of Kāñchi; and records the renewal of a grant made by [the W. Chalukya] Kīrti-varman [II.].

63.—**Ś. 730***.—*Ind. Ant.* Vol. XI. p. 157, and Plates. Wapi (in Nāsik district, now Bombay As. Soc.'s) plates² of the Rāshtrakūṭa *Mahārājādhirāja* Gōvindarāja III. Prabhūtavārsha, issued from Mayūrakhaṇḍī:—

(L. 46).—Śakanripakāl-ātita-samvatsara-śatēshu saptasu trim(trim)śad-adhikēshu Vyaya-samvatsarē Vaisākha-sita-paurṇamāsī-somagrahāṇa-mahāparvvaṇi.

The date is irregular;³ see *ibid.* Vol. XXIV. p. 11, No. 172.

Genealogy, *etc.*, substantially as in No. 64.

64.—**Ś. 730**.—*Ep. Ind.* Vol. VI. p. 242, and Plate; *PSOI.* No. 281. Rādhampur first and second plates only of the Rāshtrakūṭa *Mahārājādhirāja* Gōvindarāja III. Prabhūtavārsha, issued from Mayūrakhaṇḍī:—

(L. 53).—Śa[ka*]ripakāl-ātita-samvatsara-śatēshu saptasu trim(trim)śad-uttarēshu Sarvajin-nāmnī samvat[sa]rē Śrāvāṇa-va(ba)hula-a(1-ā)māvāsyām sūryagrahāṇa-parvvaṇi.

27th July A.D. 808; a solar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 131, No. 108.

Krishnarāja [I.], called Vallabha (took Fortune away from the Chālukya family); his son Dhōra (Dhruvarāja) Nirupama Kalivallabha Dhārāvārsha (set aside his eldest brother [Gōvindarāja II.], imprisoned the Gaṅga, subdued the Pallava, defeated Vatsarāja⁴); his son Gōvindarāja [III.] Prabhūtavārsha (defeated a coalition of twelve princes, released but re-imprisoned the Gaṅga, defeated the Gūrjara, subdued the Mālava, reduced king Mārāśarva,⁵ conquered the Pallavas, and gave orders to the lord of Vēṅgī).

65.—**Ś. 734**.—*Ind. Ant.* Vol. XII. p. 158, and Plates. Baroda (now British Museum) plates of the Rāshtrakūṭa *Mahāsāmantādhipati* Karkarāja⁶ Suvarṇavarsha of Gujārāt,⁷ issued from Siddhaśamī:—

(L. 52).—Śakanripakāl-ātita-samvatsara-śatēshu saptasu ścha(cha)tustriśa[d-ādhikē]shu mahā-Vaisākhyām.

Gōvindarāja [I.]; his son Karkarāja [I.]; his son Krishnarāja [I.] (assumed the government after uprooting a relative of his); his son Dhruvarāja; his son Gōvindarāja [III.], called Śrīvallabha; his brother, Indrarāja, was made by him ruler of Lāṭa (*Lāṭīśvara-maṇḍala*); Indrarāja's son Karkarāja.—The grant mentions, as *dūtaka*, the *rāja-putra* Dantivarman.

66.—**Ś. 735***.—*Ind. Ant.* Vol. XII. p. 13, and Plates; *Ep. Ind.* Vol. IV. p. 340. Kadaba (now Bangalore Museum) plates⁸ of the Rāshtrakūṭa *Rājādhirāja* Prabhūtavārsha (Gōvindarāja III.), recording a grant which at the request of the Gaṅga chief Chākirāja was made to the Jaina *muni* Arkakīrti (the disciple of Vijayakīrti who was the disciple of Kūli-āchārya) for having warded off the evil influence of Saturn from Chākirāja's sister's son Vimalāditya (the son of Yaśōvarman and grandson of Balavarman of the Chālukya family, and governor of the Kunuṅgīl district); issued from Mayūrakhaṇḍī:—

(L. 83).—Śakanripa-samvatsarēshu śara-śikhi-munishu vyatitēshu J[y*]ēshphamāsa-śuklapaksha-daśamyām Pushya-nakshatrē Chandravārē.

¹ Perhaps the Dantivarman of No. 652.

² Compare *Ind. Ant.* Vol. XXXI. p. 217.

³ The date would be correct for Ś. 737 current, the year Vijaya.

⁴ Or 'the king of the Vatsas.'

⁵ Compare below, No. 122.

⁶ In the signature of the grant the name is spelt *Karkarāja*.

⁷ The original has 'lord of Lāṭa' (*Lāṭīśvara*).

⁸ Read 'striśad'.

The authenticity of this grant is considered doubtful.—The description of the boundaries, *etc.*, is in Kanarese.

Monday, 24th May A.D. 812;¹ see *Ind. Ant.* Vol. XXIV. p. 9, No. 161.

Gōvindarāja [I.]; his son Kakkarāja [I.]; his son Ind[r*]arāja [II.]; his son Vairamēgha [Dantidurga]; his father's brother Akālarsha Kappēsvara [Kṛishnarāja I.]; his son Prabhūta-varsha [Gōvindarāja II.]; his younger brother Dhāravarsha Vallabha [Dhruvarāja]; his son Prabhūtavarsha [Gōvindarāja III.], also called Vallabhendra.

67.—*Ś. 735.*—*Ep. Ind.* Vol. III. p. 54, and Plate. Tōrkhdē (in Khândēsh district) plates of the reign of the Rāshtrakūṭa² *Mahārājādhirāja* Gōvindarāja III. Prabhūtavarsha, and the time of his nephew and feudatory Gōvindarāja of Gujarāt; recording a grant of the latter's subordinate, the *Mahāsāmanta* Buddhavarasa (the son of Rājāditya and grandson of Manināga) of the Śalukika family:—

(L. 1).—Śakanripakāl-ātita-samvatsara-śatēshu saptasu pañchatrīm(triṃ)śaty(d)-adhikēshu Pausha-suddha-saptamyām-aṅkatō=pi samvatsara-śatāni 735 Nandana-samvatsarē Pausahaḥ śuddha-tithih 7 asyām samvatsara-māsa-paksha-divasa-pūrvvāyām . . .

(L. 43).—vijaya-saptamyām.

Sunday, 4th December A.D. 813; see *Ind. Ant.* Vol. XXV. p. 345, No. 1.

Prabhūtavarsha Gōvindarāja [III.] Jagattuṅga³ [I.]; his brother, Indrarāja, was made by him ruler of Lāṭa (*Lāṭēsvara-maṇḍala*); Indrarāja's son Karkarāja; his younger brother Gōvindarāja.

68.—*Ś. 738.*—*Jour. Bo. As. Soc.* Vol. XX. p. 135. Nausāri (now Bombay As. Soc.'s) plates of the Rāshtrakūṭa *Mahāsāmanta* *dhipati* Karkarāja⁴ *Suvarṇavarsha* of Gujarāt, issued from Khēṭaka:—

(L. 67).—Śakanripakāl-ātita-samvatsara-śatēshu saptasv-ashṭatrinśad-⁵adhikēshu Māgha-suddha-paurṇamāsyām | chandragrahaṇa-parvvanī.

5th February A.D. 817;⁶ a lunar eclipse, visible in India.

Genealogy from Gōvindarāja [I.] to Gōvindarāja [II.] Vallabha as in No. 61; his younger brother Dhruvarāja; his son Gōvindarāja [III.] Prithvivallabha (defeated Stambha⁷ and other kings); his son Mahārāja-Śarva Amōghavarsha [I.]; his paternal uncle Indrarāja ruled Lāṭa (*Lāṭiyam maṇḍalam*), given to him by his master;⁸ his son Karkarāja.

69.—*Ś. 749.*—*Ind. Ant.* Vol. V. p. 145; *PSOI.* No. 282. Kāvī plates of the Rāshtrakūṭa *Mahāsāmanta* *dhipati* Gōvindarāja Prabhūtavarsha of Gujarāt, issued from Bharukachchha:—

(Plate iii. l. 7).—Śakanripakāl-ātita-samvatsara-[sapta]śatēshv-ēkāmnapañchāsat-samadhikēshu mahā-Vaiśākhyām.

Genealogy from Gōvindarāja [I.] to Gōvindarāja [III.] as in No. 68; his brother, Indrarāja, was made by him ruler of Lāṭa (*Lāṭēsvara-maṇḍala*); Indrarāja's son Karkarāja; his younger brother Gōvindarāja.

70.—*Ś. 757.*—*Ind. Ant.* Vol. XIV. p. 199, and Plates. Baroda third and fourth plates⁹ only of the Rāshtrakūṭa *Mahāsāmanta* *dhipati* Dhruvarāja I. Dhāravarsha Nirupama of Gujarāt, issued from Sarvamaṅgalāsattā outside Khēṭaka:—

(L. 36).—Śakanripakāl-ātita-samvatsara-śatēshu saptasu saptapañchāśad-adhikēshu Kārtika-suddha-pañchadaśyām mahā-Kārtiki-parvvanī.

[Kṛishnarāja I.]; his son Gōvindarāja [II.] Vallabha; his younger brother Dhruvarāja; his son Gōvindarāja [III.]; his son Mahārāja-Śarva [Amōghavarsha I.]; his paternal uncle

¹ But the *nakshatra* is irregular.

² The name Rāshtrakūṭa does not occur in the inscription.

³ The name here (in verse) is spelt *Jagattuṅga*.

⁴ In the signature the name is spelt *Kakkarāja*.

⁵ Read *trīṃśad*.

⁶ This, by the rules of mean intercalation, was the full moon day of the second Māgha, otherwise of Phālguna.

⁷ Compare above, No. 60.

⁸ *Viz.* Gōvindarāja III.

⁹ The second of these two plates has four notches, and the first three, on the lower edge.

Indrarāja; his son Karkarāja (after defeating some Rāshtrakūṭas, placed Amōghavarsha on his throne); his son Dhārāvarsha Nirupama Dhruvarāja [I.].

71.—*Archæol. Surv. of West. India*, Vol. V. p. 87. Ellōrā Daśavatāra cave-temple fragmentary inscription of the Rāshtrakūṭa kings; contains the names of Dantivarman [I.], Indrarāja [I.], Gōvindarāja [I.], Karkarāja [I.], Indrarāja [II.], Dantidurgarāja,¹ and Mahārāja-Śarva [Amōghavarsha I.].

72.—*Ś. 765 (?)*.—*Ind. Ant.* Vol. XIII. p. 136. Kaṇheri inscription of the reign of the Rāshtrakūṭa² Mahārājādhirāja Amōghavarsha I., and of the time of his feudatory, the [Śīlāra] Mahāsāmanta Pullaśakti, the successor of Kapardin I., 'the lord of Koṅkaṇa : '—

(L. 5).—samva [765].

73.—*Ś. 775 (for 773)*.—*Ind. Ant.* Vol. XIII. p. 134. Kaṇheri inscription of the reign of the Rāshtrakūṭa³ Mahārājādhirāja Amōghavarsha I., the successor of Jagattuṅga I. (Gōvindarāja III.), and of the time of his feudatory, the [Śīlāra] Mahāsāmanta Kapardin II., the successor of Pullaśakti, 'lord of the whole Koṅkaṇa : '—

(L. 1).—Śakanripakāl-ātita-samvatsara-śatēshu saptasu pañchasaptatishv-amkataḥ [api samva]tsaraśaḥ 775 tad-antarggata-Prajāpati-sasva(mva)tsarāntahpāti-Āśvina-va(ba)hula-dvitiyā[yām Budha]-dinē asyām samva[tsara]-māsa-paksha-di-vasa-pūrvāyām tithau.

Wednesday, 16th September A.D. 851; see *ibid.* Vol. XXIV. p. 4, No. 139.

74.—*Ś. 782*.—*Ep. Ind.* Vol. VI. p. 29. Konnūr spurious inscription⁴ of the Rāshtrakūṭa Mahārājādhirāja Amōghavarsha I. Vira-Nārāyaṇa, the successor of Jagattuṅga I. (Gōvindarāja III.), recording a grant to the Jaina Dēvēndra, made by the king, while residing at his capital of Mānyakhēṭa, at the request of his feudatory Baṅkēśa⁵ (Baṅkēya, Baṅkēyarāja) alias Sellakēṭana, the son of Adhōra (or Ādhōra) and grandson of Eṇakōri, of the Mukula family. The inscription professes to be a copy (prepared⁶ by the agency of Vīranandin, the son of Mēghachandra-traividya⁷) of a copper-plate charter. The date of the grant is :—

(L. 43).—Śakanripakāl-ātita-samvatsara-śatēshu saptasu dvā(dvya)śīty-adhikēshu tad-abhyadhika-samanantara-pravarttamāna-trayōśītita-⁸ Vikrama-samvatsar-āntarggat-Āśvayuja-paurṇamāsyām sarvvagrāsi-sōmagrahaṇē mahā-parvvani.

3rd October A.D. 860; a total eclipse of the moon, visible in India; see *ibid.* p. 26.

Before Amōghavarsha the inscription mentions, in the Yādava lineage of the Rāshtrakūṭas, Gōvinda, son of Pricchhakarāja; Karkara, son of king Indra; his son Dantidurga; Śubhatuṅgavallabha Akālavarsha; Prabhūtavarsha, son of Dhārāvarsha; his son Prabhūtavarsha Jagattuṅga.

75.—*Ś. 788*.—*Ep. Ind.* Vol. VI. p. 102, and Plate. Nīlgund Sanskrit and Kanarese inscription of the 52nd year of the reign of the Mahārājādhirāja Amōghavarsha I. Nripatuṅga, also called Atiśayadhavala, born in the race of the Rāṭṭas, 'supreme lord of the town of Lattalūra : '—

(L. 18).—Śakanripakāl-ātita-samvatsara-śata[m]gaḥ=ēl-n[ūṇ-ēnbhatt-ēṇṭa]neya Vyaya[samva]tsara[m] pra[va]rttise [śrī]ma[d-A]mōghava[rsha]-Nri[pa]tu[m]ga-[nām-āmkitanā vijayarā]jya-pravarddhamāna-samvatsa[ra]n[ga]ḥ=ayva[tt-ēraḍum=uttar-ō]ttaram [rājya-

¹ He defeated the army of Vallabha (*i.e.* the W. Chalukya Kirtivarman II.) and others, and acquired the position of Śrīvallabha (*śrīvallabhatām=avāpa*).

² The name Rāshtrakūṭa does not occur in the inscription.

³ See below, No. 302 ff.

⁴ The inscription contains a verse and a prose passage in Kanarese.

⁵ Baṅkēśa invaded Gaṅgavāḍi, took the fort of Kēḍala, put to flight the ruler of Talavanapura and, after crossing the Kāvēri, conquered the enemy's country.

⁶ About the middle of the 12th century A.D.

⁷ See below, Nos. 387 and 408.

⁸ Read -tryaśītita-.

ābhivṛddhi sal|u[tt-i]re . . . ta[d-a]ntarggata-Jyêshṭha(shṭha)-māsada kṛish[n]a-pakshad-
amāseyu[m] sūryya-grahānamum=āgi . . . ā grahāṇado[1].

[Sunday],¹ 16th June A.D. 866; a solar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 123, No. 59.

Before Amôghavarsha the inscription eulogizes Nirupama Kalivallabha [Dhruvarāja], and Prabhūtavarsha Gōvindarāja [III.] Jagattuṅga [I.] Kīrti-Nārāyaṇa.

76.—**Ś. 788.**—*Ind. Ant.* Vol. XII. p. 218. Śīrūr Sanskrit and Kanarese inscription of the 52nd year of the reign of the *Mahārājādhirāja* Amôghavarsha I. Nṛipatuṅga.

The date, etc., are practically the same as in No. 75.²

77.—**Ś. 789.**—*Ind. Ant.* Vol. XII. p. 181. Bagumrā (now Vienna Oriental Museum) plates of the Rāshtrakūṭa *Mahāsāmantādhipati* Dhruvarāja II. Dhāravarsha Nirupama of Gujarāt, issued from Bhṛigukachchha :—

(L. 64).—Śakanipakāl-ātita-saṁvatsara-śatêshu saptasv=êku(kô)nanavaty-adhikêshv-
amkataḥ saṁvat 789 Jyêshṭh-āmavāsyāyām ādityagrahāṇa-parvvaṇi.

6th June A.D. 867; a solar eclipse, visible in India; see *ibid.* Vol. XXIII. p. 131, No. 109.

Genealogy from Gōvindarāja [I.] to Indrarāja, the ruler of Lāṭa, as in No. 68; his son Kakkarāja (after defeating some Rāshtrakūṭas, placed Amôghavarsha on his throne); his son Nirupama Dhruvarāja [I.]; his son Akālavarsha Śubhatuṅga; his son Dhāravarsha Nirupama Dhruvarāja [II.] (defeated Mihira).—The grant mentions, as *dātaka*, Gōvindarāja, a son of Śubhatuṅga and younger brother of Dhāravarsha Nirupama [Dhruvarāja II.].

78.—**Ś. 789.**—*Ep. Ind.* Vol. VI. p. 287, and Plates. Gujarāt (now Dr. Bhandarkar's) plates³ of the Rāshtrakūṭa *Mahāsāmantādhipati* Talaprahārīn Dantivarman Aparimitavarsha, the younger brother of Dhruvarāja II., of Gujarāt, recording a grant made, after bathing in the river Pūrāvī, in favour of a *vihāra* (or Buddhist monastery) :—

(L. 65).—Śakanipakāl-ātita-saṁvatsara-śatêshu sa[pta]su navāśīty-adhikêshv=amkatô=pi
saṁvatsara-śatê 789 Pausa-va(ba)hula-navamyām(myâ)m=uttarāyana-mahāparvvaṇam=uddiśya.⁴

23rd December A.D. 867.

Genealogy as far as Dhruvarāja [II.] as in No. 77;⁵ his younger brother (the son of Akālavarsha) Aparimitavarsha Dantivarman.—The grant is signed by both Dantivarman and Dhruvarāja [II.].

79.—**Ś. 797.**—*Jour. Bo. As. Soc.* Vol. X. p. 194; *PSOOL.* No. 88. Saundatti Sanskrit and Kanarese Raṭṭa inscription, recording several grants. Date⁶ of the time of the Raṭṭa *Mahāsāmanta* Prithvirāma⁷ (the son of Meṇḍa), a feudatory of the Rāshtrakūṭa Kṛishnarāja [II.P.] :—

(L. 12).—Sapta-sa(śa)tyā navatyā cha samāyukt[é*]su(shu) saptasu Sa(śa)ka-kālêśv(shv)=
atitêshu Manmath-āhvaya-vatsarê ||

(For another date in the same inscription see below, No. 201.)

80.—**Ś. 799.**—*Ind. Ant.* Vol. XIII. p. 135. Kanheri inscription of the reign of the Rāshtrakūṭa⁸ *Mahārājādhirāja* Amôghavarsha I., and of the time of his feudatory, the [Śīlāra] *Mahāsāmanta* Kapardin II., 'the lord of Koṅkaṇa' :—

(L. 1).—Śakanipakāl-ātita-saṁvatsara-śatêshu saptasu navanavaty-adhikêshv=amkataḥ 799.

¹ See No. 76.

² Compare *Ind. Ant.* Vol. XXXI. p. 254.

³ But the date actually quotes the week-day (*Ādityavāra*).

⁴ Read *parv=ōddiśya*.

⁵ The defeat of Mihira by Dhruvarāja II. is not mentioned here.

⁶ According to Dr. Fleet, this date is plainly not authentic, so far, at least, as Prithvirāma is concerned; see his *Dynasties*, p. 411, note 1, and p. 552.

⁷ He is described as the disciple of Indrakīrtisvāmīn, the disciple of Guṇakīrti who was the disciple of Muḷlabhaṭṭāraka.—Compare also below, No. 142.

⁸ The name Rāshtrakūṭa does not occur in the inscription.

81.—*Ś. 810.*—*Ind. Ant.* Vol. XIII. p. 66, and Plates. Bagumrā (now Vienna Oriental Museum) plates¹ of the Rāshtrakūṭa *Mahāsāmāntādhipati* **Kṛishṇarāja Akālavarsha** of Gujārāt, issued from Ankūlēsvara :—

(Plate iib, l. 11).—*Śakanripakāl-ātita-samvatsara-śatēshv=ashtasu* *daś-ōttarēshu* Chaitrē-māvāsya[yām] sūryagrahāṇa-parvati.

15th April A.D. 888; a solar eclipse, visible in India; see *ibid.* Vol. XXIII. p. 123, No. 60.

The grant first treats of the kings from Gōvindarāja [I.] to [Nirupama Dhruvarāja II.] as No. 77; it then mentions [the latter's younger brother] Dantivarman,² and after him [his son?] Akālavarsha Kṛishṇarāja.

82.—*Ś. 822* (for 824).—*Ind. Ant.* Vol. XII. p. 221, and Plate in Vol. XI. p. 127; *PSOCI.* No. 85. Nandwāḍige Kanarese inscription of the reign of the Rāshtrakūṭa³ **Mahārājādhirāja Akālavarsha (Kṛishṇarāja II.)** :—

(L. 1).—*Śakanripakāl-ātita-samvatsara[aṁga]=eṇṭu-nūṇa*]-*ippatt-erāṇeya* Dundubhiy-emba varisha[rū] prava[r*]ttise tadva[r*]sh-ābhyantra-Māgha-su(śu)ddha-paṇchamiyūn Briha[s*]pativārāḍ=andu[rū] Uttarāshāḍa(dhā)-nakshatramūn Siddhiy-emba [yōgamu]m-āge.

Thursday, 6th January A.D. 903;⁴ see *ibid.* Vol. XXIV. p. 9, No. 162.

83.—*Ś. 824.*—*Jour. Bo. As. Soc.* Vol. X. p. 190. Mulgund fragmentary inscription of the reign of the Rāshtrakūṭa⁵ king **Kṛishṇavallabha (Kṛishṇarāja II.)** :—

(L. 2).—*Śakanripakāl-ē=shṭha(shṭa)-śatē* chaturuttaravimśad(ity)-uttarē sampragatē Dundubhi-nāmani varshē pravarttamānē.

84.—*Ś. 832.*—*Ep. Ind.* Vol. I. p. 53. Kāpaḍvapaj (in Kaira district) plates of the Rāshtrakūṭa⁶ **Akālavarsha Śubhatuṅga (Kṛishṇarāja II.)**, and his feudatory, the *Mahāsāmānta* **Prachanḍa**, the son of Dhavalappa, of the race of Brahmapaka :—

(L. 60).—*Śaka-samvat* 832 *Vaiśākha-suddha-paurṇamāsyām mahā-Vaiśākhyān.*

Śubhatuṅga Kṛishṇarāja [I.]; his son Nirupama Dhruvarāja; his son Gōvindarāja [III.]; his son Mahārāja-Shaṇḍa [Amoghavarsha I.]; his son Akālavarsha Śubhatuṅga [Kṛishṇarāja II.], called Vallabharāja.

In the race of Brahmapaka there was Kumbaḍi; his son Dēgaḍi; his son Rājaharsha Dhavalappa; his sons Prachanḍa, Akkuva (Akkuka) and Sella-Vidyādhara.

85.—*Ś. 831* (for 833).—*Ind. Ant.* Vol. XII. p. 222, and Plate in Vol. XI. p. 127; *PSOCI.* No. 79. Aihole Sanskrit and Kanarese inscription of the reign of the Rāshtrakūṭa⁷ **Kannara (Kṛishṇarāja II.)** :—

(L. 1).—*Śakanripakāl-āti(tī)ta-samvatsara-śatamga*]-*eṇṭu-nūṇa-vu(mā)vatt-o[n] d a n e y ā* *Prajāpati-y-emba samvatsara[rū*] pravarttise.*

86.—*Ś. 836.*—*Jour. Bo. As. Soc.* Vol. XVIII. p. 257, and Plates. Bagumrā⁸ plates of the Rāshtrakūṭa *Mahārājādhirāja* **Indrarāja III. Nityavarsha**, the successor of the *Mahārājādhirāja* **Kṛishṇarāja II. Akālavarsha**, residing at Mānyakhēṭa; issued from Kurundaka; (composed by Trivikramabhaṭṭa, the son of Nēmāditya) :—

(L. 52).—*Śakanripakāl-ātita-samvatsara-śatēshv=ashtasu* *shattriṁśad-uttarēshu* *Yuva-samvatsara-Phālguna-suddha-saptamyām sampannē śrī-paṭṭava(ba)ndh-ōtsavē.*

In the Sātyaki family of the lineage of the Yadus (sprung from the Moon), Dantidurga (conquered the Chālukyas, took Kāñchī, etc.); his paternal uncle Kṛishṇarāja [I.]; his son

¹ This grant is very incorrect and full of omissions.

² See above, No. 78.

³ The name Rāshtrakūṭa does not occur in the inscription.

⁴ But the *nakshatra* and the *yōga* are irregular.

⁵ Nos. 86 and 87 are spoken of as "Nausāri plates," but they were found at Bagumrā; compare *Zeitschr. D. Morg. Ges.* Vol. XL. p. 322.

Nirupama [Dhruvarāja]; his son Jagattuṅga [I. Gōvindarāja III.]; his son Śrīvallabha Vīra-Nārāyaṇa [Amōghavarsha I.] (defeated the [E.] Chalukyas); his son Kṛishṇarāja [II.]; his son Jagattuṅga [II.], married Lakshmi, the daughter of the Chēdi Raṇavigraha who was a son of Kōkkalla of the Hailuaya family; their son Indrarāja [III.]¹ (uprooted Mēru²).

87.—Ś. 836.—*Jour. Do. As. Soc.* Vol. XVIII. p. 261, and Plates. Other Bagumrā plates of the Rāshtrakūṭa *Mahārājādhirāja* Indrarāja III. Nityavarsha, of the same date as, and, excepting the formal part of the grant, identical with, No. 86.

88.—Ś. 838.—*Ind. Ant.* Vol. XII. p. 224. Hattī-Mattūr Kanarese inscription³ of the reign of the Rāshtrakūṭa⁴ *Mahārājādhirāja* Nityavarsha (Indrarāja III.), recording a grant by the *Mahāśmanta* Leṇḍeyarasa :—

(L. 3).—Sa(śa)kabhūpālakā[-ā*]krānta-saṁ[va*]tsara-Prabā(bha)v-ādi-nāmadē(dhē)ṇam-uttama-madhyama-jaghanya-pa(pha)lādā(da)-prabhṛitigaḷ=ēṇṭu-nūra-mūvatt-eṇṭe (uṭa)neya Dhātu-saṁvatsar-[-ā*]ntarggata.

89.—Ś. 840.—*Ind. Ant.* Vol. XII. p. 223. Daṇḍāpur Kanarese inscription of the reign of the Rāshtrakūṭa⁴ *Prabhūtavarsha* (Gōvindarāja IV.) :—

(L. 2).—ēṇṭu-nūra-nālvatt=avu tā || Śaka-kālaṅgaḷ=varshaṁ prakāṭam pesarim Pramāthi varttise dinapaṁ makarakke varppa saṁkramaṇa-kāladol=kūḍe banda Paushada tithiyol⁵

90.—Ś. 851.—*Ind. Ant.* Vol. XII. p. 211, No. 48; see *ibid.* p. 249. Date of a Kaḷas Kanarese inscription of Gojjigadēva (Gōvindarāja IV.) :⁶—

(L. 22).—[Śa]ka-varsha 851neya Vikṛita-saṁvatsarada Māghada punṇamey=Ādityavāram-Āślēsha(shā)-nakshatrado(?)l(?) sōma-grahaṇam samanise tuḷā-pu[rusham=i?]]ḍu tatsamayadol.

Sunday, 17th January A.D. 930; a lunar eclipse, visible in India; see *ibid.* Vol. XXIII. p. 114, No. 7.

91.—Ś. 852.—*Ep. Ind.* Vol. VII. p. 36, and Plates. Cambay plates of the Rāshtrakūṭa *Mahārājādhirāja* Gōvindarāja IV. Suvarṇavarsha, (described as) the successor of the *Mahārājādhirāja* Nityavarsha (Indrarāja III.), settled at his capital Mānyakhēṭa :⁷—

(L. 44).—Śakanripakāl-ātita-saṁvatsara-satēshv=ashtasu dvāpañchāśad-adhikēshv=aṅkatō=pi Śaka-saṁvat 852 pravarttamāna-Khara-saṁvatsar-āntarggata-Jyēshṭha-suddha-daśamyām Sōma-dinē Hasta-saṁvatsarē chandramasi.

Monday, 10th May A.D. 930; see *ibid.* p. 28.

In the family of the Yadus (sprung from the Moon), Dantidurgarāja; his paternal uncle Kṛishṇarāja [I.]; his son Gōvindarāja [II.]; his younger brother Iddhatējas Nirupama [Dhruvarāja]; after him, Jagattuṅga [I. Gōvindarāja III.]; his son Amōghavarsha [I.] (defeated the [E.] Chālukyas at Vingavalli); his son Akālavarsha [Kṛishṇarāja II.] (conquered Khēṭaka), married a daughter of Kōkkala; their son Jagattuṅga [II.], married Lakshmi, the daughter of Kōkkala's son Raṇavigraha; their son Indrarāja [III.] (uprooted Mahōdaya), married Vijāmbā, the daughter of Ammapadēva who was the son of Kōkkalla's son Arjuna; their son Gōvindarāja [IV.] Prabhūtavarsha Suvarṇavarsha.⁸

¹ Also called Raṭṭa-Kandarpa and Kirti-Nārāyaṇa.

² *I.e.*, probably, Mahōdaya; see below, No. 91.

³ This inscription is followed on the same stone by another Kanarese inscription, of the 11th or 12th century A.D., recording private grants.

⁴ The name Rāshtrakūṭa does not occur in the inscription.

⁵ See Dr. Fleet in *Ep. Ind.* Vol. VI. p. 177, note 7.

⁶ See Dr. Fleet *ibid.* p. 177.

⁷ But, when making the grant, the king had gone to Kapitthaka on the Gōdāvarī for the festival of the *paṭṭabandha*.

⁸ Also called Sāhasāṅka, Nitya-Kandarpa, Vikrānta-Nārāyaṇa, etc.

92.—*Ś. 855.*—*Ind. Ant.* Vol. XII. p. 249, and Plates. Sānglī (now Sāwantwādī) plates¹ of the Rāshtrakūṭa *Mahārājādhirāja* Gōvindarāja IV. *Suvarṇavarsha* (described as) the successor of the *Mahārājādhirāja* Nityavarsha (Indrarāja III.), residing at Mānyakhēṭa :—

(L. 44.)—Śakanripakāl-ātita-saṁvatsara-satēshv-ashṭasu pañchapañchāśad-adhikēshv-amkatō=pi saṁvatsaraṇām 855 pravarttamāna-Vijaya-saṁvatsar-āntarggata-Śrāvapa-paurṇamāsyaṁ vārē Gurōḥ Pūrvvābhadrāpadā-nakshatrē.

Thursday, 8th August A.D. 933; see *ibid.* Vol. XXIII. p. 114, No. 8.

Genealogy, etc., substantially as in No. 91.

93.—*Ś. 862.*—*Ep. Ind.* Vol. V. p. 192, and Plate. Dēōlī (in Wardhā district) plates of the Rāshtrakūṭa *Mahārājādhirāja* Kṛishnarāja III. *Akālavarsha*, the successor of the *Mahārājādhirāja* Amōghavarsha III., recording a grant made for the spiritual benefit of the king's younger brother Jagattuṅga III.; issued from Mānyakhēṭa :—

(L. 47.)—Śakanripakāl-ātita-saṁva[tsa]ra-satēshv-ashṭasu dvisha[shṭya-a]dhikē[shu] Śārvvari-saṁ[vatsar-ā]ntarggata-Vaiśākha-va(ha)hula-pañchanyāṁ(myām).

In the lunar race, in Yadu's family, there was the god Viṣṇu-Kṛishṇa; and kings of that family became known as Tuṅgas, belonging to the Sātyaki branch of it; in their lineage, Ratta; after him, named after his son Rāshtrakūṭa, the Rāshtrakūṭa family. From that family sprang Dantidurga; his paternal uncle Kṛishnarāja [I.]; his son Gōvindarāja [II.]; his younger brother Nirupama Kalivallabha [Dhruvarāja]; his son Jagattuṅga [I. Gōvindarāja III.]; his son Nripattuṅga [Amōghavarsha I.] (founded Mānyakhēṭa); his son Kṛishnarāja [II.]; his son Jagattuṅga [II.] (did not reign); his son Indrarāja [III.]; his son Amōghavarsha [II.]; his younger brother Gōvindarāja [IV.]. After him, the son of Jagattuṅga II., Amōghavarsha [III. Baddiga]; his son Kṛishnarāja [III.] (slew Dantiga and Vappuka;² in Gāṅgapāṭi deposed Rachhyāmalla, i.e. Rāchamalla I,³ and put in his place Bhūtārya, i.e. Būtuga II.; he also defeated the Pallava Appiga).

94.—*Ś. 867.*—*Ep. Ind.* Vol. IV. p. 60, and Plate. Sālōṭgi (now Inḍī) pillar inscription⁴ of the reign of Kṛishnarāja III. *Akālavarsha*, the son of Amōghavarsha III., residing at Mānyakhēṭa :—

(L. 3.)—Śaka-kālād-gat-ābdānām sa-saptādhikashashṭishu satēshv-ashṭasu tāvatsu samānām-amkatō=pi cha | Varttamānē Plavaṁg-ābdē . . .

(L. 45.)—Pūrvv-ōktē varttamān-ābdē māsē Bhādrāpadē-michitē pitṛi-parvvaṇi tasyaiva Kujavārēṇa saṁyutē sūryyagrahaṇa-kālē tu madhya-gē cha divākārē.

Tuesday, 9th September A.D. 945; a solar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 123, No. 61; and Vol. XXV. p. 269.

95.—*Ś. 872*.*—*Ep. Ind.* Vol. II. p. 171; *Ep. Carn.* Vol. III. p. 92, No. 41, and Plate; *Ep. Ind.* Vol. VI. p. 53, and Plates. Ātakūr (now Bangalore Museum) Kanarese inscription of the time of Kṛishnarāja III. *Kannaradēva*⁵ (who killed in battle at Takḱōla the Chōḷa Mūvaḍi-Chōḷa Rājāditya⁶) and of the W. Gaṅga *Permāṇaḍi Būtuga II. Satyavākya-Koṅgunivarma-dharmamahārājādhirāja*, 'lord of Kōḷāla,' 'lord of Nandagiri':—

(L. 1.)—Sa(sa)kamri(nri)pakāl-ātita-sa[m]vatsara-sa(sa)taṅga[=eṇṭu-nūḱ-[e]]patt-[e]raḍa-neya Śō(sau)myam-emba sa[m]vatsaraṁ pravarttise.

¹ Compare *Ind. Ant.* Vol. XXXI. p. 219.

² Below, in No. 98, the name is Vappuga.

³ See No. 95.

⁴ The pillar besides contains two Kanarese inscriptions, one (*ibid.* p. 63) of about the period to which the above Sanskrit inscription belongs, and the other (*ibid.* p. 65) of the 11th or 12th century A.D. The former records grants of a certain Kañchiga of the Seḷṇa race; and the latter a grant of the *Mahāmāṇḍalīvara* Gō[v]ṇarasa of the Śīlāhāra race.

⁵ Described as a bee on the waterlilies that were the feet of Amōghavarshadēva [III.]; see No. 93.

⁶ See below, Nos. 127 and 712.

The inscription mentions a follower of Bûtuga's, named Maṇalera, 'lord of Valabhi,' the Sagara *vaiṇśa*.—A subsidiary record on the stone states that Bûtuga killed Rāchamalla [1.], the son of Eṭṭeyapa, and that it was Bûtuga who treacherously stabbed Rājāditya.

96.—**Ś. 873.**—*Ind. Ant.* Vol. XII. p. 257. Soratūr Kanarese inscription of the reign of the *Mahārājādhirāja Akālavārsha Kannaradēva* (i.e. the Rāshtrakūṭa **Kṛishṇarāja III.**) :—
(L. 4).—Sa(śa)kanṇipakāl-ākṛānta-saṁvatsara-sa(śa)taṁga[ī*] 873 Virōdhi[kṛit*]-saṁvatsarada Mārggaśira-māsada puṇṇameyuma-Ādityavāramuṁ Rōhipi(nī)-nakshatramuṁ śō(sō)magrahaṇad-andu.

Sunday, 16th November A.D. 951; a lunar eclipse, visible in India; see *ibid.* Vol. XXIII. p. 114, No. 9.

97.—**Ś. 876***.—Supplied by Dr. Fleet.¹ Date of a Chiñchli (in Dhārwar district) Kanarese inscription of the time of the Rāshtrakūṭa **Kṛishṇarāja III.** :—

Sa(śa)kabhūpākāl-ākṛānta-saṁvatsara-sa(śa)taṁga[ī*] eṇṭu-nūṭ-ēlpatt-āṇeya Ānanda-saṁvatsarada Vaiśākha-su(śu)ddha-bidige Sōmavāramuṁ Mṛigaśira-nakshatramuṁ=āge(? gi).

Monday, 18th April A.D. 953.²

98.—**Ś. 880.**—*Ep. Ind.* Vol. IV. p. 281, and Plate. Karhād plates³ of the Rāshtrakūṭa *Mahārājādhirāja Kṛishṇarāja III. Akālavārsha*, the successor of the *Mahārājādhirāja Amoghavarsha III.*, issued from Mēlpāṭi :—

(L. 56).—Śaka[nṇi]pakāl-[ā*]tita-[saṁ]vatsara-satēshv=ashtasv=a[śī]ty-adhikēshu Kāla-yukta-saṁvatsar-āntarggata-Ph[ā]lguna-va(ba)hula-trayōdasyām(śyām) Vu(bu)dhē.

Wednesday, 9th March A.D. 959.⁴

Genealogy as in No. 93. **Kṛishṇarāja III.** conquered [the Kalachuri-Chēdi] Sahasrārjuna, though he was an elderly relative of his wife and his mother; he slew Dantiga and Vappuga;⁵ in Gaṅgapāṭi he deposed Rachhyāmalla (i.e. Rāchamalla I.)⁶ and put in his place Bhūtārya (i.e. Bûtuga II.); and he defeated the Pallava Appiga.

99.—**Ś. 884***.—Supplied by Dr. Fleet.⁷ Date of a Dēvi-Hosūr (in Dhārwar district) Kanarese inscription of the time of the Rāshtrakūṭa **Kṛishṇarāja III.** :—

Sa(śa)ka-varsha 884 Dundubhi-saṁvatsar-āntarggata-Pausha-su(śu)ddha-trayōdasi(śi) Ādityavāram=uttarāyana-saṁkrānti-andu.

Sunday, 22nd December A.D. 961⁸ (with the Uttarāyana-saṁkrānti on the next day, Monday).

100.—*South-Ind. Inscr.* Vol. III. No. 7, p. 12. Ukkal (Vishṇu temple) Tamil inscription of the 16th year (of the reign) of the glorious **Kaṇṇaradēva** who conquered Kachchi (i.e. Kāñchīpura) and Tañjai (i.e. Tañjāvūr), (i.e. the Rāshtrakūṭa **Kṛishṇarāja III.**).

101.—*Ep. Ind.* Vol. III. p. 284. Tirukkaḷukkuṇṇam Tamil inscription of the 17th year (of the reign) of the glorious **Kaṇṇaradēva** who conquered Kachchi and Tañjai (i.e. the Rāshtrakūṭa **Kṛishṇarāja III.**).

102.—*Ep. Ind.* Vol. III. p. 285, and Plate. Tirukkaḷukkuṇṇam Tamil inscription of the 19th year (of the reign) of **Kaṇṇaradēva** who conquered Kachchi and Tañjai (i.e. the Rāshtrakūṭa **Kṛishṇarāja III.**).

¹ See *Ep. Ind.* Vol. VI. p. 180.

² This day fell in the year Ānanda by both the northern luni-solar and the mean-sign system, but not by the southern luni-solar system.

³ Compare *Ind. Ant.* Vol. XXX. p. 373.

⁴ On this day the *tithi* of the date commenced 2 h. 33 m. after mean sunrise; see my remarks in *Ep. Ind.* Vol. IV. p. 279.

⁵ Above, in No. 93, the name is Vappuka.

⁶ See above, No. 95.

⁷ See *Ep. Ind.* Vol. VI. p. 180.

⁸ This day fell in the year Dundubhi only by the northern luni-solar system.

103.—*Ep. Ind.* Vol. IV. p. 82, and Plate. Bāvāji Hill (near Vēlūr) Tamil rock inscription of the 26th year (of the reign) of **Kaṇṇarādēva** (i.e. the Rāshtrakūṭa **Kṛishṇarāja III.**). The inscription mentions a **Vīra-Chōja**, who according to Dr. Hultzsch may be identical with the **Gaṅga-Bāpa** Prithivipati II. Hastinalla; see *ibid.* p. 223.—Compare below, No. 671.

104.—*Ś. 893.*—*Ind. Ant.* Vol. XII. p. 255. Adaraguñchi Kanarese inscription of the reign of the *Mahārājādhirāja* **Koṭṭiga** (**Khottiga**) **Nityavarsha**,¹ and the time of his feudatory, the **W. Gaṅga** **Permāṇaḍi Mārasimha II.**,² recording grants by **Pañchaladēva** :—

(L. 7).—Sa(śa)kanripakāl-ātita-samvachchha(tsa)ra-sa(śa)taṅga]=eṭṭu-nūpa-tombhatta-mūṇaneya Prajāpati-sa[m*]vachchha(tsa)raṁ sallutam-ire tad-varsh-ābhya(bhya)ntarad-āshva(śva)yuṇad-amavāse Ādityavāra sūryya-grahaya.

Sunday, 22nd October A.D. 971; a solar eclipse, visible in India; see *ibid.* Vol. XXIII. p. 123, No. 63.

105.—*Ś. 894.*—*Ind. Ant.* Vol. XII. p. 264. and Plates. Kharḍa³ (now Bombay As. Soc.'s) plates⁴ of the Rāshtrakūṭa *Mahārājādhirāja* **Kakkarāja II.** (**Kakkaladēva**) **Amōghavarsha**, 'who meditated on the feet of the *Mahārājādhirāja* **Akālavarsha**,⁵ residing at Mānyakhēṭa :—

(L. 47).—Śakanripakāl-ātita-samvatsara-śatēshv-ashtasu chaturṇṇa(rnna)vaty-adhikēshv-sakataḥ samvat 894 Āṅgirā(rah)-samvatsar-āntargata-Āśvayuja-paurṇamāsyāvān Vu(bu)dha-dinē sōmagrahaya-mahāparvvaṇi.

Wednesday, 25th September A.D. 972; a lunar eclipse, visible in India; see *ibid.* Vol. XXIII. p. 115, No. 10.

In Yadu's lineage, Dantidurga; his paternal uncle **Kṛishṇarāja** [I.]; his son **Gōvinda-rāja** [II.]; his younger brother **Nirupama** [**Dhruvarāja**]; his son **Jagattuṅga** [I. **Gōvinda-rāja** III.]; his son **Amōghavarsha** [I.] (defeated the [E.] **Chālukyas**; founded **Mānyakhēṭa**); his son **Akālavarsha** **Kṛishṇa[rāja II.]**, married the daughter of the **Chēdi Kōkkalla**, the younger sister of **Śaṅkuka**. Their son **Jagattuṅga** [II.], married **Lakshmi**, the daughter of the **Chēdi Śaṅkaragaṇa**, who bore to him **Indra[rāja III.]**; he also married 'his maternal uncle' **Śaṅkaragaṇa**'s daughter **Gōvindāmbā** who bore to him **Amōghavarsha** [III.]. **Amōghavarsha** [III.] married **Yuvarājadēva**'s daughter **Kundakadēvi**, who bore to him **Khottigadēva** who became king after the death of his eldest brother **Kṛishṇarāja** [III.]. **Amōghavarsha** **Nripattuṅga Kakkarāja** [II.]⁶ is the son of **Khottiga**'s younger brother **Nirupama**.

106.—*Ś. 898**.—*Ind. Ant.* Vol. XII. p. 271. Guṇḍūr Kanarese inscription of the reign of the *Mahārājādhirāja* **Kakkaladēva** (**Kakkarāja II.**), and the time of his feudatory, the **W. Gaṅga** **Permāṇaḍi Mārasimha II.** **Noḷambakulāntaka**, and of **Pañchaladēva** :—

(L. 13).—Sa(śa)kha(ka)-varsham=eṭṭu-nūpa-tombhatt-āṇaneya Śrīmukha-samvatsar-āshāḍa(ḍha)-dakṣhiṇāyana(na)-samkrāntiyum-Ādityavārad-andurū.

Perhaps Sunday, 22nd June A.D. 973, but the **Samkrānti** took place on Tuesday, 24th June A.D. 973; see *ibid.* Vol. XXIV. p. 12, No. 174.

107.—*Ś. 904.*—*Inscr. at Śravaṇa-Belgoḷa*, No. 57, p. 53. Eulogy, in Kanarese, of the Rāshtrakūṭa **Indrarāja IV.**, the son's son of **Kṛishṇarāja III.** Date of his death :—

Vanadhi-nabhō-nidhi-pramita-samkhyē (khyā)-Śakāvanipāja-kālamarī nēneyise Chitrabhānu parivarttise Chaitra-sitētar-āshṭamī-dina-yuta-Sōmavāradōḷu.

Monday, 20th March A.D. 982; see *Ind. Ant.* Vol. XXIII. p. 124, No. 64.

¹ Also called **Raṭṭa-Kandarpa**.

² See *Ind. Ant.* Vol. XXXI. p. 220.

³ Also called **Vīra-Nārāyaṇa**, etc.

⁴ See Dr. Fleet's *Dynasties*, p. 307; *Ep. Ind.* Vol. V. p. 173, note 1.—See also below, No. 132.

⁵ See below, No. 128 ff.

⁶ The third plate is now missing.

C.—The Western Gaṅgas.

108.—Ś. 169.—*Ind. Ant.* Vol. VIII. p. 212, and Plate. Tanjore (formerly Sir W. Elliot's, now British Museum, spurious¹) Sanskrit and Kanarese plates of the W. Gaṅga Arivarma-(Harivarma)-mahārājādhirāja :—

(L. 10).—Sa(śa)kā(ka)-kālê navôttara-shashtir=êkaśata-gatêshu Prabhava-samvatsar-âbhyantarê Shâ(Phâ)lgun(n)-âmavâsô(syâ)-Bhṛigu Rêvati(tî)-nakshatrê Vṛiddhi-yôgê Vṛishabha-lagnê.

The date is irregular; see *ibid.* Vol. XXIV. p. 10, No. 166.

In the Jâhnavêya family and Kânvâyana *gôtra*, Koṅgaṇivarma-dharmamahārājādhirāja; his son Mâdhava-mahārājādhirāja [I.] (composed a *Dattakasûtra-vṛitti*); his son Arivarma-mahārājādhirāja.

109.—Ś. 188.—*Ep. Carn.* Vol. III. p. 202, No. 122, and Plates. Tagaḍûru (spurious²) Sanskrit and Kanarese plates of the W. Gaṅga Harivarma-mahādhirājādhirāja, issued from Talavanapura :—

(L. 11).—Saka-varishêshu gatêshu aṭṭâsiti-satê Vibhava-samvatsarê Phâlguna-mâsê suddha-[daP]sami-Guruvârê Punarvasu-nakshatrê.

The date is irregular.

Genealogy substantially as in No. 108.

110.—Ś. 272 (?).—*Ind. Ant.* Vol. VII. p. 173, and Plate; *Mysore Inscr.* No. 156, p. 293. Harihar (spurious³) Sanskrit and Kanarese plates of a son (described as 'lord of Kôlâla') of the W. Gaṅga Vishnugôpa-mahārājādhirāja, the son of Koṅgulivarma-dharmamahārājādhirāja of the Jâhnavîya family :—

(L. 9).—Śaga[.] nayana-gi neyâ ?] Śâdhârâṇa-śammachhohharâda Phalguna-mâ amavâsê Adivârâd-andu.

The date is irregular.

111.—*Ind. Ant.* Vol. V. p. 136, and Plate; *Mysore Inscr.* No. 154, p. 289. Mallohalli (spurious⁴) plates of the 29th year of the reign of the W. Gaṅga Koṅgaṇi-mahārāja (Koṅgaṇi-rāja) :—

(L. 17).—âtmanah pravarddhamâna-vipula-vi[ja*]y-aisvaryya êkônâtrimśatô(?) Jaya-sabatsarê⁵ Śataya-nakshatrê.

In the Jâhnavîya family, Koṅgaṇivarma-dharmamahādhirāja; his son Mâdhavādhirāja [I.] (composed a *Dattakasûtra-vyākhyâ*); his son Harivarma-mārāja; his son Vishnugôpa-rāja; his son Mâdhava-rāja [II.]; his son Koṅgaṇi-rāja.

112.—[Ś.] 388.—*Ind. Ant.* Vol. I. p. 363, and Plate; *Coorg Inscr.* No. 1, p. 1, and Plate; *Mysore Inscr.* No. 151, p. 282. Merkara (spurious⁶) Sanskrit and Kanarese plates of the W. Gaṅga Avinita Koṅgaṇi-mahādhirāja :—

(L. 16).—ashṭa asîti uttarasya trayô satasya samvatsarasya Mâgha-mâsam Śômayârâin Svati-nakshatra suddha-pañchami.

The date is irregular; see *Ind. Ant.* Vol. XXIV. p. 11, No. 169.

In the Jâhnavîya family and Kânvâyana *gôtra*, Koṅgaṇi-mahādhirāja; his son Mâdhava-mahādhirāja [I.] (composed a *Dattakasûtra-vṛitti*); his son Harivarma-mahādhirāja; his son

¹ See *Ind. Ant.* Vol. XXX. p. 215, No. 10.

² See *ibid.* p. 221, No. 46.

³ See *ibid.* p. 221, No. 48.

⁴ See *ibid.* p. 221, No. 50.

⁵ The year Jaya according to Mr. Rice is here Ś. 376.

⁶ See *Ind. Ant.* Vol. XXX. p. 219, No. 40.

Vishṇugōpa-mahādhira; his son Mādhava-mahādhira [II.]; his son Avinīta Kōṅgaṇi-mahādhira, sister's son of the Kadamba Kṛishṇavarma-mahādhira.¹

113.—*Ind. Ant.* Vol. VII. p. 174; *Mysore Inscr.* No. 157, p. 294. Bangalore Museum (spurious²) plates³ of the third year of the reign of the W. Gaṅga Kōṅgaṇi-mahārāja:—

(L. 37).—ātmana pravarddhamāna-vipul-aśvayyē tṛtiyē savatsarē Śrāvāṇē māse tithāva-āma . . .

In the Jāhnavēya family and Kāpvyāna gōtra, Kōṅgaṇivarma-dharmamahādhira; his son Mādhava-mahādhira [I.] (composed a *Dattakasūtra-vṛtti*); his son Harivarma-mahādhira; his son Vishṇugōpa-mahādhira; his son Mādhava-mahādhira [II.]; his son Kōṅgaṇi-mahādhira, sister's son of the Kadamba Kṛishṇavarma-mahādhira; his son Kōṅgaṇi-mahārāja.

114.—*Ind. Ant.* Vol. V. p. 138, and Plates; *PSOCI.* No. 263; *Mysore Inscr.* No. 153, p. 291. Mallohalli (spurious⁴) plates of the 35th year of the reign of the W. Gaṅga Durvinita Kōṅgaṇi-vṛiddharāja:—

(L. 43).—ātmanah=pravarddhamāna-vijayaiśvayyē pañchatrinśad-Vijaya-saṁvatsarē pravarttamānē.

Genealogy as far as Mādhava-mahādhira [II.] as in No. 113; his son Avinīta Kōṅgaṇi-mahādhira, sister's son of the Kadamba Kṛishṇavarma-mahādhira; his son Durvinita Kōṅgaṇi-vṛiddharāja, daughter's son of Skandavarman (*Rājā* of Punnāḍa).

115.—*Ś. 635.*—*Ep. Carn.* Vol. III. p. 107, No. 113, and Plates. Hallegere (spurious⁵) plates of the 34th year of the reign of Śivamāra I, Prithivī-Kōṅgaṇi-mahārāja Navakāma, recording a grant made at the request of the Pallavādhiraśas Jaya and Vṛiddhi, the sons of Pallava-yuvarāja, issued from Talavanapura:—

(L. 34).—pañchatrinśōttara-shatṭhātēshu Śaka-varshēshv-atitēshu ātmanah=pravarddhamāna-vijayaiśvayya-saṁvatsarē chatustrinśatkē pravarttamānē.

Genealogy as far as Mādhava-mahādhira [II.] as in No. 113; his son Avinīta Kōṅgaṇi-mahādhira, sister's son of the Kadamba Kṛishṇavarma-mahādhira; his son Durvinita Kōṅgaṇi-vṛiddharāja (author of a commentary on 15 *sargas* or on the 15th *sarga* of the *Kirātārjunīya*); his son Mushkara Kōṅgaṇi-vṛiddharāja; his son Śrīvikrama Kōṅgaṇi-mahādhira, son of a daughter of Sindhurāja; his son Bhūvikrama Kōṅgaṇi-mahādhira Śrīvallabha (defeated the Pallavas at Velanda⁷); his younger brother Śivamāra [I.] Prithivī-Kōṅgaṇi-mahārāja Navakāma.

116.—*Ind. Ant.* Vol. XIV. p. 230, and Plates. British Museum (formerly Sir W. Elliot's, spurious⁸) Sanskrit and Kanarese⁹ plates of the W. Gaṅga dynasty, recording a grant by a certain Ereganṅa.¹⁰

The grant gives the genealogy from Kōṅgaṇivarma-dharmamahādhira to Navakāma, the younger brother of Bhūvikrama.

¹ For Kadambas named Kṛishṇavarman. see below, Nos. 613 and 614.

² See *Ind. Ant.* Vol. XXX. p. 222, No. 61.

³ The second side of the fourth plate is illegible, and the following plate or plates are lost.

⁴ See *Ind. Ant.* Vol. XXX. p. 222, No. 52.

⁵ The year Vijaya according to Mr. Rice is here Ś. 485.

⁶ See *Ind. Ant.* Vol. XXX. p. 222, No. 54.

⁷ Or Viḷanda.

⁸ See *ibid.* p. 222, No. 55.

⁹ "The language . . . is extremely corrupt; . . . the text . . . goes backwards and forwards in a way that would render the text utterly unintelligible, but for the Merkara and Nāgamaṅgala (Dēvarhāḷi) grants."

¹⁰ There is nothing to indicate whether this is another name of Navakāma (Śivamāra I.) or the name of one of his feudatories.

117.—**Ś. 672.**—*Ep. Carn.* Vol. VI. p. 151, No. 36, and Plates. Jāvaḷi (spurious?) plates of the 25th year of the reign of the W. Gaṅga Śrīpuruṣa Prithivī-Koṅguṇi-mahārāja, issued from Maṇṇagrāma :—

(L. 35).—dvāsaptatyuttara-shaṭchhatēshu Śāka-varshēshv=atītēshv=ātmanah=pravarddhamāna-vijayaiśvaryya-saṁvatsarē pañchavimśē varttamānē . . . Vaiśākha-śuklapakṣa-daśamyām Uttarāphalguṇi-nakshatrē Sōmavārē Vṛishabharāśi-saṁkrāntyām.

Monday, 20th April A.D. 750.

Genealogy as far as Śivamāra [I.] substantially as in No. 115; his son's son Śrīpuruṣa Prithivī-Koṅguṇi-mahārāja.

118.—**Ś. 684.**—*Madras Jour. Lit. Sc.* 1878, p. 138; *Mysore Inscr.* No. 152, p. 254. Hoṣar (spurious¹) plates of the W. Gaṅga Śrīpuruṣa Prithivī-Koṅguṇi-mahārāja, issued from Mānyapura :—

Chaturaśīty-uttarēshu shaṭchhatēshu Śāka-varshēshu samatītēshu . . . Vaiśākha-māsē sōma-grahapē Viśākhā-nakshatrē Śukravārē.

For Ś. 684 current the date might perhaps correspond to Friday, 24th April A.D. 761, but there was no lunar eclipse on that day; see *Ind. Ant.* Vol. XXIV. p. 11, No. 171.

Genealogy as in No. 117.

119.—**Ś. 698.**—*Ind. Ant.* Vol. II. p. 156, and Plates; *Ep. Carn.* Vol. IV. p. 233, No. 85, and Plates; specimen Plate in *Ep. Ind.* Vol. III. p. 164; *Mysore Inscr.* No. 153, p. 287. Dēvarhaḷi, formerly known as Nāgamaṅgala (spurious²) plates³ of the 50th year of the reign of the W. Gaṅga Mahārājādhirāja Śrīpuruṣa Prithuvī-Koṅguṇi-mahārāja, recording a grant made at Mānyapura, at the request of Paramagūḷa-Prithuvī-Nirgunda-rāja (the son of Duṇḍu-Nirgundayuvārāja, of the Bāṇa family?), in favour of a Jaina temple founded at Śrīpura by Prithuvī-Nirgunda-rāja's wife Kundāchehi, the daughter of Maruvarman of the Sagara family :—

(L. 41).—aṣṭānavaty-uttarēshu [sha*]ṭchhatēshu Śāka-varshēshv=atītēshv=ātmanah pravarddhamāna-vijayaiśvaryya-saṁvatsarē pañchāṣattamē pravarttamānē.

Genealogy as in No. 117.

The grant gives the line of Jaina teachers Chandrapandin, his disciple Kumārapandin, his disciple Kīrtinandin, his disciple Vimalachandrāchārya.

120.—**Ś. 261.**—*Ind. Ant.* Vol. XVIII. p. 311, and Plate. Kalbhāvi (spurious⁴) Sanskrit and Kanarese Jaina inscription, recording the restoration, by the Gaṅga Mahāmaṇḍalēśvara Kambharasa,⁵ 'lord of Kuvalāla,' of a grant that had been made by the Gaṅga Mahāmaṇḍalēśvara Saigotṭa⁶ Permānadi Śivamāra [II.], 'lord of Kuvalāla,' a feudatory of king Amōghavarsha, professedly on the date here given :—

(L. 14).—Śāka-varsha 261neya Vibhava-saṁvatsarada Pausya(sha)-bahula-chaturdaśi-Sōmavāram=uttarāyana-saṁkrāntiy-amdu.

The date is irregular; see *ibid.* Vol. XXIV. p. 11, No. 168.

The inscription mentions, in the Kāreya gāṇa and Mailāpa anvaya, Guṇakīrti, Nāgachandramunindra, Jinachandra, Śubhakīrti, and Dēvakīrti-guru.

121.—*Ep. Carn.* Vol. IV. p. 109, No. 60, and Plates. Gaḷigēkere (spurious⁷) Sanskrit and Kanarese plates of the W. Gaṅga Raṇavikramayya.

Genealogy as far as Bhūvikrama substantially as in No. 115; his . . .⁸(?) Śivamāra [I.]; his son's son Śrīpuruṣa; his son Śivamāra [II.] Koṅguṇi-mahārājādhirāja (anointed as king

¹ See *Ind. Ant.* Vol. XXX. p. 222, No. 56.

² See *ibid.* p. 223, No. 57.

³ Part of the formal portion of the grant is in Kanarese.

⁴ So far, at any rate, as regards the date; the writing is of about the eleventh century A.D.

⁵ See *Ep. Ind.* Vol. VI. p. 65, note 2.

⁶ See below, No. 127.

⁷ See *Ind. Ant.* Vol. XXX. p. 223, No. 59.

⁸ The original omits the word which is required here.

by the Rāshtrakūṭa Gōvinda and the Pallava Nandivarman) ; his brother Vijayāditya ; his son Rājamalla ; his son Raṇavikramayya.

122.—*Ep. Ind.* Vol. VI. p. 257, and Plate. Guḍigere fragmentary Kanarese inscription¹ of the reign of the [W. Gaṅga] *Mahārāja Mārassaḷba*,² under whom a certain *Daḍigarasa* was governing the district (including the village at which the inscription is).—The inscription contains the name Śubhachandra-panḍita.

123.—*Ep. Ind.* Vol. IV. p. 141, and Plate. Vallimalai Kanarese inscription (in Grantha characters), recording the foundation of a Jaina cave by the [W. Gaṅga] king Rājamalla.

Śivamāra [I.]³ ; his son Śrīpurusha ; his son Raṇavikrama ; his son Rājamalla.

124.—*Ep. Carn.* Vol. III. p. 165, No. 91, and Plate ; *Ep. Ind.* Vol. VI. p. 43, and Plates. Dodḍahundi (now Bangalore Museum) Kanarese inscription,⁴ recording the death of the W. Gaṅga Nītimārga-Koṅguṇivarma-dharmamahārājādhirāja,⁵ 'lord of Kovaḷāla,' 'lord of Nandagiri,' the illustrious Permanaḍi, and the bestowal of a grant by his eldest son Satyavākya-Pemmānaḍi⁶ on one Agarayya.

125.—*Ś. 809*.—*Ind. Ant.* Vol. VI. p. 102, No. II., and Plate ; *Coorg Inscr.* No. 2, p. 5 ; *PSOOL* No. 269. Bīḷūr Kanarese inscription of the 18th year of the reign of the W. Gaṅga Satyavākya-Koṅguṇivarma-dharmamahārājādhirāja Permanaḍi,⁷ 'lord of Kovaḷāla,' 'lord of Nandagiri : '—

'Śaka 809 (in words, l. 2), the eighteenth year (in words, l. 5) of his reign ; the fifth day (śrīpauṇṇamī) of Phālguna.'

126.—*Mysore Inscr.* No. 113, p. 209, and Plate ; *PSOOL* No. 247 ; *Ep. Ind.* Vol. I. p. 350 ; *Ep. Ind.* Vol. VI. p. 48, and Plates. Bēgūr (now Bangalore Museum) Kanarese inscription, recording that the W. Gaṅga Eṇṇayapparasa⁸ lent to Ayyapaḍēva⁹ for the purpose of fighting against Viramahēndra¹⁰ a force collected and commanded by the leader of the Nāgattaras, that this commander was killed, and that then Eṇṇayapa appointed Iruga to the leadership of the Nāgattaras and made a grant to him.

127.—*Ś. 860*.—*Ep. Ind.* Vol. III. p. 176, and Plate. Sūḍi (spurious¹¹) plates of the W. Gaṅga Bātuga II.¹² Satyanitivākya-Koṅguṇivarma-dharmamahārājādhirāja, recording a grant to a Jaina temple founded by his mistress Dīvaḷāmbā ; issued from the town of Purikara :—

(L. 68).—Sa(śa)ka-vari[sh]ēshu shashṭyuttar-āṣṭa[śa]tēshu atikrāntēshu Vikāni(ri)-samivatsara-Kā[r]tt[i]ka-Nandisva(śva)ra-su(śu)kla-pakṣaḥ aṣṭamyām Ādityavārē.

The date is irregular ; see *ibid.* p. 159.

¹ According to Dr. Fleet "the characters of it are fairly referable to closely about A.D. 800."

² According to Dr. Fleet to be identified with the Mārāsarva of No. 64 above.

³ For Śivamāra II. see No. 659.

⁴ According to Dr. Fleet to be placed roughly about A.D. 840.

⁵ By Dr. Fleet identified with Raṇavikrama of No. 123.

⁶ By Dr. Fleet identified with Rājamalla of No. 123.

⁷ For a short Kōṭūr undated Kanarese inscription of his see *Ind. Ant.* Vol. VI. p. 103, No. III. ; *Coorg Inscr.* No. 3, p. 6 ; *PSOOL* No. 270.—According to Dr. Fleet he is Bātuga I. ; see *Ep. Ind.* Vol. VI. p. 68.

⁸ According to Dr. Fleet about A.D. 908-938 ; the events recorded in the inscription, according to Dr. Fleet, have to be placed about A.D. 934-938.

⁹ Identified with a Nōḷambādhirāja Ayyapaḍēva.

¹⁰ According to Dr. Fleet in all probability identical with the E. Chalukya Chālukya-Bhūma II. Gaṇḍamahēndra ; see below, No. 560.

¹¹ See *Ind. Ant.* Vol. XXX. p. 217, No. 81.

¹² For Bātuga I. see also above, note 7.

Genealogy as far as Bhūvikrama substantially as in No. 115; his son¹ Śivamāra [I.]; his son Śrīpurusha Koṅguṇivarma-dh.²; his son Śivamāra [II.] Koṅguṇivarma-dh. Saigoṭṭa; his younger brother Vijayāditya; his son Rājamalla [I.] Satyavākya-Koṅguṇivarma-dh.; his son Eregaṅga [I.] Nītimārga-Koṅguṇivarma-dh.; his son Rājamalla [II.] Satyavākya-Koṅguṇivarma-dh.; his younger brother Būtuga [I.] Guṇaduttaraṅga (married Abbalabbā, a daughter of [the Rāshtrakūṭa] Amōghavarsha [I.]); his son Eregaṅga [II.] Nītimārga-Koṅguṇivarma-dh., also called Komara-vedeṅga ('whose forehead was adorned with the *paṭṭabandha* of, or by, Ereyappa'); his son Narasiṅgha Satyavākya-Koṅguṇivarma-dh., also called Vīra-vedeṅga; his son Rājamalla (?) [III.] Nītimārga-Koṅguṇivarma-dh., also called Kachcheya-Gaṅga; his younger brother Būtuga [II.] Satyanītvākya-Koṅguṇivarma-dh., also called Nanniya-Gaṅga, Jayaduttaraṅga, Gaṅga-Nārāyaṇa, etc. (married a daughter of Baddega, i.e. the Rāshtrakūṭa Amōghavarsha III., at Tripurī in Dāhāla; on the death of Baddega secured the kingdom for [the Rāshtrakūṭa] Kṛishṇarāja [III.]; caused fear to Kakkarāja of Alachapura, Bijja-Dantivarman of Banavāsī, Rājavarman, Dāmari of Nuḷuvugiri, and Nāgavarman; defeated [the Chōla] Rājāditya,³ besieged Tanjāpurī, etc.).

128.—Ś. 872*.—Ātakūṛ Kanarese inscription of the time of the W. Gaṅga Permāṇaḍi Būtuga II. Satyavākya-Koṅguṇivarma-dharmamahārājādhirāja; see above, No. 95.

129.—Ś. 890.—*Ind. Ant.* Vol. VII. p. 104, lines 1-50 of the text. Lakshmēshwar (spurious⁴) inscription⁵ of the W. Gaṅga Mārasimha II. Satyavākya-Koṅguṇivarma-dharmamahārājādhirāja:⁶—

(L. 24).—Śakanripakāl-ātita-saṁvatsara-śatēshv-ashṭasu navaty-uttarēshu pravarttamānē Vibhava-saṁvatsarē.⁷

In the Jāhnavēya family and Kāṇvāyana *gōtra*, Mādhava Koṅguṇivarma-dharmamahārājādhirāja; his son Mādhava-mahārājādhirāja (composed a *Dattakasūtra-vṛitti*); his son Harivarman-mahārājādhirāja; his younger brother Mārasimha.

The inscription gives the line of Jaina teachers Dēvēndra, his disciple Ēkadēva, his disciple Jayadēva-paṇḍita.

130.—Ś. 896.—*Ep. Ind.* Vol. IV. p. 351. Hebbāl Kanarese inscription, recording grants etc. by the W. Gaṅga Mārasimha II. Satyavākya-Koṅguṇivarma-dharmamahārājādhirāja (also called Nōlambakulāntakadēva, etc.), 'lord of Kōlāla,' 'lord of Nandagiri,' and his grandmother Bhujjabbarasi, the mother of Būtayya (Būtuga II.):—

(L. 16).—Sa(sa)kanripakāl-āt[ī]ta-sa[m]vatsara-śataṅga[ī]* 896neya Bhāva-saṁvatsarada Pā(phā)lguṇa(na)-su(su)ddha-paṇchami Brihaspativārad-andu.

Thursday, 18th February A.D. 975.⁸

In the reign of [the Rāshtrakūṭa] Akālavarsha Kannaradēva (Kṛishṇarāja II.), Baddegadēva (Amōghavarsha III. Baddiga) gave his daughter Rēvakanimmaḍi, the elder sister of Kannaradēva (Kṛishṇarāja III.), in marriage to Permāṇaḍi Būtayya (Būtuga II.) Satyavākya-Koṅguṇivarma-dharmamahārājādhirāja. Their son Maruḷadēva, married Bijjabe; their son Rachcha(?)—Gaṅga. Immediately after his reign, there reigned the son of Būtayya and Kallabbarasi, viz. Mārasimha [II.] Satyavākya-Koṅguṇivarma-dh., also called Nōlambakulāntakadēva, etc.

¹ Elsewhere Śivamāra is described as the younger brother of Bhūvikrama; but see also No. 121.

² I.e., here and below, -dharmamahārājādhirāja.

³ See above, No. 95.

⁴ See *Ind. Ant.* Vol. XXX. p. 218, No. 38.

⁵ Put on the stone in about the second half of the 11th century A.D.

⁶ See above, Nos. 104 and 106.

⁷ See the same date of an inscription of apparently the same king, *Ind. Ant.* Vol. VII. p. 112, third part.

⁸ On this day the *tittī* of the date commenced 6 h. 52 m. after mean sunrise.

131.—*Inscr. at Śravaṇa-Belgoḷa*, No. 38, p. 5; *Ep. Ind.* Vol. V. p. 176, and Plate. Sanskrit and Kanarese much damaged inscription, being a panegyric of the W. Gaṅga Mārasimha II. Satyavākya-Koṅṅivarma-dharmamahārājādhirāja (called Nalamba-kulāntaka, etc.); engraved after his death.¹

He conquered the northern region for [the Rāshtrakūṭa] Kṛishṇarāja [III.]; destroyed the pride of a certain Alla, an opponent of Kṛishṇarāja; crowned Indrarāja [IV.]; defeated Vajjala;² destroyed the Śabara chief Naraga; conquered the Chālukya Rājāditya, etc.—He committed religious suicide at Baṅkāpura, near the Jaina teacher Ajitasēna.

132.—Ś. 897.—*Ep. Ind.* Vol. VI. p. 259, and Plate. Mulgund fragmentary Kanarese inscription of the reign of the W. Gaṅga Pañchaladēva³ Satyavākya-Koṅṅivarma-dharmamahārājādhirāja, 'lord of Kuvaḷāḷa,' 'lord of Nandagiri,' the successor of Nalambakulāntakadēva (Mārasimha II.):—

(L. 5).—Sa(śa)ka-varsham=ṇṭunūga-tombhatt-[ē]laneya Yuva-saṁvatsarada Bhādrapada-baḷuḷa-bidiye Brihaspativāram Kanyā-saṁkrāntiyu[m].

Thursday, 26th August A.D. 975.

133.—Ś. 899.—*Ind. Ant.* Vol. VI. p. 102, No. I., and Plate; Vol. XIV. p. 76; *Coorg Inscr.* No. 4, p. 7, and Plate; *PSOCI.* No. 271. Peggu-ūr Kanarese inscription of the W. Gaṅga Rāchamalla II. Permanaḍi Satyavākya-Koṅṅivarma-dharmamahārājādhirāja, 'lord of Kōḷāḷa,' 'lord of Nandagiri':—

(L. 1).—Sa(śa)kanripakāl-ātita-saṁvatsara-sa(śa)tuṅga[!]* 899taneya īsva(śva)ra-saṁvatsaram pravartise . . . tadvarsh-ābhyanāra-Pā(phā)lgaṇa(na)-su(śu)klapakshada Nandīśva(śva)ram tallaj-āvasam=āge(?).⁴

The inscription mentions a certain Rakkasa (a younger brother of Rāchamalla?).

134.—*Inscr. at Śravaṇa-Belgoḷa*, No. 60, p. 58. Kanarese memorial tablet of Bāyiga, private attendant or guardian of the W. Gaṅga prince (?) Rakkasa.

135.—*Inscr. at Śravaṇa-Belgoḷa*, No. 61, p. 58. Kanarese memorial tablet of Gunti (who fell in battle?), the wife of Lōka-Vidyādhara, erected by her sister's husband Bāyika (Bāyiga).

136.—*Inscr. at Śravaṇa-Belgoḷa*, No. 109, p. 85. Inscription recording achievements of Chāvuṇḍarāja, general of the W. Gaṅga Jagadēkavira (i.e. Mārasimha II.). Born in the Brahmakshatra kula, he fought for Jagadēkavira, when the latter at the command of [the Rāshtrakūṭa] Indrarāja [IV.] conquered Vajjaladēva⁵ who was the younger brother of Pātālamalla; he also fought in wars with the Nalamba king, etc.

137.—*Inscr. at Śravaṇa-Belgoḷa*, No. 85, p. 67. Kanarese inscription, being a panegyric of Gommaṭṭēśvara, of whom a colossal statue was erected by Chāmuṇḍarāja, the minister of the W. Gaṅga Rāchamalla II.; (composed by the poet Boppa Sujanōttama).

138.—*Inscr. at Śravaṇa-Belgoḷa*, No. 67, p. 60. Kanarese inscription, recording the foundation of a Jaina shrine by the minister Chāmuṇḍa's son, a lay-disciple of Ajitasēna.

139.—*Inscr. at Śravaṇa-Belgoḷa*, Nos. 75 and 76, p. 62, and Plate; *Ep. Ind.* Vol. VII. p. 109, and Plate. Short Kanarese, Tamil and Marāṭhī inscriptions containing the names of Chāmuṇḍarāja (Chāvuṇḍarāja) and Gaṅgarāja.⁶

¹ According to Dr. Fleet, this record may be placed in A.D. 975.

² See below, No. 136.

³ See Nos. 106 and 140.

⁴ See *Ep. Ind.*, Vol. V. p. 168, note 4.

⁵ See above, No. 131.

⁶ See below, No. 386 ff.

D.—The Western Chálukyas of Kalyāṇi and their Feudatories.¹

140.—*Ind. Ant.* Vol. XXI. p. 167. Part of a Gadag Sanskrit and Kanarese inscription,² recording the restoration of the W. Chálukya sovereignty by Taila II., the son of Vikramāditya IV. and Bonthādēvi.—Taila destroyed some Raṭṭas, killed [the Paramāra] Muñja,³ took in battle the head of [the W. Gaṅga] Pañchala,⁴ possessed himself of the Chálukya sovereignty, and reigned for 24 years, beginning with the year Śrīmukha.

[Śrīmukha=Ś. 895.]

141.—Ś. 902.—Supplied by Dr. Fleet (compare his *Dynasties*, p. 553). Date of a Segal (in Belgaum district) Kanarese inscription of the reign of the W. Chálukya Taila II., and of his feudatory, the Raṭṭa Kārtavīrya I.,⁵ lord of the Kūṇḍi country :—

Sa(śa)ka-varsha 902neya Vikrama-saṁvatsaraś=Āshāḍa(ḍha)d=amavāsyaey=Ādiv[āraṁ] sūryyagrahaṇa-nimittadoḷ.

The date is irregular as regards both the week-day and the eclipse.

142.—Ś. 902.—*Jour. Bo. As. Soc.* Vol. X. p. 204. Saṁdatti Kanarese inscription of the reign of the W. Chálukya Tailapa (Taila II.), and of his feudatory, the Raṭṭa Mahāśālmanta Śāntivarman (Śānta), the son of Piṭṭuga (who defeated Ajavarman, and) who was the son of Pṛithvirāma.⁶—

(L. 34).—Sa(śa)kanripakāl-Ātīta-saṁvatsara-śataṅga[!]* 902neya Vikrama-saṁvatsarada Paushya(sha)-śuddha-daśamī Bṛihaspativārada=aṁdin=uttarāyana-śa(sa)mkrmanadoḷ.

Thursday, 23rd December A.D. 980; but the *tithi* which ended on this day was the 14th, not the 10th *tithi* of the bright half of Pausha; see *Ind. Ant.* Vol. XXIV. p. 6, No. 147.

143.—Ś. 904.—*Ep. Ind.* Vol. IV. p. 206. Nilgund inscription of the reign of the W. Chálukya Mahārājādhirāja Tailapa Āhavamalla (Taila II., who defeated, amongst others, king Utpala⁷), and of his feudatory Śōbhana,⁸ the younger brother and successor of Kannapa (or Kennapa) :—

(L. 17).—Sa(śa)kanripa-saṁvatsarēshu chaturadhika-ṇavaśatēshu gatēshu Chitrabhānu-saṁvatsarē Bhādrapada-māsē sūryya-grahaṇē sati.

20th September A.D. 982; a solar eclipse, visible in India.

144.—Ś. 911 (for 912).—*Ep. Ind.* Vol. III. p. 232; *PSOCI.* No. 86. Bhairanmaṭṭi Kanarese Sinda inscription.⁹ Date of the reign of the W. Chálukya Tailapayya (Taila II.), and of the Sinda Pulikāla, born in the Nāga race, 'lord of Bhōgavati,' a son of Kammara (Kamayyarasa) :—

(L. 4).—Sa(śa)ka-varsha 911 Vikri(kṛi)tam=emba saṁvatsara pravarttise.

(For a later date in the same inscription see below, No. 156).

¹ These include (among others) :—

(a).—The Raṭṭas; see Nos. 141, 142, 158, 163, 181, 189, 192, 193, 201, 220, 263-263, (and, of earlier inscriptions, No. 79).

(b).—The Sindas; see Nos. 144, 156, 189, 218, 224, 233, 234, 238, 243, 247 (and perhaps 253).

(c).—The Kādambas; see Nos. 147, 164, 168, 173, 210, 227, 235, 241, 242, 249, 254, 255, 260, 261, 262, 269, 270 (and below, Nos. 424 and 425).—For the early Kādambas see No. 602 ff.

(d).—The Pāṇḍyas of the Koṅkaṇa and Nōlambavāḍi (Nōṇambavāḍi); see Nos. 212, 219, 225, 231, 236, 238, 244, 248, 250, 251, 252.—For the Pāṇḍyas of Madhurā see below, section N.

² According to Dr. Fleet, of the time of the W. Chálukya Vikramāditya VI.; see his *Dynasties*, p. 426, note 3.

³ Compare below, No. 328.

⁴ See Nos. 182 and 259, and compare Dr. Fleet's *Dynasties*, p. 432.

⁵ See below, No. 181.

⁶ See above, No. 79.

⁷ I.e. the Paramāra Muñja; see below, No. 150. In my edition of the Nilgund inscription I have wrongly altered *Utpala* to *Utkala*.

⁸ See below, No. 146.

⁹ Put on the stone about A.D. 1070.

145.—*Ś. 919.*—*PSOCI.* No. 214; *Mysore Inscr.* No. 99, p. 186. Talgund Kanarese inscription of the reign of the W. Chālukya Tailapa Āhavamalla (Taila II.), and of his feudatory Bhimarasa:—

‘Śaka 919 (in figures, l. 12), the Hēmalambī *saṃvatsara*; Sunday, the fifth day of the bright fortnight of (?) Āśvayuja;’ (*Mys. Inscr.*: ‘Vaisākha, the 8th day of the moon’s decrease,¹ Sunday,’ which would be Sunday, 2nd May A.D. 997).

146.—*Ś. 924.*—*Ind. Ant.* Vol. II. p. 297, No. 3, and Vol. XII. p. 210, No. 31. Notice of a Gadag Kanarese inscription of the reign of the W. Chālukya Irivabedaṅga Satyāśraya,² and of his feudatory, the *Mahāsāmanta Sōbhanarasa*:³—

(L. 7.)—Sa(śa)kabhūpālākāl-ākramānta-saṃvatsara-sa(śa)taniga[1⁴] 924neya Śubhakarī-saṃvatsaram pravaritise tadvarsh-ābhyanantara-Chaitra-suddha 5 Ādityavārad-andu.

Sunday, 22nd March A.D. 1002.

147.—*Ś. 928* (for 929).—*Ind. Ant.* Vol. XII. p. 212, No. 67. Guḍikaṭṭi Kanarese Kādamba inscription.⁴ Date of the time of (?) the W. Chālukya [Yavarāja?] Jayasimha II., and of his feudatory, the Kādamba (of Goa) *Mahāmāṇḍalīśvara Shashṭhadēva* I.:⁵—

(L. 13).—Sa(śa)kam=ā(a)bda gaja-dvi-nidhi Plavaṅgadolū.

(For a later date in the same inscription see below, No. 164).

148.—*Ś. 930.*—*Ind. Ant.* Vol. XII. p. 212, No. 52. Date of a Manuvalji Kanarese inscription of the W. Chālukya (Irivabedaṅga) Satyāśraya:—

(L. 10).—Sa(śa)ka-varisha 930 Kīlaka-[saṃva]tsa[rada] Śrāvapa-bahula-chaṭṭi⁶ Sōmavārad-andu.

Monday, 26th July A.D. 1008.

149.—*Ś. 930.*—Khārēpāṭa plates of the Silāra *Maṇḍalika Raṭṭarāja*, a feudatory of the W. Chālukya (Irivabedaṅga) Satyāśraya; see below, No. 301.

150.—*Ś. 930* (for 931).—*Ind. Ant.* Vol. XVI. p. 21, and Plate. Kauthēn Plates of the W. Chālukya *Mahārājādēvīrāja Vikramāditya V. Tribhuvanamalla*, recording a grant made at the Kōṭṭīrtha at Kollāpura:—

(L. 61).—Śakanripakāl-ātita-saṃvatsara-satēshu navasu triṇ(triṇ)śad-adhikēshu gatēshu 930 prava[r⁷]ttamāna-Saumya-saṃvatsarē paurṇamāsyām sōmagrahapa-parvvapi.

Probably the 6th October A.D. 1009, with a lunar eclipse, visible in India.⁷

In the Chālukya lineage,⁸ after 59 kings at Ayōdhya *etc.*, there was Jayasimhavallabha [I.] (who conquered the Rāshtrakūṭa Kṛishṇa’s son Indra); his son Rāparāga; his son Pulakēśin [I.], (lord of Vātāpipurī); his son Kīrtivarman [I.]; his younger brother Maṅgalīśa; his elder brother’s son [Pulakēśin II.] Satyāśraya (conquered Harsha [of Kanauj]); his son Neḍamari; his son Ādityavarman; his son Vikramāditya [I.]; his son Yuddhamalla; his son Vijayāditya; his son Vikramāditya [II.]; his son Kīrtivarman [II.]; a brother (named Bhima?) of Vikramāditya [II.]; his son Kīrtivarman [III.]; his son Taila [I.]; his son Vikramāditya [III.]; his son Bhima; his son Ayyapa [I.], married a daughter of Kṛishṇa; their son Vikramāditya [IV.], married Bonthā-dēvi, a daughter of the Chēdi Lakshmapa; their son Taila [II.] (conquered the Rāshtrakūṭas

¹ But the original seems distinctly to quote the bright fortnight. For the 8th of the bright half of Āśvina the date would be Sunday, 12th September A.D. 997.

² For Satyāśraya the inscriptions also have Sattiga and Sattima; see Dr. Fleet’s *Dynasties*, p. 432.

³ See *ibid.* p. 432, and above, No. 148.

⁴ Put on the stone in A.D. 1052-53.

⁵ See Dr. Fleet’s *Dynasties*, p. 436, note 1; p. 439, note 1; and p. 537; and compare below, No. 154.

⁶ This is the true reading of the original, verified by Dr. Fleet.

⁷ In the year Saumya of the date this is the only lunar eclipse that was visible in India.

⁸ In one of the introductory verses the grant glorifies a king named Akalaṅkacharita, who would naturally be understood to be Vikramāditya V.; but the name was a *virūḍa* of Irivabedaṅga Satyāśraya.

Karkara, i.e. Kakkarāja II., and Raṣastambha, and imprisoned king Utpala, i.e. the Paramāra Muñja¹), married Jākavvā, a daughter of the Rāshtrakūṭa Bhammaha-Raṭṭa; their son [Iṣivabeḍaṅga] Satyāśraya; his younger brother Yaśovarman,² married Bhāgyavati;³ their son Vikramāditya [V.].

151.—Ś. 940.—*PSOOL*. No. 153; *Mysore Inscr.* No. 80, p. 166. Baḷagāṁve Kanarese inscription probably of the W. Chālukya Jayasimha II. Jagadēkamalla :—

‘Śaka 940 (in figures, l. 10). The other details of the date are illegible.’

152.—Ś. 941.—*Ind. Ant.* Vol. V. p. 15, and Plate; *PSOOL*. No. 154; *Mysore Inscr.* No. 72, p. 148. Baḷagāṁve Kanarese inscription of the reign of the W. Chālukya Jayasimha II. Jagadēkamalla (‘the moon to the lotus which was king Bhōja,’⁴ and ‘the lion to the elephant which was Rājendra-Chōla [I.]’⁵), and of his feudatory, the *Mahāmāṇḍalēśvara* Kundamarasa, a son of Iṣivabeḍaṅga-dēva :—

(L. 25).—Śaka-varsha 941neya Siddhārtthi-saṁvatsarada Pushya-śuddha-bidige Ādityavarad-aṁdin-uttarāyapa-saṁkrāntiya parbba(rvva)-nimitadim.

The date is irregular; see *Ind. Ant.* Vol. XXIV. p. 13, No. 177.

153.—Ś. 944.—*Ind. Ant.* Vol. XVIII. p. 273; *PSOOL*. No. 70. Bēlūr Kanarese inscription of the reign of the W. Chālukya Jayasimha II. Jagadēkamalla, and of his elder sister Akkādēvi :—

(L. 29).—Sa(sa)kanipakāl-ātita-saṁvatsara-satāṅga[*] 944neya Duṁḍubhi-saṁvatsara-uttarāyapa-saṁkrāntiyum vyatīpātāmum-Ādityavarad-a[ri*]du.

The date is irregular; see *Ind. Ant.* Vol. XXIV. p. 13, No. 178.

The inscription mentions Akkādēvi's father Daśavarman, her mother Bhāgaladēvi,⁷ and her elder brother Vikramāditya [V.] Tribhuvanamalla.

154.—Ś. 946.—*Jour. Roy. As. Soc.* Vol. II. p. 380, and Vol. III. p. 258; *Ind. Ant.* Vol. VIII. p. 11. Miraj plates of the W. Chālukya Mahārājādhirāja Jayasimha II. Jagadēkamalla, issued from near Kollāpura :—

Śakanipakāl-ātita-saṁvatsara-satēshu navasu shaṭchatvāriṁśad-adhikēshv-aṁkataḥ saṁvat 946 Raktākshi-saṁvatsar-āntarggata-Vaiśākha-paurṇamāsyām-Ādityavarē.

Sunday, 26th April A.D. 1024; see *Ind. Ant.* Vol. XXIII. p. 115, No. 12.

Genealogy as far as Vikramāditya [V.] as in No. 150;⁸ his younger brother Jayasimha [II.] Jagadēkamalla.

155.—Ś. 950.—*Ind. Ant.* Vol. IV. p. 278; *PSOOL*. No. 215; *Mysore Inscr.* No. 105, p. 201. Tālgund Kanarese inscription of the reign of the W. Chālukya Jayasimha II. Jagadēkamalla :—

(L. 8).—Sa(sa)ka-varisha 950neya Vibhava-saṁvatsarada Pushya-śuddha(ddha) 5 Sōmav[ā]rad-uttarāyapasa[ni]krāntiy-andu.

Monday, 23rd December A.D. 1028; see *Ind. Ant.* Vol. XXIII. p. 115, No. 13.

156.—Ś. 955.—*Ep. Ind.* Vol. III. p. 232; *PSOOL*. No. 86. Bhairanmaṭṭi Kanarese Sinda inscription.⁹ Date of the time of the W. Chālukya (Jayasimha II.) Jagadēkamalla, and of

¹ See above, No. 148, and below, No. 232.

² Usually called Daśavarman; see below, Nos. 158 and 164.

³ Elsewhere called Bhāgaladēvi; see below, No. 153.

⁴ I.e. the Paramāra Bhōja; compare *North, Inscr.* No. 57.

⁵ Compare below, No. 729.

⁶ According to Dr. Fleet, *Dynasties*, p. 437, note 2, quite possibly the W. Chālukya Iṣivabeḍaṅga Satyāśraya.

⁷ Above, No. 150, the names are Yaśovarman and Bhāgyavati.

⁸ But the name of Vikramāditya's father is here Daśavarman.

⁹ Put on the stone about A.D. 1070.

the Sinda *Mahāsāmanta* Nāgātiyarasa (Nāgāditya, Nāgātya), 'lord of Bhōgāvati,' the son of Pulikūla :—

(L. 52).—Sa(śa)ka-varsha 955[ne*]ya Śrīmukha-saṁvatsara pravarttise.

(For an earlier date in the same inscription see above, No. 144).

The inscription after Nāgātya mentions his son Polasinda, and after him Sōvya (the *Mahāmaṇḍalēśvara* Sōvyarasa) as a vassal of the W. Chālukya (Sōmēśvara II.) Bhuvanaikamalla.

157.—**Ś. 957.**—*PSOCL.* No. 155; *Mysore Inscr.* No. 71, p. 146. Baḷagāṁve Kanarese inscription of the W. Chālukya Jayasimha II. Jagadēkamalla, reigning at Pottalakege :—

(L. 10).—Śaka-varsha 957neya Yuva-saṁvatsarada Pushyada paṇṇamāsey=uttarā-yapasamkrānti-vyatipāram=Ādityavārad=amdu.

The date is irregular.

According to *Mys. Inscr.* p. 148, the above inscription is followed by a grant, the greater part of which has been defaced, of apparently a W. Gaṅga chief.

158.—**Ś. 962.**—*Ind. Ant.* Vol. XIX. p. 164. Maṇṭūr Kanarese inscription of the reign of the W. Chālukya (Jayasimha II.) Jagadēkamalla, reigning at Pottalakege, and of (his feudatory) the Raṭṭa *Mahāsāmanta* Eṇeyammarasa (Eṇega),¹ 'lord of Lattalūr :—

(L. 5).—Sa(śa)ka-varsha 962neya Vikra(va)-saṁvatsarada śrāheya Mārggaśira-śuddha 5 Ādityavārad=amdu.

The date is irregular; see *ibid.* Vol. XXIV. p. 13, No. 180.

159.—**Ś. 968.**—*Ind. Ant.* Vol. XII. p. 209, No. 14. Date of a Hōli Kanarese inscription of the W. Chālukya Sōmēśvara I. :—

(L. 20).—Śakanripakāḷ-āḷita-saṁvatsara-śatamgaḷa 966neya Tārapa-saṁvatsarada Puśya shya)-su(śu)dhā(ḍḍha) 10 Ādivāram=a(u)ttarāyapasaṁkrānti-āndu.

Sunday, 23rd December A.D. 1044; but the *tithi* which ended on this day was the first, not the 10th *tithi* of the bright half of Pausa; see *ibid.* Vol. XXIV. p. 6, No. 148.

160.—*PSOCL.* No. 216; *Mysore Inscr.* No. 108, p. 204. Tālgund Kanarese inscription of the reign of the W. Chālukya (Sōmēśvara I.) Trailōkyamalla, and of his feudatory, the *Mahāmaṇḍalēśvara* Singanadēvarasa :²—

'The Pārthiva saṁvatsara; Sunday, the tenth day (in figures, 1. 13) of the bright fortnight of Pushya; at the time of the sun's commencing his progress to the north.—The year is effaced.' (*Mys. Inscr.* : 'the 9th³ day').

[For Pārthiva = **Ś. 967**] the date is irregular.

161.—**Ś. 968.**—*PSOCL.* No. 156; *Mysore Inscr.* No. 92, p. 183. Baḷagāṁve Kanarese memorial tablet of the time of (the W. Chālukya Sōmēśvara I. Trailōkyamalla, and of his feudatory) the *Mahāmaṇḍalēśvara* Chāvundarāya :—

'Śaka 968 (in figures, 1. 3), the Vyaya saṁvatsara; Wednesday, the fifth day of the bright fortnight of Mārggaśirsha; (*Mys. Inscr.* : 'the 13th day of the moon's increase, Friday'?).

Wednesday, 5th November (or Friday, 14th November?) A.D. 1046.

162.—**Ś. 970.**—*Ind. Ant.* Vol. IV. p. 179, and Plate; *PSOCL.* No. 157; *Mysore Inscr.* No. 53, p. 114. Baḷagāṁve Kanarese inscription of the reign of the W. Chālukya (Sōmēśvara I.) Trailōkyamalla, and of his feudatory, the *Mahāmaṇḍalēśvara* Chāvundarāya, 'lord of Banavāsī :—

(L. 12).—Śaka-varsha 970neya Sarvvadhāri-saṁvatsarada Jyēṣṭha śuddha-trayōdaśī Ādityavārad=amdu.

The date is irregular; see *Ind. Ant.* Vol. XXIV. p. 13, No. 181.

¹ See below, No. 181.

² See Dr. Fleet's *Dynasties*, p. 439.

³ The original appears to have '10.'

163.—Ś. 970.—*Jour. Bo. As. Soc.* Vol. X. p. 172. Notice of a Saundatti Kanarese inscription containing a date of the reign of the W. Chālukya (Sômêśvara I.) Trailōkyamalla, and of his feudatory, the Raṭṭa *Mahāsāmanta Aṅka*:¹—

Śaka 970, 'the Sarvadhāri *saṁvatsara*, on Sunday, the seventh day of the dark fortnight of the month Pushya, at the time when the sun was commencing his progress to the north.'

The date is irregular.

(For a later date in the same inscription see below, No. 192).

164.—Ś. 973 (for 974).—*Ind. Ant.* Vol. XII. p. 211, No. 42. Guḍikaṭṭi Kanarese Kādamba inscription. Date of the reign of the W. Chālukya Sômêśvara I., and of his feudatory, the Kādamba (of Goa) Jayakēśin I., 'the lord of Koṅkapa':²—

(L. 19).—Sa(śa)ka-kālam guṇa-sapta-Nāmda-mṛi(mi)tam=āgal=varttakam Nandan-ābdakam.

(For an earlier date in the same inscription see above, No. 147).

165.—Ś. 975.—*Ep. Ind.* Vol. IV. p. 260, and Plate. Kelawaḍi Kanarese inscription of the reign of the W. Chālukya (Sômêśvara I.) Trailōkyamalla, and of his feudatory, the *Danḍanīyaka Bhôgadēvarasa*, recording a grant by the latter's nephew, the minister *Suppanasa*:—

(L. 21).—Sa(śa)ka [va]rsha 975neya Vijaya-saṁvatsarada ut[t*]arīyanasamkrāntīy-ahūn.

166.—Ś. 976.—*PSOI.* No. 158; *Mysore Inscr.* No. 56, p. 121. Baḷagānve Kanarese inscription of the reign of the W. Chālukya (Sômêśvara I.) Trailōkyamalla Āhavamalla:³—

(L. 15).—Sa(śa)ka-varshada 976neya Jaya-saṁvatsarada Vaisākha-bahula akshaya-tri(tī)ṭhyad-amavāse Ādivāra-nimittam.

For the *akshaya-triṭīyā* new-moon, i.e. the new-moon of Chaitra, the date regularly corresponds to Sunday, 10th April A.D. 1054; in the original date the word *Vaisākha* has been put erroneously for *Chaitra*.

167.—Ś. 976.—*Ind. Ant.* Vol. XIX. p. 272. Honwād (now Bombay As. Soc.'s) Sanskrit and Kanarese Jain inscription of the reign of the W. Chālukya (Sômêśvara I.) Trailōkyamalla, recording grants made at the request of his queen Kētaladēvi:—

(L. 33).—Sa(śa)ka-varsha 976neya Jaya-saṁvatsarada Vaisā(śā)khad-amāvāśye(sye) Sômarārad-arādina sū(sū)ryyagrahapa-nimittya(tta)dim.

10th May A.D. 1054, with a solar eclipse, visible in India; but the day was a Tuesday, not a Monday; see *ibid.* Vol. XXIV. p. 7, No. 150.

The inscription mentions, in the Mūla-saṁgha, Sēna-gaṇa, and Pogari-gachchha: Brahmasēna, his disciple Āryasēna, his disciple Mahāsēna, and his disciple Chāṅkirāja (Chāṅkapārya or Chāṅkimayya, the son of Kommarāja of the Vānasa family), an officer of Kētaladēvi.

168.—Ś. 977.—*Ind. Ant.* Vol. IV. p. 203. Notice of a Baṅkâpur Kanarese inscription of the time of the W. Chālukya Vikramāditya VI. (while viceroy under his father Sômêśvara I.) and of the Kādamba *Mahāmaṇḍalêśvara Harikêśarin*.⁴

'The inscription is dated in the Śaka year 977, being the Manmatha *saṁvatsara*.'

¹ See Dr. Fleet's *Dynasties*, p. 553; and below, No. 181.

² See *ibid.* p. 439, note 1; and p. 567; and compare below, Nos. 249 and 254.

³ Described as 'a lion to the elephant Chôla,' etc.; see below, No. 741 ff.

⁴ See Dr. Fleet's *Dynasties*, p. 563.

169.—**Ś. 984.**—*Ind. Ant.* Vol. XII. p. 209, No. 16. Date of a Hulgūr Kanarese inscription of the W. Chālukya **Sōmēśvara I.** :—

(L. 11).—Sa(śa)ka[n]ṛipakāl-ākṛānta-saṁvatsara-satamga[!*] 984neya Śubhakṛit-saṁvatsarāṁ pravarttise tadvarsh-ābhyantrada Pushya-bahula-saptame(mi) Ādityavāramun=uttarāyāṁasaṁkrāntiy-andu.

24th December A.D. 1062;¹ but the day was a Tuesday, not a Sunday; see *ibid.* Vol. XXIV. p. 7, No. 151.

170.—**Ś. 984.**—*Ind. Ant.* Vol. XII. p. 209, No. 15. Date of a Chillūr-Baḍḍi Kanarese inscription of the W. Chālukya **Sōmēśvara I.** :—

(L. 26).—Sa(śa)kanripakāl-ātīta-saṁvatsara-sa(śa)tamga[!*] 984neya [Śu]bhakṛit-saṁvatsarada Pauśya(sha)-su(śu)ddha-dasa(śa)mi Ādityavāram=uttarāyāṁasaṁkrānti-vyatīpātad=and.

The date is irregular; compare above, No. 169.

171.—**Ś. 986.**—*Ep. Ind.* Vol. IV. p. 213, and Plate. Jaṭiṅga-Rāmēśvara III Kanarese inscription of the W. Chālukya **Vishṇuvardhana Vijayāditya**, described as 'the warrior of Āhavamalla (Sōmēśvara I.)' and son of Trailōkyamalla (Sōmēśvara I.), governing the Nōlambavāḍi Thirty-two-thousand (as viceroy) at Kampili :²—

(L. 12).—Śaka-varshaṁ [9]86neya Krōdhi-saṁvatsarada Vai[śā]khada paṇṇame Sōmavārada [cha]n[dr]agrahaṇa-parbba(rvva)-nimittade.

Monday, 3rd May A.D. 1064; a lunar eclipse, visible in India.

172.—**Ś. 988.**—*PSOCI.* No. 136; *Mysore Inscr.* No. 11, p. 19. Dāvāngere Kanarese inscription of the reign of the W. Chālukya (**Sōmēśvara I.**) **Trailōkyamalla**, and of his son **Vishṇuvardhana Vijayāditya** :—

(L. 17).—Sa(śa)ka-varsha 988neya Parābhava-saṁvatsarada Bhādrapadad=amāva-syā Maṅgalavāra sūrya-grahaṇad=amdu.

The date is irregular.

173.—**Ś. 990.**—*Mysore Inscr.* No. 170. p. 320 (*Ind. Ant.* Vol. IV. p. 206, No. 2). Banavāsī Kanarese inscription of the reign of the W. Chālukya (**Sōmēśvara I.**) **Trailōkyamalla**, and of his feudatory, the Kādamba (of Hāṅgal) **Mahāmaṇḍalēśvara Kirtivarman II.**, 'lord of Banavāsī' :³—

'In the Śaka year 990, the year Kilaka, the month Chaitra, the 1st day of the moon's increase (rest not copied).'

174.—**Ś. 993.**—*PSOCI.* No. 159; *Mysore Inscr.* No. 70, p. 144. Baḷagāṁbe Kanarese inscription of the reign of the W. Chālukya (**Sōmēśvara II.**) **Bhuvanaikamalla**, and of his feudatory, the **Danḍandya Udayāditya**, residing at Baṅkāpura :—

(L. 12).—Sa(śa)ka-varsha 993neya Virōdhikṛit-saṁvatsarada Pushya-su(śu)ddha Sōmavārada=amdin=uttarāyāṁasaṁkrānti-parbba(rvva)-nimittadin.⁴

25th December A.D. 1071; but the day was a Sunday, not a Monday; see *Ind. Ant.* Vol. XXIV. p. 7, No. 152.

175.—**Ś. 993.**—*PSOCI.* No. 160; *Mysore Inscr.* No. 78, p. 164. Another Baḷagāṁbe Kanarese inscription of the reign of the W. Chālukya (**Sōmēśvara II.**) **Bhuvanaikamalla**, and of his feudatory, the **Danḍandya Udayāditya**; of the same date.

¹ On this day the *tithi* of the date commenced 10 h. 33 m. after mean sunrise.

² Compare below, No. 741.

³ See Dr. Fleet's *Dynasties*, p. 561.—Kirtivarman II. was the son of Tailapa I. in No. 210.

⁴ See *Ind. Ant.* Vol. XII. p. 212, No. 55.

176.—Ś. 993.—*Ep. Ind.* Vol. IV. p. 215, and Plate. Jatiṅga-Rāmēśvara Hill Kanarese inscription of the W. Chālukya Jayasimha III.,¹ styled 'the lion of his elder brother' (Sōmēśvara II.), encamped (as viceroy) near Gondavādi:—

(L. 8).—Sa(śa)ka-varsha 993neya Virōdhikṛit-samvatsarada Pā(phā)lguṇa(na)d-amavāse Budhavāram.

Wednesday, 21st March A.D. 1072 (P).²

177.—Ś. 996.—*Ind. Ant.* Vol. X. p. 127. Bijāpur Sanskrit and Kanarese inscription of the reign of the W. Chālukya (Sōmēśvara II.) Bhuvanaikamalla,³ and of his feudatory, the *Daṇḍanāyaka Nākimayya*:—

(L. 10).—Sa(śa)ka-varsha 996neya Ānanda-samvatsarada Puśya(shya)-su(śu)-dhadha(ddha) 5 Bri(bri)haspativārad=amdin=uttarāyapaśamkrānti-parvva-nimittam=āgi.

Thursday, 25th December A.D. 1074; see *ibid.* Vol. XXIII. p. 115, No. 15.

178.—Ś. 997.—*Archaeol. Surv. of West. India*, Vol. III. p. 105; Vol. I Plate xiii.; *Ind. Ant.* Vol. I. p. 141; *PSOCI.* No. 92 Kādarōḷi Kanarese inscription of the reign of the W. Chālukya (Sōmēśvara II.) Bhuvanaikamalla, and of his feudatory, the *Daṇḍanāyaka Kēśavāditya*:—

(L. 19).—Sa(śa)ka-varsha 997neya Rākshasa-samvatsarada Pushyada puppame Ādityavāra uttarāyapaśam(sam)krānti-vyati-pātad=amdu.

25th December A.D. 1075; but the day was a Friday, not a Sunday; see *Ind. Ant.* Vol. XXIV. p. 7, No. 153.

179.—Ś. 997.—*Ind. Ant.* Vol. IV. p. 208; *PSOCI.* No. 161; *Mysore Inscr.* No. 69, p. 142. Baḷagāmve Kanarese inscription of the reign of the W. Chālukya (Sōmēśvara II.) Bhuvanaikamalla, and of his feudatory Gaṅgapermāṇaḍi Bhuvanaikavira Udayāditya:⁴—

(L. 30).—Sa(śa)ka-varsha 997neya Rākshasa-samvatsarada Pushya-sudhdha(ddha) 1 Sōmavārad=amdin=uttarāyapaśamkrānti-parvva(rvva)-nimittadin=

The date is irregular; compare above, No. 178.

Before Bhuvanaikamalla the inscription enumerates Satyāśraya [Iṇivabeḍaṅga], Vikramāditya [V.], Ayyapa [II.], Jayasimha [II.], and Trailōkyamalla [Sōmēśvara I.].

180.—*PSOCI.* No. 162; *Mysore Inscr.* No. 61, p. 132. Baḷagāmve incomplete Kanarese inscription of the reign of the W. Chālukya (Sōmēśvara II.) Bhuvanaikamalla, and of his feudatory Bhuvanaikavira Udayāditya.

181.—*Jour. Bo. As. Soc.* Vol. X. p. 213. Saundatti fragmentary Kanarese inscription of the reign of the W. Chālukya (Sōmēśvara II.) Bhuvanaikamalla, and of his feudatory, the Raṭṭa Mahāmaṇḍalēśvara Kārtavīrya (Katta) II., 'lord of Lattalūr.'

Genealogy of Kārtavīrya II.: King Nanna; his son Katta (Kārtavīrya) [I.];⁵ his son Dāyina (Dāvari); his younger brother Kanna (Kannakaira) [I.]; his son Erega (Eraga);⁶ his younger brother Aṅka;⁷ Eraga's son Sēna [I.], married Maḷaladēvi; their son Katta (Kārtavīrya) [II.], married Bhāgaladēvi; their son Sēna [II.].

182.—*PSOCI.* No. 177; *Mysore Inscr.* No. 73, p. 151. Baḷagāmve Kanarese inscription, 'probably of' the W. Chālukya 'Vikramāditya VI. Tribhuvanamalla' (according to *Mys. Inscr.* of Sōmēśvara II. Bhuvanaikamalla).⁸

¹ The full name is Trailōkyamalla-Noḷamba-Pallava-Permāḍi-Jayasimha; see Dr. Fleet's *Dynasties*, p. 453; and below, No. 188; compare also No. 753.

² The *titli* of the date only commenced 13 h. 6 m. after mean sunrise.

³ In line 42 commences a second inscription, undated and apparently unfinished, of (Vikramāditya VI.) Tribhuvanamalla.

⁴ He is described as belonging to the lineage of Brahmakshatras, and as 'lord of Kōḷālapura' and 'lord of Nandagiri.'

⁵ See above, No. 141.

⁶ See above, No. 153.

⁷ See above, No. 163.

⁸ The date is illegible; *Mys. Inscr.* gives the year Rākshasa (which would be Ś. 997).

183.—*Ś. 998.*—*Ind. Ant.* Vol. XVIII. p. 38. Gudigere fragmentary Kanarese Jaina inscription, recording gifts of the *Āchārya Śrinandi-panḍita* :—

(L. 19).—*Sa(śa)ka-varsha 998*neya *Nāḷa-saṁvatsarada śrāheyoḷu*.

The inscription mentions Kuṅkumamahādēvi, the younger sister of the Chālukya *Chakravartin Vijayādityavallabha* (i.e., probably, the W. Chālukya Vijayāditya¹), as having formerly founded a certain Jaina temple. It also mentions a Bhuvanaikamalla-Śāntināthadēva, i.e. a Jaina temple or image of Śāntinātha that had been built or set up by the W. Chālukya Sōmēśvara II. Bhuvanaikamalla.

184.—*Ś. 999.*—*Ind. Ant.* Vol. XII. p. 209, No. 17. Date of a Hulgūr Kanarese inscription of the W. Chālukyas *Vikramāditya VI.* and *Jayasimha III.* :—

(L. 14).—*Sa(śa)kanripak[āl]-ātita-saṁvatsara-sa(śa)taṅgaḷu 999*neya *Piṅgaḷa-saṁvatsarada Āshāḍa(ḍha)-su(su)ddha 2 Ādityavāra saṁkrānti-pavitrārōhanad-amidu*.

Sunday, 25th June A.D. 1077; see *ibid.* Vol. XXIII. p. 116, No. 16.

185.—*Chā. Vi. 2.*—*Ind. Ant.* Vol. VIII. p. 11. Yēūr Sanskrit and Kanarese inscription of the reign of the W. Chālukya *Mahārājādhirāja Vikramāditya VI.* Tribhuvanamalla, residing at his capital of Kalyāṇa :—

Śrīmach-Chālukya-Vikrama-varshada 2neya *Piṅgaḷa-saṁvatsarada Śrāvapa-paurṇamāsī Ādityavāra sōmagrahaṇa-mahāparvva-nimittadiṁ*.

[*Piṅgaḷa = Ś. 999*] : Sunday, 6th August A.D. 1077; a lunar eclipse, visible in India; see *ibid.* Vol. XXII. p. 109, No. 1.

Genealogy² as far as Jayasimha [II.] Jagadēkamalla as in No. 154; his son [Sōmēśvara I.] Āhavamalla; his son [Sōmēśvara II.] Bhuvanaikamalla; his younger brother Vikramāditya [VI.] Tribhuvanamalla.

186.—*Chā. Vi. 2.*—*PSOCI.* No. 163; *Mysore Inscr.* No. 60, p. 129. Baḷagāṁve Kanarese inscription of the reign of the W. Chālukya *Vikramāditya VI.* Tribhuvanamalla, residing at Ētagiri,³ and of his feudatory, the *Daṇḍanāyaka Barmadēva* :—

(L. 39).—*śrīmach-Chālukya-Vikrama-varsha 2*neya *Piṅgaḷa-saṁvatsarada Pushya-su(su)ddha 7 Ādityavārad-amdin-uttarāyāna-saṁkrāntiya parbba(rvva)-nimittam*.⁴

[*Piṅgaḷa = Ś. 999*] : Sunday, 24th December A.D. 1077.

187.—*Chā. Vi. 2.*—*PSOCI.* No. 164; *Mysore Inscr.* No. 77, p. 163. Baḷagāṁve Kanarese inscription of the reign of the W. Chālukya *Vikramāditya VI.* Tribhuvanamalla, residing at Ētagiri, and of his feudatory, the *Daṇḍanāyaka Barmadēva* :—

(L. 26).—*śrīmach-Chālukya-Vikrama-varshada yeraḍe(ḍa)neya Piṅgaḷa-saṁvatsarada Māghada pupṇame Sōmavārad-andina sōmagrahaṇa-parvva-nimittadiṁ*.⁵

[*Piṅgaḷa = Ś. 999*] : 30th January A.D. 1078, with a lunar eclipse, visible in India; but the day was a Tuesday, not a Monday.

188.—*Chā. Vi. 3* (for 4P).—*Mysore Inscr.* No. 165, p. 305. Anantapur Kanarese inscription of the reign of the W. Chālukya (*Vikramāditya VI.*) Tribhuvanamalla, and of his younger brother, the *Yuvarāja Jayasimha III.* :—

'In the 3rd year of Chālukya Vikrama, the year Siddhārthi, at the time of *uttarāyāna-saṁkrānti*'

[*Siddhārthin = Ś. 1001.*]

¹ See above, No. 32 ff.

² The genealogy is in Sanskrit, and is professedly taken from a copper-plate charter.

³ See Dr. Fleet's *Dynasties*, p. 450, note 2.

⁴ See *Ind. Ant.* Vol. VIII. p. 190, No. 6.

⁵ See *ibid.* No. 7.

⁶ The full name is Trailōkyamalla-Vīra-Nolamba-Pallava-Permanadi-Jayasimha; compare above, No. 176.

189.—Châ. Vi. 7.—*Ep. Ind.* Vol. III. p. 308. Tidgundi plates of the reign of the W. Châlukya *Mahārājādhirāja* (Vikramāditya VI.) Tribhuvanamalla, recording that the *Mahāmaṇḍalēśvara* Muñja, 'lord of Bhōgavati,' (a son of Sindarāja who was the eldest son of Bhīma) of the Sinda family,¹ sold some villages to the [Raṭṭa] *Mahāsīmanta* Kanna-sāmanta² (Kannakaira II.) :—

(L. 12).—śrī-Vikru(kra)makāla-saṁvatsarēshu shaṭsu atītēshu saptamē Dumdubhi-saṁvatsarē pravarttamānē tasya Kā[r*]ttika-su(śu)ddha-pratipad-Ādivārē.

[For Dundubhi = Ś. 1004] the date is irregular.

190.—Châ. Vi. 9.—*Ind. Ant.* Vol. XIII. p. 92. Hadali Kanarese inscription of the reign of the W. Châlukya (Vikramāditya VI.) Tribhuvanamalla, recording a grant by Jñānaśakti-panḍita,³ the disciple of Dēvaśakti-panḍita :—

(L. 5).—śrīmach-Châlukya-Vikrama-varshada 9neya Raktākshi-saṁvatsarada Chaitra-su(śu)ddha(ddha) 1 Sōmavārad-aṁdu.

[For Raktāksha = Ś. 1006] the date is irregular.

191.—Ś. 1008 (for 1009).—*Ep. Ind.* Vol. III. p. 305, and Plate. Sītābaldī (now Nāgpur Museum) inscription of the reign of the W. Châlukya *Mahārājādhirāja* (Vikramāditya VI.) Tribhuvanamalla, and of his feudatory, the *Mahāsīmanta* Dhāḍibhaṇḍaka (also called the *Rāṇaka* Dhāḍiadēva), 'who had emigrated from Latalaura,' of the Mahārāshṭrakūṭa lineage :—

(L. 1).—Sa(śa)kanṛipakāl-ātita-saṁvatsar-āntarggata-daśasata ya[tra] ashtatyadhikē (possibly altered to ashtādhikē) Saku 1008 Prabhava-saṁvatsarē 'Vaisākha-su[dha]-tritiyā-Su(śu)kradinē.

Perhaps the 8th April A.D. 1087, but the day was a Thursday, not a Friday.

192.—Ś. 1009.—*Jour. Bo. As. Soc.* Vol. X. p. 173. Notice of a Saundatti Kanarese inscription containing a date (of the reign of the W. Châlukya Vikramāditya VI., and) of the Raṭṭa *Mahāmaṇḍalēśvara* Kārtavīrya II. and his wife Bhāgaladēvi :⁴—

Śaka 1009, 'the Prabhava saṁvatsara, on the occasion of a total eclipse of the sun on Sunday, the day of the new-moon of the month Śrāvaṇa.'

Sunday, 1st August A.D. 1087; a total eclipse of the sun, visible in India.

(For an earlier date in the same inscription see above, No. 163).

193.—Châ. Vi. 12.—*Jour. Bo. As. Soc.* Vol. X. p. 287; *PSOCI.* No. 93. Koppūr Kanarese inscription of the reign of the W. Châlukya (Vikramāditya VI.) Tribhuvanamalla, of his son Jayakarna,⁵ and of the *Daṇḍādhipa* Chāmaṇḍa, and the Raṭṭa *Maṇḍalēśvara* Sēna II. (?) and the Raṭṭa *Mahāmaṇḍalēśvara* Kanna II. :⁶—

(L. 56).—śrīmach-Châlukya-Vikrama-kālada 12neya Prabhava-saṁvatsarada Pausha-kṛishṇa-chaturdāśī Vāḍḍavārad=uttarāyānasamkrāntiy-aṁdu.

[Prabhava = Ś. 1009] : Saturday, 25th December A.D. 1087; but the *tithi* which ended on this day was the 13th, not the 14th of the dark half; compare *Ind. Ant.* Vol. XXII. p. 111, No. 12.

(The same inscription in line 63 contains another date for Jayakarna, of the 46th year and the year Playa = Ś. 1043, but some of the details of it are illegible).

¹ He is also described as 'the frontal ornament of the Nāga family.'

² See below, Nos. 193 and 201.

³ Read *Vaisākha-suddha*.

⁴ See Dr. Fleet's *Dynasties*, pp. 455 and 554.

⁵ In the original the name is written *Nyāna*.

⁶ Compare below, No. 201.

⁷ See Nos. 189 and 201.

194.—Châ. Vi. 16.—*Ind. Ant.* Vol. VIII. p. 21. Notice of an Âlûr Sanskrit and Kanarese inscription of the reign of the W. Châlukya **Vikramāditya VI. Tribhuvanamalla**, being a record of grants dated—

‘at the time of the sun’s commencing his progress to the north, on Thursday, the twelfth day of the bright fortnight of the month Pushya of the Prajâpati *saṃvatsara*, which was the sixteenth of the years of the glorious Châlukya king Vikrama.’

[Prajâpati = Ś. 1013]: Thursday, 25th December A.D. 1091; see *ibid.* Vol. XXII. p. 110, No. 3.

(The same inscription contains another record of grants, dated in the 46(P49)th year, the Krôdhin *saṃvatsara* = Ś. 1046; but the given date is irregular).

195.—Châ. Vi. 16.—*PSOCI.* No. 217; *Mysore Inscr.* No. 106, p. 202. Tâlgund Kanarese inscription of the reign of the W. Châlukya (**Vikramāditya VI.**) **Tribhuvanamalla** :—

‘The sixteenth year (in words, l. 20) of his reign,¹ the Prajâpati *saṃvatsara*; Sunday; at the time of the sun’s commencing his progress to the north. The month and lunar day are not given.’

[For Prajâpati = Ś. 1013] the date is irregular; see above, No. 194.

196.—Châ. Vi. 18.—*Ind. Ant.* Vol. V. p. 342, and Plate (facing p. 46); *PSOCI.* No. 165; *Mysore Inscr.* No. 38, p. 73. Baḷagâmve Kanarese inscription of the reign of the W. Châlukya (**Vikramāditya VI.**) **Tribhuvanamalla**, recording grants made to Sômesvara-paṇḍita² (the disciple of Śrîkaṇṭha-paṇḍita who was the disciple of Kêdâraśakti), the priest of the god Nakha-rêśvaradêva at Tâvarageṛe :—

(L. 27).—śrîmach-Châlukya-Vikrama-varshade(da) 18neya Śrîmukha-saṃvatsarada Pâ(phâ)lguṇa(na)d=amavâsye Âdivâra sûryya-grahaṇad=aṃdu.

[Śrîmukha = Ś. 1015]: Sunday, 19th March A.D. 1094; a solar eclipse, visible in India; see *Ind. Ant.* Vol. XXII. p. 110, No. 7.

197.—Châ. Vi. 18 (?).—*Mysore Inscr.* No. 173, p. 328. Date in a Heggere Kanarese Hoysala inscription :³—

‘in the (?) 18th year of Châlukya Vikrama, the month Jêṣṭha, the 5th day of the moon’s increase, Monday, at the Saṅkramaṇa.’

For Châ. Vi. 18 = Ś. 1015 the date is incorrect; for Ś. 1013 = Châ. Vi. 16 it would regularly correspond to Monday, 26th May A.D. 1091.

198.—Châ. Vi. 19 (for 20 ?).—*Ind. Ant.* Vol. X. p. 185. Dambaḷ Sanskrit and Kanarese inscription of the reign of the W. Châlukya (**Vikramāditya VI.**) **Tribhuvanamalla**, and of his queen **Lakshmâdêvi**, recording grants to two Buddhist *vihâras* (or monasteries) :—

(L. 17).—śrî-Châlukya-Vikrama-varshada 19neya Yuva-saṃvatsarada Mâgha-su(śu)ddha-parichamî Âdityavârad=aṃdu uttarâyapaṣaṃkrânti-vyatipâtad=aṃdu.

The date is intrinsically wrong and of course irregular both for **Yuvan** = Ś. 1017, and for Ś. 1016.

199.—Châ. Vi. 21.—*Ind. Ant.* Vol. VI. p. 133, and Plate; *PSOCI.* No. 71. Kaṭṭagêri Kanarese inscription, recording a grant for the purpose of maintaining a tank :—

(L. 1).—śrîmach-Châlukya-Vikrama-varshada 21neya Dhâtu-saṃvatsarada Chaitra-su(śu)ddha 5 Âdityavârad=aṃdu.

[Dhâtri = Ś. 1018]: Sunday, 2nd March A.D. 1096; see *Ind. Ant.* Vol. XXII. p. 110, No. 6.

¹ The original has *Châlukya-Vikrama-varshada*.

² Compare Dr. Fleet’s *Dynasties*, p. 500, note 6.

³ Compare *Mys. Inscr.* p. 91.

200.—Châ. Vi. 21.—*PSOCI*. No. 166; *Mysore Inscr.* No. 84, p. 170. Baḷagāmve Kanarese inscription of the reign of the W. Chālukya **Vikramāditya VI. Tribhuvanamalla**, and of his feudatory, the *Daṇḍanāyaka Sarvadēva* :—

(L. 47).—śrīmach-Chālukya-Vikrama-kālāda 21neya Dhātu-saṁvatsarada Pushya-su(śu) 5 Ādivārādh(d)=aṁdin=uttarāyaṇasaṁkrānti-vyatīpātad=aṁdu.¹

[For **Dhātṛi** = Ś. 1018] the date is irregular; compare *Ind. Ant.* Vol. XXII. p. 111, No. 11.

201.—Châ. Vi. 21.—*Jour. Bo. As. Soc.* Vol. X. p. 194; *PSOCI*. No. 88. Saundatti Sanskrit and Kanarese Raṭṭa inscription, recording several grants. Date of the time of the W. Chālukya (**Vikramāditya VI. Tribhuvanamalla**) **Permāḍidēva**, and (?) of the Raṭṭa **Sēna II.** :—

(L. 39).—Vīra-Vikrama-kāla-nāmadhēya-saṁvatsar-aikaviṁśati-pramitēshv=atītēshu | varttamāna-Dhātu-saṁvatsarē Pushya-bahula-trayōdaśyām=Ādivār-ōttarāyaṇasaṁkrāntō(ṇau).

[For **Dhātṛi** = Ś. 1018] the date is irregular; see *Ind. Ant.* Vol. XXII. p. 111, No. 11.

Of Sēna II. the inscription gives the following genealogy :²—In the race of the Raṭṭas there was, as a son of king Nanna, Kārtavīrya [I.], a feudatory of [the W. Chālukya Taila II.] Āhavamalla; his son Dāvari; his younger brother Kannakaira [I.]; his son Eṇaga; his younger brother Anka; Eṇaga's son Sēna (Kālasēna) [I.], married Maḷalādēvi; their son Kannakaira (Kanna) [II.]; his younger brother Kārtavīrya [II.]; his son Sēna (Kālasēna) [II.].

The *Mahāmaṇḍalēśvara* Kārtavīrya [II.], 'lord of Lattalūr,' is also mentioned separately as a feudatory of [Vikramāditya VI.] Tribhuvanamalla, and it is stated that his wife was Bhāgalāmbikā.³

(For another date in the same inscription see above, No. 79).

202.—Châ. Vi. 22 (for 23).—*PSOCI*. No. 167; *Mysore Inscr.* No. 47, p. 107. Baḷagāmve Kanarese inscription of the reign of the W. Chālukya (**Vikramāditya VI**) Tribhuvanamalla, and of his feudatories, the *Daṇḍanāyakas* **Bhīvaṇayya**⁴ and **Padmanābhayya** :—

(L. 39).—śrīmach-Chālukya-Vikrama-kālāda 22neya Bahudhānya-saṁvatsarada Pushyad=amavāsēy=Ādityavāram=uttarāyaṇasaṁkrānti-vyatīpātad=aṁdu.⁵

[**Bahudhānya** = Ś. 1020]: 25th December A.D. 1098; but the day was a Saturday, not a Sunday.

203.—Châ. Vi. 24.—*PSOCI*. No. 113. Kiruvatti Kanarese inscription of the reign of the W. Chālukya **Vikramāditya VI. Tribhuvanamalla** :—

(L. 34).—Chālukya-Vikrama-varishada 24neya Pramāthi-saṁvatsarada Jyēshṭha-suddha-paurṇa(rṇṇa)māsi Ādityavāra sōma-grahapad=aṁdu.⁶

[**Pramāthin** = Ś. 1021]: Sunday, 5th June A.D. 1099; a lunar eclipse, visible in India; see *Ind. Ant.* Vol. XXII. p. 110, No. 4.

204.—Châ. Vi. 27.—*PSOCI*. No. 168; *Mysore Inscr.* No. 40, p. 78. Baḷagāmve Kanarese inscription of the reign of the W. Chālukya **Vikramāditya VI. Tribhuvanamalla**, and of his feudatories, the *Daṇḍanāyakas* **Anantapāla** and **Gōvindarasa** :—

(L. 47).—śrīmach-Chālukya-Vikrama-varshada 27neya Chitrabhānu-saṁvatsarada Paushya(sha)-suddha 13 Budhavārad=uttarāyaṇasaṁkrāntiy=aṁdu.

[**Chitrabhānu** = Ś. 1024]: Wednesday, 24th December A.D. 1102.

¹ See *Ind. Ant.* Vol. VIII. p. 191, No. 17.

Compare above, No. 192.

² See *Ind. Ant.* Vol. VIII. p. 191, No. 19.

³ Compare above, No. 181.

⁴ See Dr. Fleet's *Dynasties*, p. 451.

⁵ See *ibid.* No. 20.

205.—Châ. VI. 27.—PSOCI. No. 169; *Mysore Inscr.* No. 85, p. 173. Balagâmve Kanarese memorial tablet [of the reign of the W. Châlukya Vikramāditya VI. Tribhuvanamalla ?]:—

'The twenty-seventh year (in figures, 1. 6) of his reign, the Chitrabhānu samvatsara; Monday, the first day of the dark fortnight of Phālguna;' (*Mys. Inscr.* 'the 27th year of Châlukya-Vikrama').

[For Chitrabhānu = Ś. 1024] the date is irregular.

206.—Châ. VI. 27.—PSOCI. No. 170; *Mysore Inscr.* No. 58, p. 127. Balagâmve Kanarese inscription² of the reign of the W. Châlukya Vikramāditya VI. Tribhuvanamalla [and of his *Danḍanāyaka* Gōvindarasa]:—

(L. 41).—śrīmach-Châlukya-Vikrama-varshada 27neya Chitrabhānu-samvatsarada Phālguna(na)d-amāvāsye Ādityavāra saṁkramaṇa-vyatipātad-aṁdu.³

[For Chitrabhānu = Ś. 1024] the date is irregular.

207.—Châ. VI. 28.—PSOCI. No. 171; *Mysore Inscr.* No. 68, p. 139. Balagâmve Kanarese inscription of the reign of the W. Châlukya Vikramāditya VI. Tribhuvanamalla, and of his feudatories, the *Danḍanāyakas* Anantapāla and Gōvindarāja:—

(L. 45).—śrīmach-Châlukya-Vikrama-varsha 28neya Subhānu-samvatsarada Pushya-ba 10 Su(su)kravārad-aṁdin-uttarāyana-saṁkramaṇadalli.

[Subhānu = Ś. 1025]: Friday, 25th December A.D. 1103.

208.—Châ. VI. 32.—PSOCI. No. 218; *Mysore Inscr.* No. 104, p. 199. Tālgund Kanarese inscription of the reign of the W. Châlukya (Vikramāditya VI.) Tribhuvanamalla, and of his feudatories, the *Danḍanāyakas* Anantapāla and Gōvindarāja:—

(L. 20).—Châlukya-Vikrama-kālada mūvatt-erāḍe(ḍa)neya Sarvvajit-samvatsarada Chaitra-su(su)ddha-tadige Bri(bri)haspativāradalu.⁴

[For Sarvvajit = Ś. 1029] the date is irregular.

209.—Châ. VI. 32.—*Ind. Ant.* Vol. XXII. p. 252. Date of a Hāli Kanarese memorial tablet:—

'Vadḍavāra, the fifth *tithi* of the dark fortnight of Śrāvāṇa of the Sarvvajit samvatsara, which was the thirty-second year of the Châlukya-Vikrama-kāla.'

[Sarvvajit = Ś. 1029]: Saturday, 10th August A.D. 1107.

210.—Châ. VI. 33.—*Ind. Ant.* Vol. X. p. 251. Kargudari Kanarese inscription of the reign of the W. Châlukya (Vikramāditya VI.) Tribhuvanamalla, and of his feudatory, the Kādamba (of Hāṅga) *Mahāmaṇḍalēśvara* Tailapa II., 'lord of Banavāsi,' ruling at Pānthīpura:—

(L. 38).—śrīmach-Châlukya-Vikrama-varshada 33neya Sarvvadhāri-samvatsarada Herjuggiya⁵ puṇṇami Sōmavārad-andina śubha-lagnadol.

[Sarvvadhārin = Ś. 1030]: Monday, 21st September A.D. 1103; see *ibid.* Vol. XXII. p. 110, No. 5.

The inscription gives the genealogy of the Kādambas from Mayūravarmen⁶ [I.] to Jayavarman [II.] as stated in Dr. Fleet's *Dynasties*, p. 559. Jayavarman [II.] had five sons, *viz.* Māvulidēva, Tailapa [I.], Śāntivarman [II.], Chōkidēva, and Vikrama; of these, Śāntivarman [II.] married Siriyadēvī of the Pāṇḍya family; their son Tailapa [II.], married Bāchaladēvī of the Pāṇḍya family.

¹ According to *Mys. Inscr.* the inscription is of the time of the *Mahāmaṇḍalēśvara* Permaḍidēva, 'chief of the great city of Kolālapura.' This apparently would be the *Mahāmaṇḍalēśvara* Uḍayāditya-Gaṅga-Permāḍi, of the W. Gaṅga family, mentioned in Dr. Fleet's *Dynasties*, p. 452.

² "The inscription is almost wholly illegible."

³ See *Ind. Ant.* Vol. VIII. p. 191, No. 26.

⁴ See *ibid.* p. 192, No. 29.

⁵ *Herjuggi* or *Herjuggi* is the day of the full-moon of Āśvina; see *Ep. Ind.* Vol. V. p. 15.

⁶ Compare below, No. 603.

211.—Châ. Vi. 33.—*PSOCL*. No. 137; *Mysore Inscr.* No. 10, p. 17. Dâvângere Kanarese inscription of the reign of the W. Châlukya (Vikramāditya VI.) Tribhuvanamalla, and of his feudatory, the *Danḍanāyaka* Bammarasa (Barmarasa) :—

(L. 28).—Châlukya-Vikrama-kâlada 38neya Sarvvadhâri-saṁvatsarada Prshya-suddha-paṇchami Bri(bri)havârad=uttarâyanasamkramapa-vyatipâta-nimittam=âgi.

[For Sarvadhârin = Ś. 1030] probably Thursday, 24th December A.D. 1108; but this day fell in the dark, not the bright half of Pausa.

212.—Châ. Vi. 37.—*PSOCL*. No. 172; *Mysore Inscr.* No. 41, p. 82. Baḷagâmve Sanskrit and Kanarese inscription of the reign of the W. Châlukya Vikramāditya VI. Tribhuvanamalla, and of his feudatory, the Pāṇḍya *Mahāmaṇḍalēśvara* Tribhuvanamalla Kāmadēva, 'lord of Gōkarṇa,' 'ruler of the Koṅkaṇa rāshṭra' :¹—

(L. 58).—giri-Bhavalōchana-37-pramita-Vikrama-varsha-ja-Nandan-ākhyā-vatsara-bhava-Paushya(sha)māsa-sitapaksha-chaturthi Mahājavâradol=beras-iral=uttarâyanadol.²

[Nandana = Ś. 1034] : Tuesday, 24th December A.D. 1112.

213.—Châ. Vi. 38 (for 37?).—*PSOCL*. No. 173; *Mysore Inscr.* No. 79, p. 166. Baḷagâmve Kanarese memorial tablet of the reign of the W. Châlukya (Vikramāditya VI.) Tribhuvanamalla, and of his feudatories, the *Danḍanāyakas* Anantapālayya and Gōvinda-rasa :—

(L. 4).—śrīmatu-Châlukya-Vikrama-varshada 38neya Nandana-saṁvatsarada ;³ (*Mys. Inscr.* : 'in the 4th year . . . , the year Siddhârti, the month Śrāvaṇa, the 5th' ?).

[Nandana = Ś. 1034.]

214.—Châ. Vi. 38.—*PSOCL*. No. 103. Hāngal Kanarese memorial tablet of the reign of the W. Châlukya Vikramāditya VI. Tribhuvanamalla :—

(L. 1).—[śrī]mat(ch-)Châlukya-Vikrama-varshada 38neya Vijaya-saṁvatsarada Chaitra-suddha-pāḍīva Buddha(dha)vârad=aṁḍu.⁴

[Vijaya = Ś. 1035] : Wednesday, 19th March A.D. 1113⁵

215.—Châ. Vi. 38 (or 39?).—*PSOCL*. No. 174; *Mysore Inscr.* No. 96, p. 185. Baḷagâmve Kanarese memorial tablet of the reign of the W. Châlukya Vikramāditya VI. Tribhuvanamalla, and of his *Danḍanāyaka* Gōvindarasa.⁶

216.—Châ. Vi. 39.—*PSOCL*. No. 175; *Mysore Inscr.* No. 88, p. 175. Baḷagâmve Kanarese inscription of the reign of the W. Châlukya Vikramāditya VI. Tribhuvanamalla, and of his feudatories, the *Danḍanāyakas* Anantapāla and Gōvindarāja (Gōvindamayya) :—

(L. 49).—śrīmach-Châlukya-Vikrama-kâlada 39neya Jaya-saṁvatsarada Chaitrada punṇave Âdivâra grshaṇa-vyatipâta-samkramapad=aṁḍu.⁷

[In Jaya = Ś. 1036] the *tithi* of the date commenced 1 h. 29m. after mean sunrise of Sunday, 22nd March A.D. 1114; but there was no eclipse, and the Mēsha-samkrānti only took place on the 24th March A.D. 1114.

217.—Châ. Vi. 43.—*Ind. Ant.* Vol. IX. p. 75, and Plate; *PSOCL*. No. 82. Aihole Kanarese inscription, recording donations to a temple :—

(L. 1).—Châlukya-Vikrama-varishada 43[ne*]ya Viḷambi-saṁvatsarada uttarâyanasamkramapad=aṁḍu.

[Viḷamba = Ś. 1040.]

¹ See Dr. Fleet's *Dynasties*, p. 452.

² See *ibid.* p. 192, No. 30.

³ On this day the *tithi* of the date commenced 5 h. 10 m. after mean sunrise.

⁴ The details of the date seem quite doubtful.

⁵ See *Ind. Ant.* Vol. VIII. p. 190, No. 3.

⁶ See *ibid.* No. 31.

⁷ See *Ind. Ant.* Vol. VIII. p. 192, No. 32.

218.—Chā. Vi. 45¹ (for 47 ?).—*Jour. Bo. As. Soc.* Vol. XI. p. 247. Koḍikop Kanarese inscription of the W. Chālukya (Vikramāditya VI.) Tribhuvanamalla, reigning at Jayantipura, and of his feudatory, the Sinda *Mahāmaṇḍalēśvara Ācha (Āchama) II.* :²—

(L. 16).—śrīmat(ch-)Chālukya-Vikramā-kālāda 45neya Śubhakri(kṛi)t-saṁva-
chehha(tsa)rada Chaitra-su(śu)ddha 8 Sōmavāra uttarāyaṇasaṁkrāntiy-aṁdu.

The date is intrinsically wrong and of course irregular for both Śubhakrit = Ś. 1044 and Ś. 1042.

219.—Chā. Vi. 46.³—*PSOCI.* No. 138; *Mysore Inscr.* No. 7, p. 14. Dāvāṅgere Kanarese inscription of the reign of the W. Chālukya Vikramāditya VI. Tribhuvanamalla, and of his feudatory, the *Mahāmaṇḍalēśvara Tribhuvanamalla Pāṇḍyadēva*, 'lord of Kāñchīpura,' ruling the Nolambavāḍi Thirty-two-thousand :—

(L. 37).—Chālukya-Vikrama-varshada 46neya Plava-saṁvatsarad=Āśvija-bahula-pañchami
Ādivārad=aṁdu.

[Plava = Ś. 1043] : Sunday, 2nd October A.D. 1121.

220.—Ś. 1045.—*Ind. Ant.* Vol. XIV. p. 15. Tērdāl Kanarese Jain inscription. Date of a grant of the *Maṇḍalika Goṅka*⁴ (Goṅkidēvarasa) of Tēridāla, a dependent of the W. Chālukya Vikramāditya VI. Tribhuvanamalla Permāḍirāya, and of his feudatory, the Rāṭṭa *Mahāmaṇḍalēśvara Kārtavīrya II.*,⁵ 'lord of Lattanūra :—

(L. 49).—Sa(śa)ka-va[r*]sha 1045neya Śu(sō)bhakri(kṛi)t-saṁvatsarada Vaisākhada
puṇṇami Bra(bṛi)haspativāradalu.

Thursday, 12th April A.D. 1123; see *ibid.* Vol. XXIII. p. 116, No. 19.

The inscription mentions, as Goṅka's preceptor, the *Maṇḍalāchārya Māghaṇandi-saiddhāntika*, the priest of the temple of Rāpa-Nārāyaṇa at Kollāpura (Kollagira). The same Māghaṇandi-saiddhāntika also is described as the preceptor of the *Sāmanta Nimbādēva*.⁶

(For later dates in the same inscription see below, Nos. 256 and 258).

221.—Ś. 1047.—*Ind. Ant.* Vol. XII. p. 212, No. 56. Date of a Narēndra Kanarese inscription of the W. Chālukya Vikramāditya VI. :—

(L. 108).—Śaka-varshaṁ 1047neya Visvā(śvā)vasu-saṁvatsarada [Bhā]drapada-ba 13
Śukravāra mahātithi-yugādi-aṁdu.

Friday, 28th August A.D. 1125; see *ibid.* Vol. XXIII. p. 124, No. 67.

222.—*PSOCI.* No. 176; *Mysore Inscr.* No. 63, p. 135. Baḷagāṁve Kanarese inscription of the reign of the W. Chālukya (Vikramāditya VI.) Tribhuvanamalla, and of his feudatory, the *Danḍanāyaka Guṇḍamarasa*.

223.—*PSOCI.* No. 108. Chauḍadāmpur incomplete Kanarese inscription of the reign of the W. Chālukya Vikramāditya VI. Tribhuvanamalla; of his feudatory, the *Mahāsāmāntādhīpati Gōvindarasa*, and of a subordinate (?) of the latter, the Gutta *Mahāsāmanta* (?) Malla (Mallidēva),⁷ the son of Gutta I. who was the son of Māgutta.

224.—[Ś. 872*].—*Jour. Bo. As. Soc.* Vol. XI. p. 224. Narēgal incomplete Kanarese inscription of the reign of the W. Chālukya Vikramāditya VI. Tribhuvanamalla Permāḍi, and of

¹ For a Drākshārāma inscription dated in S. 1042 and in the Chālukya-Vikrama year 45, see *Ep. Ind.* Vol. IV. p. 37.

² See Dr. Fleet's *Dynasties*, p. 574; and below, No. 224.

³ For two Kanarese inscriptions at the fort of Gutti, of the years 46 and 47 (Plava and Śubhakrit), see *South. Ind. Inscr.* Vol. I. p. 167.

⁴ He is stated to have sprung from the family of Jimātavāhana; compare below, No. 301 ff.

⁵ But the date of the grant does not belong to his time; see Dr. Fleet's *Dynasties*, p. 554, note 4; and above, No. 201.

⁶ See also below, Nos. 319 and 413.

⁷ See Dr. Fleet's *Dynasties*, p. 80. The time of the inscription according to Dr. Fleet is about A.D. 1115.—Compare below, No. 298.

the Sinda, *Mahāmaṇḍalēśvara* Permādi I., ruling at Erambarage; records a grant which is stated to have been made¹—

(L. 47).—Sa(sa)ka-varsha 872neya Saumya-saṁvatsarada Pushya-su(su)ddha-puṇṇime Sôma-vāra sôma-grahanaṁ=uttarāyana-saṁkrānti-y-aṁdu.

The *tithi* of the date ended on Monday, 7th January A.D. 950; but there was no eclipse, and the Uttarāyana-saṁkrānti had taken place already on the 23rd December A.D. 949; see *Ind. Ant.* Vol. XXIV. p. 12, No. 173.

In the Sinda family, Âchugi [I.]; his younger brothers Nāka, Siṅga [I.], Dāsa, Dāva, Chaṇḍa (Châvunḍa) [I.], and Chāva; Âchugi's son Bamma; after him, Âchugi (Âcha) [II.] (put to flight the Poysala, took Gôve, put to flight Lakshma, seized upon the Koṅkaṇa, etc.), married Mahādēvi (Mādēvi); their son Permādi [I.]²

225.—Ś. 1045(P).—PSOCI. No. 146; *Mysore Inscr.* No. 4, p. 8. Chitaldurg Kanarese inscription of the W. Châlukya Jagadēkamalla II.,³ and of his feudatory, the *Mahāmaṇḍalēśvara* Vijaya-Pāṇḍyadēva,⁴ 'lord of Kāuchipura,' residing at Uchchaṅgi and ruling the Nôlambavāḍi Thirty-two-thousand:—

'Śaka 1045 (in figures, the last two effaced, l. 28), the Śôbhakṛit saṁvatsara; Sunday, the tenth day of the bright fortnight of Phālguna;' (*Mys. Inscr.*: 'at the time of the equinox'?).

The date is irregular.

226.—Ś. 1051*.—*Ind. Ant.* Vol. XII. p. 212, No. 57. Date of an Ingleshwar Kanarese inscription of the W. Châlukya Sômesvara III., and of his feudatory, the Kalachurya *Mahāmaṇḍalēśvara* Permādi:⁵—

Śakha(ka)-varusha 1051neya Kilaka-saṁvatsarada Kārttika-paurṇamāseyo sômagrahaṇa-nimittam.

8th November A.D. 1128, with a lunar eclipse, visible in India; see *ibid.* Vol. XXIII. p. 127, No. 84.

227.—PSOCI. No. 178; *Mysore Inscr.* No. 42, p. 87. Baḷagāṁve Kanarese inscription of the third year of the reign of the W. Châlukya Sômesvara III. Bhûlôkamalla, and of his feudatory, the Kādamba (of Hāṅgal) *Mahāmaṇḍalēśvara* Taila II.,⁶ 'lord of Banavāsapura':—

'The third year (in figures, l. 70) of his reign, the Kilaka saṁvatsara; Thursday, the day of the new-moon of Māgha.'

[For Kilaka = Ś. 1050] the date is irregular; it would correspond to Wednesday, 20th February A.D. 1129.

228.—*Ind. Ant.* Vol. X. p. 132. Hunaśikaṭṭi Kanarese inscription of the 6th year (of the reign) of the W. Châlukya (Sômesvara III.) Bhûlôkamalla, recording a gift by the *Mahāmaṇḍalēśvara* Mārasimhadēvarasa:—

(L. 1).—śrīmad-Bhûlôkamalladēvara varāsa(rsha) 6neya Sāvā(dhā)raṇa-saṁvatsarada Phālguna(na)-śu 5 Âdivārad=aṁdu.

[For Sādhāraṇa = Ś. 1052] the date is irregular.

¹ The date, of course, has nothing to do with the reign of Vikramāditya VI. See Dr. Fleet's *Dynasties*, p. 575, note 3.—Compare below, No. 234.

² Compare below, No. 243.

³ See Dr. Fleet's *Dynasties*, p. 457, note 3; compare also below, No. 229. According to Dr. Fleet, Jagadēkamalla, at the time of the date, 'may possibly have held some administrative post under his grandfather (Vikramāditya VI.). But the record speaks of him as if he were himself the paramount sovereign.'

⁴ Described as 'defeater of the designs of Rājiga-Chôla' (i.e. Rājendra-Chôla II., Kulôttuṅga-Chôla I.); see below, Nos. 250 and 571.

⁵ See Dr. Fleet's *Dynasties*, p. 470; and compare below, No. 238, where the name (in Sanskrit) is Paramardīn.

⁶ The Tailapa II. in No. 210.

229.—*Ind. Ant.* Vol. VI. p. 140; *PSOCI.* No. 44. Bādāmi Kanarese inscription of the second year (of the reign) of the W. Chālukya *Pratāpa-chakravartin Jagadēkamalla II.*, recording a grant by his *Danḍanāyaka* Mahādēva and Pāladēva:—

(L. 21).—Chālukya-Jagadēkamalla-varishada eraḍe(ḍa)neya Siddhārthi-saṁvatsarada Kārttika-su(su)ddha-trayōdasi(sī) Sōmavārad-aṁḍu.

[Siddhārthin = Ś. 1061]: Monday, 6th November A.D. 1139.

230.—*PSOCI.* No. 179; *Mysore Inscr.* No. 62, p. 134. Baḷagāṁve Kanarese inscription of the reign¹ of the W. Chālukya (Sōmēśvara III.) Bhūlōkamalla:—

'The Siddhārthi saṁvatsara; Sunday, the thirteenth day (in words, l. 21) of the bright fortnight of Pushya; at the time of the sun's commencing his progress to the north.'

[For Siddhārthin = Ś. 1061] the date is irregular.

231.—*PSOCI.* No. 139; *Mysore Inscr.* No. 8, p. 16. Dāvāngere Kanarese inscription of the reign² of the W. Chālukya (Sōmēśvara III.) Bhūlōkamalla, and of his feudatory Virā-Pāṇḍyadēva, residing at Uchchaṅgīdurga and ruling the Nōḷambavāḍi Thirty-two-thousand:—

'Monday, the eleventh day (in words, l. 23) of the (?) bright fortnight of Pushya of the Dundubhi saṁvatsara; at the time of the sun's commencing his progress to the north.'

[For Dundubhi = Ś. 1064] the date is irregular.

232.—*Ep. Ind.* Vol. V. p. 15. Managōḷi Kanarese inscription of the 6th year of the reign of the Kaḷachūrya Bijjala (below, No. 278); in lines 1-59 refers to certain events of the time of the W. Chālukya *Pratāpa-chakravartin Jagadēkamalla II.* (and his feudatory, the *Danḍanāyaka* Bammaṇayya), and gives the following date of the 5th year of that king's reign:—

(L. 39).—nija-bhuja-vijaya-nām-āṁkita-varshada 5neya Dundubhi-saṁvatsarada Puishya-suddha 10 Bri(bri)haspativārad-aṁḍ-uttarāyana-saṁkrānti-vyatipāta-nimittav-āgi.

[For Dundubhi = Ś. 1064] the date is irregular; see *ibid.* p. 11.

The inscription, before Ayyapa [I.] (the father of Vikramāditya IV.), mentions a Chalukya Kattiyaradēva.³ It also states that Taila [II.] annihilated the Rāshṭrakūṭas Kakkara (Kakkarāja II.) and Rapakambha (Rapaṣambha); see above, No. 150.

233.—*Jour. Bo. As. Soc.* Vol. XI. p. 253. Koḍikop Kanarese inscription of the 7th year (of the reign) of the W. Chālukya *Pratāpa-chakravartin Jagadēkamalla II.*, and of his feudatory, the Sinda *Mahāmaṇḍalēśvara Jagadēkamalla Permāḍi I.*:⁴—

(L. 22).—Jagadēkamalla-varshada 7neya Raktākshi-saṁvatsarada Pushyad-amāvāsye Sōmavāra uttarāyana-saṁkrānti-vyatipāta-sūryyagrahaṇad-aṁḍu.

[For Raktāksha = Ś. 1066] probably Monday, 25th December A.D. 1144; the Uttarāyana-saṁkrānti took place on Sunday, the 24th December, and there was a solar eclipse which was visible in India on Tuesday, the 26th December, A.D. 1144.

234.—[Ś. 872].—*Jour. Bo. As. Soc.* Vol. XI. p. 239. Narēgal incomplete Kanarese inscription of the reign of the W. Chālukya *Jagadēkamalla II.*, and of the Sinda *Mahāmaṇḍalēśvara Jagadēkamalla Permāḍi I.*, ruling at Erāmbirage; records a grant which is stated to have been made⁵—

(L. 37).—Sa(sa)ka-varsha 872neya Sādhārāpa-saṁvatsarada Kārttikad-amāvāsye Vri(bri)haspativārad-aṁḍina sūryya-grahaṇadol.

The date is irregular; but see *Ind. Ant.* Vol. XXIV. p. 5, No. 144.

¹ But see Dr. Fleet's *Dynasties*, p. 455, note 6.

² But see *ibid.* — Part of the inscription is illegible.

³ Compare above, No. 51.

⁴ See Dr. Fleet's *Dynasties*, p. 575.

⁵ The date, of course, has nothing to do with the reign of Jagadēkamalla II. See Dr. Fleet's *Dynasties*, p. 575, note 2. — Compare above, No. 224.

Permādi [I.] vanquished Kulasēkharāṅka, besieged and beheaded Chaṭṭa, put to flight [the Kādamba of Goa] Jayakēsin [II.], and defeated Biṭṭiga (*i.e.* the Hoysala Vishṇuvardhana).

235.—*PSOCI.* No. 97. Lakshmēshwar Sanskrit and Kanarese inscription of the 10th year (of the reign) of the W. Chālukya *Pratāpa-chakravartin* Jagadēkamalla II., and of the [Kādamba of Goa?] *Mahāmaṇḍalēśvara* Jayakēsin [II. ?]:—

(L. 55).—Jagadēkamalladēva-varshada 10neya Prabhava-saṁvatsarada Āshāḍha-śuddha 12 Bṛihaspativāra dakṣiṇāyanasaṁkramaṇa-vyatipātāṁ (?).

[For Prabhava = Ś. 1069] probably Thursday, 26th June A.D. 1147; but this day fell in the dark, not the bright half of Āshāḍha.

236.—*PSOCI.* No. 116; *Mysore Inscr.* No. 34, p. 67. Harihar Kanarese inscription¹ of the W. Chālukya Perma Jagadēkamalla II., and of his feudatory, the *Mahāmaṇḍalēśvara* Vira-Pāṇḍyadēva, ruling the Nolambavāḍi Thirty-two-thousand:—

Mys. Inscr.: 'in the 10th year of the emperor Jagadēkamalla, the year Prabhava, the month Ashvija, new-moon day, Sunday.'

[Prabhava = Ś. 1069]: Sunday, 26th October A.D. 1147.

237.—*PSOCI.* No. 180; *Mysore Inscr.* No. 44, p. 97. Baḷagāmve Kanarese inscription of the 13th (?) year² (of the reign) of the W. Chālukya *Pratāpa-chakravartin* Jagadēkamalla II., and of his feudatory, the *Mahāmaṇḍalēśvara* Tribhuvanamalla Jagaddēva³ of the Śāntara family of Paṭṭi-Pombuchchapura:—

(L. 40).—Jagadēkamalladēva-varshada 13neya Śukla-saṁvatsarada Kārttikada paurnṇamāsyē Sōmavāra sōma-grahapad=amdu.

[For Śukla = Ś. 1071] the date is irregular.

238.—*PSOCI.* No. 119; *Mysore Inscr.* No. 32, p. 60. Harihar Kanarese inscription of the time⁴ of the W. Chālukya Jagadēkamalla II., and of the Kaḷachurya Bijjala and his servant, the *Mahāmaṇḍalēśvara* Vijaya-Pāṇḍyadēva, the ruler of the Nolambavāḍi Thirty-two-thousand (an official of whom was a person of Sinda descent, called king Īśvara,⁵ 'lord of Karahāṭa').

239.—Ś. 1076.—*Ind. Ant.* Vol. XII, p. 209, No. 18. Date of a Hulgūr Kanarese inscription of the W. Chālukya Taila III.:—

(L. 18).—Śakanri(nṛi)pakāl-ātita-śatamgaḷ 1076neya Bhāva-saṁvatsarada Āśā(śā)-ḍa(ḍha)-su(śu)ddha 5 Bṛi(bṛi)haspativārad=amdu.

Thursday, 17th June A.D. 1154; see *ibid.* Vol. XXIII, p. 116, No. 21.

240.—*PSOCI.* No. 181; *Mysore Inscr.* No. 45, p. 100. Baḷagāmve Kanarese inscription of the 6th year (of the reign) of the W. Chālukya (Taila III.) Trailōkyamalla, and of the Kaḷachurya *Mahāmaṇḍalēśvara* Bijjaṇa, 'lord of Kālaṅjara,' and his *Daṇḍanāyaka* Mahādēva:—

(L. 44).—Trailōkyamalla-varshada 6neya Yuva-saṁvatsarada Māghad=amāvāsyeṇa uttarāyaṇasaṁkrānti-Sōmavāra-vyatipātad=amdu.

[For Yuva = Ś. 1077] the day may be the 25th December A.D. 1155, but this was a Sunday, and the new-moon day of Pausa.

¹ See Dr. Fleet's *Dynasties*, p. 569; and compare below, Nos. 240 and 254, and No. 405, note.

² Much of the inscription is illegible.

³ See Dr. Fleet's *Dynasties*, p. 457, note 5. ⁴ Compare below, Nos. 388 and 584.

⁵ The photograph does not show the date; see Dr. Fleet's *Dynasties*, p. 470.

⁶ See *ibid.* p. 577.

241.—*Ś. 1080.*—*Ind. Ant.* Vol. XI. p. 273. Siddāpur Kanarese inscription of the reign of the Kādamba (of Goa) *Mahāmaṇḍalēśvara Śivachitta Permāḍi*, 'lord of Banavāsī,' and (his brother) the *Yuvarāja Vijayāditya II.*,¹ staying near Sampagāḍi:—

(L. 28).—*Śaka-varṣam*(rsham), 1080neya Bahudhānya-saṁvatsarada Āśā(shā)ḍa(ḍha)d=amavāsya Sōmavārad=amdu dakṣiṇāyanasaṁkrānti-vyatipātada puṇya-tithiyolu.

27th June A.D. 1158, but this was a Friday, not a Monday; see *ibid.* Vol. XXIV. p. 8, No. 154.

242.—*Jour. Bo. As. Soc.* Vol. IX. p. 296. Golihalli Kanarese inscription of the 14th, 17th and 26th years (of the reign) of the Kādamba *Mahāmaṇḍalēśvara Koṅkaṇa-chakravartin Śivachitta Permāḍi*, 'lord of Banavāsī,' ruling at his capital of Gōve (Goa):—

(L. 33).—*śrī-Kādamba-Śivachitta-śrī-Vira-Permmāḍidēva-varshada* 14neya Vikrama-saṁvatsarada Vaiśākha-māsada śuddha-daśamī Sōmavārad=amdu.

[For Vikrama= *Ś. 1082* = Ky. 4261] the date is irregular.

(L. 37).—*Permmāḍidēva-varshada* 17neya Svabhānu-saṁvatsarada Mārggaśira-bahula-daśamī (?)² Sōmavārad=amdu.

[Svabhānu = *Ś. 1085* = Ky. 4264]: Monday, 18th November A.D. 1163.

(L. 54).—*Permmāḍidēva-varshada* 26neya Nandana-saṁvatsara Māghamāsa-śuddha-daśamī Brīhaspativārad=amdu.

[Nandana = *Ś. 1094* = Ky. 4273]: Thursday, 25th January A.D. 1173.

243.—*Ś. 1084* (for 1085).—*Jour. Bo. As. Soc.* Vol. XI. p. 259; *PSOCI.* No. 67.. Paṭṭadakal Kanarese inscription of the Sinda *Mahāmaṇḍalēśvara Chāvunḍa II.*, (who was, or rather had been) a feudatory of the W. Chālukya *Nūрмаḍi-Taila* (Taila III.)³:—

(L. 66).—*Sa(śa)ka-varshada* sāsiraḍ-embhatta-nālke(lka)neya Subhānu-saṁvatsarada Jē(jyē)shṭha-su(śu)ddha-paurṇamāsye Sōmavāra sōmagrahaṇa-vyatipāta-saṁkramapada puṇya-tithiyal.

The date is irregular; see *Ind. Ant.* Vol. XXIV. p. 15, No. 187.

In the Sinda family, Āchugi [I.]; his brothers Nāka, Simha [I.], Dāsa, Dāma, Chāvunḍa [I.], and Chāva. Ācha's (Āchugi's) son Bamma; his younger brother Siṅga [II.]; his son Ācha [II.] (burnt Gōve and repulsed [the Śilāhāra] Bhōja [I.]); his son Pemma (Permāḍi) [I.]; his younger brother Chāvunḍa [II.], married Dēmaladēvi; their sons Āchidēva [III.] and Permmāḍi [II.].⁴

244.—*PSOCI.* No. 140; *Mysore Inscr.* No. 9, p. 17. Dāvāngere Kanarese inscription⁵ of the *Mahāmaṇḍalēśvara Vijaya-Pāṇḍyadēva*, who ruled the Nolambavāḍi Thirty-two-thousand and resided at Uchchaṅgi, of the 15th year of the reign of (?) the W. Chālukya *Tailapa Trailōkyamalla* (Taila III.), the year Pārthiva.⁶

[Pārthiva = *Ś. 1087*.]

245.—*PSOCI.* No. 120; *Mysore Inscr.* No. 30, p. 57. Harihar Kanarese inscription⁷ of the time of the W. Chālukya *Nūрмаḍi-Tailapa* (Taila III.), and of the Kaḷachurya *Bijjala* and his dependent *Kasapayya-nāyaka*.⁸

¹ Compare below, Nos. 249 and 254.

² According to the translation this should be *pañchamī*, and the European equivalent of the date, given above, is for this *tithi*.

³ See Dr. Fleet's *Dynasties*, p. 575.

⁴ Compare Nos. 224 and 247.

⁵ Part of the inscription is illegible.

⁶ See Dr. Fleet's *Dynasties*, p. 459, note 3, and p. 463, note 1. According to Dr. Fleet, the record belongs to a period subsequent to the death of Taila III.

⁷ The date is illegible; see Dr. Fleet's *Dynasties*, p. 472.

⁸ See below, Nos. 279 and 281.

246.—*PSOCI.* No. 104 and No. 105. Two Hāṅgal Kanarese memorial tablets of the time of the W. Chālukya Nūrmāḍi-Tailapa (Taila III.).

247.—Chā. Vi. 94.—*Ind. Ant.* Vol. IX. p. 97; *PSOCI.* No. 83. Aihole Kanarese inscription of the Sinda *Mahāmaṇḍalēśvara* Chāmuṇḍa (Chāvunḍa) II. and his sons (by Shriyādēvi) Bijjala and Vikrama :—

(L. 23).—śrīmach-Chālukya-[Vikrama-varshada] 94neya Virōdhi-samvatsarada . . .¹
[Virōdhi = Ś. 1091.]

248.—Ś. 1091.—*PSOCI.* No. 141; *Mysore Inscr.* No. 13, p. 23. Dāvāngere Kanarese inscription of the *Mahāmaṇḍalēśvara* Vijaya-Pāṇḍyadēva, 'lord of Kāñchīpura,' residing at Uchchaṅgi and ruling the Nōlambavāḍi Thirty-two-thousand :—

(L. 16).—śrīmat-Saka-varshada² 1091neya Virōdhi-samvatsarada dvitīya-Śrāvāṇa-suddha-puṇṇami Sōmavārad-amḍu.³

In the given year Śrāvāṇa was intercalary, but otherwise the date is irregular; see *Ind. Ant.* Vol. XXIV. p. 15, No. 188.

249.—Ky. 4270 and 4272.—*Jour. Bo. As. Soc.* Vol. IX. p. 278; *Ind. Inscr.* No. 32. Halsi inscription⁴ of the 23rd year of the reign of the Kādamba (of Goa) Śivachitta Paramardin, and of the 25th year (of his reign, and) of his younger brother Vishnuchitta; (the first part of the inscription was composed by Madhusūdanasūri, the second by Yajñēśvarasūri⁵) :—

(L. 18).—Saṁnivṛttē Kalēḥ kālē kha-sapta-dvi-payōnidhau | pravardhamānē tad-rājyē trayō-vimśē Virōdhini | samvatsarē Suchau māsē darśē vārē Vṛi(bṛi)haspatēḥ | dakṣiṇāyana-saṁkrāntau.

[Virōdhi = Ś. 1091 = Ky. 4270]: Thursday, 26th June A.D. 1169; see *Ind. Ant.* Vol. XVII. p. 264, No. 15.

(L. 34).—Saṁnivṛttē Kalēḥ kālā(lē)=śva(śvi)-sapta-dvi-payōnidhau | pravardhamānē tad-rājyē pañcha-vimśē samē Kharē | Māghē cha suddha-dvādaśyām māsē vārē Vṛi(bṛi)haspatēḥ | saṁprāptē Vaidhṛitau yōgē.

[For Kharā = Ś. 1093 = Ky. 4272] this date is irregular; see *ibid.* p. 265, No. 16.

The mythical Jayanta (Trilōchana); in his race, Jayakēsin [I.], conquered the Ālupas and established the Chālukyas in their kingdom, and took his abode at Gōpakapaṭṭana (Goa); his son Vijayāditya [I.]; his son Jayakēsin [II.] married Mailalamahādēvi, the daughter of the [W.] Chālukya Vikramārka (Vikramāditya VI.); their son Paramardin Śivachitta; his younger brother Vishnuchitta.

250.—Ś. 1093* and 1095*.—*PSOCI.* No. 118; *Mysore Inscr.* No. 28, p. 51. Harihar Kanarese inscription of the *Mahāmaṇḍalēśvara* Vijaya-Pāṇḍyadēva,⁶ 'lord of Kāñchīpura,' and of his *Danḍandītha* Vijaya-Permāḍi :—

(L. 49).—Śaka-varsha 1093re(ṛa)neya Vikṛita-samvatsarada Pushya-bahula-pāḍīva Śukravārad=uttarāyana-saṁkrāmapad-amḍu.

(L. 63).—Śaka-varsha 1095neya Namdana-samvatsarada Bhādrapada-suddha-tadige Bṛihaspativārad-amḍu.

Friday, 25th December A.D. 1170;⁷ and Thursday, 24th August A.D. 1172.

¹ Compare above, No. 243.

² Read *śrīmach-Chhaka*.

³ Professedly copied from a copper-plate (or copper-plates).—The descriptions of the boundaries contain Kanarese words and inflections.

⁴ Compare below, No. 289.

⁵ Described as 'defeater of the designs of Rājiga-Chōla'; see above, No. 225.

⁶ The inscription also mentions a Kādamba *Mahāmaṇḍalēśvara* Kētarasa, 'lord of Uchchaṅgigiri'; see Dr. Fleet's *Dynasties*, p. 564.

⁷ On this day the *tīthi* of the date commenced 2 h. 36 m. after mean sunrise.

² The full details of the date are illegible.

⁴ See *Ind. Ant.* Vol. XIX. p. 156, No. 37.

251.—*PSOCL.* No. 117; *Mysore Inscr.* No. 35, p. 71. Harihar Kanarese inscription of the *Mahāmaṇḍalēśvara* *Vīra-Pāṇḍyadēva* and *Vijaya-Pāṇḍyadēva*.¹

252.—*PSOCL.* No. 135; *Mysore Inscr.* No. 36, p. 71. Harihar Kanarese inscription of *Vijaya-Pāṇḍyadēva*(?).²

253.—*Ś. 1095* and *1103*.—*As. Res.* Vol. IX. p. 431; Colebrooke's *Misc. Essays*, Vol. II. p. 271. Translation of a 'Curugode' (Kurgōḍ, now Calcutta Museum) Sanskrit and Kanarese inscription³ of the reign⁴ of the W. Chālukya Tribhuvanamalla *Vīra-Sōmēśvara* (*Sōmēśvara IV.*), reigning at Kalyāṇa; recording grants by the *Mahāmaṇḍalēśvara* *Iṛmaḍi-Rāchamalla* (surnamed *Sindagōvinda*) of Kuṛugōḍadurga:—

'The year of Śālivāhan⁵ 1095 in the Vijaya year of the cycle, and on the 30th of the month Mārgaśīra, on Monday, in the time of an eclipse of the sun.'

'The year of Śālivāhan⁶ 1103, of the cycle Plava, and on the 15th of Kārttika, on Monday, in the gracious time of the moon's eclipse.'

Both dates are irregular.

In the lineage of the long-armed Sinda was Rāchamalla; to him and his wife Sōvaladēvi was born Iṛuṅgula; and to him and his wife Bōhaladēvi were born Iṛmaḍi-Rāchamalla and Sōma.

254.—*Ky. 4275*.—*Jour. Bo. As. Soc.* Vol. IX. pp. 266 and 287. Two Dēgāmve inscriptions⁶ of the 28th year of the reign of the Kādamba Śivachitta *Permāḍi*, residing at Gōpakapuri (Goa); recording a grant made at the request of his queen *Kamalādēvi*; (composed by Gōvindadēva):—

(P. 269, l. 33, and p. 291, l. 42).—pañhasaptatyadhika-dviśatōttara-chatuṣsahasrēshu Kaliyuga-samvatsarēshu parāvrittēshu pravartamānē cha śrī-Kādamba-Śivachitta-Vīra-Permāḍidēvasya pravardhamāna-vijayarājya-samvatsarē ashtāvimśē Jay-āhvayē Mārgaśīrshē amāvāsyārī Bhaumavārē sūryagrahaṇa-parvaṇi.

[Jaya = *Ś. 1096* = *Ky. 4275*]: Tuesday, 26th November A.D. 1174; a solar eclipse, visible in India; see *Ind. Ant.* Vol. XVII. p. 266, No. 17.

The mythical Trilōchana-Kadamba; in his lineage, the Kādamba kings; in their family, Gūhalla Vyāghramārin; his son Shashthadēva [I.]; his son Jayakēsin [I.], a god of death to the king of Kāpardika-dvīpa, uprooted Kāmādēva etc.; his son Vijayāditya [I.]; his son Jayakēsin [II.], married Mailalamahādēvi, the daughter of the [W.] Chālukya Vikrama (Vikramāditya VI.); their son Śivachitta *Permāḍi*, married *Kamalādēvi*, the daughter of Kāmādēva of the lunar race and of his wife, the Pāṇḍya princess Chaṭṭaladēvi.

255.—*Jour. Bo. As. Soc.* Vol. IX. p. 294. Dēgāmve Kanarese inscription, recording the construction of two temples at the command of *Kamalādēvi*, the queen of the Kādamba (of Goa) Śivachitta *Permāḍi* (and daughter of king Kāma, here described as belonging to the solar race, and Chaṭṭaladēvi, here described as belonging to the lunar race?).

¹ The inscription is almost entirely illegible. The date given in *Mys. Inscr.* is quite incorrect.

² The greater part of the inscription is illegible.

³ I owe an account of this inscription to Dr. Fléet; for some fantastic characters in it see *Ind. Ant.* Vol. XV. p. 304.

⁴ But compare Dr. Fleet's *Dynasties*, p. 463, note 4.

⁵ *Śālivāhana* really does not occur in these dates; see *Ind. Ant.* Vol. XXX. p. 208, note 29.

⁶ The two inscriptions are identical, one being in Nāgarī and the other in Kanarese characters; compare above, No. 48. Both (called *upala-sāṇa*) are perhaps copies of a copper-plate inscription.

⁷ Compare above, No. 254.

256.—*Ś. 1104**.—*Ind. Ant.* Vol. XIV. p. 15. Têrdâl Kanarese Jaina inscription. Date of a private grant:—

(L. 59).—Sa(śa)ka-varshaṁ 1104neya Plava-saṁvatsarada Âśvayuja-bahula 3 Âdivârâdalu.

Sunday, 27th September A.D. 1181; see *ibid.* Vol. XXIII. p. 129, No. 100.

(For other dates in the same inscription see Nos. 220 and 258).

257.—*Ś. 1106*.—*PSOCI.* No. 102. Dambaḷ Sanskrit and Kanarese inscription of the W. Châlukya Sômesvara IV. Tribhuvanamalla:—

(L. 71).—Sa(śa)kanri(nri)pakâl-âtita-saṁvatsara 1106neya Krôdhi-saṁvatsarad-Âśâ(shâ)ḍa(ḍha)d=amâvâsyê Sôma-vâra sûryyagrahaṇa-saṁkrânti-vyatipâtad=amdu.¹

Perhaps Monday, 9th July A.D. 1184; but there was no eclipse and no Saṁkrânti on that day.

258.—*Ś. 1109*.—*Ind. Ant.* Vol. XIV. p. 15. Têrdâl Kanarese Jaina inscription. Date of a grant by the *Danḍanâdyaka Bhâyidêva*, the son of the *Danḍanâdyaka Têjugi*:²—

(L. 79).—Sa(śa)ka-varshaṁ(rshaṁ) 1109neya Plavaṅga-saṁvatsarada Chaitra-su 10 Bri(bri)haspatiivârâd=amdu.

The date is irregular; see *ibid.* Vol. XXIV. p. 15, No. 190.

(For other dates in the same inscription see above, Nos. 220 and 256).

259.—*Ś. 1110**.—*Ind. Ant.* Vol. XII. p. 96. Toragal Kanarese inscription of (the *Mahâmaṇḍalêśvara*) Barma,³ ruling at Toragale, recording a grant by his wife Suggaladêvi:—

(L. 33).—Sa(śa)ka-varshaṁ 1110neya Plavaṅga-saṁvatsarada Puśya(shya)-bahula 10 Vaḍḍavârav=uttarâyanasamkramaṇa-vyatipâtadalu.

Saturday, 26th December A.D. 1187; see *ibid.* Vol. XXIII. p. 130, No. 101.

The *Mahâmaṇḍalêśvara* Âhavamalla-Bhûtiga (as a feudatory of Nûrmaḍi-Taila, i.e. Taila II., killed Pañchala⁴); his son Dâvaramalla [I.]; his son Chaṭṭa [I.]; his son Dâvaramalla [II.]; his son Chaṭṭa [II.]; his son Bhûta (Bhûtiga); his son Barma.

260.—*Ś. 1111*.—*PSOCI.* No. 90.⁵ Hângal Kanarese inscription of the W. Châlukya Sômesvara IV. Tribhuvanamalla, and of his feudatory, the Kâdamba (of Hângal) *Mahâmaṇḍalêśvara Kâmadêva*:⁶—

'Śaka 1111 (in words, l. 74), the Saumya saṁvatsara; at the time of the sun's commencing his progress to the north.'

261.—*Ky. 4288*.⁷—*Jour. Bo. As. Soc.* Vol. IX. p. 241. Halsi plates of the 13th year of the reign of the Kâdamba (of Goa) Jayakêśin III.; (composed by Gaṅgâdharasûri, the son of Yajñêśvara⁸):—

(L. 66).—sâstâśiti-śatadvay-âdhikêśhu chaturshu sahasrêśhu Kaliyuga-saṁvatsarêśhu parâvrittêśhu śrî-Saptakôṭîśvara-labdha-varaprasâda-śrî-Kâdamba-Vîra-Jayakêśidêva-vijayarâjyê pravartamânê trayôdaśê Siddhârthi-saṁvatsarê Chaitra-śuddha-dvâdaśî-Guruvârê damanârôpaṇa-samanantaram.

[Siddhârthin = *Ś. 1121* = *Ky. 4300*]: Thursday, 11th March A.D. 1199; see *Ind. Ant.* Vol. XVII. p. 299, No. 19.

¹ See *Ind. Ant.* Vol. XII. p. 209, No. 19.

² See Dr. Fleet's *Dynasties*, p. 465. Têjugi (Têja) is described as 'a thunderbolt in breaking the mountain Simhanârâya, and a lion to the elephant—the brave Kaṇiṅgarâya.'

³ This person is different from the *Danḍanâdyaka Barma* (Bammanna, etc.) who was a son of Kâma (Kâvaṇa); see below, No. 284.

⁴ See above, No. 140.

⁵ See Dr. Fleet's *Dynasties*, p. 466, note 1, and p. 568.

⁶ A son of Tailama who was a son of Tailapa II. in No. 210.—See also below, Nos. 424 and 425.

⁷ This is not the year in which the grant was made, but the year from which the regnal years were counted.

⁸ See above, No. 249.

The mythical Jayanta or Trilôchana-Kadamba; in his lineage, Shashthadêva [I.]; his son Jayakêsin [I.]; his son Vijayâditya [I.]; his son Jayakêsin [II.], married Mailalanahâdêvi, the daughter of [the W. Châlukya] Permâdi (Vikramâditya VI.) and younger sister of Sôma (Sômésvara III.); their sons Śivachitta Permâdi and Vijayâditya [II.] (Vijayârka, Vâpi-bhûshana); the latter married Lakshmi who bore to him Jayakêsin [III.].

262.—**Ky. 4289***.¹—*Jour. Bo. As. Soc.* Vol. IX. p. 304; *Ind. Inscri.* No. 33. Kittûr Kanarese inscription of the 15th year of the reign of the Kâdamba (of Goa) Jayakêsin III., 'lord of Banavâsi,' recording a trial by ordeal.²—

(L. 3).—Kaliyuga-saṁvatsaram 4289neya saṁd=ad=âḍi(di)y-âgi . . .

(L. 12).—śrī-Vīra-Jayakêsi(śi)dêv-arasara varshaka(da) 15neya Du[*]mmati-saṁvatsarada Âshâḍa(ḍha)-śud[ḍh*]a aṣṭamī 8 Âdivârad=amdu.

(L. 25).—tat-saṁvatsarada Âshâḍa(ḍha)-bahuḷa 7 sapṭamī Âdivârad=adum.³

(L. 30).—â bahuḷa 8 Sôma-vâra de(di)vasa.

[Durmati = Ś. 1123 = **Ky. 4302**] : Sunday, 10th June; Sunday, 24th June; and Monday, 25th June A.D. 1201; see *Ind. Ant.* Vol. XVII. p. 297, No. 18.

263.—*PSOIL* No. 94; *Archæol. Surv. of West. India*, Vol. III. p. 103; *Jour. Bo. As. Soc.* Vol. X. p. 181. Koppûr much damaged Kanarese inscription of the Râṭṭa Mahâmaṇḍalêśvara Chakravartin Kattama (Kârtavīrya III. ?):⁴—

'The . . . year of his reign, the . . . saṁvatsara; Monday, the eleventh day of the bright fortnight of Pushya; at the time of the sun's commencing his progress to the north.'

264.—**Ś. 1124***.—Graham's *Kolhapoor*, p. 415, No. 9. Translation of a Râybag inscription⁵ of the Râṭṭa Mahâmaṇḍalêśvara Kârtavīrya IV., dated Śaka 1124, the Durmati saṁvatsara, Friday, the 15th of the bright half of Vaiśâkha.

Friday, 20th April A.D. 1201.

265.—**Ś. 1127***.—*Jour. Bo. As. Soc.* Vol. X. p. 220; *PSOIL* No. 95. Kalhoḷe Kanarese inscription of the Râṭṭa Mahâmaṇḍalêśvara Kârtavīrya IV., 'lord of Lattanûr,' ruling at Vêṇugrama, and of his younger brother, the Yuvarâja Mallikârijuna :—

(L. 54).—Śaka-varsham 1127neya Raktâkshi-saṁvatsarada Paushya(sha)-śuddha-bidigo Śanivârad=amdu-uttarâyana-saṁkramaṇadalli.

Saturday, 25th December A.D. 1204; see *Ind. Ant.* Vol. XXIII. p. 128, No. 90.

Sêna [II.]⁶ married Lakshmidêvi; their son Kattama (Kârtavīrya) [III.], married Padmaladêvi; their son Lakshmidêva (Lakshmapa) [I.], married Chandrike (Chandrikadêvi, Chandaladêvi); their sons Kârtavīrya [IV.] (who married Êchaladêvi) and Mallikârijuna.

266.—**Ś. 1131***.—*Ind. Ant.* Vol. XIX. p. 245. Bhôj plates of the Râṭṭa Mahâmaṇḍalêśvara Kârtavīrya IV., 'lord of Lattanûr,' ruling at Vêṇugrama, and of his younger brother, the Yuvarâja Mallikârijuna; (composed by Âdityadêva?):—

(L. 97).—Śakanripa-kâlasy=aikatpi(tri)ṁsaduttara-śatâdhika-saha-ratamasya Vibhava-saṁvatsarasya Kârtika-mâsasya śukla-dvâdaśyâm Budhavâra-samanvitâyâm.

Wednesday, 22nd October A.D. 1208; see *ibid.* Vol. XXIII. p. 128, No. 91.

In the Râṭṭa race, raised to eminence by Kṛishṇarâja,⁷ was Sêna [II.]; his son Kârtavīrya [III.]; his son Lakshmidêva (Lakshmidhara) [I.], married Chandrikadêvi; their sons Kârtavīrya [IV.] (who married Êchaladêvi) and Mallikârijuna.

¹ This, again, is the year from which the regnal years were counted; it is quoted here as a current year; see above, No. 261.

² See Dr. Fleet's *Dynasties*, p. 571.

³ See Dr. Fleet's *Dynasties*, p. 555.

⁴ See above, No. 201.

⁵ *See the Râshṭrakûṭa Kṛishṇarâja II.*

⁶ Read =amdu.

⁷ See *ibid.* p. 557.

⁸ For another Âdityadêva see below, Nos. 298 and 300.

267.—*Ś. 1141**.—*Jour. Bo. As. Soc.* Vol. X. p. 240. Nēsargi (Nēsargige) Kanarese inscription of the Raṭṭa *Mahāmaṇḍalēśvara Kārtavīrya IV.*, ruling at Vēṇupura (Vēṇugrāma):—

(L. 57).—Sa(śa)ka-varśa(rsha) 1141neya Bahudhānya-saṁvatsarada Māgha-suddha 7 Guruvārad-aṁd=uttarāyaṇasaṁkrānti-vyatīpāta kûḍida puṇya-tithiyal=.

Either the 25th December A.D. 1218 (but this was a Tuesday and the 7th of the bright half of Pausa) or Thursday, the 24th January A.D. 1219 (but this was the day of the Kumbha-saṁkrānti); see *Ind. Ant.* Vol. XXIV. p. 8, No. 156, and Vol. XXV. p. 293, note 64.

Genealogy from Sēna [II.] to Kārtavīrya [IV.] as in No. 266.

268.—*Ś. 1151**.—*Jour. Bo. As. Soc.* Vol. X. p. 260; *Archæol. Surv. of West. India*, Vol. II. p. 223, and Plate lxxiii.; and Vol. III. p. 110; *PSOCI.* No. 89. Saundatti Kanarese inscription of the time of the Raṭṭa *Mahāmaṇḍalēśvara Lakshmidēva II.*, 'lord of Lattantū,' ruling at Vēṇugrāma, the son of Kārtavīrya IV. and Mādēvī; recording grants made at the command of the *Rājaguru* Munichandra:—

(L. 64).—Śaka-varshaṁ 1151neya Sarvvadhāri-saṁvatsarada Āshāḍhad-amavāse Sōmavārad-aṁdina sarvvagrāsi-sūryyagrahaṇad-uttama-tithiyol.

Monday, 3rd July A.D. 1228; a total eclipse of the sun, visible in India; see *Ind. Ant.* Vol. XXIII. p. 130, No. 103.

269.—*Ky. 4348*.¹—*Ind. Ant.* Vol. XIV. p. 289. Goa (now Bombay As. Soc.'s) plates of the 5th year of the reign of the Kādamba (of Goa) Śivachitta Shashṭhadēva II. and of his brother-in-law Kāmadēva (Kāvaṇa); (composed by Chatyaṇārya, the son of Sōmanātha and grandson of Yajñavarya²):—

(L. 29).—aṣṭāchatvāriṁśadadhika-trisatō[tta*]rēshu chatuḥ-sahasrēshu Kaliyuga-saṁvatsarēshu parāvṛttēshu satsu | svarājy-ānubhava-kālē pañchamē Sādhāraṇa-saṁvatsarē [I ta]sy=Āśvayuja-śu[d*]dha-pratipadi Budhavārē Tulā-rāsim-upagatavati bhagavati bhāskarē vishuva-saṁkrāntau | mah[ā*]puṇya-kālē |

[Sādhāraṇa = *Ś. 1172* = *Ky. 4351*]: Wednesday, 28th September A.D. 1250; see *ibid.* Vol. XVII. p. 300, No. 20.

The mythical Jayanta in whose family were many kings. Among them was Gūhalla; then Shashṭha [I.]; his son Jayakēśin [I.]; his son Vijayārka [I.]; his son Jayakēśin [II.], married Mailalamahādēvī, the daughter of the [W.] Chālukya Permāḍi (Vikramāditya VI.); their sons Permāḍi and Vijaya [II.]; Vijaya's son Jayakēśin [III.], married Mahādēvī; their son Tribhuvanamalla, married Mānikādēvī; their son Shashṭha [II.].—His sister was married to the prince Kāmadēva (Kāvaṇa), the son of Lakshmidēva and Lakshmi.

270.—*Jour. Bo. As. Soc.* Vol. IX. p. 310. Dēgāṁve Kanarese Kādamba inscription (P).

271.—*Ś. 1182*.—*Jour. Roy. As. Soc.* Vol. V. p. 177; *Jour. Bo. As. Soc.* Vol. IV. p. 105. Terwaṇ plates of the reign of the Chālukya *Mahāmaṇḍalēśvara Kāṁvadēvarāya*, 'lord of Kalyāṇapura,' recording a grant by his minister Kēśava:—

(L. 1).—Śrī-Śaku 1182 varshē Raudra-saṁvatsarē | Pushya-vadi saptami(mi) Sa(śa)ni-dinē | . . . uttarāyaṇasaṁkrānti-parvaṇi.

Saturday, 25th December A.D. 1260;³ see *Ind. Ant.* Vol. XXIV. p. 1, No. 124.

¹ This is not the year in which the grant was made, but the year from which the regnal years were counted.

² Probably the *Yajñēśvara* of No. 249.

³ On this day the *tithi* of the date commenced 13 h. 19 m. (and the Uttarāyaṇa-saṁkrānti took place 16 h. 45 m.) after mean sunrise.

272.—*Ind. Ant.* Vol. XIV. p. 141, and Plates. British Museum (spurious) Sanskrit and Kanarese plates¹ of the Chālukya *Mahārājādhirāja Chakravartin Vira-Satyāśraya*, lord of, and residing at, Kalyānapura, the son of Gōvindarāja :—

(L. 20).—Bhāva-saṁvachharē Jyēṣṭha-māsē kṛishṇa-pakṣhē Sasivārē saptamyām tithau.

273.—*Ś. 366*.—*Ind. Ant.* Vol. VIII. p. 94, and specimen Plate. Bangalore Museum (spurious²) Sanskrit and Kanarese plates of the Chālukya *Mahārājādhirāja Chakravartin Vira-Nanamba*, lord of, and residing at, Kalyānapura :—

(L. 13).—Saka-varuṣa 366 Tāraṇa-saṁvachharē Phālguna-māsē kṛishṇa-pakṣhē Bihavāra amāvāsya-yām tithau.

For *Ś. 366* the date would regularly correspond to Thursday, 22nd February A.D. 445; but *Ś. 366* could be called Tāraṇa only by the southern luni-solar system, which was not in use at so early a period; see *ibid.* Vol. XXIV. p. 9, No. 163.

274.—*Jour. Bo. As. Soc.* Vol. II. p. 270; Graham's *Kolhapoor*, p. 479, No. 23. Translation of a Kolhāpur inscription³ of a Chālukya named Sōmadēva (Sōmēśvara).—In a Chālukya family which flourished at Saṁgamēśvara in the Koṅkaṇ was born king Karṇa (who lived at 'Vijaypat'); his son Vēṭugidēva; his son Sōmadēva; his younger brother (?) Sōmadēva (Sōmēśvara), whose queen was Māṇikyadēvī.

E.—The Kālachuryas.⁴

275.—*Ś. 1079*.—*PSOCI.* No. 219; *Mysore Inscr.* No. 102, p. 188. Tālgund Kanarese inscription of the Kālachurya *Mahāmaṇḍalēśvara Bhujabala-chakravartin Bijjana*,⁵ 'lord of Kālaṇjara,' and of his *Danḍanāyaka Kēśimayya (Kēśava)* :—

(L. 57).—Sa(śa)ka-varṣaṁ 1079ney-Īśvara-saṁvachcha(tsa)rada Puṣyada puṇṇami Sōmavāram=uttarāyāpasamkramana-vyatiṭṭad=amdu.

The date is irregular.

The inscription mentions the W. Chālukya kings as far as Taila III., but conveys no distinct information as to the exact relations then existing between Taila III. and Bijjana.⁶

276.—*PSOCI.* No. 182; *Mysore Inscr.* No. 90, p. 182. Baḷagāṁve Kanarese memorial tablet of the third (?) year of the reign of the Kālachurya *Bhujabala-chakravartin Bijjana* :—

'The second year⁷ (in figures, 1. 3) of his reign, the Bahudhānya saṁvatsara; Tuesday, the fourteenth day of the dark fortnight of Chaitra;' (*Mys. Inscr.* : 'the month Kārttika, the last day of the moon's decrease, new-moon day, Tuesday').

[For Bahudhānya = *Ś. 1080*] the date would be irregular, with either reading.

277.—*Ś. 1080*.—*PSOCI.* No. 183; *Mysore Inscr.* No. 74, p. 152. Baḷagāṁve Kanarese inscription. Date of the time of the Kālachurya *Mahārājādhirāja Bhujabala-chakravartin Bijjala Tribhuvanamalla*, 'lord of Kālaṇjara,' and of his *Danḍanāyaka Kēśimayya (Kēśava, Kēśirāja)* :—

(L. 62).—Śaka-varṣaṁ 1080neya Bahudhānya-saṁvachcha(tsa)rada Puṣya(shya)da puṇṇami Sōmavāram=uttarāyāpasamkrānti-vyatiṭṭa-sōmagrahaṇad=amdu.⁸

¹ According to Dr. Fleet referable to perhaps the 13th or 14th century A.D.—Compare also *Ind. Ant.* Vol. XXX. p. 389.

² See *Ind. Ant.* Vol. XXX. p. 221, No. 49; the grant apparently is a quite modern forgery.

³ See *ibid.* p. 207.

⁴ See also above, Nos. 226, 232, 238, 240 and 245.

⁵ Here and in other inscriptions Bijjana has the *biruda* Nīśāṅkamalla.

⁶ See Dr. Fleet's *Dynasties*, p. 473.

⁷ According to Dr. Fleet's *Dynasties*, p. 474, the third year, and probably the month Bhādrapada; (for *Ś. 1080* the 14th of the dark half of Bhādrapada would correspond to Tuesday, 23rd September A.D. 1158).

⁸ See *Ind. Ant.* Vol. XII. p. 212, No. 59.

Monday, 5th January A.D. 1159; but there was no lunar eclipse and no Saṅkrānti on this day.

The inscription mentions the W. Chālukya kings as far as Taila III., but conveys no distinct information as to the exact relations then existing between Taila III. and Bijjala.¹

(For another date in the same inscription, of the third year of the Kaḷachurya Saṅkama, see below, No. 292).

278.—*Ep. Ind.* Vol. V. p. 15. Managōli Kanarese inscription of the 6th year (of the reign) of the Kaḷachurya *Bhujabala-chakravartin* Bijjala:—

(L. 59).—Bijjaladēva-varshada 6neya Vish[u*]-sainvatsarada Bhādrapada-bahula 6 Maṅgaḷavāhad=amḍ[u].

(L. 64).—Kapila-chattī-vyatipāta-parvva-nimittav-āg[i].

[Vishu = Ś. 1083] : Tuesday, 12th September A.D. 1161, when the *nakshatra* was Rōhiṇī and the *yōga* Vyatipāta.²

(In lines 1-59 the inscription refers to events of the time of the W. Chālukya Jagadēka-malla II., and contains a date of the 5th year of that king's reign; see above, No. 232).

279.—*PSOCI.* No. 184; *Mysore Inscr.* No. 43, p. 92. Baḷagāṇve Kanarese inscription³ of the 6th year (of the reign) of the Kaḷachurya *Mahārājādhirāja Bhujabala-chakravartin* Bijjala Tribhuvanamalla, 'lord of Kālāñjara,' and of his *Danḍandya* Barmarasa; recording a grant which was made at the request of Bijjala's dependent *Kasapayya-nāyaka*.⁴—

(L. 46).—6neya Vishu-sainvatsarada Pushya-māsad-amāvāsye sūryya-grahanaḍ=amḍu.

[Vishu = Ś. 1083] : 17th January A.D. 1162, with a solar eclipse, visible in India.

280.—*Ep. Ind.* Vol. V. p. 24. Managōli Kanarese inscription of the 10th year (of the reign) of the Kaḷachurya *Mahārājādhirāja Bhujabala-chakravartin* Bijjala, 'lord of Kālāñjara,' reigning at his capital of Kalyāṇa, and of his *Danḍandya* Ammanayya:—

(L. 18).—Bijjaladēva-varshada 10neya Pārti(rthi)va-sainvatsarada Mārggaśirad=amāvāsye Ādityavāra sūryyagrahana-bya(vya)tipāta-nimittadin.

[Pārthiva = Ś. 1087] : Sunday, 5th December A.D. 1165; but there was no solar eclipse on this day; see *ibid.* p. 24.

281.—*PSOCI.* No. 121; *Mysore Inscr.* No. 33, p. 64. Harihar incomplete Kanarese inscription⁵ of the Kaḷachurya *Mahārājādhirāja Bhujabala-chakravartin* Bijjala Tribhuvanamalla, and of his *Danḍandya* Barmarasa, the son of Muñjaladēva and nephew of Kasapayya-nāyaka, of the lineage of Sagara.

282.—*PSOCI.* No. 186; *Mysore Inscr.* No. 83, p. 169. Baḷagāṇve Kanarese memorial tablet of the time of the Kaḷachurya *Bhujabala-chakravartin* Bijjala, and of his *Danḍandya* Padmarasa.

283.—*PSOCI.* No. 187; *Mysore Inscr.* No. 91, p. 182. Baḷagāṇve Kanarese memorial tablet of the time of the Kaḷachurya *Bhujabala-chakravartin* Bijjala.

284.—*PSOCI.* No. 223; *Mysore Inscr.* No. 110, p. 206. Sorab Kanarese memorial tablet of the time of the Kaḷachurya (?) Bijjala; (according to *Mys. Inscr.* apparently of the time of a W. Chālukya king).

285.—*PSOCI.* No. 185; *Mysore Inscr.* No. 48, p. 109. Baḷagāṇve Kanarese inscription of the 16th Kaḷachurya year,⁷ recording the transference of the government by the Kaḷachurya

¹ See Dr. Fleet's *Dynasties*, p. 473.

² See *Ind. Ant.* Vol. XXVI. p. 183, Bhādrapada-kṛishnapakṣa VI.

³ The inscription, besides other literary works, mentions the *Kaumdra*, *Pāṇintya* and *Śikāṭāgana* grammars.

⁴ See Dr. Fleet's *Dynasties*, p. 475.

⁵ See Nos. 245 and 281.

⁶ For an account of the descent of Bijjala (Bijjala), taken from this inscription, see Dr. Fleet's *Dynasties*, p. 468.

⁷ See Dr. Fleet's *Dynasties*, p. 476, note 4.

Bhujabala-chakravartin Bijjaṇa Tribhuvanamalla to his son Sôma (Sôvidêva),¹ and grants made with the latter's permission by the *Daṇḍanūyaka* Bolikeya-Kêsimayya (Kêśava) :—

(L. 37).—śrīmat-Kaḷachuryya-varshada 16neya Sarvadhâri-saṁvatsarada Vaisākha-paurṇ[imā?] Âdityavâra sômagrahaṇa-saṁkramaṇa-vyatîpâtad=amdu.

[For Sarvadhârin = Ś. 1090] the date is irregular.

286.—*PSOCI*. No. 188; *Mysore Inscr.* No. 86, p. 174. Baḷagâṁve Kanarese memorial tablet of the 6th (?) year (of the reign) of the Kaḷachurya *Bhujabala-chakravartin* Sôvidêva :—

(L. 2).—Sôvidêva-varshada [6]neya² Khara-saṁvatsarada Śrāvapa-bahulaḍ=amavâsye Sôma-vârad=amdu.

[Khara = Ś. 1093] : Monday, 2nd August A.D. 1171.³

287.—*PSOCI*. No. 101. Narsâpûr Kanarese inscription of the 7th year (of the reign) of the Kaḷachurya *Bhujabala-chakravartin* Sôvidêva :—

(L. 84).—Sôvidêva-varshada 7neya Vijaya-saṁvatsarada Pushya-su(śu)dha(1dha) 13 Sôma-vârad=amdu.

[For Vijaya = Ś. 1095] the date is irregular.⁴

288.—Ś. 1096.—*Jour. Bo. As. Soc.* Vol. XVIII. p. 273, and Plates. Kokatnûr (Belgaum district) plates of the Kalachuri *Mahârâjâbhîrâja* Sôma (Sômêśvara, Sôvidêva), recording a grant which was made with his permission by his queen Sâvaladêvi; (composed by Âdityadêva,⁵ the disciple of Śrîpâda) :—

(L. 71).—Shannavatyadhika-sahasratamê Śakê Jaya-saṁvatsarê Kârttika-śukla-dvâdaśyâṁ Bṛhaspativâra-Rêvatīnakshatra-Vyatîpâtayôga-Va(ba)vakarapa-yuktâyâṁ.

Thursday, 7th November A.D. 1174; but the day fell in the month Mârgaśirsha, not Kârttika; see *Ind. Ant.* Vol. XXIV. p. 5, No. 145.

In the Kalachuri Kshatriya lineage, king Kṛishṇa; his son Jôgama; his son Paramardî; his son Bijjaṇa; his son Sôma.

289.—Ś. 1096.—*Ind. Ant.* Vol. XVIII. p. 127. Dates in a Hulgûr Kanarese inscription of the Kaḷachurya (Kaḷachurya) Sômêśvara (Sôvidêva) :—

(L. 18).—Śaka-varsha 1096neya Jaya-saṁvatsarada Jyêshṭhâda amavâsye Âdityavâra sūryyagrahaṇa-vyatîpâtad=amdu.

1st June A.D. 1174, with a solar eclipse, visible in India; but the day was a Saturday, not a Sunday; see *ibid.* Vol. XXIV. p. 8, No. 155.

(L. 35).—Śaka-varshada 1096neya Jaya-saṁvatsarada Mârgaśirâda punṇami Âdityavâra sôma-grahaṇad=amdu.

Sunday, 10th November A.D. 1174; a lunar eclipse, visible in India; see *ibid.* Vol. XXIII. p. 117, No. 25.

(L. 40).—Śaka-varshada 1096neya Jaya-saṁvatsarada Mârgaśirâ-bahulaḍ=amavâsye Maṅgalavâra sūrya-grahaṇad=amdu.

Tuesday, 26th November A.D. 1174; a solar eclipse, visible in India; see *ibid.* Vol. XXIII. p. 124, No. 69.

¹ Here and elsewhere he has the *biruda* Râya-Murâri.

² *Mys. Inscr.* : 'the 5th year.'

³ But on this day the *tithi* of the date only commenced 10 h. 21 m. after mean sunrise.

⁴ In line 89 the inscription contains another date of Ś. 1194 (by-mistake for 1094), the year Nandana; that date also is irregular.

⁵ See No. 300, and compare No. 266.

⁶ Compare above, No. 226, where the name (in Kanarese) is Permâḍi.

290.—*PSOCI.* No. 220; *Mysore Inscr.* No. 100, p. 187. Tālgund Kanarese memorial tablet of the reign of the Kaḷachurya *Chakravartin* **Sōvidēva** :—

(L. 1).—Sōvidēva-varushada Virōdhikri(kri)tu-samvatsarada Âsvija-balhula Snê Âdivanad=am[du?].

Virōdhikrit may be a mistake for *Virōdhi*; but the date is irregular for Virōdhi = Ś. 1091 (as well as for Virōdhakrit = Ś. 1113).

291.—*Ep. Ind.* Vol. V. p. 26. Managōli Kanarese inscription of the third year (of the reign) of the Kaḷachurya *Mahārājādhirāja Bhujabala-chakravartin* **San̄kama**, 'lord of Kālañjara,' and of the *Danḍandya* **Kēsimayya (Kēśava)** and his nephew **Brahmadēva** :—

(L. 24).—San̄kamadēva-varsha(rsha)da mūṇaneya Viḷa[ṇbi-saṇ]vatsarad=Âśâ(shâ)-ḍa(ḍha)-su(su)dhḍha(ddha) 11 Âdityavāra dakṣiṇāyanasam̄kramapa-parvva-nimittah.

[For **Vilamba** = Ś. 1100] probably the 27th June A.D. 1178, but this was a Tuesday, not a Sunday; see *ibid.* p. 26.

292.—*PSOCI.* No. 183; *Mysore Inscr.* No. 74, p. 161. Baḷagāṇve Kanarese inscription. Date of the third year (of the reign) of the Kaḷachurya *Chakravartin* **San̄kama Niśśan̄kamalla**, and of his *Danḍandya* **Kēśirājayya**, and the Guṭta *Mahāmaṇḍalēśvara* **Sampakarasa** :—

(L. 81).—San̄kamadēva-varshada Śneya Vikāri-samvatsarada Chaitrada. puṇṇame Sōmavāra viśhusam̄krānti-vyatipāta-sōmagrahaṇad=am̄du.

[For **Vikārin** = Ś. 1101] the date is irregular, but the intended day may be Sunday, the 25th March A.D. 1179.³

(For another date in the same inscription, of the time of the Kaḷachurya **Bijjala**, see above, No. 277).

293.—*Ind. Ant.* Vol. V. p. 46; *PSOCI.* No. 189; *Mysore Inscr.* No. 89, p. 75. Baḷagāṇve Kanarese inscription. Date of the 5th year (of the reign) of the Kaḷachurya **San̄kama**,³ the younger brother of Sōma (Sōvidēva) who was the son of **Bijjala Tribhuvanamalla**, 'lord of Kālañjara:'—

(L. 28).—San̄kamadēva-varshada Śneya Vikāri-samvatsarada Vaiśākhamaśad=amāvāsye Sōmavāra Viśhasam̄kramapa-vyatipāta=am̄du.

[For **Vikārin** = Ś. 1101] this date is irregular.

The inscription also records grants made on the same date by the *Mahāmaṇḍalēśvara* **Tailahadēva (Tailapa)** and **Eṇaha**;⁴ and it also records a grant made in Ś. 1108, the *Parābhava samvatsara*.

294.—*PSOCI.* No. 122; *Mysore Inscr.* No. 31, p. 60. Harihar much defaced Kanarese inscription of the Kaḷachurya **San̄kama**, and his *Danḍandya* **Kāvaṇa (Kāvaṇayya)**, a son of the *Danḍandya* **Barmadēva**⁵ and his wife **Jakkapaṇve**.

295.—*PSOCI.* No. 190; *Mysore Inscr.* No. 95, p. 184. Baḷagāṇve Kanarese memorial tablet of the time of the Kaḷachurya *Chakravartin* **Âhavamalla** :—

'The Śārvari *samvatsara*;⁶ Sunday, the first day of the bright fortnight of Kārttika,' (*Mys. Inscr.* : 'of the moon's decrease').

[For **Śārvari** = Ś. 1102] the date is irregular.

³ See Dr. Fleet's *Dynasties*, pp. 487 and 581.

⁴ This was the day of the Mēsha-(vishuva-)sam̄krānti, and the full-moon *tithi* of Chaitra ended on the preceding Saturday, but there was no lunar eclipse.

⁵ The inscription mentions as the leader of his whole army the *Danḍandya* **Kāvaṇayya**.

⁶ Also mentioned in No. 297; see *Mys. Inscr.* p. 117.

⁷ See Dr. Fleet's *Dynasties*, p. 464, note 6.—Kāvaṇa (Kāma) himself had a son, again named **Brahma** (**Bamma**, **Bammaṇa**, **Bammayya**, **Bammaraṇa**, **Bammidēva**) and mentioned below, in No. 419.

⁸ See Dr. Fleet's *Dynasties*, p. 458, note 3.

296.—*PSOCI.* No. 191; *Mysore Inscr.* No. 67, p. 138. Baḷagāṁve Kanarese memorial tablet of the reign of the Kaḷachurya *Chakravartin* **Āhavamalla**, and of his *Daṇḍandya* **Kēśimayya** :—

(L. 1).—Āhavamalladēva-varshada Sā(śā)rvvari-saṁvatsarada Phālguna(na)d-amāvāse Sômaṇṇad=amdu.

[Śārvari = Ś. 1102]: Monday, 16th March A.D. 1181.¹

297.—*PSOCI.* No. 192; *Mysore Inscr.* No. 55, p. 115. Baḷagāṁve Kanarese inscription of the third year (of the reign) of the Kaḷachurya *Bhujabala-chakravartin* **Āhavamalla**, and of his *Daṇḍandya* **Kēśimayya** (**Kṛishṇa-Kēśava**) :²—

(L. 69).—Āhavamalladēva-varshada 3neya Plava-saṁvatsarada Śrāvaṇa-bahula 12 (or 13 P) [Ādi?]vāra³ saṁkramaṇa-vyatīpātad=amdu.

[Plava = Ś. 1103]: Sunday, 9th August A.D. 1181; the 12th *tilhi* ended and the 13th commenced 9 m. after mean sunrise; but there was no Saṁkrānti on this day.

298.—Ś. 1103 and Ś. 1110*.—*PSOCI.* No. 230. Haraḷahalli⁴ Kanarese inscription of the reign of the Kaḷachurya **Āhavamalla**, and of his feudatory, the Gutta *Mahāmaṇḍalēśvara* **Jōyidēva** (**Jōma**) I., the son of **Vīra-Vikramāditya** I. who was the son of **Mallidēva**.⁵—

‘Śaka 1103 (in words, l. 83), the Plava *saṁvatsara*; at the time of the sun’s commencing his progress to the north.’

The inscription, besides, contains the following date,⁶ connected with the Gutta *Mahāmaṇḍalēśvara* **Vīra-Vikramāditya** II., the son of Gutta II. who was the brother of **Jōyidēva** I. :—

‘Śaka 1110 (in figures, l. 103), the Plavaṅga *saṁvatsara*; Thursday, the thirteenth day of the bright fortnight of Phālguna.’

This date is irregular.

299.—*PSOCI.* No. 193; *Mysore Inscr.* No. 94, p. 184. Baḷagāṁve Kanarese memorial tablet of the 8th year of the reign of the Kaḷachurya **Āhavamalla** :—

‘The eighth year (in figures, l. 3) of his reign, the Śōbhakṛit *saṁvatsara*; Monday, the fifth day of the (?) bright fortnight of Phālguna;’ (*Mys. Inscr.* ‘the month Bhādrapada, the 13th day of the moon’s decrease’).⁷

[For Śōbhakṛit = Ś. 1105] the date is irregular, with either reading.

300.—Ś. 1105.—*Ind. Ant.* Vol. IV. p. 275. Bēhaṭṭi plates of the Kaḷachuri *Mahārājādhirāja* **Siṅghana**;⁸ (composed by Ādityadēva,⁹ the disciple of Śrīpāda) :—

(L. 59).—Sa(śa)kanṇipakāl-ātītē cha pañchōttara-satādhika-sahasratagē(mē) Śakē Śōbhakṛit-saṁvatsarē Āsva(śva)yukt-āmāṇṣyām Sômaṇṇē Vyatīpāta-yōgē.

The date is irregular; see *ibid.* Vol. XXIV. p. 15, No. 189.

Genealogy as far as Sôma as in No. 288; his younger brother Saṅkama; his brother **Āhavamalla**; his younger brother **Siṅghana**.

¹ On this day the *tilhi* of the date commenced 1 h. 34 m. after mean sunrise.

² See Dr. Fleet’s *Dynasties*, p. 489.

³ Dr. Fleet and Mr. Rice both have ‘Sunday.’

⁴ See *ibid.* p. 581, note 4.

⁵ Compare above, No. 223.

⁶ The same date occurs in another Haraḷahalli Kanarese inscription of the Gutta **Vīra-Vikramāditya** II., *PSOCI.* No. 231.—Compare also below, No. 335.

⁷ See Dr. Fleet’s *Dynasties*, p. 489, note 3.

⁸ A postscript in Kanarese records a minor grant by the *Daṇḍandya* **Divākara**.

⁹ See above, No. 288.

F.—The Silāras, Śilāras, Śilāhāras.¹

301.—Ś. 930.—*Ep. Ind.* Vol. III, p. 297, and Plate. Khārēpāṭa plates² of the Silāra Maṇḍalika Raṭṭarāja, a feudatory of the W. Chālukya Mahārājādhirāja (Iṭivabeḍaṅga) Satyāśraya:—

(L. 40).—Śakanipakāl-ātita-samvatsara-nava-satēshu trimśad-adhikēshu pravarttamāna-Kilaka-samvatsar-āntargata-Jyēsthā-paurṇamāsyān.

In the race of the Rāshtrakūṭa lords there was Dantidurga; his father's brother Krishnarāja [I.]; his son Gōvindarāja [II.]; [his younger brother] Nirupama [Dhruvarāja]; his son Jagattuṅga [I.] [Gōvindarāja III.]; his son Amōghavarsha [I.]; his son Akālavarsha [Krishnarāja II.]; his grandson Indrarāja [III.]; his son Amōghavarsha [II.]; his younger brother Gōvindarāja [IV.]; his father's brother (the son of Jagattuṅga [II. who did not reign]) Vaddiga; his son Krishnarāja [III.]; his brother Khōṭika (Khottiga); his brother's son Kakkala (Kakkarāja II.), was defeated by the [W.] Chālukya Tailapa (Taila II.), whose son Satyāśraya is represented as ruling over Raṭṭapāṭi.

Genealogy of Raṭṭarāja:—From the regent of the Vidyādhara, Jīmūtakēṭa's son Jīmūtavāhana, sprang the Silāra family. To that family belonged: [Sa]paphulla, a favourite of [the Rāshtrakūṭa] Krishnarāja [I.]; his son Dhammiyara (founded Valipattana); his son Aiyaparāja; his son Avasara [I.]; his son Ādityavarman; his son Avasara [II.]; his son Indrarāja; his son Bhīma; his son Avasara [III.]; his son, the king (rājā) Raṭṭa (Raṭṭarāja).

The inscription mentions the Mattamayūra line of ascetics; see *North. Inscr.* No. 405.

302.—Ś. 765(P).—Kāp̄heri inscription of the [Śilāra] Mahāsāmanta Pullaśakti,³ the successor of Kapardin I., 'the lord of Koṅkapa'; see above, No. 72.

303.—Ś. 775 (for 773).—Kāp̄heri inscription of the [Śilāra] Mahāsāmanta Kapardin II., the successor of Pullaśakti, 'lord of the whole Koṅkapa'; see above, No. 73.

304.—Ś. 799.—Kāp̄heri inscription of the [Śilāra] Mahāsāmanta Kapardin II., 'the lord of Koṅkapa'; see above, No. 80.

305.—Ś. 919.—*Ep. Ind.* Vol. III, p. 271, and Plates. Bhādāna⁴ plates of the Śilāra Mahāmaṇḍalēśvara Aparājitaḍvārāja, 'lord of Tagara,'⁵ issued (after the downfall of the Raṭṭa, i.e. Rāshtrakūṭa, rule) from Sthānaka:—

(L. 53).—Sa(śa)kanipakāl-ātita-samvatsara-sa(śa)tēshu navasu(sv=) ākōnavimśaty-uttarēshu pravarttamāna-Hēmalanva(mba)-samvatsar-ānta⁶ Āshāḍha-va(ba)hula-chatusyām(rthyām=) anka(nka)tō=pi samvat 919 Āshāḍha-vadi 4 . . . samjāta-dakṣiṇāyana-Karkkṭa-sa[m]krānti-parvvaṇi.

The date is not quite regular; the day intended may be the 25th or the 26th June A.D. 997; see *ibid.* p. 270.

The inscription first gives the following list of the Raṭṭa (Rāshtrakūṭa) kings:—1, Gōvindarāja [I.]; 2, Karkarāja [I.]; 3, Indrarāja [II.]; 4, his son Dantivarman [II.]; 5, Karkarāja's son Krishnarāja [I.]; 6, Gōvindarāja [II.]; 7, his younger brother Dhruva; 8, his son Jagattuṅga [I.] [Gōvindarāja III.]; 9, Durlabha Amōghavarsha [I.]; 10, his son Krishnarāja [II.]; 11, Jagattuṅga's⁷ son Indradēva [III.] Nityamvarsha; 12, his son Amōghavarsha [II.] (reigned

¹ Compare above, No. 94, note, and 220, note.

² The plates are numbered with numeral figures.

³ Below, in No. 305 ff., the name is spelt *Pulafakti*.

⁴ This is the name of the village granted. The plates were found in the Bhiwadi taluka of the Thāpā district and belong to Colonel A. F. Dobbs.

⁵ See Dr. Fleet in *Jour. Roy. As. Soc.* 1901, p. 597.

⁶ Read *samvatsar-āntargat-Āshāḍha*.

⁷ This Jagattuṅga [II.] was a son of Krishnarāja II.; he did not reign.

for one year); 13, his younger brother Govindarāja [IV.] Suvarnavarsha; 14, his paternal uncle Vaddiga, the younger brother of Nityavarsha; 15, Krishnarāja [III.]; 16, Khotṭiga; 17, Nirupama's son Kakkala (Kakkarāja II.), who was overthrown by [the W. Chālukya] Tailappa (Taila II.).

Then the genealogy of Aparājita himself is given thus:—The mythical beings Jīmūtakētu and his son Jīmūtavāhana, 'the ornament of the Śīlāra family;' in his family, Kapardin [I.]; Pulaśakti; his son Kapardin [II.]; Va[ppu]vanna; his son Jhañjha; his brother Goggirāja; his son Vajjaḍa [I.]; his son Aparājita, surnamed Mrigāṅka.

306.—**Ś. 939.**—*As. Res.* Vol. I. p. 357. Translation and lithograph of part of the text of the Thāpā plates of the Śīlāra Mahāmaṇḍalēśvara Arikēśarin, 'lord of Tagara':—

'On the fifteenth of the bright moon of Cārtica, in the middle of the year Piṅgala, when nine hundred and forty years, save one, are reckoned as past from the time of King Śaca, or, in figures, the year 939, of the bright moon of Cārtica 15 . . . the moon being then full and eclipsed.'

6th November A.D. 1017; a lunar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 115, No. 11.

Genealogy as far as Aparājita as in No. 305; his son Vajjaḍa [II.]; his brother Arikēśarin.

307.—**Ś. 948.**—*Ind. Ant.* Vol. V. p. 277. Bhāṇḍūp plates of the Śīlāra (or Śīlāhāra) Mahāmaṇḍalēśvara Chhittarājādēva, 'lord of Tagara,' ruler of the whole Koṅkaṇa country:—

(L. 32).—Sa(sa)kanripakāl-ātita-samvatsara-sa(sa)tēshu navasu(sv=) aṣṭachiatvāriṃśad-adhikēshu Kshaya-samvatsar-āntarggata-Kārttika-su(su)ddha-paṃchadasyāṃ(śyām) yatṛ=āṅkatō=pi samvat 948 Kārttika-su(su)ddha 15 Ravau samjātō(ta) ādityagrahapa-parvvaṇi.

The date is irregular; see *ibid.* Vol. XXIV. p. 13, No. 179.

Jīmūtakētu's son Jīmūtavāhana; in his lineage, the Śīlāra Kapardin [I.]; his son Pulaśakti; his son Kapardin [II.] (Laghu-Kapardin); his son Ghayuvanta (? Vappuvanna); his son Jhañjha; his brother Goggi; his son Vajjaḍa [I.]; his son Aparājita; his son Vajjaḍa [II.]; his elder (?) brother Kēśidēva (? i.e. Arikēśarin); his nephew, Vajjaḍa's son Chhittarāja.

308.—**Ś. 982 (?)**.—*Jour. Bo. As. Soc.* Vol. IX. p. 219 and Plate; and Vol. XII. p. 329 and Plate. Kalyāṇ Ambarnāth temple inscription of the Śīlāra Mahāmaṇḍalēśvara Māmvaṇi-rājādēva, recording the construction of a temple of the god (?) of the Mahāmaṇḍalēśvara Chhittarājādēva:—

(L. 1).—Śaka-samvat 982 Śrā[vaṇa?]-śuddha 9 Su(su)krē.¹

The date is irregular for Ś. 982 current and expired.

309.—**Ś. 1016.**—*Ind. Ant.* Vol. IX. p. 33, and Plates. Khārēpāṭa plates of the Śīlāra Mahāmaṇḍalēśvarādhipati Anantapāla (Anantadēva), 'lord of Tagara,' ruler of the whole Koṅkaṇa country:—

(L. 73).—Sa(sa)kanripakāl-ātita-samvatsara-daśa-sa(sa)tēshu shōḍas(ś)-ādhikēshu Bhāva-samvatsar-āntarggata-Māgha-su(su)ddha-pratipadāyāṃ yatṛ=āṅkatō=pi samvat 1016.

Jīmūtakētu's son Jīmūtavāhana; in his lineage, the Śīlāra Kapardin [I.]; his son Pulaśakti; his son Kapardin [II.] (Laghu-Kapardin); his son Va[ppu]vanna; his son Jhañjha; his brother

¹ So the date is given in *Jour. Bo. As. Soc.* Vol. XII. p. 329. *Ibid.* Vol. IX. p. 219, the reading is 'Śaka-samvat 782 Jēṭha-sudha 9 Sukrē,' for which compare *Ind. Ant.* Vol. XVIII. p. 94, and Vol. XXIII. p. 113, No. 4. But a photograph of the date, taken by Mr. Cousens and given to me by Dr. Fleet, shows that the first figure of the year of the date is undoubtedly '9.' The second figure of the year, the name of the month, and the number of the *tiṭhi* seem to me doubtful.—Compare also Dr. Fleet's *Dynasties*, p. 543.

² In lines 80 and 84 of the grant he is called *Koṅkaṇa-chakravartin*.

Goggi; his son Vajjaḍa [I.]; his son Aparājita¹ (contemporary of Gōma, Aiyapadēva, and of the kings Bhīllama and²); his son Vajjaḍa [II.]; his brother Arikēsarin; his nephew, Vajjaḍa's son Chhittarāja; his younger brother Nāgārjuna; his younger brother Mummupi; Nāgārjuna's son Anantapāla.

310.—Ś. 1076.—From an impression supplied by Dr. Burgess. British Museum inscription the reign (?) of [the Śīlāra] Haripālādēva:³—

(L. 1).—Śaku 1076 Bhāva-samvatsarē Māgha-su(śu)ddha-paurṇamāsyām parvvi . . .

(L. 4).—śrī-Haripālādēvu.

311.—Ś. 1078.—From impressions supplied by Dr. Fleet. Chiplūn (now Bombay As. Soc.'s) fragmentary inscription of the [Śīlāra] Mahāmaṇḍalīśvarādhipati Mallikārjuna:⁴—

(L. 3. of one fragment).—Śakanripakāl-ātīta-samvatsara-satēshu daśa[sv-a]shtasaptaty-adhikēshu Śaka-samvatu || 1078(?) | Dhātā(tri)-samvatsarē Vaiśākha-[śuddha]-akṣa[ra*]trītiyāyām yugādi-parvvi Bhauma-dinē Mṛgaśīra-nakṣatrē.

Tuesday, 24th April A.D. 1156; see *Ind. Ant.* Vol. XXIII. p. 116, No. 22.

312.—Ś. 1107.—From impressions supplied by Dr. Fleet. Bombay As. Soc.'s inscription of the reign of [the Śīlāra] Aparāditya:—

(L. 1).—[Śaka-?]samvatu 1107 Viśvā(śvā)vasu-samvachohha(ṭsa)rē Chaitra-śuddha 15 Ravau dinē.⁵

Sunday, 17th March A.D. 1185.

313.—Ś. 1109*.—*Jour. Bo. As. Soc.* Vol. XII. p. 333, and Plate. Parel (now Bombay As. Soc.'s) inscription⁶ of the [Śīlāra] Mahārājādhirāja Koṅkaṇa-chakravartin Aparāditya:—

(L. 1).—Śaka-samvatu 1109 Parābhava-samvatsarē || Māghē māsi ||

(L. 8).—samjāta-Māghī-parvvi.

314.—Ś. 1181.—From impressions supplied by Dr. Fleet. Bombay As. Soc.'s inscription⁷ of the reign of the Śīlāhāra Mahāsāmantādhipati Koṅkaṇa-chakravartin Sōmēśvara,⁸ 'lord of Tagara.'

The year of the date is Ś. 1181 (in words and figures), the Siddhārthin samvatsara, but I am unable to give the date in full.

315.—Ś. 980.—*Jour. Roy. As. Soc.* Vol. IV. p. 251; *Cave-Temples of West India*, p. 102, and Plates. Miraj plates⁹ of the Śīlāhāra Mahāmaṇḍalīśvara Mārasimha, 'lord of Tagara,' issued from Khilgiladurga (Kilgiladurga):—

(L. 44).—Sa(śa)kanripakāl-ātīta-samvatsara-satēshu | aśī(śī)tyadhika-n a v a s a t ē s h v = amhēshu | pravartatayiti¹⁰ Viṣambī-samvatsarē | Pausa-māsasya śuddha-pakṣhē | saptamāyām Bṛhaspativārē | udagayana-parvvi |

¹ He is surnamed Birudānka-Rāma; compare Birudānka-Bhīma in No. 568.

² The original has *Bhīllamāmmamamēva-kṣitibhīrām*.

³ I believe this to be the king of whom three inscriptions (of Ś. 1071, 1072 and 1075) are mentioned in the *Bombay Gazetteer*, Vol. XIII. Part II. p. 426.—This inscription contains only 9 short lines and is for the most part written in a kind of old Marāṭhī. It contains the usual curse of the ass and the woman, but no sculpture.

⁴ The Bombay As. Soc. has another inscription (from Bassein) of Mallikārjuna, the date of which I cannot make out with confidence. In it Mallikārjuna is described as *Mahāsāmantādhipati, Tagarapura-paramēvara* and *Si(śi)lāhāra-narēndra*. The inscription contains a sculpture of an ass and a woman.

⁵ The date is given wrongly in *Ind. Ant.* Vol. IX. p. 40, note 62.

⁶ Lines 22-24 are "in the local dialect of the Koṅkaṇa language of the period. Below the inscription is a rude sculpture of an ass and a woman."

⁷ The inscription contains a sculpture of an ass and a woman.

⁸ See Dr. Bhandarkar's *Early History of the Deccan*, p. 115.

⁹ These plates belonged to Mr. Wathen; they are now lost.

¹⁰ For *pravartamānē*.

Thursday, 24th December A.D. 1058; see *Ind. Ant.* Vol. XXIII. p. 115, No. 14.

Jatiga [II.], the ornament of the Śīyāḥāra (Śīlāhāra) family, born in the lineage of Jīmūta-vāha (Jīmūtavāhana); his son Goṅka; his younger brother Gūhala [I.]: Goṅka's son Mārasimha.

316.—*Ind. Ant.* Vol. XII. p. 102. Honnūr Kanarese inscription of the [Śīlāhāra] *Mahāmaṇḍalēśvara* Ballāla and Gaṇḍarāditya.

317.—Ś. 1032*[and 1033*].—*Jour. Do. As. Soc.* Vol. XIII. p. 2, and Plates. Tālaṇḍ plates of the Śīlāhāra *Mahāmaṇḍalēśvara* Gaṇḍarāditya, 'lord of Tagara,' issued from Thuvāḍa:—

(L. 26).—Śakanripakāl-ātīta-dvātrīṃśaduttara-sahasrē Virōdhi-saṃvatsarē Māgha-suddha-daśamyām Maṅgalavārē.

(L. 31).—tatsaṃvatsar-ōparitana-Vikṛita-saṃvatsara-Vaiśākha-paurṇamāsyām sōmagrahaṇa-parvāṇi.

Tuesday, 1st February A.D. 1110; and [Thursday], 5th May A.D. 1110,¹ with a lunar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 127, No. 83.

In the Śīlāhāra family, Jatiga [I.]; his son Nāyivarman; his son Chandrarāja; his son Jatiga [II.]; his son Goṅka; his brother Gūhala [I.]; his brother Kirtirāja; Goṅka's son Mārasimha; his son Gūhala [II.]; his brother Bhōjadēva [I.]; his brother Ballāla; his brother Gaṇḍarāditya.

318.—Ś. 1040.—Graham's *Kolhapoor*, p. 349, No. 2. Herley Kanarese inscription of the Śīlāhāra Gaṇḍarāditya, ruling at Vaḷavāḍa; dated Śaka 1040, the Vilamba saṃvatsara, on the occasion of an eclipse of the moon.

The eclipse probably is the one of Wednesday, 5th June A.D. 1118, the only lunar eclipse of Ś. 1040 that was visible in India.

319.—Ś. 1058*.—Graham's *Kolhapoor*, p. 357, No. 3; *Jour. Do. As. Soc.* Vol. II. p. 26f. No. VI. Kōlhāpur Kanarese inscription of the Śīlāhāra Gaṇḍarāditya, 'lord of Tagara,' and of his subordinate, the *Mahāsāmanta* Nimbādēvarasa,² dated (in words) Śaka 1058 the Rākshasa saṃvatsara, Monday, the fifth of the dark half of Kārtika.

Monday, 28th October A.D. 1135.³

320.—Graham's *Kolhapoor*, p. 465, No. 20. Kōlhāpur Sanskrit and Kanarese inscription of Gaṇḍarāditya.

321.—Ś. 1065*.—*Ep. Ind.* Vol. III. p. 209; *Ind. Inscr.* No. 45. Kōlhāpur inscription* of the Śīlāhāra *Mahāmaṇḍalēśvara* Vijayāditya, 'lord of Tagara,' residing at Vaḷavāḍa:—

(L. 16).—Śaka-varshēshu pañchashashṭyuttara-sahasra-pramitēshv-ātītēshu pravarttanāna-Duṃdubhi-saṃvatsara-Māgha-māsa-paurṇamāsyām Sōmavārē | sōmagrahaṇa-parvanimittam.

Monday, 1st February A.D. 1143; a lunar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 127, No. 86.

In the Śīlāhāra Kshatriya lineage, Jatiga [II.]; his four sons Goṅkala, Gūhala [I.], Kirtirāja and Chandraditya; Goṅkala's son Mārasimha; his five sons Gūhala [II.], Gaṅgadēva, Ballāla

¹ This appears to be the date of the inscription of Gaṇḍarāditya, mentioned in Graham's *Kolhapoor*, p. 342, No. 1.

² He is mentioned also in the two Kōlhāpur Kanarese inscriptions in Graham's *Kolhapoor*, p. 465, No. 19. and p. 466, No. 21.—Compare also above, No. 220, and below, No. 413.

³ On this day the *tithi* of the date commenced 1 h. 25 m. after mean sunrise.

⁴ The inscription ends with a Kanarese verse.

Bhōjadēva [I.], and Gaṇḍarāditya; Gaṇḍarāditya's son Vijayāditya.—The inscription also mentions a *Sāmanta* Kāmadēva.¹

322.—Ś. 1065* and 1066*.—*PSOCI*. No. 96. Miraj Kanarese inscription of the Śilāhāra *Mahāmaṇḍalēśvara* Vijayāditya, and his minister Mādirayya :—

(L. 19).—[Śaka]-varsha 1065neya Dumdubhi-saṁvatsarada Bhādrapada-su(śu)dhadha(ddha) 2 (*altered to 6*) Śukravārādaya.²

(L. 47).—Sa(śa)ka-varshaṁ 1066neya Rudhirōdgāri-saṁvatsarada Māgha-bahula 14 Vaḍḍavārādaya Śivarātreyā parvva-nimittav-āgi.

The first date corresponds to Friday, 28th August A.D. 1142; the second is irregular;³ see *Ind. Ant.* Vol. XXIII. p. 127, No. 85; and Vol. XXIV. p. 14, No. 186.

323.—Ś. 1073*.—*Ep. Ind.* Vol. III. p. 212; *Ind. Inscr.* No. 43. Bāmaṇi inscription of the Śilāhāra *Mahāmaṇḍalēśvara* Vijayāditya, 'lord of Tagara,' residing at Valavāḍa :—

(L. 12).—Śaka-varshēshu trisaptatyuttara-sahasra-pramitēshv-atītēshu amkatō-pi 1073 pravarttamāna-Pramōda-saṁvatsara-Bhādrapada-paurṇamāsī-Śukravārē sōmagrahaṇa-parvva-nimittam.

Friday, 8th September A.D. 1150; a lunar eclipse, visible in India.

In the Śilāhāra family, Jatiga [II.]; his sons Goṅkala and Gūvala [I.]; Goṅkala's son Mārasimha; his son Gaṇḍarāditya; his son Vijayāditya.

324.—Ś. 1101*.—Graham's *Kolhapoor*, p. 382, No. 6. Kōlhāpur Kanarese inscription of the *Mahāmaṇḍalēśvara* Bhōjadēva II., residing at Valavāḍa; dated Śaka 1101, the Vilamba saṁvatsara, the 10th of the bright half of Āshāḍha, the Dakṣiṇāyana-saṁkramapa.

The 26th June A.D. 1178.⁴

325.—Ś. 1109.—Graham's *Kolhapoor*, p. 397, No. 7. Kōlhāpur inscription of the *Mahāmaṇḍalēśvara* Bhōjadēva II., residing at Kollāpura; dated (in words) Śaka 1109, the Plavaṅga saṁvatsara, on Friday, the new-moon *tithi* of the month Bhādrapada, on the occasion of an eclipse of the sun.

Friday, 4th September A.D. 1187; a solar eclipse, visible in India.

326.—Ś. 1112, 1114 [and 1115].—*Ep. Ind.* Vol. III. p. 215. Kōlhāpur inscription of the Śilāhāra *Mahāmaṇḍalēśvara* Vira-Bhōjadēva II., residing at Pranālakadurga (also called Pannāledurga) :—

(L. 2).—Śakanripa-kālād-ārabhya varshēshu dvādaśōttara-śatādhika-sahasrēshu nivrittēshu varttamāna-Sādhāraṇa-saṁvatsar-āntarggata-Pushya-bahula-dvādaśyām Bhaumavārē bhānōr-uttarāyana-saṁkramapa-parvvaṇi.

(L. 13).—Śakanripa-kālād-ārabhya varshēshu chaturdśōttara-śatādhika-sahasrēshu nivrittēshu varttamāna-Paridhāvi-saṁvatsar-āntarggata-Āśvija-suddha-pratipadi Śukravārē.

(L. 19).—Pramādi-saṁvatsar-āntarggata-Phālguna-suddha-paṁchamāyām Śukravārē.

The first date corresponds to Tuesday, 25th December A.D. 1190; the third to Friday, 28th February A.D. 1194; the second is irregular.

¹ The inscription mentions the town of Kōlhāpur (Kollāpura) under the name Kshullakapura; the same name we have in No. 323.—Kāmadēva is also mentioned below, in No. 418.

² See *Ind. Ant.* Vol. XIX. p. 317.

³ The *tithi* of the date ended 13 h. 11 m. after mean sunrise of Friday, 4th February A.D. 1144, and the proper day for the Śiva-rātri therefore would have been the preceding Thursday; see *ibid.* Vol. XXVI. p. 187.

⁴ On his day the 10th *tithi* of the bright half of Āshāḍha ended 15 h. 4 m., and the Dakṣiṇāyana-saṁkrānti took place 16 h. 19 m. after mean sunrise.

327.—**Ś. 1113.**—*Transactions, Lit. Soc. of Bombay*, Vol. III. p. 393. Sātārā plates of the Śilāhāra *Mahāmaṇḍalēśvara Bhōjadēva II.*, 'lord of Tagara,' residing at Padmanāladurga; recording a grant made at the request of the prince Gaṇḍarāditya:—

Śaka-varshēshu satrayōdaśa-śatādhika-sahasrēshu 1113 gatēshu vartamāna-Virōdhikṛita-saṁvatsarē Āshāḍha-śuddha-chaturthyaṁ Brihaspativārē dakṣiṇāyana-saṁkramaṇa-parvāṇi.

Thursday, 27th June A.D. 1191.

In the Śilāhāra family, Jatiga [I.]; his son Nāyimma; his son Chandrarāja; his son Jatiga [II.]; his son Gōkalla (or Gōkala); his brother Gūvala [I.]; his brother Kīrtirāja; his brother Chandraditya; Gōkalla's son Mārasimha; his son Gūvala [II.]; his brother Bhōjadēva [I.]; his brother Ballāla; his brother Gaṇḍarāditya; his son Vijayārka (Vijayāditya); his son Bhōjadēva [II.].

G.—The Yādavas of Sēunadēsa and Dēvagiri.¹

328.—**Ś. 922.**—*Ep. Ind.* Vol. II. p. 217. Saṁgamnēr plates of the Yādava *Mahāsāmanta Bhīllama II.*, 'lord of Dvāravati,' residing at Sindinagara; issued from Nāsika:—

(L. 1).—Śakanṛipakāl-ātita-saṁvatsara-śatēshu navasu dvāvimśaty-adhikēshv-aṁkatō=pi saṁvatsarāḥ 922 ||

(L. 110).—Sā(śa)rvvarisaṁvatsarīya-Bhādrapad-āmāvāsyaṁ . . . sūrya-grahaṇē.

The date is irregular; see *Ind. Ant.* Vol. XXIV. p. 12, No. 176.

Mythical genealogy from the god Śambhu to Yadu; in his family, Sēunachandra [I.]; his son Dhāḍi[yappa]; [his son] Bhīllama [I.]; his son Rāja (or Rājan); his son Vaddiga (Vaddiga, a follower of [the Rāshtrakūṭa] Kṛishṇarāja [III.]), married Vōddiyavvā, a daughter of the [probably Rāshtrakūṭa] prince Dhōrappa [*i.e.*, probably, Nirupama]; their son Bhīllama [II.] (defeated [the Paramāra] Muñja² for Raparaṅgabhīma [*i.e.*, apparently, the W. Chālukya Taila II. Āhavamalla]), married Lakshmī [on her mother's side] of the Rāshtrakūṭa family.

329.—**Ś. 948*.**—*Ind. Ant.* Vol. XVII. p. 120, and Plate. Kalas-Budrūkh plates³ of the Yādava *Mahāsāmanta Bhīllama III.*, whose capital was Sindinagara; (composed by Harichandra, the son of Rudrapaṇḍita):—

(L. 14).—Śakanṛipakāl-ātita-saṁvatsara-śatēshu navasy-ashtāchatvāri[m*]śad-adhikēshv-aṁkatō=pi || 948 || Krōdhana-saṁvatsarā-Kārtika-saṁjāt-ādityagrahaṇē.

23rd November A.D. 1025; a solar eclipse, visible in India; see *ibid.* Vol. XXIII. p. 129, No. 98.

In the lineage of Yadu, Sēunachandra [I.]; his son Dhāḍiyappa; his son Bhīllama [I.]; his son Rāja (or Śrīrāja); his son Vaddiga; his son Bhīllama [II.], married Lakshmī [on her mother's side] of the Rāshtrakūṭa family; their son Vēstū; his son Bhīllama [III.].

330.—**Ś. 991.**—*Ep. Ind.* Vol. II. p. 225. Vāghlī inscription of the Yādava *Mahāmaṇḍalanātha Sēuna (Sēunachandra II.)*, and of his feudatory, the Maurya chief Gōvindarāja:—

(Page 227, l. 9).—Rūpa-Nāmd-āmka-tulyē tu 991 Śaka-kālasya bhūpatau Saumya-saṁvatsar-Āshāḍha-ravigrahaṇa-parvvaṇi ||

21st July A.D. 1069; a solar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 124, No. 66.

In the Maurya family (which sprang from Māndhātṛi of the solar race, and whose capital originally was Valabhi in Surāshtra): Kikāṭa; Takshaka; Bhīma; Sarvasūra; Gōvindarāja; Sādhvasika; Jhañjha; his son Dēvahastin; his son Muñja; his son Padmākara; (two names illegible); Vappaiya; his son (name not preserved); his son Vālaparāja; Sādhvasika; Śantirāja; his son Pravaraśūkara (?); his son Bhāilēka; Bhīmarāja; Gōvindarāja (whose wife was Nāyaki).

¹ These include the Gutta inscriptions Nos. 335, 340, 351, 363 and 364. Compare also above, Nos. 223, 292 and 298.

² Compare above, No. 140.

³ The plates are numbered with numeral figures.

331.—*Ś. 991.*—*Ind. Ant.* Vol. XII. p. 119. Bassein plates¹ of the Yādava *Mahāmaṇḍalēśvara* Sēunachandra II. :—

(L. 24).—Sa(śa)ka-saṁvat ēkanavatyadhika-navasa(śa)tēshu saṁvat 991 Saunya-saṁvatsariya-Śrāvana-sudi chaturdasyām(syām) Guru-dinē.

The date is irregular; see *ibid.* Vol. XXIV. p. 14, No. 182.

Driḍhaprahāra came from Dvārāvati and founded(?) Chandrādityapura; his son Sēunachandra [I.], founded Sēunapura in Sindinēra; his son Dhāḍiyappa; his son Bhillama [I.]; his son Śrīrāja (or Rāja); his son Vaddiga; his son Bhillama [II.], married Lachchhiyavā (Lakshmi), the daughter of king Jhañjha² [and on her mother's side] of the Rāshtrakūṭa lineage; their son Vāsuka(?), married Nāyaladēvi, the daughter of the *Maṇḍalikatilaka* Gōgi of the Chālukya lineage;³ their son Bhillama [III.], married Hammā, also called Avalladēvi, a daughter of the [W.] Chālukya Jayasinha [II.];⁴ in his family, Sēunachandra [II.].

332.—*Ś. 1063* (for 1064).—*Ind. Ant.* Vol. XII. p. 126, and Plate. Anjanēri inscription of the reign of the Yādava *Mahāsāmanta* Sēunadēva, 'lord of Dvārāvati':—

(L. 1).—Śaka-saṁvat 1033 Dumḍubhi-saṁvatsar-āntargata-Jyēsthā-sudi pañchadaśyām Nōmē Anurādhā-nakshatrē Siddha-yōgē asyām saṁvatsara-māsa-paksha-divasa-pūrvvāyām tithau.

Monday, 11th May A.D. 1142; see *ibid.* Vol. XXIV. p. 4, No. 140.

333.—*Ś. 1075.*—*Ind. Ant.* Vol. VIII. p. 39, and Plate; *PSOCI.* No. 283. Pāṭṭa (in Khândōs) inscription of the Nikumbha family. Date of the foundation of a temple by Indrarāja :—

(L. 20).—Varshā[pān] pañchasaṁvatsarā sahasrē sādrikē gatē | 1075 | Śakabūpāla-kālasya tathā Śrīnukha-vatsarē ||

In the race of the mythical king Nikumbha who was of the solar race, Kṛishnarāja [I.]; his son Gōvana [I.]; his son Gōvindrāja; his son Gōvana [II.]; his son Kṛishnarāja [II.]; his son Indrarāja (whose minister was Chaṅgadēva) married Śrīdēvi of the lineage of Sagara; their son Gōvana [III.].⁵

334.—*Ś. 1113.*—*Ep. Ind.* Vol. III. p. 219. Gadag inscription of the Dēvagiri-Yādava *Mahārājādhirāja Pratāpa-chakravartin* Bhillama, recording a grant which was made at the request of his minister Jaitasinha,⁶ from the camp at Hērūrā :—

(L. 13).—Śakanipakāl-āṭṭa-saṁvatsara-satēshu trayōdaś-ādrikēshy-ēkādaśasu vartimāna-Virōdhakṛit-saṁvatsar-āntargata-Jyēsth-āmāvāsyaśyām-Ādityavārē sūrya-grahapē.

Sunday, 23rd June A.D. 1191; a solar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 125, No. 71.

In Yadu's family, Sēvapa;⁷ his son Mallugi; his son Amaragaṅga; his younger brother Karpa; his son Bhillama.

335.—*Ś. 1113.*—*PSOCI.* No. 109. Chaudāḍāmpur Kanarese inscription of the Gutta *Mahāmaṇḍalēśvara* Vira-Vikramāditya II.,⁸ and his *Nāyaka* Khaṇḍeya-Kāra-Kāmeya-nāyaka :—

(L. 72).—Sa(śa)ka-varshaṁ 1113neya Virōdhikri(kṛi)tu-saṁvatsarada Mārgasirad-āmāvāse sūryya-grahapad-amdu.⁹

¹ The plates were bought by Dr. Bhāu Dāji, but it is not known where they are now.

² Perhaps the Jhañjha of No. 305 ff.

³ For a Goggirāja who may be intended here, see *Norik. Inscr.* No. 354. According to Dr. Bhandarkar perhaps the Goggirāja of No. 305 ff., above.

⁴ See above, No. 151 ff.

⁵ See below, No. 337.

⁶ *I.e.* the Jaitasinha of No. 419.

⁷ Probably Sēunachandra II. of Nos. 330 and 331.

⁸ Compare Dr. Fleet's *Dynasties*, p. 582, and see above, Nos. 223, 292, and 298.

⁹ In line 80 there is another date of the month Pausa of the same year, but it is irregular.

18th December A.D. 1191; a solar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 125, No. 72.

336.—*Ep. Ind.* Vol. V. p. 29. Managōli fragmentary Kanarese inscription of the time of the Dēvagiri-Yādava Jaitugidēva (Jaitapāla) I., the son of Bhillama.—The inscription mentions one of Jaitugi's officers, the *Daṇḍanātha* Sahadēva, whose elder brother was the *Daṇḍanātha* Mallidēva.

337.—*Ś. 1128* (for 1129).—*Ep. Ind.* Vol. I. p. 341; *PSOCL.* No. 234. Pāṭṇā (in Khândés) inscription,¹ recording that the chief astrologer of the Dēvagiri-Yādava Siṅghaṇa, Chaṅgadēva, a grandson of the astronomer Bhāskarāchārya, founded a college for the study of the *Siddhāntasirōmaṇi*, etc., which was endowed by the brothers Sôidēva and Hēmādīdēva of the Nikumbha family, feudatories of the Yādavas. Date of Sôidēva's grant:—

(L. 21).—*Śākē* 1128 Prabhava-saṁvatsarē Śrāvapa-māsē paurṇamāsyāṁ chaṁdragrahaṇa-samayā.

9th August A.D. 1207; a lunar eclipse, visible in India; see *Ind. Ant.* Vol. XXIV. p. 5, No. 141.

In Yadu's race, Bhillama; Jaitrapāla [I.]; his son Siṅghaṇa (Siṁha).—In Nikumbha's family (see No. 333), Krishnarāja [II.]; his son Indrarāja; his son Gōvana [III.]; his son Sôidēva; after his death, his younger brother Hēmādīdēva.—Of Chaṅgadēva the following genealogy is given: In the Sāṇḍilya family, the poet Trivikrama; his son Bhāskarabhaṭṭa (received from king Bhōja the title *Vidyāpati*); his son Gōvinda-sarvajña; his son Prabhākara; his son Manōratha; his son, the poet Mahēśvarāchārya; his son Bhāskara (the astronomer); his son Lakshmidhara (appointed chief Paṇḍit by king Jaitrapāla); his son Chaṅgadēva (chief astrologer of king Siṅghaṇa). Compare below, No. 343.

338.—*Ś. 1135**.—*PSOCL.* No. 100; *Ind. Ant.* Vol. II. p. 297, No. 1. Gadag Sanskrit and Kanarese inscription of the reign of the Dēvagiri-Yādava Siṅghaṇa:—

(L. 34).—*Śakaṁpakāḷ-ākṛānta-saṁvatsara-sataraṅgaḷu* 1135neya Āṅgirasa-saṁvatsarada Phālguṇa(na)-śudhdha(ddha)-bidige Śanaishcharavārada=amdu.²

The date is irregular.

339.—*Ś. 1136**.—*Jour. Bo. As. Soc.* Vol. XII. p. 7. Khidrāpur inscription of the Dēvagiri-Yādava *Mahārājādhirāja Pratāpa-chakravartin* Siṅghaṇa (Siṁha), 'lord of Dvāravāt', residing at Dēvagiri:—

(L. 8).—*Śaka-varshē* 1136 Śrīmukha-saṁvatsarē Chaitrē sūrya-parba(rva)ṇi Sōma-dinē.

Monday, 22nd April A.D. 1213; a solar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 130, No. 102.

340.—*Ś. 1136**.—*PSOCL.* No. 234. Harajahalli³ Kanarese inscription of the Gutta *Mahāmaṇḍalēśvara Vira-Vikramāditya* II., whose daughter (by Paṭṭamādēvi) Tuḷvaladēvi (Tuḷvaladēvi) was married to Ballāḷa (son of a feudatory chief named Siṁha, Siṅga, Siṅgidēva, lord of the Sāntālī *maṇḍala*), and whose sons were Jōvidēva (Jōyidēva) II.⁴ and Vikrama (Vikramāditya III.):—

(L. 63).—*Śaka-varshada* 1136neya Śrīmukha-saṁvatsarada Chaitrad=amavāsye Sōmavāra sūryyagrahaṇa-saṁkrānti-vyātiyapātad=adnu.⁵

Monday, 22nd April A.D. 1213; a solar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 130, No. 102. (The Vṛishabha-saṁkrānti took place on the following Wednesday).

¹ The concluding lines of the inscription are in old Marāṭhī.

² See *Ind. Ant.* Vol. XII. p. 210, No. 29.

³ See Dr. Fleet's *Dynasties*, p. 583, and above, No. 335.

⁴ See below, No. 351.

⁵ Read *-vyātiyapātad=amdu*.

341.—**Ś. 1137.**—*PSOCI.* No. 201; *Mysore Inscr.* No. 37, p. 72. Baḷagāhve Kanarese inscription of the Dēvagiri-Yādava Mahārājādhirāja Siṅghaṇa (Siṅghaṇa), 'lord of Dvārāvati':—

(L. 23).— . . . 1137neya Yuva-saṁvatsarada Bhādrapadaḍ=amāvāsye Bri(bṛi)haspati-vārad=aṁdu.

Thursday, 24th September A.D. 1215; see *Ind. Ant.* Vol. XXIII. p. 125, No. 73.

342.—**Ś. 1140.**—From an impression supplied by Dr. Fleet; Graham's *Kolhapoor*, p. 425, No. 11; *Ind. Inscr.* No. 48. Kōlhāpur inscription of the Dēvagiri-Yādava Chakravartin Siṅghaṇa (Siṅghaṇa), the son of Jaitrapāla who was the son of Bhillama :—

(L. 16).— Śaka-varsha 1140 Bahudhānya-saṁvatsarē.

343.—**Ś. 1144.**—*Ep. Ind.* Vol. III. p. 112. Bahāl (in Khândés) inscription, recording the foundation of a temple by Anantadēva, the chief astrologer of the Dēvagiri-Yādava Siṅha (Siṅghaṇa); (a *prāśasti* composed by Anantadēva's younger brother Mahēśvara) :—

(L. 18).— Shaṭk-ōṇē sadala-śat-ādhi[kē] sahasrē 1144 varshānām Śaka-prithivīpatēḥ prayātē | Chaitr-ādyā-pratipadi Chitrabhānu-varshē.

The ornament of Yadu's family Bhillama; his son Jaitrapāla [I.] (made Gaṇapati¹ lord of the Andhra country); his son Siṅha (defeated king Arjuna²).—Of Anantadēva the following genealogy is given: In the family of the sage Śāṇḍilya, Manōratha; his son Mahēśvara (composed astronomical works); his son Śrīpati; his son Gaṇapati; his son Anantadēva (author of astronomical works). Compare above, No. 337.

344.—**Ś. 1145*.**—*Jour. Bo. As. Soc.* Vol. XII. p. 11; *Archæol. Surv. of West. India*, Vol. II. p. 233, and Plate lxxiv.; and Vol. III. p. 116; *PSOCI.* No. 91. Munōḷi (Manōḷi) Kanarese inscription of the reign of the Dēvagiri-Yādava Mahārājādhirāja Pratāpa-chakravartin Siṅghaṇa, ruling at his capital of Dēvagiri; recording grants made by his Daṇḍanāyaka Purushōttama and others :—

(L. 24).— Sa(śa)ka-varsha 1145neya Chitrabhānu-saṁvatsarada Kārttika-su(śu)dhdha(dhha)-pūṇami Sōmavāra sōmagrahaṇa-bya(vya)tipātadalli.

22nd October A.D. 1222, with a lunar eclipse, visible in India; but the day was a Saturday, not a Monday; see *Ind. Ant.* Vol. XXIV. p. 8, No. 157.

345.—**Ś. 1145.**—*Ind. Ant.* Vol. XIX. p. 157. Notice of a Kōlār (Kōlhār) Kanarese inscription of the time of the Dēvagiri-Yādava Siṅghaṇa, reigning at his capital of Dēvendrāgiri :—

(L. 9).— Śaka-varusada³ 1145de(da)neya Svabhānu-saṁvachchharada⁴ dvitīya-Bhādrapada-su(śu)dhdha(ddha) 5 Su(śu)kravārad=aṁdu.

Friday, 1st September A.D. 1223; see *ibid.* Vol. XXIII. p. 117, No. 28.

346.—**Ś. 1148*.**—*PSOCI.* No. 110. Chaudādāmpur Kanarese inscription. Date (of the time of the Dēvagiri-Yādava Siṅghaṇa?) :—

(L. 26).— Śaka-varsha 1148neya Pārthiva-saṁvatsarada Bhādrapa[da*]-śuddha 15 Sōmavāra chaṁdrōparāga-⁵pūṇyatithiya madhyāhnasamaya⁶.

19th August A.D. 1225, with a lunar eclipse, visible in India; but the day was a Tuesday, not a Monday; see *Ind. Ant.* Vol. XXIV. p. 8, No. 158.

(For two later dates in the same inscription see below, Nos. 361 and 363).

¹ I.e. the Kākatīya Gaṇapati; compare below, No. 585 ff.

² I.e., probably, the Paramāra Arjunavarman; see *North. Inscr.* No. 195.

³ Read *-varshada*.

⁴ Read *-saṁvatsarada*.

⁵ Read *punya*².

347.—Ś. 1156.—PSOCI. No. 87. Bijāpur Kanarese inscription of the Dēvagiri-Yādava Siṅghaṇa (Siṅghaṇa):—

(L. 5).—Śaka-varushada¹ 1156neya Jaya-samvatsarada Vaisā(śā)kha-su(su)ddha-puṇṇame² Vaddavārad-aṁdu.

Saturday, 15th April A.D. 1234; see *Ind. Ant.* Vol. XXIII. p. 118, No. 29.

348.—Ś. 1157.—From an impression supplied by Dr. Fleet; Graham's *Kolhapoor*, p. 426, No. 12; *Ind. Inscr.* No. 47. Kōlhāpur fragmentary inscription of the Dēvagiri-Yādava Siṅghaṇa:—

(L. 1).—Śaka 1157 Manmatha-samvatsarē Śrāvapa-bahula 30 Gurau.

For Manmatha = Ś. 1157 the date is irregular; (for Ś. 1157* = Jaya it would correspond to Thursday, 27th July A.D. 1234); see *Ind. Ant.* Vol. XXIV. p. 16, No. 192.

349.—Ś. 1158.—From an impression supplied by Dr. Fleet; Graham's *Kolhapoor*, p. 426, No. 13. Kōlhāpur inscription of the reign of the Dēvagiri-Yādava Mahārājādhirāja Praudha-pratāpa-chakravartin Siṅghaṇa, 'lord of Dvārāvati':—

(L. 1).—Śaka 1158 varshē Durmmukha-samvatsarē Māgha-suddha-pūrṇamāsyām tithau Sōma-dinē |

(L. 14).— . . . sōmē=pavi[ddhē?] . . .

Monday, 12th January A.D. 1237; a lunar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 118, No. 31.

350.—Ś. 1160*.—PSOCI. No. 112. Tiliwalli Sanskrit and Kanarese inscription of the Dēvagiri-Yādava Siṅghaṇa (Siṅghaṇa), and of his feudatory Śāvanta-Thakkura:—

(L. 77).—Śaka-varsha 1160neya Hēmapāmbi-[sa]mavatsarada Phālguna(na)-su(śu) 3 Bri(bri)haspativārad-aṁdu.

Thursday, 18th February A.D. 1233; see *Ind. Ant.* Vol. XXIV. p. 2, No. 130.

351.—Ś. 1160*.—*Jour. Bo. 4s. Soc.* Vol. XV. p. 386, and Plates. Haralahaḷli (now Bombay As. Soc.'s) plates⁴ of the reign of the Dēvagiri-Yādava Mahārājādhirāja Praudha-pratāpa-chakravartin Siṅghaṇa, 'lord of Dvārāvati,' recording a grant by his Daṇḍēśa Bichirāya⁵ (Bicha, Viehaṇa), the son of Chikkadēva and younger brother of Malla, made with the consent of the Gutta Mahāmāṇḍalēśvara Jōyidēva II.,⁶ 'lord of Ujjayani':—

(L. 62).—Śaka-varshād-ārabhya shashṭyadhika-śatōttara-śa(sa)hasra-mitē Hēma-ṇa[ṇ*]vi(bi)-sām(sam)vatsarē Phālguna-māsē saptamāyām.

In the Yādava race was Amaragāṅgēya; in that family was Mallugi; from him sprang Bhullama; from him, Jaitugi [I.]; from him, Siṅghaṇa.

352.—Ś. 1162.—*Archæol. Surv. of West. India*, Vol. III. p. 87, and Plate lviii.; PSOCI. No. 286. Ambā inscription of the Dēvagiri-Yādava Siṅghaṇa (Siṅghaṇa), and of his generals Khōlēśvara (the son of Trivikrama) and his son Rāma of the Maudgala family; (a *prastāvi* composed by Kavirāja?):—

(L. 27).—Śaku 1162 Śārvarī-samvatsarē | Kārtika-suddha [da-10?].

353.—PSOCI. No. 285. Ambā inscription⁷ of the time of the Dēvagiri-Yādava Siṅghaṇa, his general Khōlēśvara, etc.

¹ Read Śaka-varshada.

² Read -puṇṇame.


³ On this day the *tithi* of the date commenced 5 h. 12 m. after mean sunrise.

⁴ The description of the boundaries is in Kanarese.

⁵ Not Chikkadēva.—Compare below, No. 357.

⁶ See Dr. Fleet's *Dynasties*, p. 588; and above, No. 340.

⁷ An edition of this inscription is desirable.



354.—*PSOOL*. No. 111. Chaudadāmpur Kanarese inscription. Date (l. 99) of 'the Śubhakṛit *saṁvatsara*, in the era of the Yādava king *Simhaṇa* (*Singhaṇa*); Friday, the third day of the bright fortnight of Pushya.'

[*Subhakṛit* = *Ś. 1164*]: Friday, 26th December A.D. 1242 (the day for the celebration of the *Uttarāyana-saṁkrānti*, which took place shortly before mean sunrise).

(For two later dates in the same inscription see below, Nos. 364 and 365).

355.—*Ind. Ant.* Vol. XII. p. 100. Kaḍakoḷ Kanarese memorial tablet of the 37th year (of the reign) of the Dēvagiri-Yādava *Bhujabala-pratāpa-chakravartin* *Simhaṇa* (*Singhaṇa*):—

(L. 2).—*Simhaṇadēva-varsha* 37 *Parābhava-saṁvatsarada* *Mārggaśira-su(śu)dha(ddha)-pāñchami* *Bri(bṛi)havāradalu*.

[*Parābhava* = *Ś. 1168*]: Thursday, 15th November A.D. 1246.

356.—*Ś. 1172**.—Graham's *Kolhapoor*, p. 437, No. 14; *Jour. Bo. As. Soc.* Vol. II. p. 264, No. iii. Kōlhāpur inscription of the reign of the Dēvagiri-Yādava *Kanharadēva* (*Kṛishṇa*), dated Śaka 1172, the *Saumya saṁvatsara*, "Vaiśākha-vadi 30 Śukrē."

Friday, 14th May A.D. 1249.

357.—*Ś. 1171*.—*Ind. Ant.* Vol. VII. p. 304, and Plates; *PSOOL*. No. 21. Chikka-Bāgewāḍi plates of the reign of the Dēvagiri-Yādava *Kanhāra* or *Kanhara* (*Kṛishṇa*, the son of Jaitugi II who was the son of *Simhaṇa*, i.e. *Singhaṇa*); recording a grant by the minister *Mallisaṭṭi* (*Malla*, the elder brother of Bīcha and son of Chikkadēva¹), which was confirmed (by means of this copper-plate charter) by *Malla's* son, the minister *Chaunḍisaṭṭi*:—

(L. 19).—*Ēkasaptatyuttara-śatādhē(dhi)ka-sahasra-saṁkhyēshu* *Śak-āvdē(bdē)shv=atilēshu pravarttamānē* *Saun(sau)mya-saṁvatsarē tad-aṁta[r*]gat-Āshāḍha-paurṇamāsyām* *Śanaishcharavārē Pūrvāshāḍh[ā*]-nakshatrē Vaidhṛiti-yōgē itthambhūta-puṁ(pu)nyakālē*.

Saturday, 26th June A.D. 1249; see *ibid.* Vol. XXIII. p. 118, No. 32.

358.—*Ś. 1171*.—*Ind. Ant.* Vol. XIV. p. 69. Bēḍigeri plates of the reign of the Dēvagiri-Yādava *Kanhāra* or *Kanhara* (*Kṛishṇa*, described as in No. 357); recording a grant by the minister *Mallisaṭṭi*, for which the king's sanction (with this copper-plate charter) was obtained by his son, the minister *Chaunḍisaṭṭi*:—

(L. 22).—*Śaka-saṁvatsarasya śatādhika-sahasra-aikādhika-saptatyās=ch=ānamtarē* *Saumyē=bdē Śrāvaṇē māsi sita-pakshē dvādaśyām Guruvārē*.

Thursday, 22nd July A.D. 1249; see *ibid.* Vol. XXIII. p. 118, No. 33.

359.—*Ś. 1174**.—*Jour. Bo. As. Soc.* Vol. XII. p. 34. Munōḷi (*Manōḷi*) Kanarese inscription of the reign of the Dēvagiri-Yādava *Bhujabala-prauḍha-pratāpa-chakravartin* *Kandhara* (*Kṛishṇa*, the son of Jaitugi II. who was the son of *Singhaṇa*), 'lord of *Dvāravattī*,' residing at his capital of Dēvagiri:—

(L. 20).—*Sa(sa)ka-varsha* 1174^{neya} *Virō[dhikṛitu]-saṁvatsarada* *Jēshṭha-²bahuja* *va(a)māvasē sūryya-grahṇa* *Su(śu)kravā[rad=a]mdu*.

The date is irregular; see *Ind. Ant.* Vol. XXIV. p. 16, No. 193.

360.—*Ś. 1175*.—*Jour. Bo. As. Soc.* Vol. XII. p. 42. Bēhāṭṭi plates of the 7th year (of the reign) of the Dēvagiri-Yādava *Mahārājādhirāja* *Kanhara* (*Kṛishṇa*), 'lord of *Dvāravattī*,' recording a grant by the minister *Chaunḍa* (*Chāvunḍa*)-*rāja*, the son of *Vīchaṇa* who was the younger brother of *Agramalla* (? *Malla*³):—

(L. 51).—*Panichasaptatyadhika-śatōttara-sahasrakē* *Śaka-varshē varttamānē* *svasti śrīmad-Yādavanārāyana-bhujava(ba)laprauḍhapratāpachakravartti-śrī-Kanharadēva-varshēshu* *saptamē* *Pramādi-saṁvatsarē* *Chaitra-māsē* *kṛishṇa-pakshē amāvāsyāyām* *Sōmavārē*.

The date is irregular; see *Ind. Ant.* Vol. XXIV. p. 16, No. 194.

¹ See above, No. 361.

² Read *Jyēshṭha*.

³ Compare above, No. 351.

In the race of the Yadus there was Amaragāṅgēya; also Jaitugi [I.]; his son Sīṃhala (Sīṃhapa); his grandson Kṛishṇa.

361.—*PSOCI*. No. 110. Chauḍadāmpur Kanarese inscription; the four lines round the top of the stone. Date of the time of the Dēvagiri-Yādava Kanhara (Kṛishṇa):—

(L. 1).—Kanhara-dēva-varshada Siddhārthi-saṃvatsarada Chaitra-baṇḍa 15 Sô sūryya-grahapada samaya(P).

[For Siddhārthin = Ś. 1181] the date is irregular.

(For two other dates in the same inscription see Nos. 346 and 363).

362.—Ś. 1183.—From an impression supplied by Dr. Fleet. Renadāḷ inscription¹ of the reign of the Dēvagiri-Yādava Praudha-pratāpa-chakravartin Mahādēva, 'lord of Dvāravati':—

(L. 1).—Śaku 1183 Dā(du)rmmati-saṃvatsarē.

363.—*PSOCI*. No. 110. Chauḍadāmpur Kanarese inscription. Date of the third year of the reign of the Dēvagiri-Yādava Mahādēva, and of the Gutta Gutta III., the son of Vikrama (Vikramāditya III.) and Majjaladēvi:²—

(L. 40).—Mahādēvarāya-vijayarājy-ōdaye(ya)da 3ṛaneya Dundubhi-saṃvatsarada Vaya-śākha-su(śu)ddha(ddha) 15 Sômarā sôma-grahapadalli.

[For Dundubhi = Ś. 1184] the date is irregular; see No. 364.

(For two earlier dates in the same inscription see above, Nos. 346 and 361).

364.—Ś. 1185*.—*PSOCI*. No. 111. Chauḍadāmpur Kanarese inscription. Date of the time of the Dēvagiri-Yādava Mahādēva, and of the Gutta Gutta III.:³—

(L. 79).—Śaka-varsha 1185neya Dundubhi-saṃvatsarada Vayaśākha-suddha 15 Sômarā sôma-grahapad-andu.

The date is irregular; see No. 363.

(For two other dates in the same inscription see Nos. 354 and 365).

365.—*PSOCI*. No. 111. Chauḍadāmpur Kanarese inscription. Date of the time of the Dēvagiri-Yādava Mahādēva:—

(L. 92).—Rudhirōdgārī-[saṃvatsa]rada Jēshṭha-baṇḍa 5 (but possibly 1) Âdivāra Shadastimukha-saṃkrānti taḥkālādalli.

[Rudhirōdgārī = Ś. 1185]: Sunday, 27th May A.D. 1263; but the *tithi* which ended on this day was the third of the dark half; see *Ind. Ant.* Vol. XXV. p. 346, No. 4.

(For two earlier dates in the same inscription see above, Nos. 354 and 364).

366.—Ś. 1187.—From an impression supplied by Dr. Fleet;⁴ *Ind. Inscr.* No. 49. Kōlhāpur inscription of the reign of the Dēvagiri-Yādava Praudha-pratāpa-chakravartin Mahārāja Mahādēva, the younger brother of Kanhara (Kṛishṇa):—

(L. 8).—Śaka-varshē 1187 varttamāna-Krōdhana-saṃvatsarē Māghamāsa-pūṇṇimāyām Śukra-dinē.

Friday, 22nd January A.D. 1266; see *Ind. Ant.* Vol. XXIII. p. 118, No. 34.

367.—Ś. 1189.—*Ind. Ant.* Vol. XVIII. p. 128. Date of a Hulgūr Sanskrit and Kanarese inscription of the Dēvagiri-Yādava Mahādēva:—

(L. 15).—Śaka-varṣada⁵ 1189neya Prabhava-saṃvatsarada Jēshṭha-⁶ba 30 Budhavāra sūrya-grahapad-andu.

Wednesday, 25th May A.D. 1267; a solar eclipse, visible in India; see *ibid.* Vol. XXIII. p. 125, No. 74.

¹ The last lines of the inscription appear to be in old Marāṭhī.

² See Dr. Fleet's *Dynasties*, p. 583, and above, No. 340.

³ See above, No. 363.

⁴ Compare *Jour. Bo. As. Soc.* Vol. II. p. 264, No. ii.

⁵ Read -varshada and *Jyēshṭha*.

368.—PSOUI. No. 142; *Mysore Inscr.* No. 12, p. 20. Dāvāgere Kanarese inscription of the reign of the Dēvagiri-Yādava Rāmachandra. Date of the time (?) of the Dēvagiri-Yādava Mahādēva :—

'The Prajāpati *samvatsara*. No further details of the date are given.'

[Prajāpati = Ś. 1193.]

369.—Ś. 1193.—*Ind. Ant.* Vol. XIV. p. 315. Paithān (now Bombay Secretariat's?) plates¹ of the Dēvagiri-Yādava Rāma (Rāmachandra) :—

(L. 62).—Sa(śa)kē cha śkādaśasu trinavaty-adhikēshv-atitēshu 1193 varttamāna-Prajāpati-samvatsar-āntargata-Māgha-suddha-dvādaśyām Vu(bu)dhē.

Wednesday, 13th January A.D. 1272; see *ibid.* Vol. XXIII. p. 118, No. 35.

In the race of Yadu, in the Moon's family, Siāghana; his son Mallugi; after him, Bhillama; his son Jaitugi [I.] (killed the king of Trikalīnga and liberated king Gapapati² from prison); his son Siāghana (overthrew Ballāla,⁴ the Andhra king, Kakkalla,⁵ the lord of Bhambhāgiri, Bhōja,⁶ and Arjuna⁷); his son Jaitugi [II.]; his son Kṛishṇa; his younger brother [Mahādēva] (defeated Viśala⁸); his son Āmana; from him Kṛishṇa's son Rāma took away the kingdom.

370.—Ś. 1194.—*Jour. Roy. As. Soc.* Vol. V. p. 183. Ṭhānā plates of the reign of the Dēvagiri-Yādava Rāmachandra, 'lord of Dvāravati,' recording a grant by Achyuta-Nāyaka :—

Śālivāhana-Śakē 1194 Āngirā-nāma-samvatsarē Āśvina-suddha 5 Ravau.

The date is irregular.

In the race of the Yadus, Bhillama; after him, Jaitrapāla [I.]; his son Siāghana; after him, Kṛishṇa; his younger brother Mahādēva; Kṛishṇa's son Rāmachandra.

371.—Ś. 1194.—From an impression supplied by Dr. Fleet;⁹ Graham's *Kolhapoor*, p. 437, No. 15. Kōlhāpur inscription of the reign of the Dēvagiri-Yādava Praudha-pratāpa-chakravartin Rāmadēva (Rāmachandra) :—

(L. 23).—Śaka-varshēshu 1194 vēd-āṁka-Rudra-pramitēshu vyatitēshu varttamān-Āngirah-[sam]vatsara-Māgha-pūrṇimāyām sōmagrahaṇa-parvati.

3rd February A.D. 1273; a lunar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 119, No. 36.

372.—Ś. 1199*.—From an impression supplied by Dr. Fleet; Graham's *Kolhapoor*, p. 451, No. 16. Sidnūr inscription¹⁰ of the reign of the Dēvagiri-Yādava Praudha-pratāpa-chakravartin Rāmachandra :—

(L. 13).—Śaka-varshēshu 1199 raṁdhra-āṁka-Rudra-pramitēshu gatēshu varttamāna-Dhātṛi-samvatsar-ānt(ā)ntargata-Śrāvāṇa-pūrṇimāyām Sōma-dinē yajñōpavita-parvati.

Monday, 27th July A.D. 1276; see *Ind. Ant.* Vol. XXIII. p. 128, No. 93.

373.—Ś. 1199.—PSOUI. No. 125; *Mysore Inscr.* No. 26, p. 44; compare *Jour. Bo. As. Soc.* Vol. XII. p. 4. Harihar Kanarese inscription of the Dēvagiri-Yādava Praudha-pratāpa-

¹ See Dr. Fleet's *Dynasties*, p. 528 and p. 529, note 1.

² Compare *Ind. Ant.* Vol. XXX. p. 517.

³ *I.e.* the Kākatya Gapapati; see below, No. 585 ff.

⁴ *I.e.* the Hoysala Ballāla II.; see below, No. 415 ff.

⁵ Perhaps some prince Kakkalla of the Kalachuri (Chēdi) family.

⁶ *I.e.* the Śilāhara Bhōja II.; see above, No. 324 ff.

⁷ *I.e.*, probably, the Paramāra Arjunavarman; see above, No. 843.

⁸ Compare *North. Inscr.* No. 225.

⁹ Compare *Jour. Bo. As. Soc.* Vol. II. p. 264, No. iv.

¹⁰ The inscription contains a sculpture of an ass and a woman.

chakravartin Rāmachandra, 'lord of Dvārāvati,' and of his feudatory, the *Mahāmaṇḍalēśvara* Śāluva-Tikkamadēva :—

'Śaka 1199 (in figures, l. 67), the Īśvara *saṃvatsara*; Friday, the thirteenth day of the (?) bright fortnight of Chaitra.'

Friday, 19th March A.D. 1277.¹

The inscription contains two other dates of the Bahudhānya *saṃvatsara* (Ś. 1200) and of the 'Pramādi' (Pramāthin) *saṃvatsara* (Ś. 1201).

374.—*PSOCL*. No. 202; *Mysore Inscr.* No. 57, p. 127. Baḷagāmve Kanarese memorial tablet of the time of the Dēvagiri-Yādava Rāmachandra :—

'The twelfth or thirteenth year (in figures, l. 16) of his reign, the Chitrabhānu *saṃvatsara*; Sunday, the fifteenth day of the bright fortnight of Māgha or, perhaps, Mārgaśīrsha;' (*Mys. Inscr.* : 'the 14th year . . . the 1st day of the moon's increase, Sunday').

[For Chitrabhānu = Ś. 1204] the date is irregular, for either month.

375.—*PSOCL*. No. 225; *Mysore Inscr.* No. 111, p. 207. Sorab Kanarese memorial tablet of the 12th year of the reign of the Dēvagiri-Yādava Rāmachandra :—

(L. 4).—Rāmachandradēva-vijayarājya-ōdayada 12 Svabhānu-saṃvatsarada Phālguna(na)-su(śu) 5 Vaddavārad-aṃdu.

[For Subhānu = Ś. 1205] the date is irregular.

376.—*PSOCL*. No. 203; *Mysore Inscr.* No. 82, p. 169. Baḷagāmve Kanarese memorial tablet of the 14th year of the reign of the Dēvagiri-Yādava Rāmachandra :—

'The fourteenth year (in figures, l. 3) of his reign, the Tārana *saṃvatsara*; Sunday, the first day of the bright fortnight of Chaitra;' (*Mys. Inscr.* : 'the 3rd day').

[Tārana = Ś. 1206] : Sunday, 19th March A.D. 1284 (which is the proper equivalent for the first *tithi* of the bright half of Chaitra).

377.—*PSOCL*. No. 204; *Mysore Inscr.* No. 52, p. 113. Baḷagāmve Kanarese memorial tablet of the 14th year of the reign of the Dēvagiri-Yādava Rāmachandra :—

'The fourteenth year (in figures, l. 2) of his reign, the Tārana *saṃvatsara*; Wednesday, the tenth day of the bright fortnight of Vaiśākha.'

[Tārana = Ś. 1206] : Wednesday, 26th April A.D. 1284.

378.—*PSOCL*. No. 205; *Mysore Inscr.* No. 81, p. 168. Baḷagāmve Kanarese memorial tablet of the 16th year of the reign of the Dēvagiri-Yādava Rāmachandra :—

'The sixteenth year (in figures, l. 6) of his reign, the Vyaya *saṃvatsara*. The other details of the date are illegible.'

[Vyaya = Ś. 1208.]

379.—Ś. 1212*.—*Jour. Roy. As. Soc.* Vol. V. p. 178. Thāṇā plates of the reign of the Dēvagiri-Yādava Mahārājādhirāja Praudha-pratāpa-chakravartin Rāmachandra, 'lord of Dvārāvati,' recording a grant by Kṛishṇadēva, the governor of Koṅkana :—

Śālivāhana-Śakā 1212 Virōdhi-saṃvatsarē Vaiśākha-suddha-paurṇamāsyām Bhaumē.

The date is irregular.

In the race of the Yadus, Bhillama; after him, Jaitrapāla [I.]; his son Siṅghana; after him, Jaitrapāla [II.]; after him, Kṛishṇa; his younger brother Mahādēva; Kṛishṇa's son Rāmachandra.

380.—Ś. 1219*.—From an impression supplied by Dr. Burgess. British Museum inscription of the Dēvagiri-Yādava Praudha-pratāpa-chakravartin Rāmachandra :—

(L. 1).—Śaku-saṃvatu 1219 || Durmushī(khī)-saṃvatsarē Kārttika-vadi amāvāsyām Ravau.

¹ This is the proper equivalent of the *tithi* for the bright half of Chaitra.

(L. 5).—sūrya-parvapi.

Sunday, 28th October A.D. 1296; a solar eclipse, visible in India.

381.—Ś. 1222.—From impressions supplied by Dr. Fleet. Vēlāpur inscription¹ of the reign of the Dēvagiri-Yādava *Praugha-pratāpa-chakravartin Rāmachandra* :—

(L. 1).—Śak[u] 1222 Śārvari-saṁvatsarē Mārgisaru-vadi [9?] Sômā.

Supposing the figure for the *tithi* to be really 9, the date corresponds to Monday, 5th December A.D. 1300.

382.—Ś. 1227.—From impressions supplied by Dr. Fleet. Vēlāpur inscription of the reign of the Dēvagiri-Yādava *Praugha-pratāpa-chakravartin Rāmachandra* :—

(L. 1).—Śāku 1227 | Viśvāvasu-saṁvachchha(tsa)rē | Mārga-su(śu)dha(ddha) 5 Sômā.

Monday, 22nd November A.D. 1305; see *Ind. Ant.* Vol. XXIII. p. 119, No. 38.

H.—The Hoysālas.²

383.—Ś. 961 (?).—*Mysore Inscr.* No. 174, p. 329. Date in a Sindigere Kanarese inscription.³ The Hoysāla (Hoysala) *Mahāmaṇḍalēśvara Vinayāditya Tribhuvanamalla*, 'lord of Dvārāvatī,' and his wife *Keḷeyabbarisi (Keḷeyalādēvi)*, residing at their capital of Sosavūru(?),⁴ gave a girl in marriage to, and bestowed the lordship of Sindageṛe on, the *Daṇḍanāyaka Maṇiyāne* :—

'The Śaka year 961,⁵ the year Sarvajit, the month Phālguna, the 3rd day of the moon's increase, Monday.'

For Ś. 961 expired, which, however, was Pramāthin, the date would correspond to Monday, 16th February A.D. 1040.

(For other dates in the same inscription see below, Nos. 385 and 401).

384.—Ś. 987 (?).—*Mysore Inscr.* No. 166, p. 307. Date (in the Nirgund inscription of the time (?) of the Hoysāla Sōmēśvara, below, No. 438) of the time (?) of the W. Gaṅga *Mahāmaṇḍalēśvara Gaṅgarasa* and (?) the Hoysāla *Vishṇuvardhana* :—

'In the Śaka year 987, the year Nala, the month Pushya, the 5th day of the moon's increase, Thursday, the time of the sun's entering the northern signs.'

Nala (Anala) would be Ś. 998 expired, but for that year the date is incorrect; it is incorrect also for Ś. 987 current and expired.

385.—Ś. 1025.—*Mysore Inscr.* No. 174, p. 330. Another date in the Sindigere Kanarese inscription (above, No. 383). The Hoysāla *Ballāla I.*, reigning at his capital of Bēlāpura (Vēlāpura), married *Padmalādēvi*, *Chāvalidēvi* and *Boppadēvi*, the three daughters of the *Daṇḍanāyaka Maṇiyāne* of the second generation, on whom he again conferred the lordship of Sindageṛe :—

'The Śaka year 1025, the year Svabhānu, the month Kārttika, the 10th day of the moon's increase, Thursday.'

The date is irregular.

(For other dates in the same inscription see Nos. 383 and 401).

386.—Ś. 1037 (for 1035).—*Inscr. at Śravaṇa-Belgoḷa*, No. 46, p. 22. Sanskrit and Kanarese inscription recording the date of the death of *Būchana (Būchirāja)*, the son of the

¹ The inscription contains a sculpture of an ass and a woman.

² Compare also above, Nos. 197 and 234, and below, No. 713.

³ Compare Dr. Fleet's *Dynasties*, p. 451, note 4.

⁴ The translation has 'Soslūya.'

⁵ In the Alēśandra inscription in *Ep. Carn.* Vol. IV, p. 203, No. 32, where the same date is given, the year is '867.' Sarvajit would be Ś. 969; for that year the date is incorrect, and it is incorrect also for Ś. 967 current and expired.

⁶ Compare Dr. Fleet's *Dynasties*, p. 492, note 3.

⁷ The same date is given in the Alēśandra inscription, *Ep. Carn.* Vol. IV, p. 203, No. 32.

Danḍanāyakitī Lakkale (Lakshmi, the wife of Gaṅgarāja) and lay-disciple of Śubhachandra-siddhāntadēva; and the erection of a pillar in his memory by his mother :¹—

Śaka-varsha 1037neya Vijaya-saṁvatsarada Vaisākha-su(su)ddha 10 Ādityavārad-andu.
[Vijaya = Ś. 1035] : Sunday, 27th April A.D. 1113.

387.—Ś. 1037.—*Inscr. at Śravana-Belgoḷa*, No. 47, p. 23. Sanskrit and Kanarese inscription recording the date of the death of Mēghachandra-traividya-dēva, the disciple of Sōmadēva (Sakalachandra); and the erection of a monument in his memory by (the lay-disciple of his disciple Prabhāchandra-siddhāntadēva) the *Danḍanāyakitī* Lakshmi-mati (Lakshmi), the wife of Gaṅgarāja, minister of the Hoysala Vishṇuvardhana :—

Sa(śa)ka-varshaṁ 1037neya Maṁmatha-saṁvatsarada Mārggaśira-su(su)ddha 14 Bhīṣṇavāram Dhanur-lagnada pūrvvāhpad-āru-ghaṇiyeṣ=app-āgaḷu.

Thursday, 2nd December A.D. 1115; see *Ind. Ant.* Vol. XXIII. p. 116, No. 17.

388.—Ś. 1039.—*PSOCI.* No. 18; *Mysore Inscr.* No. 146, p. 260. Belūr Sanskrit and Kanarese plates of the Hoysala Mahāmaṇḍalēśvara Vishṇuvardhana Tribhuvanamalla, 'lord of Dvārāvati,' reigning at Vēlāpura (Bēlāpura), and his Paṭṭamahādēvi Śāntaladēvi :—

(L. 5 of side 9).—Śaka-varsha sāsirada-mūvatt-ombhatte(tta)neya Hēmaḷambi-saṁvatsarada Chaitra-suddha-pañchami-Ādivāra.

The date is irregular.

In Yādu's lineage (the legendary) Śāla received the royal name Poysala. Among the Poysalas, 'lords of Dvārāvati,' born in Śāsāpura, was Vinayāditya, who married Keḷeyabbe (Keḷyaladēvi). Their son Eṣyaṅga married Echaladēvi; their sons Ballāla [I.], Vishṇu (Vishṇuvardhana, also called Bhujabala-Gaṅga, defeated Jagaddēva² and Narasiṁha), and Udayāditya.

(Commencing with side 11 is an undated inscription of Vīra-Ballāla (Ballāla II.); and commencing with l. 21 of side 12 is a short inscription of Narasiṁha III., dated 'Sunday, the fifth day of the bright fortnight of Chaitra of the Ānanda saṁvatsara;' this date, for Ānanda = Ś. 1176, is irregular).

389.—Ś. 1039.—*Inscr. at Śravana-Belgoḷa*, No. 59, p. 56. Sanskrit and Kanarese inscription³ of the reign of the Hoysala Mahāmaṇḍalēśvara Vishṇuvardhana Tribhuvanamalla, 'lord of Dvārāvati;' recording a grant by his minister, the *Danḍanāyaka* Gaṅgarāja, which was confirmed by the *Danḍanāyaka* Eḥirāja :—

Sa(śa)ka-varshaṁ 1039neya Hēmaḷambi-saṁvatsarada Phālguna(na)-suddha 5 Sōmavārad-andu.

Monday, 28th January A.D. 1118; see *Ind. Ant.* Vol. XXIII. p. 116, No. 18.

Māra⁴ married Mākaṇabbe; their son Echaṁ (Echirāja),⁵ married Pōchikabbe; their son Gaṅgarāja (defeated the army of the [W.] Chāḷukya Chakravartin [Vikramāditya VI.] Tribhuvanamalla Permāḍidēva), married Lakshmidēvi; he was a lay-disciple of Śubhachandra-siddhāntadēva.

390.—Ś. 1042*.—*Inscr. at Śravana-Belgoḷa*, No. 49, p. 27. Sanskrit and Kanarese inscription recording the date of the death of Dēmiyyaka (Dēmati), the daughter of the *Danḍanāyakitī* Lakkale (Lakshmi, who was the mother of Būchirāja), wife of Chāmuṇḍasēṭṭi,

¹ Compare below, No. 390.

² According to Dr. Fleet perhaps an ancestor of, or identical with, the Jagaddēva in No. 287; compare also below, No. 584.

³ Identical with part of this is *Inscr. at Śravana-Belgoḷa*, No. 45, p. 20; compare also below, No. 415.

⁴ In *Inscr. at Śravana-Belgoḷa* No. 144 (below, No. 406) he is called Māramayya and described as the son of Nigavarman.

⁵ Below, No. 395, called Budhamitra.

and lay-disciple of Śubhachandra-siddhāntadēva; and the erection of a pillar in her memory by her mother :¹—

Sa(śa)ka-varusha 1042neya Vikāri-samvatsarada Phālguna(na)-bahuḷa 11 Bṛhavarārad-andu.

Thursday, 26th February A.D. 1120; see *Ind. Ant.* Vol. XXIII. p. 129, No. 99.

391.—*Inscr. at Śravaṇa-Belgoḷa*, No. 63, p. 59. Inscription recording the foundation of a temple by Lakshmi, the wife of Gaṅgarāja.

392.—*Ś. 1043**.—*Inscr. at Śravaṇa-Belgoḷa*, No. 44, p. 19. Sanskrit and Kanarese inscription recording the date of the death of Pôchikabbe (Pôchāmbike, Pôchaladēvi), and the erection of a tomb in her memory by her son Gaṅgarāja :—

Sa(śa)ka-varusha 1043neya Sâ(śâ)rvvari-samvatsarada Âshâḍha-su(śu)ddha 5 Sômarārad-andu.

The date is irregular.

393.—*Ś. 1044**.—*Inscr. at Śravaṇa-Belgoḷa*, No. 48, p. 26. Sanskrit and Kanarese inscription recording the date of the death of the *Daṇḍanāyakti* Lakṣavve (Lakshmyāmbike), the wife of Gaṅgarāja and lay-disciple of Śubhachandra-siddhāntadēva; and the erection of a monument in her memory by her husband :—

Sa(śa)ka-varusha 1044neya Plava-samvatsarada . . . śuddha 11 Śukravārad-andu.

394.—*Inscr. at Śravaṇa-Belgoḷa*, No. 64, p. 59. Kanarese inscription recording the erection of a shrine for Pôchayve by her son Gaṅgarāja.

395.—*Inscr. at Śravaṇa-Belgoḷa*, No. 65, p. 60. Inscription recording the erection, by Gaṅgarāja, the son of Budhamitra² and Pôchāmbikâ, of a shrine (for his wife Lakshmi?).

396.—*Ś. 1045*.—*Inscr. at Śravaṇa-Belgoḷa*, No. 53, p. 36. Sanskrit³ and Kanarese inscription. Date of grants made by Śāntaladēvi, the chief queen of the Hoysala *Mahāmāṇḍa-lêśvara* Viṣṇuvardhana (Bittidēva),⁴ 'lord of Dvârāvâtî :—

(P. 41).—Sa(śa)ka-varusha sâvirada-nâlvatt-ayde(yda)neya Śôbhakrit-samvatsarada Chaitra-su(śu)ddha-pâḍiva Bṛhaspativārad-andu.

The date is irregular.

(For a later date in the same inscription see below, No. 400).

397.—*Ś. 1045*.—*Inscr. at Śravaṇa-Belgoḷa*, No. 56, p. 50. Sanskrit and Kanarese inscription, recording the same grants of Śāntaladēvi, with the same date as in No. 396.

398.—*Ś. 1045*.—*Inscr. at Śravaṇa-Belgoḷa*, No. 43, p. 16. Sanskrit and Kanarese inscription recording the date of the death of Śubhachandra-siddhāntadēva, the chief disciple of Maladhâridēva; and the erection of a tomb in his memory by his lay-disciple Gaṅgarāja :—

Bâṇ-âmbhōdhi-nabhaś-śasâṅka-tuḷitê jâtê Śak-âbdê tatô varshê Śôbhakrit(d)-âhvayê vyupanatê mâsê punaś-Śrâvanê | pakshê kṛishṇa-vipaksha-varttini Sitê vârê daśamyâm tithau.

Friday, 3rd August A.D. 1123; see *Ind. Ant.* Vol. XXIII. p. 116, No. 20.

399.—*Inscr. at Śravaṇa-Belgoḷa*, No. 62, p. 59. Inscription recording the foundation of a temple by Śāntaladēvi, the chief queen of the Hoysala Viṣṇu (Viṣṇuvardhana).

¹ See above, No. 386.

² This must be another name of Êcham (Êchirāja); see above, No. 389.

³ Only the first verse and the last are in Sanskrit.

⁴ He supported 'the rise of Paṭṭi-Perumāla's own kingdom,' burnt Chakragôṭṭa, defeated Adiyama (Idigama), Narasimhavarman, etc.

400.—**Ś. 1053.**—*Inscr. at Śravaṇa-Belgoḷa*, No. 53, p. 36. Sanskrit and Kanarese inscription. Date of the death of **Śāntalādēvi**,¹ the chief queen of the Hoysala **Vishṇuvardhana**:—

(P. 38).—**Sa(śa)ka-varuṣaṁ 1050mūre(ṣa)neya Virōdhikṛit-samvatsarada Chaitra-su(śu)ddha-pañchamī Sōmavārad-andu.**

The date is irregular.

(For an earlier date in the same inscription see above, No. 396).

401.—**Ś. 1060*.**—*Mysore Inscr.* No. 174, p. 333. Sindigere Kanarese inscription. Date of the time of the Hoysala **Mahāmaṇḍalēśvara Vishṇuvardhana**, 'lord of Dvārāvati,' residing at Dōrasamudra, and of the **Danḍanāyaka Maṛiyāne** and **Bharata** (**Bharataṇa**, **Bharatamayya**):—

'In the Śaka year 1060, the year Paingala, the month Pushya, the 10th day of the moon's increase, uttarāyana-samkrānti.'

The date is irregular; see *Ind. Ant.* Vol. XXIV. p. 14, No. 185.

(For two earlier dates in the same inscription see above, Nos. 383 and 385).

402.—*Inscr. at Śravaṇa-Belgoḷa*, No. 115, p. 87. Kanarese inscription recording works of piety by the minister, the **Danḍanāyaka Bharatamayya** (**Bharata**), the younger brother of the **Danḍanātha Maṛiyāne**.²

403.—**Ś. 1061 (P).**—*Inscr. at Śravaṇa-Belgoḷa*, No. 52, p. 34. Kanarese inscription recording the erection of a monument for **Singimayya**,³ the son of the **Danḍanāyaka Baladēva** and his wife **Bāchikabbe**:—

Sa(śa)ka-varuṣa 1041 (in translation 1061)neya Siddhārthi-samvatsarada Kārttika-su(śu)ddha-dvādasa(śi) Sōmavārad-andu.

[For **Siddhārthin** = **Ś. 1061**] the date is irregular.

404.—**Ś. 1061 (P).**—*Inscr. at Śravaṇa-Belgoḷa*, No. 51, p. 33. Kanarese inscription recording the date of the death of **Baladēva**, a son of **Nāgadēva** (whose brother was **Siṅgaṇa**) and his wife **Nāgiyakka**, and grandson of the **Danḍanāyaka Baladēva**⁴ (whose wife was **Bāchikabbe**):—

Sa(śa)ka-varuṣa 1041 (in translation 1061) Siddhārthi-samvatsarada Mārggasi(śi)ra-su(śu)ddha-pādīva Sōmavārad-andu.

[For **Siddhārthin** = **Ś. 1061**] the date is irregular.

405.—*PSOCI* No. 232; *Mysore Inscr.* No. 117, p. 213. Halēbid Kanarese inscription of the Hoysala **Mahāmaṇḍalēśvara Vishṇuvardhana**,⁴ 'lord of Dvārāvati.'

In Yadu's lineage (the legendary) **Saḷa**; **Vinayāditya**; his son **Eṇyaṅga**, married **Ēchalādēvi**; their sons **Ballāḷa** [I.], **Vishṇu** and **Udayāditya**.

406.—*Inscr. at Śravaṇa-Belgoḷa*, No. 144, p. 112. Sanskrit and Kanarese inscription recording the death of the **Danḍanāyaka Ēcha** (**Ēchirāja**), the son of **Gaṅgarāja**'s⁵ elder brother **Bamma** and his wife **Bāgapabbe** (a disciple of **Bhānukīrtidēva**); the erection of a tomb for him by **Gaṅgarāja**'s eldest son, the **Danḍanāyaka Boppadēva**, as well as grants by him to **Mādhava-chandradēva**, the disciple of **Śubhachandra-siddhāntadēva**; and donations by **Ēchirāja**'s wife **Ēchikabbe**, etc.—In the introductory part the inscription first mentions the [W.] **Chālukya** [**Vikramāditya VI.**] **Tribhuvanamalla**, and then the **Poysaḷas** (**Hoysaḷas**) **Vinayāditya**, his son **Eṇyaṅga** (**Eṇga**), his son **Ballāḷa** [I.], and **Ballāḷa**'s younger brother **Vishṇuvardhana**.


¹ Her *guru* was **Prabhāchandra-siddhāntadēva**; her father, **Mārasingayya**; and her mother, **Māchikabbe** (the daughter of **Baladēva** and **Bāchikabbe**, and elder sister of **Singimayya**, **Siṅga**). Compare below, Nos. 403 and 404.

² Compare *Mysore Inscr.* p. 332 f., above, No. 401.

³ See above, note 1.

⁴ He defeated [the **Kādamba**] **Jayakēśin** [II.]. Compare above, No. 235, note.

⁵ He killed **Narasīṅga** (**Narasimha**).



407.—*Inscr. at Śravaṇa-Belgoḷa*, No. 66, p. 60. Inscription recording the foundation of a shrine by Ēchana (Boppaṇa), the son of Gaṅga[rāja].

408.—Ś. 1088*.—*Inscr. at Śravaṇa-Belgoḷa*, No. 50, p. 28. Sanskrit and Kanarese inscription¹ recording the date of the death of Prabhāchandra-siddhāntadēva, the disciple of Mēghachandra-traividyadēva and fellow-student of Mēghachandra's son Virapandin :²—

Sa(śa)ka-varshaṁ 1068neya Krōdhana-saṁvatsarada Āsvīja-su(śu)ddha-daśamī
Bṛihavārad=andū Dhanur-lagnada pūrvvāhṇad=āṣu-ghaḷigey=app=āgaḷ.

Thursday, 27th September A.D. 1145; see *Ind. Ant.* Vol. XXIII. p. 127, No. 87.

The inscription mentions Mēghachandra's fellow-student Śubhakīrti, the son of Bālachandra; and as a lay-disciple of Prabhāchandra the Hoysaḷa Viṣṇuvardhana's *Paṭṭamahādēvi* Śāntaladēvi, whose mother was Māchikabbe.

409.—Ś. 1081.—*Inscr. at Śravaṇa-Belgoḷa*, No. 138, p. 106. Sanskrit and Kanarese inscription, recording grants, etc., by the Hoysaḷa Nārasiṁha I. and his minister and senior treasurer Huḷḷapa, the son of Jakkirāja and Lōkāmḃikā, of the Vāji *vamśa* :³—

Ēkāśītyuttara-sahasra-Śaka-varshēshu gatēshu Pramādi(thi)-saṁvatsarasya Pushyamāsa-suddha-Śukravāra-chaturdaśyām=uttarāyana-saṅkrāntau.

Friday, 25th December A.D. 1159; see *Ind. Ant.* Vol. XXIII, p. 117, No. 23.

In the Hoysaḷa race, sprung from Yadu: Vinayāditya, married Kēḷiyadēvi; their son Eṇṇyaṅga (burnt Dhārā, laid waste Chakragōṭṭa), married Ēchaladēvi; their son Viṣṇu (defeated Nārasiṁhavarman, Adiyama, the lord of Mālava, Jagaddēva⁴ and Irūṅgōḷa), married Lakshmīdēvi; their son Nārasiṁha (Nārasiṁha I., surnamed Bhujabala-Vīra-Gaṅga and Pratāpa-Hoysaḷa), married Ēchaladēvi.

410.—*Inscr. at Śravaṇa-Belgoḷa*, No. 137, first part, p. 101. Kanarese inscription⁵ of the reign of the Hoysaḷa *Mahāmaṇḍalēśvara* Nārasiṁha (Nārasiṁha I.) Tribhuvanamalla, 'lord of Dvārāvati,' recording works of piety and donations by himself and his minister, the *Danḍanāyaka* Huḷḷa (Huḷḷarāja, Huḷḷapa, Huḷḷana, Puḷḷana), the son of Yaksharāja of the Vāchi *vamśa*⁶ and husband of Padmāvati.

411.—*Inscr. at Śravaṇa-Belgoḷa*, No. 80, p. 63. Kanarese inscription recording donations by Huḷḷamayya, the minister and senior treasurer of Nārasiṁha I.

412.—Ś. 1085.—*Inscr. at Śravaṇa-Belgoḷa*, No. 39, p. 7. Sanskrit and Kanarese inscription recording the date of the death of the *Mahāmaṇḍalāchārya* Dēvakīrti-panḍitadēva :—

Śaka-varsha sāsirada-emḃhatt-aidaneya || Varshē khyāta-Subhānu-nāmani sitē pakshē tad-Āshāḍhakē māsē tan-navamī-tithau Budha-yutē vārē dinēś-ōdayē.

Wednesday, 12th June A.D. 1163; see *Ind. Ant.* Vol. XXIII. p. 117, No. 24.

413.—*Inscr. at Śravaṇa-Belgoḷa*, No. 40, p. 8. Sanskrit and Kanarese inscription recording the erection of a tomb in memory of the *Mahāmaṇḍalāchārya* Dēvakīrti-panḍitadēva by the *Danḍanāyaka* Huḷḷarāja (Huḷḷapa), the son of Yaksharāja of the Vāji *vamśa* and Lōkāmḃike, and minister and senior treasurer of Nārasiṅga (Nārasiṁha I.).—The inscription mentions the temple of Rūpa-Nārāyaṇa⁷ at Kollāpura; also the *Sāmantas* Nimbādēva⁸ and Kāmādēva,⁹ who were lay-disciples of Māghanandin.

414.—Ś. 1099*.—*Inscr. at Śravaṇa-Belgoḷa*, No. 42, p. 12, and specimen Plate. Sanskrit and Kanarese inscription recording the date of the death of Huḷḷa's friend *Nayakīrtidēva*, the (son and) disciple of Guṇachandradēva, fellow-student of Guṇachandradēva's son

¹ The inscription is partly identical with No. 387.

² Compare Nos. 410 and 413.

³ The text agrees partly with the text of No. 416.

⁴ See Nos. 220 and 319.

⁵ Compare above, No. 74.

⁶ See above, No. 388.

⁷ Compare Nos. 409 and 413.

⁸ See No. 321.

Māpikyanandin, and *guru* of king Irupgōla; and the erection of a tomb in his memory by his lay-disciple, the minister Nāgadēva, the son of Bammadēva and Jōgāmbā :—

Śākē randhra-nava-dyu-chandramasi Durmmukhy-ākhyā-saṁvatsarē Vaiśākhē dhavalē chaturddasa-dinē vārē cha Sūryātma-jē | pūrvvāhṇē praharē gatē 'rddha-sahitē.

Saturday, 24th April A.D. 1176; see *Ind. Ant.* Vol. XXIII. p. 128, No. 89.

415.—*Inscr. at Śravaṇa-Belgoḷa*, No. 90, p. 71. Sanskrit and Kanarese inscription,¹ eulogizing, and recording works of piety by, Gaṅgarāja,² minister and general of the Hoysala Vishṇuvardhana, and Huḷḷayya (Huḷḷa), minister and senior treasurer of Vira-Ballāḷa (Ballāḷa II.),³ and lay-disciple of Nayakīrtidēva, the son of Guṇachandradēva.

416.—Ś. 1104*.—*Inscr. at Śravaṇa-Belgoḷa*, No. 124, p. 89. Sanskrit and Kanarese inscription,⁴ recording a grant by the Hoysala Mahāmaṇḍalēśvara Vira-Ballāḷa Tribhuvanamalla (Ballāḷa II., the son of Narasimha I. and Ēchaladēvī), 'lord of Dvārāvātī,' made at the request of his minister Chandramauli, the son of Śambhudēva and Akkavve :—

Śaka-varshada sāyirada-nūṇa-nālke(lka)neya Plava-saṁvatsarada Paushya(sha)-bahula-tadige Su(śu)kravārada-uttarāyana-saṁkrāntiy=e(a)ndu.

Friday, 25th December A.D. 1181;⁵ see *Ind. Ant.* Vol. XXIV. p. 1, No. 123.

Vira-Ballāḷa laid siege to Uchchaṅgī and captured its Pāṇḍya king Kāmadēva.⁶

417.—*Inscr. at Śravaṇa-Belgoḷa*, No. 107, p. 81. Kanarese inscription recording a grant by the Hoysala Vira-Ballāḷa (Ballāḷa II.), made at the request of Chandramauli's wife Āchaladēvī.⁷

418.—Ś. 1113(P).—*PSOCI.* No. 221; *Mysore Inscr.* No. 103, p. 196. Tālgund Kanarese inscription of the Hoysala Vira-Ballāḷa (Ballāḷa II.) :—

(L. 51).—Sa(śa)ka-varshada 1113neya Siddhārththi-saṁtsarada⁸ Chaitra-su 11 Ādivāra vyatīyapāta-saṁkramāṇad=⁹amdu.

Siddhārththi would be Ś. 1121 expired; but the date is irregular for that year, as well as for Ś. 1113 current and expired.

419.—Ś. 1114.—*Ep. Ind.* Vol. VI. p. 94; *PSOCI.* No. 98. Gadag inscription of the Hoysala Mahārājādhirāja Pratāpa-chakravartin Vira-Ballāḷa (Ballāḷa II.), 'lord of Dvārāvātī,' recording a grant made from his camp at Lokkiguṇḍi; (composed by Agnisarman) :—

(L. 43).—Śakaṇṇipakāl-ātita-saṁvatsara-satēśhu chaturddas-ādihikēshv-ēkādasaśu amkatō=pi 1114 varttamāna-Paridhāvi-saṁvatsar-āntarggata-Mārggaśirsha-paurṇamāsyām Śanaishchara-vārē sōma-grahāṇē.

Saturday, 21st November A.D. 1192; a lunar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 117, No. 26.

In the lineage of Yadu (the legendary) king Saḷa, at Śasakapura, acquired the name Hoysala; then, after other kings, Vinayāditya; his son Eṇṇyaṅga; his sons Ballāḷa [I.]

¹ Partly identical with *Inscr. at Śravaṇa-Belgoḷa*, No. 59; above, No. 389.

² He defeated the Chōla's feudatory Adiyama, the 'tigula Dāman, the feudatory Dāmōdara, Narasimhavarman and other Chōla feudatories.—Regarding Adiyama compare *Ep. Ind.* Vol. VI. p. 331, note 7.

³ He laid siege to Uchchaṅgī and took its king Kāmadēva; compare No. 416.

⁴ The text partly agrees with the text of No. 410.

⁵ On this day the *tithi* of the date commenced 0 h 30 m. after mean sunrise.

⁶ Compare Nos. 415 and 423.

⁷ A full account of her is given in *Inscr. at Śravaṇa-Belgoḷa*, No. 124 (above, No. 416) where her name is given also as Āchiyakka.

⁸ Read *Siddhārththi-saṁvatsarada Chaitra-sū*.

⁹ Read *vṛatīpāta-saṁkramāṇad*.

(defeated Jagaddêva¹), Vishṇuvardhana and Udayāditya; Vishṇuvardhana's son Narasiṃha [I.] married Êchaladêvi; their son Vîra-Ballâja (defeated the general Brahman,² and Jaitrasimha, the right arm of Bhillama³).

420.—Ś. 1114.—*PSOCI*. No. 200; *Mysore Inscr.* No. 46, p. 103. Baḷagâṃve Sanskrit and Kanarese inscription of the Hoysaḷa *Mahârâjâdhirâja Pratâpa-chakravartin Vîra-Ballâja (Ballâja II.)*, reigning at Lakkigundi:—

'Śaka 1114⁴ (in figures, l. 62), the Paridhâvi *saṃvatsara*; Friday, the fifth day of the dark fortnight of Pushya; at the time of the sun's commencing his progress to the north;' (*Mys. Inscr.*: 'the 6th day').

Friday, 25th December A.D. 1192.⁵

421.—Ś. 1114 (for 1115).—*PSOCI*. No. 224; *Mysore Inscr.* No. 109, p. 206. Sorab Kanarese memorial tablet of the time of the Hoysaḷa *Vîra-Ballâja (Ballâja II.)*:—

'Śaka 1114 (in figures, l. 5), the Pramâdi *saṃvatsara*; Sunday, the fifth day of the bright fortnight of Bhâdrapada;' (*Mys. Inscr.*: 'the Śaka year 1116,' and 'the 8th day').

Pramâdin would be Ś. 1115; but for that year the date would be irregular, for either *tithi*.

422.—Ś. 1117*.—*PSOCI*. No. 194; *Mysore Inscr.* No. 89, p. 180. Baḷagâṃve Sanskrit and Kanarese inscription of the Hoysaḷa *Vîra-Ballâja (Ballâja II.)*:—

(L. 34).—Sa(sa)kanṇipa-saṃvachchha(tsa)ram-ârabhya śatâdhika-sahasrôpari saptada-cha(śa)mê Â[na*]nda-saṃvachchha(tsa)rê Mârggaśîraḥ-âmâvâsyâyâṃ Sôṃavârê vyatîpâta-yôgâ.⁶
The date is irregular.

423.—Ś. 1118*.—*Inscr. at Śravaṇa-Belgoḷa*, No. 130, p. 97. Kanarese inscription of the reign of the Hoysaḷa *Mahâmaṇḍalêśvara Pratâpa-chakravartin Vîra-Ballâja (Ballâja II.)*, 'lord of Dvârâvatî.' Date of private donations:—

Sa(śa)ka-varsha 1118neya Râkshasa-saṃvatsarada Jêshṭha-7su 1 Brihavârad-andu.
The date is irregular.

Laying siege to Uchchangî, Vîra-Ballâja took its king Kâmadêva.⁸

424.—*PSOCI*. No. 106. Hângal Kanarese memorial tablet of the time of the Hoysaḷa *Ballâja II.* and the Kâdamba (of Hângal) *Kâmadêva*:—

'The (?) sixteenth year (in figures, l. 12) of Kâmadêva, the Nala *saṃvatsara*; Tuesday, the . . . day of the dark fortnight of Âśvayuja.'

[Nala, Anala = Ś. 1118.]

425.—*PSOCI*. No. 107. Another Hângal Kanarese memorial tablet of the time of the Kâdamba (of Hângal) *Kâmadêva*, not dated.

426.—*PSOCI*. No. 233; *Mysore Inscr.* No. 118, p. 217. Halêbbî Kanarese inscription of the Hoysaḷa *Vîra-Ballâja (Ballâja II.)*:—

'Thursday, the first day (in words, l. 7) of the bright fortnight of Kârttika of the Nala *saṃvatsara*;' (*Mys. Inscr.*: 'Sunday').

[Nala, Anala = Ś. 1118]: Thursday, 24th October A.D. 1196.

¹ Compare above, No. 388.

² See No. 294, note.

³ See No. 334.

⁴ See Dr. Fleet's *Dynasties*, p. 505, note 1.

⁵ This is the proper equivalent for the 5th *tithi*.

⁶ See *Ind. Ant.* Vol. XII. p. 210, No. 35.

⁷ This (for *Jyêshṭha*-) is the reading of the Roman and Kanarese texts; the translation has *Bhâdrapada*.

⁸ Compare above, No. 416.

⁹ See Dr. Fleet's *Dynasties*, p. 563. See also above, No. 283.

427.—*Ś. 1121.*—*PSOCI.* No. 99; *Ind. Ant.* Vol. II. p. 298, No. 5. Gadag Kanarese inscription of the Hoysala Vira-Ballāla (Ballāla II.), and his feudatory, the *Mahāmaṇḍalēśvara Rāyadēva*, 'lord of Āsatimayūrapura'.¹—

(L. 31).—*Śakanripakāḷ-ātita-saṁvatsara-śataṅgalu 1121neya Siddhārthi-saṁvatsarada pratham-Āshāḍa(ḍha)-śuklapakṣ-āṣṭamī Bṛihaspativāra-Bya(vya)tipāta-puṇya-dinadoḷ-ā Bya(vya)tipāta-nimittam.*²

Thursday, 3rd June A.D. 1199; see *Ind. Ant.* Vol. XXIII. p. 117, No. 27.

428.—*PSOCI.* No. 195, *Mysore Inscr.* No. 75, p. 162. Baḷagāmve Kanarese inscription of the 11th year of the reign³ of the Hoysala Vira-Ballāla (Ballāla II.):—

'The eleventh year (in figures, l. 4) of his reign, the Dundubhi *saṁvatsara*; Monday, the thirteenth day of the bright fortnight of Chaitra.'

[For Dundubhi = *Ś. 1124*] the date is irregular.⁴

429.—*PSOCI.* No. 196; *Mysore Inscr.* No. 59, p. 128. Baḷagāmve Kanarese memorial tablet of the time of the Hoysala Vira-Ballāla (Ballāla II.):—

'The bright fortnight of Āshāḍha of the Dundubhi *saṁvatsara*. The other details of the date are illegible.'

[Dundubhi = *Ś. 1124*]

430.—*PSOCI.* No. 197; *Mysore Inscr.* No. 65, p. 137. Baḷagāmve Kanarese memorial tablet of the 15th year of the reign of the Hoysala Vira-Ballāla (Ballāla II.):—

'The fifteenth year (in figures, l. 1) of his reign, the Krôdhana *saṁvatsara*; Monday, the eleventh day of the bright fortnight of Chaitra.'

[For Krôdhana = *Ś. 1127*] the date is irregular.⁵

431.—*PSOCI.* No. 198; *Mysore Inscr.* No. 64, p. 137. Baḷagāmve Kanarese memorial tablet of the 17th year of the reign of the Hoysala Vira-Ballāla (Ballāla II.):—

'The seventeenth year (in figures, l. 1) of his reign, the (?) Prabhava *saṁvatsara*; (?) Sunday, the (?) thirteenth day of the dark fortnight of Kārttika;' (*Mys. Inscr.*: 'the 10th day of the moon's decrease, Monday').

[For Prabhava = *Ś. 1129*] the date is irregular, with either reading.

432.—*PSOCI.* No. 199; *Mysore Inscr.* No. 97, p. 185. Baḷagāmve Kanarese memorial tablet of the 18th (or 8th ?) year of the reign of the Hoysala Vira-Ballāla (Ballāla II.).

433.—*PSOCI.* No. 235. Halēbid Kanarese inscription of the Hoysala Vira-Ballāla (Ballāla II.), and of his *Danḍandya*, the *Kumēra* or junior Lakshma (Lakshmidhara, Lakshmidēva).⁶

434.—*Ś. 1145.*—*PSOCI.* No. 123; *Mysore Inscr.* No. 20, p. 30. Harihar Sanskrit and Kanarese inscription of the Hoysala *Mahārājādhirāja* Narasimha II., 'lord of Dvārāvati,' residing at Dōrasamudra, and his minister, the *Danḍandya* Polālva, the son of Attirāja:⁷—

(L. 67).—*Śaka-varshaṁ 1145ne[ya] Svabhānu-saṁvatsarada Māgha-śuddha 11 Bṛiha-vārad-aṁdu.*

The date is irregular.

In the family of Yadu (the legendary) Saḷa; Vinayāditya; Eṇyaṅga; his sons Ballāla [I.], Bittidēva (Bittiga, Vishṇuvardhana), and Udayāditya; of these Vishṇuvardhana married Lakumadēvi (Lakshmidēvi); their son Narasimha [I.]; his son Ballāla [II.] (defeated the army of king Sōmana, i.e. the W. Chālukya Sōmēśvara IV.), married Padmaladēvi; their son Narasimha [II.], described as 'the uprooter of the Makara kingdom' and 'the establisher of the Chōla kingdom'.⁸

¹ See Dr. Fleet's *Dynasties*, p. 506.

² See Dr. Fleet's *Dynasties*, p. 503, note 4.

³ The date would be wrong also for *Ś. 1247*.

⁴ See *ibid.* p. 507.

⁵ See *Ind. Ant.* Vol. XIX. p. 155.

⁶ The date would be wrong also for *Ś. 1244*.

⁷ See Dr. Fleet's *Dynasties*, p. 506.

⁸ See below, No. 817.

435.—*Inscr. at Śravaṇa-Belgoḷa*, No. 81, p. 63. Kanarese inscription of the reign of the Hoysaḷa *Mahārājādhirāja Pratāpa-chakravartin Vira-Narasimha (Narasimha II.)*,¹ 'lord of Dvārāvātī,' recording donations by Gommaṭasetṭi:—

Khara-saṁvatsarada Pushya-śuddha uttarāyana-saṁkrānti pāḍi-diva Bri(bṛi)havārad=andu.
[Khara = Ś. 1153]: 26th December A.D. 1231; but the day was a Friday, not a Thursday.

436.—Ś. 1175*.—*Mysore Inscr.* No. 171, p. 321. Bangalore Museum Sanskrit and Kanarese plates of the Hoysaḷa *Sōmēśvara (Vira-Sōmēśvara)*, residing at Vikramapura² in the Chōḷa *maṇḍala*; recording grants made for the spiritual benefit of his *Paṭṭamahishī* (or chief queen) *Sōmaladēvi*:—

Paridhāvi(vi)-saṁvatsarasya Phālguna-māsasy=ānāvāsyaśyām sūrya-ōparāgē . . . Śaka-varsha 1175neya Paridhāvi-saṁvatsarada Phālguna-māsad=amāvāsye sūrya-grahanaḍalu.³

1st March A.D. 1253, with a solar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII, p. 130, No. 105.

437.—*Inscr. at Śravaṇa-Belgoḷa* No. 128, p. 96. Kanarese inscription of the time of the Hoysaḷa *Sōmēśvara*, the son (?) of *Vira-Ballāḷa (Ballāḷa II.)*, concerning the settlement of certain dues.

438.—*Mysore Inscr.* No. 166, p. 307. Nirgund Kanarese inscription of the time (?) of the Hoysaḷa *Vira-Sōmēśvara (Sōmēśvara)*.

(For a date in this inscription of Ś. 987(?) see above, No. 384).

439.—[Ś. 1176.]—A grant of the Hoysaḷa *Narasimha III.*, recorded at the end of the Bēlūr plates, above, No. 388.

440.—Ś. 1177.—*Coorg Inscr.* No. 6, p. 9. Niduta Kanarese memorial tablet of the time of the Hoysaḷa *Pratāpa-chakravartin Vira-Narasimha (Narasimha III.)*:—

Śaka-varusha 1177nē Rākshasa-saṁ Vaisākha-śudha(ddha) 11.

441.—*Ep. Ind.* Vol. III, p. 9. Date of a Śrīraṅgam (Raṅganātha temple) Tamiḷ inscription of the second year (of the reign) of the Poysaḷa (Hoysaḷa) *Vira-Rāmanātha*, a son of *Sōmēśvara* and the Chālukya princess *Dēvaladēvi*:—

'The day of Bharanī, which corresponded to Wednesday, the seventh *tithi* of the first half of the month of Kumbha.'

[Ś. 1178]: Wednesday, 24th January A.D. 1257.

442.—*Ep. Ind.* Vol. III, p. 10. Date of a Śrīraṅgam (Jambukēśvara temple) Tamiḷ inscription of the [7th] year (of the reign) of the Poysaḷa (Hoysaḷa) *Vira-Rāmanātha*:—

'The day of Pūrva-Phalgunī (?), which corresponded to Wednesday, the sixth *tithi* of the second half of the month of Dhanu.'

[Ś. 1183]: Wednesday, 14th December A.D. 1261; but the *nakshatra* on this day was Uttara-Phalgunī.

443.—Ś. 1184*.—*PSOCI.* No. 19; *Mysore Inscr.* No. 147, p. 270. Bēlūr Sanskrit and Kanarese plates of the Hoysaḷa *Niśāṅka-pratāpa-chakravartin Narasimha III.*, 'lord of Dvārāvātī,' residing at Dōrasamudra, and of his *Danḍanāyaka Perumāle*:—

(L. 18 of the fourth side).—Śaka-varshasya chaturadhika-sāśītīśatōttara-sahasratamasya Durmmati-saṁvatsarasya Chaitra-śuddha-dvā[da*]śyām Bhaumavārē.

Tuesday, 15th March A.D. 1261.

In the lineage of Yadu (the legendary) Saḷa, the founder of the Hoysaḷa family; in that family, Vinayāditya; his son Eṇyaṅga; his son Viṣṇu; his son Narasimha [I.]; his son Ballāḷa [II.]; his son Nṛsimha [II.]; his son Sōma, married Bijjalā; their son Nṛsimha [III.].

¹ See Dr. Fleet's *Dynasties*, p. 507, note 3.

² I.e. Kaṇṇanūr, five miles north of Śrīraṅgam.— Compare also below, Nos. 864, 865 and 904.

³ See *Ep. Ind.* Vol. III, p. 8, note 5.

⁴ See below, No. 451.

427.—**Ś. 1121.**—*PSOCI.* No. 99; *Ind. Ant.* Vol. II. p. 298, No. 5. Gadag Kanarese inscription of the Hoysala **Vira-Ballāla** (**Ballāla II.**), and his feudatory, the *Mahāmaṇḍalēśvara Rāyadēva*, 'lord of Āsaṭimayūrapura'.¹—

(L. 31).—*Śakanripakāl-ātita-saṁvatsara-śataṅgalu* 1121neya Siddhārthi-saṁvatsarada pratham-Āshāḍa(ḍha)-śuklapaksh-āṣṭamī Bṛihaspativāra-Bya(vya)tipāta-punya-dinadoḷ-ā Bya(vya)tipāta-nimittam.²

Thursday, 3rd June A.D. 1199; see *Ind. Ant.* Vol. XXIII. p. 117, No. 27.

428.—*PSOCI.* No. 195, *Mysore Inscr.* No. 75, p. 162. Baḷagāṁve Kanarese inscription of the 11th year of the reign³ of the Hoysala **Vira-Ballāla** (**Ballāla II.**):—

'The eleventh year (in figures, l. 4) of his reign, the Dundubhi *saṁvatsara*; Monday, the thirteenth day of the bright fortnight of Chaitra.'

[For Dundubhi = **Ś. 1124**] the date is irregular.⁴

429.—*PSOCI.* No. 196; *Mysore Inscr.* No. 59, p. 128. Baḷagāṁve Kanarese memorial tablet of the time of the Hoysala **Vira-Ballāla** (**Ballāla II.**):—

'The bright fortnight, of Āshāḍha of the Dundubhi *saṁvatsara*. The other details of the date are illegible.'

[Dundubhi = **Ś. 1124**]

430.—*PSOCI.* No. 197; *Mysore Inscr.* No. 65, p. 137. Baḷagāṁve Kanarese memorial tablet of the 15th year of the reign of the Hoysala **Vira-Ballāla** (**Ballāla II.**):—

'The fifteenth year (in figures, l. 1) of his reign, the Krôdhana *saṁvatsara*; Monday, the eleventh day of the bright fortnight of Chaitra.'

[For Krôdhana = **Ś. 1127**] the date is irregular.⁵

431.—*PSOCI.* No. 198; *Mysore Inscr.* No. 64, p. 137. Baḷagāṁve Kanarese memorial tablet of the 17th year of the reign of the Hoysala **Vira-Ballāla** (**Ballāla II.**):—

'The seventeenth year (in figures, l. 1) of his reign, the (?) Prabhava *saṁvatsara*; (?) Sunday, the (?) thirteenth day of the dark fortnight of Kārttika;' (*Mys. Inscr.*: 'the 10th day of the moon's decrease, Monday').

[For Prabhava = **Ś. 1129**] the date is irregular, with either reading.

432.—*PSOCI.* No. 199; *Mysore Inscr.* No. 97, p. 185. Baḷagāṁve Kanarese memorial tablet of the 18th (or 8th ?) year of the reign of the Hoysala **Vira-Ballāla** (**Ballāla II.**).

433.—*PSOCI.* No. 235. Halēbid Kanarese inscription of the Hoysala **Vira-Ballāla** (**Ballāla II.**), and of his *Daṇḍanāyaka*, the *Kumāra* or junior **Lakshma** (**Lakshmidhara**, **Lakshmidēva**).⁶

434.—**Ś. 1145.**—*PSOCI.* No. 123; *Mysore Inscr.* No. 20, p. 30. Harihar Sanskrit and Kanarese inscription of the Hoysala *Mahārājādhirāja* **Narasimha II.**, 'lord of Dvārāvati,' residing at Dōrasamudra, and his minister, the *Daṇḍanāyaka* **Polāḷva**, the son of Attirāja.⁷—

(L. 67).—*Śaka-varshaṁ* 1145ne[ya] Svabhānu-saṁvatsarada Māgha-suddha 11 Bṛiha-vārad-amḍu.

The date is irregular.

In the family of Yadu (the legendary) **Sala**; **Vinayāditya**; **Eṇeyaṅga**; his sons **Ballāla** [I.], **Biṭṭidēva** (**Biṭṭiga**, **Vishṇuvardhana**), and **Udayāditya**; of these **Vishṇuvardhana** married **Lakumadēvi** (**Lakshmidēvi**); their son **Narasimha** [I.]; his son **Ballāla** [II.] (defeated the army of king **Sōmana**, i.e. the W. Chālukya **Sōmēśvara IV.**), married **Padmaladēvi**; their son **Narasimha** [II.], described as 'the uprooter of the Makara kingdom' and 'the establisher of the Chōla kingdom'.⁸

¹ See Dr. Fleet's *Dynasties*, p. 506.

² See Dr. Fleet's *Dynasties*, p. 503, note 4.

³ The date would be wrong also for **Ś. 1124**.

⁴ See *ibid.* p. 507.

⁵ See *Ind. Ant.* Vol. XIX. p. 155.

⁶ The date would be wrong also for **Ś. 1124**.

⁷ See Dr. Fleet's *Dynasties*, p. 506.

⁸ See below, No. 817.

435.—*Inscr. at Śravaṇa-Belgoḷa*, No. 81, p. 63. Kanarese inscription of the reign of the Hoysala *Mahārājādhirāja Pratāpa-chakravartin Vira-Nārasimha (Narasimha II.)*,¹ 'lord of Dvārāvati,' recording donations by Gommatasetṭi:—

Khara-saṁvatsarada Pushya-śuddha uttarāyana-saṅkrānti pāṇi-diva Bri(bṛi)havārad-andu.
[Khara = Ś. 1153]: 26th December A.D. 1231; but the day was a Friday, not a Thursday.

436.—Ś. 1175*.—*Mysore Inscr.* No. 171, p. 321. Bangalore Museum Sanskrit and Kanarese plates of the Hoysala Sômesvara (*Vira-Sômesvara*), residing at Vikramapura² in the Chôla *maṇḍala*; recording grants made for the spiritual benefit of his *Paṭṭamahishî* (or chief queen) Sômaladêvi:—

Paridhâvi(vi)-saṁvatsarasya Phālguna-māsasy-ānāvāsyāyām sūry-ôparāgê . . . Śaka-varsha 1175neya Paridhâvi-saṁvatsarada Phālguna-māsad-amāvāsyê sūrya-grahanaḍalu.³

1st March A.D. 1253, with a solar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 130, No. 105.

437.—*Inscr. at Śravaṇa-Belgoḷa* No. 128, p. 96. Kanarese inscription of the time of the Hoysala Sômesvara, the son (?) of Vira-Ballāla (Ballāla II.), concerning the settlement of certain dues.

438.—*Mysore Inscr.* No. 166, p. 307. Nîrgund Kanarese inscription of the time (?) of the Hoysala *Vira-Sômesvara (Sômesvara)*.

(For a date in this inscription of Ś. 987(?) see above, No. 384).

439.—[Ś. 1176.]—A grant of the Hoysala *Narasimha III.*, recorded at the end of the Bêlûr plates, above, No. 388.

440.—Ś. 1177.—*Coorg Inscr.* No. 6, p. 9. Niduta Kanarese memorial tablet of the time of the Hoysala *Pratāpa-chakravartin Vira-Narasimha (Narasimha III.)*:—

Śaka-varusha 1177nê Rākshasa-saṁ Vaisākha-śudha(ddha) 11.

441.—*Ep. Ind.* Vol. III. p. 9. Date of a Śrīraṅgam (Raṅganātha temple) Tamîl inscription of the second year (of the reign) of the Poysala (Hoysala) *Vira-Rāmanātha*, a son of Sômesvara and the Chālukya princess Dêvaladêvi:—

'The day of Bharanî, which corresponded to Wednesday, the seventh *tithi* of the first half of the month of Kumbha.'

[Ś. 1178]: Wednesday, 24th January A.D. 1257.

442.—*Ep. Ind.* Vol. III. p. 10. Date of a Śrīraṅgam (Jambukêśvara temple) Tamîl inscription of the [7th] year (of the reign) of the Poysala (Hoysala) *Vira-Rāmanātha*:—

'The day of Pûrva-Phalguni (?), which corresponded to Wednesday, the sixth *tithi* of the second half of the month of Dhanus.'

[Ś. 1183]: Wednesday, 14th December A.D. 1261; but the *nakshatra* on this day was Uttara-Phalgunî.

443.—Ś. 1184*.—*PSOCI.* No. 19; *Mysore Inscr.* No. 147, p. 270. Bêlûr Sanskrit and Kanarese plates of the Hoysala *Niśāṅka-pratāpa-chakravartin Narasimha III.*, 'lord of Dvārāvati,' residing at Dôrasamudra, and of his *Daṇḍanāyaka Perumāle*:—

(L. 18 of the fourth side).—Śaka-varshasya chaturadhika-sâstīsatôttara-sahasratamasya Durmmati-saṁvatsarasya Chaitra-śuddha-dvâ[da*]śyām Bhaumavârê.

Tuesday, 15th March A.D. 1261.

In the lineage of Yadu (the legendary) Sâla, the founder of the Hoysala family; in that family, Vinayāditya; his son Eṇṇayāṅga; his son Vishṇu; his son *Narasimha* [I.]; his son *Ballāla* [II.]; his son *Nṛsimha* [II.]; his son Sôma, married Bijjalâ; their son *Nṛsimha* [III.].

¹ See Dr. Fleet's *Dynasties*, p. 507, note 3.

² I. s. Kappanûr, five miles north of Śrīraṅgam.— Compare also below, Nos. 864, 865 and 904.

³ See *Ep. Ind.* Vol. III. p. 8, note 5.

⁴ See below, No. 451.

444.—**Ś. 1190.**—*PSOCI.* No. 124; *Mysore Inscr.* No. 27, p. 48. Harihar Sanskrit and Kanarese inscription of the (?) Hoysala **Narasimha III.**, and of his *Danḍanāyaka Sôma* :—

Mys. Inscr. : 'The Śaka year 1190 having passed, and the year Vibhava being current.'

445.—*Ep. Ind.* Vol. III. p. 10. Date of a Śrīraṅgam (Raṅganātha temple) Tamil inscription of the 15th year (of the reign) of the Hoysala **Vira-Rāmanātha** :—

'The day of Aśvinī, which corresponded to Monday, the first *tithi* of the first half of the month of Mīna.'

[**Ś. 1191**] : Monday, 24th March A.D. 1270.

446.—**Ś. 1191** (for 1195 ?).—*Inscr. at Śrāvāṇa-Belgoḷa*, No. 96, p. 74. Kanarese inscription of the time of the Hoysala *Pratāpa-chakravartin* **Vira-Nārasimha** (**Narasimha III.**), reigning at Dōrasamudra :—

Śaka-varuṣa 1191neya Śrīmukha-saṁvatsarada Śrāvāṇa-suddha 15 Ādivāradallu.

Śrīmukha would be Ś. 1195, and in that year the *tithi* of the date commenced 6 h. 14 m. after mean sunrise of Sunday, 30th July A.D. 1273.

The inscription records a grant to Chandraprabhadēva, the disciple of the *Mahā-maṇḍalāchārya* Nayakīrtidēva.

447.—**Ś. 1192*** [and **Ś. 1198**].—*Ep. Carn.* Vol. III. p. 166, No. 97; *Mysore Inscr.* No. 172, No. 323. Sōmanāthapura Sanskrit and Kanarese inscription of the Hoysala *Mahārājādhirāja Pratāpa-chakravartin* **Vira-Nārasimha** (**Narasimha III.**), 'lord of Dvārāvati,' residing at Dōrasamudra; and of his minister, the *Danḍanāyaka Sôma*,¹ and Sôma's sister's sons, the *Danḍanāyakas* **Mallidēva** and **Chikka-Kētaya** :—

Śaka-varuṣa sāsirada-nūṇa-tombhatt-erāḍaneya Śukla-saṁvatsarada Āshāḍha-suddha-dvādasi(śi) Budhavārad=andū.

Wednesday, 12th June A.D. 1269;² see *Ind. Ant.* Vol. XXIV. p. 3, No. 132.

The inscription contains another date—

Dhātu-saṁvatsarada Āśvīja-suddha-tadige Ādivārad=andū.

This date, for Dhātṛi = Ś. 1198, is irregular.

448.—*Ep. Ind.* Vol. III. p. 10. Date of a Śrīraṅgam (Raṅganātha temple) Tamil inscription of the 15th year (of the reign) of the Hoysala (**Hoysala**) **Vira-Rāmanātha** :—

'The day of Bharanī, which corresponded to Sunday, the eleventh *tithi* of the second half of the month of Mithuna.'

[**Ś. 1192**] : Sunday, 15th June A.D. 1270.

449.—*Ep. Ind.* Vol. III. p. 10. Date of a Kappanūr (Poysalēśvara temple) Tamil inscription of the 17th year (of the reign) of the Hoysala (**Hoysala**) **Vira-Rāmanātha** :—

'Tuesday, the thirteenth *tithi* of the bright half of Śrāvāṇa in the Prajāpati year, which corresponded to the twenty-fourth solar day of the month of Āḍi.'

[**Prajāpati** = **Ś. 1193**] : Tuesday, 21st July A.D. 1271.

450.—**Ś. 1200.**—*PSOCI.* No. 20; *Mysore Inscr.* No. 148, p. 275. Bēlūr Sanskrit and Kanarese plates of the Hoysala *Niṣṭāṅka-pratāpa-chakravartin* **Narasimha III.**, 'lord of Dvārāvati,' residing at Dōrasamudra :—

(L. 41).—Śaka-varuṣasya dvīṣatōttara-sahasratamasya Bahudhānya-saṁvatsarasya Māgha-kṛishṇa-chaturdaśyām Maṁdavārē.

Saturday, 11th February A.D. 1279.

¹ He is described as the king's dear son.

² On this day the *tithi* of the date commenced 2 h. 25 m. after mean sunrise.

451.—Ś. 1208.—*PSOCI.* No. 148; *Mysore Inscr.* No. 6, p. 11. Chitaldurg Kanarese inscription of the Hoysala *Pratāpa-chakravartin* Narasimha III., residing at Dōrasamudra, and of his minister, the *Danḍandāyaka* Perumāledēva¹ (also called Rānttarāya and Javanike-Nārāyaṇa):—

(L. 14).—Śaka-varusha 1208 sâ(sa)m̐da varttamāna-Bya(vya)ya-sam̐ Chayatra-²śu 10 Bri(bri)d-aṁdu.

Thursday, 7th March A.D. 1286.

452.—*Coorg Inscr.* No. 7, p. 10. Niduta Kanarese memorial tablet of the time of the Hoysala *Pratāpa-chakravartin* Vira-Narasimha (Narasimha III.).³

453.—*PSOCI.* No. 147; *Mysore Inscr.* No. 3, p. 6. Chitaldurg Kanarese inscription of the Hoysala *Mahārājādhirāja* Ballāla III., the son of Narasimha III. who was the son of Sōmāśvara, residing at Dōrasamudra:—

(L. 33).—⁴Sādhāraṇa-samvatsarada Vaiśākha-su(śu) 3 Su(śu).⁵

[Sādhāraṇa = Ś. 1232]: Friday, 3rd April A.D. 1310.

I.—The Dynasties of Vijayanagara.⁶

454.—Ś. 1261 (for 1262).—*Ind. Ant.* Vol. X. p. 63. Bādāmi Kanarese inscription of the *Mahāmaṇḍalēśvara* Vira-Hariyappa-Voḍeyar (Harihara I.), and of Chāmeya-Nāyaka (Chāmarāja⁷):—

(L. 1).—Śaka-varusha 1261neya Vikrama-samvatsarada Chaitra-su(śu) 1 Gu.

Probably Thursday, 9th March A.D. 1340; but the *tithi* which ended on this day was the 10th, not the first *tithi* of the bright half of Chaitra; see *ibid.* Vol. XXIV. p. 16, No. 196.

455.—Ś. 1276*.—*Jour. Bo. As. Soc.* Vol. XII. p. 346; *PSOCI.* No. 22; *Mysore Inscr.* No. 131, p. 234. Harihar Sanskrit and Kanarese plates of the *Mahārājādhirāja* Bukkarāja (Bukkarāya) I., the son of Saṁgama I.:—

(L. 20).—nripa-Śālivāhana-Śaka 1276neya Vijaya-samvatsarada Māgha-śudha(ddha) 15 Chandravāra sōmōparāma(ga)-parvvaṇi vu(u)shpakāladallu.

The date is irregular; see *Ind. Ant.* Vol. XXIV. p. 17, No. 197.

456.—Ś. 1277.—*PSOCI.* No. 149; *Mysore Inscr.* No. 1, p. 2. Chitaldurg Kanarese inscription of the reign of the *Mahāmaṇḍalēśvara* Vira-Bukkarāja-Voḍeyar (Bukkarāja I.), residing at Hosapatṭana; recording a grant by the *Mahāmaṇḍalēśvara* Mallinātha-Voḍeyar:—

(L. 13).—Sa(śa)ka-varusha 1277neya Manumatha-samvachchōha(tsa)rada Jēshṭha-(j)ēshṭha)-śudhdha(ddha) 7 Sō.

Monday, 18th May A.D. 1355;⁸ see *Ind. Ant.* Vol. XXIV. p. 3, No. 134.

457.—Ś. 1278.—*PSOCI.* No. 150; *Mysore Inscr.* No. 2, p. 4. Chitaldurg Kanarese inscription of the reign of the *Mahāmaṇḍalēśvara* Vira-Bukkarāja-Voḍeyar (Bukkarāja I.), residing at Hosapatṭana; recording a grant by the *Mahāmaṇḍalēśvara* Mallinātha-Voḍeyar:—

(L. 17).—Sa(śa)kha(ka)-varusha 1278neya Durmmukha-samvatsarada Āshāḍha-bahula-tadige Guruvāradalu.

Thursday, 16th June A.D. 1356.

¹ He slew (a king) Ratnapāla; see Dr. Fleet's *Dynasties*, p. 509.—Compare above, No. 443.

² Read *Chaitra*.

³ The given date is valueless.

⁴ The Śaka year is effaced.

⁵ I.e. *Śukravādra*.

⁶ First dynasty, Nos. 454-500; second dynasty, Nos. 502-534; third dynasty, No. 535 ff.

⁷ For another Chāmarāja see below, No. 488.

⁸ Bukka I. had a son whose name was also Mallinātha (Mallapp-Ōḍeyar); compare *Ep. Ind.* Vol. VI. p. 327, and *Ind. Ant.* Vol. XXVI. p. 381, No. 10.

⁹ On this day the *tithi* of the date commenced 3 h. 53 m. after mean sunrise.

458.—*South-Ind. Inscr.* Vol. I. No. 154, p. 167. Rock inscription at the fort of Gutti, of the time of king Bukka (perhaps Bukkarāya I.).

459.—*Ś. 1273.*—*Ep. Ind.* Vol. III. p. 24, and Plates. Biṭraguṇṭa¹ plates of Saṅgama II. (the verses were written on the plates by Bhōganātha,² the *narma-sachiva* of Saṅgama II.):—

(L. 75).—Śāk-ābdē nāga-sāila-dhyu(dyū)maṇi-parimitē 1273 Durmukh-ābdē tru(tri)-tiyyē(yē) māsi saṅgamē chaṁdra-bā(bhā)nvēḥ.

Saṅgama [I.] had five sons: Harihara [I.], Kampa (Kampaṇa I.), Bukka [I.], Mārāpa, and Muddapa; Kampa's son Saṅgama [II.].

460.—*Ś. 1286* (for 1287).—*South-Ind. Inscr.* Vol. I. Nos. 86 and 87, pp. 118 and 121. Two Conjeeveram Tamil pillar inscriptions of the reign of the *Mahāmaṇḍalēśvara Vira-Kampaṇa-Uḍaiyar* (i.e. Kampaṇa II.³):—

'From the month of Āḍi of the Viśvāvasu⁴ year, which was current after the Śaka year one thousand two hundred and eighty-six.'

461.—*Ś. 1290.*—*Ind. Ant.* Vol. XIV. p. 233; *Inscr. at Śravaṇa-Belgoḷa*, No. 136, p. 100. Kanarese inscription, containing what is known as Rāmānujāchārya's *Śāsana*, of the time (?) of the *Mahāmaṇḍalēśvara Vira-Bukkarāya* (Bukkarāya I.):—

Inscr. at Śr.-Belg.: Śaka-varsha 1290neya Kilaka-saṁvatsarada Bhādrapada-śu 10 Bṛi. Thursday, 24th August A.D. 1368.

462.—*South-Ind. Inscr.* Vol. I. No. 88, p. 124. Conjeeveram Tamil inscription of the reign of *Vira-Kampaṇa-Uḍaiyar* (i.e. Kampaṇa II.):⁵—

'On the day of Tēr (i.e. Rōhiṇī), which corresponds to Tuesday, the seventh lunar day of the latter half of the month of Makara of the Kilaka year, which was current (during the reign) of Vira-Kampaṇa-Uḍaiyar.'

[For Kilaka = *Ś. 1290*] the date is irregular; see *Ind. Ant.* Vol. XXII. p. 138, No. 9.

463.—*Ś. 1293.*—*Ep. Ind.* Vol. VI. p. 330. Śrīraṅgam (Raṅganātha temple) inscription of Goppaṇārya (Gōpaṇa), (an officer of Kampaṇa-Uḍaiyar, i.e. Kampaṇa II., the son of Vira-Bokkapa-Uḍaiyar, i.e. Bukkarāya I.):—

(L. 1).—bandhu-priyē Śāk-ābdē.

464.—*Ś. 1296.*—*South-Ind. Inscr.* Vol. I. No. 72, p. 103. Tirumalai Tamil inscription of the reign of the *Mahāmaṇḍalika Ommaṇa-Uḍaiyar*, the son of Vira-Kampaṇa-Uḍaiyar (alias) Kumāra-Kampaṇa-Uḍaiyar (i.e. Kampaṇa II.):⁶—

'On the day of Uttirattādi (i.e. Uttara-Bhādrapadā), which corresponds to Monday, the eighth lunar day of the former half of the month of Dhanus of the Ānanda year, which was current after the Śaka year 1296.'

Monday, 11th December A.D. 1374;⁷ see *Ind. Ant.* Vol. XXIV. p. 3, No. 135.

465.—*Ś. 1301.*—*Jour. Bo. As. Soc.* Vol. XII. p. 352. Pambal plates⁸ of the *Rājādhirāja Virapratāpa Harihara* (Harihara II.), residing at Vijayanagara:¹⁰—

(L. 100).—Śāk-ābdē Śālivāhasya sahasrēpa tribhiḥ śataih | ēk-ādhikāś=cha gaṇitē Siddhārthē=bdē śubhē dinē || Jyē(jyai)shṭhyān Bhaumē niśānāth-ōparāgē.

¹ This is the name of the village granted; the plates are at Nellore. They are marked with numeral figures, and also with notches.

² Probably identical with Bhōganātha, the brother of Mādhava and Sāyana.

³ The son of Bukkarāya I.; see *Ep. Ind.* Vol. VI. p. 324. For a list of inscriptions of Kampaṇa II. see *ibid.* p. 325 ff.

⁴ The second inscription has *Vīsvādi* instead.

⁵ See above, No. 460.

⁶ See *Ep. Ind.* Vol. VI. p. 325, and above, Nos. 460 and 462.

⁷ On this day the *śikhi* of the date commenced 3 h. 41 m. after mean sunrise.

⁸ Some of the (nine) plates are numbered.

⁹ This title occurs in a verse.

¹⁰ The inscription is remarkable for the large number of villages mentioned in it.—For a list of inscriptions of Harihara II. see *Ep. Ind.* Vol. VI. p. 327 f.

Tuesday, 31st May A.D. 1379; a lunar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 119, No. 39.

In Yadu's race, Saṅgama [I.]; his sons Harihara [I.] and Bukka [I.]; Bukka's son Harihara [II.].

466.—Ś. 1301.—*PSOCI.* No. 126; *Mysore Inscr.* No. 29, p. 55. Harihar Sanskrit and Kanarese inscription of the reign of Harihara II., residing at Vijayanagara; recording a grant by the *Danḍandya Mudda* :—

(L. 39).—Śaṣi-kha-sikhi-chandra-samitē Śākē Sidhdhā(ddhā)rtthi(rttthi)-samjñitē oh-ābdē [I*] Kārttika-māsasya sita-dvādaśyām Bhāskarē vārē [I*]

Sunday, 23rd October A.D. 1379; see *Ind. Ant.* Vol. XXIII. p. 119, No. 40.

Genealogy of Harihara II. as in No. 465.

467.—Ś. 1304.—*PSOCI.* No. 23; *Mysore Inscr.* No. 146, p. 267. Bêlūr Sanskrit and Kanarese plates of Harihara II. and his *Danḍandya Mudda* :—

(L. 41).—Śaka-varsha sāvirada-mūnūṇa-nāka(lka)neya Duṁdubhi-saṁvatsarada Kārttika-bahula-daśami Ādivāradali.

The date is irregular.

468.—Ś. 1305 (for 1306).—*Ep. Ind.* Vol. III. p. 226, and Plate. Ālampūṇḍi plate of Virūpāksha I.,² the son of Harihara II., recording a grant made at the request of Harihara's sister (?) Jannāmbikā :—

(L. 13).—Śakavarsha-sahasr-ādhi-paṅchōttara-śata-trayē | Raktākshī(kshi)-Pushya-saṁkrāntau pupya-kālē śubhē dinē.

In the race of the Moon, Bukkarāja [I.], the son of Saṅgama [I.] and Kāmākshī; his son Harihara [II.], married Mallādēvī of the family of Rāmadēva;³ their son Virūpāksha [I.].

469.—Ś. 1307.—*South-Ind. Inscr.* Vol. I. No. 152, p. 156. Vijayanagara lamp-pillar inscription of the time of Harihara II. (the son of Bukka I. of the Yādava race), recording the building of a Jaina temple by the *Danḍēsa Iruga (Irugapa)*,⁴ the son of Harihara's minister, the *Danḍanātha Baicha (Baichapa)*;⁵—

(L. 36).—Śaka-varshē 1307 pravarttamānē Krōdhana-vatsarē Phālguna-māsē kṛishṇa-pakshē dvitīyāyām tithau Śukravārē.

Friday, 16th February A.D. 1386; see *Ind. Ant.* Vol. XXIII. p. 126, No. 77.

470.—Ś. 1309*.—*Ep. Ind.* Vol. III. p. 117. Date of the Bhatka Kanarese plates of the *Mahārājādhirāja Vira-Harihara (Harihara II.)* and his dependent *Mallāna-Oḍeyar*, who resided at Honnāvura (Honavar) :—

(L. 7).—[Śa]ka-varusha sāvirada-munūṇa-om̐bhattaneya Kshaya-[saṁ]va[t*]sarada Simhāda Guru Pushya-[bahu]la-paṁchami Guruvārada[lu].

Thursday, 10th January A.D. 1387; see *Ind. Ant.* Vol. XXV. p. 270.

471.—Ś. 1313.—*Jour. Bo. As. Soc.* Vol. IV. p. 115. Plates of the reign of Harihara II., recording a grant by the minister *Mādhavarāja* :—

Śākē trayōdaśdhika-trisatōttara-sahasrē gatē vartamāna-Prajāpati-saṁvatsarē Vaisākha-māsē kṛishṇa-pakshē amāvāsyāyām Saumya-dinē sūryōparāga-puṇyakālē.

Wednesday, 5th April A.D. 1391;⁶ a solar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 122, No. 57, and Vol. XXV. p. 271.

¹ Compare No. 466.

² For a list of inscriptions of his see *Ep. Ind.* Vol. VI. p. 328 f.

³ I.e., probably, the Dēvagiri-Yādava Rāmachandra (Rāmadēva); see above, No. 369 ff.

⁴ He is the author of the *Nandriharatnamālā*.—Compare below, No. 466 and under *Addenda*.

⁵ Compare below, No. 486.

⁶ But this day fell in the *amānta* month Chaitra

472.—Ś. 1315.—*Ep. Ind.* Vol. III. p. 229. Conjeeveram inscription of Harihara II. :—
(L. 1).—Śaktyâlôkê Śak-âbdê pariṇama[ti] śubhê Śrī(śrī)mukh-Âshâ[ḍha]-mâsê śuddhê pakshê daśamyâm Ravisuta-divasê Mitra-bhê.

The date is irregular; see *Ind. Ant.* Vol. XXIV. p. 211, note 65.

473.—Ś. 1317.—*PSOCI* No. 24; *Mysore Inscr.* No. 149, p. 277. Hasan Sanskrit and Kanarese plates of Harihara II. :—

(L. 36).—Śak-âvda(bda) rishi-chamdr-âshni(gni)-vidhun-âyata-vatsarê | Yuv-âkhyê Mâgha(?) -mâsê(?) cha śukla-pakshê śubh[ê*] dinê | saptamyâm cha mahâ-parvati.¹

474.—Ś. 1317 (for 1318).—*As. Res.* Vol. IX. p. 420; Colebrooke's *Misc. Essays*, Vol. II. p. 262. Chitradurg (Chitaldurg) Sanskrit and Kanarese plates of Harihara II. :—

Rishi-bhû-vahni-chandrê tu gapitê Dhât[ri]-vatsarê | Mâgha-mâsê śukla-pakshê paurṇamâsyâm mahâtithau || nakshatrê pitri-daivatye Bhânuvârêpa samyutê |

Sunday, 14th January A.D. 1307; but the *tithi* which ended on this day was the first *tithi* of the dark half, not the full-moon *tithi*; see *Ind. Ant.* Vol. XXIV. p. 7, No. 149.

In Yadu's family, Saṅgama [I.]; had five sons, Harihara [I.], Kampa [I.], Bukkarâya [I.], Mârâpa, and Mudgapa.² Bukkarâya made Vidyânagarî his capital, and married Gaurâmbikâ; their son Harihara [II.].

475.—Ś. 1321.—*Ep. Ind.* Vol. III. p. 120. Nallûr³ plates of Virapratâpa Harihara (Harihara II.), residing at Vijayanagara; (the verses were composed by Mallanârâdhyavṛttika, the son of Kôṭṭisârâdhyâ⁴) :—

(L. 50).—Dhâtri-nêtra-guṇa-kshapêta(śva)ra-yutê śrī(śrī)-Sâlivâhê gatê [Śâkhê(kê) gô]-tradhacha (?) Pramâdi(thi)ni tidhau (?) mâsy=Ūrakê nâmanî (?) | pakshê tatra vaḷakshakê Budha-dinê śrī-paurṇimâsyâm tidhau(thau) | kâlê pu[nyâ]ma[ham]tarê śubha-karê sômôparâgê varê |

Wednesday, 15th October A.D. 1399; a lunar eclipse, visible in India.

In the race of the Yādavas, Saṅgama [I.]; his son Vîra-Bhukka or Bhukka (Bukka I.), married Gaurî; their son Harihara [II.].

476.—*PSOCI* No. 238; *Mysore Inscr.* No. 125, p. 222. Bêlûr Kanarese inscription of Harihara II. and his Daṇḍanâtha Guṇḍa.⁵

477.—*PSOCI* No. 239; *Mysore Inscr.* No. 128, p. 226. Bêlûr Sanskrit and Kanarese unfinished inscription of Harihara II. and his Daṇḍanâtha Guṇḍa.

478.—*Inscr. at Śravaṇa-Belgoḷa*, No. 126, p. 95. Kanarese inscription recording the date of the death of Harihararâya :⁶—

(L. 1).—Târâpa-samvatsarâda Bhâdrapada-bahuḷa-daśamiyû Sôma-vâradalu.

The date is irregular for both Târâpa = Ś. 1266 and Târâpa = Ś. 1326.⁷

479.—Ś. 1328 [and 1327].—*South-Ind. Inscr.* Vol. I. No. 55, p. 80. Vêppambattu (nera Vêlûr) Tamiḷ inscription recording a sale (which took place on the first date here given) concerning two villages that were granted (on the second date here given) by the Mahârâjâdhîrâja Virapratâpa Bukkamahârâya (Bukkarâya II.) :⁸—

First date: 'On Thursday, the new-moon day of the dark half of Jyâishṭha of the Vyaya year, which follows the Pârthiva year (and) which was current after the Śaka year 132[8].'

¹ See *Ind. Ant.* Vol. XII. p. 213, No. 70.

² Really Muddapa; see above, No. 459.

³ This is the name of the village granted. The grant was edited from Sir W. Elliot's impressions. The plates are numbered with numeral figures.

⁴ Compare below, No. 517.

⁵ Compare below, No. 501.

⁶ I.e. according to Mr. Rice, Harihara II.

⁷ For Ś. 1326 the date would correspond to Saturday, 30th August A.D. 1404.

⁸ A son of Harihara II.; see *Ep. Ind.* Vol. III. p. 36, note 3.—For a list of inscriptions of his see *ibid.* Vol. VI. p. 329 f.

Second date : 'Thursday, the twelfth lunar day of the bright half of Vaiśākha (of) the Pārthiva year.'

Both dates (the first for Vyaya = Ś. 1328, and the second for Pārthiva = Ś. 1327) are irregular ; see *Ind. Ant.* Vol. XXIV. p. 203, note 50.

480.—Ś. 1328.—*PSOCL.* No. 25 ; *Mysore Inscr.* No. 150, p. 279. Hāsan Sanskrit and Kanarese plates of the *Mahārājādhirāja Virapratāpa Dēvarāya (Dēvarāya I.)*, giving the date of his coronation :—

(L. 21).—Sa(śa)ka-varsh[ē] 132[8] varttamāna-Vya[ya]-samvatsarē Kārttī[rti]kamāsa-[krishṇa]pakshē daśamyām Ś[u]k[r]avārē [Uttarā(?)]-Bhādrapadē Prīti-yōgē Bava-karaṇē ēvañ-vi[śi*]shṭa-śubha-kālē . . . svasya paṭṭābhishēka-samayē.

Friday, 5th November A.D. 1406 ; but the *nakshatra*¹ was Uttara-Phalgunī, not Uttara-Bhādrapadā, and the *karaṇa* Bava only commenced after the expiration of the 10th *tithi* ; see *Ind. Ant.* Vol. XXIV. p. 204, note 51 (where it should have been stated that the *yōga* Prīti commenced 14 h. 3 m. after mean sunrise).

Saṅgama [I.] ; his son Bukkarāya [I.] ; his son Harihara [II.] ; his son Dēvarāya [I.]

481.—Ś. 1332.—*PSOCL.* No. 127 ; *Mysore Inscr.* No. 18, p. 26. Harihar Sanskrit and Kanarese inscription of *Dēvarāya I.* :—

(L. 15).—Śākē nētr-āgni-vahn-īndu-saṁkhyē Vikra(kṛi)ti-nāmakē varushē² Nabhasya-dvādaśyām śuklāyām Sōmavārakē.³

Monday, 11th August A.D. 1410 ;⁴ see *Ind. Ant.* Vol. XXIII. p. 119, No. 41.

482.—*As. Res.* Vol. XX. p. 31. Translation of a Vijayanagara Kanarese inscription of *Dēvarāya I.* and his minister *Lakshmaṇa (?)*.

483.—Ś. 1334*.—*PSOCL.* No. 151 ; *Mysore Inscr.* No. 5, p. 9. Chitaldurg Kanarese inscription of the *Mahāmaṇḍalēśvara Vira-Mallanna-Voḍeyar* (a son of *Virapratāpa Dēvarāya I.*) recording grants for the spiritual merit of his mother *Mallayavve* :—

(L. 4).—Sa(śa)ka-varusa(sha) 1334meva Khara-samvatsarada Kārttika-su(śu) 15 Śa.⁵

Saturday, 31st October A.D. 1411.

484.—Ś. 1338.—*Prāchīnalēkhamālā*, Vol. I. p. 178.⁶ Vandavāsi Sanskrit and Kanarese plates of the *Mahāmaṇḍalēśvara Virapratāpa Vijayarāya (Vira-Vijaya)*, a son of *Dēvarāya I.* :—

Śaka-varsha 1338 vartamāna-Durmukhi-samvatsarada Bhādrapada-bauḷa-saptamiyalu.

In the lineage of Yadu, Saṅgama [I.] ; his son Bukka [I.] ; his son, from Gaurāmbikā, Harihara [II.] ; his son Pratāpa-Dēvarāya (Dēvarāya I.) ; his son, from Hēmāmbikā, Vira-Vijaya (Vijaya).

485.—Ś. 1344.—*PSOCL.* No. 206 ; *Mysore Inscr.* No. 49, p. 112. Baḷagāṁve much damaged Kanarese memorial tablet of the time of *Vira-Vijaya (?)*, a son of *Virapratāpa Dēvarāya I.* :—

Mysore Inscr. : 'In the Śaka year 1344, the year Subhakṛit, the month Aśvija, the 5th day of the moon's increase, Sunday.'

Sunday, 20th September A.D. 1422.⁷

¹ For dates in which similar mistakes occur see below, Nos. 604 and 853.

² Read *varshē*.

³ See *Ind. Ant.* Vol. XII. p. 214, No. 88.

⁴ This date fell in the first Bhādrapada of Ś. 1332.

⁵ This *akṣara* is quite clear.

⁶ Taken from the *Madras Jour. Lit. Sc.* 1881, p. 249.

⁷ On this day the *tithi* of the date commenced 5 h. 57 m. after mean sunrise.

486.—*Inscr. at Śravaṇa-Belgoḷa*, No. 82, p. 63. Inscription recording donations by the *Danḍanātha Irugapa*, the son of Maṅgapa who was the youngest son of Bukkarāya's minister Baicha (Baichapa):—

Śubhakṛiti vatsarē jayati Kārttika-māsi tithau Muramathanasya puṣṭim upajagmushi śītaruchau.

[Śubhakṛit = Ś. 1344.]¹

Baicha (Baichapa) had three sons, Irugapa, Bukkaṇa, and Maṅgapa; Maṅgapa's sons were Baichapa and Irugapa.²

487.—Ś. 1346.—*Ep. Ind.* Vol. III, p. 37, and Plate. Satyamaṅgalam plates of Dēvarāya II., reigning at Vijayanagara:—

(L. 40).—Tat[ti*]valōkē Śakasy-ābdē Krōdhi-samvatsarē śubhē | Āśāḍh-āmātithau puṇyē³ Sōmavāra-virājītē |

Monday, 26th June A.D. 1424;⁴ (with a solar eclipse, *not* visible in India).

In the lineage of Yadu, Saṅgama [I.]; his son Bukka [I.]; his son, from Gauri, Harihara [II.]; his son, from Malāmbikā, Pratāpa-Dēvarāya (Dēvarāya I.); his son, from Hēmaṁbikā, Vīra-Vijaya; his son, from Nārayaṇāmbikā, Dēvarāya [II.]; he had a younger brother, named Pratāpa-Dēvarāya.⁵

488.—Ś. 1348.—*PSOCI.* No. 128, *Mysore Inscr.* No. 23, p. 39. Harihar Kanarese inscription of the time (?) of Virapratāpa Dēvarāya (Dēvarāya II.), and of (the *Danḍanātha*) Chāmarāja:⁶—

(L. 16).—Śaka-varuṣa 1346neya Krōdhi-samvachchha(tsa)rada Kārttika-suddha 12 Sōmavāraṁ kṛdida puṇya-tithiyōḷu.

The date is irregular.

489.—Ś. 1347.—*South-Ind. Inscr.* Vol. I. No. 56, p. 83. Viriñchipuram Tamil inscription of the reign of the *Mahārājādhirāja Virapratāpa Dēvarāya (Dēvarāya II.)*:—

'On the day of Anusham (*i.e.* Anurādhā), which corresponds to Wednesday, the sixth lunar day, the 3rd (solar day) of the month of Paṅguni of the Viśvāvasu year, which was current after the Śaka year 1347.'

Wednesday, 27th February A.D. 1426; see *Ind. Ant.* Vol. XXIII. p. 132, No. 113.

490.—Ś. 1348.—*South-Ind. Inscr.* Vol. I. No. 153, p. 162. Vijayanagara Jaina inscription of Dēvarāja II., residing at Vijayanagara:—

(L. 25).—Śākē-bdē pramītē yātē vasu-simḍhu-guṇ-ēmdubhiḥ | Parābhav-ābdē Kārttikyāṁ.

In the Yādava lineage, Bukka [I.]; his son Harihara [II.]; his son Dēvarāja [I.]; his son Vijaya (Vīra-Vijaya); his son Dēvarāja [II.] (Abhinava-Dēvarāja, Vīra-Dēvarāja).

491.—Ś. 1353*.—*South-Ind. Inscr.* Vol. I. No. 54, p. 79. Tellūr (near Vēlūr) Tamil inscription of the reign of the *Mahāmaṇḍalēśvara Virapratāpa Dēvarāja (Dēvarāja II.)*:—

'On the day of Tiruvōṇam (*i.e.* Śravaṇa), which corresponds to Monday, the fifth lunar day of the former half of the month of Karkāṭaka of the Sādhārāṇa year (and) the Śaka year 1353.'

Monday, 20th November A.D. 1430; but see *Ind. Ant.* Vol. XXIV. p. 6, No. 146.⁷

492.—Ś. 1353*.—*PSOCI.* Nos. 227 and 26; *Mysore Inscr.* No. 116, p. 213, and No. 145, p. 259. Muḷbāgal Kanarese inscription and Telugu plate of the reign of Dēvarāja II., the son of Vijaya:—

No. 227: (L. 1).—Śaka-varuṣa 1353neya Sādhārāṇa-samvachchha(tsa)rada Phālgu[na]-su(śu) 10.

¹ By Mr. Rice the year is taken to be Ś. 1234.

² Read *puṇyē*.

³ Compare below, No. 496.

⁴ The above equivalent of the date is correct only on the supposition that the word *Karkāṭaka* of the date has been put erroneously instead of *Kārttikā*.

⁵ Compare above, No. 469.

⁶ This date fell in the *first* Āśāḍha of Ś. 1346.

⁷ For another Chāmarāja see above, No. 464.

No. 26 : (L. 3).—Śālivāhana-Śaka-varuṣam[ga]ṇa 1353nē Sādhāraṇa-nāma-samvatsarada Phālguna(na)-śu 10.

493.—*South-Ind. Inscr.* Vol. I. No. 79, p. 109. Paḍavēḍu Tamiḻ inscription of the reign of the *Rājādhirāja Vira-Dēvarāya (Dēvarāya II.)* :—

‘On the tenth day of the month of Māsi of the Pramādīcha year.’

[Pramādin = Ś. 1355.]

494.—*South-Ind. Inscr.* Vol. I. No. 80, p. 109. Paḍavēḍu Tamiḻ inscription of the reign of the *Mahārājādhirāja Vira-Dēvarāya (Dēvarāya II.)* :—

‘On the 2nd day of the month of Āḍi of the Ānanda year.’

[Ānanda = Ś. 1358.]

495.—*Inscr. at Śravana-Belgoḷa*, No. 125, p. 95. Inscription recording the date of the death of *Pratāpa-Dēvarāya* (the younger brother¹ of *Dēvarāya II.* ?) :—

(L. 1).—Kṣayālvaya-kuvatsarē dvitayayukta-Vaiśākhakē Mahitanaya-vārakē yuta-bālakṣha-pakṣ-ētarē | Pratāpanidhi-Dēvarātṭ pralayam-āpa hant-āsamaś-chaturdaśa-dinē katham Pitri-patē (?)² nivāryā gatiḥ ||

[Kṣaya = Ś. 1363] : Tuesday, 24th May A.D. 1446; see *Ind. Ant.* Vol. XXV. p. 346, No. 5.

496.—Ś. 1368.—*South-Ind. Inscr.* Vol. II. No. 71, p. 339. Tanjore (Rājarājēśvara temple) Tamiḻ inscription of the reign of *Dēvarāya II.* :—

‘(On the day) of the *nakṣatra* Pūrva-Phalgunī, which corresponded to a Wednesday and to the fifth *tithi* of the first fortnight, at the auspicious time of³ . . . in the Kṣaya *samvat[sara]* which was current after the Śaka year 1368.’

Wednesday, 29th June A.D. 1446.

497.—Ś. 1371.—*South-Ind. Inscr.* Vol. I. No. 81, p. 110. Paḍavēḍu (Sōmanāthēśvara temple) incomplete Tamiḻ inscription of the reign of the *Mahāmaṇḍalēśvara Rājādhirāja Virapratāpa Praudha-Immaḍi-Dēvarāya (i.e. Mallikārjuna)* :—

‘On the day of Uttirāḍam (i.e. Uttarāṣāḍhā), which corresponds to the *yōga* Āyushmat and to Saturday, the thirteenth lunar day of the former half of the month of Simha of the Śukla year, which was current after the Śaka year 1371.’

Saturday, 2nd August A.D. 1449; see *Ind. Ant.* Vol. XXIII. p. 132, No. 114.

498.—Ś. 1377.—*South-Ind. Inscr.* Vol. II. No. 23, p. 118, and Plate v. Tanjore (Rājarājēśvara temple) Sanskrit and Tamiḻ inscription of the *Mahāmaṇḍalēśvara Mēdinimisaragaṇḍa Kaṭṭāri Sāluva-sāluva Tirumalaidēva-mahārāja* :—

‘[On the 17th day] of the month of Śittirai in the Yuvan year, which was current after the Bhāva year (and) after the Śaka year one thousand three hundred and seventy-seven.’

499.—Ś. 1387.—*Ind. Ant.* Vol. XXI. p. 322. Date of a Conjeeveram (Arulāla-Perumāl temple) Tamiḻ inscription of the reign of *Mallikārjuna*, a son of *Virapratāpa Dēvarāya (Dēvarāya II.)* :—

‘On the day of Krittikā, which corresponded to Sunday, the full-moon *tithi* of the first fortnight of the month of Vṛiśchika in the Pārthiva year, which was current after the Śaka year 1387.’

Sunday, 3rd November A.D. 1465.

¹ Compare above, No. 487.

² The Kanarese transcript (on p. 128) has *pitriyatō*; read *Pitri-patēr*.

³ The word that has to be supplied is *dakṣiṇāyana-samkrānti*.

⁴ Compare *s.g. Ep. Carn.* Vol. III. p. 18, and *Ind. Ant.* Vol. XXV. p. 346, note 6.

⁵ He was a brother of the Sāluva Nṛsiṃharāja, the father of Immaḍi-Nṛsiṃha, below, No. 501; compare *Ep. Ind.* Vol. VII. p. 77, note 2.

500.—**Ś. 1392.**—*Ind. Ant.* Vol. XXI. p. 322. Date of a Conjeeveram (Arulāḷa-Perumāl temple) Tamiḷ inscription of the reign of **Virūpāksha II.**, a son of **Dēvarāya II.** :—

'At the auspicious time of the *Arđhōdaya* on the day of Śravaṇa, which corresponded to **Sunday**, the new-moon *tithi* of the second fortnight of the month of Makara in the Vikṛiti year, which was current after the Śaka year 1392.'

Sunday, 20th January A.D. 1471.¹

501.—**Ś. 1427*.**—*Ep. Ind.* Vol. VII. p. 80, and Plate. Dēvulapalli plates of (the Śāluva chief) the **Mahārāya Immaḍi-Nṛisimha**, represented as ruler of the province of Penugonḍa :—

(L. 62).—Śākē=bdē parisamkhyātē giri-nētra-yug-ēmdubhiḥ | Raktākshy-ākhyē Bhādra-pada-paunarṇasīyām Ravē=dinē | chaṁdrōparāga-samayē mahāpuṇyaphala-pradē |

Sunday, 25th August A.D. 1504; a lunar eclipse, visible in India.

In the Moon's family, Guṇḍa [I.]; had six sons, Guṇḍa [II.] Bomma, Mādirāja, Gautaya [I.], Virahōbala, Sāvitrī-Maṅgi, and Śāluva-Maṅgi; the last's son Gauta [II.]; his son Guṇḍa [III.], married Mallāmbikā; their son Nṛisimharāya² (surnamed Misaragaṇḍa, Kaṭhāri, Śāluva, Dharanivarāha, Dharāvarāha, Barbarabāha, etc.) married Śrīraḡgamāmbā; their son Immaḍi-Nṛisimha.³

502.—**Ś. 1430** (for 1431).—*Ep. Ind.* Vol. I. p. 363; (compare *Ind. Ant.* Vol. V. p. 73, and *PSOCI.* No. 115). Hampe Sanskrit and Kanarese inscription of the **Mahārājādhirāja Kṛishṇarāya**, residing at Vijayanagara :—

(North face, l. 27).—Śālivāhana-Śaka-varsha 1430 saṁdu mēle naḍava Śukla-saṁvatsarada Māgha-śu 14lu . . . paṭṭābhishēkōtsava-puṇyakāladalu.⁴

Mythical genealogy from the Moon to Turvasu. In Turvasu's race, Timma (famous among the Tuḷuva kings), married Dēvaki; their son, Īśvara,⁵ married Bukkamā; their son Narasa (Nṛisimha),⁶ was succeeded by his son, from Tippāji, Vīra-Nṛisimha (-Narasimha, -Nārasimha); succeeded by Narasa's son from Nāgalā (Nāgāmbikā), Kṛishṇarāya (Kṛishṇadēva-mahārāja, Virapratāpa Vīra-Kṛishṇarāya).

503.—**Ś. 1494** (for 1435).—*Jour. Bo. As. Soc.* Vol. XII. p. 381. Kuppēlūr Sanskrit and Kanarese plates⁶ of **Kṛishṇarāya** :—

(L. 52).—Śāk-ābdē Śālivāhasya sahasrēṇa chatuḥ-śataiḥ | chatustrimśat-samair-yuktē samkhyātē gaṇita-kramāt || Śrīmukhi-vatsarē ślāghyē Māghē ch-āsita-pakshakē | Śivarātrau mahātithyām⁷ puṇya-kālē śubhē dinē ||

Genealogy as in No. 502.

504.—**Ś. 1435.**—*Ep. Ind.* Vol. IV. p. 267. Śaṅkalāpura Sanskrit and Kanarese inscription of **Kṛishṇarāya**, the son of Nṛihari (Narasa) and Nāgāmbikā :—

(L. 76).—[Śā]livāhana-Śaka-varushaṁgaḷu 1435neya Śrīmukhi-saṁvatsara nija-Bhādrapada-ba 6 Maṁgaḷavāra Ka[pi]la-shashthi⁸-puṇyakāladalū.

Tuesday, 20th September A.D. 1513; see *ibid.* p. 267, and *Ind. Ant.* Vol. XXV. p. 345, No. 3.

¹ On this day the *tithi* of the date commenced 5 h. 19 m. after mean sunrise.

² Being minister and general of the first dynasty of Vijayanagara, he overthrew that dynasty. For inscriptions of his (of Ś. 1394 and Ś. 1404) see *South-Ind. Inscr.* Vol. I. Nos. 116 and 119.

³ For an inscription of his of Ś. 1418 see *ibid.* No. 115. See also *Ep. Ind.* Vol. VII. p. 79, note 7.

⁴ I.e. either the day of the king's coronation or an anniversary of it.

⁵ They were both generals of the Nṛisimharāya in No. 501. After the usurpation of the Vijayanagara kingdom by Nṛisimharāya (see No. 501), Narasa in turn took it away from Nṛisimharāya's family; see *Ep. Ind.* Vol. VII. p. 78.—For a date, corresponding to the 13th December A.D. 1493, of the time of Narasa, see *Ind. Ant.* Vol. XXVI. p. 380, No. 3.

⁶ The text of the inscription is interspersed with parenthetical remarks (such as would ordinarily be made by a commentator) regarding the contents and import of the different parts of the inscription.

⁷ Read *puṇya*.

⁸ Read *-puṇya*.

505.—Ś. 1435 (for 1436).—*As. Res.* Vol. XX. p. 30. Translation of a Krishṇarāya inscription of Krishṇarāya :—

'In the reign of Śālivāhana 1435, corresponding to the year Bhāva, in Phālguna Tṛitīyā, Śukravār.'

Friday, 16th February A.D. 1515; see below, No. 506.

506.—Ś. 1436.—*As. Res.* Vol. XX. pp. 21 and 37. Krishṇarāya Sanskrit and Kanarese inscription of Krishṇarāya :—

Śālivāhana-Śak-ābdāḥ || 1436 || . . . Bā(Bhā)va-nāma-samvatsara-Phālguna-suddha 3 Śukravāra.

Friday, 16th February A.D. 1515; see *Ind. Ant.* Vol. XXIII. p. 120, No. 43.

507.—Ś. 1436.—*Archaeol. Surv. of West. India*, Vol. III. p. 115. Reference to a Sanskrit Kanarese inscription of the time of Krishṇarāya :—

Śālivāhana-Śaka-varushamgaḷu 1436neya Bhāva-samvatsaradallu.

508.—Ś. 1437-1443.—*Ep. Ind.* Vol. VI. p. 117. Maṅgalagiri and Kāzā pillar in connection of the reign of Krishṇarāya of Vijayanagara, recording grants by his prime-minister Sālva-(Sālva-)Timma (the son of the minister Rācha and grandson of the minister Vēma, and husband of Lakshmi), and by the two ministers Appa and Gōpa (Nādiṇḍla-Appa and Nādiṇḍla-Gōpa), sons of the minister Timma and his wife Krishṇāmbā (Krishṇamāmbā) who was a sister of Sālva-Timma. The inscription records the capture of Koṇḍavīṭi (Koṇḍavīṭi) from the Gajapati (of Orissa) by Sālva-Timma on the following date :—

(L. 47).—Sālva-vāṅka-Śakavatsara-gany-Āshāḍha-sudhdha(ddha)-Harivāsara-Saurav (. . . which there is the remark : Sālva-vāṅka akshara-samjūa | 1437 Śaka-varshālu).

Saturday, 23rd June A.D. 1515.

509.—Ś. 1442.—*Ep. Ind.* Vol. VI. p. 233. Koṇḍavīṭi Sanskrit and Telugu pillar inscription of the reign of Krishṇarāya of Vijayanagara, recording grants by Nādiṇḍla-Gōpa, the governor of Koṇḍavīṭi, made for the benefit of Krishṇarāya's minister Sālva-Timma and his wife Lakshmi (Lakshamma) ;³ (the Sanskrit part was composed by Lōlla-Lakshmiṇḍara Yajvan) :—

(L. 92).—Śak-ābdē-kshi-yug-ābdhi-chaṇdra-gaṇitē samvatsarē Vikramē.

(L. 109).—Jayābhyudaya-Śālivāhana-Śaka-varshāmbulu 1442agunēṇṭi Vikramavatsara Vaisākha-sudhdha(ddha) 15 Bu | sōmagrahana-punyakālam=amdu.

Wednesday, 2nd May A.D. 1520; a lunar eclipse, visible in India.

510.—Ś. 1442.—*As. Res.* Vol. XX. p. 28. Translation of a Vijayanagara inscription of the time of Krishṇarāya :—

'In the year of Śālivāhana 1442, corresponding to . . . Vikrama, in Māgha saptamī . . . on Rādhāsaptamī,⁴ the 7th of the moon.'

511.—Ś. 1444 (for 1445).—*PSOCI*. No. 27; *Mysore Inscr.* No. 135, p. 242. Śālivāhana Sanskrit and Kanarese plates of Krishṇarāya :—

(L. 77).—Śālivāhana-nirṇī(rṇī)tē Śak-ābdē daśabhiḥ śataiḥ | chatuś-śataiś=chatuś-chatvāriṁśatā gaṇitē kramāt | Svabhānu-vatsarē Pushya-māsē Makara-samkramē | Hanta-rkshē Bhāumavārē cha.

Tuesday, 29th December A.D. 1523; see *Ind. Ant.* Vol. XXIV. p. 5, No. 142.

Genealogy as in No. 502.

¹ With a few explanatory remarks in Telugu.—For another inscription of Ś. 1437 see below, under *Addenda*.

² The other (very numerous) dates it is impossible to give here. In one of the dates, in lines 151 and 152, *indra-jalad(dā)-tīndu* appears to be wrong for *indru-jaladh-tīndra* (1441).

³ See above, No. 508.

⁴ This should be *ratha-saptamī*.

512.—Ś. 1448.—*As. Res.* Vol. III. p. 39. Translation with specimen lithograph of the text of Conjeeveram plates of **Kṛishṇarāya** :—

'One thousand four hundred and forty-eight years of the *Sacābda*, or era established in memory of Śālivāhana, being elapsed; in the year *Vyaya*, in the month of *Pushya*, when the sun was entering *Macara*, in the dark fortnight, on the day of *Bhṛigu*, and on that venerable *tithi*, the tenth of the moon; under the constellation *Viśākhā*.'

Friday, 28th December A.D. 1526.¹

513.—Ś. 1450 and 1451.—*Ep. Ind.* Vol. I. p. 399. **Kṛishṇapuram** Sanskrit and Kanarese inscription of the *Mahārājādhirāja Virapratāpa Vira-Kṛishṇarāya* (**Kṛishṇarāya**), reigning at **Vijayanagara** :—

(L. 1).—Śālivāhana-Śaka-varuṣaṅgaḷu 1451neya Virōdhi-samvatsarada Vaiśākha-śukla (ddha) 15 Śudantū (i.e. Śukravāradantū) . . .

(L. 22).—Virōdhi-samvatsarada Vaiśākha-śu 15 Śudantū sōmagrā(gra)haṇa-punya-kāladantū.

Friday, 23rd April A.D. 1529; a lunar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII p. 120, No. 45.

(L. 45).—Śākē sārdaish=chaturbhiḥ=²daśabhir=api śataiḥ sammitē Sarvadā(dhā)riṇḥ=abdhē(bdē) Chaitr-ākhyā-māsē sita-Madana-tithau Jivavārē=ryamarkshē |

Thursday, 2nd April A.D. 1528; see *ibid.* p. 120, No. 44.

514.—Ś. 1452.—*Ind. Ant.* Vol. IV. p. 328; *PSOCI.* No. 129; *Mysore Inscr.* No. 22, p. 53. Harihar Sanskrit and Kanarese inscription of the reign of the *Rājādhirāja Virapratāpa Achyutarāya*, recording a grant by *Nārāyaṇadēva*, the son of *Timmarasa* :—

(L. 4).—Śālivāhana-Śaka-varsha 1452 Vikru(kṛi)ti-samvatsarada Śrāvapa-bahula 8va Sōmavāra Jayamti.³pūṇyakāladantū śrī-Kru(kṛi)śūpāvatāra-samayadantū.

Monday, 15th August A.D. 1530; ⁴see *Ind. Ant.* Vol. XXIV. p. 2, No. 126.

515.—Ś. 1453.—*PSOCI.* No. 130; *Mysore Inscr.* No. 25, p. 43. Harihar Kanarese inscription of the time of **Virapratāpa Achyutarāya**, reigning at **Vijayanagara** :—

(L. 3).—Śālivāhana-Śaka-varuṣa(sha)ṅgaḷu 1453neya Khara-samva[tsa]rada Āśvija-śu 10 Saumyavāradantū.

Wednesday, 20th September A.D. 1531.⁵

516.—Ś. 1455*.—*Ind. Ant.* Vol. V. p. 19; *PSOCI.* No. 72. Toḷachguḍ (Bādāmi) fragmentary Kanarese inscription of the reign of **Virapratāpa Achyutarāya**,⁶ and of his *Sénādhipati* **Chinnapa-Nāyaka** :—

(L. 4).—Śālivāhana-Śaka-varsha 1455neya Nandana-samvatsarada Jē(jyē)shṭha-śu 5 Guruvāradantū.

Thursday, 9th May A.D. 1532; see *Ind. Ant.* Vol. XXIII. p. 129, No. 97.

517.—Ś. 1460.—*Ind. Ant.* Vol. IV. p. 330, and Plate in Vol. V. p. 362; *PSOCI.* No. 131. *Mysore Inscr.* No. 21, p. 36. Harihar inscription of the reign of **Achyutarāya**, recording a grant by his minister **Achyutamallapaṇṇa** (**Akkapa**); (the verses were composed by *Vādhūla Mallapārādhyā*, the son of *Timmapārādhyā*, of the family of *Kōṭṭisa*?) :—

(L. 15).—Śālivāhana-nirṇāta-Śaka-varuṣa-⁸kram-āgatē | vyōma-tarkka-chatuś-chandrasamkhyayā cha samanvitē || Viḷambi-nāmakē varshē māśē Kārttika-nāmani | paurnamāśrām sitē pakshē vārē Śāsisutasya cha || Sōmōparāga-samayē.

¹ On this day the *tithi* of the date commenced 2 h. 29 m. after mean sunrise.

² Read *sārdaish=chaturbhiḥ=*.

³ Read *pūṇya*.

⁴ On this day the *tithi* of the date commenced 12 h. 45 m. after mean sunrise.

⁵ On this day the *tithi* of the date commenced 1 h. 46 m. after mean sunrise.

⁶ For an inscription of his of Ś. 1454, the year *Nandana*, see *South-Ind. Inscr.* Vol. I. No. 123, p. 133.

⁷ Compare above, No. 475.

⁸ Read *-varsha*.

Wednesday, 6th November A.D. 1538; a lunar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 120, No. 46.

518.—Ś. 1461.—*PSOOL*. No. 132; *Mysore Inscr.* No. 19, p. 29. Harihar Sanskrit and Kanarese inscription of Virapratāpa Achyutarāya :—

(L. 8).—Śākē chaṁdra-ras-Āmarēndra-gaṇitā . . . Bhādrapadasya . . . dvādaśy-
abhikhyē tithau vārē Bhūmisutasya ;¹ (*Mys. Inscr.*: 'the 12th day of the moon's increase, the
nakshatra being Śravana').

Tuesday, 26th August A.D. 1539 (when the *nakshatra* was Śravana).

519.—Ś. 1462.—*Ep. Ind.* Vol. III. p. 151, and Plates. Ūṇamāñjēri plates² of Achyuta-
rāya, residing at Vijayanagara, recording a grant made at the request of his minister Virūpāksha-
Nāyaka, who was born in the family of Ananta and belonged to the [Ā]diyappēndra Nāyakas;
(composed by Sabhāpati) :—

(L. 91).—Śak-ābdē Śālivāhasya sahasrēṇa chatuś-śataih | dvishashṭyā cha samāyuktē(ktai)-
gaganām prāpitē kramāt || Śārvarī-nāmakē varshē māsi Kārttika-nāmami | śukla-pakshē
cha punyāyām-utthāna-dvādaśī-tithau ||

Genealogy as far as Kṛṣṇarāya as in No. 502; he was succeeded by his younger brother
Achyutēndra (Achyutarāya), the son of Nṛsiṁha (Narasa) from Ōbāmbikā.

520.—Ś. 1463*.—*As. Res.* Vol. XX. p. 26. Translation of a Vijayanagara Kanarese
inscription of the time of Achyutarāya :—

'In the year of Śālivāhana 1463, corresponding to the year Śārvarī, in the month of
Kārttika, sudi-paūchamī, Guruvār.'

The date is irregular.

521.—*Ind. Ant.* Vol. X. p. 64, and Plate; *PSOOL*. No. 45. Bādāmi Kanarese pillar
inscription of the time of Sadāśivarāya, and of the Haḍapadaḷa³ Kṛṣṇappa-Nāyaka, and
Koṇḍarāja :—

(L. 1).—Śōbhakru(kṛi)t-saṁvatsarada Āśāḍa(ḍha)-śu 15lā.
[Śōbhakṛit=Ś. 1465.]

522.—*Ind. Ant.* Vol. X. p. 64; *Archæol. Surv. of West. India*, Vol. I. Plate xxxiv. 10;
PSOOL. No. 46. Bādāmi Kanarese pillar inscription of Koṇḍarāja :—

(L. 1).—Śōbhakru(kṛi)ttu(tu)-saṁvatsarada Āśāḍa-su⁴ 15lā.
[Śōbhakṛit=Ś. 1465.]

523.—Ś. 1466*.—*Ind. Ant.* Vol. X. p. 66. Tolachguḍ(Bādāmi) Kanarese inscription of the
reign of the Mahārājādhirāja Virapratāpa Sadāśivarāya, recording a grant by the
Haḍapadaḷa³ Kṛṣṇappa-Nāyaka :—

(L. 2).—Śālivāhana-Śaka-varuṣa 1466neya Śōbhakru(kṛi)t-saṁvatsarada Ā[śvi]ja-śu]dha-
(ddha) . . . [1]lā.

524.—Ś. 1467.—*As. Res.* Vol. XX. p. 35. Translation of a Vijayanagara inscription of the
time of Sadāśivarāya :—

'In the year of Śālivāhana 1467, corresponding to the year Viśvāvasu, in Krishna(!) sudi-
triṭyā, Guruvāram.'

525.—Ś. 1469.—*Ind. Ant.* Vol. X. p. 64. Bādāmi Kanarese inscription of the reign of the
Mahārājādhirāja Virapratāpa Sadāśivarāya :—

(L. 2).—Śālivāhana-Śaka 1469neya Plavaṅga-saṁvatsarada A(ā)śvayuja-śu 15yalā.

¹ See *Ind. Ant.* Vol. XII. p. 214, No. 89.

² For an inscription of his of Ś. 1463 expired, the year Plava, see *South-Ind. Inscr.* Vol. I. No. 118, p. 132.

³ See *Ep. Ind.* Vol. III. p. viii, note on p. 208.

⁴ Read *Āśāḍa-śu*.

⁵ The plates are marked with numeral figures.

⁶ See below, No. 531.

⁷ See above, No. 521.

526.—Ś. 1470.—*PSOCL*. No. 240; *Mysore Inscr.* No. 126, p. 224. Bêlûr Kanarese inscription of the reign of Sadâśivarâya:—

‘Śâlivâhana-Śaka 1470 (in figures, l. 4), the Kîlaka *saṃvatsara*; Monday, the eleventh day of the dark fortnight of Âshâḍha.’

The date is irregular.

527.—Ś. 1471.—*South-Ind. Inscr.* Vol. I. No. 57, p. 84. Viriñchipuram Tamîl inscription of Bommu-Nâyaka [of Vêlûr]:—

‘On Thursday, the day of Punarvasu, which corresponds to the seventh lunar day of the former half of the month of Mêsâ of the Saumya year, which was current after the Śâlivâha-Śaka year 1471.’

Thursday, 4th April A.D. 1549; see *Ind. Ant.* Vol. XXIII. p. 132, No. 115.

528.—Ś. 1476.—*PSOCL*. No. 133; *Mysore Inscr.* No. 17, p. 25. Harihar Kanarese inscription of the reign of Virapratâpa Sadâśivarâya, residing at Vidyânagara, recording a grant by Kṛishṇappa-Nâyaka, the son of Bayappa-Nâyaka:—

(L. 3).—Śâlivâhana-Śaka-varsha 147[6]neya Ânamîda-saṃvatsarada Vayaśâkha-³ba 14 Sômarâradalu . . . śrî-Narasihva-³jayantî-⁴pumnyakâlâdalu.

Monday, 16th April A.D. 1554; see *Ind. Ant.* Vol. XXIII. p. 120, No. 47.

529.—Ś. 1477.—*PSOCL*. No. 241; *Mysore Inscr.* No. 127, p. 225. Bêlûr Kanarese inscription of the reign of Virapratâpa Sadâśivarâya, residing at Vidyânagara:—

‘Śâlivâhana-Śaka 1477 (in figures, l. 3), the Râkshasa *saṃvatsara*; the fifth day of the bright fortnight of Mâgha.’

530.—Ś. 1478.—*Ep. Ind.* Vol. IV. p. 12. British Museum (formerly Sir W. Elliot's) plates⁵ of Sadâśivarâya, residing at Vijayanagara (Vidyânagara); recording a grant made at the request of (king Raṅgarâja's, Śîraṅgarâya's, son) Râmarâja,⁶ the ruler of the Karpâta kingdom, who had been requested in this matter by the prince Koṇḍarâja (descended from king Bukka of Âpaviḍu); (composed by Sabhâpati):—

(L. 115).—Kramâd=vasu-hay-âbhdh-îmdu-gapitê Śaka-vatsarê | Naḷa-saṃvatsarê mâsi Mârgaśrîsha iti śrutê | sūryôparâgê-mâvâsyâ-tithâ(thau) Mârttâmda-vâsarê |

The date is irregular; see *Ind. Ant.* Vol. XXIV. p. 17, No. 199.

Genealogy as far as Achyutarâya as in No. 519, except that according to this inscription Ōhâmbikâ bore to Nṛisîṃha (Narasa) two sons, Raṅga and Achyutarâya. Achyutarâya was succeeded by his son Veṅkaṭarâya, and when the latter died, Râma,⁶ the ruler of the Karpâta kingdom and ‘husband of (Sadâśiva's) sister,’⁷ made the ministers install Sadâśivarâya, the son of (Achyutarâya's brother) Raṅga and Timmâmbâ.—The inscription also gives the genealogy of Koṇḍarâja.

531.—Ś. 1482 (for 1483).—*PSOCL*. No. 134; *Mysore Inscr.* No. 24, p. 41. Harihar Sanskrit and Kanarese inscription of the reign of Virapratâpa Sadâśivarâya, residing at Vidyânagara:—

(L. 8).—Śâlivâhanana-⁸Śaka-varsha 1482 Duṃmatî-saṃvatsarada Mâgha-śu 15 Sômarâra sôṃôparâga-⁴pumnyakâlâdâlû.

¹ See below, No. 534.

² Read *Vaiśākha*.

³ Read *Narasimha*, and compare *Ind. Ant.* Vol. XXVI. p. 150, l. 1.

⁴ Read *-punya*.

⁵ The plates are marked with numeral figures.—The grant is remarkable for the large number of villages mentioned in it.

⁶ I.e. Râmarâja II. of the third Vijayanagara dynasty; see below, No. 533.

⁷ More probably Sadâśiva's cousin, the daughter of Kṛishṇarâya.

⁸ Read *Śâlivâhana*.

20th January A.D. 1562, with a lunar eclipse, visible in India; but the day was a Tuesday, not a Monday; see *Ind. Ant.* Vol. XXIV. p. 9, No. 159.

532.—Ś. 1483.—*As. Res.* Vol. XX. p. 28. Translation of a Vijayanagara inscription of the time of Sadāśivarāya :—

‘In the year of Śālivāhana 1483, corresponding to the year Durmati, in Chaitra sudi-
pañchamī, Śānivār, . . . in the season of Makara-samkrānti-puṇyakāla.’

The date is irregular.

533.—Ś. 1482 (P for 1485).—*PSOCI.* No. 246; *Mysore Inscr.* No. 129, p. 228. Hāsan Kanarese inscription of Sadāśivarāya, residing at Vidyānagara, and of Kṛishṇappa-Nāyaka, the son of Bayappa-Nāyaka :—

(L. 5).—Śālivāhana-Śaka-varsha 1482(P)ya varttamānakka(kke) nilāva¹ Rudhirōdgāri-saṁvatsarada Śrāvāṇa-su 13 Sōmavāra ²puṇyakāladalli.

For Rudhirōdgārin = Ś. 1485 the date would correspond to Monday, 2nd August A.D. 1563.

534.—Ś. 1488.—*South-Ind. Inscr.* Vol. I. Nos. 43-46, p. 70 ff. Four Tamil inscriptions at Aṇṇappakkam, Ariyūr, Arumbaritti and Śaduppēri (all near Vēlūr), of the reign of Sadāśivarāya; recording grants made by the *Mahāmaṇḍalēśvara* Tirumalarāja (I., the younger brother of Rāmarāja II. of Karpāṭa³) at the request of Śiṇṇa-Bommu-Nāyaka of Vēlūr :⁴—

‘On Wednesday, the twelfth lunar day of the latter half of the month of Kumbha of the Akshaya-saṁvatsara, which was current after the Śaka year 1488.’

Wednesday, 5th February A.D. 1567; see *Ind. Ant.* Vol. XXIII. p. 133, No. 116.

535.—Ś. 1497.⁵—*South-Ind. Inscr.* Vol. I. Nos. 47-49, p. 73 ff. Three Tamil inscriptions at Śattuvāchchēri, Śamaṅginellūr and Perumai (all near Vēlūr), of the reign of the *Mahāmaṇḍalēśvara* Śrīraṅgarāya II.³ (usually described as I.); recording grants made by Kṛishṇappa-Nāyaka Ayyaṇ at the request of Śiṇṇa-Bommu-Nāyaka of Vēlūr :⁶—

‘On Wednesday, the thirteenth lunar day of the dark half of the month of Makara of the Yuva-saṁvatsara, which was current after the Śaka year 1497.’

The date is irregular; see *Ind. Ant.* Vol. XXIV. p. 17, No. 200.

536.—Ś. 1500.—*PSOCI.* No. 242; *Mysore Inscr.* No. 121, p. 220. Bēlūr Kanarese inscription of the reign of the *Mahārājādhirāja* Virapratāpa Śrīraṅgarāya II.³ (usually described as I.), recording a grant by Kṛishṇappa-Nāyaka, [the son of] Veṅkaṭādri-Nāyaka :—

‘Śālivāhana-Śaka 1500 or 1560 (in figures, l. 10), the Bahudhānya saṁvatsara; Saturday, the eighth day of the dark fortnight of Śrāvāṇa;’ (*Mys. Inscr.* : ‘the year 1500’).

Saturday, 26th July A.D. 1578.⁷

537.—Ś. 1506.—*PSOCI.* No. 28; *Mysore Inscr.* No. 140, p. 252. Dēvanhaḷḷi plates of Śrīraṅgarāya II.³ (usually described as I.) :—

(L. 114).—Khyāt-āṅg-āmbara-bāṇ-ēṇḍu-gaṇitē Śaka-vatsarē | vatsarē Tāraṇ-ābhikhyē māsi Kārttika-nāmani || Pakshē valakshē puṇyāyām paurnimāyām mahātithau | sōmōparāga-samayē.⁸

7th November A.D. 1584; a lunar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 121, No. 48.

¹ Read *salluva* (P).

² Read *puṇya*.

³ See below, No. 539.

⁴ See above, No. 527.

⁵ For plates of Śrīraṅgarāya II. of the same year see *Ind. Ant.* Vol. XIII. p. 155.

⁶ See above, No. 534.

⁷ On this day the *tithi* of the date (which was the *Kṛishṇaśṣṭamī*) commenced 2 h. 42 m. after mean sunrise.

⁸ See *Ind. Ant.* Vol. XII. p. 213, No. 74.

538.—Ś. 1514.—*South-Ind. Inscr.* Vol. I. No. 58, p. 85. Viriñchipuram Tamil inscription of the reign of the *Mahāmaṇḍalēśvara Veṅkaṭapati I.*,¹ recording a grant by *Periya-Erama-Nāyaka* of Puṇṇārrūr :—

‘On the 6th solar day of the month of Tai of the Nandana year, which was current after the Śaka year 1514.’

539.—Ś. 1523.—*Ep. Ind.* Vol. IV. p. 272; *Ind. Ant.* Vol. II. p. 371, and Plates. Veḷāppākam (Vilāpāka) plates² of *Vira-Veṅkaṭapati-mahārāya (Veṅkaṭapati I.)* of Karṇāṭa, recording a grant which was ‘made at the request of Liṅga, the son of Bomma of Vēlūru³ and grandson of Virappa-Nāyaka; (composed by Rāma, the son of Kāmakoṭi and grandson of Sabhāpati) :—

(L. 109).—Śakti-nētra-kaḷamb-ēndu-gaṇitē Śaka-vatsarē | [Pla]va-saṁvatsarē puṇyē māsi(s) Vaisākha-nāmani | pakshē [va]lakshē puṇya-rkshē puṇyāyām dvādasi(s)-tithau |

In the Moon’s race (after mythical and legendary beings), Tāta-Pinnama [I.]; his son Sōmidēva; his son Rāghavadēva; his son Pinnama [II.], lord of Āravīḍu; his son Bukka (firmly established the kingdom of Sāḷuva-Nṛsiṁha⁴); his son Rāmarāja [I.]; his son Śrīraṅgarāja [I.]; his sons Rāmarāja [II.],⁵ Tirumalarāja [I.],⁶ and Veṅkaṭādri, of whom Tirumalarāja [I.] was installed as king; his son Śrīraṅgarāja [II.];⁷ his younger brother Veṅkaṭapati [I.] (defeated Mahamandāsāhu, the son of Malikībharāma, i.e. Muḥammad Shāh, the son of Malik Ibrāhīm of Golkonda).

540.—Ś. 1543.—*PSOCI.* No. 29; *Mysore Inscr.* No. 136, p. 247. Śimoggā Sanskrit and Kanarese plates⁸ of the reign of Rāmadēva [IV. of Karṇāṭa ?]:⁹—

‘Śaka 1543 (in words, l. 18 of the first side; *vēda*, 3; *ambudhī*, 4; *sara*, 5; and *kshōpī*, 1), the Durmati saṁvatsara; Saturday, the third day of the bright fortnight of Vaisākha.’¹⁰

Saturday, 14th April A.D. 1621; see *Ind. Ant.* Vol. XXIII. p. 121, No. 49.

541.—Ś. 1547.—*PSOCI.* No. 243; *Mysore Inscr.* No. 122, p. 221. Bēlūr Kanarese inscription of Kṛishṇappa-Nāyaka, Veṅkaṭādri-Nāyaka, and others :—

(L. 4).—Śālivāhana-Sha(śa)ka-varuṣaṁgaḷu 1547nē Krōdhana-saṁvatsarada Māgha-ba 5 Sōmavāra.

Monday, 6th February A.D. 1626.

542.—Ś. 1556.¹¹—*Ep. Ind.* Vol. III. p. 240. Kūniyūr plates¹² of *Vira-Veṅkaṭapati-mahārāya (Peda-Veṅkaṭa, Veṅkaṭapati II., the elder son of Śrīraṅgarāja IV. who was a son of Rāmarāja II.)* of Karṇāṭa, residing at Penugonda; recording a grant which was made at the request of *Tirumala-Nāyaka* (of Madhurā); (composed by Rāma, the son of Kāmakoṭi and grandson of Sabhāpati) :—

(L. 103).—Ri(ri)tu-bāpa-kaḷamb-ēndu-gaṇitē Śaka-vatsarē | Bhāv-ābhidā(dhā)nakē varshē māsi Vaisākha-nāmani | pakshē vaḷakshē puṇya-rkshē paurṇa(rṇa)māsyām mahātithau |

For a full genealogy of the family to which Veṅkaṭapati II. belonged, see the Table facing *ibid.* p. 238.

Genealogy of Tirumala: Nāga of the Kāśyapa gōtra; his son Viśvanātha; his son Kṛishṇappa-Nāyaka; his son Virappa; his son Viśvappa-Nāyaka; his son Muddukrishṇa; his sons Mudduvīra and Tirumala.

¹ See No. 539.

² The plates are marked with numeral figures.

³ See No. 535.—*South-Ind. Inscr.* Vol. I. No. 133, dated Ś. 1524, records a grant by Bommu-Nāyaka’s son Liṅgama-Nāyaka.

⁴ See No. 501.

⁵ See No. 530.

⁶ See No. 534.

⁷ See Nos. 535-537.

⁸ Compare *Ep. Ind.* Vol. III., Table facing p. 238.

⁹ In the photograph the greater part of the date is illegible.

¹⁰ For a Viriñchipuram Tamil inscription of the same king, and of the year Śrīmukha=Ś. 1556*, see *South-Ind. Inscr.* Vol. I. No. 133, p. 136.

543.—*Ś. 1558.*—*Ind. Ant.* Vol. XIII. p. 128. Koṇḍyāta¹ (now Madras Museum) plates of **Veṅkaṭapati II.** of Karṇāṭa; (composed by Rāma, the son of Kāmakōṭi and grandson of Sabhāpati):—

(L. 121).—Vasu-bāpa-kaḷamb-ēndu-gaṇitē Śaka-vatsarē | Dhātṛi-saṁvatsarē(ṛa-)nāmni nāsi ch=Āśāḍha-nāmani | pakshē vaḷakshē puṇya-rkshē dvādaśyām(śyām) cha mahātithau |

The greater part of the genealogical portion of this record is identical with the corresponding portion of No. 542

544.—*Ś. 1560**.—*PSOCI.* No. 237; *Mysore Inscr.* No. 119, p. 218. Halēbīḍ Kanarese inscription of the time of **Veṅkaṭādri-Nāyaka Ayya**, the son of Kṛishṇappa-Nāyaka Ayya, of Bēlūr:—

‘Śālivāhana-Śaka 1560 (in figures, l. 9), the Śvara saṁvatsara; Thursday, the fifth day of the bright fortnight of Phālguna.’

Thursday, 8th February A.D. 1638;² see *Ind. Ant.* Vol. XXIV. p. 3, No. 136.

545.—*Ś. 1566.*—*Ind. Ant.* Vol. XIII. p. 156. Kaḷḷakursi³ plates of **Śrīraṅgarāya VI.** (usually described as II.) of Karṇāṭa, the son of Pina(China)-Veṅkaṭa III. who was the younger brother of Veṅkaṭapati II., and adopted son of Gōpāla who was the son of Śrīraṅga V. and grandson of Veṅkaṭādri, the youngest brother of Rāmarāja II.;⁴ (composed by Rāma, the son of Kāmakōṭi and grandson of Sabhāpati):—

(L. 105).—Rasa-rtu-bāpa-chaṁḍr-ākhyā-gaṇitē Śaka-vatsarē [] Tāru(ṛa)ṇ-ākhyē mahā-varshē māsi Phālguna(ṇa)-nāmakē | pakshē vaḷakshē puṇya-rkshē dvādaśyām(śyām) cha mahātithau |

546.—*Ś. 1615.*—*Coorg Inscr.* No. 11, p. 16. Kaṭṭepura Kanarese plate of **Kṛishṇappa-Nāyaka**, the son of Veṅkaṭādri-Nāyaka and grandson of Kṛishṇappa-Nāyaka, of Bēlūr:—

Śālivāhana-Śaka-varushagaḷu 1615neya Śrīmukha-nāma-saṁvatsarada Pushya-śu 12lu Makarasaṅkramana-puṇyakāḷadalli.

29th December A.D. 1693.

J.—The Eastern Chalukyas (or Chālukyas, including those of Piṭhāpuram and Śrīkūrmam) and minor chiefs of the Telugu country.⁵

547.—*Ind. Ant.* Vol. XIX. p. 309, and Plate. Sātārā (now British Museum) plates of the E. Chalukya⁶ **Yuvarāja Vishṇuvardhana⁷ I. Vishamasiddhi**; of the 8th year (of the reign) of the **Mahārāja** (the W. Chalukya Pulakēśin II.⁸); issued from Kurumarathya:—

(L. 13).—Kārttika-paurṇamāsyām.

(L. 35).—Śrī-mahārājasya pravarddhamānaka-saṁvatsarē aṣṭamē.

In the family of the Chalukyas, Raṇavikrama Satyāśraya [Pulakēśin I.]; his son Kīrti-varman [I.]; his son Vishṇuvardhana [I.] Vishamasiddhi.

548.—*Ind. Ant.* Vol. XX. p. 16; Dr. Burnell's *South-Ind. Palæography*, 2nd ed., Plate xxvii. Chīpurupalle plates of the 18th year (of the reign) of the E. Chalukya **Mahārāja Vishṇuvar-**

¹ This is the name of the village granted; I do not know where the plates were found.

² On this day the *tithi* of the date commenced 3 h. 12 m. after mean sunrise.

³ This is the name of the village granted; the grant was edited from Sir W. Elliot's impressions.

⁴ Compare *Ep. Ind.* Vol. III., Table facing p. 238.

⁵ Viz. the chiefs of Koṇḍapaḍmaṭi, Velāṅḍu and Kōnamāṇḍala (Nos. 581-593), the Kākatiyas (Nos. 584-599), the chiefs of Amarāvati and Nātavāḍi (Nos. 590-592), the Reḍḍis of Koṇḍavīḍu and Rājamaṇḍrangura (Nos. 593-599), the Matsyas of Oḍḍavāḍi (No. 600) and Nāmaya-Nāyaka of Piṭhāpuri (No. 601).

⁶ The original has *Chalukya*.

⁷ On the seal called Biṭṭarasa.—He is the Kubja-Vishṇuvardhana of No. 557 ff.

⁸ See above, No. 9 ff.

dhana I. Vishamasiddhi, the younger brother of the *Mahārāja* Satyāśraya (Pulakēśin II.); issued from Cherupūra:—

(L. 14).—Śrāvaṇa-māsē chandragrahaṇa-nimittē.

(L. 20).—sain 10 8 mā (?) 4 (?) di 10 5.

[Ś. 554]: 7th July A.D. 632; a lunar eclipse, visible in India; see *Ind. Ant.* Vol. XX. p. 4.

The *ājñapti* (or *dūtaka*) of the grant was Aṭavidurjaya of the Matsya¹ family.

549.—*Ind. Ant.* Vol. XIII. p. 137, and Plate. Pedda-Maddāli plates of the 18th year of the reign of the E. Chalukya *Mahārāja* Jayasimha I. (Sarvasiddhi), the son of [Vishamasiddhi²] and grandson of Kīrtivarman I.; issued from Udayapūra:—

(L. 18).—vishuva-nimittē vijayarāja-saṁvatsarē aṣṭādaś[ē*].

550.—*Ind. Ant.* Vol. VII. p. 186, and Plates in Vol. VIII. p. 320. Nellore district (formerly Sir W. Elliot's, now British Museum?) plates of the second year of the reign of the E. Chalukya *Mahārāja* Vishṇuvardhana II. (Vishamasiddhi), the grandson of the *Mahārāja* Vishṇuvardhana I., and son of Indra-bhaṭṭāraka who was the younger brother of the *Mahārāja* Jayasimha I.:—

(L. 65).—varddhamāna-rāja-dvaya³-saṁvatsarē Chaitra-māsē śukla-pakṣhē daśamyaṁ Maghā-nakṣatrē Budhavārēṣhu.

[Ś. 556]: Wednesday, 13th March A.D. 664; see *ibid.* Vol. XX. p. 8.

551.—*Ind. Ant.* Vol. VII. p. 191, and Plate. Maṭṭewāḍa (? formerly Sir W. Elliot's, now British Museum?) first and second plates⁴ only of the 5th year of the reign of the E. Chalukya *Mahārāja* Vishṇuvardhana II. (Vishamasiddhi), the great-grandson of Kīrtivarman I., grandson of the *Mahārāja* Vishṇuvardhana I., and son of Indra-bhaṭṭāraka who was the brother of the *Mahārāja* Jayasimha I.:—

(L. 19).—a(ā)tmanō vijayarāja-pañcamē saṁvatsarē Phālguna(na)-māsē anāvāsyāyāṁ sūryyagra[hu*]ṇa-nimi[tte*].

[Ś. 559]: 17th February A.D. 668; a solar eclipse (in the *pūrṇimānta* Phālguna), not visible in India;⁵ see *ibid.* Vol. XX. p. 9.

552.—*Ind. Ant.* Vol. XX. p. 105. Madras Museum plates of the 20th year of the reign of the E. Chalukya *Mahārāja* Sarvalōkāśraya (Vijayasiddhi, i.e. Maṅgi-yuvarāja⁶), the son of the *Mahārāja* Vishṇuvardhana II., who was the son of Indra-bhaṭṭāraka, the younger brother of the *Mahārāja* Jayasimha I.:—

(L. 24).—uttarāyaṇa-nimittē . . . [pravarddhamāna-vi]jarāja-saṁvatsarē viṣaḥ.⁷

553.—*South-Ind. Inscr.* Vol. I. No. 35, p. 33; *Ind. Ant.* Vol. XX. p. 415. British Museum (formerly Sir W. Elliot's) plates of the E. Chalukya *Mahārājādhirāja* Vijayāditya II. Narēndramṛigarāja, the son of the *Mahārāja* Vishṇuvardhana IV. and grandson of the *Mahārāja* Vijayāditya I.:—

(L. 42).—chandru(ndra)grahaṇa-nimittē.

The inscription mentions as *ājñapti* (or *dūtaka*) Narēndramṛigarāja's brother, the prince Nṛipa-Rudra, born in the Haihaya family.

554.—*Ep. Ind.* Vol. V. p. 120, and Plate. Eḍḍeru (now Madras Museum) plates of the E. Chalukya *Mahārājādhirāja* Vijayāditya II., the son of the *Mahārāja* Vishṇuvardhana IV. and grandson of Vikramarāma (i.e. Vijayāditya I.):—

(L. 20).—sū[r*]yyagrahaṇa-nimittē.

¹ Compare below, No. 600.

² I.e. Vishṇuvardhana I. Vishamasiddhi; the actual name is omitted in the grant.

³ Read -*dvitīya*-.

⁴ The two plates are numbered with numerical symbols. ⁵ Compare above, No. 9.

⁶ Compare below, No. 557 ff.

⁷ Read *viṣaḥ*.

555.—*Ind. Ant.* Vol. XIII. p. 186, and Plates. Ahadanakaram (formerly Sir W. Elliot's, now British Museum) Sanskrit and Telugu¹ plates of the E. Chālukya *Mahārāja Vishṇuvardhana V.* (*i.e.* Kali-Vishṇuvardhana²), the son of the *Mahārāja Vijayāditya II.* and grandson of the *Mahārāja Vishṇuvardhana IV.*

556.—*Ep. Ind.* Vol. V. p. 123, and Plate. Masulipatam (P, formerly Sir W. Elliot's) plates³ of the E. Chālukya *Mahārāja Vijayāditya III.* (who in battle slew Maṅgi), the son of the *Mahārāja Vishṇuvardhana V.* who was the son of the *Mahārāja Vijayāditya II.* (here also called Chālukya-Ārjuna⁴):—

(L. 27).—chandragrahaṇa-nimittē.

557.—*Ep. Ind.* Vol. V. p. 128, and Plate. Bezvāḍa plates⁵ of the E. Chālukya *Mahārāja-dhīrāja Bhīma I. Vishṇuvardhana* (also called Chālukya-Bhīma I.):—

(L. 20).—niḥpaṭṭabandha-samayē.

In the Chālukya family, Satyāśraya's⁶ brother Kubja-Vishṇuvardhana [Vishṇuvardhana I.] (reigned 18 years); his son Jayasīṃha [I.] (33 ys.); his younger brother Indra-bhaṭṭāraka's son Vishṇuvardhana [II.] (9 ys.); his son Maṅgi-yuvarāja (25 ys.); his son Jayasīṃha [II.] (13 ys.); his younger brother from a different mother, Kokkili (6 months); his eldest brother Vishṇuvardhana [III.]⁷ (37 ys.); his son Vijayāditya-bhaṭṭāraka [Vijayāditya I.] (18 ys.); his son Vishṇurāja [Vishṇuvardhana IV.] (36 ys.); his son Vijayāditya [II.] (40 ys.); his son Kali-Vishṇuvardhana [Vishṇuvardhana V.] (1½ ys.); his son Vijayāditya [III.] (44 ys.); Bhīma [*i.e.* Chālukya-Bhīma I.] is the son of his brother, the *Yuvarāja Vikramāditya I.*

558.—*Ep. Ind.* Vol. V. p. 132, and Plate. Masulipatam (now Madras Museum) plates of the E. Chālukya *Mahārāja Ammarāja I. Vishṇuvardhana*, recording a grant to Mahākāla, a general, and son of a foster-sister, of Ammarāja's grandfather Bhīma I.

Genealogy with lengths of reigns as far as Vijayāditya [III.] substantially as in No. 557. From his younger brother, the *Yuvarāja Vikramāditya I.*, sprang Bhīma [I., *i.e.* Chālukya-Bhīma I.] (who reigned 30 ys.); his son Vijayāditya [IV.] (6 months); his son Ammarāja [I.]

559.—*South-Ind. Inscr.* Vol. I. No. 36, p. 39. Êḍēru (now Madras Museum) plates of the E. Chālukya *Mahārāja Amma I. Vishṇuvardhana*, surnamed Rājamahēndra; recording a grant to one of the king's military officers named Bhaṇḍanāditya-Kuntāditya, of the Paṭṭavardhinī family.

Genealogy with lengths of reigns from Kubja-Vishṇuvardhana⁸ to Vishṇuvardhana [IV.] substantially as in No. 557. Vishṇuvardhana's son Vijayāditya [II.] (reigned 44 ys.); his son Kali-Vishṇuvardhana [Vishṇuvardhana V.] (1½ ys.); his son Vijayāditya [III.] (cut off the head of Maṅgi; frightened Kṛishṇa and Saṅkila, and burnt their city [Kiraṇapura];⁹ reigned 44 ys.); his younger brother Vikramāditya's son Chālukya-Bhīma¹⁰ [I.] (30 ys.); his son Vijayāditya¹¹ [IV.]; his son Amma [I.].

¹ The whole of the donative part of the grant is in Telugu.

² See below, No. 557 ff.

³ There is no information as to what has become of the plates.

⁴ He also is described as a fire of destruction to the Gaṅga family.

⁵ The plates are quasi-palimpsests.

⁶ *I.e.* Pulakēśin II., above, No. 9 ff.

⁷ Compare below, No. 634.

⁸ The inscription mentions an enemy of his, (a king) Daddara.

⁹ See *Ep. Ind.* Vol. IV. p. 226; the Kṛishṇa mentioned above is by Dr. Holtzsch suggested to be a Paramāra of Mālava; but he may be the Rāshtrakūṭa Kṛishṇarāja II. See below, No. 560.

¹⁰ Here also called Drōhārjuna.

¹¹ Here also called Kaliyarttyaṅka.

560.—*Ind. Ant.* Vol. XIII. p. 213, and Plates. Pāganavaram (formerly Sir W. Elliot's, now British Museum) plates of the E. Chalukya *Mahārājādhirāja* Chalukya-Bhīma II. Vishṇuvardhana, surnamed Gaṇḍamahēndra,¹ the son of Vijayāditya IV. and Mēlāmbā.

Genealogy with lengths of reigns as far as Vishṇuvardhana [IV.] substantially as in No. 557. His son Narēndramrigarāja [Vijayāditya II.] (reigned 48 ys.); his son Kali-Vishṇuvardhana [Vishṇuvardhana V.] ($1\frac{1}{2}$ ys.); his son Guṇaga-Vijayāditya [Vijayāditya III.] (slew Maṅgi, and burnt Kirāṇapura;² reigned 44 ys.); his younger brother the *Yuvarāja* Vikramāditya's son Chālukya-Bhīma [I.] (30 ys.); his son Vijayāditya [IV.] (6 months); his eldest son Ammarāja [I.] (7 ys.); having expelled his son Vijayāditya [V.], Tāha (one month); having slain him, Chālukya-Bhīma's son Vikramāditya [II.] (11 months); having defeated him, Amma's son Bhīma (8 months); having killed him, Tāha's eldest son Malla [Yuddhamalla II.] (7 ys.); having expelled him, [Chalukya-] Bhīma [II.].

561.—*Ep. Ind.* Vol. V. p. 135, and Plate. Masulipatam (? formerly Sir W. Elliot's, now British Museum) plates of the E. Chālukya *Mahārājādhirāja* [Chālukya-Bhīma³ II.] Vishṇuvardhana, the son of Vijayāditya IV. and Mēlāmbā :—

(L. 31).—uttarā[yapa-nim]ittē.

Genealogy with lengths of reigns as far as Vikramāditya [II.] substantially⁴ as in No. 560. The inscription then immediately goes on to the son of Mēlāmbā and Vijayāditya [IV.].

562.—*South-Ind. Inscr.* Vol. I. No. 37, p. 44. Kolaveṇṇu (now Madras Museum) plates⁵ of the E. Chālukya *Mahārājādhirāja* Chālukya-Bhīma II. Vishṇuvardhana, surnamed Rājamārtanḍa, the son of Vijayāditya IV. and brother of Ammarāja I. from a different mother; recording a grant made at the request of the prince Vājaya of the Pānara family :—

(L. 30).—uttarāyapa-nimittē.

Genealogy with lengths of reigns as far as Ammarāja [I.] substantially⁶ as in No. 560. His son Vijayāditya [V.] (reigned half a month); Tālāpa (one month); having conquered him, Chālukya-Bhīma's son Vikramāditya [II.] (one year); Chālukya-Bhīma [II.], the son of Vijayāditya [IV.] (conquered Tātabikyana and Dhaḷadi).

563.—*Ind. Ant.* Vol. VII. p. 15, and Plates. British Museum (? formerly Sir W. Elliot's) plates of the E. Chālukya *Mahārājādhirāja* Ammarāja II. Vijayāditya VI., the son of Chālukya-Bhīma II. and Lōkamahādēvi :⁷—

(L. 51).—sōmagrahaṇa-nimittam.

Genealogy with lengths of reigns as far as Ammarāja [I.] substantially⁸ as in No. 560. Having expelled his son Vijayāditya [V.], Tālāpa (reigned one month); having conquered him, Chālukya-Bhīma's son Vikramāditya [II.] (11 months); Tālāpa's son Yuddhamalla [II.] (7 ys.); having expelled him, Ammarāja's younger brother Bhīma [*i.e.* Chālukya-Bhīma II.] (12 ys.). His son Ammarāja [II.] assumed the crown in the 12th year of his life on the date—

(L. 31).—Giri-rasa-vasu-saṁkhyābdē Śaka-samayē Mārggaśirsha-māsē-smin kṛishṇa-trayōdaśa-dinē Bhṛiguvārē Maitra-nakshatrē || Dhanushi ravau Ghaṭa-lagnē.

[Ś. 867] : Friday, 5th December A.D. 945; see *ibid.* Vol. XXIII. p. 123, No. 62.

¹ Compare above, No. 126.

² See above, No. 559.

³ This name is not given in the inscription.

⁴ But Guṇaga-Vijayāditya is here called Guṇaga-Vijayāditya.

⁵ The grant on these plates was left incomplete.

⁶ But the length of the reign of Vijayāditya-II. Narēndramrigarāja is given as 40 years (*see* No. 557); and Guṇaga-Vijayāditya is called Guṇakenalla-Vijayāditya.

⁷ The poetry of the grant is by Mādhavabhaṭṭa.

⁸ But the length of the reign of Jayasimha I. is given (wrongly) as 30 years; Guṇaga-Vijayāditya is called Guṇagaṅka-Vijayāditya; and Vijayāditya IV. is called Kollabigaṇḍa-Vijayāditya.

564.—*Ep. Ind.* Vol. V. p. 140, and Plate. Masulipatam (now Madras Museum) plates of the E. Chālukya *Mahārāja Rājādhirāja*¹ Ammarāja II. Vijayāditya VI., surnamed *Rājamahendra*, the son of Chālukya-Bhīma II. and Lōkamahādēvi; recording a grant to the *Yuvārāja* Ball[ā]lādēva-Vēlābhata, also called Boḍḍiya, the son of (the lady) Pammavā of the Paṭṭavardhinī family.

Genealogy with lengths of reigns substantially² as in No. 563.

565.—*Ind. Ant.* Vol. XII. p. 91, and Plates. Elavarū plates³ of the E. Chālukya *Mahārājādhirāja* Ammarāja II. Vijayāditya VI., the son of Chālukya-Bhīma II. and Lōkamahādēvi:⁴—

(L. 54).—uttarāyana-nimittē.

Genealogy with lengths of reigns substantially as in No. 564.

566.—*Ind. Ant.* Vol. XIII. p. 249, and Plate. British Museum (formerly Sir W. Elliot's) plates of the E. Chālukya *Mahārājādhirāja* Ammarāja II. Vijayāditya VI., surnamed *Rājamahendra*, the son of Chālukya-Bhīma II. and Lōkamahādēvi; recording a grant made at the request of the king's wife's parents Kāma and Nāyamāmbā:⁵—

(L. 28).—uttarāyana-nimittē.

Genealogy with lengths of reigns as far as Bhīma (*i.e.* Chālukya-Bhīma I.) substantially as in No. 560. His son Kollabigaṇḍa-bhāskara [Vijayāditya IV.] (reigned 6 months); his eldest son Ambarāja [Ammarāja I.] (7 ys.); his eldest son Vijayāditya [V.] (half a month); having put him in prison, Tāla, the son of Yuddhamalla [I.] who was the paternal uncle of Chālukya-Bhīma [I.] (one month); Vikramāditya [II.] (1 y.); Kollabigaṇḍa's son Bhīma [Chālukya-Bhīma II.], surnamed Kaṇṇavillādāta (12 ys.); his son Ammarāja [II.].

567.—*South-Ind. Inscr.* Vol. I. No. 38, p. 47. Masulipatam (now Madras Museum) plates⁶ of the E. Chālukya *Mahārājādhirāja* Ammarāja II. Vijayāditya VI., the son of Chālukya-Bhīma II. and Lōkamahādēvi.

Genealogy with lengths of reigns as far as Ammarāja [I.] substantially as in No. 560. After him, Tālapa (reigned one month); having expelled him, Chālukya-Bhīma's son Vikramāditya [II.] (1 y.); Yuddhamalla [II.] (7 ys.); having expelled him, Ammarāja's younger brother [Chālukya-Bhīma [II.]] (12 ys.); his son Ammarāja [II.].

568.—*Ep. Ind.* Vol. VI. p. 351, and Plates. Raṇastipūṇḍī⁷ plates⁸ of the 8th year (of the reign) of the E. Chālukya *Mahārājādhirāja* Vimalāditya Vishṇuvardhana:⁹—

(L. 97).—aṣṭama-varsha-varddhanē Simha-m[ā*]sē.

Date of Vimalāditya's coronation:—

(L. 42).—Anal-ānala-randhra-gatē Śaka-varshē Vṛishabha-māsi sita-pakshē [I*] yash-shaṣṭhyām Guru-Pushyē Simhē lagnē prasiddham=abhishikṭaḥ [I(II)]

[Ś. 933]: Thursday, 10th May A.D. 1011; but the *tithi* which ended on this day was the 5th, not the 6th; see *ibid.* p. 349.

Mythical genealogy from Nārāyaṇa (Vishṇu), through the Moon, to Udayana who was the first of 59 kings of Ayōdhyā. Descended from them, Vijayāditya, was killed in battle with Trilōchana-Pallava; his posthumous son Vishṇuvardhana; his son (from a

¹ Perhaps a mistake for *Mahārājādhirāja*.

² But the length of the reign of Jayasīma I. is given (correctly) as 33 years; and Tālapa is called Tāl-ādhipa and Tāl-ādhipati.

³ The grant is partly a quasi-palimpsest.

⁴ The poetry of the grant is by Pōtanabhaṭṭa.

⁵ The poetry of the grant is by Mādhavabhaṭṭa.

⁶ They are all much worn, and of the third plate one entire half is lost.

⁷ This is the name of the village granted; the plates were found in the Amalāpuram tāluka and belong to an inhabitant of Amalāpuram.

⁸ The description of the boundaries of the village granted is in Sanskrit and Telugu.

⁹ The poetry of the grant is by Bhīmanabhaṭṭa.

Pallava princess) Vijayāditya; his son Polakēśivallabha (Pulakēśin I.); his son Kīrtivarman [I.]. Then genealogy with lengths of reigns from Kubja-Vishṇuvardhana to Yuddhamalla [II.] substantially¹ as in No. 563. Having expelled Yuddhamalla [II.], Rājabhīma (Bhīma, Chālukya-Bhīma [II.]), the younger brother of Ammarāja [I.], (reigned 12 years); his son Ammarāja [II.] (25 ys.); Dāna or Dānārṇava, his brother from a different mother (3 ys.); an interregnum of 27 years; Dāna's son Śaktivarman (12 ys.); after him Vimalāditya² (Tribhuvanāṅkuśa, Birudaṅka-Bhīma,³ Mummaḍi-Bhīma, Bhūpamahendra), the son of Dāna and Āryā-mahādēvi.

569.—*Ind. Ant.* Vol. XIV. p. 50, and Plates. Korumelli (formerly Sir W. Elliot's, now British Museum) plates⁴ of the E. Chālukya *Mahārājādhirāja Rājarāja I. Vishṇuvardhana*, the son of Vimalāditya and his wife Kundavā who was the younger sister of [the Chōla king] Rājendra-Chōḍa [I.] and daughter of [the Chōla king] Rājarāja [I.] of the solar race :⁵—

(L. 103).—imḍuparāgē.

Date of Rājarāja's coronation :—

(L. 65).—Yō rakshitum vasumatim Śaka-vatsarēshu vēd-āmburāsi-nidhi-varttiṣhu Simha-gē-rkkē [*] kṛishṇa-dvitiya-divavas-⁶Ottarabhadrikāyām varē Gurōr=Vvaṇṇi lagna-vai= bhishikṭah ||

[Ś. 944.]: Thursday, 16th August A.D. 1022; see *ibid.* Vol. XXIII. p. 131, No. 110.

Mythical genealogy, etc., as far as the interregnum substantially as in No. 568; Dāna's son Chālukya-Chandra [Śaktivarman] (reigned 12 ys.); his younger brother Vimalāditya (7 ys.); his son Rājarāja [I.].

570.—*Ep. Ind.* Vol. IV. p. 303. Madras Museum Sanskrit and Telugu⁷ plates (Nandamapūṇḍi grant) of the 32nd year of the reign of the E. Chālukya *Mahārājādhirāja Rājarāja I. Vishṇuvardhana*, the son of Vimalāditya and his wife Kundavā of the solar race :⁸—

(L. 78).—sōmagrahana-nimittē.

(L. 92).—dvātrimsattamē vijayarāja-varsh[ē] varddha[mā*]nē.

The lunar eclipse mentioned is probably that of the 28th November A.D. 1033 [in Ś. 975], which was visible in India; see *ibid.* p. 303.

Date of coronation and genealogy with lengths of reigns substantially as in No. 569.

571.—*Ep. Ind.* Vol. VI. p. 336, and Plates. Tēki plates⁹ of the E. Chālukya *Mahārājādhirāja Chōḍagaṅga Rājarāja Vishṇuvardhana*, ruler of Vēṅgi, of the 17th year of the reign (of Kulōttuṅga-Chōḍa I.); issued from Jananāthanagarī :—

(L. 108).—śrī-vijayarāja-saṁvatsara(rē) saptadaśē.

Date of Chōḍagaṅga's appointment as ruler of Vēṅgi :—

(L. 61).—Śāk-ābdē rasa-kh-āmbar-ēṁdu-gaṇitē Jyēshthē=dha(tha) māśē sitē pakshē pūrṇa(rṇa)-tidhau(thau) dinē Suragurōr=Jyēshthām śasāmkē gate [*] Śimha(hē) lagna-varē.

[For Ś. 1006] the date is irregular.

¹ But Indrarāja (Indra-bhaṭṭāraka) is here stated to have reigned for 7 days, and Tālapa is called Tādapa.

² He amongst others defeated the Śakas, Lātas and Gurjaras.

³ Compare Birudaṅka-Rāma, above, in No. 309, note.

⁴ The first plate is a quasi-palimpsest.

⁵ The poetry of the grant is by Chētanabhaṭṭa, the son of Bhīma (No. 568).—For the Chōla kings Rājarāja I. and Rājendra-Chōḍa (-Chōḍa I.) see below, Nos. 696 ff. and 721 ff.

⁶ Read -*divas*—.

⁷ The description of the boundaries of the village granted is in Telugu.

⁸ The poetry of the grant is by Nanniyabhaṭṭa.

⁹ Composed by Viddayabhaṭṭa; see Nos. 572 and 573.—The plates do not refer to a grant of land, but confer certain honorary privileges.

Genealogy, etc., as far as Vimalāditya substantially as in No. 569. His son Rājarāja [I.] (reigned 41 years), married Ammaṅgadēvi, the daughter of [the Chōḷa] Rājendra-Chōḷa [I.] of the solar race. Their son Rājendra-Chōḷa [II.], at first ruler of Vēṅgī, as Kulōttuṅga-Chōḷa I. was anointed in the Chōḷa kingdom.¹ He had many queens and from them several sons. He first appointed his son Mummaḍi-Chōḷa [Rājarāja] to the sovereignty of Vēṅgī (which had been held before by Kulōttuṅga's paternal uncle Vijayāditya [VII.]² for 15 years), and Mummaḍi-Chōḷa held it for one year. Kulōttuṅga then appointed the latter's younger brother Vira-Chōḷa, but recalled him after six years. He then appointed his eldest son Chōḷagaṅga.

572.—*South-Ind. Inscr.* Vol. I. No. 39, p. 53; *Ind. Ant.* Vol. XIX. p. 427. Chellūr (formerly Sir W. Elliot's, now British Museum) plates³ of the E. Chālukya *Mahārājādhirāja Vira-Chōḷa Vishṇuvardhana*, ruler of Vēṅgī, of the 21st year of the reign (of Kulōttuṅga-Chōḷa I.):⁴—

(L. 113).—śrī-vijayarājya-saṁvatsarē śvakavimsē.

Date of Vira-Chōḷa's appointment as ruler of Vēṅgī:—

(L. 76).—Śāk-ābdē śāśi-khadray-ēndu-gaṇitē Simh-ādhirūḍē(ḍhē) ravau chaṁdrē vṛddhimati trayōdasa-tithau vārē Gurōr=Vṛṣichikē [*] lagnē=tha Śrāvapē.

[Ś. 1001*]: Thursday, 23rd August A.D. 1078;⁵ see *Ind. Ant.* Vol. XXIV. p. 2, No. 128.

Genealogy, etc., as far as Kulōttuṅga (Kulōttuṅga-Chōḷa I.) substantially as in No. 571. He married Madhurāntaki, the daughter of [the Chōḷa] Rājendradēva, and appointed his son Vira-Chōḷa to the sovereignty of Vēṅgī (which had been held before by Kulōttuṅga's paternal uncle Vijayāditya [VII.] for 15 years, and by Vira-Chōḷa's elder brother [Mummaḍi-Chōḷa] Rājarāja for one year).

573.—*Ep. Ind.* Vol. V. p. 74; specimen plate in Dr. Burnell's *South-Ind. Palaeography*, 2nd ed., Plate xxix. Piṭhāpuram (now Madras Museum?) plates⁶ of the E. Chālukya *Mahārājādhirāja Vira-Chōḷa Vishṇuvardhana*, ruler of Vēṅgī, of the 23rd year of the reign (of Kulōttuṅga-Chōḷa I.):⁴—

(L. 186).—uttarāyana-nimitt[ā*].

(L. 279).—śrī-vijayarājya-saṁvatsarē tryutta[ra*]-vimsati-saṁvatsarē.

Date of Vira-Chōḷa's appointment as ruler of Vēṅgī and genealogy, etc., substantially⁷ as in No. 572.

574.—Ś. 1056 (for 1065).—*Ind. Ant.* Vol. XIV. p. 56, and Plates. Chellūr (formerly Sir W. Elliot's, now British Museum) plates⁸ of the reign of the E. Chālukya *Kulōttuṅga-Chōḷa II.*, recording a grant by his *Daṇḍādhirāja Kāṭa*, otherwise called *Kolani-Kāṭama-Nāyaka*, i.e. Kāṭama-Nāyaka of Kolani:—

(L. 49).—Śāk-ābdānām pramāṇē rasa-viśikha-viyach-chaṁdra-saṁkhyāṁ prayātē . . . s-Ādra-rkshē pūrvva-ma(pa)kshē vishuvati sutithā(thau).

For Ś. 1056 the date is irregular; for Ś. 1065 it regularly corresponds to the 24th March A.D. 1143;⁹ compare *Ep. Ind.* Vol. VII. p. 9.

¹ See below, No. 756 ff.

² See below, No. 754.

³ In the description of the boundaries the language is a mixture of Sanskrit and Telugu.

⁴ The poetry of the grant is by Viddayabhaṭṭa; see No. 571.

⁵ On this day the *tithi* of the date commenced 0 h. 30 m. after mean sunrise.

⁶ In the description of the boundaries the language is a mixture of Telugu and Sanskrit.—The grant is remarkable for the large number of donees (536 Brāhmins whose names are given).

⁷ But Guṇaga-Vijayāditya (probably by a mistake of the writer) is stated to have reigned 40 (instead of 45) years.

⁸ The writer of the date has written *rasa-viśikha* instead of *viśikha-rasa*.

Genealogy¹ with lengths of reigns from Kubja-Vishnupurvardhana to Ammarāja [II.] substantially² as in No. 563. Ammarāja [II.] (reigned 25 years); his eldest brother Dānārava (30 ys.); his son Śaktivarman (12 ys.); his younger brother Vimalāditya (7 ys.); his son Rājārāja [I.] (41 ys.); his son Kulōttuṅga-Chōḍa [I.] (49 ys.); his son Vikrama-Chōḍa (15 ys.); his son Kulōttuṅga-Chōḍa [II.].

575.—Ś. 1079.—Date of the coronation of Vijayāditya III., one of the E. Chālukyas of Piṭhāpuram, as given in the Piṭhāpuram inscription of Mallapadēva III. (below, No. 576):—

(L. 74).—Yō rājēmdū[h] Śak-[ā]bdē nidhi-jaladhi-[vi]yach-chamdra-gē Māgha-māsē śuklē pakshē dasamyāv(m)=Inatanaya-dinē Rōhiṇī-tārakā[yām] [Mi]nē [la]gnē=bhishi[kṭē]

Saturday, 11th January A.D. 1158; see *Ep. Ind.* Vol. IV. p. 228.

576.—Ś. 1124.—*Ep. Ind.* Vol. IV. p. 231, and Plate in Vol. VI. p. 270. Piṭhāpuram Sanskrit and Telugu pillar inscription of the *Mahārāja Malla* or *Mallapadēva III. Vishnupurvardhana alias Mallapadēva-Chakravartin*, E. Chālukya of Piṭhāpuram, dated on the day of his coronation:—

(L. 78).—Śāk-[ā]bdē vēda-nētra-kshiti-śasi-gapitē Śrēṣṭha-kṛishṇē [da*]śamyām Bhānū(nō)r-vvārē [su]-lagnē mahati Mrigapatāv=Aśvi-be(bhē) Piṭhapu[ryyām].

(L. 85).—Śakavarshambhu(bu)lu 11[2]4gu[nēm]ti Jyēṣṭha-ba[hu][la*]-dasamiyun-Ādivāramu nāmṭi Simhodayamuna!

Sunday, 16th June A.D. 1202; see *ibid.* Vol. IV. p. 228.

After giving the genealogy with the lengths of the reigns of the E. Chālukyas from Kubja-Vishnupurvardhana to Vikrama-Chōḍa (surnamed Tyāgasamudra, compare No. 807), the inscription gives the following genealogy of Mallapadēva: Bēta (Kaṇṭhikā-Bēta, or Vijayāditya³ [I.], who was the son of Ammarāja [I.] and had been expelled by Tāḍapa); his son Satyāśraya (Uttama-Chālukya), married Gaurī of the Gaṅga race; their sons Vijayāditya [II.], Vimalāditya, Vikramāditya, Vishnupurvardhana [I.], Mallapa [I.], Kāma, and Rājamārtanḍa. Of these, Vijayāditya [II.] married Vijayā of the solar race; their sons Vishnupurvardhana [II.], Mallapa [II.], and Sāmidēva. Of these, Mallapa [II.] married Chandaladēvi, the daughter of the Haihaya Brahman, lord of the Sagara-vishaya; their son Vijayāditya [III.] (crowned in Ś. 1079, see No. 575), married Gaṅgā, the daughter of the lord of [Āra]davāḍa; their son Malla (Mallapa [III.] Vishnupurvardhana).

577.—Ś. 1195.—*Ep. Ind.* Vol. V. p. 32. Śrīkūrmam pillar inscription of Vijayāditya II. a descendant of the E. Chālukya Rājārāja I.:—

(L. 19).—Svasti śrī-Śāka-varshē śara-nidhi-śasi-bhū-sammitē[=rkkē] Tulā-stē(sthē) Rudrāḥē Saumyavārē sita-yuji.

The date is irregular; see *ibid.* p. 34, note 3.

In the race of the Moon, the [E.] Chālukya Vimalāditya (above, No. 563); his son Rājārāja [I.] (translated into Andhra, i.e. Telugu, the history of the Bhārata race, i.e. the *Mahābhārata*; resided at Rājamāhēndrapaṭṭana). In his race, Vijayāditya [I.]; his son Rājārāja, was minister of Vira-Nṛsiṃha;⁴ his son Vijayāditya [II.].

578.—Ś. 1199.—*Ep. Ind.* Vol. V. p. 34. Śrīkūrmam Sanskrit and Telugu pillar inscription of (the E. Chālukya) Purushōttama, a son of Rājārāja (and brother of Vijayāditya II.; see No. 577):—

(L. 1).—Svasti śrī-Śāka-vatsarē [naya]-nidhi-kshōṇ-īndubhis=sammitē.

(L. 4).—Śāka-[va*]rshambulu || 1199yagunēmti.

¹ An introductory verse implies that the family belongs to the *Sōma-vāṃśa*.

² But Indrarāja (Indra-bhaṭṭāraka) is stated to have reigned for 7 days; and Tāḍapa is called Tāḍapa.

³ I.e. Vijayāditya V. of the E. Chālukya genealogy.

⁴ I.e. the E. Gaṅga king (of Kalinga) Narasiṃha I.; see *North. Ins.* No. 367.

579.—**Ś. 1231.**—*Ep. Ind.* Vol. V. p. 35. Śrīkūrmam Sanskrit and Telugu pillar inscription of the [3rd] year of the reign of the (E. Chālukya) *Sāmanā Viśvanātha* (*Jagannātha*), a son of Purushōttama (see No. 578); and of the reign of *Vira-Bāṇudē.a*:¹—

(L. 1).—Svasti śrī-Śāka-varshê śāsi-guṇa-ravi-gê ch=Ā[śvayuk-śu]kla-pakshê māsê Kauntēya-tithyān Suraguru-divasê.

(L. 11).—srī-Śāka-varshambhu(bu)lu 1231gunēm[tti] śrī-Jaga[n]āthadēvara vijaya-rājya-sam[vva]tsarambulu [3]gu śrāhi Kanya-śukla 5yu Guruvāramuna.

The date is irregular; see *ibid.* p. 36, note 4.

580.—**Ś. 1240.**—*Ep. Ind.* Vol. V. p. 36. Śrīkūrmam pillar inscription of (the E. Chālukya) *Purushōttama*, the brother of Vijayarka (*Vijayāditya* II.) who was a son of Rājārāja (see No. 577); (composed by Nṛsiṃha):—

(L. 5).—Śākê vyōma-yug-ô[shṇa]didi(dhi)ti-yut(tê) vasê(rshê) Nabhō-va(mâ)si.

581.—**Ś. 1093.**—*Ep. Ind.* Vol. VI. p. 269. Tsandavōlu² Sanskrit and Telugu pillar inscription³ of the *Mahāmaṇḍalēśvara* *Buddharāja* of *Koṇḍapaḍmaṭi*—surnamed *Aniyankabhīma* and *Eladāyasimha*, and described as ‘a worshipper of the feet of *Kulōttuṅga-Chōḍa*’ (i.e. the E. Chālukya *Kulōttuṅga-Chōḍa* II.)—of the *Durjaya* family:—

(L. 49).—Śāk-ābdê śakti-Namd-āmbara-śāsi-gaṇite . . . saumyāyanê.

(L. 70).—Śāka-varshambulu 1093nēmṭi [u]ttā(tta)rāyana-nimittamuna.

Buddhavarman (of the *Chaturthābhijana* or *Śūdra* caste) was a feudatory of *Kubja-Vishṇu*⁴ of the lunar race. After some ancestors had passed away, there was in his family *Maṇḍa* (*Maṇḍana*) [I.]; his son *Gaṇḍa*; his son *Maṇḍa* [II.], married *Kundāmbikā*; their son *Buddharāja* (whose sister *Aṅkama*⁵ was the wife of *Goṅka*’s⁶ son *Rājendra-Chōḍa*).

582.—**Ś. 1108.**—*Ep. Ind.* Vol. IV. p. 39, and Plate in Vol. VI. p. 270. *Piṭhāpuram* Sanskrit and Telugu pillar inscription of (the *Mahāmaṇḍalēśvara*) *Prithviśvara*⁷ of *Velanāṇḍu*, recording a grant by his mother *Jāyāmbikā*, the queen of the *Mahāmaṇḍalēśvara* *Goṅka* III.; (composed by *Ayyapillāya*):—

(L. 136).—Nāga-vyōm-ēṇḍu-rūpa-pramita-Śāka-saran-Mēshasaṁkrānti-kālê pu[nyê] . . .

(L. 139).—Śākava[r*]shāmbulu 1108gunēmṭi Mēshasaṁkrānti-nimittamuna.

The inscription gives the following genealogy⁸ of the family which belonged to the *Chaturthānvaya* or *Śūdra* caste: After a number of fictitious personages, *Malla* [I.]; his son *Eṇiyavarman*; his son *Kuṇḍiyavarman* [I.]; his son *Malla* [II.] *Piḍuvārāditya*; his son *Kuṇḍiyavarman* [II.] (feudatory of the E. Chālukya *Vimalāditya*; above, No. 568); his son *Eṇṇaya*; his son *Nannirāja*; his sons *Vedura* [I.,] *Gaṇḍa*, *Goṅka* [I.] (feudatory of the E. Chālukya *Kulōttuṅga-Chōḍa* I.), *Mallaya*, and *Paṇḍa*; *Gaṇḍa*’s son *Vedura* [II.] (feudatory of the E. Chālukya *Vira-Chōḍa*); *Goṅka*’s son *Chōḍa* (feudatory and adopted son of the E. Chālukya *Kulōttuṅga-Chōḍa* I.), married *Guṇḍāmbikā*; their son *Goṅka* [II.], married *Sabbāmbikā*; their son *Vira-Rājendra-Chōḍa*⁹ (*Rājendra-Chōḍa*, *Velanāṇṭi-Kulōttuṅga-Rājendra-Chōḍayarāja*), married *Akkāmbikā*; ¹⁰ their son *Goṅka* [III.] (*Kulōttuṅga-Manma-Goṅkarāja*), married *Jāyāmbikā* (*Jāyamāmbā*, *Jāyamadēvi*); their son *Prithviśvara*.

¹ I.e. the E. Gaṅga king (of *Kaliṅga*) *Bhānudēva* II.; see *North. Inscr.* No. 369.

² This is the modern name of *Dhanadapura* (*Dhanadaprōlu*), the capital of the chiefs of *Velanāṇḍu*; see below, No. 582.

³ For abstracts of 14 other inscriptions of the *Koṇḍapaḍmaṭi* chiefs and for the pedigrees derived from them see *Ep. Ind.* Vol. VI. p. 274 ff. Names of chiefs occurring in them, besides those given above, are *Chōḍa* (*Chōḍa-rāja*), *Eṇṇa-Maṇḍa*, *Malla* (*Mallerāja*), *Maṇḍerāja* and *Manma-Maṇḍa*.

⁴ I.e. the E. Chālukya *Kubja-Vishṇuvardhana*.

⁵ Called *Akkāmbikā* in No. 582.

⁶ I.e. *Goṅka* II. of No. 582.

⁷ See No. 583.

⁸ See *Ep. Ind.* Vol. IV. p. 35.

⁹ He killed a certain *Bhīma*, who had taken refuge on an island in a lake (probably the *Kollerulake*).

¹⁰ Called *Aṅkama* in No. 581.

583.—**Ś. 1117.**—*Ep. Ind.* Vol. IV. p. 87, and Plate in Vol. VI. p. 270. Piṭhāpuram Sanskrit and Telugu pillar inscription of the *Mahāmaṇḍalēśvara* **Mallidēva** and **Manma-Satya II.** of **Kōnamaṇḍala** (probably dependents of “Kulōttuṅga-Prithivīśvara¹ of Velanāṇḍu, who was again a vassal of [a king] Rājārāja, a descendant of the E. Chālukya dynasty”) :—

(L. 109).—Śaka-varṣaśambulu² 1117gunēṁṭṭi Mēśhasaṁkrānti-nimittamuna.

After giving the genealogy of the E. Chālukya dynasty with the lengths of the reigns as far as Maṅgi-yuvarāja, and a reference to a king Rājārāja of the Chālukya family who appears to be represented as reigning at the time, the inscription gives a genealogy of the chiefs of Kōnamaṇḍala who derived their descent from Kārtavīrya, the grandson of Haihaya, a descendant of Yadu. The names given are :³ Mummaḍi-Bhīma [I.]; Venna; Rājapaṇḍu [I.]; Mummaḍi-Bhīma [II.]; Rājendra-Chōḍa [I.]; Satya [I.] (Satyāśraya); Bēta; Mallidēva; Manma-Chōḍa [II.]; Sūrya; Lōkabhūpālaka (Lōkamahīpāla); Rājapaṇḍu [II.]; Bhīma [III.]; Vallabha; Manma-Satya [II.] (Manma-Satti); Mahīpāṇḍu.

584.—**Ś. 1084.**—*Ind. Ant.* Vol. XI. p. 12, and Plates. Anmakonḍa Sanskrit and Telugu pillar inscription of the **Kākatya (Kākatīya) Mahāmaṇḍalēśvara Rudradēva**, whose capital was Anumakonḍa (Anmakonḍa, Anmakunḍā); (composed by Achintāndravara, the son of Rāmēśvara-dīkshita and disciple of Advayāṁṛita) :—

(L. 6).—Śaka-varṣaśambulu 1084vunēṁṭṭi Chitrabhānu-saṁvatsara Māgha-śu 13 Vāḍḍa-vīramu nāmḍu.

Saturday, 19th January A.D. 1163;⁴ see *ibid.* Vol. XXIV. p. 2, No. 129.

In the Kākatya family, Tribhuvanamalla; his son Prōlērāja (Prōla; made captive the [W.] Chālukya Tailapadēva, *i.e.* Taila III.);⁵ defeated Gōvindarāja and Guṇḍa of Mantrakūṭa; conquered but re-instated king Udaya, *i.e.* Chōḍōdaya; put to flight Jagaddēva [compare No. 237] *etc.*, married Muppamadēvi; their son Rudradēva (subdued a certain Ḍomma, conquered Mailigidēva,⁶ burnt the city of Chōḍōdaya, *etc.*).

585.—**Ś. 1135.**⁷—*Ep. Ind.* Vol. V. p. 143. Chēbrōlu Sanskrit and Telugu pillar inscription of **Jāya (Jāyana)**,⁸ chief of the elephant-troop of the Kākatīya **Gaṇapati**⁹ (surnamed Chhala-mattigaṇḍa) who granted to Jāya ‘the city of Shanmukha’ (*i.e.* Tāmrapurī, Chēbrōlu) on the date here given :—

(L. 82).—Paṁchattrimśad-upēta-Rudra-śata-saṁkhyātē Śak-ābdē Madhau māsi Śrīmukha-yatsarē.

In the solar race, in the family of the Raghus, Durjaya; his son Bēta [Tribhuvanamalla]; after him, Prōla; his son Rudra; his brother Mahādēva; his son Gaṇapati.

586.—**Ś. 1153.**—*Ep. Ind.* Vol. III. p. 84, and Plate. Gaṇapēśvaram Sanskrit and Telugu pillar inscription of the time of the Kākatīya **Gaṇapati**, and of his general **Jāya (Jāyana, Jāyapa-Nāyaka)** :—

(L. 119).—Guṇa-śara-Bhava-mita-Śākē Khara-varṣhē Mādhavē sitē Gauryyāḥ | tithyām (thyām).

¹ *I.e.* the Prithivīśvara of No. 582.

² Read *varṣaśambulu*.

³ See *Ep. Ind.* Vol. IV. p. 85.

⁴ On this day the *tithi* of the date commenced 2 h. 29 m. after mean sunrise.

⁵ See above, No. 239 ff.—The inscription mentions the death of Taila III.

⁶ According to Dr. Hultzsch probably the Dēvagiri-Yādava Mallugi; see *Ind. Ant.* Vol. XXI. p. 198, and above Nos. 351 and 369.

⁷ The inscription itself may have been incised some years later, because it records works of piety accomplished by Jāya at Chēbrōlu.

⁸ For an account of another inscription of Jāya and his sovereign Gaṇapati, at Tsandavōlu, the capital of the chiefs of Velanāṇḍu, see *Ep. Ind.* Vol. V. p. 150.

⁹ Compare above, Nos. 343 and 369.

Prôla, residing at Annakonḍa, 'the family capital of the kings sprung from the race of Kâkati,' (defeated Mantena-Guṇḍa,¹ Tailapadêva, *i.e.* the W. Châlukya Taila III., and Gôvinda-Daṇḍêśa, and re-instated Chôḍôdaya), married Muppalaḍêvi; their sons Rudra and Mahâdêva. Rudra succeeded his father, and was succeeded by Mahâdêva, whose son by Bayyâmbikâ was Gaṇapati. Gaṇapati (who had defeated the kings of Chôḷa, Kalinga, Sêvaṇa,² Karṇâṭa and Lâṭa, and conquered the country of Velanânḍu) married Nârama (Nârâmbâ) and Pêrama (Pêramâmbâ), the elder sisters of Jâya (whose genealogy is given).

587.—*Ś. 1157.*—*Ep. Ind.* Vol. VI. p. 39. Chêbrôlu Sanskrit and Telugu pillar inscription of the general Jâya (Jâyaṇa), for the greatest part identical with No. 586:—

(L. 142).—giri-sara-kshmâ-chaṇdra-saṁkhyêṁ³ Śakêṇḍr-âbdê Mâdhava-mâsa-
sûdtha-(ddha)-Girijâ-tithyâm Śanêr=vâsarê.
Saturday, 21st April A.D. 1235.⁴

588.—*Ś. 1172*.*—*Ind. Ant.* Vol. XXI. p. 200. Conjeeveram (Ēkâmrânâtha temple) inscription of the Kâkatîya Gaṇapati,⁵ and his minister and general Sâmantâ-Bhôja:⁶—

(L. 13).—Śâk-âbdê tu dvisaptaty-adhika-Śiva-sata-khyâta-saṁkhyâna-mânê Sapmy-âbdê
Śrêshṭha-mâsê bahula-Hari-dinê Bhaumavârê samê=hni.

Tuesday, 8th June A.D. 1249; see *ibid.* Vol. XXIII. p. 130, No. 104.

In the solar race, king Betmarâja [Tribhuvanamalla]; after him, Prôḍarâja Jagatikêśarin; after him, Rudradêva; his younger brother Mahâdêva; his son Gaṇapati (defeated [the Dêvagiri-Yâdava] Siṁhaṇa (Siṁghaṇa),⁷ the Kalinga king, *etc.*).

589.—[*Ś. 1172**].⁸—*Ep. Ind.* Vol. III. p. 96. Yenamadala fragmentary Sanskrit and Telugu pillar inscription of the Kâkatîya princess Gaṇapâmbâ, recording the building of temples, *etc.*, in honour of her deceased husband Bêta and of her father Gaṇapati.

In the family of the Kâkatîśas (Kâkatîyas), Prôla; his son Mâdhava (*i.e.* Mahâdêva, was killed in battle); his son Gaṇapati (Gaṇapa); his daughter Gaṇapâmbâ (Gaṇapâmbikâ), was married to Bêta, the son of Rudrarâja and grandson of Kêtarâja,⁹ lord of the Konnâtavâḍi-vishaya (residing at Śrî-Dhânyâṅkapura, *i.e.* Amarâvatî).

590.—*Ś. 1104.*—*Ep. Ind.* Vol. VI. p. 148. Amarâvatî Sanskrit and Telugu pillar inscription of the *Mahâmaṇḍalêśvara Kêta II.* (Kôṭa-Kêtarâja), 'lord of Śrî-Dhânyakâṭaka':¹⁰—

(L. 103).—Śâk-âbdê yuga-kh-êṇḍu-rûpa-gaṇitê Mâghê daśamyâm tithau sūklâyâm Guru-vâsarê.

This date¹¹ (though repeated four times) is irregular; see *ibid.* p. 147, note 6.

In the city of Śrî-Dhânyakâṭaka, in a family of kings born from the feet of the Creator (*i.e.* in the Śûdra caste), was Bhîma [I.]; his son Kêta [I.]; his son Bhîma [II.], married Sabbamâḍêvi (Sabbamâḍêvi); their son Kêta [II.],¹² whose elder brother was Chôḍerâja.

¹ In No. 587 the name is spelt *Manthena-Guṇḍa*.

² *I.e.* the Dêvagiri-Yâdavas; compare No. 588.

³ Read *-saṁkhyê*.

⁴ On this day the *tithi* of the date (as a *kṣhaya-tithi*) commenced 0 h. 51 m. and ended 22 h. 7 m. after mean sunrise.

⁵ Compare below, No. 904.

⁶ For a short inscription of his at Kâlâhasti, according to which his father was the minister Dêchi and his mother Vâchâmbâ, see *Ep. Ind.* Vol. III. p. 93.

⁷ Compare above, Nos. 343 and 369.

⁸ See *Ep. Ind.* Vol. III. p. 95.

⁹ *I.e.* Kêta II. of No. 590.

¹⁰ Dhânyakâṭaka is the old name of the present Amarâvatî.

¹¹ Probably the day of the king's accession.

¹² See above, No. 589.

591.—Ś. 1123.—*Ep. Ind.* Vol. VI. p. 159. Bezvāḍa Telugu pillar inscription of the *Mahāmaṇḍalēśvara Rudradēvarāja*¹ of Maḍapalla in Nātavāḍi, the son of Buddarāja, who was the brother-in-law of the Kākatiya king Gaṇapati :—

(L. 1).—Śaka-va[r*]shambulu 1123[ḍa]gu Durmukhi-saṁvatsara-Vaiśākha-sudhdha(ddha) 15 Guruvāramuna.

Thursday, 19th April A.D. 1201.²

592.—Ś. 1156.—*Ep. Ind.* Vol. VI. p. 157. Amarāvati Sanskrit and Telugu pillar inscription of Bayyamāmbā (Kōṭa-Bayyalamahādēvi),³ the daughter of the *Mahāmaṇḍalēśvara Rudradēva-mahārāja*, the son of Buddha and grandson of Durga, who belonged to the Chaturtha-kula or Śūdra caste and resided at Maḍapalli in the Nāthavāḍi (or Nāthavāṭi) district :⁴—

(L. 212).—Śāk-ābdē tarkka-bāpa-kshiti-ra(śa)śi-gaṇitē vatsarē-smim⁵ Jay-ākhyē Jyēshthē mā[=l]jyavārē Muraripu-divasē śukla-pakshē prasa[stē].

Thursday, 11th May A.D. 1234.

593.—Ś. 1296.—*Ep. Ind.* Vol. III. p. 288. Naḍupūru⁶ (formerly Sir W. Elliot's, now British Museum?) Sanskrit and Telugu plates⁷ of Anna-Vēma of the Redḍi dynasty of Koṇḍaviḍu, recording a grant made for the spiritual benefit of his sister Vēmasāni :—

(L. 28).—Śāk-ābdē rasa-ratna-bhānu-1296-gaṇi[tē] grastē vidhau Rāhu[r]ā Kārt[t*]ikyām.

The date is irregular; see *ibid.* p. 287.

In the caste sprung from Viṣṇu's foot (*i.e.* the fourth or Śūdra caste) was king Prōla; his son Vēma; his son Anna-Vōta; his younger brother Anna-Vēma (Ana-Vēma, surnamed Vasantarāya and Pallava-Trinētra); his sister Vēmasāni, was married to a prince Nallanūka.

594.—Ś. 1300 (for 1301).—*Ep. Ind.* Vol. III. p. 60, and Plate. Vānapalli (now Madras Museum) plates of Anna-Vēma of the Redḍi dynasty of Koṇḍaviḍu; (composed by Trilōchanārya) :—

(L. 41).—Śāk-ābdē gagan-ābhra-viśva-gaṇitē Sidhdhā(ddhā)rdhhi(rthi)-saṁvatsarē Māghē kṛishṇa-chaturddāśi-Śiva-tidhau(thau).

Genealogy of Anna-Vēma (Ana-Vēma, here surnamed Jaganobbagaṇḍa,⁸ Kshurikākali-vēṭāla, and Karpūravasantarāya) as in No. 593.

595.—Ś. 1313.—*Ep. Ind.* Vol. IV. p. 328, and Plate in Vol. VI. p. 270. Piṭhāpuram Sanskrit and Telugu pillar inscription of the Redḍi Vēma (Kāṭamareḍḍi-Vēmireḍḍi, *i.e.* Kāṭaya-Vēma), the son of Kāṭa II. (Kāṭamareḍḍi) and Doḍḍasāni-amma (a daughter of Anna-Vōta [of Koṇḍaviḍu]), grandson of Māra, and great-grandson of Kāṭaya I. :—

(L. 4).—Śaka-varshambulu 1313agunēmti Prajāpati-saṁvatsara-Pushya-śu 2 Gu | nāmṭi Makarasamkrānti-[pu]nyakālamamdu.

Thursday, 28th December A.D. 1391; see *ibid.* Vol. IV. p. 328.

596.—Ś. 1333.—*Ep. Ind.* Vol. IV. p. 321. Tottaramūḍi (now Madras Museum) Sanskrit and Telugu plates⁷ of Vēma (Kāṭaya-Vēma) of Rājamahēndranagara, minister of Kumāragiri of Koṇḍaviḍu; (composed by Śrīvallabha, the son of Śrīvallabhārya and Lakshmi) :—

(L. 45).—Śrī-Śākē guṇa-Rāma-viśva-gaṇitē Kārt[t*]iky-ahē-bdē Kharē.

¹ Compare below, No. 592.

² On this day the *tithi* of the date commenced 1 h. 38 m. after mean sunrise.

³ According to Dr. Hultzsch, she very probably was one of the wives of Kēta II. in No. 590.

⁴ See above, No. 591.

⁵ Read =smim=.

⁶ This is the name of the village granted; the grant was edited from Sir W. Elliot's impressions.—Naḍupūru (Vēmapura) was in Kōṇasthala.

⁷ The plates are numbered with Telugu numeral figures.

⁸ *I.e.* 'the only hero in the world.'

In the *Paṇṭa kula* of the fourth caste, Vēma, surnamed Jaganobbagaṇḍa;¹ his son Ana-Vōta (Anna-Vōta); his younger brother Anna-Vēma (Ana-Vēma, surnamed Vasantarāya, and Kshurikāśahāya); Ana-Vōta's son Kumāragiri, resided at his capital of Koṇḍaviṭṭu.—His minister Kāṭaya-Vēma (Kāṭaya-Vēmaya)² received from him the eastern country with Rājamahēndranagari as capital.

597.—**Ś. 1336.**—*Ep. Ind.* Vol. IV. p. 329. Drākshārāma Sanskrit and Telugu pillar inscription of a subordinate of Vēma (Kātamareḍḍi-Vēmāreḍḍi, i.e. Kāṭaya-Vēma):—

(L. 10).—Śaka-varshambulu 1336agunēnti Jaya-samvatsara-Kārt[ti]ka-śu 15 Bhā | nāmḍu.

Sunday, 28th October A.D. 1414; see *ibid.* p. 328.

The inscription mentions a son of Vēma's, named, in Telugu, Komaragirireḍḍi.

598.—**Ś. 1328** (for 1338).—*Ep. Ind.* Vol. IV. p. 330. Drākshārāma Sanskrit and Telugu pillar inscription of the wife of the subordinate, mentioned in No. 597, of Vēma (i.e. Kāṭaya-Vēma):—

(L. 15).—Śaka-varshambulu 1328[a]gunēnti Durmmukha-samvatsara-Chaitra-[śu] 11 Sō | nāmḍu.

Monday, 9th March A.D. 1416; see *ibid.* p. 328.

This inscription also mentions Vēma's son Komaragirireḍḍi.

599.—**Ś. 1352.**—*Ep. Ind.* Vol. V. p. 57. Koṅkuduru (now Madras Museum) Sanskrit and Telugu plates³ of the Reḍḍi Dodḍa II. (Allaya-Dodḍa) of Rājamahēndranagara:—

(L. 45).—Śri-Śākē kara-bhāṇa-viēva-gaṇitē Sādhārāṇē vataṇṇē Paushē-rdhōdaya-nāmnī puṇya-samayē.

Sunday, 14th January A.D. 1431; see *ibid.* p. 55, and *Ind. Ant.* Vol. XXV. p. 345, No. 2.

In the *Paṇṭa kula* of the fourth caste, Dodḍa [I.] of the [Po]lvōla gōtra; his sons Annavrōla, Kōṭaya and Alla (Allāḍa). Of these, Alla married Vēmāmbikā (a daughter of a Chōḍa prince Bhīma), and had four sons, Vēma, Virabhadra, Dodḍa [II.] and Anna. The eldest of these, Vēma (Allaya-Vēma), had for his capital Rājamahēndranagara, of which he was joint ruler with Virabhadra. Their younger brother Dodḍa [II.] (Allaya-Dodḍa, Allāḍareḍḍi-Dodḍa) had the surnames Karpūrasantarāya, Saṅgrāmabhīma and Jaganobbagaṇḍa.⁴

600.—**Ś. 1191.**—*Ep. Ind.* Vol. V. p. 110, and Plates. Dibbida (now Madras Museum) plates⁴ of Arjuna of the Matsya family of Oḍḍavāḍi:⁵—

(L. 31).—Śāk-ābdē chaṇdra-ramdhra-kshiti-śāsi-gaṇitē y-ākshay-ādyā tṛtīyā(yā) Vaiśākhē māsi tasyām Ravisuta-divasē.

Saturday, 6th April A.D. 1269; see *ibid.* p. 109.

A mythical being, named Satyamārtapḍa, was appointed by Jayatsēna, the lord of Utkala, to rule over the Oḍḍavāḍi country, and founded the Matsya family. In this family there were: Bhīma's younger brother Gaṅga; his son Vallabha; his son Yuddhamalla; his son Gōṇaṅga [I.]; his son Bhīma [I.]; his son Rēvaṇa [I.]; his son Kokkila; his son Guḍḍa [I.]; his son Āditya; his son Kaṇḍi [I.]; his sons Ehīma [II.] and Rēvaṇa [II.]; Rēvaṇa's sons Gōṇaṅga [II.] and Guḍḍa [II.]; Guḍḍa's son Kaṇḍi [II.]; his son Ārya (did not reign); his son Paragaṇḍa; his sons Guḍḍa [III.] and Bhīma [III.]; Bhīma's son Nṛsiṃha; his son Maṅkāḍitya; his son Bhīma [IV.]; his younger brother Jayanta, married Chitgamāmbā; their son Arjuna.

¹ See above, No. 594, note.

² For his genealogy see No. 595; his mother's name here is Dodḍāmbikā; his wife was Mallāmbikā (a sister of Kumāragiri).

³ The plates (excepting the 5th and 7th) are numbered with Telugu numeral figures.

⁴ The plates are numbered with Telugu numeral figures.—The text contains some Telugu words.

⁵ See Mr. Venkayya's *Report* for 1899-1900, p. 32.

601.—*Ś. 1258* (for 1260 ?).—*Ep. Ind.* Vol. IV. p. 358, and Plates in Vol. V. p. 265. Donepūṇḍi¹ (now Madras Museum) Sanskrit and Telugu plates of the *Sāmanta Nāmaya-Nāyaka* (*Nāmi-Nēni*), surnamed *Pagamechchuganḍa*² (the son of *Prōlaya-Nāyaka* and *Chōdamāmbā*, and grandson of *Koppulakāpa-Nāyaka*), of *Piṭhāpuri*:—

(L. 31).—*Śāk-ābdē* *Namda-bāṇ-ārka-mitē* *Bhādrapadē tathā* | *paurṇma*(*rṇṇa*)*māsyām* *Ravē-vvārē*.

Probably Sunday, 30th August A.D. 1338; see *ibid.* Vol. IV. p. 358.

K.—The Kadambas.³

602.—*Ind. Ant.* Vol. VI. p. 23, and Plate; *PSOCI.* No. 2. *Halsī* (now Dr. Fleet's) lates of the Kadamba *Yuvarāja Kākusthavarman*, of the 80th year; issued at *Palāśikā*:—

(L. 4).—*svavaijayikē* *asītitamē* *saṁvatsarē*.

603.—*Ep. Carn.* Vol. IV. Introduction, p. 1. Notice of a *Tālgund* pillar inscription,⁴ recording the foundation of a tank by the Kadamba *Kākustha* (*Kākusthavarman*); (composed by *Kubja* by order of *Kākusthavarman*'s son *Śāntivarman*).

In the Kadamba family was the *Brāhmaṇ* *Mayūrasarman*⁵ (who was anointed ruler of a tract of country by the *Pallavas*⁶ of *Kāñchī*); his son *Kaṅg[a]*varman; his son *Bhagīratha*; his son *Raghu*; his brother *Kākustha*; his son *Śāntivarman*.

604.—*Ind. Ant.* Vol. VII. p. 35, and Plate; *PSOCI.* No. 3. *Dēvagēri* plates of the 3rd year of the reign of the Kadamba *Mahārāja Mṛigēsavaravarman* (*Mṛigēsavarman*), the son of *Śāntivaravarman*, of the lineage of *Kākustha*; issued at *Vaijayantī*:—

(L. 7).—*ātmanah* *rājyasya* *tritīyē* *varshē* *Paushē* *saṁvatsarē* *Kārttikamāsa-bahulapakshē* *daśamyām* *tithau* *Uttarābhadrapadē* *nakshatrē*.⁷

605.—*Ind. Ant.* Vol. VII. p. 37, and Plates; *PSOCI.* No. 4. *Dēvagēri* plates of the 4th year (of the reign) of the Kadamba *Dharmamahārāja Vijaya-Śiva-Mṛigēsavarman*,⁸ issued at *Vaijayantī*:—

(L. 4).—*Mṛigēsavarmanah* *vijay-āyur-ārōgy-aśvarya-pravarddhana-karah* *saṁvatsarah* *chaturtthah* *varshā-pakshah* *ashtamah* *tithih* *paurṇamāsī* *anay-ānupūrvyā*.

606.—*Ind. Ant.* Vol. VI. p. 24, and Plate; *PSOCI.* No. 5. *Halsī* (now Dr. Fleet's) plates of the 8th year (of the reign) of the Kadamba king *Mṛigēśa* (*Mṛigēsavarman*), the eldest son of *Śāntivaravarman* who was a son of *Kākustha*; issued at *Vaijayantī*:—

(L. 10).—*svavaijayikē* *ashtamē* *Vaiśākhē* *saṁvatsarē* *Kārttika-paurṇamāsyām*.

607.—*Ep. Ind.* Vol. VI. p. 14, and Plate. *Kūḍgere* plates of the 2nd year (of the reign) of the Kadamba *Dharmamahārāja Vijaya-Śiva-Māndhātivarman*, issued at *Vaijayantī*:—

(L. 6).—*saṁvatsarē*⁹ *dvitīyē* *Vaiśākha-paurṇamāsyām*.

¹ This is the name of the village granted by this record.—The plates are numbered with Telugu numeral figures.

² *I. e.* 'the destroyer of the pride of adversaries.'

³ For the later Kadambas see above, p. 26, note 1, c.

⁴ I owe a photograph (furnished by Mr. Rice) of the inscription to Dr. Fleet.—Compare Dr. Fleet's *Dynasties*, p. 286, and *Nachrichten Ges. d. Wiss. Göttingen*, 1899, p. 182.

⁵ Compare above, No. 210.—The genealogical Table in *Ep. Carn.* Vol. VI. Introduction, p. 4, is incorrect.

⁶ See below, No. 616 ff.

⁷ Here either the *nakshatra* *Uttara-Bhadrapadā* has been quoted erroneously instead of *Uttara-Phalgunī*, or *bahula-pakshē* is a mistake for *śukla-pakshē*. Compare Nos. 480 and 853.

⁸ For other (*Hitṛahebbāgilu*) plates of the 7th year (of the reign) of the same king see *Ep. Carn.* Vol. IV. p. 136, No. 18, and Plates.

⁹ Read *saṁvatsarē*.

608.—*Ind. Ant.* Vol. VI. p. 25, and Plates; *PSOCL.* No. 6. Halsi (now Dr. Fleet's) plates of the Kadamba king **Ravi (Ravivarman)**, recording grants and ordinances made at Palāsikā. The inscription mentions the king's predecessors Kākusthavarman, Śāntivarman, and Mrigēśa.

609.—*Ind. Ant.* Vol. VI. p. 29, and Plate; *PSOCL.* No. 8. Halsi (now Dr. Fleet's) plates of the Kadamba king **Ravi (Ravivarman)** (who conquered Vishṇuvarman¹ and other kings), residing at Palāsikā.

610.—*Ind. Ant.* Vol. VI. p. 28, and Plate; *PSOCL.* No. 7. Halsi (now Dr. Fleet's) plates of the 11th year of the reign of the Kadamba *Dharmamahārāja* **Ravivarman**, the son of Mrigēśa who was the eldest son of Śāntivarman, the son of Kākustha; recording donations made by Ravivarman's younger brother **Bhānuvarman**, at Palāsikā :—

(L. 11).—pravarddhamānārājya-śrī- Ravivarmanma-dharmamahārājasya ēkādaśē saṁvatsarē hēmantā-shashṭha-pakṣhē daśamyām tithau.

611.—*Ind. Ant.* Vol. VI. p. 30, and Plate; *PSOCL.* No. 9. Halsi (now Dr. Fleet's) plates of 4th year of the reign of the Kadamba *Mahārāja* **Harivarman**, recording donations made by him at the advice of his paternal uncle **Śivaratha**; issued at Uchchaśringī :—

(L. 6).— svarājya-saṁvatsarē chaturthē Phālguna(na)-śukla-trayōdaśyām.

612.—*Ind. Ant.* Vol. VI. p. 31, and Plate; *PSOCL.* No. 10. Halsi (now Dr. Fleet's) plates of the 5th year of the reign of the Kadamba *Mahārāja* **Harivarman**, the son of the *Mahārāja* Ravivarman, recording donations made at the request of king **Bhānuśakti** of the family of the Sēndrakas; issued at Palāsikā :—

(L. 8).— svarājya-saṁvatsarē pañchamē.

613.—*Ind. Ant.* Vol. VII. p. 33, and Plate; *PSOCL.* No. 1. Dēvagēri plates of the *Yuvarāja* **Dēvavarman**, son of the Kadamba *Dharmamahārāja* **Kṛishṇavarman** [I. ?]; issued at Tripavata.

614.—*Ep. Ind.* Vol. VI. p. 18, and Plate. Bannahalli (now Halēbīd) plates of the 7th year of the reign of the Kadamba *Mahārāja* **Kṛishṇavarman II.**, the son of the *Mahārāja* **Siṁhavarman**, who was a son of the *Dharmamahārāja* Vishṇuvarman,² who was begotten by the *Dharmamahārāja* **Kṛishṇavarman I.** on a daughter of Kaikēya :—

(L. 13).— varddhamāna-vijayarājya-saṁvatsarē saptamē Kārttika-māsē āpūryyamāṇa-pakṣhē pañchamyām Jyēsthā-nakṣatrē.

615.—*Ind. Ant.* Vol. XXI. p. 93. Konṇūr rock inscription of the Kadamba king **Dāmōdara**.

L.—The Pallavas, Gaṅga-Pallavas, Bāṇas and Gaṅga-Bāṇas.³

616.—*Ind. Ant.* Vol. IX. p. 101, and Plate. Guṇṭūr district (formerly Sir W. Elliot's, now British Museum) Prākṛit plates⁴ of the queen of the Pallava *Yuvaramahārāja* **Vijaya-Buddhavarman**, of the reign of the *Mahārāja* **Vijaya-Skandavarman** :—

(L. 1).— Sīri-Vijayakhandaṁmahārājassa saṁvachhara

¹ Perhaps the Vishṇuvarman of No. 614. See also Dr. Fleet's *Dynasties*, p. 322.

² For (Bīrūr spurious?) plates of the *Dharmamahārāja* Vishṇuvarman, the eldest son of the *Dharmamahārāja* **Kṛishṇavarman**, recording a grant made with the permission of Vishṇuvarman's father's eldest brother (*jyēsthā-pitṛi*), the *Dharmamahārāja* Śāntivaravarman, see *Ep. Carn.* Vol. VI. p. 91, No. 162, and Plates.

³ Nos. 616-643; 644-658; 659-668; and 669-671.

⁴ The three plates are numbered (wrongly) with numerical symbols.— Compare also *Ep. Ind.* Vol. I. p. 2, notes.

617.— *Ep. Ind.* Vol. VI. p. 86, and Plates.¹ Mayidavôlu (now Madras Museum) Prâkrit plates² of the Pallava Yuvamahârâja Śivaskandavarman, of the 10th year (of the reign of his predecessor); issued from Kâñchîpura :—

(L. 25).— sa[m]vachhara[m] dasama 10 gimhâ pakho chhaṭho 6 divasa pañchami 5.³

618.— *Ep. Ind.* Vol. I. p. 5, and Plates. Hirahadagalli Prâkrit plates⁴ of the 8th year (of the reign) of the Pallava Dharmamahârâjâdhirâja Śivaskandavarman, issued from Kâñchîpura :—

(L. 49).— samva 8 vâsa 6 diva 5.³

619.— *Ind. Ant.* Vol. V. p. 51, and Plates; *PSOCI.* No. 267. Ururupalli⁵ plates of the Pallava Dharmayuvamahârâja Vishṇugôpavarman, the son of the Mahârâja Skandavarman II., grandson of the Mahârâja Viravarman, and great-grandson of the Mahârâja Skandavarman I.; of the 11th year (of the reign) of the Mahârâja Simhavarman I.; issued from Palakkada :—

(L. 33).— Simhavarmma-mâ(ma)hârâjasya vijaya-samvatsarê êkâdasê Paushya(sha)-mâsê krishṇa-pakshê dasamyâm.

620.— *Ind. Ant.* Vol. V. p. 155, and Plates. Mângaḷûr⁶ plates of the 8th year of the reign of the Pallava Dharmamahârâja Simhavarman II., the son of the Yuvarâja Vishṇugôpa (Vishṇugôpavarman), grandson of the Mahârâja Skandavarman II., and great-grandson of the Mahârâja Viravarman; issued from Daśanapura :—

(L. 26).— samêdhamâna-vijayarâjy-âṣṭama-samvatsara-Chaitramâsa-śuklapaksha-pañchamyâm.

621.— *Ep. Ind.* Vol. III. 145; *Ind. Ant.* Vol. VIII. p. 168, Plates. Udayêndiram (spurious?) plates of the first year of the reign of the Pallava Dharmamahârâja Nandivarman, the son of the Mahârâja Skandavarman, grandson of the Mahârâja Simhavarman, and great-grandson of the Râjâ Skandavarman; issued from Kâñchîpura :—

(L. 19).— pravardhamâna-ve(vi)je(ja)yarâjya-prata(tha)[ma*]-sa[mva*]tsarê Va(vai)-śâka(kha)-mâsê śukuksh[ê]⁸ pañchamyâ[m*].

The plates contain a Tamil endorsement of the 26th year (of the reign) of king Parakêśarivarman who took Madirai, i.e. the Chôla king Parântaka I.⁹

622.— *Ep. Ind.* Vol. I. p. 398, and Plate. Darśi (now Madras Museum) first plate only of a great-grandson of the [Pallava] Mahârâja Virakôrchavarman, issued from Daśanapura.

623.— *South-Ind. Inscr.* Vol. II. No. 72, p. 341, and Plate. Vallam cave Tamil inscription, recording the foundation of a temple by Skandasêna, the son of Vasantapriyârâja, a vassal of Paṅḍipidugu¹⁰ Lalitâñkura Śatrumalla Guṇabhara Mahêṇdrapôtarâja (i.e., probably, the Pallava Mahêṇdravarman I.).

624.— *Ep. Ind.* Vol. IV. p. 153, and Plate. Mahêṇdravâḍi inscription of Guṇabhara (Mahêṇdra), (i.e., probably, the Pallava Mahêṇdravarman I.).

¹ For the seal see *Ep. Ind.* Vol. VI. Plate facing p. 294.

² Plates ii. to viii. are numbered with numerical symbols. The alphabet closely resembles that of No. 1014.

³ These numbers are denoted by numerical symbols.

⁴ The (eight) plates are numbered with numerical symbols.— See also *Ep. Ind.* Vol. II. p. 483.

⁵ This is the name of the village granted; the inscription was edited from Sir W. Elliot's impressions. The plates are numbered with numerical symbols.

⁶ The inscription records a grant to a temple founded by a *Sêṇḍapati* Vishṇuvarman. See the same name above, in Nos. 609 and 614.

⁷ See *Ind. Ant.* Vol. XXX. p. 215, No. 9.

⁸ See below, No. 634 and No. 681 ff.

⁹ Read *śukla-pakshê*.

¹⁰ I.e. 'the thunderbolt which cannot be split.'

625.— *South-Ind. Inscr.* Vol. I. Nos. 33 and 34, p. 29 f., and Plate x. facing Vol. II. p. 340; *Ep. Ind.* Vol. I. p. 59 f. Trichinopoly cave inscriptions of the Pallava **Guṇabhara** (**Satya-saṁdha**, **Śatrumalla**, **Purushōttama**), (*i.e.*, probably, the Pallava **Mahēndravarman I.**).

626.— *Ep. Ind.* Vol. VI. p. 320, and Plate. Śīyamaṅgalam cave inscription of **Lalitāṅkura** (*i.e.*, probably, the Pallava **Mahēndravarman I.**), recording the construction of a temple called **Avanibhājana-Pallavēśvara**.

627.— *Ind. Ant.* Vol. IX. p. 100, and Plate; *PSOOL* No. 38. Bādāmi fragmentary rock inscription of the time of the Pallava [**Narasim**]havishṇu (? *i.e.* **Narasimhavarman I.** ?):¹—
(L. 1).— . . . [saṁ]vatsarē ātmanō rājya-varshē cha varddhamānē bra[yōdaśē] .

The fragment contains the epithet or *biruda* **Mahāmalla**,² and the name **Vātāpi**.

628.— *South-Ind. Inscr.* Vol. I. No. 151, p. 148; Vol. II. Plates xi. and xii. Kāram Sanskrit³ and Tamil plates of the Pallava king **Paramēśvaravarman I.** (who defeated [the **W. Chalukya**] **Vikramāditya I.**), the son of **Mahēndravarman II.**, and grandson of **Narasimhavarman I.** (who defeated [the **W. Chalukya**] **Pulakēsin II.**);⁴ recording a grant made at the request of the Pallava lord (**Pallav-ādhirāja**) **Vidyāvinīta**.— The historical part of the grant is preceded by a mythical genealogy of Pallava (the supposed founder of the Pallava race) whose descent is derived from the god Brahman.

629.— *South-Ind. Inscr.* Vol. I. Nos. 24-26, p. 12 ff. Conjeeveram inscriptions of the Pallava **Rājasimha** (**Atyantakāma**, **Śribhara**, **Raṇajaya**), (*i.e.* **Narasimhavarman II.**), the son of **Ugradaṇḍa Paramēśvara** (*i.e.* **Paramēśvaravarman I.**) who destroyed the city of **Raṇarasika** (*i.e.* the **W. Chalukya Vikramāditya I.**).⁵

630.— *South-Ind. Inscr.* Vol. I. No. 31, p. 24. Panamalai inscription of the Pallava **Rājasimha** (*i.e.* **Narasimhavarman II.**), consisting of one verse which is identical with the last verse of *South-Ind. Inscr.* Vol. I. No. 24, above, No. 629.

631.— *South-Ind. Inscr.* Vol. I. Nos. 29 and 30, p. 23 f. Conjeeveram inscriptions of **Raṅgapatākā**, the queen of the Pallava **Narasimhavishṇu** (*i.e.* **Rājasimha**, **Narasimhavarman II.**).

632.— *South-Ind. Inscr.* Vol. I. No. 27, p. 22. Conjeeveram inscription of the Pallava **Mahendra** (*i.e.* **Mahēndravarman III.**), the son of **Rājasimha** (*i.e.* **Narasimhavarman II.**), who was the son of **Lōkāditya** (*i.e.* **Paramēśvaravarman I.**) who defeated **Raṇarasika** (*i.e.* the **W. Chalukya Vikramāditya I.**).⁶

633.— *Madras Christian College Magazine* of August 1890. Conjeeveram Tamil inscription of the 18th year of the reign of [the Pallava] **Nandipōttaraiyan** (*i.e.* **Nandivarman**).⁷

634.— *South-Ind. Inscr.* Vol. II. No. 74, p. 365; *Ind. Ant.* Vol. VIII. p. 274, Plates. Udayēndiram plates⁸ of the 21st year (of the reign) of the Pallava **Nandivarman-Pallavamalla**, recording a grant made at the request of his military officer or feudatory **Udaya-chandra** who was of the Pūchān family and lord of **Vilvalapura**:—

(L. 37).— tasy=aiva Nandivarmanṇa(ṇa) ēkaviṁśati-saṁkhyām pūrayati saṁvatsarē.

¹ See Dr. Fleet's *Dynasties*, p. 328.

² Compare above, No. 20, note.

³ The Sanskrit part is called a *prasasti*, the name of the author of which, if it was given, is broken away.

⁴ Compare above, No. 20.

⁵ See Dr. Fleet's *Dynasties*, p. 329, and above, No. 20, note.

⁶ See above, No. 629.

⁷ See above, No. 49.

⁸ The inscription on these plates (numbered with numeral figures), if genuine, is a copy, made at a later date, of two inscriptions, one of **Nandivarman**, and one of the **Chōla king Parāntaka I.**

Mythical genealogy from Brahman to Pallava. In his race, Simhavishnu; his son Mahēndravarman [I.]; his son Narasimhavarman [I.] (conquered Vallabharāja, *i.e.* the W. Chalukya Pulakēsin II.); his son Mahēndravarman [II.]; his son Paramēśvaravarman [I.] (defeated Vallabha, *i.e.* the W. Chalukya Vikramāditya I.); his son Narasimhavarman [II.]; his son Paramēśvaravarman [II.]; his son¹ Nandivarman.—Udayachandra slew the Pallava king Chitramāya; defeated the Śabara king Udayana,² and the Nishāda chief Prithivivāghra; and subjected the district of Vishnūrāja (*i.e.* the E. Chalukya Vishnuvardhana III.) to the Pallava.

The inscription ends³ with the same Tamil endorsement as No. 621 above, of the 26th year of king Parakēsarivarman who took Madirai, *i.e.* the Chōla king Parāntaka I.

635.—*South-Ind. Inscr.* Vol. II. No. 73, p. 346, and Plates. Kāsākuḍi Sanskrit⁴ and Tamil plates of the 22nd year of the reign of the Pallava *Mahārāja* Nandivarman Pallavamalla (also called Kshatriyamalla and Śrīdhara), recording a grant made at the request of his prime-minister Brahmasīrāja (Brahmayuvarāja):—

(L. 79).—sāmrajya-saṁvatsarē dvāvimśē [va]rttamānē.

Mythical genealogy from Brahman to Aśōkavarman. After him came the Pallava kings among whom were Skandavarman, Kalindavarman, Kāṇagōpa, Vishnugōpa, Virakūcha, Virasimha, Simhavarman, Vishnusiṁha, and others. Then came Simhavishnu (called Avanisiṁha); after him, Mahēndravarman [I.]; his son Narasimhavarman [I.] (conquered Vātāpi);⁵ his son Mahēndravarman [II.]; then, Paramēśvarapōtavarman (*i.e.* Paramēśvaravarman) [I.]; his son Narasimhavarman [II.]; his son Paramēśvarapōtavarman (*i.e.* Paramēśvaravarman) [II.]. At the time of the inscription his kingdom was ruled by Nandivarman (Nandipōtarāja, Nandin), who was descended from Simhavishnu's younger brother Bhīmavarman, between whom and Nandivarman there intervened the Pallava rulers Buddhavarman, Ādityavarman, Gōvīndavarman, and Nandivarman's father Hiranya (whose wife was Rōhini).

636.—*Ep. Ind.* Vol. IV. p. 137, and Plate facing p. 142. Pañchapāṇḍavamalai Tamil inscription, recording that the image, near which it is, was caused to be engraved in the 50th year (of the reign) of Nandippōttarāsar (Nandipōtarāja), (*i.e.* the Pallava Nandivarman).

637.—*South-Ind. Inscr.* Vol. I. Nos. 1-16, p. 2, and Plate x. facing Vol. II. p. 340. Māmallapuram Dharmarāja-Ratha inscriptions containing *birudas* of a Pallava king Narasimha.

638.—*South-Ind. Inscr.* Vol. I. Nos. 17-20, p. 4 ff., and facsimile of No. 17 on Plate x. facing Vol. II. p. 340. Māmallapuram inscriptions of a Pallava king Atyantakāma, a successor of Narasimha.

639.—*South-Ind. Inscr.* Vol. I. Nos. 21-23, p. 6 ff. Śāluvaṅkuppam inscriptions of a Pallava king Atiraṇachanda.

640.—*South-Ind. Inscr.* Vol. I. No. 28, p. 23. Conjeeveram inscription describing a temple as 'the temple of the holy Nityavinītēśvara' (founded by a Pallava king Nityavinita?).

641.—*South-Ind. Inscr.* Vol. I. No. 32, p. 26. Amarāvati (now Madras Museum) pillar inscription⁶ of a Pallava king Simhavarman [II.]; mentions Pallava's son Mahēndravarman, his son Simhavarman [I.], his son Arkavarman, Ugravarman, Simhavishnu's son Nandivarman, and Simhavarman [II.].—The inscription opens with an invocation of Buddha and with a mythical genealogy from Brahman to Pallava.

¹ But see No. 635.

² Possibly the Udayana of *North. Inscr.* No. 614 ff.

³ The preceding Sanskrit part is called a *prastāvi*, composed by Paramēśvara, the son of Chandradēva, of the family of Mēdhāvin.

⁴ The Sanskrit part, called a *prastāvi*, was composed by Trivikrama.

⁵ See below, No. 680.

⁶ The inscription is read from the bottom upwards; compare above, No. 5.—In the first verse the author appears to have imitated a verse of Bāṇa's *Kadambari*.

642.—*Ep. Ind.* Vol. VII. p. 26. Taṇḍalam Tamil rock inscription¹ of the 10th year (of the reign) of Śatti (Śakti), the king of the Kāḍavas, i.e. Pallavas, recording the building of a sluice :—

‘ In (the year) twice five (i.e. ten), which was engraved on palm-leaves, from the year when (the name of) Śatti, the king of the Kāḍavas, was entered on a gold leaf.’²

643.—*Mysore Inscr.* No. 115, p. 212; *PSOCI.* No. 226. Nandi (Bhōga-Nandi) Kanarese inscription of a Pallava Nōḷambādhirāja.³

644.—*Ep. Ind.* Vol. V. p. 51, and Plate. Rāyakōṭa (formerly Sir W. Elliot's, now British Museum?) Sanskrit and Tamil plates⁴ of the 14th year (of the reign) of [the Gaṅga-Pallava] Skandaśishya (king Vijaya-Skandaśishyavikramavarman), recording a grant made at the request of (his feudatory) Mahāvali-Vāṇarāja.⁵

Mythical genealogy from Brahman to Aśvatthāman; his son (?) by a Nāga woman was the Adhīrāja Skandaśishya; in his family was born the Skandaśishya who issued this grant.

645.—*Ep. Ind.* Vol. IV. p. 360, and Plate. Kīl-Muṭṭugūr (now Madras Museum) Tamil memorial stone of the 3rd year (of the reign) of king Vijaya-Narasimhavarman.

646.—*Ep. Ind.* Vol. IV. p. 178, and Plate facing p. 182. Kīl-Muṭṭugūr (now Madras Museum) Tamil inscription of the 18th year (of the reign) of king Vijaya-Narasimhavarman.

647.—*Ep. Ind.* Vol. VII. p. 23, and Plate. Baṅgavādi Tamil memorial stone of the 24th year (of the reign) of king Vijaya-Narasimhavikramavarman, recording the death of a servant of a Bāṇa chief named Skanda (Skanda-Bāṇādhirāja).

648.—*Ep. Ind.* Vol. VI. p. 321, and Plate. Śīyamaṅgalam Tamil cave inscription of the 3rd year (of the reign) of king Vijaya-Nandivikramavarman,⁶ recording the building of a *maṇḍapa* by a certain person with the permission of a Gaṅga chief named Nērguṭṭi, who must have been subordinate to Vijaya-Nandivikramavarman.

649.—*South-Ind. Inscr.* Vol. III. No. 43, p. 93. Tiruvallam (Bilvanāthēśvara temple) Tamil inscription⁷ of the 17th year⁸ (of the reign) of king Vijaya-Nandivikramavarman, recording a grant which was made at the request of Māvali-Vāṇarāja alias Vikkiramāditta-Vāṇarāja (i.e., according to Dr. Hultzsch, probably the Bāṇa king Vikramāditya I. of No. 663).

650.—*South-Ind. Inscr.* Vol. I. No. 108, p. 130. Notice of a Śaduppēri (near Vēlūr) fragmentary Tamil inscription of the 52nd year (of the reign) of king Vijaya-Nandivikramavarman.⁹

651.—*South-Ind. Inscr.* Vol. III. No. 42, page 91, and Plate. Tiruvallam Tamil rock inscription of the 62nd year (of the reign) of king Vijaya-Nandivikramavarman, “ while the

¹ According to Dr. Hultzsch perhaps of about the second half of the 9th century A.D.

² “ This seems to refer to some custom observed at the coronation of a king.”

³ See Dr. Fleet's *Dynasties*, p. 332.

⁴ The alphabet according to Dr. Hultzsch is more developed than that of Nos. 628 and 635, but more archaic than that of No. 670.

⁵ An hereditary designation of the Bāṇa chiefs.

⁶ Identical with Nandivarman, the father of Vijaya-Nripatungavarman in No. 652.

⁷ The inscription professes to be a copy of a stone inscription which existed before the *maṇḍapa* of the temple had been pulled down and re-erected.

⁸ For another inscription of the 17th year of the same king see below, under *Addenda*.

⁹ For inscriptions of the 9th and 47th years of the same king see *South-Ind. Inscr.* Vol. I. Nos. 124 and 125, p. 133.

glorious **Māvali-Vānarāya** (or **Mahāvali-Vānarāya**), born from the family of Mahābali, . . . was ruling the **Vaṇḍugavāli** (*i.e.* 'the Telugu road') twelve-thousand."

652.—*Ep. Ind.* Vol. IV. p. 180. Notice of the Bāhūr Sanskrit and Tamil plates of the 8th year of the reign of king **Vijaya-Nṛpatuṅgavarman**.¹—Mythical genealogy from Brahman to Pallava; in his family, Vimala, Koṅkaṇika and other kings; after them, Dantivarman;² his son Nandivarman, married Śaṅkhā³ of the Rāshtrakūṭa family; their son Nṛpatuṅgadēva.

653.—*Ep. Ind.* Vol. IV. pp. 182 and 183, and Plate. Two Āmbūr Tamil memorial stone inscriptions of the 26th year (of the reign) of king **Vijaya-Nṛpatuṅgavikramavarman**, recording the death of servants of **Pirudi-Gaṅgaraiyar** (*i.e.*, according to Dr. Hultzsch, perhaps the W. Gaṅga king Prithivīpati I. in No. 670).

654.—*Ep. Ind.* Vol. VII. p. 25, and Plate. Hebbiṇi Tamil memorial stone inscription of the 12th year (of the reign) of king **Vijaya-Īśvaravarman**, recording the death of a hero who was killed by a Bāṇa chief named **Kārōniri** (Kārōniri-Bāṇarāja).

655.—*Ep. Ind.* Vol. VII. p. 24, and Plate. Two Hanumantapuram Tamil memorial stone inscriptions of the 17th year (of the reign) of king **Vijaya-Īśvaravarman**, recording the death of two heroes in the service of **Kāṭṭirai**⁴ (*i.e.* 'the king of the forest,' a title of the Pallavas).

656.—*South-Ind. Inscr.* Vol. I. No. 53, p. 78; *Ep. Ind.* Vol. VII. p. 194, and Plate. Śōḷapuram (near Vēlūr) incomplete Tamil inscription of the 23rd year (of the reign) of king **Vijaya-Kampa-vikramavarman**.⁵

657.—*South-Ind. Inscr.* Vol. III. No. 8, p. 13. Ukkal (Viṣṇu temple) Tamil inscription⁶ of the 10th year (of the reign) of **Kampavarman**.⁷

658.—*South-Ind. Inscr.* Vol. III. No. 5, p. 9, and Plate. Ukkal (Viṣṇu temple) Tamil inscription⁸ of the 15th year (of the reign) of **Kampavarman**.

659.—*South-Ind. Inscr.* Vol. III. No. 47, p. 99. Tiruvallam (Bilvanāthēśvara temple) Tamil inscription,⁹ recording a gift by **Vāṇa-mahādēvi** (*i.e.* 'the great queen of the Bāṇa'), the daughter of Pratipati-Araiṇar,¹⁰ the son of Koṅṇi-dharmamahārāja, the supreme lord of Kuṇḍilapura,¹¹ *alias* Śrīnātha, the glorious Śivamahārāja.¹² Perumāṇaḍigal, (and) the great queen of **Vāṇavidyādharaṇāya** *alias* **Vānarāya** (*i.e.* the Bāṇa king Vāṇavidyādhara¹³), born from the family of Mahābali.

660.—*South-Ind. Inscr.* Vol. III. No. 48, p. 100. Tiruvallam (Bilvanāthēśvara temple) Tamil inscription,¹⁴ recording a gift by **Kundavvaiyār** *alias* **Vāṇa-mahādēvi** (*i.e.* 'the great

¹ For other plates (which cannot be traced now) of the 6th year of his reign see Mr. Sewell's *Lists of Antiquities*, Vol. II. p. 30, No. 209.—For inscriptions of the 21st year see below, under *Addenda*.

² Perhaps identical with the Dantiga in No. 62.

³ Perhaps a daughter of the Rāshtrakūṭa Amoghavarsha I. Nṛpatuṅga; see above, No. 63 ff.

⁴ Compare *Kāḍava*, above, No. 642.

⁵ He was perhaps a brother of Vijaya-Nṛpatuṅgavikramavarman in Nos. 652 and 653 above; see *Ep. Ind.* Vol. VII. p. 196.—For an inscription of the 8th year of Vijaya-Kampa see below, under *Addenda*.

⁶ According to Dr. Hultzsch, the archaic alphabet of these inscriptions "proves that Kampavarman must be anterior to the Chōla occupation of Topḍai-maṇḍalam. A stone inscription of the 9th year of the same king is quoted in the unpublished Madras Museum plates of Parakēsarivarman *alias* Uttama-Chōḷadēva."

⁷ Probably identical with king Vijaya-Kampavikramavarman, above, No. 656.

⁸ The inscription professes to be a copy of an earlier stone inscription.

⁹ *I.e.*, according to Dr. Hultzsch, the W. Gaṅga Prithivīpati I., the son of Śivamāra II., in No. 670.

¹⁰ A mistake of the copyist for Kuṇḍilapura. Compare Nos. 660, 708 and 724.

¹¹ *I.e.* Śivamāra II. For Śivamāra I. see above, No. 123.

¹² *I.e.*, according to Dr. Fleet and Dr. Hultzsch, the Bāṇa king Vikramāditya I. of No. 668; see also No. 662.

¹³ The inscription was copied from an earlier stone inscription.

queen of the Bâṇa'), the daughter of Pratipati-Araiya, the son of Koṅṅunivarma-dharma-mahârāja, the supreme lord of Nipunilapura,¹ *alias* Śrīnātha, the glorious Śivamahârāja. Perumāṇaḍigal, (and the queen of) Vāṇavidyādhara-rāja *alias* Vāṇarāya (*i.e.* the Bâṇa king Vāṇavidyādhara), born from the family of Mahābali.²

661.—*South-Ind. Inscr.* Vol. III. No. 46, p. 98. Tiruvallam (Bilvanāthēśvara temple) Tamil inscription, recording a gift by the queen of Vāṇavidyādhara-Vāṇarāya, born from the family of Mahābali.³

662.—*Ind. Ant.* Vol. X. p. 39, No. II., and Plate; *Mysore Inscr.* No. 164, p. 305. Gūlgānpode Sanskrit and Kanarese memorial stone of the reign of the Bâṇa king Vikramāditya Jayamēru, surnamed Bâṇavidyādhara (*i.e.* Vikramāditya I.).³

663.—*Ep. Ind.* Vol. III. p. 75, and Plate. Udayēndiram fragmentary plates of the Bâṇa king Vikramāditya II. Vijayabāhu.

The Asura Bali; his son Bâṇa; in his lineage, Bâṇādhirāja. When he and many other Bâṇa princes had passed away, there was in this family Jayanandivarman, who ruled the land west of the Andhra country. His son Vijayāditya [I.]; his son Malladēva Jagadēkamalla; his son Bâṇavidyādhara; his son Prabhumēru; his son Vikramāditya [I.]; his son Vijayāditya [II.] Puṅḡavippavargaṇḍa;⁴ his son Vikramāditya [II.] Vijayabāhu (was a friend of Kṛishṇarāja⁵).

664.—*Ś. 810.*—*South-Ind. Inscr.* Vol. III. No. 44, p. 95. Tiruvallam (Bilvanāthēśvara temple) Tamil inscription,⁶ dated “(during the reign of some) Mahāvali-Vāṇarāja, [born from the family of Mahābali] . . . in the Śaka year eight hundred and ten.”

665.—*South-Ind. Inscr.* Vol. III. No. 45, p. 96. Tiruvallam (Bilvanāthēśvara temple) Tamil inscription⁷ of the reign of some Mahāvali-Vāṇarāja, born from the family of Mahābali.

666.—*Ind. Ant.* Vol. X. p. 39, No. I., and Plate; *Mysore Inscr.* No. 163, p. 304. Gūlgānpode Kanarese memorial stone of the reign of some Mahāvali-Bāṇarasa, born in the family of Mahāvali.

667.—*Ep. Ind.* Vol. IV. p. 142, and Plate. Vaḷḷimalai Kanarese inscription⁸ (in Grantha characters), recording that the image below which it is engraved represents a pupil of the spiritual preceptor of Bâṇarāja (or ‘a king of the Bâṇa family’).

668.—*Ś. 261.*—*Ind. Ant.* Vol. XV. p. 175. Muḍiyanūr (spurious⁹) plates of the 23rd year (of the reign) of the Bâṇa king Śrīvadhūvallabha Malladēva-Nandivarman, ruler of the seven and a half lakh country in the Āndhra maṇḍala; issued from Āvanyapura:—

(L. 23).—ēkashasṭyuttara-dvayaśatē Śak-ābdaḥ pravarddhamān-ātmanah trayōvīmśati varttamāna-Viḷambi-saṁvatsarē Kārttikā(ka)-śuklapakṣhē trayōdaśyām Sōmavārē Aśvinyām nakṣatrē.

The date is irregular; see *ibid.* Vol. XXIV. p. 10, No. 167.

The inscription mentions the Dānava Mahābali, Nandivarman, and his son Vijayāditya.

¹ A mistake of the copyist for Kuvaḷālapura.

² See No. 659.

³ See No. 663.

⁴ *I.e.* ‘the disgracer of vainglorious (kings);’ compare below, No. 698.

⁵ *I.e.*, probably, the Rāshtrakūṭa Kṛishṇarāja II.; see above, No. 82 ff.

⁶ The inscription was copied from an earlier stone inscription.

⁷ The inscription apparently was copied from an earlier stone inscription.

⁸ Immediately above this inscription is another, short inscription in the Kanarese alphabet and language, recording that the image below which it is engraved was founded by (the Jaina preceptor) Ajjanandi, (Āryanandin); see *Ep. Ind.* Vol. IV. p. 141, and Plate. The same personage (named Ajjanandi, the pupil of Bālachandra) is mentioned in another Kanarese inscription, *ibid.* p. 142, and Plate facing p. 140.

⁹ See *Ind. Ant.* Vol. XXX. p. 221, No. 47. — The record is, at least in part, a palimpsest.

669.—Sholinghur Sanskrit and Tamil partly mutilated rock inscription of the 9th year (of the reign) of [Parakēsarivarman, i.e. the Chōla king Parāntaka I.], recording a grant which was executed by his feudatory Hastimalla Vira-Chōla (i.e. the Gaṅga-Bāṇa Prithivipati II.), 'the king of the people of Paṇivai.'—See below, No. 681.

670.—*South-Ind. Inscr.* Vol. II. No. 76, p. 382, and Plate. Udayēndiram Sanskrit and Tamil plates, recording a grant by the Gaṅga-Bāṇa king Prithivipati II. Hastimalla (Śembiyaṇ Māvali-Vāṇarāyar), 'lord of Paṇivipuri, lord of Nandi,' made with the permission, and in the 15th year (of the reign), of his sovereign, the Chōla king Parāntaka I. (king Parakēsarivarman who took Madirai).¹

Genealogy of Parāntaka I.; see below, No. 685.

Genealogy of Prithivipati II.: In the Gaṅga family, which was descended from the sage Kaṇva, and which obtained increase through the might of Simhanandin, there was at Kuvalālapura Koṅkapi; in his lineage (in which were Vishṇugōpa, Hari, Mādhava, Durvīṇa, Bhūvikrama,² etc.) was the son of Śivamāra [II.],³ Prithivipati [I.] Aparājita (saved king Diṇḍi's sons Iriga and Nāgadanta, the one from [the Rāshtrakūṭa] Amoghavarsha [I.], the other from death; defeated the Pāṇḍya Varaguna); his son Mārasimha [I.]; his son Prithivipati [II.] Hastimalla (was made by Parāntaka I. lord of the Bāṇas).

671.—*Ep. Ind.* Vol. III. p. 80, and Plate in *Ind. Ant.* Vol. IX. p. 47. Udayēndiram second and fifth plates⁴ only of Vira-Chōla (i.e. the Gaṅga-Bāṇa king Prithivipati II. Hastimalla), the subordinate of Parakēsarivarman (i.e. the Chōla king Parāntaka I.).⁵

M.—The Chōlas.⁶

672.—*South-Ind. Inscr.* Vol. I. No. 85, p. 116. Conjeeveram (Kailāsanātha temple) Tamil inscription of the 4th year (of the reign) of king Parakēsarivarman (perhaps⁷ identical with Vijayālaya, the grandfather of Parāntaka I.).

673.—*South-Ind. Inscr.* Vol. I. No. 148, p. 141. Conjeeveram (Kailāsanātha temple) fragmentary Tamil inscription of the 15th year (of the reign) of king Parakēsarivarman (perhaps identical with Vijayālaya, the grandfather of Parāntaka I.).

674.—*South-Ind. Inscr.* Vol. III. No. 11, p. 17. Ukkal (Viṣṇu temple) Tamil inscription of the 16th year (of the reign) of king Parakēsarivarman (perhaps identical with Vijayālaya, the grandfather of Parāntaka I.).

675.—*Ep. Ind.* Vol. V. p. 42, and Plate. Śuchindram (Sthāpūnātha temple) Tamil inscription of the 34th year (of the reign) of king Parakēsarivarman (perhaps identical with Vijayālaya, the grandfather of Parāntaka I.).

676.—*South-Ind. Inscr.* Vol. I. No. 84, p. 116. Conjeeveram (Kailāsanātha temple) Tamil inscription of the 3rd year⁸ (of the reign) of king Rājakēsarivarman (perhaps⁹ identical with Āditya I., the father of Parāntaka I.).

677.—*South-Ind. Inscr.* Vol. III. No. 27, p. 50. Maṇimaṅgalam (Rājagōpāla-Perumāḷ temple) Sanskrit and Tamil inscription of the 6th year (of the reign) of king Rājakēsarivarman (perhaps identical with Āditya I., the father of Parāntaka I.).

¹ Compare *Ep. Ind.* Vol. IV. p. 222.

² Compare above, No. 108 ff.

³ For Śivamāra I. see No. 123.

⁴ The plates are marked with the Tamil numerals 2 and 5.

⁵ See *Ep. Ind.* Vol. IV. p. 223.—Compare below, No. 681; also above, No. 103.

⁶ These include some Telugu-Chōḍas, Nos. 880—888.

⁷ See *South-Ind. Inscr.* Vol. III. p. 17, note 4; and below, No. 712.—See also under *Addenda*.

⁸ For a fragmentary Conjeeveram Tamil inscription of the same year of Rājakēsarivarman, see *South-Ind. Inscr.* Vol. I. No. 147, p. 140.

⁹ See *ibid.* Vol. III. p. 2, note 4; and below, No. 712.

678.—*South-Ind. Inscr.* Vol. III. No. 13, p. 20. Ukkal (Vishṇu temple) unfinished Tamil inscription of the 122nd day of the 17th year (of the reign) of king **Rājakēsarivarman** (perhaps identical with **Āditya I.**, the father of **Parāntaka I.**).

679.—*South-Ind. Inscr.* Vol. III. No. 1, p. 2, and Plate. Ukkal (Vishṇu temple) Tamil inscription of the 23rd year (of the reign) of king **Rājakēsarivarman** (perhaps identical with **Āditya I.**, the father of **Parāntaka I.**).

680.—*Ep. Ind.* Vol. III. p. 279, and Plate. Tirukkaḷukkuṇṇam (Vēdagiriśvara temple) Tamil inscription of the 27th year (of the reign) of king **Rājakēsarivarman** (perhaps identical with **Āditya I.**, the father of **Parāntaka I.**); recording the renewal of a grant which had been made by a [Pallava] king **Skandaśishya** (*i.e.*, probably, **Skandavarman**) and confirmed by the king **Naraśingappōttaraiyar** who took **Vātāpi** (*i.e.* **Narasimhavarman I.**).¹

681.—*Ep. Ind.* Vol. IV. p. 223. Sholinghur Sanskrit² and Tamil partly mutilated rock inscription of the 9th year (of the reign) of [**Parakēsarivarman**, *i.e.* the Chōḷa king **Parāntaka I.**], recording a grant which was executed by his feudatory **Hastimalla Vira-Chōḷa** (*i.e.* the Gaṅga-Bāṇa king **Prithivipati II.**).—See above, No. 669.

In the race of the Sun, **Āditya [I.]**; his son **Vīra-Nārāyaṇa Parāntaka [I.]**, conferred the title of 'lord of the Bāṇas' on **Prithivipati [II.] Hastimalla Vīra-Chōḷa** of the Gaṅga lineage.

682.—Udayēndiram second and fifth plates only of **Vīra-Chōḷa** (*i.e.* the Gaṅga-Bāṇa **Prithivipati II. Hastimalla**), the feudatory of **Parakēsarivarman** (*i.e.* the Chōḷa king **Parāntaka I.**).—See above, No. 671.

683.—*Ep. Ind.* Vol. III. p. 281, and Plate. Tirukkaḷukkuṇṇam (Vēdagiriśvara temple) Tamil inscription of the 13th year (of the reign) of king **Parakēsarivarman** who took **Madirai** (*i.e.* the Chōḷa king **Parāntaka I.**).

684.—*South-Ind. Inscr.* Vol. I. Nos. 82 and 83, pp. 113 and 114. Two Conjeeveram (Kailāsanātha temple) Tamil inscriptions of the 15th year (of the reign) of king **Parakēsarivarman** who took **Madirai** (*i.e.* the Chōḷa king **Parāntaka I.**).

685.—Udayēndiram plates (above, No. 670), recording a grant by the Gaṅga-Bāṇa king **Prithivipati II. Hastimalla**, made in the 15th year (of the reign) of his sovereign, king **Parakēsarivarman** who took **Madirai** (*i.e.* the Chōḷa king **Parāntaka I.**).

Genealogy of **Parāntaka I.**: From Brahman through the Sun to Śibi; in his race (in which there were **Kōṅkilī**, **Chōḷa**, **Karikāla**, **Kōchchaṅkan** and other kings) there was **Vijayālaya**; his son **Āditya [I.]**; his son **Vīra-Nārāyaṇa** (**Saṁgrāma-Rāghava**, **Parakēsarīn**, **Parāntaka [I.]**) uprooted two Bāṇa kings, defeated the **Vaidumba**, and the **Pāṇḍya Rājasimha**, *etc.*—For the rest see above, No. 670.

686.—Tamil endorsement of the 26th³ year (of the reign) of king **Parakēsarivarman** who took **Madirai** (*i.e.* the Chōḷa king **Parāntaka I.**), in the Udayēndiram (spurious) plates of the Pallava **Nandivarman** and the Udayēndiram plates of the Pallava **Nandivarman Pallavamalla**; above, Nos. 621 and 634.

687.—*Ep. Ind.* Vol. IV. p. 179, and Plate. Kīl-Muṭṭugūr (now Madras Museum) Tamil memorial stone of the 29th year (of the reign) of king **Parakēsarivarman** who took **Madirai** (*i.e.* the Chōḷa king **Parāntaka I.**).

688.—*Ep. Ind.* Vol. IV. p. 179, and Plate facing p. 360. Kīl-Muṭṭugūr (now Madras Museum) Tamil inscription of the 32nd year (of the reign) of king **Parakēsarivarman** who

¹ See above, No. 635.

² The Sanskrit part of this '*prasasti*' was composed by Kumāra.

³ For inscriptions of the 23rd and 28th years see below, under *Addenda*.

took Madirai (*i.e.* the Chôla king Parântaka I.), on a stone set up to mark the spot at which a tiger had been killed by an inhabitant of Mukkuṭṭūr (*i.e.* the modern Kīl-Muṭṭugūr).

689.—*South-Ind. Inscr.* Vol. II. No. 75, p. 375. Uyyakkoṇḍāṇ-Tirumalai (Ujġivanātha temple) Tamil pillar inscription of the 34th year (of the reign) of king Parakēsarivarman who took Madirai (*i.e.* the Chôla king Parântaka I.), recording donations by the queen of Pirântakaṇ-Kaṇḍarādittadēvar (*i.e.* Gaṇḍarādityavarman, the second son of Parântaka I.).

690.—*South-Ind. Inscr.* Vol. III. No. 12, p. 19, and Plate. Ukkal (Vishṇu temple) Tamil inscription of the 37th year (of the reign) of king Parakēsarivarman who took Madirai (*i.e.* the Chôla king Parântaka I.).

691.—*Ep. Ind.* Vol. VII. p. 1, No. 55. Date of a Kâram (Kēśava-Perumāḷ temple) Tamil inscription of the 40th year (of the reign) of king Parakēsarivarman who took Madirai and entered Îlam (*i.e.* the Chôla king Parântaka I.):—

‘In the fortieth year . . . at night on the day of Rôhiṇī, which corresponded to a Saturday and to the ninth *tithi* of the second fortnight of the month of [Karkāṣa]ka in this year.’

Between A.D. 900 and 985 the date would be correct only for Saturday, 24th July A.D. 919 [in Ś. 841], and Saturday, 25th July A.D. 946 [in Ś. 868].

692.—*Ep. Ind.* Vol. V. p. 43, and Plate. Śuchindram (Sthāpūnātha temple) Tamil inscription of the month of Kumbha of the 40th year (of the reign) of king Parakēsarivarman who took Madirai and Îlam (*i.e.* the Chôla king Parântaka I.).

693.—*South-Ind. Inscr.* Vol. I. No. 145, p. 140. Conjeeveram (Kailāsanātha temple) fragmentary Tamil inscription of the reign of king Parakēsarivarman who took Madirai (*i.e.* the Chôla king Parântaka I.).

694.—*South-Ind. Inscr.* Vol. III. No. 14, p. 21. Ukkal (Vishṇu temple) Tamil inscription of the 4th year (of the reign) of king Parakēsarivarman¹ who took the head of Vīra-Pāṇḍya.²

695.—*Ep. Ind.* Vol. IV. p. 331. Karikal Tamil inscription of the 5th year (of the reign) of king Rājakēsarivarman who took Madirai.³

696.—*South-Ind. Inscr.* Vol. III. No. 49, p. 102. Tiruvallam (Bilvanāthēśvara temple) incomplete Tamil inscription of the 7th year (of the reign) of king Rājarājakēsarivarman (*i.e.* the Chôla king Rājarāja I.):—

‘In the 7th year . . . on the day of an eclipse of the moon at the equinox which corresponded to (the day of) Rêvatī and to a full-moon *tithi* of the month of Aippasi in this very year.’

[Ś. 913]: 26th September A.D. 991; a lunar eclipse, visible in India; see *Ep. Ind.* Vol. IV. p. 66, No. 1.

The inscription records a visit to the temple by a certain Gaṇḍarāditya, son of Madhurāntaka. —According to Dr. Hultzsch, he perhaps was an (otherwise unknown) son of Madhurāntaka, the son of Gaṇḍarāditya and immediate predecessor of Rājarāja I.; compare below, No. 712.

697.—*South-Ind. Inscr.* Vol. III. No. 50, p. 103. Another Tiruvallam (Bilvanāthēśvara temple) Tamil inscription of the 7th year (of the reign) of king Rājarājakēsarivarman (*i.e.* the Chôla king Rājarāja I.).

¹ According to Dr. Hultzsch, this king may be identified with Āditya II, surnamed Karikāla, the elder brother of Rājarāja I. (see below, No. 712).—But Āditya II. would be expected to be a Rājakēsarivarman.

² According to Dr. Hultzsch “this phrase implies that the king, while seated on the throne, placed his feet on the crown of the Pāṇḍya king;” see *South-Ind. Inscr.* Vol. III. p. 215, note 4.

³ By Dr. Hultzsch identified with the “Madhurāntaka who, according to the large Leyden grant (below, No. 712), was the son of Gaṇḍarāditya [the second son of Parântaka I.] and ruled between Āditya II. and Rājarāja I.”—But that Madhurāntaka would be expected to be a Parakēsarivarman.

⁴ The accession of Rājarāja I. took place between (approximately) the 25th June and the 25th July A.D. 985; see *Ep. Ind.* Vol. VII. p. 6.

698.—*Ep. Ind.* Vol. IV. p. 139. Pañchapaṇḍavamalai (Tami) Jain rock inscription of the 8th year (of the reign) of king Rājārājakesarivarman (*i.e.* the Chōla king Rājārāja I.), containing an order of the Lāṭarāja Vira-Chōla, the son of Puṅgavippavarganda.¹

699.—*Ep. Ind.* Vol. V. p. 44, and Plate. Śūchindram (Sthāpūnātha temple) Tamil inscription of the 10th² year (of the reign) of king Rājārājakesarivarman (*i.e.* the Chōla king Rājārāja I.), dated 'in the month of Karkātaka with which (this) year began.'

700.—*South-Ind. Inscr.* Vol. I. No. 146, p. 140. Conjeeveram (Kailāsanātha temple) fragmentary Tamil inscription of the 12th year (of the reign) of king Rājārājakesarivarman who destroyed the ships (at) Kāndaḷūr-Śālai; (*i.e.* the Chōla king Rājārāja I.).

701.—*South-Ind. Inscr.* Vol. III. No. 2, p. 4, and Plate. Ukkal (Viṣṇu temple) Tamil inscription of the 13th year (of the reign) of king Rājārājakesarivarman who destroyed the ships (at) Śālai;³ (*i.e.* the Chōla king Rājārāja I.).

702.—*South-Ind. Inscr.* Vol. III. No. 3, p. 5. Ukkal (Viṣṇu temple) Tamil inscription of the 14th year (of the reign) of king Rājārājakesarivarman who, having destroyed the ships (at) Śālai,³ conquered Vēṅgai-nāḍu (Vēṅgai-nāḍu), Gaṅga-pāḍi, Taḍiya-vali (Taḍigai-pāḍi) and Nuḷamba-pāḍi; (*i.e.* the Chōla king Rājārāja I.).

703.—*Ep. Ind.* Vol. V. p. 45, and Plate. Śūchindram (Sthāpūnātha temple) Tamil inscription of the month of Vṛiśchika of the 14th year (of the reign) of king Rājārājakesarivarman who, having destroyed the ships (at) Kāndaḷūr-Śālai, conquered Gaṅga-pāḍi, Nuḷamba-pāḍi, Taḍiga-vali (Taḍigai-pāḍi) and Vēṅgai-nāḍu; (*i.e.* the Chōla king Rājārāja I.).

704.—*South-Ind. Inscr.* Vol. III. No. 19, p. 29. Mēlpāḍi (Sōmanāthēśvara temple) Tamil inscription of the 14th year (of the reign) of the glorious Mummudi-Chōladēva⁴ (*alias*) king Rājārāja Rājakesarivarman who . . . was pleased to destroy the ships (at) Kāndaḷūr-Śālai, conquered Gaṅga-pāḍi, Nuḷamba-pāḍi, Taḍiya-pāḍi (Taḍigai-pāḍi), Vēṅgai-nāḍu and Kuḍamalai-nāḍu (*i.e.* Malabar), and deprived the Śēliyas (*i.e.* Pāṇḍyas) of (their) splendour; (*i.e.* the Chōla king Rājārāja I.).

705.—*Ep. Ind.* Vol. V. p. 45, and Plate. Śūchindram (Sthāpūnātha temple) Tamil inscription of the 15th year (of the reign) of king Rājārājakesarivarman, described as in No. 704; (*i.e.* the Chōla king Rājārāja I.):—

'In the year fifteen . . . on the day of Pūrva-Bhadrpadā, . . . Tuesday, three evenings, having expired of the month of Kanyā.'

[§. 921]: Tuesday, 29th August A.D. 999; see *ibid.* p. 48, No. 25.

706.—*Ep. Ind.* Vol. V. p. 197. Date of a Maṇimaṅgalam (Vaikuṇṭha-Perumāḷ temple) Tamil inscription of the 15th year (of the reign) [of the Chōla king Rājārāja I.]:—

'In the 15th year . . . on the day of Hasta, which corresponded to a Thursday and to the tenth *tithi* of the first fortnight of the month of Rishabhā.'

[§. 922]: 15th May A.D. 1000;⁵ but the day was a Wednesday, not a Thursday.

707.—*Ep. Ind.* Vol. V. p. 46, and Plate. Shērmādēvi (Rāmasvāmin temple) unfinished Tamil inscription of the 15th year (of the reign) of king Rājārājakesarivarman, described as in No. 704; (*i.e.* the Chōla king Rājārāja I.).

¹ *I.e.* 'the disgracer of vainglorious (kings)'; compare above, No. 668.

² For inscriptions of the 9th and 11th years see below, under *Addenda*.

³ *I.e.* Kāndaḷūr-Śālai.

⁴ *I.e.* 'the Chōla king (who wears) three crowns,' *viz.* those of the Chōla, Pāṇḍya and Chēra kingdoms.—But compare Dr. Fleet in *Ep. Ind.* Vol. VI. p. 51, note 4.

⁵ That the above is the proper equivalent of the date follows from 'the fact that Rājārāja's reign commenced between the 25th June and the 25th July A.D. 985; see above, No. 696, note.

708.—*South-Ind. Inscr.* Vol. III. No. 51, p. 104. Tiruvallam (Bilvanāthēśvara temple) Tamil inscription of the 16th year (of the reign) of king Rājārāja Rājakēsarivarman (i.e. the Chōla king Rājārāja I.).—To the conquests enumerated in No. 704 the inscription adds those of Kollam and Kalingam.

The inscription records the sale of some land to “Śamkaradēva, (the son of) Koṅṅuivarmadharmamahārāja, the supreme lord of Nipunilapura,¹ Śrinātha, the glorious Śivamahārāja-Tiruvaiyaṇ,” who granted it to a temple.

709.—*South-Ind. Inscr.* Vol. III. No. 6, p. 9. Ukkal (Viṣṇu temple) Tamil inscription of the 1[7]th year (of the reign) of king Rājārāja Rājakēsarivarman (i.e. the Chōla king Rājārāja I.).—The conquests enumerated are the same as in No. 708.

710.—*South-Ind. Inscr.* Vol. III. No. 52, p. 106. Tiruvallam (Bilvanāthēśvara temple) Tamil inscription of the 20th year (of the reign) of king Rājārāja Rājakēsarivarman *alias* the glorious Rājārājadēva (i.e. the Chōla king Rājārāja I.).—To the conquests enumerated in No. 708 the inscription adds that of Īla-maṇḍalam.

The inscription records the gift of a lamp by a chief of the Vaidumba family.

711.—*South-Ind. Inscr.* Vol. I. No. 66, p. 94. Tirumalai Tamil rock inscription of the 21st year (of the reign) of king Rājārājakēsarivarman *alias* the glorious Rājārājadēva [I.].²—The conquests enumerated are the same as in No. 710.

712.—*Archæol. Surv. of South. India.* Vol. IV. p. 206. The large Sanskrit³ and Tamil Leyden grant⁴ (on 21 plates) of the 21st year of the reign of Rājārāja Rājāśraya Rājakēsarivarman (i.e. the Chōla king Rājārāja I.).

Mythical genealogy from the Sun to Chōla; then Rājakēsarīn and Parakēsarīn (after whom the kings of this family are alternately called Rājakēsarīn and Parakēsarīn); in their family there were Suraguru Rājendra Mṛityujit, Vyāghrakētu, Pañchapa, Karikāla, Kōchchaṅkappān and Kōlkilli. Then, Vijayālaya; his son Āditya [I.]; his son Parāntaka [I.]; he had three sons, Rājāditya, Gaṇḍarāditya, and Arimjaya; Gaṇḍarāditya's son was Madhurāntaka; Arimjaya's son, Parāntaka [II.]; his two sons were Āditya [II.] Karikāla and Rājārāja [I.].—The succession from Vijayālaya to Rājārāja I. was: 1, Vijayālaya; 2, Āditya [I.]; 3, Parāntaka [I. Parakēsarivarman]; 4, Rājāditya (conquered [the Rāshtrakūṭa] Kṛishṇarāja [III.],⁵ but fell in battle); 5, Gaṇḍarāditya (Gaṇḍarādityavarman); 6, Arimjaya; 7, Parāntaka [II.]; 8, Āditya [II.] Karikāla (while a boy, played sportively in battle with Vīra-Pāṇḍya); 9, Madhurāntaka; 10, Rājārāja [I. Rājakēsarivarman] (conquered [the W. Chālukya Iṣivabedāṅga] Satyāśraya⁶ and others).

713.—Ś. 928.—*Ep. Carn.* Vol. III. p. 149, No. 44. Kaliyūr Kanarese inscription consisting of praises of Apramēya, ‘lord of Kotta-maṇḍala,’ a general and minister under Rājārājadēva [I.]:—

(L. 1).—Sa(śa)kanripakāl-ātita-saṁvatsaraśataṅga[*] 928neya⁷ [Par]ābhava-saṁvatsarada Chaitra-māsada bahuja-paṁchamiyuma-Ādityav[ā*]rad-andu.

The date is irregular; see *Ep. Ind.* Vol. IV. p. 67, No. 2.

¹ “A mistake for Kuvalālapura.” Compare below, No. 724, and above, Nos. 659 and 660. See also No. 108 ff.

² The inscription also gives Arumōḷi as a surname of Rājārāja.

³ The Sanskrit *prasasti* was composed by Nandanārāyaṇa.

⁴ The inscription will soon be properly edited. Its object is to record the grant of a village to a Buddhist temple at Negapatam, commenced to be built by Chūlāmanivarman, king of Kaṭāha (or, in Tamil, Kidāram, apparently some portion of Lower Burma or of the Indo-Chinese peninsula), and completed by his son Māraviyayōttuṅgarvarman. See Mr. Venkayya's *Report* for 1898-99, p. 17.

⁵ Compare above, No. 95.

⁶ See above, No. 146 ff.

⁷ This is Dr. Fleet's reading of the year of the date, from an impression sent to him by Dr. Hultzsch.

Apramêya is said "to have defeated the Poysala (Hoysala) minister Nāganna; and to have slain . . . the Hoysala leaders Mañjaga, Kāliga (or ? Kāli-Gaṅga), Nāgavarmma."

714.—*South-Ind. Inscr.* Vol. III. No. 9, p. 14. Ukkal (Vishṇu temple) Tamil inscription of the 143rd day of the 24th year (of the reign) of king Rājārājakēśarivarman *alias* the glorious Rājārājadēva [I.], containing an order which was issued by the king at (his capital) Tañjāvūr on the 124th day of the 24th year of his reign.—To the conquests enumerated in No. 710 the inscription adds that of the seven and a half *lakshas* of Ilaṭṭa-pāḍi (Iraṭṭa-pāḍi).

715.—*South-Ind. Inscr.* Vol. I. Nos. 40 and 41, pp. 64 and 67. Two Māmallapuram Tamil inscriptions of the 25th and 26th years (of the reign) of king Rājārāja Rājakēśarivarman *alias* the glorious Rājārājadēva [I.].—The conquests enumerated are the same as in No. 714.

716.—*South-Ind. Inscr.* Vol. II. Nos. 1-6, 24-35, 37-39, 42, 44-53, 55, 56, 59, 63-66, 69, 70 and 57, with Plates of Nos. 1 and 29. Forty-one Tanjore (Rājārājēśvara temple) Tamil¹ inscriptions of king Rājakēśarivarman *alias* the glorious Rājārājadēva [I.], engraved by his order of the 20th day of the 26th year (of his reign), that the gifts made by himself, by his elder sister (Kundavaiyār, the daughter of Parāntaka II. and queen of Vallavaraiyar Vandyadēvar, Nos. 2 and 6), his queens (Lōkamahādēvī, No. 34, Chōlamahādēvī, Nos. 42 and 46, Abhimānavalli, No. 44, Trailōkyaamahādēvī, No. 48, Pañchavaṇmahādēvī, Nos. 51 and 53) and others (such as the commander of his army Kṛishṇa Rāma, Nos. 31 and 39) should be recorded on the walls of the Tañjāvūr temple.—The conquests enumerated in No. 1 and others are the same as in No. 714. No. 1 specially mentions the conquest of Satyāśraya (*i.e.* the W. Chālukya Iṇivabeḍaṅga Satyāśraya).²

717.—*Ś. 934.—Ep. Carn.* Vol. III. p. 78, No. 140; *Ep. Ind.* Vol. IV. p. 68, No. 3. Balmuri (Agastyaēśvara temple) Kanarese inscription of the 28th year (of the reign) of Rājārājadēva (Rājārājakēśarivarman *alias* Rājārājadēva [I.]):—

'In the twenty-eighth year . . . the Paridhāvin year . . . the Śaka year 934 . . . at the Uttarāyana-saṁkrānti in the month of Pausa of this year.'

The date would correspond to the 23rd December A.D. 1012, but contains no details for verification.

718.—*South-Ind. Inscr.* Vol. III. Nos. 15-17, p. 23 ff., and Plate of No. 17. Three Mēlpāḍi (Chōlēśvara temple) Tamil inscriptions of the 29th year (of the reign) of king Rājārājakēśarivarman³ *alias* the glorious Rājārājadēva [I.].—The conquests enumerated are the same as in No. 714.

719.—*South-Ind. Inscr.* Vol. III. No. 4, p. 7. Ukkal (Vishṇu temple) Tamil inscription of the 29th year (of the reign) of king Rājakēśarivarman *alias* the glorious Rājārājadēva [I.].—To the conquests enumerated in No. 714 is added that of twelve thousand ancient islands of the sea.

720.—*Ep. Ind.* Vol. V. p. 47, and Plate. Shērmādēvī (Rāmasvāmin temple) unfinished Tamil inscription [of Rājārājakēśarivarman, *i.e.* the Chōḷa king Rājārāja I.].—The conquests enumerated are the same as in No. 708.

721.—*South-Ind. Inscr.* Vol. II. No. 60, p. 245. Tanjore (Rājārājēśvara temple) Tamil inscription, recording donations made until the 2nd year (of the reign) of the lord, the glorious Rājendra-Chōḷadēva (*i.e.* the Chōḷa king Rājendra-Chōḷa I.).⁴

¹ Nos. 1 and 31 open with a Sanskrit *śloka*.

² See above, No. 712.

³ No. 17 has *Rājārāja-Rājakēśarivarman*.

⁴ The accession of Rājendra-Chōḷa I. took place between (approximately) the 26th November A.D. 1011 and the 7th July A.D. 1012; see *Ep. Ind.* Vol. VII. p. 7.

722.—*South-Ind. Inscr.* Vol. II. Nos. 7, 8, 40, 41, and 43. Five Tanjore (Rājarājēśvara temple) Tamil inscriptions, recording donations made until (and in) the 3rd year (of the reign) of king Parakēsarivarman *alias* the lord, the glorious Rājendra-Chōladēva [I.].—The donations recorded in Nos. 7 and 8 were made by Kundavaiyār, the elder sister of Rājarāja I.; see above, No. 716.

723.—*Ep. Ind.* Vol. V. p. 47, and Plate. Shērmādēvi (Rāmasvāmin temple) Tamil inscription of the 3rd year (of the reign) of king Parakēsarivarman *alias* the glorious Rājendra-Chōladēva [I.].¹

724.—*South-Ind. Inscr.* Vol. III. No. 53, p. 108. Tiruvallam (Bilvanāthēśvara temple) Tamil inscription of the 3rd year (of the reign) of king Parakēsarivarman *alias* the glorious Rājendra-Chōladēva [I.].

The inscription records the sale of some land to “Sōmanātha, (the son of) Koḡgunivarmadharmamahārāja, the supreme lord of Nipunilapura,² Śrīnātha, the glorious Śivamahārāja, the Vaidumba Śaṅkaradēva.”

725.—*South-Ind. Inscr.* Vol. III. No. 10, p. 16. Ukkal (Vishṇu temple) Tamil inscription of the 4th year (of the reign) of king Parakēsarivarman *alias* the glorious Rājendra-Chōladēva [I.].

726.—*South-Ind. Inscr.* Vol. III. No. 54, p. 109. Tiruvallam (Bilvanāthēśvara temple) Tamil inscription of the 4th year (of the reign) of king Parakēsarivarman *alias* the glorious Rājendra-Chōladēva [I.].

727.—*South-Ind. Inscr.* Vol. II. No. 9, p. 90. Tanjore (Rājarājēśvara temple) Tamil inscription of the 6th year (of the reign) of king Parakēsarivarman *alias* the lord, the glorious Rājendra-Chōladēva [I.], who conquered Idaiturai-nādu, Vanavāsi, Kolippākkai, the camp of Maṇṇai (Maṇṇaikkaḍagam or Maṇṇaikkaḍakkam), the crown of the king of Īlam, . . . the crown of Sundara and the pearl-necklace of Indra which the king of the South (*i.e.* the Pāṇḍya) had previously given to that (king of Īlam), the whole Īla-maṇḍalam, the crown *etc.* of the (king of) Kēraḷa, and many ancient islands.

728.—*Ś. 943**.—*Ep. Carn.* Vol. IV. p. 115, No. 16. Belatūru (Bānēśvara temple) Kanarese inscription of the 9th year of the reign of the glorious Muḍigoṇḍa-Rājendra-Chōḷa (*i.e.* the Chōḷa king Rājendra-Chōḷa I.):—

‘Thursday, the moon being in Makara, the *nakṣatra* being Uttarāśādhā, during the full-moon *tithi* of the month of Āśādhā in the Raudra year (which corresponded to) the nine-hundred-and-forty-third year of the Śaka years,—in the ninth year of the reign . . .’

Thursday, 7th July A.D. 1020; see *Ep. Ind.* Vol. VI. p. 20, No. 32.

729.—*South-Ind. Inscr.* Vol. III. No. 18, p. 27. Mēlpāḍi (Chōḷēśvara temple) Tamil inscription of the 9th year (of the reign) of king Parakēsarivarman *alias* the glorious Rājendra-Chōladēva [I.].—To the conquests enumerated in No. 727 the inscription adds those of the crown of pure gold which Paraśurāma had deposited at Śāndimattivu, of the seven and a half *lakṣhas* of Iraṭṭa-pāḍi (Iraṭṭa-pāḍi, Raṭṭa-pāḍi) of Jayasimha (*i.e.* the W. Chālukya Jayasimha II.)³ who was defeated at Muśaṅgi,⁴ and of the principal great mountains (which contained) the nine treasures (of Kuvēra).

¹ Certain names in this inscription suggest that Rājendra-Chōḷa I. had the *diruḍa* Nigarili-Chōḷa, *i.e.* ‘the unequalled Chōḷa.’ Probably he also was called Uttama Chōḷa; see *South-Ind. Inscr.* Vol. III. p. 14.

² ‘A mistake for Kuvalālapura.’ Compare above, No. 708.

³ Compare above, No. 152.

⁴ Some inscriptions have *Muyaṅgi*.

730.—*South-Ind. Inscr.* Vol. I. No. 42, p. 68. Māmallapuram Tamil inscription of the 9th year (of the reign) of the glorious Rājendra-Chōladēva¹ (*i.e.*, probably, the Chōla king Rājendra-Chōla I.).

731.—*Ś. 943**.—*Ep. Carn.* Vol. III. p. 204, No. 134. Nandigunda (Mallēdēva temple) Kanarese inscription [of the Chōla king Rājendra-Chōla I.] :—

(L. 1).—Sa(sa)ka-varisham 943ne[ya] Raudra-samvatsarada Phālguna-māsa[da] su(su)kla-[pa]ksham Budhavāram punname Uttare-nakshatram sōma-grahāpad=andu.

Wednesday, 1st March A.D. 1021; a lunar eclipse, visible in India; see *Ep. Ind.* Vol. IV. p. 68, No. 4.

The inscription records the conquests enumerated in No. 729.

732.—*South-Ind. Inscr.* Vol. II. Nos. 10-19, and 54. Eleven Tanjore (Rājārājēśvara temple) Tamil inscriptions of the 10th year² (of the reign) of king Parakēsarivarman *alias* the glorious Rājendra-Chōladēva [I.].—The conquests enumerated are the same as in No. 729.

733.—*South-Ind. Inscr.* Vol. I. Nos. 67 and 68, pp. 98 and 100. Two Tirumalai Tamil rock inscriptions of the 12th year (of the reign) of king Parakēsarivarman *alias* the lord, the glorious Rājendra-Chōladēva [I.].—To the conquests enumerated in No. 729 the inscriptions add those of Śakkara-kōttam (Chakrakōtta), Madura-maṇḍalam, Nāmaṇaikkōṇai, Pañchappalli, Māsuni-dēsam, the treasures of Indiradan (Indraratha ?)³ of the race of the Moon (whom he defeated in the hall at Ādinagar), Oḍḍa-vishayam, Kōśalai-nāḍu, Taṇḍabutti (Daṇḍabhukti) of Dharmapāla, Takkaṇalāḍam (Dakṣiṇa-Lāṭa) of Raṇasūtra, Vaṅgāla-dēsam of Gōvindachandra, elephants *etc.* of Mahipāla,⁴ Uttiralāḍam (Uttara-Lāṭa), and the Gaṅgā.

734.—*South-Ind. Inscr.* Vol. II. No. 20, p. 106, and Plates. Tanjore (Rājārājēśvara temple) Tamil inscription of the 242nd day of the 19th year (of the reign) of king Parakēsarivarman *alias* the lord, the glorious Rājendra-Chōladēva [I.].—After recording the conquests enumerated in No. 733, the inscription adds that the king, having despatched many ships and caught Saṁgrāmaṇijayōttuṅgavarman, the king of Kaḍāram,⁵ took his treasures *etc.*, Śrīvishayam,⁶ Pannai, Malaiyūr, Māyirūṇḍam (surrounded by the sea), Ilaṅgāśōgam (*i.e.* Laṅkāśōka), Pappālam,⁶ Mēvilimbaṅgam, Vālaippandūru, Talaitakkōlam, Mādamāliṅgam, Ilāmuri-dēsam, Nakkavāram (*i.e.* the Nicobar Islands),⁶ and Kaḍāram.

735.—*Ś. 954*.—*Ep. Carn.* Vol. III. p. 208, No. 164. Suttūru (Sōmēśvara temple) Kanarese inscription of the 31st (*really* 21st) year (of the reign) of king Parakēsarivarman *alias* the lord, the glorious Rājendra-Chōladēva [I.], who took the Eastern country, the Gaṅgā, and Kaḍāram :—

(L. 3).—Sa(sa)ka-var[sha] 9[54]neya Âṅgira-samvatsarada Kārttika-māsa . . [rp]nam[i]⁷ tale-devasam=āge bidige Sōmavāra Rōhiṇi-nakshatradal.

Monday, 23rd October A.D. 1032; see *Ep. Ind.* Vol. IV. p. 69, No. 5, and Vol. VI. p. 22.

¹ The published text has *Vī[ra*]-Rājendra*-, but the above is in accordance with a correction communicated to me by Dr. Hultzsch.

² Nos. 12 and 13 have: "After (the harvest of) *paśāṇ* in the tenth year."

³ For an Indraratha who probably was a contemporary of Rājendra-Chōla I., see *North. Inscr.* No. 340.

⁴ Perhaps the Pāla king Mahipāla I.; compare *ibid.* No. 59.

⁵ See Mr. Venkayya's *Report* for 1898-99, p. 17, and compare above, No. 712, note. See also *South-Ind. Inscr.* Vol. III. p. 194 f.

⁶ [This is the reading of an inscription at Kaṇḍiyūr (No. 23 of 1895). According to l. 80 of the large Leyden grant, Śrīvishaya was the country ruled over by the king of Kaṭāha or Kaḍāram.—E. H.]

⁷ Read *paurṇami*(?).

736.—*Ś. 955.*—*Ep. Carn.* Vol. IV. p. 115, No. 17. Belatūru (Bānēśvara temple) Kanarese inscription of the 22nd year (of the reign) of king Parakēsarivarman *alias* the glorious Rājendra-Chōladēva [I.], who took the Eastern country, the Gaṅgā, and Kaḍāram:—

(L. 5).—Sa(śa)kanṇipakāḷ-ātīta-saivatsara-sataṅga[!]*955ya Śrīmukha-saivatsarada Mārggaśira-su(śu)ddha-pāḍivam=Mūl-Ārkkad-aṁdu.

Sunday, 25th November A.D. 1033;¹ see *Ep. Ind.* Vol. VI. p. 21, No. 33.

737.—*Ś. 959.*—*Ep. Carn.* Vol. IV. p. 130, No. 104. Aṅkanāthapura (Arkēśvara temple) Kanarese inscription of the 26th² year (of the reign) of the glorious Muḍigoṇḍa-Gaṅgegoṇḍa-Rājendra-Chōladēva (*i.e.* the Chōḷa king Rājendra-Chōḷa I.):—

(L. 1).—Sha(śa)ka-varisharṇ 959neya I(i)śvara-shatsamrada³ Āśaḍa-māssada Kāḷāshṭavaya Shāṭi-naktra Sommararada [a]ndu.

The date is irregular; see *Ep. Ind.* Vol. VI. p. 21, No. 34.

738.—*Ep. Ind.* Vol. IV. p. 218, No. 15. Date of a Tirumalavāḍi (Vaidyanātha temple) Tamil inscription of the [3]2nd (*really* 22nd) year (of the reign) of Jayaṅgoṇḍa-Chōḷa, the king Rājakēsarivarman *alias* the lord, the glorious Rājādhirājadēva (*i.e.* the Chōḷa king Rājādhirāja I.):—

‘In the [3]2nd (*really* 22nd) year . . . on the day of Śravana, which corresponded to a Thursday in the month of Vriśchika in this year.’

[*Ś. 961*] : Thursday, 22nd November A.D. 1039.

739.—*Ep. Ind.* Vol. IV. p. 216, No. 12. Date of a Tirumalavāḍi (Vaidyanātha temple) Tamil inscription of the 26th year (of the reign) of king Rājakēsarivarman, surnamed Jayaṅgoṇḍa-Chōḷa, *alias* the lord, the glorious Rājādhirājadēva [I.]:—

‘In the [2]6th year . . . at night on the day of Uttara (-Phalgunī), which corresponded to a Wednesday in the month of Mīna in this year.’

[*Ś. 965*] : Wednesday, 14th March A.D. 1044.

740.—*Ep. Ind.* Vol. IV. p. 217, No. 13. Date of a Tiruppaṅgili (Nīlivanēśvara temple) Tamil inscription of the 27th year (of the reign) of Jayaṅgoṇḍa-Chōḷa, the king Rājakēsarivarman *alias* the lord, the glorious Rājādhirājadēva [I.]:—

‘In the [2]7th year . . . on the day of Mūla, which corresponded to a Wednesday and to the ninth *tithi* of the second fortnight of the month of Kumbha.’

[*Ś. 968*] : Wednesday, 13th February A.D. 1045.

741.—*South-Ind. Inscr.* Vol. III. No. 28, p. 53. Maṇimaṅgalam (Rājagōpāla-Perumāḷ temple) Tamil inscription of the 29th year (of the reign) of king Rājakēsarivarman *alias* the lord, the glorious Rājādhirājadēva, surnamed Jayaṅgoṇḍa-Chōḷa; (*i.e.* the Chōḷa king Rājādhirāja I.):—

‘In the 29th year . . . on the day of Śravana, which corresponded to a Wednesday and to the second *tithi* of the first fortnight of the month of Dhanuṣ.’

[*Ś. 969*] : Wednesday, 3rd December A.D. 1046; but the *tithi* which ended on this day was the third, not the second *tithi* of the bright half; see *Ep. Ind.* Vol. IV. p. 217, No. 14.

The inscription mentions among those conquered by Rājādhirāja: the three allied kings of the South Mānābharaṇa, Vira-Kēraḷa, and Sundara-Pāṇḍya; [the W. Chālukyas] Āhavamalla (Sōmēśvara I.),⁵ Vikki (*i.e.* Vikramāditya VI.) and Vijayāditya (*i.e.* Vishnuvardhana Vijayāditya); Śāṅgamayaṇ; the kings of Ceylon Vikramabāhu, Vikrama-Pāṇḍya,

¹ Ordinarily this day would fall in the month Pausa; but see *Ep. Ind.* Vol. VI. p. 21, note 3.

² For an inscription of the 31st year see below, under *Addenda*.

³ Read *-samvatsarada Āśāḍha-māssada Kāḷāshṭamiyūṁ Sōḍṭi-nakshatram Sōmarad-aṁdu*.

⁴ The accession of Rājādhirāja I. took place between (approximately) the 15th March and the 3rd December A.D. 1018; see *Ep. Ind.* Vol. VII. p. 7.

⁵ See above, No. 159 ff.

Vīra-Śālamēgaṇ, and Śrīvallabha-Madanarāja; and also, in the northern region, Gaṇḍar-Dinakaraṇ (Gaṇḍarāditya ?), Nāranaṇ (Nārāyaṇa), Kaṇavadi (Gaṇapati), and Madisūdanaṇ (Madhusūdana).¹

742.—Ś. 970*.—*Ep. Ind.* Vol. V. p. 207, and Plate. Miṇḍigal (Sômēśvara temple) Kanarese inscription of the 30th year (of the reign) of king Rājakēsarivarman *alias* the lord, the glorious Rājādhirājadēva [I.] (who took the head² of the glorious Vīra-Pāṇḍya and the Sāle of Śerama *i.e.* the Chēra king),³ and of his *Danḍanāyaka* Appimayya *alias* Rājendra-Chōḷa-Brahmamārāya :—

(L. 1).—Sa(śa)ka-varisha 970nē yī Sabbajitu-samvatsaradal . . . śrī-Rājādhirājadēva[r*]gge yāṇḍu muvattaneya; see *ibid.* Vol. IV. p. 216, No. 11.

743.—Ś. 975.—*Ep. Carn.* Vol. IV. p. 131, No. 114. Koḷagāla (Māri temple) Kanarese inscription of the 35th year (of the reign) of the glorious Rājādhirājadēva [I.] :—

(L. 1).— . . . [35]āvaḍu [Sa]kha-va[ri]śam⁴ 975[ne]ya Vijayōschaiva-samvatsara[da] Jēshṭha-māsada sukla-pakshada tra[yō*]daśi Ādityavārad=andu.

Probably Sunday, 23rd May A.D. 1053; but the *tīthi* which ended on this day was the 3rd, not the 13th *tīthi* of the bright half; see *Ep. Ind.* Vol. VI. p. 22, No. 35.

744.—*South-Ind. Inscr.* Vol. III. No. 55, p. 112. Tiruvallam (Bilvanāthēśvara temple) incomplete Tamil inscription of the 3rd year (of the reign) of king Parakēsarivarman *alias* the lord, the glorious Rājēndradēva (*i.e.* the Chōḷa king Rājēndradēva).⁵—The inscription mentions Rājēndradēva's elder brother (*viz.* Rājādhirāja I.) and refers to the conquest of Iraṭṭa-pāḍi, the setting-up of a pillar of victory at Kollāpuram, and the defeat of (the W. Chālukya) Āhavamalla (Sômēśvara I.) at Koppam.

745.—*South-Ind. Inscr.* Vol. III. No. 29, p. 59. Maṇimaṅgalam (Rājagōpāla-Perumāḷ temple) Tamil inscription of the 82nd day of the 4th year (of the reign) of king Parakēsarivarman *alias* the lord, the glorious Rājēndradēva :—

'On the 8[2]nd day of the fourth year . . . on the day of Rōhiṇī, which corresponded to a Thursday and to the eighth *tīthi* of the second fortnight of the month of Simha in this year.'

[Ś. 977]: Thursday, 17th August A.D. 1055;⁶ see *Ep. Ind.* Vol. VI. p. 24, No. 38.

The inscription opens with a list of relatives on whom the king conferred certain titles. It gives a detailed account of the defeat of the Śālukki (*i.e.* W. Chālukya) Āhavamalla Sômēśvara I.) at Koppam. It also records the despatch of an army to Ceylon, where the Kālīṅga king Vīra-Śālamēgaṇ was decapitated and the two sons of the Ceylon king Mānābharaṇa were taken prisoners.

746.—*South-Ind. Inscr.* Vol. I. No. 127, p. 134, and Vol. II. p. 304, C. Viriñchipuram (Mārgasahāyēśvara temple) Tamil inscription of the 5th year (of the reign) of king Parakēsarivarman *alias* the lord, the glorious Rājēndradēva, who defeated (the W. Chālukya) Āhavamalla (Sômēśvara I.) at Koppam.

¹ The introduction states that Rājādhirāja appointed seven relatives to be governors over the Chēra, Chālukya, Pāṇḍya and Gaṅga countries, Ceylon, the Pallava country and Kanyakubja. In the expedition to the north he destroyed the palace of the Chālukya at Kampili; compare above, No. 171.

² See above, p. 115, note 2.

³ No. 741 above states that the king destroyed the ships of the Chēra king at Kāṇḍāṭṭur-Śālai.

⁴ Read *Śaka-varsham* *Jyēshṭha-māsada sukla-*.

⁵ The accession of Rājēndradēva took place on (approximately) the 28th May A.D. 1052; see *Ep. Ind.* Vol. VII. p. 7.

⁶ On this date the *tīthi* of the date (which was the *Janm-dśhtamī* or *Kṛishṇ-dśhtamī*) commenced 14 h. 20 m. after mean sunrise.

747.—*Ś. 979.*—*Ep. Ind.* Vol. VI. p. 215, and Plate. Beḷatūru Kanarese inscription of the 6th year of the reign of the glorious Chōḷa king Rājēndradēva, recording the self-immolation¹ of a Śūdra's wife after her husband's death; (composed by Malla) :—

'When the glorious Chōḷa king had taken possession of the whole earth,—(he,) Rājēndradēva, the slayer of crowds of proud enemies,—(and) was renowned, when six years (of his reign) had passed, and when one said: "the Śaka year in (its) extent (is) ninety-seven and nine" (and when) the (cyclic) year (was) the well-known Hēmaḷambi, the auspicious month indeed Kārttika (and) the day of the dark (half) the twelfth (*tithi*), a Monday.'

Monday, 27th October A.D. 1057; see *ibid.* p. 23, No. 36.

748.—*South-Ind. Inscr.* Vol. II. No. 67, p. 306.² Tanjore (Rājarājēśvara temple) Tamil inscription of the 6th year (of the reign) of king Parakēsarivarman *alias* the lord, the glorious Rājēndradēva, who defeated (the W. Chālukya) Āhavamalla (Sōmēśvara I.) at Koppam.

749.—*South-Ind. Inscr.* Vol. III. No. 21, p. 39. Karuvūr (Paśupatiśvara temple) Tamil inscription of the 9th year (of the reign) of king Parakēsarivarman *alias* the lord, the glorious Rājēndradēva, who defeated (the W. Chālukya) Āhavamalla (Sōmēśvara I.) at Koppam.

750.—*South-Ind. Inscr.* Vol. III. No. 22, p. 41. Karuvūr (Paśupatiśvara temple) Tamil inscription of the 9th year (of the reign) of king Parakēsarivarman *alias* the lord, the glorious Rājendra-Chōḷadēva (*i.e.* the Chōḷa king Rājēndradēva).—The historical introduction is the same as in No. 749.

751.—*Ś. 984.*—*Ep. Carn.* Vol. IV. p. 131, No. 115; *Ep. Ind.* Vol. VI. p. 23, No. 37. Gujjappanahundi Kanarese memorial stone of the 12th (*really* 11th) year (of the reign) of king Rājakēsarivarman (!) *alias* the lord, the glorious Rājēndradēva :—

'In the twelfth year . . . during the full-moon *tithi* of the month of Phālguna in the . . . year (which was) the Śaka year 984.'

The introduction mentions Rājēndradēva's elder brother (*vis.* Rājādhirāja I.), the setting-up of a pillar of victory at Kollāpuram, and the defeat of (the W. Chālukya) Āhavamalla (Sōmēśvara I.) at Koppam.

752.—*South-Ind. Inscr.* Vol. III. No. 56, p. 113. Tiruvallam (Bilvanāthēśvara temple) incomplete Tamil inscription of the 2nd year (of the reign) of king Rājakēsarivarman *alias* the lord, the glorious Rājamahēndradēva (*i.e.* the Chōḷa king Rājamahēndra).³

753.—*South-Ind. Inscr.* Vol. III. No. 20, p. 33. Karuvūr (Paśupatiśvara temple) Tamil inscription (of the reign) of king Rājakēsarivarman *alias* the lord, the glorious Virarājēndradēva (*i.e.* the Chōḷa king Virarājēndra I.), recording a grant which was to take effect "from (the year) which was opposite to the 3rd year" (of the king's reign).⁴—The inscription records, amongst other things, the defeat of (the W. Chālukya) Āhavamalla (Sōmēśvara I.) and his two sons Vikkalaṇ (*i.e.* Vikramāditya VI.) and Siṅgaṇaṇ (*i.e.* Jayasimha III.)⁵ at Kūḍalaṅgamam.

¹ This "is not identical with the so-called suttee (*sati*) of Brāhmanical usage."

² *ibid.* the introductions are given of seven other inscriptions of the 3rd, 5th and 9th years of Rājēndradēva; three of them state that Rājēndradēva set up a pillar of victory at Kollāpuram.—For another inscription of the 6th year see below, under *Addenda*.

³ By Dr. Hultzsch provisionally placed between Rājēndra and Virarājēndra I. "Perhaps Rājamahēndra was a son and temporary co-regent of Rājēndra."

⁴ For inscriptions of the 4th, 5th, 6th and 7th years see below, under *Addenda*. The inscription No. 755 mentions "the year which was opposite to the seventh year (of the reign) of the emperor Sri-Virarājēndradēva."—For the name of Virarājēndra's queen see below, No. 765.

⁵ Compare above, No. 176.

754.—*South-Ind. Inscr.* Vol. III. No. 30, p. 65. Maṇimaṅgalam (Rājagōpāla-Perumā temple) Tamil inscription of the 5th year (of the reign) of king Rājakēsarivarman *alias* the lord, the glorious Virarājēndradēva [I.] :—

‘In the fifth year . . . on the day of Uttara (-Phalgunī), which corresponded to a Monday and to the fourteenth *tithi* of the second fortnight of the month of Kanyā in this year.’

Between A.D. 1054 and 1069 the only day for which this date would be correct is Monday, 10th September A.D. 1067 [in Ś. 989]; see *Ep. Ind.* Vol. VII. p. 9.

The first portion of the historical introduction agrees with that of No. 753. The subsequent portion, among other things, relates the sham coronation (of Vikramāditya VI.) as Vallabha (*i.e.* W. Chālukya king), and records the bestowal of the country of Vēṅgi on Vijayāditya (*i.e.* the E. Chālukya Vijayāditya VI.¹).

755.—*South-Ind. Inscr.* Vol. III. No. 57, p. 115. Tiruvallam (Bilvanāthēśvara temple) Tamil inscription of the 200th day of the 3rd year (of the reign) of king Parakēsarivarman *alias* the lord, the glorious Adhirājēndradēva (*i.e.* the Chōla king Adhirājendra).²—The inscription mentions his queen (by the title) Ulagamuluduḍaiyār (*i.e.* ‘the mistress of the whole world’).

756.—*South-Ind. Inscr.* Vol. III. No. 64, p. 133. Tiruvorriyūr (Ādhipurēśvara temple) Tamil inscription of the 2nd year (of the reign) of king Rājakēsarivarman *alias* the lord, the glorious Rājendra-Chōladēva [II.], who captured elephants at Vayirāgaram (Vajrākara), conquered the king of Dhārā at Chakrakōṭṭa, and took possession of the Eastern country; ³ (*i.e.* the Chōla king Kulōttuṅga-Chōla I.).⁴

757.—*South-Ind. Inscr.* Vol. III. No. 65, p. 135. Tiruvālaṅgāḍu (Vaṭāranyēśvara temple) Tamil inscription of the 2nd year (of the reign) of king Rājakēsarivarman *alias* the lord, the glorious Rājendra-Chōladēva [II.], described as in No. 756; (*i.e.* the Chōla king Kulōttuṅga-Chōla I.).

758.—*South-Ind. Inscr.* Vol. III. No. 66, p. 137. Kōlār (Kōlāramma temple) damaged Tamil inscription of the 2nd year (of the reign) of king Rājakēsarivarman *alias* the lord, the glorious Rājendra-Chōladēva [II.], described as in No. 756; (*i.e.* the Chōla king Kulōttuṅga-Chōla I.).

759.—*South-Ind. Inscr.* Vol. III. No. 67, p. 139. Sōmaṅgalam (Saundararāja-Perumā temple) Tamil inscription of the 3rd year (of the reign) of king Rājakēsarivarman *alias* the lord, the glorious Rājendra-Chōladēva [II.], described as in No. 756; (*i.e.* the Chōla king Kulōttuṅga-Chōla I.).

760.—*South-Ind. Inscr.* Vol. III. No. 77, p. 172. Kāvāntaṇḍalam (Lakshminārāyaṇa temple) incomplete Tamil inscription of the 4th year (of the reign) of king Rājakēsarivarman *alias* the lord, the glorious Rājendra-Chōladēva [II.], described as in No. 756; (*i.e.* the Chōla king Kulōttuṅga-Chōla I.) :—

‘In the 4th year . . . on a Thursday which corresponded to (the day of) Śravana and to the sixth *tithi* of the first fortnight of the month of Vṛiśchika in this year.’

[Ś. 995] : Thursday, 7th November A.D. 1073; ⁵ see *Ep. Ind.* Vol. VII. p. 1, No. 56.

¹ See *South-Ind. Inscr.* Vol. III. pp. 128 and 132; and above, Nos. 571 and 572.

² By Dr. Hultzsch provisionally placed between Virarājendra I. and Kulōttuṅga-Chōla I.—The inscription refers to some transactions of the year which was opposite to the seventh year (of the reign) of the emperor Śrī-Virarājēndradēva.

³ *I.e.*, perhaps, the country of Vēṅgi.

⁴ The accession of Kulōttuṅga-Chōla I. took place between (approximately) the 14th March and the 8th October A.D. 1070; see *Ep. Ind.* Vol. VII. p. 7.—Compare also above, No. 571.

⁵ On this day the *tithi* of the date commenced 1 h. 38 m. after mean sunrise.

761.—*South-Ind. Inscr.* Vol. III. No. 68, p. 141.¹ Conjeeveram (Pāṇḍava-Perumāḷ temple) Tamil inscription of the 5th year (of the reign) of king Rājakesarivarman *alias* the lord, the glorious Kulōttuṅga-Chōḷadēva [I.].

The inscription refers to the king's victories, gained while he was heir-apparent, at Chakrakōṭṭa and Vayirāgaram (Vajrākara); it then states that he vanquished the king of Kuntala, crowned himself as king of the country on the banks of the Kāvēri, and decapitated an unnamed king of the South.

762.—*Ś. 998.—Ep. Ind.* Vol. VI. p. 220, and p. 278, No. 39. Date of a Chēbrōlu Telugu inscription of the 7th year of the reign of the asylum of the whole world, the glorious Vishṇuwardhana-mahārāja (*i.e.* the Chōḷa king Kulōttuṅga-Chōḷa I.) :—

(L. 1).—Śakha(ka)-varshaṁblu 998nēmti Nala-śam(śam)vatsara śrāhi . . . pravarddhamāna-vijayarājya-śam(śam)vatsara[mblu] 7nēṇḍu Māgha-māsamuna punnamayu Su(śu)kravāramuna sōmagrahana-nimittamunan=.

Friday, 10th February A.D. 1077; a lunar eclipse, visible in India; but the day was the full-moon day of Phālguna, not of Māgha.

763.—*South-Ind. Inscr.* Vol. III. No. 78, p. 174. Perumbēr (Tāndōṇṇīśvara temple) Tamil inscription of the 11th year (of the reign) of king Rājakesarivarman *alias* the lord, the glorious Kulōttuṅga-Chōḷadēva [I.].—To the account given in No. 761 the inscription adds that the king defeated Vikkalaṇ (*i.e.* the W. Chālukya Vikramāditya VI.) and conquered Gaṅga-maṇḍalam and Śiṅgaṇam.²

764.—*South-Ind. Inscr.* Vol. III. No. 69, p. 144. Tirukkālukkunṇam (Vēdagiriśvara temple) Tamil inscription of the 14th and 15th years (of the reign) of king Rājakesarivarman *alias* the Chakravartin, the glorious Kulōttuṅga-Chōḷadēva [I.].—After the account given in No. 763 the inscription states that the king invaded the Pāṇḍya country, destroyed the forest in which the five Pāṇchavas (*i.e.* Pāṇḍyas) had sought refuge, “subdued the south-western portion of the peninsula as far as the Gulf of Maṇṇār, the Podiyil mountain (in the Tinnevely district), Cape Comorin, Kōṭṭāṇṇu, the Sahya (*i.e.* the Western Ghāṭs) and Kuḍamalai-nāḍu (*i.e.* Malabar).”

765.—*South-Ind. Inscr.* Vol. II. No. 58, p. 232. Tanjore (Rājarājēśvara temple) apparently unfinished Tamil inscription of the 15th³ year (of the reign) of king Rājakesarivarman *alias* the Chakravartin, the glorious Kulōttuṅga-Chōḷadēva [I.].—The historical account is the same as in No. 764. The inscription gives the name (Arumōḷi-Naṅgaiyār) of the queen of Virarājēndradēva I.⁴

766.—Tēki plates of the E. Chālukya Chōḍagaṅga Rājarāja of Vēṅḡ, of the 17th year of the reign (of Kulōttuṅga-Chōḷa I.); see above, No. 571.

767.—*South-Ind. Inscr.* Vol. III. No. 70, p. 149. Śrīraṅgam (Raṅgaṇātha temple) Tamil inscription of the 18th year (of the reign) of king Rājakesarivarman *alias* the Chakravartin, the glorious Kulōttuṅga-Chōḷadēva [I.].—The historical introduction is the same as in No. 764.

768.—*South-Ind. Inscr.* Vol. II. No. 77, p. 391. Conjeeveram Tamil inscription of the 20th year (of the reign) of the glorious Kulōttuṅga-Chōḷadēva [I.].—The inscription mentions the king's consort (by the title) Bhuvanamuḷududaiyāl (*i.e.* ‘the mistress of the whole world’).

769.—*South-Ind. Inscr.* Vol. III. No. 71, p. 152.¹ Kīlappaluvūr (Vatamūlēśvara temple) Tamil inscription of the 20th year (of the reign) of king Rājakesarivarman *alias* the

¹ See *Ind. Ant.* Vol. XXI. p. 281.

² According to Dr. Hultzsch this seems to refer to the dominions of Vikramāditya's younger brother Jayasimha.

III.—Instead of Śiṅgaṇam No. 777 has *Koṅgaṇa-dēyam* (the Koṅkaṇa country).

³ For an inscription of the 16th year see below, under *Addenda*.

⁴ See above, No. 758 f.

Tribhuvanachakravartin, the glorious **Kulōttuṅga-Chōḷadēva** [I.].—The historical introduction¹ is the same as in No. 764.

770.—*Archæol. Surv. of South. India*, Vol. IV. p. 224. The small Tamil Leyden grant² (on three plates) of the 20th year (of the reign) of king **Rājakēsarivarman** *alias* the *Chakravartin*, the glorious **Kulōttuṅga-Chōḷadēva** [I.].

771.—Chellūr plates of the E. Chālukya **Vira-Chōḍa** of Vēṅgī, of the 21st year of the reign (of **Kulōttuṅga-Chōḍa I.**); see above, No. 572.

772.—Pithāpuram plates of the E. Chālukya **Vira-Chōḍa** of Vēṅgī, of the 23rd year of the reign (of **Kulōttuṅga-Chōḍa I.**); see above, No. 573.

773.—*South-Ind. Inscr.* Vol. III. No. 59, p. 120. Tiruvallam (Bilvanāthēśvara temple) Tamil inscription of the 23rd year (of the reign) of **Kulōttuṅga-Chōḷadēva** [I.], recording a gift by a Gaṅga chief (Nīlagaṅga ?) for the benefit of his daughter who was the consort of prince **Vira-Chōḷadēva** (*i.e.*, according to Dr. Hultsch, **Vira-Chōḍa**, the son of **Kulōttuṅga-Chōḷa I.** and viceroy of Vēṅgī),³

774.—*South-Ind. Inscr.* Vol. III. No. 58, p. 119. Tiruvallam (Bilvanāthēśvara temple) Tamil inscription of the 26th year (of the reign) of king **Rājakēsarivarman** *alias* the *Chakravartin*, the glorious **Kulōttuṅga-Chōḷadēva** [I.].—The inscription refers to the defeat of (the W. Chālukyas) **Vikkalaṇ** and **Śīṅgaṇaṇ** (*i.e.* **Vikramāditya VI.** and **Jayasimha III.**). It also mentions the king's consort (by the title) **Bhūṇanamuluduḍaiyāl** (*i.e.* 'the mistress of the whole world').

775.—*South-Ind. Inscr.* Vol. III. No. 72, p. 156.⁴ Tiruvīḍaimarudūr (Mahāliṅgasvamin temple) Tamil inscription of the 172nd day of the 26th year (of the reign) of king **Rājakēsarivarman** *alias* the *Chakravartin*, the glorious **Kulōttuṅga-Chōḷadēva** [I.].—To the account given in No. 764 the inscription adds the conquest of **Kaliṅga-maṇḍalam**. It also mentions the king's three queens **Dīnachintāmaṇi**, **Ēḷisai-Vallabhī**, and **Tyāgavallī**.

776.—*Ep. Ind.* Vol. V. p. 106. Tiruvorriyūr (Ādhipurīśvara temple) inscription of the 30th year (of the reign) of **Jayadhara** (*i.e.* the Chōḷa king **Kulōttuṅga-Chōḷa I.**):—
(L. 1).—**Trimśat(t)-samē Jayadharasya tu va[r]ttamānē.**

777.—*South-Ind. Inscr.* Vol. III. No. 73, p. 160. Chōḷapuram (Chōḷēśvara temple) incomplete Tamil inscription of the 180th day of the 30th year (of the reign) of king **Rājakēsarivarman** *alias* the *Chakravartin*, the glorious **Kulōttuṅga-Chōḷadēva** [I.], recording a grant made by himself from his palace at **Kāñchipuram**.—The historical introduction agrees on the whole with that of No. 775; but of the queens **Dīnachintāmaṇi** is omitted.

778.—*South-Ind. Inscr.* Vol. II. No. 78, p. 392. Conjeeveram Tamil inscription of the 34th year (of the reign) of the Chōḷa king **Kulōttuṅga-Chōḷadēva** [I.].—The introduction of this inscription is identical with that of No. 768.

779.—§. 1030 (for 1028).—*Ep. Carn.* Vol. III. p. 191, No. 51; *Ep. Ind.* Vol. IV. p. 70, No. 6. Sindhuvaḷḷi (Śamkarēśvara temple) Tamil inscription of the 37th year of the reign of the glorious **Kulōttuṅga-Chōḷadēva** [I.]:—

'In the Vyaya year which corresponded to the Śaka year one thousand and thirty, (and) in the thirty-seventh year of the reign'

¹ The inscription mentions a man who had the title 'Virudarājabhayaṅkara' which was a surname of **Kulōttuṅga-Chōḷa I.** himself.

² The grant will soon be properly edited.

³ See above, Nos. 771 and 772.

⁴ See *Ind. Ant.* Vol. XXI. p. 282.

780.— *Ep. Ind.* Vol. V. p. 104, and Plate. Tiruvengāḍu (Śvêtāranyēśvara temple) inscription of the 39th year of the reign of the glorious Kulōttuṅga-Chōḷa [I.] :—

(L. 1).— . . . avati vasumatīm śr[i]-Kulōttuṅga-Chōḷē . . . tan-nava-ttūmā-varshē.

781.— *South-Ind. Inscr.* Vol. III. No. 74, p. 163. Conjeeveram (Pāṇḍava-Perumāḷ temple) Tamil inscription of the 39th year (of the reign) of king Rājakēsarivarman *alias* the lord, the glorious Kulōttuṅga-Chōḷadēva [I.] :— The historical introduction is the same as in No. 761.

782.— *South-Ind. Inscr.* Vol. III. No. 75, p. 165,¹ and Plate. Tirukkalukkuṇṇam (Vēdagiriśvara temple) Tamil inscription of the 42nd year (of the reign) of . . . the Chakravartin, the glorious Kulōttuṅga-Chōḷadēva [I.] :— The historical introduction is the same as in No. 777.

783.— Ś. 1035.— *Ep. Carn.* Vol. III. p. 190, No. 44. Ēchiganahalli (Sômēśvara temple) Kanarese inscription of the reign of the glorious Kulōttuṅga-Chōḷadēva [I.] :—

(L. 1).— Sa(sa)k[a-va]risham 1035neya Jaya-samvatsarada Pā(phā)lguna-māsada aparapaksham pā[ḍi]va Ādityavāram Hasta-nakshatram.

Sunday, 22nd February A.D. 1114; but the Jovian year was Vijaya, not Jaya; see *Ep. Ind.* Vol. IV. p. 72, No. 9.

784.— *Ep. Ind.* Vol. V. p. 105. Chidambaram (Natarāja temple) Tamil inscription of the 44th year (of the reign) of Jayadhara (*i.e.* the Chōḷa king Kulōttuṅga-Chōḷa I., originally named Rājendra-Chōḷa [II.]), recording donations by Kundavai Āḷvār, the daughter of (the E. Chōḷukya) Rājārāja [I.] and younger sister of the *Tribhuvanachakravartin* Kulōttuṅga-Chōḷa [I.] :—

‘In the year forty-four (of the reign) of Jayadhara . . . at the time (of the rising o the sign) Rishabha, on the day of Rōhiṇi, which corresponded to a Friday in the month during which (the sign) Mīna was shining.’

[Ś. 1035]: Friday, 13th March A.D. 1114; see *ibid.* Vol. IV. p. 70, No. 7.

The second portion of the inscription states that a stone which the king of Kambōja had given to Rājendra-Chōḷa (*i.e.* Kulōttuṅga-Chōḷa I.) by order of the latter was inserted into the wall of a hall in front of the shrine.

c. 785.— *Ep. Ind.* Vol. IV. p. 70, No. 8. Date of an Ālaṅguḍi (Āpatsahāyēśvara temple) Tamil inscription of the 45th year (of the reign) of king Rājakēsarivarman *alias* the *Tribhuvanachakravartin*, the glorious Kulōttuṅga-Chōḷadēva [I.] :—

‘In the 45th year . . . on the day of Uttar[āshāḍhā], which corresponded to a Thursday and to the seventh *tithi* of the first fortnight of the month of Tūlā.’

[Ś. 1036]: Thursday, 8th October A.D. 1114.

786.— Ś. 1036.— *Ep. Ind.* Vol. VI. p. 220, and p. 279, No. 40. Date of a Drākshārāmu (Bhīmēśvara temple) Telugu inscription of the 45th year of the reign of the asylum of the whole world, the glorious Vishṇuvardhana-mahārāja (*i.e.* the Chōḷa king Kulōttuṅga-Chōḷa I.) :—

(L. 1).— Śaka-va[r*]ṣamābulu 1036 . . . [pra]varddhamāna-vijayarājya-divya-samvatsa 45 Dhanu-māsamuna śukla-pa[kshamu]na ēkāda[s]iyu Budhavāramu nāṇḍu uttarāyana-vyākṛānta-nimittamuna.

Perhaps Wednesday, 9th December A.D. 1114;³ but this was not the day of the Uttarāyana-samkrānti (which took place on the 24th December).

¹ Compare *Ind. Ant.* Vol. XXI. p. 286.

² Read -vyākṛānta-.

³ On this day the *tithi* of the date commenced 7 h. 52 m. after mean sunrise.

787.— Ś. 1037.— *Ep. Ind.* Vol. VI. p. 222. Bhīṃavaram (Nārāyaṇasvāmin temple) Sanskrit and Telugu pillar inscription of the 45th year of the reign of king Parāntaka . . . the asylum of the whole world, the glorious Viṣṇuvardhana-mahārāja (*i.e.* the Chōla king Kulōttuṅga-Chōla I.) :—

(L. 11).— Sarvvalōkāśraya-śrī-Viṣṇuvarddhana-mahārājula pravarddhamāna-vijayarājya-sarivatsarambulu 45gu śrāhi Sa(śa)ka-va[r*]shambulu 1037gunēṇḍi(ṇṭi) Chaitra-vishuvusaṁkrāntti-ni[mitta]muna.¹

788.— *South-Ind. Inscr.* Vol. III. No. 76, p. 168. Śrīraṅgam (Jambukēśvara temple) Tamil inscription of the 47th year (of the reign) of king Rājakēsarivarman *alias* the *Tribhuvanachakravartin*, the glorious Kulōttuṅga-Chōladēva [I.]— The historical introduction is the same as in No. 777.

789.— *Ep. Ind.* Vol. V. p. 48, No. 26. Date of a Maṇṇārguḍi (Rājagōpāla-Perumāḷ temple) Tamil inscription of the 48th year (of the reign) of king Rājakēsarivarman *alias* the *Tribhuvanachakravartin*, the glorious Kulōttuṅga-Chōladēva [I.] :—

‘In the 48th year . . . on the day of Ādrā, which corresponded to a Monday and to the thirteenth *tithi* of the first fortnight of the month of Makara.’

[Ś. 1039] : Monday, 7th January A.D. 1118.

790.— *South-Ind. Inscr.* Vol. III. No. 31, p. 71. Maṇimaṅgalam (Rājagōpāla-Perumāḷ temple) Tamil inscription of the 48th year (of the reign) of king Rājakēsarivarman *alias* the *Tribhuvanachakravartin*, the glorious Kulōttuṅga-Chōladēva [I.] :—

‘In the [48]th year . . . on the day of Śatabhishaj, which corresponded to a Friday and to the second *tithi* of the first fortnight of the month of Kumbha.’

[Ś. 1039] : Friday, 25th January A.D. 1118 ; see *Ep. Ind.* Vol. IV. p. 262, No. 20.

The inscription mentions the king's consort (by the title) Ulaguḍaiyāl (*i.e.* ‘the mistress of the world’).

791.— *South-Ind. Inscr.* Vol. III. No. 32, p. 74. Another Maṇimaṅgalam (Rājagōpāla-Perumāḷ temple) mutilated Tamil inscription of the 48th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Kulōttuṅga-Chōladēva [I.]

The date of this inscription is the same as that of No. 790, except that the twelfth is wrongly quoted instead of the second *tithi* ; see *Ep. Ind.* Vol. V. p. 198, No. 28.

792.— Ś. 1040.— *Ep. Ind.* Vol. VI. p. 221, No. 9. Date of a Drākshārāma (Bhīmēśvara temple) Sanskrit and Telugu inscription of the 250th day of the 49th year of the reign of the *Mahārājādhirāja*² Viṣṇuvardhana, the *Tribhuvanachakravartin*, the glorious Kulōttuṅga-Chōladēva [I.] :—

(L. 3).— Śā[k]-ābdē vyōma-vēd-āmba[ra-śāsi]-ga[ṇi]tē . . . Śaka-va[r*]shambulu 104[0]ṇḍa . . . [rā*]jya-divya-sarivatsa 49yagu śr[ā*]hi dinamulu 250 . . . uttarāyana-saṁkr[ā*]ānti-ni[mittamuna].³

793.— *South-Ind. Inscr.* Vol. I. No. 155, p. 168 ; *Ep. Ind.* Vol. V. p. 103, and Plate. Ohidambaram inscription of the glorious Kulōttuṅga-Chōla [I.], who subdued the five Pāṇḍyas, burnt the fort of Kōṭṭāra, and crushed the army of the Kēraḷas.⁴

794.— *Ep. Ind.* Vol. IV. p. 263, No. 21. Date of a Tiruviḍaimarudūr (Mahāliṅgasvāmin temple) Tamil inscription of the 4th year (of the reign) of king Parakēsarivarman *alias* the

¹ The date would correspond to the 24th March A.D. 1115, but does not admit of verification.

² The inscription gives many more titles and names of the king.

³ Read *-mittamuna*.

⁴ Compare above, No. 764.

Tribhuvanachakravartin, the glorious **Vikrama-Chôladêva** (*i.e.* the Chôla king **Vikrama-Chôla**):—

'In the 4th year . . . on the day of Śatabhishaj, which corresponded to a Monday and to the eighth *tithi* of the second fortnight of the month of Rishabha.'

[§. 1044]: Monday, 1st May A.D. 1122; see *ibid.* Vol. VII. p. 3.

795.—*South-Ind. Inscr.* Vol. II. No. 68, p. 310. Tanjore (Rājarājēśvara temple) Tamil inscription of the 4th year (of the reign) of king **Parakēsarivarman** *alias* the *Tribhuvanachakravartin*, the glorious **Vikrama-Chôladêva**.—The historical introduction records that in his youth the king put to flight the Teliṅga Vīmaṇ (Bhima)² of Kuḷam and burnt the country of Kaliṅga, stayed in Vēṅgai-maṇḍalam, conquered the North and then proceeded to the South, where he crowned himself (as Chôla king). The inscription mentions his queens Mukkōkkilānaḍi³ and Tyāgapatākā.

796.—*South-Ind. Inscr.* Vol. III. No. 33, p. 75. Maṇimaṅgalam (Rājagôpāla-Perumāḷ temple) damaged Tamil inscription of the 4th year (of the reign) of king **Parakēsarivarman** *alias* the *Tribhuvanachakravartin*, the glorious **Vikrama-Chôladêva**.—The historical introduction, so far as it is preserved, agrees with that of No. 795.

797.—*Ep. Ind.* Vol. IV. p. 263, No. 22. Date of a Tiruvēṅgāḍu (Śvētāranyēśvara temple) Tamil inscription of the 5th year (of the reign) of king **Parakēsarivarman** *alias* the *Tribhuvanachakravartin*, the glorious **Vikrama-Chôladêva**:—

'In the 5th year . . . on the day of Ārdrā, which corresponded to a Monday and to the eleventh *tithi* of the second fortnight of the month of Simha.'

[§. 1044]: Monday, 31st July A.D. 1122; see *ibid.* Vol. VII. p. 3.

798.—*Ep. Ind.* Vol. VII. p. 3, No. 57. Date in a Tiruvârûr (Tyāgarāja temple) Tamil inscription of the 5th year (of the reign) of the *Tribhuvanachakravartin*, the glorious **Vikrama-Chôladêva**:—

'In the fifth year . . . on a Thursday which corresponded to (the day of) Maghā and to the fifth *tithi* of the first fortnight of the month of Mithuna.'

[§. 1045]: Thursday, 31st May A.D. 1123.

799.—*Ep. Ind.* Vol. IV. p. 73, No. 10. Another date in the same Tiruvârûr (Tyāgarāja temple) Tamil inscription, of the 340th day of the 5th year (of the reign) of king **Parakēsarivarman** *alias* the *Tribhuvanachakravartin*, the glorious **Vikrama-Chôladêva**:—

'In the fifth year . . . on the three-hundred-and-fortieth day, which was (the day of) Hasta, a Sunday, and the seventh *tithi* of the first fortnight of the month of Mithuna.'

[§. 1045]: Sunday, 3rd June A.D. 1123; but the *tithi* which ended on this day was the 8th, not the 7th; see *ibid.* Vol. VII. p. 4.

800.—§. 1049.—*Ep. Ind.* Vol. VI. p. 225. Chēbrôlu (Kēśavasvāmin temple) Telugu inscription of the 9th year of the reign of the Chôla *Mahārājādhirāja Tribhuvanachakravartin* **Vikrama-Chôla**, recording a grant by the *Mahāmaṇḍalēśvara Nambaya*,⁴ 'lord of the town of Kolipākā,' of the Durjaya family:—

(L. 12).— . . . pravardda(rddha)māna-vijayarāja-saṁvatsarambulu 9agunē[ṇṭi] Sa(śa)ka-[va]rūshambulu 1049agn Shla(Plā)va-⁵saṁvatsara Jēshṭha-⁶māsa sōmagrahana(ṇa)-nimityamuna.

¹ The accession of Vikrama-Chôla took place on (approximately) the 29th June A.D. 1118; see *Ep. Ind.* Vol. VII. p. 8.

² According to Dr. Hultzsch apparently one of the Nāyakas of Ellora.— Compare below, No. 833.

³ Compare below, Nos. 801 and 812.

⁴ For an inscription of the same Nambaya (Nambirāja, Nambha) of §. 1052 (for 1051) see *Ep. Ind.* Vol. VI. p. 224; for one of his son Trailōkyamalla of §. 1081 (for 1082) *ibid.* p. 225; the name of Nambaya's father most probably was Malla.

⁵ Wrong for *Plavanāya*.

⁶ Read *Jyēṣṭhā*- or *Jyāishṭhā*.

27th May A.D. 1127; a lunar eclipse, visible in India; see *Ep. Ind.* Vol. VI. p. 280, No. 42, and Vol. VII. p. 3.

801.— *South-Ind. Inscr.* Vol. III. No. 80, p. 187. Conjeeveram (Arulāla-Perumā temple) Tamil inscription of the 9th year (of the reign) of king **Parakēsarivarman** *alias* the *Tribhuvanachakravartin*, the glorious **Vikrama-Chōḷadēva**.— The introduction mentions the conquest of Kalinga, and the king's queen Mukkōkkilānādi.¹

802.— The Tirumalavāḍi (Vaidyanātha temple) Tamil inscription of the 15th year of the reign of king **Parakēsarivarman** *alias* the *Tribhuvanachakravartin*, the glorious **Vikrama-Chōḷadēva** (below, No. 805), records gifts made by him—

‘in the tenth year (of his reign, in) the month Sittirai, on a Sunday which corresponded to (the day of) Hasta (on) the thirteenth *tithi* of the fortnight of the auspicious waxing moon.’

[S. 1050]: Sunday, 15th April, or Saturday, 14th April A.D. 1128;² see *Ep. Ind.* Vol. VII. p. 5, No. 59.

803.— *Ep. Ind.* Vol. VII. p. 170, No. 64. Date of a Tirumāṇikuḷi (Vāmanapurīśvara temple) Tamil inscription of the 11th year (of the reign) of king **Parakēsarivarman** *alias* the *Tribhuvanachakravartin*, the glorious **Vikrama-Chōḷadēva** :—

‘In the eleventh year . . . on the day of Viśākhā, which corresponded to a Wednesday and to the eleventh *tithi* of the second fortnight of the month of’³

[S. 1050]: Wednesday, 19th December A.D. 1128.

804.— *Ep. Ind.* Vol. VII. p. 4, No. 58. Date of a Kōvilāḍi (Divyajñānēśvara temple) Tamil inscription of the 11th year (of the reign) of the *Tribhuvanachakravartin*, the glorious **Vikrama-Chōḷadēva** :—

‘In the 11th year . . . on the day of Punarvasu, which corresponded to a Saturday and to the thirteenth *tithi* of the first fortnight of the month of Makara.’

[S. 1050]: Saturday, 5th January A.D. 1129.

805.— *South-Ind. Inscr.* Vol. III. No. 79, p. 182. Tirumalavāḍi (Vaidyanātha temple) Tamil inscription of the 15th year (of the reign) of king **Parakēsarivarman** *alias* the *Tribhuvanachakravartin*, the glorious **Vikrama-Chōḷadēva**.— The historical introduction agrees with that of No. 795. The inscription mentions two of the king's queens, Tyāgapatākā and Dharanimuḷuduḍaiyāl (*i.e.* ‘the mistress of the whole earth’).

(For a date of the 10th year in the same inscription see above, No. 802.)

806.— *Ep. Ind.* Vol. VII. p. 171, No. 65. Date of an Uḍaiyārkōyil (Karavandīśvara temple) Tamil inscription of the 15th year (of the reign) of king [Parakēsari]varman *alias* the *Tribhuvanachakravartin*, the glorious **Vikrama-Chōḷadēva** :—

‘In the 15th year . . . [on the day of] . . . , which corresponded to a Thursday and to the . . . [tithi] of the second fortnight of the month of Simha.’

807.— *Ep. Ind.* Vol. VI. p. 228. Śevilimēḍu (Kailāsanātha temple) inscription of the 16th year (of the reign) of king **Vikrama-Chōḷadēva**, surnamed **Akalāṅka** and **Tyāgavārākara** :—

(L. 2).— Śrīmad-Vikra[ma]-Chōḷadēva-nṛipatēr=vva[rshē] śubhē shōḍaśē . . . Vaiśākha-māsē=parē [*] pakshē s=ōttara-Chandravāra-viditē kālē.

[S. 1056]: Monday, 16th April A.D. 1134; see *ibid.* Vol. VI. p. 279, No. 41, and Vol. VII. p. 3.

¹ Compare Nos. 795 and 812.

² In the original date either the *nakṣatra* or the week-day is quoted incorrectly.

³ The month was that of Dhanu.

⁴ *I.e.* Tyāgasamudra; compare above, No. 576.

808.— **Ś. 1054** (for 1057).— *Ep. Ind.* Vol. VI. p. 281, No. 43. Date of a Niḍubrōlu Telugu inscription of the 17th year of the reign of the *Tribhuvanachakravartin*, the glorious **Vikrama-Chōḍadēva** :—

(L. 63).— vijayarājya-samvatsarambulu pa[d]iyēḍ=agunēmḍu Śaka-varshambulu 1054-gunēmṭṭi Vaisākha-suddha-tṭṭitṭyayū¹ Guruvāramu nāṇḍu.

[**Ś. 1057**] : Thursday, 18th April A.D. 1135; see *ibid.* Vol. VII. p. 5.

809.— **Ś. 1056** (for 1065).— Chellūr plates of the reign of **Kulōttuṅga-Chōḍa II.**, the son of **Vikrama-Chōḍa**; above, No. 574 (the date of which corresponds to the 24th March A.D. 1143).

810.— *South-Ind. Inscr.* Vol. III. No. 34, p. 77. Maṇimaṅgalam (Rājagōpāla-Perumāl temple) Tamil inscription of the 8th year (of the reign) of the *Tribhuvanachakravartin*, the glorious **Kulōttuṅga-Chōḍadēva** (*i.e.*, probably, the Chōḷa king **Kulōttuṅga-Chōḷa II.**).— The inscription records the grant of a piece of land which had been purchased in the 13th year (of the reign) of **Vikrama-Chōḍadēva**.

811.— *South-Ind. Inscr.* Vol. I. No. 89, p. 126. Notice of a Māmallapuram Tamil inscription of the 14th year (of the reign) of king **Rājakēsarivarman** *alias* the glorious **Kulōttuṅga-Chōḍadēva** (*i.e.*, probably, the Chōḷa king **Kulōttuṅga-Chōḷa II.**).

812.— *South-Ind. Inscr.* Vol. III. No. 35, p. 79. Maṇimaṅgalam (Rājagōpāla-Perumāl temple) Tamil inscription of the 8th² year (of the reign) of king **Parakēsarivarman** *alias* the *Tribhuvanachakravartin*, the glorious **Rājarājadēva** (*i.e.* the Chōḷa king **Rājarāja II.**).— The inscription mentions the king's consort (under the name or title) **Mukkōkkiḷāṇaḍigal**.³

813.— Supplied by Dr. Hultzsch.⁴ Date of a Conjeeveram (Ēkāmrānātha temple) Tamil inscription of the 15th year (of the reign) of king **Parakēsarivarman** *alias* the *Tribhuvanachakravartin*, the glorious **Rājarājadēva** (*i.e.* the Chōḷa king **Rājarāja II.**):⁵—

'In the fifteenth year . . . on the day of Purnavasū, which was a Thursday and the fourteenth *tithi* of the first fortnight of the month of Tai.'

814.— *South-Ind. Inscr.* Vol. III. No. 85, p. 209. Tirumāṇikulī (Vāmanapurīśvara temple) Tamil inscription of the 3rd year (of the reign) of king **Parakēsarivarman** *alias* the *Tribhuvanachakravartin*, the glorious **Kulōttuṅga-Chōḍadēva** (*i.e.* the Chōḷa king **Kulōttuṅga-Chōḷa III.**),⁶ who was pleased to be seated together with (his queen) **Bhuvanamuḷududaiyāl** (*i.e.* 'the mistress of the whole world') on the throne of heroes (which consisted of) pure gold :—

'In the third year . . . on the day of Āśvinī, which corresponded to a Monday and to the fifth *tithi* of the second fortnight of the month of Sīmha.'

[**Ś. 1102**] : 12th August A.D. 1180; but the day was a Tuesday, not a Monday; see *Ep. Ind.* Vol. VII. p. 171, No. 66.

815.— *Ep. Ind.* Vol. VII. p. 171, No. 67. Date of a Giḍaṅgil (Bhaktaparādīśvara temple) Tamil inscription of the 3rd year (of the reign) of king **Parakēsarivarman** *alias* the *Tribhuvanachakravartin*, the glorious **Kulōttuṅga-Chōḍadēva** [III.] :—

'In the 3rd year . . . on the day of Āśvinī, which corresponded to a Wednesday which was the twenty-seventh solar day of the month of Sīmha.'

The date is irregular.

¹ Read *-tṭṭitṭyayū*.

² For an inscription which quotes the third year of apparently **Rājarāja II.**, see below, under *Adiṇḍa*.

³ Compare above, Nos. 795 and 801.

⁴ Compare *South-Ind. Inscr.* Vol. III. p. 79, and note 4.

⁵ The inscription opens with the same panegyric introduction as No. 812.

⁶ The accession of **Kulōttuṅga-Chōḷa III.** took place between (approximately) the 8th June and the 8th July A.D. 1178; see *Ep. Ind.* Vol. VII. p. 8.

816.— *Ep. Ind.* Vol. VII. p. 172, No. 68. Date of a Tirumâṇikūḷi (Vâmanapurisvara temple) Tamil inscription of the 7th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Virarâjendra-Chôḷadêva (i.e. the Chôḷa king Kulôttuṅga-Chôḷa III.) :—

‘In the seventh year . . . on the day of Śatabhishaj, which was the fourteenth *tithi* of the first fortnight and a Wednesday, which was the twenty-sixth solar day of the month of Simba.’

[S. 1106] : Wednesday, 22nd August A.D. 1184.

817.— *Ep. Ind.* Vol. IV. p. 264, No. 23. Date of a Tiruvengâḍu (Śvêtâranyêśvara temple) Tamil inscription of the 8th year (of the reign) of king Parakêsarivarman alias the *Tribhuvanachakravartin*, the glorious Kulôttuṅga-Chôḷadêva [III.] :—

‘In the eighth year . . . on the day of Anurâdhâ, which corresponded to a Monday and to the tenth *tithi* of the first fortnight of the month of Karkâṭaka.’

[S. 1107] : Monday, 8th July A.D. 1185.¹

818.— *South-Ind. Inscr.* Vol. III. No. 60, p. 121. Tiruvallam (Bilvanâthêśvara temple) Tamil inscription of the 8th² year (of the reign) of Kulôttuṅga-Chôḷadêva [III.], dated ‘from the month of Mâsi;’ recording a grant by Miṇḍaṇ Attimallaṇ Śambuvarâyaṇ of the Śeṅgēṇi family.

819.— *South-Ind. Inscr.* Vol. I. No. 132, p. 136. Notice of a Viriñchipuram Tamil inscription of the 10th (?) year (of the reign) of the *Tribhuvanachakravartin* Kônêrimêṇkoṇḍa³ Kulôttuṅga-Chôḷadêva (i.e. the Chôḷa king Kulôttuṅga-Chôḷa III.),⁴ recording a grant by the Śeṅgēṇi chief mentioned in No. 820.

820.— *South-Ind. Inscr.* Vol. III. No. 61, p. 121. Tiruvallam (Bilvanâthêśvara temple) Tamil inscription of the 11th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Kônêrimêḷkoṇḍa⁵ Kulôttuṅga-Chôḷadêva (i.e. the Chôḷa king Kulôttuṅga-Chôḷa III.), recording a grant by the Śeṅgēṇi chief Ammaiappaṇ Kaṇṇuḍaipperumâṇ alias Vikrama-Śôḷa-Śambuvarâyaṇ.

821.— *South-Ind. Inscr.* Vol. III. No. 36, p. 82. Maṇimaṅgalam (Râjagôpâla-Perumâḷ temple) Tamil inscription of the 12th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Kulôttuṅga-Chôḷadêva [III.], who was pleased to take Madurai, Îlam, and the crowned head of the Pâṇḍya :⁶—

‘In the 12th year . . . on the day of Chitrâ, which corresponded to a Monday and to the ninth *tithi* of the second fortnight of the month of Dhanus.’

[S. 1111] : Monday, 4th December A.D. 1189; but the *tithi* of the date ended 0 h. 51 m. before mean sunrise of this day; see *Ep. Ind.* Vol. IV. p. 220, No. 19.

822.— *Ep. Ind.* Vol. VII. p. 6, No. 60. Date of a Sômaṅgalam (Sômanâthêśvara temple) Tamil inscription of the 14th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Kulôttuṅga-Chôḷadêva [III.], who was pleased to take Madurai and Îlam :—

‘In the 14th year . . . on a day which was Thursday, (the day of) Pushya, and the first *tithi* of the first fortnight of the month of Makara.’

[S. 1113] : Thursday, 2nd January A.D. 1192.⁷

¹ The *tithi* of the date was either a current *tithi* or a *prâthama-dâśami*.

² For inscriptions of the 9th and 11th years see below, under *Addenda*.

³ Compare Kônêrimaikoṇḍa, ‘the unequalled among kings’; on this title see *South-Ind. Inscr.* Vol. II. p. 110.

⁴ See *ibid.* Vol. III. p. 121.

⁵ See No. 819.

⁶ Compare above, p. 115, note 2.

⁷ In the original date the first fortnight is wrongly quoted instead of the second.

823.— *Ep. Ind.* Vol. IV. p. 265, No. 24. Date of a Kaḍappēri (Śvētāranyēśvara temple) Tamil inscription of the 16th year (of the reign) of the *Tribhuvanachakravartin*, the glorious **Kulōttuṅga-Chōḷadēva** [III.] :—

‘In the sixteenth year . . . on the day which was a Saturday and (the day of) Mūla and a fourth *tithi* and the tenth solar day of the month of Āni.’

[Ś. 1116] : Saturday, 4th June A.D. 1194; but the *tithi* which ended on this day was a 14th, not a 4th *tithi*.

824.— *Ep. Ind.* Vol. VII. p. 172, No. 69. Date of a Tirunallār (Darbhāranyēśvara temple) Tamil inscription of the 17th year (of the reign) of the *Tribhuvanachakravartin*, the glorious **Kulōttuṅga-Chōḷadēva** [III.], who, having taken Madurai, was pleased to take also the crowned head of the Pāṇḍya :—

‘In the 17th year . . . on the day of Uttara-Bhadrapadā, which corresponded to a Monday and to the second *tithi* of the first fortnight of the month of Kumbha.’

[Ś. 1116] : Monday, 13th February A.D. 1195.²

825.— *Ep. Ind.* Vol. VII. p. 172, No. 70. Date of a Tiruveṇṇainallūr (Kṛipāpurīśvara temple) Tamil inscription of the 17th year (of the reign) of the *Tribhuvanachakravartin*, the glorious **Kulōttuṅga-Chōḷadēva** [III.], who was pleased to take Madurai and the crowned head of the Pāṇḍya :—

‘In the 17th year . . . on the day of Rōhinī, which corresponded to a Thursday and to the thirteenth *tithi* of the second fortnight of the month of Mithuna.’

[Ś. 1117] : Thursday, 8th June A.D. 1195.

826.— *Ep. Ind.* Vol. VII. p. 173, No. 71. Date of a Kōvilvenṇi (Ikshupurīśvara temple) Tamil inscription of the 19th year (of the reign) of the *Tribhuvanachakravartin*, the glorious **Kulōttuṅga-Chōḷadēva** [III.], who was pleased to take Madurai and the crowned head of the Pāṇḍya :—

‘In the nineteenth year . . . on the day of Hasta, which corresponded to a Monday and to the ninth *tithi* of the first fortnight of the month of Kanyā.’

[Ś. 1118] : Monday, 2nd September A.D. 1196; but the *nakshatra* is irregular.

827.— *South-Ind. Inscr.* Vol. III. No. 88, p. 217. Śrīraṅgam (Raṅganātha temple) incomplete Tamil³ inscription of the 19th year (of the reign) of king Parakēsarivarman, who was pleased to be seated together with (his queen) Bhuvanamuḷudaiyār (*i.e.* ‘the mistress of the whole world’) on the throne of heroes (which consisted of) pure gold, *alias* the *Tribhuvanachakravartin*, the glorious **Kulōttuṅga-Chōḷadēva** [III.], who, having taken Madurai, was pleased to take the crowned head of the Pāṇḍya :—

‘In the 19th year . . . on the day of Pushya, which corresponded to a Tuesday and to the fifth *tithi* of the second fortnight of the month of Vṛiśchika.’

[Ś. 1118] : Tuesday, 12th November A.D. 1196; see *Ep. Ind.* Vol. IV. p. 219, No. 17.

The inscription notices an expedition into the North, at the end of which the king entered Kachohi (*i.e.* Conjeeveram). It then states that he defeated the son of [Vīra-]Pāṇḍya, took Madurai and bestowed it on Vikrama-Pāṇḍya, and that he took the crowned head of Vīra-Pāṇḍya who had revolted again and given battle at Neṭṭūr. It further relates that he pardoned the Pāṇḍya (apparently Vīra-Pāṇḍya), and the Chēra king, who seems to be identical with a person subsequently mentioned as Vīra-Kēraḷa.

828.— *Ep. Ind.* Vol. VII. p. 173, No. 72. Date of a Tirumāpikuḷi (Vāmaṇapurīśvara temple) Tamil inscription of the 19th year (of the reign) of the *Tribhuvanachakravartin*, the glorious

¹ Compare above, p. 115, note 2.

² On this day the *tithi* of the date commenced 1 h. 55 m. after mean sunrise.

³ The inscription contains one verse in Sanskrit.

Kulōttuṅga-Chōḷadēva [III.], who, having taken Madurai, was pleased to take also the crowned head of the Pāṇḍya :—

‘In the nineteenth year . . . on the day of Hasta, which corresponded to a Wednesday and to the twelfth *tithi* of the first fortnight, which was the sixth solar day of the month of Rishabha.’

[Ś. 1119] : Wednesday, 30th April A.D. 1197.

829.—Ś. 1119.—*Ep. Ind.* Vol. IV. p. 219, No. 16. Date of a Nellore (Raiganāyaka temple) Tamil inscription of the 19th (*really* 20th) year of the reign of the glorious **Kulōttuṅga-Chōḷadēva** [III.], who took Madurai and Īlam and was pleased to take the crowned head of the Pāṇḍya :—

‘In the year Piṅgala (which corresponded to) the Śaka year one thousand one hundred and nineteen, (and) in the nineteenth year (of the reign) . . . [on the day of] Rêvatî and a Friday which was the fifteenth solar day of the month of Vṛiṣchika.’

Friday, 21st November A.D. 1197; but this was the 25th, not the 15th day of the month of Vṛiṣchika.

830.—*Ep. Ind.* Vol. V. p. 199, No. 31. Date of a Maṇimaṅgalam (Rājagōpāla-Perumāḷ temple) Tamil inscription of the 20th year (of the reign) of the *Tribhuvanachakravartin* **Kulōttuṅga-Chōḷadēva** [III.], who was pleased to take Madurai and the crowned head of the Pāṇḍya :—

‘In the 20th year . . . on the day of Svāti, which corresponded to a Thursday and to the tenth *tithi* of the first fortnight of the month of Vṛiṣabha.’

The date is irregular.

831.—*Ep. Ind.* Vol. VII. p. 174, No. 73. Date of a Tirumāṇikūḷi (Vāmanapurīśvara temple) Tamil inscription of the 21st year (of the reign) of the *Tribhuvanachakravartin*, the glorious **Kulōttuṅga-Chōḷadēva** [III.], who was pleased to take Madurai, Īlam, and the crowned head of the Pāṇḍya :—

‘In the 21st year . . . on the day of Maghā, which corresponded to a Wednesday and to the tenth *tithi* of the first fortnight of the month of Mēsha.’

[Ś. 1121] : Wednesday, 7th April A.D. 1199.

832.—*Ep. Ind.* Vol. VII. p. 174, No. 74. Date of a Tirumāṇikūḷi (Vāmanapurīśvara temple) Tamil inscription of the 21st year (of the reign) of king **Parakēsarivarman** *alias* the *Tribhuvanachakravartin*, the glorious **Kulōttuṅga-Chōḷadēva** [III.], who, having taken Madurai and Īlam, was pleased to take also the crowned head of the Pāṇḍya :—

‘In the 21st year . . . on the day of Hasta, which corresponded to a Saturday and to the thirteenth *tithi* of the first fortnight of the month of Rishabha.’

[Ś. 1121] : Saturday, 10th April A.D. 1199; but this day fell in the month of Mēsha, not of Rishabha.

833.—*Ep. Ind.* Vol. VI. p. 333. Kambayanallūr (Dēsināthēśvara temple) Tamil inscription of the 22nd year (of the reign) of the *Tribhuvanachakravartin*, the glorious **Kulōttuṅga-Chōḷadēva** [III.], recording a grant by **Viḍugāḍaḷagiya-Perumāḷ**,¹ the king of Tagaḍai² and (son of) Rājārāja-Adigaṇ,³ to Nāgai-Nāyaka of Kuḷaṇ (*i.e.* Kuḷam⁴ or Kuḷaṇūr, the modern Ellore).

¹ See below, No. 834.

² *I.e.* Tagaḍūr, the modern Dharmapuri, the head-quarters of a tāluka in the Salem district.

³ *I.e.* Rājārāja, the lord of Adigai (the modern Tiruvadi near Cuddalore).

⁴ Compare above, No. 795.

834.— *South-Ind. Inscr.* Vol. I. No. 75, p. 106 (see also No. 76, p. 107); *Ep. Ind.* Vol. VI. p. 332. Tirumalai (near Pôlûr) Sanskrit and Tamil inscription, recording the restoration of images of a Yaksha and a Yakshî, which had been set up by the Kêraḷa (or Chêra, Vañji¹) king Yavanikâ (or, in Tamil, Eḷiṇi), by his descendant Vyāmuktaśravaṇôjjvala (in Tamil, Viḍugāḍaḷagiya-Perumāl),² the lord of Takatâ (in Tamil, Tagadai) and son of the Adhika prince Râjarâja (in Tamil, Adigaṇṇ³ Vagaṇṇ).

835.— *South-Ind. Inscr.* Vol. III. No. 23, p. 43. Karuvûr (Paśupatiśvara temple) Tamil inscription of the 23rd year (of the reign) of the *Tribhuvanachakravartin*, the glorious Kulôttuṅga-Chôḷadêva, who was pleased to take Îlam, Madurai, the crowned head of the Pândya, and Karuvûr,— the *Tribhuvanachakravartin* Kônêri[nmai]koṇḍaṇ;⁴ (i.e. the Chôḷa king Kulôttuṅga-Chôḷa III.).

836.— *South-Ind. Inscr.* Vol. III. No. 24, p. 45. Karuvûr (Paśupatiśvara temple) Tamil inscription of the 25th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Kulôttuṅga-Chôḷadêva [III.], who was pleased to take Îlam, Madurai, the crowned head of the Pândya, and Karuvûr.

837.— *Ep. Ind.* Vol. VI. p. 281, No. 44. Date of a Conjeeveram (Êkâmrânâtha temple) Tamil inscription of the 27th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Kulôttuṅga-Chôḷadêva [III.], who was pleased to take Madurai and the crowned head of the Pândya :—

‘In the 27th year . . . on the day of Anurâdhâ, which corresponded to a Thursday and to the eleventh day of the month of Vaigâsi in this year.’

[S. 1127]: Thursday, 5th May A.D. 1205.

The inscription⁵ mentions “the supreme lord of Kuvalâlapura, he who was born from the Gaṅga family, Śiyagaṅgaṇ Amarâbharanaṇ *alias* Tiruvêgambam-ndaiyâṇ.”⁶

838.— *South-Ind. Inscr.* Vol. III. No. 37, p. 84. Maṇimaṅgalam (Râjagôpâla-Perumâl temple) Tamil inscription of the 28th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Kulôttuṅga-Chôḷadêva [III.], who was pleased to take Madurai and the crowned head of the Pândya.

839.— *Ep. Ind.* Vol. V. p. 198, No. 29. Date of a Maṇimaṅgalam (Dharmêśvara temple) Tamil inscription of the 29th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Kulôttuṅga-Chôḷadêva [III.], who was pleased to take Madurai, Îlam, and the crowned head of the Pândya :—

‘In the 2[9]th year . . . on the day of Mṛigaśīrsha, which corresponded to a Wednesday and to the seventh *tithi* of the first fortnight of the month of Mîna.’

[S. 1128]: Wednesday, 7th March A.D. 1207.

840.— *Ep. Ind.* Vol. IV. p. 220, No. 18. Date of a Tirumalavâḍi (Vaidyanâtha temple) Tamil inscription of the 34th year (of the reign) of king Parakêsarivarmaṇ *alias* the *Tribhuvanachakravartin*, the glorious Tribhuvanaviradêva, who took Madurai, Îlam, Karuvûr, and the crowned head of the Pândya; (i.e. the Chôḷa king Kulôttuṅga-Chôḷa III.) :—

‘In the 34th year . . . on the day of Śravaṇa, which corresponded to a Monday and to the tenth *tithi* of the first fortnight of the month of Kanyâ.’

[S. 1133]: Monday, 19th September A.D. 1211.

¹ The traditional capital of the Chêra kingdom.

² See above, No. 833.

³ I.e. the lord of Adigai.— Compare Adiyaṇ, below, No. 937, and Adiyama, above, *s.g.* No. 415, note.

⁴ See above, No. 819.

⁵ See *South-Ind. Inscr.* Vol. III. p. 122, and note 9.

⁶ Compare below, No. 841.

841.— *South-Ind. Inscr.* Vol. III. No. 62, p. 122. Tiruvallam (Bilvanāthēśvara temple) Tamil inscription of the [3]4th year (of the reign) of Kulōttuṅga-Chōḷadēva [III.].— The inscription records a gift by Ariyapillai, the queen of (the Gaṅga chief) Amarābharāṇa-Śiyagaṅga, mentioned in No. 837.

842.— *Ep. Ind.* Vol. V. p. 199, No. 30. Date of an Uttaramallūr (Vaikuṇṭha-Perumāḷ temple) Tamil inscription of the 37th year (of the reign) of the *Tribhuvanachakravartin* Tribhuvanaviradēva, who was pleased to take Madurai, Iḷam, Karuvūr, and the crowned head of the Pāṇḍya; (*i.e.* the Chōḷa king Kulōttuṅga-Chōḷa III.):—

‘In the 37th year . . . on the day of Hasta, which corresponded to a Sunday and to the ninth *tithi* of the first fortnight of the month of Mithuna.’

[Ś. 1137]: Sunday, 7th June A.D. 1215.

843.— *Ep. Ind.* Vol. VII. p. 174 f., Nos. 75 and 76. Two dates of a Māgaral (Tirumālīśvara temple) Tamil inscription of the 4th and 5th years (of the reign) of the *Tribhuvanachakravartin*, the glorious Rājarājadēva (*i.e.* the Chōḷa king Rājarāja III.):¹—

‘In the fourth year . . . on the day of Śatabhishaj, which corresponded to a Monday and to the fifth *tithi* of the second fortnight of the month of Mithuna.’

[Ś. 1142]: Monday, 22nd June A.D. 1220.

‘In the 5th year . . . on the day of Aśvini, which corresponded to a Wednesday and to the fifth *tithi* of the second fortnight of the month of Simha.’

[Ś. 1142]: Wednesday, 19th August A.D. 1220.²

844.— *Ep. Ind.* Vol. VII. p. 175, No. 77. Date of a Kōvilveṇṇi (Ikshupurīśvara temple) Tamil inscription of the year opposite the 6th (*i.e.* the 7th year of the reign) of the *Tribhuvanachakravartin*, the glorious Rājarājadēva [III.]:—

‘In the year which was opposite the 6th year . . . on the day of Uttarāśāḍhā, which corresponded to a Thursday and to the seventh *tithi* of the first fortnight of the month of Tulā.’

[Ś. 1144]: Thursday, 13th October A.D. 1222.

845.— *Ep. Ind.* Vol. VII. p. 175, No. 78. Date of a Kīḷ-Kāśākuḍi (Ādiyappaṇ temple) Tamil inscription of the 10th year (of the reign) of Rājarājadēva [III.]:—

‘In the tenth year . . . on the day of Śravisṭhā, which corresponded to a Tuesday and to the eighth *tithi* of the second fortnight of the month of Mēsha.’

[Ś. 1148]: Tuesday, 21st April A.D. 1226.

846.— *South-Ind. Inscr.* Vol. III. No. 38, p. 85. Maṇimaṅgalam (Rājagōpāla-Perumāḷ temple) Tamil inscription of the 13th year (of the reign) of Rājarājadēva [III.].³

847.— *Ep. Ind.* Vol. VII. p. 167. Tiruvēndipuram (Dēvanāyaka-Perumāḷ temple) Tamil inscription of the year opposite the 15th year (*i.e.* the 16th year of the reign) of the *Tribhuvanachakravartin*, the glorious Rājarājadēva [III.]:—

The inscription records that, when the *Pratāpa-chakravartin*, the Hoysāṇa (Hoysaḷa) Vira-Narasimhadēva (*i.e.* Narasimha II., above, Nos. 434 and 435), heard that Kōpperuñjiṅga⁴ held Rājarāja [III.] captive at Śēndamaṅgalam, he started from Dōrasamudra, conquered the Mahara⁴ kingdom and seized its king; and that then his *Danḍanāyakas* Appana and Samudra-

¹ The accession of Rājarāja III. took place between (approximately) the 23rd June and the 13th August A.D. 1215; see *Ep. Ind.* Vol. VII. p. 169.

² As the *tithi* of the date, the 5th, commenced on this day 10 h. 38 m. after mean sunrise, it has probably been quoted erroneously instead of the 4th.

³ In other inscriptions he is called a Kāḍava or Pallava (compare above, No. 642). For an account of inscriptions of his, from which it appears that, originally a Chōḷa feudatory, he became an independent king in A.D. 1243, see *Ep. Ind.* Vol. VII. p. 163 ff.

⁴ Elsewhere called the Makara or Magara kingdom; compare above, No. 434.

Goppaya by his orders continued the campaign (in the course of which, amongst others, Parâ-kramabâhu, the king¹ of Îlam, was killed), advanced against Śēndamaṅgalam, forced Kōpperuñ-jāga to release the Chōla king, and accompanied the latter to his dominions.

848.—*Ep. Ind.* Vol. VI. p. 281, No. 45. Date of a Śrīraṅgam (Jambukēśvara temple) Tamil inscription of the year opposite the 16th year (*i.e.* the 17th year of the reign) of king Rājakēsarivarman *alias* the *Tribhuvanachakravartin*, the glorious Rājārājadēva [III.] :—

‘In the year opposite the 16th year . . . on the day of Śravaṇa, which corresponded to a Saturday and to the tenth *tithi* of the first fortnight of the month of Kanyā.’

[Ś. 1154] : Saturday, 25th September A.D. 1232.

849.—*Ep. Ind.* Vol. VI. p. 282, No. 46. Date of a Conjeeveram (Ēkāmraṇātha temple) Tamil inscription of the 17th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Rājārājadēva [III.] :—

‘In the 17th year . . . on the day of Aśvinī and a Tuesday in the first fortnight of the month of Makara.’

[Ś. 1154] : Tuesday, 18th January A.D. 1233.

850.—*South-Ind. Inscr.* Vol. III. No. 41, p. 87. Maṇimaṅgalam (Dharmēśvara temple) Tamil inscription of the 18th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Rājārājadēva [III.] :—

‘In the 18th year . . . on the day of Rēvatī, which corresponded to a Tuesday and to the second *tithi* of the second fortnight of the month of Śimha.’

[Ś. 1155] : Tuesday, 23rd August A.D. 1233 ; see *Ep. Ind.* Vol. VI. p. 282, No. 47.

851.—*South-Ind. Inscr.* Vol. III. No. 39, p. 86. Maṇimaṅgalam (Rājagōpāla-Perumāḷ temple) Tamil inscription of the 18th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Rājārājadēva [III.] :—

‘In the 18th year . . . on the day of Dhanishṭhā, which corresponded to a Wednesday and to the fifth *tithi* of the first fortnight of the month of Dhanu.’

[Ś. 1155] : Wednesday, 7th December A.D. 1233 ; see *Ep. Ind.* Vol. VI. p. 282, No. 48.

852.—*South-Ind. Inscr.* Vol. III. No. 40, p. 86. Maṇimaṅgalam (Rājagōpāla-Perumāḷ temple) Sanskrit and Tamil inscription of the 18th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Rājārājadēva [III.] :—

‘In the 18th year . . . on the day of Śravaṇa, which corresponded to a Monday and to the first *tithi* of the first fortnight of the month of Makara.’

[Ś. 1155] : Monday, 2nd January A.D. 1234 ; see *Ep. Ind.* Vol. VI. p. 283, No. 49.

853.—*Ep. Ind.* Vol. VI. p. 283, No. 50. Date of a Tiruvorriyūr (Ādhipurīśvara temple) Tamil inscription of the 19th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Rājārājadēva [III.] :—

‘In the 19th year . . . on a Sunday which corresponded to (the day of) Uttara-Bhadrpadā and to the third *tithi* of the first fortnight of the month of Śimha.’

[Ś. 1156] : either Sunday, 30th July, or Sunday, 13th August, A.D. 1234, probably the latter.²

854.—*South-Ind. Inscr.* Vol. I. No. 74, p. 105. Tirumalai Tamil inscription of the 20th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Rājārājadēva [III.], recording a donation by Attimallaṅ Śambukula-Perumāḷ³ *alias* Rājagambhira-Śambuvarāyaṇ.⁴

¹ According to Dr. Hultzsch, perhaps a prince of Ceylon.

² In the original date either Uttara-Bhadrpadā has been wrongly quoted instead of Uttara-Phalgunī, or the first fortnight instead of the second. Compare above, Nos. 480 and 604.

³ *I.e.* the Perumāḷ of the Śambu race.

⁴ Compare below, No. 866.

855.— *Ep. Ind.* Vol. VI. p. 284, No. 51. Date of a Tiruvengāḍu (Śvêtāranyēśvara temple) Tamil inscription of the 22nd year (of the reign) of the *Tribhuvanachakravartin*, the glorious Rājarājadēva [III.] :—

‘In the 22nd year . . . on the day of Uttara-Bhadrapadā, which corresponded to a Tuesday and to the fourth *tithi* of the second fortnight of the month of Mīna.’

[Ś. 1159] : Tuesday, 16th March A.D. 1238 ; but the *tithi* which ended on this day was a 14th, not a 4th *tithi*.

856.— Ś. 1160*.— *South-Ind. Inscr.* Vol. I. Nos. 59 and 60,¹ pp. 87 and 88. Two Poygai (near Viriñchipuram) Tamil inscriptions of the 22nd year (of the reign) of the *Tribhuvanachakravartin*, the glorious Rājarājadēva [III.], recording donations by the Śeṅgēṇi chief Virāśani-Ammaiyappaṇ Aḷagiya-Śōḷaṇ *alias* Edirili-Śōḷa-Śambuvarāyaṇ] :—

‘[In the month of] Tai of the twenty-second year . . . which was current during the Śaka year one thousand one hundred and sixty.’

857.— *Ep. Ind.* Vol. VI. p. 284, No. 52. Date of a Maṇṇārguḍi (Rājagōpāla-Perumāḷ temple) Tamil inscription of the year opposite the 22nd year (*i.e.* the 23rd year of the reign) of the *Tribhuvanachakravartin*, the glorious Rājarājadēva [III.] :—

‘In the year which was opposite the twenty-second year . . . on the day of Pūrvā-shāḍhā, which corresponded to a Monday and to the ninth *tithi* of the second fortnight of the month of Mīna.’

[Ś. 1160] : Monday, 28th February A.D. 1239.

858.— *Ep. Ind.* Vol. VI. p. 284, No. 53. Date of a Maṇṇārguḍi (Kailāsanātha temple) Tamil inscription of the year opposite the 22nd year (*i.e.* the 23rd year of the reign) of the *Tribhuvanachakravartin*, the glorious Rājarājadēva [III.] :—

‘In the year which was opposite the twenty-second year . . . on the day of Uttarā-shāḍhā, which corresponded to a Wednesday and to the tenth *tithi* of the second fortnight of the month of Mīna :—

[Ś. 1160] : Wednesday, 2nd March A.D. 1239.

859.— *Ep. Ind.* Vol. VI. p. 285, No. 54. Date of a Maṇṇārguḍi (Kailāsanātha temple) Tamil inscription of the year opposite the 22nd year (*i.e.* the 23rd year of the reign) of the *Tribhuvanachakravartin*, the glorious Rājarājadēva [III.] :—

‘In the year which was opposite the twenty-second year . . . on the day of Dhanishṭhā, which corresponded to a Friday and to the thirteenth *tithi* of the second fortnight of the month of Mīna.’

[Ś. 1160] : Friday, 4th March A.D. 1239.³

860.— Ś. 1161.— *South-Ind. Inscr.* Vol. I. Nos. 61 and 62,⁴ pp. 89 and 90. Two Poygai (near Viriñchipuram) Tamil inscriptions of the 24th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Rājarājadēva [III.], recording donations by Virāśani-Ammaiyappaṇ Aḷagiya-Śōḷaṇ *alias* Edirili-Śōḷa-Śambuvarāyaṇ] :—

‘From the month of Tai of the twenty-fourth year . . . which was current during the Śaka year one thousand one hundred and sixty-one.’

¹ Of No. 60 only the date remains.

² Compare below, Nos. 860 and 862.

³ On this day the *tithi* of the date commenced 5 h. 57 m. after mean sunrise.

⁴ *Ibid.* No. 63, p. 90, is a short Tamil inscription referring to the gift of the village of Puttūr, which is also recorded in Nos. 61 and 62.— No. 62 is a duplicate of No. 61.

⁵ Compare Nos. 856 and 862.

861.—*South-Ind. Inscr.* Vol. I. No. 150, p. 143. Conjeeveram (Râjasimhavarmêśvara temple) Tamil pillar inscription of the 26th year (of the reign) of the *Tribhuvanachakravartin* Râjarâjadêva [III.].

862.—*Ś. 1165.*—*South-Ind. Inscr.* Vol. I. No. 64, p. 91. Poygai (near Viriñchipuram) Tamil inscription of the 28th year (of the reign) of the glorious Râjarâjadêva [III.], recording donations by the Śeṅgēpi chief Virâśani-Ammaiappaṇ Alagiya-Śōḷaṇ alias Edirili-Śōḷa-śambuvarāyaṇ :¹—

‘From the month of Karkāṭaka of the 28th year . . . which was current after the Śaka year one thousand one hundred and sixty-five.’

863.—*Ep. Ind.* Vol. VII. p. 175, No. 79. Date of an Uḍaiyârkôyil (Karavandîśvara temple) Tamil inscription of the 3rd year (of the reign) of the *Tribhuvanachakravartin*, the glorious Râjendra-Chôḷadêva (i.e. the Chôḷa king Râjendra-Chôḷa III.) :²—

‘In the 3rd year . . . on the day of Rôhiṇî, which corresponded to a Saturday and to the fifth *tithi* of the first fortnight of the month of Mîna.’

[*Ś. 1171*]: Saturday, 20th March A.D. 1249.³

864.—*Ep. Ind.* Vol. VII. p. 176, No. 80. Date of a Śrîraṅgam (Raṅganâtha temple) Tamil inscription of the 7th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Râjendra-Chôḷadêva [III.], the hostile rod of death to the Kannariga (i.e. Karṇāṭaka) king, he who had drowned the power of the Kali (age) in the ocean, the hero's anklets on whose feet were put on by the hands of Vira-Sômêśvara⁴ :—

‘In the 7th year . . . on the day of Chitrâ, which corresponded to a Wednesday and to the eighth *tithi* of the second fortnight of the month of Makara.’

[*Ś. 1174*]: Wednesday, 25th December A.D. 1252.⁵

865.—*Ep. Ind.* Vol. VII. p. 177, No. 83. Date of a Śrîraṅgam (Raṅganâtha temple) Tamil inscription of the year opposite the 7th (i.e. the 8th year of the reign) of the *Tribhuvanachakravartin*, the glorious Râjendra-Chôḷadêva [III.], the hostile rod of death of (his) uncle Sômêśvara :⁶—

‘In the year which was opposite the seventh year . . . on the day of Aśvini, which corresponded to a Monday and to the fifth *tithi* of the first fortnight of the month of Vṛiścika.’

The date is irregular.

866.—*Ś. 1180.*—*South-Ind. Inscr.* Vol. I. No. 78, p. 108. Paḍavêḍu (Ammaiappêśvara temple) Tamil inscription of Râjagambhira Śambuvarāyaṇ :⁷—

‘To-day, which is (the day of) Rêvatî and Monday, the seventh lunar day of the former half of the month of Karkāṭaka,⁸ which was current after the Śaka year one thousand one hundred and eighty.’

The day may be Monday, 8th July A.D. 1258,⁹ but if so, the *nakshatra* is irregular; see *Ind. Ant.* Vol. XXIV. p. 16, No. 195.—During the month of Karkāṭaka of the given year the moon was in Rêvatî on Monday, 22nd July A.D. 1258, but the *tithi* which ended on this day was the 5th of the dark half.

¹ Compare above, Nos. 856 and 860.

² The accession of Râjendra-Chôḷa III. took place between (approximately) the 21st March and the 8th May A.D. 1246.

³ On this day the *tithi* of the date commenced 0 h. 30 m. after mean sunrise.

⁴ See above, No. 436.

⁵ This was the day of the Makara-(Uttarâyaṇa-)samkrânti.

⁶ See above, No. 864.

⁷ Compare above, No. 854.

⁸ Here the name of the Jovian year appears to have been omitted.

⁹ On this day the *tithi* of the date commenced 3 h. 53 m. after mean sunrise.

867.—*Ep. Ind.* Vol. VII. p. 176, No. 81. Date of a Maṇṇārguḍi (Rājagōpāla-Perumāḷ temple) Tamil inscription of the 21st year (of the reign) of the *Tribhuvanachakravartin*, the glorious Rājendra-Chōḷadēva [III.] :—

‘In the 21st year . . . on the day of Rōhiṇī, which corresponded to a Wednesday and to the eleventh *tithi* of the second fortnight of the month of Karkāṭaka.’

[Ś. 1188]: Wednesday, 30th June A.D. 1266.

868.—*Ep. Ind.* Vol. VII. p. 177, No. 82. Date of a Maṇṇārguḍi (Aṇṇāmalainātha temple) Tamil inscription of the 22nd year (of the reign) of the *Tribhuvanachakravartin*, the glorious Rājendra-Chōḷadēva [III.] :—

‘In the 22nd year . . . on the day of Viśākhā, which corresponded to a Sunday and to the fourteenth *tithi* of the first fortnight of the month of Ṛishabha.’

[Ś. 1189]: Sunday, 8th May A.D. 1267.

869.—Ś. 1236.—*Ep. Ind.* Vol. III. p. 70. Tiruvallam (Bilvanāthēśvara temple) inscription of Vira-Champa, surnamed Nidrāvasānavijayin, the son of a Chōḷa king :¹—

(L. 4).—Tuṅgaśrīka-Śakābda-bhā[ji] samayē.

870.—Ś. 1236.—*Ep. Ind.* Vol. III. p. 71. Tiruvattiyūr (Arulāḷa-Perumāḷ temple) inscription of Champa (i.e. Vira-Champa), the son of Vira-Chōḷa; (composed by Champa’s minister Vanabhid) :—

(L. 1).—Tuṅgaśrīka-śaran-mitē Śaka-nripē.

871.—*South-Ind. Inscr.* Vol. I. No. 52, p. 77. Gāṅganūr (near Vēlūr) Tamil inscription of the 17th year (of the reign) of the *Sakalalōkachakravartin* Veṇṇumaṇkoṇḍa² Sambuvarāya :—

‘On the day of Rōhiṇī, which corresponds to Monday, the first lunar day of the former half of the month of Ṛishabha of the Pramāthin year, (which was) the 17th year (of the reign)’

[Pramāthin=Ś. 1261]: Monday, 10th May A.D. 1339; see *Ind. Ant.* Vol. XXII. p. 137, No. 4.

872.—*South-Ind. Inscr.* Vol. I. No. 90, p. 126. Notice of a Māmallapuram Tamil inscription of apparently the 5th year of the reign of [Rāja]nārāyaṇa Sambuvarāya.³

873.—*South-Ind. Inscr.* Vol. I. No. 70, p. 102. Tirumalai Tamil inscription of the 12th year (of the reign) of Rājanārāyaṇa Sambuvarāja.

874.—Ś. 1403.—*Ep. Ind.* Vol. III. p. 72, and Plate. Śrīraṅgam (Jambukēśvara temple) Tamil inscription of the *Mahāmaṇḍalēśvara* Vālaka-Kāmaya alias Akkalarāja,⁴ ‘lord of Uṇṇaiyūr’:⁵—

‘At the auspicious time of Mahāmagam (Mahāmāgha), (when) Jupiter (was in) Simha, on the day of Magam (Maghā), which corresponded to a Sunday and to the full-moon *tithi* of the first fortnight of the month of Kumbha of the Plava *saṁvatsara*, which was current after the Śaka year 1403.’

Sunday, 3rd February A.D. 1482; see *Ind. Ant.* Vol. XXIV. p. 205, note 56, and Vol. XXV. p. 270.

¹ See below, No. 870.

² I.e. ‘he who took the earth by conquest.’

³ According to Mr. Venkayya, *Report* for 1899-1900, p. 34, his accession took place in Śaka-saṁvat 1259.—For a Virūchipuram Tamil inscription which mentions the *Sakalalōkachakravartin* Rājanārāyaṇa Sambuvarāya, see *South-Ind. Inscr.* Vol. I. No. 128, p. 135.

⁴ He claims to be a successor of the Chōḷa dynasty. According to Mr. Krishnaswami he probably was a dependent of one of the last kings of the first Vijayanagara dynasty.

⁵ Now a suburb of Trichinopoly.

875.—*South-Ind. Inscr.* Vol. III. No. 26, p. 47. Karuvûr (Paśupatiśvara temple) Tamil inscription of **Koṇērimēlkoṇḍāṇ**,¹ dated "on the four-hundred-and-thirty-eighth (!) day" of the 23rd year (of his reign). Since the king settled certain temple servants in a quarter which was called **Vira-Śōlaṇ-Tirumaḍaiviḷāgam** after his own name, it follows that his actual name was **Vira-Chōḷa**.

876.—*South-Ind. Inscr.* Vol. II. No. 61, p. 246, and Plate. Tanjore (Rājarājēśvara temple) Tamil inscription of the *Tribhuvanachakravartin* **Kōṇēriṇmaikoṇḍāṇ**, dated on the 334th day of the second year (of his reign).

877.—*South-Ind. Inscr.* Vol. II. No. 21, p. 111. Tanjore (Rājarājēśvara temple) Tamil inscription of the *Tribhuvanachakravartin* **Kōṇēriṇmaikoṇḍāṇ**, dated on the seventh day of the year opposite the fifth year (of his reign).

878.—*South-Ind. Inscr.* Vol. III. No. 25, p. 47. Karuvûr (Paśupatiśvara temple) Tamil inscription of the *Tribhuvanachakravartin*, the glorious **Kōṇēriṇmaikoṇḍāṇ**, containing an order which was to take effect from the month of Āḍi of the 15th (year of his reign).

879.—*South-Ind. Inscr.* Vol. II. No. 22, p. 113. Tanjore (Rājarājēśvara temple) Tamil inscription of the *Tribhuvanachakravartin* **Kōṇēriṇmaikoṇḍāṇ**, dated on the sixty-fourth day of the thirty-fifth year (of his reign).

880.—**Ś. 1127.**—*Ep. Ind.* Vol. VII. p. 153. Conjeeveram (Arulāḷa-Perumāl temple) inscription of (the **Telugu-Chōḍa**²) **Tammusiddha** or **Tammusiddhi**, recording a grant which was made at Nellûr,³ at the time of his coronation:—

(L. 20).—**śārayōgyē Śak-ābdē.**

After a number of mythical ancestors, the inscription mentions (in the solar race) Kalikāla; in his race, Madhurāntaka Pottappi-Chōḷa (founded the town of Pottappi in the Andhra country); in his family, Vetta (Betta) [I.]. In his family was king Siddhi; his younger brother Vetta (Betta) [II.]; his eldest son Dāyabhīma; his younger brother Ērasiddhi; had three sons, Manmasiddhi, Vetta (Betta) [III.] (who did not reign), and Tammusiddhi (described as the son of Gaṇḍagopāla [Ērasiddhi] and Śrīdēvi).

881.—**Ś. 1129.**—*Ep. Ind.* Vol. VII. p. 123. Tiruvālaṅgāḍu (Vatāraṇyēśvara temple) inscription of **Tammusiddha** or **Tammusiddhi**:—

(L. 18).—**Śak-ābdē dhīrayāyini.**

Genealogy substantially as in No. 880, but the names Pottappi and Vetta are here given as Pottapi and Betta. After Pottapi-Chōḷa the inscription mentions Tiluṅgavidya, while it omits Vetta (Betta) [I.]. The name Manmasiddhi is also given as Manmasiddha.

882.—**Ś. 1129.**—*Ep. Ind.* Vol. VII. p. 126. Tiruppāśûr (Vāchīśvara temple) inscription of **Tammusiddha** or **Tammusiddhi**:—

(L. 57).—**Śak-ābdē dhīrayāyini.**

Genealogy, with some omissions, generally as in No. 881; but the inscription mentions Nallasiddhi as an elder brother of Ērasiddhi.

883.—**Ś. 1129.**—*Ep. Ind.* Vol. VII. p. 149. Tiruvorriyûr (Ādhipurīśvara temple) inscription of **Tammusiddha** or **Tammusiddhi**:—

(L. 24).—**Śak-ābdē dhīrayāyini.**

This inscription, like No. 880, after Pottappi-Chōḷa, introduces Betta [I.], as an ancestor of Tiluṅgavidya (see No. 881), here called Tiluṅgabijja. Otherwise it generally agrees with Nos. 881 and 882.

¹ I group together here five inscriptions, Nos. 875-879, of kings mentioned under this title (for which see above, No. 819). Their exact identification is doubtful, and it is even uncertain whether they are all Chōḷa kings.

² Compare Mr. Venkayya's *Report* for 1899-1900, p. 17.

³ *I.e.* the modern Nellore.

884.—*South-Ind. Inscr.* Vol. III. No. 63, p. 123. Tiruvallam (Bilvanâthêśvara temple) Tamil inscription, recording a remission of taxes from the 3rd year (of the reign) of (the Telugu-Chôḍa¹) Vijaya-Gaṇḍagôpâladêva,² made by Alagiya-Pallavaṇ (*alias*) Edirili-Śôḷa-Śambu-varâyaṇ.³

885.—Supplied by Dr. Hultsch. Date of a Conjeeveram (Arulâḷa-Perumâl temple) Tamil inscription⁴ of the 7th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Vijaya-Gaṇḍagôpâladêva :—

‘In the 7th year . . . on the day of Śatabhishaj, which corresponded to a Monday and to the twelfth *tithi* of the first fortnight of the month of Tulâ.’

[Ś. 1178] : Monday, 2nd October A.D. 1256.

886.—Ś. 1187.—*Ind. Ant.* Vol. XXI. p. 122. Date of a Conjeeveram (Arulâḷa-Perumâl temple) Tamil inscription of the 15th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Vijaya-Gaṇḍagôpâladêva :—

‘In the 15th year . . . which corresponded to the Śaka year 1187, on the day of Râhîṇî, which corresponded to Saturday, the thirteenth *tithi* of the second fortnight of the month of Mithuna.’

Saturday, 13th June A.D. 1265; see *ibid.* Vol. XXII. p. 220.

887.—Ś. 1187.—*Ind. Ant.* Vol. XXI. p. 122. Date⁵ of a Conjeeveram (Arulâḷa-Perumâl temple) Tamil inscription of the 16th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Vijaya-Gaṇḍagôpâladêva :—

‘In the 1[6]th year . . . which corresponded to the Śaka year 1187, on the day of Uttara-Bhadrâpadâ, which corresponded to Saturday, the third *tithi* of the second fortnight of the month of Simha.’

Saturday, 1st August A.D. 1265; see *ibid.* Vol. XXII. p. 220.

888.—*Ep. Ind.* Vol. V. p. 123, note. Notice of Madras Museum plates⁶ of a Chôḷa⁷ chief named Śrikanṭha.—The inscription gives the following line of chiefs, who are said to belong to the family of the Chôḷa Karikâla : ‘Sundarananda, Navarâma, Eṇeyamma, Vijayakâma, Virârjuna, Agraṇipidugu, Kôkili, Mahêndravarman, Eḷaḷḷa, Nṛipakâma, Divâkara, and Śrikanṭha.’

N.—The Pāṇḍyas of Madhurâ.⁸

889.—*Ep. Ind.* Vol. VI. p. 302, No. 2. Date of a Tinnevely (Nellaiyappar temple) Tamil inscription of the year opposite the 13th (*i.e.* the 14th) year (of the reign) of the glorious [Pāṇḍya] king Jaṭavarman *alias* the *Tribhuvanachakravartin*, the glorious Kulaśêkharadêva :⁹—

‘In the year opposite the thirteenth year . . . on the day of Pûrvâshâḍhâ, which corresponded to a Thursday, and to the tenth *tithi* of the second fortnight, and to the fourth solar day of the month of Mîna.’

[Ś. 1125] : Thursday, 26th February A.D. 1204.¹⁰

¹ See Mr. Venkayya's *Report* for 1899-1900, p. 20.

² The accession of Vijaya-Gaṇḍagôpâla took place between (approximately) the 14th June and the 1st August A.D. 1250.—Compare also below, No. 904.

³ Compare above, Nos. 856, 860 and 862.

⁴ No. 47 of the Government Epigraphist's collection for 1893.

⁵ In *Ind. Ant.* Vol. XXI. p. 122, the same date is given from a Conjeeveram (Êkâmrânâtha temple) Tamil inscription of the same king; but in it the *nakṣatra* Uttaraśhâḍhâ is wrongly quoted instead of Uttara-Bhadrâpadâ.

⁶ See Mr. Sewell's *Lists of Antiquities*, Vol. II. p. 24, No. 174.

⁷ According to Mr. Venkayya, *Report* for 1899-1900, p. 21, a Telugu-Chôḍa.

⁸ For Pāṇḍya feudatories of the W. Châlukyas see above, p. 26, note 1, d.

The accession of Jaṭavarman Kulaśêkhara took place between (approximately) the 27th February and the 29th November A.D. 1190.

¹⁰ On this day the *tithi* of the date commenced 3 h. 33 m. after mean sunrise.

890.—*Archæol. Surv. of South. India*, Vol. IV. p. 21; facsimiles of 5 plates in *Ind. Ant.* Vol. VI. p. 142. The larger Tiruppûvanam Sanskrit¹ and Tamil grant (on 11 plates) of the 25th year (of the reign) of the glorious [Pāṇḍya] king Jaṭavarman *alias* the *Tribhuvanachakravartin*, the glorious Kulaśékharaḍēva, surnamed Rājagambhīraḍēva :—

(Plate i. a, line 4 f.).—nijē vatsarē pañchavimsē chaṇḍāmsāv-ātta-Châpē Kanakapati-tithau kṛishṇapaksh-Ārkivāra-Svāti-yôgê.

(Plate v. b, line 2 f.).—‘the day of Svāti, which corresponded to a Saturday, and to the eleventh *tithi* of the second fortnight, and to the fourth solar day of the month of Dhanus, in the twelfth year opposite the thirteenth.’

[S. 1136]: Saturday, 29th November A.D. 1214; see *Ep. Ind.* Vol. VI. p. 301, No. 1.

The introductory lines indicate that the Pāṇḍya lords were descended from the Moon.

891.—*Ep. Ind.* Vol. VI. p. 304, No. 6. Date of a Tirukkâṭṭuppalī (Agnīśvara temple) Tamil inscription of the 7th year (of the reign) of king Māṇavarman *alias* the *Tribhuvanachakravartin* Sundara-Pāṇḍyaḍēva [I.] who presented the Chôla country :²—

‘In the 7th year . . . on the auspicious occasion of the Rishabhā (*lagna*) on the day of Pushya, which corresponded to . . . and to the ninth *tithi* of the first fortnight of the month of Mīna.’

[S. 1145]: [Monday], 13th March A.D. 1223.³

892.—*Archæol. Surv. of South. India*, Vol. IV. p. 43, No. 29. Tirupparankunṇam Tamil cave inscription of the 325th day of the 7th year (of the reign) of the glorious king Māṇavarman *alias* the *Tribhuvanachakravartin*, the glorious Sundara-Pāṇḍyaḍēva [I.] who was pleased to present the Chôla country.⁴

893.—*Ep. Ind.* Vol. VI. p. 303, No. 5. Date of a Śrīraṅgam (Raṅganātha temple) Tamil inscription of the 9th year (of the reign) of the glorious king Māṇavarman *alias* the *Tribhuvanachakravartin*, the glorious Sundara-Pāṇḍyaḍēva [I.] who was pleased to present the Chôla country :—

‘In the ninth year . . . on the day of Viśākhâ, which corresponded to a Friday and to the third *tithi* of the second fortnight of the month of Mēsha.’

[S. 1147]: Friday, 28th March A.D. 1225.

894.—*Archæol. Surv. of South. India*, Vol. IV. p. 37, and facsimile in *Ind. Ant.* Vol. VI. p. 143. The Tiruppûvanam Sanskrit⁵ and Tamil supplementary grant (on one plate) of the 11th year (of the reign) of [Māṇavarman] Sundara-Pāṇḍyaḍēva [I.] who presented the Chôla country.⁶

895.—*Ep. Ind.* Vol. VI. p. 302, No. 3. Date of a Tinnevely (Nellaiyappar temple) Tamil inscription of the year opposite the year opposite the 17th (*i.e.* the 19th) year (of the reign) of the glorious king Māṇavarman *alias* the *Tribhuvanachakravartin*, the glorious Sundara-Pāṇḍyaḍēva [I.] who was pleased to take the Chôla country and to perform the anointment of heroes at Maḍikonḍasôlapuram :—

‘In the year opposite the year opposite the seventeenth year . . . on the day of Uttaraśāḍhâ, which corresponded to a Monday, and to the tenth *tithi*, and to the seventh solar day of the month of Purattādi in this year.’

[S. 1156]: Monday, 4th September A.D. 1234.

896.—*Ep. Ind.* Vol. VI. p. 303, No. 4. Date of a Tinnevely (Nellaiyappar temple) Tamil inscription of the year opposite the year opposite the 17th (*i.e.* the 19th) year (of the reign) of the

¹ Only the first five lines are in Sanskrit.

² The accession of Māṇavarman Sundara-Pāṇḍya I. took place between (approximately) the 23th March and the 4th September A.D. 1216.

³ But the *tithi* of the date had ended 0 h. 21 m. *before* mean sunrise of this day.

⁴ See *Ind. Ant.* Vol. XXI. p. 344, note 6.

⁵ Only one verse at the end of the grant is in Sanskrit.

⁶ See *Ind. Ant.* Vol. XXI. p. 344, note 7.

glorious king **Māṛavarman** *alias* the *Tribhuvanachakravartin*, the glorious **Sundara-Pāṇḍya-dēva** [I.] who was pleased to take the Chôla country and to perform the anointment of heroes at Muṇḍikonda[śōlapuram]:—

‘In the year opposite the year opposite the 17th year . . . on the day of Pārva-Bhadrapadā, which corresponded to a Monday, and to the first *tithi* of the first fortnight, and to the twenty-seventh solar day of . . .’¹

[Ś. 1156]: Monday, 19th February A.D. 1235.²

897.—*Ep. Ind.* Vol. VI. p. 305, No. 10. Date of a Tinnevely (Nellaiyappar temple) Tamil inscription of the 11th year (of the reign) of king **Māṛavarman** *alias* the *Tribhuvanachakravartin*, the glorious **Sundara-Pāṇḍyadēva** [II.]:—

‘In the eleventh year . . . on the day of Hasta, which corresponded to Sunday, the first solar day of the month of Vaigāsi.’

[Ś. 1171]: Sunday, 25th April A.D. 1249.

898.—*Ep. Ind.* Vol. VI. p. 304, Nos. 7 and 8. Date of two Tinnevely (Nellaiyappar temple) Tamil inscriptions of the year opposite the year opposite the 11th (*i.e.* the 13th) year (of the reign) of the glorious king **Māṛavarman** *alias* the *Tribhuvanachakravartin*, the glorious **Sundara-Pāṇḍyadēva** [II.]:—

‘In the year opposite the year opposite the eleventh year . . . on the day of Anurādhā, which corresponded to a Wednesday, and to the tenth *tithi* of the second fortnight, and to the twenty-fourth solar day of the month of Makara.’

[Ś. 1172]: Wednesday, 18th January A.D. 1251.

899.—*Ep. Ind.* Vol. VI. p. 305, No. 9. Date of a Tinnevely (Nellaiyappar temple) Tamil inscription of the year opposite the year opposite the 11th (*i.e.* the 13th) year (of the reign) of the glorious king **Māṛavarman** *alias* the *Tribhuvanachakravartin*, the glorious **Sundara-Pāṇḍyadēva** [II.]:—

‘In the year opposite the year opposite the eleventh year . . . on the day of Āśvini, which corresponded to a Wednesday, and to the ninth *tithi* of the second fortnight, and to the nineteenth solar day of the month of Mīna.’

[Ś. 1173]: Wednesday, 14th June A.D. 1251; but the day fell in the month of Mithuna, not of Mīna.⁴

900.—*Ep. Ind.* Vol. VI. p. 306, No. 11. Date of a Tiruvaiyāru (Pañchanadēśvara temple) Tamil inscription of the 2nd year (of the reign) of king **Jaṭāvarman** *alias* the *Tribhuvanachakravartin*, the glorious **Sundara-Pāṇḍyadēva** [I.]:—

‘In the 2nd year . . . on the day of Śatabhishaj, which corresponded to a Thursday and to the eleventh *tithi* of the second fortnight of the month of Mēsha.’

[Ś. 1175]: Thursday, 27th March A.D. 1253.

901.—*Ep. Ind.* Vol. VI. p. 306, No. 12. Date of a Tirumalavāḍi (Vaidyanātha temple) Tamil inscription of the 2nd year (of the reign) of king **Jaṭāvarman** *alias* the *Tribhuvanachakravartin*, the glorious **Sundara-Pāṇḍyadēva** [I.]:—

‘In the 2nd year . . . on the day of Mūla, which corresponded to a Saturday and to the fourth *tithi* of the second fortnight of the month of Mēsha.’

[Ś. 1175]: Saturday, 19th April A.D. 1253.

¹ The name of the month would be Kumbha.

² On this day the *tithi* of the date commenced 0 h. 30 m. after mean sunrise.

³ The accession of Māṛavarman Sundara-Pāṇḍya II. took place between (approximately) the 15th June A.D. 1238 and the 18th January A.D. 1239.

⁴ For the month of Mīna the date is intrinsically wrong.

⁵ The accession of Jaṭāvarman Sundara-Pāṇḍya I. took place between (approximately) the 20th and the 28th April A.D. 1251.

902.— *Ep. Ind.* Vol. VI. p. 306, No. 13. Date of a Tirumalavāḍi (Vaidyanātha temple) Tamil inscription of the 3rd year (of the reign) of king Jaṭavarman *alias* the *Tribhuvanachakravartin*, the glorious Sundara-Pāṇḍyadēva [I.] :—

‘In the 3rd year . . . on the day of Uttarāśhāḍhā, which corresponded to a Wednesday and to the sixth *tithi* of the first fortnight of the month of Vṛ̥ṣ̥chika.’

[S. 1175] : Wednesday, 29th October A.D. 1253.

903.— *Ep. Ind.* Vol. VI. p. 307, No. 17. Date of a Tiruppandurutti (Pushpavanēśvara temple) Tamil inscription of the 7th year (of the reign) of the glorious king Jaṭavarman *alias* the *Tribhuvanachakravartin*, the glorious Sundara-Pāṇḍyadēva [I.] :—

‘In the 7th year . . . on the day of Hasta, which corresponded to a Sunday and to the thirteenth *tithi* of the second fortnight of the month of Kanyā.’

[S. 1179] : Sunday, 7th October A.D. 1257; but the day fell in the month of Tulā, not of Kanyā.²

904.— *Ind. Ant.* Vol. XXI. p. 343. Date of a Tirukkalukkuṇṇam (Vēdagiriśvara temple) Tamil inscription of the 9th year (of the reign) of the *Mahārājādhirāja*, the *Tribhuvanachakravartin*, the glorious Sundara-Pāṇḍyadēva [I.],³ the ornament of the race of the Moon, the Mādhava of the city of Madhurā, the uprooter of the Kēraḷa race, a second Rāma in plundering the island of Laṅkā, the thunderbolt to the mountain—the Chōḷa race, the dispeller of the Kārṇāṭa king,⁴ the fever to the elephant—the Kāṭhaka (king),⁵ . . . the jungle-fire to the forest—Vira-Gaṇḍagōpāla,⁶ the tiger to the deer—Gaṇapati⁷ (who was) the lord of Kāñchi, he who performed the anointment of heroes at Nellūrapura :—

‘In the 9th year . . . on the day of Punarvasu, which corresponded to a Tuesday and to the fifth *tithi* of the first fortnight of the month of Rishabha.’

[S. 1181] : Tuesday, 29th April A.D. 1259; see *Ep. Ind.* Vol. VI. p. 307, No. 14.

905.— *Ep. Ind.* Vol. VI. p. 307, No. 15. Date of a Tirukkalukkuṇṇam (Vēdagiriśvara temple) Tamil inscription of the 9th year (of the reign) of the glorious king Jaṭavarman *alias* the *Tribhuvanachakravartin*, the glorious Sundara-Pāṇḍyadēva [I.] who was pleased to take every country :—

‘In the 9th year . . . on the day of Rēvatī, which corresponded to a Sunday and to the ninth *tithi* of the second fortnight of the month of Mithuna.’

[S. 1181] : Sunday, 15th June A.D. 1259.

906.— *Ep. Ind.* Vol. VII. p. 11, No. 32. Date of an Achcharapākkam (Akshēśvara temple) Tamil inscription of the 7th year (of the reign) of the *Tribhuvanachakravartin*, the glorious Vira-Pāṇḍyadēva :⁸—

‘In the 7th year . . . on the day of Aśvini, which corresponded to a Sunday and to the seventh *tithi* of the second fortnight of the month of Karkāṭaka.’

[S. 1181] : Sunday, 13th July A.D. 1259.

907.— *Ind. Ant.* Vol. XXI. p. 121. Date of a Śrīraṅgam (Jambukēśvara temple) Tamil inscription of the 10th year (of the reign) of the *Mahārājādhirāja*, king Jaṭavarman *alias* the

¹ He took Kaṇṇapūr (see above, No. 436, note) from the Hoysala king and covered the temple at Śrīraṅgam with gold.— See below, No. 909.

² For the month of Kanyā the date is intrinsically wrong.

³ I.e. Jaṭavarman Sundara-Pāṇḍya I.

⁴ I.e. the Hoysala Sōmēśvara; see above, No. 436.

⁵ According to Dr. Hultzsch, probably one of the Gajapati kings of Orissa whose capital was Kaṭaka (Cuttack).

⁶ Compare Vijaya-Gaṇḍagōpāla, above, No. 884 ff.

⁷ I.e. the Kākatya Gaṇapa i; compare above, No. 588.

⁸ The accession of Vira-Pāṇḍya took place between (approximately) the 11th November A.D. 1252 and the 13th July A.D. 1253.

Tribhuvanachakravartin, the glorious **Sundara-Pāṇḍyadēva** [I.] who was pleased to take every country :—

‘In the 10th—tenth—year . . . on the day of Anurādhā, which corresponded to a Wednesday and to the first *tithi* of the second fortnight of the month of Rishabha.’

[Ś. 1182] : Wednesday, 28th April A.D. 1260 ; see *Ep. Ind.* Vol. VI. p. 307, No. 16.

908.—*Ep. Ind.* Vol. VI. p. 308, No. 18. Date of a Tirumalavāḍi (Vaidyanātha temple) Tamil inscription of the 11th year (of the reign) of king **Jaṭavarman** (*alias*) the *Tribhuvanachakravartin*, the glorious **Sundara-Pāṇḍyadēva** [I.] :—

‘In the 11th year . . . on the day of Aśvinī, which corresponded to a Thursday and to the sixth *tithi* of the second fortnight of the month of Karkāṭaka.’

[Ś. 1183] : 19th July A.D. 1261 ; but this was a Tuesday, not a Thursday.

909.—*Ep. Ind.* Vol. III. p. 11, and Plate. Śrīraṅgam (Raṅganātha temple) inscription of **Sundara-Pāṇḍyadēva** [I.],² of the race of the Moon, residing at Madhurā. He took Śrīraṅgam from ‘the moon of Karṇāṭa,’³ and plundered the capital of the Kāthaka king.⁴

910.—*Ep. Ind.* Vol. VII. p. 10, No. 31. Date of a Śrīvaikunṭham (Kailāsapati temple) Tamil inscription of the 15th year (of the reign) of the glorious **Vira-Pāṇḍyadēva** :—

‘In the 15th year . . . on the day of Maghā, which corresponded to a Thursday, and to the seventh *tithi* of the second fortnight, and to the 13th solar day of the month of Kārttigai.’

[Ś. 1189] : Thursday, 10th November A.D. 1267.

911.—*Ep. Ind.* Vol. VI. p. 309, No. 20. Date of a Śrīraṅgam (Jambukēśvara temple) Tamil inscription of the 10th year (of the reign) of the glorious king **Māṇavarman** *alias* the *Tribhuvanachakravartin*, the glorious **Kulaśēkharadēva** [I.] :⁵—

‘In the tenth year . . . on the day of Rōhiṇī, which corresponded to a Wednesday and to the tenth *tithi* of the first fortnight of the month of Makara.’

[Ś. 1199] : Wednesday, 5th January A.D. 1278.

912.—*Ep. Ind.* Vol. VI. p. 311, No. 25. Date of a Tāramaṅgalam (Iḷamīśvara temple) Tamil inscription of the 6th year (of the reign) of king **Jaṭavarman** *alias* the *Tribhuvanachakravartin*, the glorious **Sundara-Pāṇḍyadēva** [II.] :⁶—

‘In the 6th—sixth—year . . . on the day of Uttara-Phalgunī, which corresponded to a Monday and to the fourth *tithi* of the first fortnight of the month of Karkāṭaka.’

[Ś. 1203] : Monday, 21st July A.D. 1281.

913.—Supplied by Dr. Hultsch. Date of a Tiruvēndipuram (Dēvanāyaka-Perumāḷ temple) Tamil inscription⁷ of the 10th year (of the reign) of king **Jaṭavarman** *alias* the *Tribhuvanachakravartin*, the glorious **Sundara-Pāṇḍyadēva** [II.] :—

‘In the 10th—tenth—year . . . on the day of Rēvatī, which corresponded to a Monday and to the fifth *tithi* of the second fortnight of the month of Karkāṭaka :—

[Ś. 1207] : Monday, 23rd July A.D. 1285.

¹ The king otherwise is described as in No. 904.

² *I.e.* Jaṭavarman Sundara-Pāṇḍya I. He covered the shrine of the temple with gold and assumed, with reference to it, the surname Hēmāchchhādanarāja.—Compare above, No. 903.

³ *I.e.* the Hoysala Sōmēśvara.

⁴ Compare above, No. 904.

⁵ The accession of Māṇavarman Kulaśēkhara I. took place between (approximately) the 25th February and the 18th November A.D. 1268.

⁶ The accession of Jaṭavarman Sundara-Pāṇḍya II. took place between (approximately) the 13th September A.D. 1275 and the 15th May A.D. 1276.

⁷ No. 187 of the Government Epigraphist's collection for 1902.

914.—*Ep. Ind.* Vol. VI. p. 311, No. 26. Date of a Maṇṇārguḍi (Jayaṅgaṇḍanātha temple) Tamil inscription of the 12th year (of the reign) of the glorious king Jaṭāvarman *alias* the *Tribhuvanachakravartin*, the glorious **Sundara-Pāṇḍyadēva** [II.] :—

‘In the twelfth year . . . on the day of Svāti, which corresponded to a Friday and to the thirteenth *tithi* of the first fortnight of the month of Kanyā.’

[**Ś. 1209**] : Friday, 12th September A.D. 1287 ; but the *tithi* which ended on this day was a 3rd, not a 13th *tithi* of the bright half.

915.—*Ep. Ind.* Vol. VI. p. 310, No. 23. Date of a Tāramaṅgalam (Iḷamiśvara temple) Tamil inscription of the 13th (*really* 14th) year (of the reign) of king Jaṭāvarman *alias* the *Tribhuvanachakravartin*, the glorious **Sundara-Pāṇḍyadēva** [II.] :—

‘In the thirteenth year . . . on the day of Uttaraśhāḍhā which corresponded to a Monday and to the thirteenth *tithi* of the first fortnight of the month of Simha.’

[**Ś. 1211**] : Monday, 1st August A.D. 1289.

916.—*Ep. Ind.* Vol. VI. p. 310, No. 24. Date of a Tiruvorriyūr (Ādhipurīśvara temple) Tamil inscription of the 13th (*really* 14th) year (of the reign) of king Jaṭāvarman *alias* the *Tribhuvanachakravartin*, the glorious **Sundara-Pāṇḍyadēva** [II.] :—

‘In the thirteenth year . . . on the day of Uttara-Bhadrpadā, which corresponded to a Friday and to the third *tithi* of the second fortnight of the month of Simha.’

[**Ś. 1211**] : Friday, 5th August A.D. 1289.

917.—*Ep. Ind.* Vol. VI. p. 312, No. 27. Date of a Tāramaṅgalam (Iḷamiśvara temple) Tamil inscription of (the year) opposite the 14th (*i.e.* the 15th) year (of the reign) of king Jaṭāvarman *alias* the *Tribhuvanachakravartin*, the glorious **Sundara-Pāṇḍyadēva** [II.] :—

‘(In the year) opposite the fourteenth year . . . on the day of Pushya, which corresponded to a Monday . . . [of the first fortnight] of the month of Rishabha.’

[**Ś. 1212**] : Monday, 15th May A.D. 1290.

918.—Supplied by Dr. Hultsch. Date of an Achcharapākkam (Akshēśvara temple) Tamil inscription¹ of the 2nd opposite the 13th (*i.e.* the 15th) year (of the reign) of king Jaṭāvarman (*alias*) the *Tribhuvanachakravartin*, the glorious **Sundara-Pāṇḍyadēva** [II.] :—

‘In the 2nd opposite the 13th year . . . on the day of Rôhinī, which corresponded to a Monday and to the seventh *tithi* of the second fortnight of the month of Kanyā.’

[**Ś. 1212**] : Monday, 28th August A.D. 1290 ; but this was the last day of the month of Simha (preceding the month of Kanyā).

919.—*Ep. Ind.* Vol. VI. p. 309, No. 21. Date of a Tinnevely (Nellaiyappar temple) Tamil inscription of the 26th year (of the reign) of the glorious king Māṇavarman *alias* the *Tribhuvanachakravartin*, the glorious **Kulaśēkharadēva** [I.] who was pleased to take every country :—

‘In the [2]6th year . . . on the day of Punarvasu, which corresponded to a Wednesday, and to the second *tithi* of the second fortnight, and to the twenty-second solar day of the month of Vṛiśchika.’

[**Ś. 1215**] : Wednesday, 18th November A.D. 1293 ; but the *tithi* which ended on this day was a third, not a second *tithi* of the dark half.

920.—*Ep. Ind.* Vol. VI. p. 308, No. 19. Date of a Tinnevely (Nellaiyappar temple) Tamil inscription of the 27th year (of the reign) of the glorious king Māṇavarman *alias* the

¹ No. 252 of the Government Epigraphist's collection for 1901.

Tribhuvanachakravartin, the glorious **Kulaśēkharadēva** [I.] who was pleased to take every country :—

‘In the 27th year . . . on the day of Uttara-Phalgunī, which corresponded to the seventh *tithi* of the second fortnight, and to a Friday, and to the 14th solar day of the month of Dhanus.

[§. 1216]: Friday, 10th December A.D. 1294.¹

921.—*Ep. Ind.* Vol. VI. p. 310, No. 22. Date of a Kaḍappēri (Śvētāranyēśvara temple) Tamil inscription of the 40th year (of the reign) of king **Māṛavarman** (*alias*) the *Tribhuvanachakravartin*, the glorious **Kulaśēkharadēva** [I.] :—

‘In the 40th year . . . on the day of Rēvatī, which corresponded to a Saturday and to the second *tithi* of the first fortnight of the month of Mīna.’

[§. 1228]: Saturday, 24th February A.D. 1308.

922.—*Ep. Ind.* Vol. VI. p. 313, No. 29. Date of a Gaṅgaikondaśōlapuram (Bṛihadīśvara temple) Tamil inscription of the 4th year (of the reign) of king **Māṛavarman** (*alias*) the *Tribhuvanachakravartin*, the glorious **Kulaśēkharadēva** [II.] :—

‘In the 4th year . . . on the day of Uttarāśāḍhā, which corresponded to a Saturday and to the fourteenth *tithi* of the first fortnight of the month of Karkāṭaka.’

[§. 1238]: Saturday, 23rd July A.D. 1317.

923.—*Ep. Ind.* Vol. VI. p. 313, No. 30. Date of a Gaṅgaikondaśōlapuram (Bṛihadīśvara temple) Tamil inscription of the 5th year (of the reign) of king **Māṛavarman** (*alias*) the *Tribhuvanachakravartin*, the glorious **Kulaśēkharadēva** [II.] :—

‘In the 5th year . . . on the day of Pushya, which corresponded to a Monday and to the thirteenth *tithi* of the first fortnight of the month of Sīṃha.’

[§. 1240]: Monday, 5th March A.D. 1319; but the day fell in the month of Mīna, not Sīṃha,³ and the *nakṣatra* on it was Pūrva-Phalgunī (*Pāram*), not Pushya (*Pāṣam*).

924.—*Ep. Ind.* Vol. VI. p. 312, No. 28. Date of a Tinnevely (Nellaiyappar temple) Tamil inscription of the 8th year (of the reign) of the glorious king **Māṛavarman** (*alias*) the *Tribhuvanachakravartin*, the glorious **Kulaśēkharadēva** [II.] :—

‘In the eighth year . . . on the day of Uttara-Phalgunī, which corresponded to a Saturday, and to the ninth *tithi* of the second fortnight, and to the seventeenth solar day of the month of Vṛiśchika.’

[§. 1243]: Saturday, 14th November A.D. 1321.

925.—§. 1262.—*Ep. Ind.* Vol. VII. p. 11, No. 33. Date of a Śēngama (Rishabhēśvara temple) Tamil inscription of the 6th year (of the reign) of king **Māṛavarman** (*alias*) the *Tribhuvanachakravartin*, the glorious **Parākrama-Pāṇḍyadēva** :—

‘After the Śaka year 1262 (had passed), in the 6th year . . . on the day of Uttara-Bhadrapadā, which corresponded to a Wednesday and to the twelfth *tithi* of the first fortnight of the month of Vṛiśchika.’

Wednesday, 1st November A.D. 1340.

¹ On this day the *tithi* of the date commenced 4 h. 45 m. after mean sunrise.

² The accession of Māṛavarman Kulaśēkhara II. took place between (approximately) the 6th March and the 23rd July A.D. 1314.

³ The wording of the date is intrinsically wrong.

⁴ The accession of Māṛavarman Parākrama-Pāṇḍya took place between (approximately) the 1st December A.D. 1334 and the 1st November A.D. 1335.

926.—*Ep. Ind.* Vol. VII. p. 11, No. 34. Date of a Maṇṇārguḍi (Kailāsanātha temple) Tamil inscription of the 8th (*really* 18th) year (of the reign) of king Māra-varman (*alias*) the *Tribhuvanachakravartin*, the glorious Parākrama-Pāṇḍyadēva:—

‘In the [8th] year . . . on the day of Hasta, which corresponded to a Friday and to the ninth *tithi* of the second fortnight of the month of Dhanus.’

[§. 1274]: Friday, 30th November A.D. 1352.¹

927.—§. 1293.—*Ep. Ind.* Vol. VII. p. 12, No. 35. Date of a Chōlapuram (near Nagercoil, Chōlēsvara temple) Tamil inscription of the 10th opposite the 5th (*i.e.* the 15th) year (of the reign) of the glorious king Jaṭavarman *alias* the *Tribhuvanachakravartin*, the glorious Parākrama-Pāṇḍyadēva:²—

‘After the Śaka year 1293 (had passed), in the tenth opposite the fifth year . . . on the day of Śatabhishaj, which corresponded to a Friday and to the third *tithi* of the first fortnight of the month of Makara.’

Friday, 9th January A.D. 1372.

928.—*Ep. Ind.* Vol. VII. p. 13, No. 37. Date of a Teṇkāsi (Viśvanātha temple) Tamil inscription of (the year) opposite the 31st (*i.e.* the 32nd) year (of the reign) of king Jaṭilavarman *alias* the *Tribhuvanachakravartin*, the glorious Parākrama-Pāṇḍyadēva:³—

‘(In the year) opposite the thirty-first year . . . on the day of Uttarāshāḍhā, which corresponded to a Monday, and to the fourteenth *tithi* of the first fortnight, and to the twenty-first solar day of the month of Karkāṭaka.’

[§. 1375]: 19th July A.D. 1453; but this was a Thursday, not a Monday.

929.—§. 1377.—*Ep. Ind.* Vol. VII. p. 12, No. 36. Date of a Kuttālam (Kuttālanātha temple) Tamil inscription of the 2nd opposite the 31st (*i.e.* the 33rd) year (of the reign) of Parākrama-Pāṇḍyadēva:³—

‘In the second opposite the 31st year . . . which was current after the Śaka year 1377 (had passed),—on the day of Mṛgaśīrsha, which corresponded to a Monday, and to the sixth *tithi* of the first fortnight, and to the twenty-eighth solar day of the month of Mīna.’

Monday, 24th March A.D. 1455.

930.—*Ep. Ind.* Vol. VII. p. 13, No. 38. Date of a Kuttālam (Kuttālanātha temple) Tamil inscription of the 4th opposite the 31st (*i.e.* the 35th) year (of the reign) of king Jaṭilavarman *alias* the *Tribhuvanachakravartin*, the glorious Parākrama-Pāṇḍyadēva:³—

‘In the fourth opposite the thirty-first year . . . on the day of Anurādhā, which corresponded to a Wednesday, and to the fifth *tithi* of the second fortnight, and to the twentieth solar day of the month of Mīna.’

[§. 1378]: Wednesday, 16th March A.D. 1457.

931.— §. 1381 (for 1383).—*Ep. Ind.* Vol. VII. p. 13, No. 39. Date of a Teṇkāsi (Viśvanātha temple) Tamil inscription of the 8th opposite the 31st (*i.e.* the 39th) year (of the reign) of Arikēsari-dēva *alias* Parākrama-Pāṇḍyadēva:⁴—

‘In the 8th opposite the 31st year . . . which was current after the Śaka year one thousand three hundred and eighty-one (had passed),—on the day of Svāti, which corresponded to a

¹ On this day the *tithi* of the date commenced 0 h. 17 m. after mean sunrise.

² The accession of Jaṭavarman Parākrama-Pāṇḍya took place between (approximately) the 10th January A.D. 1357 and the 9th January A.D. 1358.

³ *I.e.* Jaṭilavarman Parākrama-Pāṇḍya Arikēsari-dēva; see No. 931.—His accession took place between (approximately) the 18th June and the 19th July A.D. 1422.

⁴ *I.e.* Jaṭilavarman Parākrama-Pāṇḍya Arikēsari-dēva; see Nos. 928-930.

Wednesday, and to the tenth *tithi* of the first fortnight, and to the twenty-third solar day of the month of Mithuna.'

Wednesday, 17th June A.D. 1461; but this was the 21st, not the 23rd day of the month of Mithuna.

932.—**Ś. 1421.**—*Ep. Ind.* Vol. VII. p. 14, No. 40. Date of a Tenkâsi (Viśvanâtha temple) Tamil inscription of the 20th year (of the reign) of king Jaṭilavarman *alias* the *Tribhuvanachakravartin* Parākrama-Pāṇḍyadēva *alias* Kulaśēkharadēva who was born on the day of Kṛittikā: ¹—

'In the twentieth year . . . which was current after the Śaka year 1421 (had passed),— on the day of Rêvati, which corresponded to a Thursday, and to the twelfth *tithi* of the first fortnight, and to the fifteenth solar day of the month of Vṛiśchika.'

Thursday, 14th November A.D. 1499.

933.—**Ś. 1459.**—*Ep. Ind.* Vol. VII. p. 15, No. 41. Date of a Tenkâsi (Viśvanâtha temple) Tamil inscription of the 3rd year (of the reign) of king Jaṭilavarman *alias* the *Tribhuvanachakravartin*, Kônērmaikoṇḍāṇ ² . . . Perumāḷ Śrivalḷabhadēva: ³—

'In the Hêvilambin year, the third year . . . which was current after the Śaka year one thousand four hundred and fifty-nine (had passed),— on the day of Svâti, which corresponded to a Wednesday, and to the eleventh *tithi* of the second fortnight, and to the twenty-ninth solar day of (the month in which) the sun (was) in Vṛiśchika.'

Wednesday, 28th November A.D. 1537.

934.—**Ś. 1477.**—*Ep. Ind.* Vol. VII. p. 15, No. 42. Date of a Gaṅgaikoṇḍāṇ (Kailâsapati temple) Tamil inscription of the 22nd opposite the 2nd (*i.e.* the 24th) year (of the reign) of king Mâṛavarman *alias* the *Tribhuvanachakravartin*, Kônērmaikoṇḍāṇ, ² the glorious Sundara-Pāṇḍyadēva [III.]: ⁴—

'In the Râkshasa year which was current after the Śaka year 1477 (had passed, and which corresponded to) the 22nd opposite the 2nd year . . . on the day of Svâti, which corresponded to a Saturday, and to the twelfth *tithi* of the first fortnight, and to the 3rd solar day of the month of Âṇi.'

Saturday, 1st June A.D. 1555.

935.—**Ś. 1489.**—*Ep. Ind.* Vol. VII. p. 16, No. 43. Date of a Tenkâsi (Kulaśēkharamudaiyâr temple) Tamil inscription of the 5th year (of the reign) of king Jaṭilavarman *alias* the *Tribhuvanachakravartin*, Kônērmaikoṇḍāṇ ² Śrî-Perumāḷ Aḷagaṇ-Perumāḷ Ativirarâma Śrivalḷabhadēva: ⁵—

'In the Prabhava year (corresponding to) the fifth year . . . which was current after the Śaka year 1489 (had passed),— on the day of Uttara-Bhadrpadâ, which corresponded to the Vapik-karâṇa and to the Gaṇḍa-yôga and to a Friday, and to the third *tithi* of the second fortnight, and to the 22nd solar day of the month of Âṇi.'

Friday, 22nd August A.D. 1567.

¹ The king's accession took place between (approximately) the 15th November A.D. 1479 and the 14th November A.D. 1480.

² See above, No. 819.

³ The king's accession took place between (approximately) the 29th November A.D. 1534 and the 28th November A.D. 1535.

⁴ The king's accession took place between (approximately) the 2nd June A.D. 1531 and the 1st June A.D. 1532.

⁵ The king's accession took place between (approximately) the 23rd August A.D. 1562 and the 22nd August A.D. 1563.

936.—*South-Ind. Inscr.* Vol. I. No. 69, p. 101. Tirumalai Tamil inscription¹ of the 10th year (of the reign) of king **Māra-varman**, the *Tribhuvanachakravartin*, the glorious **Vira-Pāṇḍyadēva**.

937.—*Ind. Ant.* Vol. XXII. p. 69, and Plates. Madras Museum Sanskrit and Tamil plates² of the 17th year of the reign of the Pāṇḍya king **Jaṭilavarman**³ (in Tamil, **Neḍuñjaḍaiyaṇ**), the son of king Māra-varman of the Pāṇḍya race, descended from the Moon.—The *ājñapti* (or *dūtaka*) of the grant was the *Mahāsāmanta* Dhīrataran Mūrti-Eyīṇaṇ of the Vaidya race, chief of Viramaṅgalam.

938.—*Ind. Ant.* Vol. XXII. p. 67. Tamil inscription of the 6th year of the reign of **Kō Mārañ-Jaḍaiyaṇ**,⁴ and of his *Mahāsāmanta* Śāttan Gaṇapati of the Vaidya race, who was the chief of Pāṇḍi-Amirdamaṅgalam.

O.—Kings and Chiefs of Kēraḷa.⁵

939.—Ś. 1188.—*Ep. Ind.* Vol. IV. p. 146. Conjeeveram (Aruḷāḷa-Perumāḷ temple) incomplete Sanskrit and Tamil inscription of the *Mahārāja* **Ravivarman** *alias* **Samgrāmadhira** and **Kulaśēkharadēva**, the *Tribhuvanachakravartin* **Kōṇēriṇmaikoṇḍāṇ**,⁶ a son of the Kēraḷa *Mahārājādhirāja* Jayasimha⁷ (of the family of Yadu in the lunar race) and his wife Umādēvi.—Date of Ravivarman's birth :—

(L. 1).—*dēhavyāpya*.⁸ Śakābda-bhāji samayē.

When 33 years of age (*i.e.* about A.D. 1299-1300), Ravivarman took possession of Kēraḷa which he ruled as he did his town of Kōḷamba; he defeated a certain Vira-Pāṇḍya,⁹ subjected the Pāṇḍyas and Chōḷas to the Kēraḷas, and at the age of 46 (*i.e.* about A.D. 1312-13) was crowned on the banks of the Vēgavatī; he then apparently again made war against Vira-Pāṇḍya and conquered the northern country; in the fourth year of his reign (*i.e.* about A.D. 1315-16) he was at Kāñchi.

940.—Ś. 1188.—*Ep. Ind.* Vol. IV. p. 149. Śrīraṅgam (Raṅganātha temple) inscription of the *Mahārāja* **Ravivarman** *alias* **Samgrāmadhira** and **Kulaśēkharadēva**, the son of Jayasimha, of Kēraḷa; (partly composed by Kavibhūṣaṇa).—Date of Ravivarman's birth as in No. 939, with which this inscription is partly identical. In both Ravivarman, besides other epithets, has those of 'the Kūpaka universal monarch' and 'king Bhōja of the South.'

941.—Ś. 1296.—*Ep. Ind.* Vol. IV. p. 203. Trivandrum¹⁰ (Padmanābhasvāmin temple) inscription of a prince **Sarvāṅganātha** :—

(L. 1).—Simha-sthē cha Bṛihaspatau abdē cha Chōḷapriyē.¹²

942.—Ś. 1312.—*Ind. Ant.* Vol. II. p. 361. Śuchindram inscription of the Kēraḷa king **Mārtanḍavarman** :—

Rākālōkē¹³ Śak-ābdē Surapati-sachivē Simha-yātē Tulāyām=ārūḍhē padminisē=py=Aditidina-yutē Bhānuvārē cha.

¹ I am unable to state the times of this inscription and of Nos. 937 and 938.

² The (seven) plates are numbered with Vaṭṭeḷuttu numeral figures.

³ He put to flight, amongst others, a certain Adiyaṇ. With this name compare Adigaṇ, above, Nos. 833 and 834, and Adiyama, *e.g.* in No. 415, note.

⁴ According to Mr. Venkaya he may be identical with the Jaṭilavarman of No. 937.

⁵ I give first inscriptions dated in Saka years, then those dated in Kollam years, and finally undated inscriptions.—For Kēraḷa kings see also above, No. 834.

⁶ See above No. 819.

⁷ Compare below, No. 959.

⁸ *I.e.* 1188.

⁹ For a Vira-Pāṇḍya who apparently was a contemporary of Ravivarman, see below, No. 957.

¹⁰ In the inscription called Syānandūra; compare below, No. 956.

¹¹ According to the late Mr. P. S. Pillai, this would be the surname of an Ādityavarman who is mentioned in another Trivandrum inscription, translated in *Ind. Ant.* Vol. XXV. p. 186.

¹² *I.e.* 1296.

¹³ *I.e.* 1312.

Perhaps Sunday, 2nd October A.D. 1390; but on this day Jupiter's true place was in Vṛśchika (and his mean place in Dhanuḥ), not in Siṃha.

943.—Kollam 301.—*Ind. Ant.* Vol. XXIV. p. 253. Translation¹ of a Chôḷapuram (Rājendra-Chôḷēśvara temple) Tamiḷ inscription of Vira-Kēraḷavarman of Vēṇāḍu :²—

'In the year opposite the year 301, since the appearance of Kollam, with the sun in the sign of Leo' (Siṃha).

[Kollam 301 = Ś. 1047-48.]

944.—Kollam 319.—*Ind. Ant.* Vol. XXIV. p. 255. Translation of a Tiruvallam Old Malayāḷam inscription of Vira-Kēraḷavarman of Vēṇāḍu :—

'In the Kollam year 319, with Jupiter in the sign Scorpio' (Vṛśchika), 'and the sun in Capricornus' (Makara).³

[Kollam 319 = Ś. 1065-66.]

945.—Kollam 335.—*Ind. Ant.* Vol. XXVI. p. 141. Puravachēri Tamiḷ inscription recording private donations :—

'In the year opposite the year 335 after the appearance of Kollam.'

[Kollam 335 = Ś. 1081-82.]

946.—Kollam 336.—*Ind. Ant.* Vol. XXIV. p. 257. Translation of a Puravachēri Tamiḷ inscription⁴ of Vira-Ravivarman of Vēṇāḍu :—

'In the year opposite the year 336, after the appearance of Kollam, with the sun six days old⁵ in the sign of Taurus' (Vṛśhabha), 'Saturday, Makayiram' (Mṛgaśīrsha) 'star.'

[Ś. 1083] : Saturday, 29th April A.D. 1161; see *ibid.* Vol. XXV. p. 54, No. 1.

947.—Kollam 342.—*Ind. Ant.* Vol. XXIV. p. 277. Translation of a Puravachēri Tamiḷ inscription [of Vira-Ravivarman of Vēṇāḍu ?] :—

'In the year 342 after the appearance of Kollam, with the sun 7 days old in Leo' (Siṃha).

[Kollam 342 = Ś. 1088-89.]

948.—Kollam 348 (for 347 ?).—*Ind. Ant.* Vol. XXIV. p. 278. Translation of a Tiruvaṭṭār Old Malayāḷam inscription of Vira-Udaiyamārtāṇḍavarman of Vēṇāḍu :—

'In the Kollam year 348, with Jupiter in Cancer' (Karkāṭaka), 'and the sun . . days old in Pisces' (Mīna), 'Thursday, Anusham' (Anurādhā) 'star.'

[Ś. 1094] : Thursday, 16th March A.D. 1172; see *ibid.* Vol. XXV. p. 54, No. 4, and p. 174.

949.—Kollam 368.—*Ind. Ant.* Vol. XXIV. p. 283. Translation of Virapam (near Āṅṅāṅal) fragments of one or two Tamiḷ inscriptions [of a Vira-Kēraḷavarman ?], one of which is dated—

'in the Kollam year 368, with Jupiter in Virgo' (Kanyā), 'and the sun two days old in Taurus' (Vṛśhabha).⁶

[Kollam 368 = Ś. 1114-15.]

¹ For this and the following inscriptions compare also the late P. S. Pillai's *Some Early Sovereigns of Travancore*, Madras, 1894.

² This is the Tamiḷ name of the Travancore country.

³ In the Kollam year 319 = A.D. 1143-44 Jupiter was not in Vṛśchika.

⁴ For another Tamiḷ inscription from the same place and of apparently the same date, see *Ind. Ant.* Vol. XXIV. p. 258.

⁵ *I.e.* 'on the 6th solar day.'

⁶ In the Kollam year 368 = A.D. 1192-93 Jupiter was not in Kanyā.

950.—Kollam 371.—*Ind. Ant.* Vol. XXIV. p. 284. Translation of a Kupangarai Old Malayālam inscription of Vira-Rāmavarman of Vēṇāḍu :—

‘In the Kollam year 371, with Jupiter in Cancer’ (Karkāṭaka), ‘and the sun 24 days old in Aries’ (Mēsha).

[Kollam 371 = Ś. 1117-18.]

951.—Kollam 384.—*Ind. Ant.* Vol. XXIV. p. 305. Translation of a Trivandrum (Padmanābhasvāmin temple) Old Malayālam mutilated inscription of Vira-Rāma [Kēraḷavarman] of Vēṇāḍu :—

‘In the Kollam year 384, with Jupiter in Cancer’ (Karkāṭaka), ‘[and the sun . . days old in Gemini’ (Mithuna)].

[Kollam 384 = Ś. 1130-31.]

952.—Kollam 389 (for 390?)—*Ind. Ant.* Vol. XXIV. p. 307. Translation of a Kaṭṭinaṅkulam (Mahādēva temple) Tamil inscription of Vira-Rāma Kēraḷavarman of Kīlaṭṭūr, ruler of Vēṇāḍu :—

‘In the year opposite the Kollam year 389, with Jupiter in Aquarius’ (Kumbha), ‘and the sun 18 days old¹ in Pisces’ (Mina), ‘Thursday, Pushya star, the 10th lunar day, Aries’ (Mēsha) ‘(being the rising sign).’

[Ś. 1137]: Thursday, 12th March A.D. 1215; see *ibid.* Vol. XXV. p. 54, No. 3.

953.—Kollam 392 (Ky. 4317).—*Ind. Ant.* Vol. XXVI. p. 144. Kōṭṭār (Chōlapuram temple) Tamil inscription :—

‘In the Kollam year 392 opposite² the Kaliyuga year 4317, the sun being in Vṛiśchika.’

[Kollam 392 = Ky. 4317 = Ś. 1138.]

954.—Kollam 396.—*Ind. Ant.* Vol. XXVI. p. 145. Kōṭṭār (Chōlapuram temple) Tamil inscription :—

‘In the year 396 after the appearance of Kollam, when the sun was in Mithuna.’

[Kollam 396 = Ś. 1142-43.]

955.—Kollam 410.—*Ind. Ant.* Vol. XXIV. p. 308. Translation of a Maṇalikkarai (Ālvār temple) Old Malayālam inscription of Vira-Ravi Kēraḷavarman of Vēṇāḍu :—

‘In the year opposite the Kollam year 410, with Jupiter in Scorpio’ (Vṛiśchika), ‘and the sun 27 days old in Aries’ (Mēsha).

[Kollam 410 = Ś. 1156-57.]

956.—Kollam 427.—*Ind. Ant.* Vol. XXIV. p. 333. Translation of a Varkkalai Old Malayālam inscription of Vira-Padmanābha Mārtāṇḍavarman of Vēṇāḍu :—

‘In the Kollam year 427, with Jupiter entering into Aries’ (Mēsha), ‘and the sun 21 days old³ in Taurus’ (Vṛiśhabha), ‘Wednesday, the 5th lunar day after new-moon, and with the sign of Cancer’ (Karkāṭaka) ‘rising in the orient.’

[Ś. 1174]: Wednesday, 15th May A.D. 1252; see *ibid.* Vol. XXV. p. 54, No. 2.

957.—Kollam 491.—*Ind. Ant.* Vol. XXIV. p. 335. Translation of a Kēraḷapuram Old Malayālam inscription of Vira-Udaiyamārtāṇḍavarman *alias* Vira-Pāṇḍyadēva⁴ of Vēṇāḍu :—

‘In the Kollam year 491, and in the 4th year, the sun being 21 days old in Aquarius’ (Kumbha).

[Kollam 491 = Ś. 1237-38.]

¹ *I.e.* ‘on the 18th solar day.’

² For the month of Vṛiśchika the Kollam year 392 corresponds to Kaliyuga 4317 expired.

³ *I.e.* ‘on the 21st solar day.’

⁴ Compare above, No. 989.

958.—Kollam 578.—*Ind. Ant.* Vol. XXV. pp. 187 and 188. Translation of a Padmanābhapuram (Āṭvār temple) Sanskrit and Tamil inscription of the Kēraḷa king Vira-Kēraḷa Mārtāṇḍavarman of Kīlappēṭūr :—

‘In the Kollam year 578, the sun being 26 days old¹ in Mēṣham, on Saturday, new moon, [the lunar mansion being] Bharanī.²

[Ś. 1325] : Saturday, 21st April A.D. 1403.

959.—Kollam 644.—*Ind. Ant.* Vol. II. p. 360. Inscription on a bell, given to a temple at Tirukuraṅguḍi by a prince Āḍityavarman, ruler of Vañchi,³ of the lineage of Jayasimha :⁴—

Śrīmat-Kōlamba-varshā bhavati.⁵

[Kollam 644 = Ś. 1390-91.]

960.—Kollam 654.—*Ind. Ant.* Vol. II. p. 361. Śūchindram inscription of a prince Rāma-varman, ruler of Vañchi.³—

Abdē Kōlamba-saṁjñē viśati⁶ Gavi Guran mitra-yātē(?) Tul-āntyē(?) Maitrē(trar)kshē s-Ēnduvārē pratipadi Vanitā-lagnakē.

[Ś. 1400] : Monday, 26th October A.D. 1478 ; see *ibid.* Vol. XXV. p. 56, No. 15.

961.—Kollam 655.—*Ep. Ind.* Vol. IV. p. 204. Varkkalai inscription of Mārtāṇḍa :—

(L. 1).—Kōlambē mamat=⁷ēti vatsara itē māsē Vṛish-ārdhē Gurōr=vvārē bhē Mṛigaśirshakē Vidhi-tithau Simhē cha lagnē śubhē.

[Ś. 1402] : Thursday, 11th May A.D. 1480.

962.—*Ep. Ind.* Vol. III. p. 68, and Plate. Cochin (Jews') Tamil plates of Kōḡōṇmaikoṇḍāṇ,⁸ His Majesty the king, the glorious Bhāskara Ravivarman, staying at Muiyikkōḍu,⁹ recording a grant made to Issuppu Iṇappāṇ (i.e. Joseph Rabbān) ; dated—

‘in the thirty-sixth year opposite the second year.’

963.—*Ind. Ant.* Vol. XX. p. 290, and Plate. Tirunelli (now Colonel Wooldridge's) Tamil plates of His Majesty king Bhāskara Ravivarman, containing an order by his feudatory Saṁkara-Kōḍavarman of Puṇaigilānāḍu ; dated—

‘in the forty-sixth year opposite the current year . . . in the month of Makara, when Jupiter was standing in Simha, in the above year.’

964.—*Madras Jour. Lit. Sc.* Vol. XIII. Part I. p. 123. Kōṭṭayam (Syrian Christians') Tamil plates of king Sthāṇu Ravi,¹⁰ dated¹¹—

‘in the fifth year which was current within the time during which king . . . was reigning . . . in this year.’

965.—*Ep. Ind.* Vol. IV. p. 295, and Plate. Kōṭṭayam (Syrian Christians') Tamil plate of Vira-Rāghava-Chakravartin, a descendant of Vira-Kēraḷa-Chakravartin :—

‘On the day of Rōhiṇī, a Saturday on which passed¹² (the day) twenty-one (of) the month Mina, (when) Jupiter (was) in Makara, while the glorious Vira-Rāghava-Chakravartin . . . was ruling prosperously.’

[Ś. 1241] : Saturday, 15th March A.D. 1320 ; see *ibid.* Vol. VI. p. 83.

¹ I.e. ‘on the 26th solar day.’

² In the Sanskrit part of the inscription the date is assigned to Ś. 1325 (*Śākhāḍika*).

³ I.e. Vañji ; see above, No. 834.

⁴ Compare above, No. 939.

⁵ I.e. 644.

⁶ I.e. 654.

⁷ I.e. 655.

⁸ I.e. ‘he who had assumed the title “king of kings.”’

⁹ In the Hebrew translation (in the possession of the Cochin Jews) identified with Koḍuññallūr (Cranganore).

¹⁰ See *Ep. Ind.* Vol. IV. p. 291, note 5.

¹¹ See *Ind. Ant.* Vol. XX. p. 287.

¹² I owe the literal translation of the date to Dr. Hultsch.

966.—*Ep. Ind.* Vol. IV. p. 202. Trivandrum¹ (Padmanâbhasvâmin temple) Sanskrit and Tamil inscription² of the time of **Gôda-Mârtâṇḍa**, the lord of Gôḷamba (Kôḷamba) :—

(L. 3).—Dhanushî . . . uttumaṅga-Jîvê.³

P.—Miscellaneous dated Inscriptions.

967.—**Ś. 856.**—*Ind. Ant.* Vol. X. p. 104, and Plate; *PSOCI.* No. 52. Bâdâmi (Mahâkûṭṭa) unfinished Kanarese pillar inscription of the *Mahâsâmantâ Bappuvarasa* :—

(L. 6).—Sa(śa)kanṇipakâl-âtita-sa[m]vatsara-śatamga[-enṭu-nu(nṭ)ra-ayivatta-âṇa neya Jaya-sa[m]vatsarada Kârta(rtti)ka-su(śu)ddha-pañchamiyûṇ Budhavârad-andu[m].

Wednesday, 15th October A.D. 924;⁴ see *ibid.* Vol. XXIV. p. 2, No. 127.

Bappuvarasa⁵ is described as 'a very Bhairava . . . to the assemblage of the enemies of the brave Gôpâla (Vîra-Gôpâla?).'

968.—**Ś. 1041*.**—*Inscr. at Śravaṇa-Belgoḷa*, No. 139, p. 109. Sanskrit and Kanarese inscription recording the date of the death of a female disciple of Divâkaranandi-siddhântadêva :—

Śaka-varshaṁ 1041neya Viḷambi-saṁvatsarada Phâlguna(na)-śuddha-pañchamî Budhavârad-andu.

The date is irregular.

Divâkaranandi-siddhântadêva's disciple was Maladhâridêva, whose disciple was Śubha-chandra-siddhântadêva.⁶

969.—**Ś. 1050.**—*Inscr. at Śravaṇa-Belgoḷa*, No. 54, p. 41; *Ep. Ind.* Vol. III. p. 189, and Plate. Pillar inscription recording the date of the death of **Mallishêṇa Maladhâridêva**, the disciple of Ajitasêṇa, 'preceded by a sort of historical sketch of the Śravaṇa-Belgoḷa branch of the Digambara branch of the Jains;' (composed by Maladhâridêva's lay-disciple Mallinâtha) :—

(L. 218).—Śâkê śūnya-śar-âmba-âvani-mitê saṁvatsarê Kilakê mâsê [Ph]âlgunakê tri(tri)tiya-divasê vâre-sitê Bhâskarê Svâtau . . . madhyâhnê.

Sunday, 10th March A.D. 1129; see *Ind. Ant.* Vol. XXIII. p. 124, No. 68.

Of royal personages the inscription mentions: Chandragupta (in connection with Bhadrabâhu); Sâhasatunga and Himaśîṭala (in connection with Akalaṅka); Śatrubhayankara (in connection with Vimalachandra); Kṛishṇarâja (in connection with Paravâdimalla); the Poysala (Hoysala) Vinayâdiya (in connection with Śântidêva); and Âhavamalla (i.e. perhaps the N. Châlukya Sômêśvara I., in connection with Śabdachaturmukha, i.e. perhaps Śântinâtha).

970.—**Ś. 1059** (for 1051?).—*Inscr. at Śravaṇa-Belgoḷa*, No. 68, p. 60. Kanarese pillar inscription recording the date of the death of **Tribhuvanamalla Chaladaṅkarâva Hoysalasetṭi**, and the erection by his wife of a monument in his memory :—

Sa(śa)ka-varsha(rsha) 1059neya Saumya-saṁvatsarada Mâgha-mâsada śukla-pakshada saṅkramapad-andu.

Saumya would be Ś. 1051 expired.

971.—**Ś. 1121.**—*PSOCI.* No. 114. Hampe Kanarese inscription of **Maiduna-Chauḍayya** :—
'Śaka 1121 (in figures, 1. 11), the Siddhârthî saṁvatsara; at the time of the sun's commencing his progress to the north.'

¹ In the inscription called Syânandûra; compare above, No. 941.

² Of about the 14th century A.D.—Mr P. S. Pillai has taken the inscription to be dated in the Kollam year 965; see *Ind. Ant.* Vol. XXIV. p. 280, and Vol. XXVI. p. 109.

³ I.e. (in the month of Dhanu) when Jupiter was in the sign Karkâṭaka.—Compare *Raghuvamśa* III. 13, S. P. Pandit's note.

⁴ On this day the *tithi* of the date commenced 2 h. 42 m. after mean sunrise.

He appears to have the *biruda* Ratnâvalôka.

⁵ Compare above, No. 398.

972.—Ś. 1130 (for 1131).—*Ep. Ind.* Vol. III. p. 316. Sironcha (on the Gôdâvarî, now Nâgpur Museum) Telugu inscription of **Sômêśvara** (**Jagadêkabhûshaṇa-Mahârāja** *alias* **Sômêśvaradêva-Chakravartin**) of the *Nâga vamśa*, 'lord of Bhôgâvntî';¹ recording a grant by his chief queen **Gaṅgamahâdêvi**:—

(L. 26).—Śakanri(nri)pakâl-âtîta-saṁvatsaramulu 1130agunêrñi Phâlguna(na)-śu-
[kra(kla)]-dvâdaśini Âdityavâramu nâṁḍu.

Sunday, 7th February A.D. 1210; see *ibid.* p. 315.

973.—Ś. 1156.—*Cave-Temples of West. India*, p. 99. Ellôrâ Jaina image inscription:—

(L. 1).—Śâkê 1156 Jaya-savachharê [Phâlguna-sudha-trîtiâ Budhê].

(L. 3).—Phâlguna-tritîyâm Vṛdhê.

Wednesday, 21st February A.D. 1235; see *Ind. Ant.* Vol. XXIII. p. 118, No. 30.

974.—Ś. 1189.—*Ind. Ant.* Vol. XII. p. 101. Kaḍako! Kanarese memorial tablet of a disciple of **Śrinandi-bhaṭṭâarakadêva**:—

(L. 1).—Sa(śa)ka-varusa(sha) 1189 Prabhava-saṁvatsarada Mâgha-su(śu)dba(ddha) 5
Su(śu)kravâradalu.

Friday, 20th January A.D. 1268;² see *ibid.* Vol. XXIV. p. 3, No. 131.

975.—Ś. 1197*.—*PSOI.* No. 236; *Mysore Inscr.* No. 120, p. 219. Haḷêbiḍ Kanarese memorial tablet of a disciple of (?) **Mâghanandi-bhaṭṭâarakadêva**:—

'Śaka 1197 (in figures, l. 8), the Bhâva saṁvatsara; Wednesday, the twelfth day of the bright fortnight of Bhâdrapada.'

Wednesday, 15th August A.D. 1274; see *Ind. Ant.* Vol. XXIII. p. 128, No. 92.

976.—Ś. 1200.—*Inscr. at Śravaṇa-Belgoḷa*, No. 137, second part, p. 105 Kanarese inscription recording donations by **Munichandradêva**, disciple of the *Mahâmaṇḍalâchârya Udayachandradêva, and by others:—*

Śâlivâhana-Śaka-varshaṁ 1200neya Bahudhânya-saṁvatsarada Chaitra-suddha 1 Śukravâra.

Friday, 25th March A.D. 1278;³ see *Ind. Ant.* Vol. XXIII. p. 119, No. 37.

977.—Ś. 1201.—*Ind. Ant.* Vol. XII. p. 101. Kaḍako! Kanarese memorial tablet of a female disciple of (?) **Paḍumasina-bhaṭṭâarakadêva**:—

(L. 1).—Sa(śa)ka-varusa(sha) 1201 Pramâthi-saṁvatsarada Bhâdrapada-su(śu)ddha-chhaṭ[t]i Sôma-vârad-aṁḍu.

Monday, 14th August A.D. 1279;⁴ see *ibid.* Vol. XXIV. p. 3, No. 133.

978.—Ś. 1203 (for 1201)? and [Ś. 1210].—*Inscr. at Śravaṇa-Belgoḷa*, No. 131, p. 99. Kanarese inscription recording grants by private persons:—

Śrîmatu-Śaka-varsha 1203neya Pramâdi-saṁvatsara Mârggaśîra-su 10 Bri(bri)d-andu.

Pramâdin would be Ś. 1235 expired. Perhaps the intended year is Ś. 1201 expired = Pramâthin, but for that year the date is irregular.

Below the above is another Kanarese inscription recording a private grant, dated:—

Sarvadhâri-saṁvatsarada dvitîya-Bhâdrapada-su 5 Bri.

This date, for Sarvadhârin = Ś. 1210, in which Bhâdrapada was intercalary, corresponds to Thursday, 2nd September A.D. 1288.

¹ Sômêśvara therefore probably belonged to the Sinda family; compare above, Nos. 144, 156 and 189.

² On this day the *tithi* of the date commenced 2 h. 42 m. after mean sunrise.

³ This was the day of the Mêsha-saṁkrânti.

⁴ On this day the *tithi* of the date commenced 4 h. 19 m. after mean sunrise.

979.—**Ś. 1203.**—*Ep. Ind.* Vol. VI. p. 263. Śrīkūrmam (Kūrmēśvara temple) pillar inscription of **Naraharītīrtha**¹ (probably governor of the Kalinga country), the pupil of Ānandatīrtha (who explained the *Vyāsa-sūtras* in accordance with the principles of the Dvaita school), who was the pupil of Purushōttama-mahātīrtha (who composed a *bhāṣya*):—

(L. 15).— . . Śaka-vatsarē hutavaha-vyōma-dvaya-kṣmā-yutē Mēshē śukla-Śaśāṃkka-
kharā-[di]nē vārē [cha] Saumyē varē.

The date is irregular; see *ibid.* p. 266.

980.—**Ś. 1205*.**—*Inscr. at Śravaṇa-Belgoḷa*, No. 129, p. 96. Sanskrit and Kanarese inscription recording grants by **Bālachandradēva**, disciple of the *Mahāmaṇḍalāchārya* Nēmichandra-
paṇḍitadēva, and by others:—

Sa(śa)ka-varṣam 1205neya Chitrabhānu-saṃvatsara Śrāvāna-su 10 Bṛid=andu.

Thursday, 16th July A.D. 1282; see *Ind. Ant.* Vol. XXIII. p. 128, No. 94.

981.—**Ś. 1235.**—*Inscr. at Śravaṇa-Belgoḷa*, No. 41, p. 11. Sanskrit and Kanarese inscription recording the date of the death of **Subhachandramuni**:—

Pañchatrīmśatsaṃyuta-śatadvayādika-sahasra-nuta-varṣhēshu | vṛttēshu Śaka-nṛipasya
tu kālē vistirṇṇa-vilasad-arṇṇavanēmau || Pramādi-vatsarē māsē Śrāvānē tanum=atyajat |
Vakrē kṛṣṇa-chaturddāśyām Śubhachandrō mahāyatih ||

Tuesday, 21st August A.D. 1313; see *Ind. Ant.* Vol. XXIII. p. 125, No. 75.

The inscription praises Mēghachandra-traividya² and others.

982.—**Ś. 1295*.**—*Inscr. at Śravaṇa-Belgoḷa*, No. 111, p. 86. Partly illegible rock inscription, recording that some work or other was done by (?) **Vardhamānasvāmin**:—

Śaka-varṣa 1295 Paridhāvi-saṃvatsara Vaiśākha-śuddha 3 Budhavāra.

Wednesday, 7th April A.D. 1372; see *Ind. Ant.* Vol. XXIII. p. 129, No. 95.

983.—**Ś. 1320*.**—*Inscr. at Śravaṇa-Belgoḷa*, No. 105, p. 76. Pillar inscription recording the date of the death of **Purupaṇḍita**, and the erection of a tomb for him by his disciple **Abhinavapaṇḍitadēva**; preceded by a long account of **Jaina** teachers; (composed by **Arhaddāsa**):—

Tatra trayōdaśa-śatais=cha daśa-dvayēna Śākē=bdakē parimitē=bhavad=Īśvar-ākhyē |
Māghē chaturddāśa-tithau sitabhāji vārē Svātau Śanaish(nēh) surapadam Purupaṇḍitasya ||

The date is irregular.

984.—**Ś. 1331.**—*Inscr. at Śravaṇa-Belgoḷa*, No. 106, p. 80. Sanskrit and Kanarese inscription, recording a grant by a certain **Māyappa**, a disciple of **Chandrakīrti**:—

Śaka-varṣa 1331neya Virōdhi-saṃvatsarada Chaitra-ba 5 Gu.

Thursday, 4th April A.D. 1409; see *Ind. Ant.* Vol. XXIII. p. 126, No. 78.

985.—**Ś. 1353.**—*Ep. Ind.* Vol. VII. p. 110. Inscription on a colossal **Jaina** statue³ at **Kārkaḷa** in the South Canara district, erected by **Vira-Pāṇḍya** (**Pāṇḍyarāya**), the son of **Bhairavēndra** of the lineage of the Moon, by the advice of the **Jaina** priest **Lalitakīrti**:⁴—

(L. 5).— Svasti śrī-Śakabhūpatēs=tri-śara-vahn-īndōr=V virōdhyādikṛd-varṣhē Phālguna-
Saumyavāra-dhavalā-śrī-dvādaśi-sattithau.

(L. 14).— Śaka-varṣa 1353.

Wednesday, 13th February A.D. 1432; see *Ind. Ant.* Vol. XXIII. p. 119, No. 42.

¹ In *Ep. Ind.* Vol. VI. p. 266 ff. are given the dates of five other inscriptions which record gifts of **Naraharītīrtha**; one of them (No. 2) quotes the coincidence called *Arādhodaya* and a solar eclipse which was visible in India; another (No. 4), of Ś. 1215 (corresponding to the 21st May A.D. 1293), is of the 18th year of the reign of **Vira-śrī-Naranārasimhadēva** (i.e. the Gaṅga king of Kalinga **Narasimhadēva** II.; see *North. Inscr.* No. 867).—Compare also Mr. Venkayya's *Report* for 1900, p. 33.

² See above, Nos. 74, 337, and 408.

³ For a short Kanarese inscription of **Pāṇḍyarāya**, on the same statue, see *Ep. Ind.* Vol. VII. p. 111.

⁴ Compare below, Nos. 987, 993 and 994.

986.—Ś. 1355*.—*Inscr. at Śravana-Belgoḷa*, No. 108, p. 81. Pillar inscription recording the death of Śrutamuni and the erection of a tomb for him; preceded by a long account of Jaina teachers; (composed by Maṅgarāja):—

Ishu-śara-sikhi-vidhu-mita-Śaka-Paridhāvi-śarad-dvitiyag-Āshādhē | sita-navami-Vidhudin-²
ōdayajushi sa-Visākhē pratishṭhit-ēyam=iha ||

Monday, 7th July A.D. 1432; see *Ind. Ant.* Vol. XXIII. p. 129, No. 96.

987.—Ś. 1358*.—*Ep. Ind.* Vol. VII. p. 111. Kārkaḷa Kanarese pillar inscription of Vira-Pāṇḍya, the son of Bhairava of the family of Jinadatta:¹—

(L. 1).—Śaka-nripaṇa 1358 Rākshasa-saṁvatsara[da Ph]ālguna-śu 12lu ||

988.—Ś. 1432*.—*Inscr. at Śravana-Belgoḷa*, No. 103, p. 75. Kanarese inscription recording some repairs made by a son of Keśavanātha, the minister of the Maṇḍalēśvara Kulōttuṅga-Chaṅgāḷa-Mahādēva:—

Sa(śa)kha(ka)-varuṣa 1432ḍaneya Śukla-saṁvatsarada Vayisākha-ba 10lā.

989.—Ś. 1438(?).—*PSOCI.* No. 228; *Mysore Inscr.* No. 112, p. 208. Tyākal Kanarese rock inscription; appears to treat of a Mahāmaṇḍalēśvara Gōparāja (Sāluva-Gōparāja)² and others:—

‘Śaka 1438 (in figures, l. 1), the Pramādi saṁvatsara; the first day of the bright fortnight of Phālguna;’ (*Mys. Inscr.*: ‘the year 1434’).

Pramādin would be Ś. 1415; (Pramōda = Ś. 1432, and Pramāthin = Ś. 1441).

990.—Ś. 1459 (for 1460).—*Inscr. at Śravana-Belgoḷa*, No. 99, p. 75. Kanarese pillar inscription recording a private grant:—

Śaka-varuṣa sāviraḍa 1459taneya Viḷambi-saṁvatsarada Māgha-suddha 5yalu.

991.—Ś. 1486.—*Coorg Inscr.* No. 10, p. 14. Añjanagiri Kanarese Jaina inscription, caused to be written by Śāntikīrtidēva, the fellow student of Abhinava-Chārūkīrti-paṇḍitadēva:—

Śaka-varuṣa 1466 sanda vartamāna-Krōdhi-saṁvatsarada Kārti(rti)ka-śu 15yallu.

992.—Ś. 1476*.—*PSOCI.* No. 47; *Archæol. Surv. of West. India*, Vol. I. Plate xxxiii. 8. Bādāmi Telugu pillar inscription:³—

(L. 1).—Śālivāhana-Śaka-varuṣambulu 1476guna(nē)ṭi Pramādi-saṁ[va*]tsara
Āshāḍa(ḍha)-ba 11lu.

993.—Ś. 1508.—*Ind. Ant.* Vol. V. p. 40; corrected by Dr. Hultzsch from inked estampages. Kārkaḷa Jaina temple Sanskrit and Kanarese inscription of Immaḍi-Bhairarasa-Oḍeya or Bhairava [II.], surnamed Vīranarasimha-Chaṅganarēndra, a descendant of the family of Jinadatta and the nephew of Bhairarasa-Oḍeya or Bhairava [I.], ‘supreme lord of Paṭṭi-Pombuchchapura’:⁴—

(L. 7).—śrīmach-Chhāli-Śak-ābdakē cha gali(ni)tē nāg-ābhra-bāp-ēndubhiś=ch=ābdē sad-
Vyaya-nāmnī Chaitra-sita-shaṣṭyām(shṭhyām) Saumyavārē Vṛishē | lagnē san-Mru(mṛi)-
gaśiraha-bhē.

(L. 9).—Śālivāhana-Śaka-varuṣa | 1508neya Vyaya-saṁvatsarada Chaitra-suddha-sha-
ṣṭi(shṭhi)yā Budhavāra Mṛigaśirā-nakshatraḍ(vā) Vṛishabha-lagnadallā.

Wednesday, 16th March A.D. 1586.

¹ Compare above, No. 985.

² Compare above, Nos. 501, 508 and 509.

³ For another, undated Bādāmi Telugu pillar inscription see *PSOCI.* No. 48, and *Archæol. Surv. of West. India*, Vol. I. Plate xxxiii. 9.

⁴ Compare above, Nos. 985 and 987; also No. 237.

994.—**Ś. 1525.**—*Ep. Ind.* Vol. VII. p. 113. Inscription on a colossal Jaina statue¹ at Vēnūr in the South Canara district, erected by **Timamarāja** (the younger brother of Pāṇḍya, son of queen Pāṇḍyaka, and nephew and son-in-law of Rāyakuvāra) of the Chāmūṇḍa family, by the advice of the Jaina priest Chārukīrti :—

(L. 4).—Śaka-varshēshv-atitē[shu vi]shay-ākshi-sar-ēmdushu | va[ritamā]nē Śōbhakṛiti vatsarē Phālgun-ā[khyakē ||] Māsē=tha suklapaksh-ēddha-dasamyām Gu[ru-Pu]shyakē | su-lagnē Mithunē.

Thursday, 1st March A.D. 1604; see *ibid.* p. 112.

995.—**Ś. 1556.**—*Inscr. at Śravaṇa-Belgoḷa*, No. 84, p. 66, and No. 140, p. 111. Kanarese stone and Kanarese copper-plate inscription of the *Mahārājādhirāja Chāmarāja-Voḍeyar*, lord of the city of Maisūru (Mahīśūrapattana) :—

Śālivāhana-Śaka-varuṣa 1556neya Bhāva-saṁvatsarada Āshāḍa(dha)-śu 13 Śthiravāra-Brahmayōgadalū.

Saturday, 28th June A.D. 1634; see *Ind. Ant.* Vol. XXIII. p. 121, No. 50.

996.—**Ś. 1565.**—*Inscr. at Śravaṇa-Belgoḷa*, No. 142, p. 112. Rock inscription recording the date of the death of **Chārukīrti-paṇḍita** :—

Śrī-Śakavaruṣa 1565neya Śrīmach-Chārusukīrtipaṇḍita-yatiḥ Śōbhānu-saṁvatsarē mācē Pushya-chaturddasī-tithi-varē kṛishṇē supakshē mahān | madhyāhnē vara-Mūla-bhē cha(?) karapē Bhārggavyavārē Dhṛi(dhru)vē yōgē svargga-purān jagāma matimān(māms)=traividya-chakrēśvaraḥ ||

Friday, 29th December A.D. 1643; see *Ind. Ant.* Vol. XXIII. p. 126, No. 79.

997.—**Ś. 1576.**—*Mysore Inscr.* No. 175, p. 333. Yelandur Kanarese (?) inscription of **Mudda-bhūpati (Muddu-rāja)** of Padināḍu :—

‘In the Śaka year 1576, the year Jaya.’

Mudda-bhūpati was one of the successors of Singhadēva-bhūpa of whom the inscription records a donation made ‘in the Śaka year 1490, the year Vibhava.’

998.—**Ś. 1594*.**—*PSOCL.* No. 33; *Mysore Inscr.* No. 137, p. 249. Śimoggā Kanarese date of **Keladi-Sōmasēkhara-Nāyaka**.²—

(L. 1).—Śālivāhana-Śaka-varuṣa(sha) 1594neya Virēdhikṛitu-saṁvatsarada Śrāvāṇa-śu 151ā,

999.—**Ś. 1601.**—*Ep. Carn.* Vol. III. p. 81, No. 151; *Mysore Inscr.* No. 167, p. 309. Karigatta (Karēghatta) Sanskrit and Kanarese plates of **Chikkadēvēndra** of Mahīśūrapura, reigning at Paśchima-Raṅganagara (Śrīraṅgapattana) :—

Indu-bindv-aṅga-chandrēshu Śak-ābdēshu gatēshv=atha | Siddhārthini Sabē kṛishṇa-dvitiyāyām pitus=tithau ||

Certain kings of Yadu’s race came from Dvārakā to the Karṇāṭa country and settled at Mahīśūrapura; from them sprang Dēvarāja; he had four sons the eldest of whom, Doḍḍadēva-rāja, married Amṛitāmbā; their sons Chikkadēvēndra and Kaṇṭhīra. Chikkadēvēndra defeated the Pāṇḍya Chokka, the princes of Keladi, Raṇadulā-khāna, Mushtika, Timmappa-Gauḍa and Rāmappa-Gauḍa.

¹ The same statue contains a Kanarese inscription (*Ep. Ind.* Vol. VII. p. 114)—dated on the same day, but in Ś. 1526 current—which gives the same information. In it Rāyakuvāra is called Rāyakumāra, and Timma is stated to have belonged to the lunar race and to have ruled over the kingdom of Puñjajike.

See below, No. 1003.

1000.—**Ś. 1619.**—*PSOCI.* Nos. 35 and 229; *Mysore Inscr.* Nos. 114 and 142, pp. 211 and 256. Dēvanhaḷli Kanarese plates and stone inscription of Gōpāla-Gauḍa, 'lord of the Āvatīnāḍ:—

'Śālivāhana-Śaka 1619, the Īśvara saṁvatsara; Saturday, the fifteenth day of the bright fortnight of Māgha.'

Saturday, 15th January A.D. 1698;¹ see *Ind. Ant.* Vol. XXIV. p. 4, No. 137.

1001.—**Ś. 1620.**—*PSOCI.* No. 36; *Mysore Inscr.* No. 144, p. 258. Kōlār Telugu plate of 'Prithvi Saṭṭi, and the royal minister Bhāskara,' and others:—

(L. 1).—Śālivāhana-Śaka-varuṣaṁbulu 1620agunēṭi Bahudhānya-saṁvatsara Jēṣṭha-śu 7lu.

1002.—**Ś. 1621** (for 1645?).—*Inscr. at Śravaṇa-Belgoḷa*, No. 83, p. 65. Kanarese inscription of the *Mahārājādhirāja Doḍḍa-Kṛishṇarāja-Voḍeyar* (Kṛishṇarāja), lord of the Mahīśūra country:—

Śālivāhana-Śaka-varsha 1621nē saluva Śōbhakṛitu-saṁvatsarada Kārttika-ba 13 Guruvāradallu.

For Śōbhakṛit = Ś. 1645 the date would correspond to Thursday, 14th November A.D. 1723.

1003.—**Ś. 1636*.**—*PSOCI.* No. 34; *Mysore Inscr.* No. 138, p. 250. Śimoggā Kanarese plates of Basavappa-Nāyaka, the son of Sōmasēkhara-Nāyaka, grandson of Śivappa-Nāyaka and great-grandson of Siddappa-Nāyaka, descendant of Keḷadi-Sadāśiva-Nāyaka:²—

(L. 3).—Śālivāhana-Śaka(ka)-varuṣa(sha) 1636neya varttamānakke saluva Vijaya-nāma-saṁvatsarada Chaitra-śu 15lu.

1004.—**Ś. 1644.**—*Ep. Carn.* Vol. III. p. 39, No. 64; *Mysore Inscr.* No. 163, p. 311. Tonḍanūr Sanskrit and Kanarese plates of Kṛishṇarāja (the son of Kaṇṭhīra-Narasa and grandson of Ohikkadēvēndra⁴) of Mahīśūra, issued from Śrīraṅgaṇaṭṭana; (composed by Rāmāyana-Tirumalārya):—

Śālivāhē Śak-ābdē bhūtē vēd-ārpava-rttu-kṣhiti-pariganitē 'nantarē varttamānē || Śubha-kṛid-vatsarē Mārggē pūṛṇimā-Bhaumavāsarē | Brahmayōga-yut-Ārdṛāyām Bālavē karaṇē tathā | ēvaṁ śubha-dinē . . . sōmōparāga-samayē.

Tuesday, 11th December A.D. 1723; a lunar eclipse, visible in India; see *Ind. Ant.* Vol. XXIII. p. 121, No. 51.

1005.—**Ś. 1646.**—*Ep. Carn.* Vol. III. p. 59, No. 100, and specimen plate; *Mysore Inscr.* No. 169, p. 318. Mēlukōṭe Sanskrit and Kanarese plates of Kṛishṇarāja of Mahīśūra, issued from Śrīraṅgaṇaṭṭana; (composed by Rāmāyana-Tirumalārya):⁵—

Śālivāhē Śak-ābdē bhūtē pītv-ārpav-āṅga-kṣhiti-pariganitē 'nantarē varttamānē || Krōdhi-saṁvatsarē Pushyē kṛishṇa-pakṣhē Harēr-ddinē | Budh-Ānurādhā-saṁyukta-Vṛiddhi-yōgē sa-Bālavē | uttarē tv-ayanē puṇyē Makaram yāti bhāsvati | ēvaṁ śubhē dinē prāhṇē . . . Śālivāhana-Śaka-varuṣaṅgaḷu 1646 sandu varttamānavāda Krōdhi-saṁvatsarada Pushya-bahula 11yū Saumyavāradallū.

Wednesday, 30th December A.D. 1724.

1006.—**Ś. 1650.**—Date of the time of the Coorg (Kōḍagu) Rājā Doḍḍa-Virappa-Voḍeyar, in the Abbiṁṭha plate of Vīra-Rājendra-Voḍeyar (below, No. 1009):—

Śālivāhana-Śaka-varuṣa 1650nē Kilaka-saṁvatsarada Kārttika-śuddha 2 Budhavāradallu.

Wednesday, 23rd October A.D. 1728; see *Ind. Ant.* Vol. XXIII. p. 121, No. 52.

¹ On this day the *tithi* of the date commenced 6 h. 52 m. after mean sunrise.

² According to *PSOCI.* the name is Basapayya; according to *Ep. Carn.* Vol. VI. Introduction, p. 23, Basappa.

³ Compare above, No. 998.

⁴ See above, No. 999. For the full genealogy see *Ep. Carn.* Vol. III. Introduction, p. 38.

⁵ A great part of the text is identical with part of the text of No. 1004.

1007.— **Ś. 1683.**— *PSOCL.* No. 37; *Mysore Inscr.* No. 143, p. 257. Kōlār Kanarese plate of **Chikkaṇṇa-Ṣeṭṭi** and others:—

(L. 1).— Śālivāhana-Śaka-varuṣaṁgaḷu 1683nē Vishu-saṁvatsarada Chaitra-ṣu 1 Sōma-vāradallu.

Monday, 6th April A.D. 1761; see *Ind. Ant.* Vol. XXIII. p. 121, No. 53.

1008.— **Ky. 4881*.**— *Coorg Inscr.* No. 12, p. 18. Mahādēvapura Kanarese plate of **Vira-Rājendra-Voḍeyar** of Coorg (Kodagu), recording the date of the death of his father, the **Mahārāja Liṅga-Rājendra-Voḍeyar**, the son of Appājendra-Voḍeyar:—

Kali sanda 4881nē vartamānakke salluva Vikāri-saṁvatsarada Māgha-bahula 10yu Budhavāra.

For Vikārin=Ky. 4881*=Ś. 1701 the date is irregular; it would correspond to Tuesday, 29th February A.D. 1780.

1009.— **Ś. 1718.**— *Coorg Inscr.* Nos. 13 and 14, pp. 20 and 22. Abbimāṭha and Mahādēvapura Kanarese plates of the Coorg (Kodagu) **Rājā Vira-Rājendra-Voḍeyar**, the son of Liṅga-Rājendra-Voḍeyar and grandson of Appājendra-Voḍeyar:—

Śālivāhana-Śaka-varuṣa 1718nē vartamānakke salluva Nala-saṁvatsarada Chaitra-ṣu 1 Bhārga[va*]vāradallu.

Friday, 8th April A.D. 1796; see *Ind. Ant.* Vol. XXIII. p. 122, No. 54.

(For a date of the time of the *Rāja's* great-grandfather Doḍḍa-Virappa-Voḍeyar, in the Abbimāṭha plate, see above, No. 1006).

1010.— **Ś. 1731.**— *Inscr. at Śravaṇa-Belgoḷa*, No. 72, p. 61. Kanarese inscription recording the date of the death of **Aditakirtidēva**:—

Śālivāhana-Śak-ābdāḥ 1731neya Śukla-nāma-saṁvatsarada Bhādrapada-ba 4 Budhavāradalli.

Wednesday, 27th September A.D. 1809; see *Ind. Ant.* Vol. XXIII. p. 126, No. 80.

1011.— **Ś. 1739 [and 1742].**— *Coorg Inscr.* No. 17, p. 25. Merkara Kanarese plate of the Coorg (Kodagu) **Rājā Liṅga-Rājendra-Voḍeyar**, the son(?) of Liṅga-Rājendra-Voḍeyar and grandson of Appāji-Rājendra:—

Śālivāhana-Śaka-varuṣa 1739ney-Īśvara saṁvatsarada Jēshṭha-bahula bidigeyu Bhānu-vāraḷḷe Kali-dina 1796 392nē yī śubha-divasadalī.

Sunday, 1st June A.D. 1817; see *Ind. Ant.* Vol. XXIII. p. 126, No. 81.

The inscription also contains the date: Vikrama-saṁvatsarada Chaitra-śuddha-dvādaśīyu Bhānuvāraḷḷe varige varuṣa 2 tiṅgaḷu 9 dina 25 Kali-dina 1797 421nē yētaḍruṣa su-divasadalī—corresponding, for Vikrama=Ś. 1742, to Sunday, 26th March A.D. 1820.

It also contains the date: Kali-varuṣa 4922nē Vikrama-saṁvatsarada nija-Jēshṭha tāriku 22nē Bhānuvāra,—corresponding, for Vikrama=Kaliyuga 4922*=Ś. 1742, to Sunday, 2nd July A.D. 1820, which was the 7th of the dark half of the second Jyāishṭha.

1012.— **Ś. 1748.**— *Inscr. at Śravaṇa-Belgoḷa*, No. 98, p. 74. Kanarese pillar inscription recording a donation made in the time of **Kṛishṇarāja-Voḍeyar**, lord of Mahīśūrapura:—

Śālivāhana-Śaka(ka)-varuṣa 1748neya sanda vartamānakke saluva Vyaya-nāma-saṁvatsarada Phālguna-ba 5 Bhānuvāradalu.

Sunday, 18th March A.D. 1827; see *Ind. Ant.* Vol. XXIII. p. 127, No. 82.

1013.— **Ś. 1752=V. 1868*=2493 after Vardhamāna's Nirvāṇa.**— *Inscr. at Śravaṇa-Belgoḷa*, No. 141, p. 111. Inscription recording the confirmation of some grants by **Kṛishṇarāja**, the son of Chāmarāja, reigning at Mahīśūra:—

Svasti śrī-Vardhamān-ākhyē Jinē muktīm gatē sati | vahni-randhr-ābdhi-nētrais=cha vatsarēshu mitēshu vai || Vikramāṅka-samāsv=indu-gaja-sāmaja-hastibhiḥ¹ | satīshu gapaṇīyāsu

¹ Note the irregular position of the word *indu* (for 1).

ganita-jñair=bbudhais=tadā || Śālivāhana-varshēshu nētra-bāṇa-nag-ēndubhiḥ | pramitēshu Vikrity-abdē Śrāvaṇē māsi māṅgalē || Kṛishṇa-pakshē cha pañchamyām tithau Chandrasya vāsarē |

Monday, 9th August A.D. 1830 ; see *Ind. Ant.* Vol. XXV. p. 346, No. 6.

Q.—Miscellaneous undated¹ Inscriptions.

1014.—*Ep. Ind.* Vol. VI. p. 316, and Plates. Koṇḍamudi (now Madras Museum) Prākṛit² plates³ of the *Mulādrāja* (or *Rājā*) **Jayavarman** of the *gōtra* of the Bṛihatphalāyanas, issued from the camp (or capital) of Kūdūra,⁴ and copied on the plates in the 10th year (of the king's reign) :—

(L. 41).—sahva 10 hē pa 1 diva 1.

1015.—*Ind. Ant.* Vol. IX. p. 102, and Plate. Guṇṭūr district (formerly Sir W. Elliot's, now British Museum?) plates⁵ of the *Rājā* **Attivarman**, born in the family (*kula*) of king (*nṛpati*) Kandara, which was born in the race (*vaṃśu*) of the great sage Ānanda.

1016.—*Ind. Ant.* Vol. XVIII. p. 366, and Plate. Kōmaralingam (spurious⁶) Sanskrit and Kanarese plates⁷ of a king or chief **Ravidatta** (of the Punnāḍu-vishaya?), recording grants made from Kitthipura (? Kīrtipura) with the permission of a certain **Cheramma** :—

(L. 12).—Pālgunamāsyām⁸ Ādityavārē Rēvati(tī)-nakshatrē sūryya-grāhāṇē.⁹

A king Rāshṭravarman of the Kāśyapa *gōtra* (?); his son Nāgadatta; his son Bhujaṅgā-dhirāja(?) (whose wife was the daughter of a king Śiṅgavarman); his son Skandavarman; his son Punnāṭarāja (?); his descendant (?) Ravidatta.

1017.—**Yudhishtīra-Śaka 89.**—*Ind. Ant.* Vol. IV. p. 333 ; *PSOCI.* No. 30 ; *Mysore Inscr.* No. 139, p. 251. Bhīmankaṭṭi (near Tīrthahallī in Mysore, spurious¹⁰) plates of the *Mahārājā* **Janamējaya** of the Kuru *kula*, issued from Kishkindhyā-nagarī :—

(L. 4).—Yudhithi(shṭhi)ra-Śakē Plavaṅg-ākhyē yē(ē)kōṇanavati-vatsarē Sahaaya-māsi amāvāsyāyām Saumyavāsarē . . .

(L. 29).—uparāga-samaya(yē).

1018.—*Ind. Ant.* Vol. VIII. p. 91. Bēgūr (spurious¹¹) plates of the Pāṇḍava *Mahārājā* **Chakravartin**¹² **Janamējaya**, lord of, and residing at, Hastināpura :—

Chaitra-māsē kṛishṇa-pakshē Bhauma-dinē tritīyāyām Indra-bha-nakshatrē sankrānta-vyati-pāta tan-nimitta.

1019.—*Proceedings Beng. As. Soc.* 1873, p. 76 ; *Ind. Ant.* Vol. I. p. 375 ; *PSOCI.* No. 32 ; *Mysore Inscr.* No. 133, p. 238. Kuppagaḍḍe or Sorab (spurious¹³) plates of the Pāṇḍava *Mahārājā* **Chakravartin** **Janamējaya**, lord of, and residing at, Hastināpura :—

(L. 15).—Chaitra-māsē kṛishṇa-pakshē Sōma-d[inē] Bharanī-mahānakshatrē sankrānti-vyati-pāta-nimittē.

¹ One (spurious) inscription, No. 1017, is dated in the Yudhishtīra-Śaka 89.

² The legend on the seal is in Sanskrit. The alphabet used closely resembles that of No. 617.

³ The (eight) plates are marked with numerical symbols, and other numerical symbols occur in the text and date.

⁴ Kūdūrahāra, in which the village granted was situated, "may be a more ancient form of Gudrahāra, Gudravāra, Gudrāvāra or Gudrāra."

⁵ The characters are an early form of Grantha, not later in my opinion than about A.D. 650 ; see *Ep. Ind.* Vol. V. p. 122, note 4.—For an ancient inscription (at Chēzarlā in the Kistna district) of apparently the same family see Mr. Venkayya's *Report* for 1900, p. 5.

⁶ See *Ind. Ant.* Vol. XXX. p. 215, No. 11.

⁸ Read *Phālgun-amāvāsyām*.

⁹ See *Ind. Ant.* Vol. XXX. p. 219, No. 41 ; compare *ibid.* Vol. I. p. 375 ff.

¹⁰ See *ibid.* Vol. XXX. p. 220, No. 42.

¹¹ See *Ind. Ant.* Vol. XXX. p. 220, No. 43.

⁷ Of about the 9th century A.D. (?).

⁸ Read *-grahāṇē*.

¹² Compare above, No. 273.

1020.— *Proceedings Beng. As. Soc.* 1873, p. 75; *Ind. Ant.* Vol. I. p. 377, and Vol. III. p. 268, and Plates; *PSOCI.* No. 31; *Mysore Inscr.* No. 130, p. 232. Gauj or Anantapur (spurious¹) plates of the Pāṇḍava *Mahārōjādhirāja Chakravartin Janamējaya*, lord of, and residing at, Hastināpura :—

(L. 13).—Chaitra-māsē krishṇa va-karaṇē uttarāyana-sam[krānti]-vyatipāta-nimittē sūryya-parvaṇi ardhagrāsa-grahita-samāē.

1021.— *Inscr. at Śravaṇa-Belgoḷa*, No. 1, p. 1, and Plates; *Ep. Ind.* Vol. IV. p. 26, and Plate. Rock inscription² recording the death of the *Āchārya Prabhāchandra*.

1022.— *Inscr. at Śravaṇa-Belgoḷa*, No. 55, p. 47. Sanskrit and Kanarese inscription,³ giving an account of some Jaina teachers among whom is a *Prabhāchandra* whose feet were worshipped by *Bhōjarāja*, the king of Dhārā.

1023.— *Inscr. at Śravaṇa-Belgoḷa*, No. 58, p. 55. Fragmentary Kanarese inscription, commemorating the death of a certain *Piḷḷa* (called *Māvana-gandhahastī*, 'a rutting elephant to his father-in-law'), which took place—

Chitrabhānu-samvatsaram adhik-Āshādha-bahula-dasa(śa)mi-dinadoḷ.

Āshādha was intercalary in Chitrabhānu = Ś. 904 and 1384; according to Mr. Rice, the former year would be intended here.

1024.— *Coorg Inscr.* No. 8, p. 11, and Plate. Bhagamaṇḍala inscription⁴ of the time 'while Metpudi Kunniyarasa was ruling the nād :—

(L. 1).—Kany-ārūḍha-Brihaspatau Vṛischik-ākhyē mahā-māsē Brihaspaty-Uttarā-dinē.

1025.— *Ind. Ant.* Vol. IX. p. 74; *PSOCI.* No. 75; *Archæol. Surv. of West. India*, Vol. I. Plate lv. No. 33. Aihole inscription⁵ containing the name of *Narasobba*,⁶ perhaps the builder of a temple.

1026.— *Ind. Ant.* Vol. VIII. p. 287, and Plate; *PSOCI.* No. 78. Two Aihole Kanarese inscriptions⁷ recording gifts to 'the Five-hundred of Āryapura (Ayyāvole).'

1027.— *Ind. Ant.* Vol. IX. p. 99; *PSOCI.* No. 84. Aihole Sanskrit and Kanarese rock inscription⁸ of *Baregedēva-Nāyaka* :—

(L. 3).—Prajōtpatya-samhacharada | Chayitra-ba llū |

1028.— *Ind. Ant.* Vol. IX. p. 74, and Plate; *PSOCI.* No. 81. Aihole inscription consisting of the words *Vaṁśiga-Biṭṭu-kṛitam*.

1029.— *Archæol. Surv. of West. India*, Vol. III. p. 127, No. 24; *PSOCI.* No. 74. Aihole Kanarese memorial tablet.

1030.— *Ind. Ant.* Vol. IX. p. 74, and Plate; *PSOCI.* No. 80. Aihole Kanarese(?) inscription.

1031.— *Ind. Ant.* Vol. X. p. 104, and Plate; *PSOCI.* No. 51. Bādāmi (Mahākūṭa) Kanarese pillar inscription; mentions a *Mahāsāmanta Ereve*.

1032.— *Ind. Ant.* Vol. X. p. 61, and Plate; *PSOCI.* No. 42. Bādāmi Sanskrit and Kanarese inscription in praise of one *Kappe-Arabhaṭṭa*.

1033.— *Ind. Ant.* Vol. X. p. 62, and Plate; *PSOCI.* No. 43. Bādāmi Kanarese inscription recording a gift to one *Śridharabhūtesvara*.

¹ See *Ind. Ant.* Vol. XXX. p. 220, No. 44.

² According to Mr. Rice "certainly not later than about 400 A.D.;" according to Dr. Fleet, on palaeographic grounds "to be allotted to approximately the seventh century A.D."

³ According to Mr. Rice, of about A.D. 1115.

⁴ Part of the text is in Sanskrit; what the language of the rest is, has not been ascertained.

⁵ Of about the 7th or 8th century A.D.

⁶ Compare the name Ganasobba, in *Archæol. Surv. of West. India*, Vol. I. Plate lv. No. 34; *Ind. Ant.* Vol. IX. p. 74.

⁷ Of about the 8th or 9th century A.D.

⁸ Of about the 15th or 16th century A.D.

1034.— *Ind. Ant.* Vol. X. p. 65, and Plate; *PSOICI.* No. 49. Bādāmi inscription,¹ mentioning a certain Ravidēva-tridaṇḍin, and recording the advent of the goddess Mahālakshmi from Kollāpura (Kōlhāpur).

1035.— *Ind. Ant.* Vol. X. p. 59; *PSOICI.* Nos. 40 and 41. Bādāmi rock inscriptions containing names probably of visitors.

1036.— *PSOICI.* No. 212; *Mysore Inscr.* No. 93, p. 183. Baḷagāṁve Sanskrit and Kanarese memorial tablet.

1037.— *PSOICI.* Nos. 207-211; *Mysore Inscr.* Nos. 50, 51, 54, 66 and 76, pp. 113, 115, 138 and 162. Five Baḷagāṁve Kanarese memorial tablets.

1038.— *PSOICI.* Nos. 244 and 245; *Mysore Inscr.* Nos. 123 and 124, p. 221. Two Bēlūr Kanarese inscriptions.

1039.— *PSOICI.* Nos. 143, 144 and 145; *Mysore Inscr.* Nos. 14, 15 and 16, p. 24. Three Dāvāṅgere Kanarese memorial tablets.

1040.— *Ind. Ant.* Vol. X. p. 170, and Plate; *PSOICI.* No. 68. Paṭṭadakal Kanarese inscription² in praise of a certain (architect) Chaṭṭara-Revadi-Ovajja.

1041.— *Ind. Ant.* Vol. X. p. 171, and Plate; *PSOICI.* No. 69. A short Paṭṭadakal inscription.²

1042.— *Ind. Ant.* Vol. X. p. 167; *PSOICI.* No. 56. Paṭṭadakal pillar inscription;³ two verses, by Achala, in praise of Bharata, the writer on dramatic composition.

1043.— *Ind. Ant.* Vol. X. pp. 167 and 168; *PSOICI.* Nos. 61-64. Four short Paṭṭadakal Kanarese pillar inscriptions, mostly containing names (of no historical importance).

1044.— *Ind. Ant.* Vol. X. p. 170, and Plate; *PSOICI.* Nos. 65 and 66. Two short Paṭṭadakal Kanarese pillar inscriptions (of no historical importance).

1045.— *PSOICI.* Nos. 213 and 222; *Mysore Inscr.* Nos. 101 and 107, pp. 188 and 203. Two Tālgund Kanarese memorial tablets.

1046.— *South-Ind. Inscr.* Vol. II. No. 36, p. 149. Tanjore (Rājarājēśvara temple) Tamil inscription of Aravaṇai alias Māl-Ari-Kēśavaṇ, head-overseer of the Rājarājēśvara temple.

1047.— *South-Ind. Inscr.* Vol. I. No. 73, p. 104. Tirumalai Tamil inscription recording that Ariṣṭhaṇṣmi-āchārya, a pupil of Paravādimalla, caused the image of a *yakshi* to be made.

1048.— *South-Ind. Inscr.* Vol. I. Nos. 91-94, p. 127. Four Vēlūr Tamil inscriptions recording the erection of monuments of devotion by a certain Chandra-pillai of Kāṭṭēri.

1049.— *South-Ind. Inscr.* Vol. II. No. 62, p. 248. Tanjore (Rājarājēśvara temple) Tamil inscription of a certain Mallappa-Nāyakkar.

1050.— *South-Ind. Inscr.* Vol. I. No. 50, p. 76. Śēkkaṇūr (near Vēlūr) Tamil inscription, recording the gift of the village of Śēkkaṇūr to the Vēlūr temple.

1051.— *South-Ind. Inscr.* Vol. I. No. 65, p. 92. Vakkaṇāpuram (near Viriñchipuram, Īśvara temple) Tamil inscription, recording that some people agreed to found a temple, called Okkaninṅga-nāyaṇār, and made grants 'from the month of Kārttika of the Siddhārthin year forward.'

1052.— *South-Ind. Inscr.* Vol. I. No. 71, p. 102. Tirumalai Tamil inscription recording the gift of a well.

1053.— *South-Ind. Inscr.* Vol. I. No. 77, p. 107. Tirumalai Tamil inscription recording the gift of a sluice.

¹ Of about the 16th or 17th century A.D.

² Of about the 8th or 9th century A.D.

³ Of about the 7th or 8th century A.D.

R.—Addenda.

1054.—*Ś. 787.*—*Ep. Ind.* Vol. VII. p. 201, and Plate. Mantrawādi (now Shiggaon) Kanarese inscription of the time of the Rāshtrakūṭa¹ *Mahārājādhirāja Amōghavarsha I.*,² and his feudatory *Kuppēya* :—

(L. 3).—*Śakanripakāl-ātita-samvatsara-śatamgaḥ=ēl-nūṛ-epbhatt-ēlaneya Pārthiva-samvat-saram pravarttise . . . Vaisākha-māsada paurṇamāse(si)y-and=.*

1055.—*Ep. Ind.* Vol. VII. p. 212, and Plate. Nidugundi (now Shiggaon) Kanarese inscription of the time of the Rāshtrakūṭa¹ *Mahārājādhirāja Amōghavarsha I.*, and his feudatories *Baṅkēyarasa (Baṅkēya)*³ and *Baṅkēya's son Kundatte* :—

(L. 1).—*Amōghavarsha . . . ond-uttaram rājyam-geyyutt-ire.*⁴

1056.—*Ś. 871.*—*Ep. Ind.* Vol. VII. p. 195. Śōlapuram Tamil inscription, dated—

'(in) the year two,⁵ the Śaka year eight hundred and seventy-one, the year in which the *Chakravartin Kannaradēva-Vallabha*,⁶ having pierced *Rājāditya*, entered the *Torḍai-maṇḍalam*.'

The inscription records the construction of a pond named after a daughter of the Gaṅga chief *Attimallar (i.e. Hastimalla) alias Kannaradēva-Prithvigāṅgaraiyar*,⁷ the son of *Vayiri-Adiyan*.

1057.—*Ś. 875.*—*Ep. Ind.* Vol. VII. p. 196. Śōlapuram incomplete Tamil inscription, dated—

'(in) the [eight-hundred]-and-seventy-fifth year of the Śaka (king), while the glorious *Attimallar (i.e. Hastimalla) alias Kannaradēva-Prithvigāṅgaraiyar*,⁸ was ruling the *Kalle-ḍuppūr-maryādā*.'

1058.—*Ep. Ind.* Vol. VII. p. 135. Tirunāmanallūr (Bhaktajanēśvara temple) Tamil inscription of the 17th year (of the reign) of the glorious *Kannaradēva (i.e. the Rāshtrakūṭa Kṛishṇarāja III.)*; recording the gift of a lamp by a chief of *Milāḍu*, named *Narasimhavarman*, surnamed *Śaktinātha* and *Siddhavaḍava*, of the lineage of *Śukra* and belonging to the *Malaiya-kula (i.e. the family of the rulers of Malaiyanāḍu or Malaināḍu, of which Milāḍu and Malāḍu are contracted forms).*⁹

1059.—*Ep. Ind.* Vol. VII. p. 142, and Plate. Tirukkōvalūr (Virattāṇēśvara temple) Tamil inscription of the 21st year (of the reign) of *Kannaradēva (i.e. the Rāshtrakūṭa Kṛishṇarāja III.)*; recording a grant of land by the *Vaidumba-mahārāja Śandayan Tiruvayan (i.e. Tiruvayan)*¹⁰ the son of *Śandayan* and his queen *Śāttiradēvī*.

1060.—*Ep. Ind.* Vol. VII. p. 143. Tirukkōvalūr (Virattāṇēśvara temple) Tamil inscription of the [22nd ?] year (of the reign) of *Kannaradēva (i.e. the Rāshtrakūṭa Kṛishṇarāja III.)*; recording a gift of gold by a female relative of the *Vaidumba-mahārāja Tiruvayan*.

1061.—*Ep. Ind.* Vol. VII. p. 144, and Plate. Tirukkōvalūr (Virattāṇēśvara temple) Tamil inscription of the 24th year (of the reign) of *Kannaradēva (i.e. the Rāshtrakūṭa Kṛishṇarāja III.)*; recording the gift of 24 lamps by the *Vaidumba-mahārāja Tiruvayan*.

¹ The name Rāshtrakūṭa does not occur in the inscription.

² See above, No. 71 ff.

³ Compare above, No. 74.

⁴ I.e. 'while Amōghavarsha . . . was reigning increased by one.' According to Dr. Fleet 'increased by one' would be an abbreviation of the full expression 'the sixtieth year increased by one.'

⁵ According to Dr. Hultzsch, of the reign of the Chōla king *Rājāditya*, mentioned in the sequel.—Compare above, No. 95.

⁶ I.e. the Rāshtrakūṭa *Kṛishṇarāja III.*; above, No. 98 ff.

⁷ See above, No. 1056.

⁸ Compare below, No. 1080.

⁹ See below, No. 1057.

¹⁰ I.e. the *Tiruvayan* of No. 708.

1062.—*Ep. Ind.* Vol. VII. p. 115. Tirupparuttikkunru (near Conjeeveram) Tamil inscription, recording a grant made by the minister Irugappa,¹ the son of the *Danḍanātha* Vaichaya, for the merit of the *Mahāmaṇḍalēśvara* Bukkarāja [II.], the son of Arihararāja (i.e. Harihara II.) :—

‘(In) the Dundubhi year, (on) the day of Kāttigai (Kṛittikā), which corresponded to a Monday and to the full-moon *tithi* of the first fortnight in the month of Kāttigai.’

[For Dundubhi=Ś. 1304] the date is irregular; see *ibid.* Vol. VI. p. 329, No. 1.

1063.—*Ep. Ind.* Vol. VII. p. 116. Tirupparuttikkunru (near Conjeeveram) inscription, recording that the *maṇḍapa* on which it is found was built by the general Irugappa, the son of the *Danḍanātha* Vaichaya, at the command of (the Jaina priest) Pushpasēna.

(L. 1).—*samvatsarē Prābhavē.*

[Prabhava=Ś. 1309.]

1064.—Ś. 1437.—*Ep. Ind.* Vol. VII. p. 20. Amarāvati (Amarēśvara temple) inscription of Kṛishnarāja, the son of Narasa and Nāgamāmbā, of Vijayanagara :—

(L. 35).—Āshādhē=bdē Yuv-ākhyē muni-pura-jaladh-imdv-amkitē . . Śak-ābdā . . dvādaśyām.²

The king took Śivanasamudra, Udayādri, Vinikonda and Bellakonda, captured the Gajapati king's son Virabhadra, and took Koṇḍaviṭṭu.

1065.—*Ep. Ind.* Vol. VII. p. 185. British Museum (formerly Sir W. Elliot's) plates³ (Kaluchumbagru grant) of the E. Chālukya *Mahārājādhirāja* Ammarāja II. Vijayāditya VI.,⁴ lord of Vēngi, recording a grant to the Jaina teacher Arhanandin (the disciple of Ayyapōti who was the disciple of Sakalachandra-siddhānta), made at the instance of Arhanandin's pupil, the lady Chāmekāmbā of the Paṭṭavardhika⁵ lineage :—

(L. 62).—uttarāyana-nimittēna.

Genealogy with lengths of reigns as far as Kali-Vishṇuvardhana [Vishṇuvardhana V.] substantially⁶ as in No. 560. His son Gunaga-Vijayāditya [Vijayāditya III.] ('had his arms honoured' by the Vallabha king;⁷ reigned 44 years); his younger brother the Yuvarāja Vikramāditya's son [Chālukya-] Bhīma [I.] (conquered Kṛishnavallabha;⁸ 30 ys.); his son Vijayāditya [IV.] Kollabigaṇḍa (6 months); his eldest son Ammarāja [I.] Rājamahēndra (7 ys.); having expelled his son Vijayāditya [V.], Tālupa, the son of Yuddhamalla [I.] (one month); having conquered him, Chālukya-Bhīma's son Vikramāditya [II.] (9 months); Tālupa's eldest son Yuddhamalla [II.] (7 ys.); the son of Kollabigaṇḍa [Vijayāditya IV.] and brother, from a different mother, of Rājamahēndra [Ammarāja I.], viz. [Chālukya-] Bhīma [II.] (Rājabhīma, conquered Rājamayya,⁹ Dhalaga,¹⁰ Tātabikki,¹⁰ Bijja,¹¹ Ayyapa,¹² Gōvindarāja,¹³ the Chōla Lōvabikki, and [his own predecessor] Yuddhamalla [II.]; reigned 12 ys.); his son, from Lōkamahādēvi, Ammarāja [II.].

1066.—Ś. 1238.—*Ep. Ind.* Vol. VII. p. 130. Conjeeveram (Arulāla-Perumāḷ temple) Sanskrit and Tamil inscription of the time of the Kākatīya¹⁴ *Mahāmaṇḍalachakravartin*

¹ See above, No. 469.

² The date is identical with that of No. 568, and would therefore correspond to the 23rd June A.D. 1515.

³ They contain a short Telugu passage and otherwise a few Telugu words.

⁴ See above, No. 563 ff.

⁵ See above, Nos. 559 and 564.

⁶ But Kubja-Vishṇuvardhana is called Kubja-Vishṇu (compare No. 531), and Indra-bhattāraka Indrarāja.

⁷ I.e. the Rāshtrakūṭa Amoghavarsha I. or Kṛishnarāja II.

⁸ I.e. the Rāshtrakūṭa Kṛishnarāja II.

⁹ Perhaps the Rājavarman in No. 127 above.

¹⁰ Compare above, No. 562.

¹¹ Perhaps the Bijja-Dantivarman of Banavāsi, above, No. 127.

¹² Perhaps the Ayyapadēva in No. 126 above.

¹³ I.e. the Rāshtrakūṭa Gōvindarāja IV.

¹⁴ See above, No. 584 ff.

Pratāparudra of Ēkaśilānagarī.¹ The inscription records that Pratāparudra's general **Muppiḍi (Muppiḍi-Nāyaka)** entered Kāñchī and, on the first date here given, installed there a certain **Mānavira** as governor ; and that, on the second date, he made certain grants *etc.* at Kāñchī-puram :—

(L. 2).— Naḷ-ābdē || Māsē Śūchau Sarppa-dinē cha kṛishṇē vārē sa-Śukrē.

(L. 3).— ‘(In) the Śaka year 1238, the Nala-samvatsara, (on) a day which corresponded to an eleventh *tithi*, to a Wednesday, and to the twenty-first solar day (of) the month Āṇi.’

Friday, 11th, and Wednesday, 16th June, A.D. 1316 ; see *ibid.* p. 128 f.

1067.— *Ep. Ind.* Vol. VII. p. 139. Tirukkōvalūr (Vīraṭṭāṇēśvara temple) Tamil inscription of the 17th year (of the reign) of king **Vijaya-Nandivikrama**.²

1068.— *Ep. Ind.* Vol. VII. p. 139, and Plate. Tirukkōvalūr (Vīraṭṭāṇēśvara temple) Tamil inscription of the 21st year (of the reign) of king **Vijaya-Nripatuṅgavikrama**.³

1069.— *Ep. Ind.* Vol. VII. p. 140. Another Tirukkōvalūr (Vīraṭṭāṇēśvara temple) Tamil inscription of the 21st year (of the reign) of king **Vijaya-Nripatuṅgavikramavarman**.

1070.— *Ep. Ind.* Vol. VII. p. 193, and Plate. Śōlapuram mutilated Sanskrit and Tamil inscription of the 8th year (of the reign) of king **Vijaya-Kampa**.⁴

The Tamil portion records that a chief named Rājāditya built a temple *etc.* in memory of his deceased father Prithivigaṅgaraiyar. The mutilated Sanskrit portion states that Rājāditya's earliest ancestor was Mādhava of the Gāṅgēya family, whose son was ‘he who was renowned as the splitter of even a stone-pillar,’ and that from the latter was descended a king whose name is given in the corrupt form of Atvivarman (apparently the father of Prithivigaṅgaraiyar).

1071.— *Ep. Ind.* Vol. VII. p. 140. Tirukkōvalūr (Vīraṭṭāṇēśvara temple) Tamil inscription of the 5th year (of the reign) of king **Parakēsarivarman** (perhaps identical with Vijayālaya, the grandfather of Parāntaka I.).⁵

1072.— *Ep. Ind.* Vol. VII. p. 133. Tirunāmanallūr (Bhaktajanēśvara temple) Tamil inscription of the 28th year (of the reign) of king **Parakēsarivarman** who took Madirai (*i.e.* the Chōḷa king Parāntaka I.) ;⁶ recording the gift of two lamps by a servant of Kōkkilāṇaḍi, the queen of Parāntaka I. and mother of his son Rājāditya.⁷

1073.— *Ep. Ind.* Vol. VII. p. 141, and Plate. Tirukkōvalūr (Vīraṭṭāṇēśvara temple) Tamil inscription of the 28th year (of the reign) of king **Parakēsarivarman** who took Madurai (*i.e.* the Chōḷa king Parāntaka I.) ; recording a gift by a daughter of Kayirūr Perumāṇār, a chief of Milāḍu.

1074.— *Ep. Ind.* Vol. VII. p. 141, and Plate. Tirukkōvalūr (Vīraṭṭāṇēśvara temple) Tamil inscription of the 33rd year (of the reign) of king **Parakēsarivarman** who took Madurai (*i.e.* the Chōḷa king Parāntaka I.) ; recording a gift by the regiment of prince Arikulakēsarin (*i.e.*, perhaps, Arinjaya,⁷ the third son of Parāntaka I.).

1075.— *Ep. Ind.* Vol. VII. p. 134. Tirunāmanallūr (Bhaktajanēśvara temple) Tamil inscription of the 39th year (of the reign) of king **Parakēsarivarman** who took Madurai and Ilam (*i.e.* the Chōḷa king Parāntaka I.) ; recording the gift of a lamp by Mahādēvaḍi, the queen of prince Rājāditya⁷ and daughter of Ilāḍarāyar (*i.e.* Lāṭarāja), for the merit of her elder brother Rājādittan Puḷaḷvippavargaṇḍa.⁸

1076.— *Ep. Ind.* Vol. VII. p. 144. Tirukkōvalūr (Vīraṭṭāṇēśvara temple) Tamil inscription of the 9th year (of the reign) of king **Rājarājakēsarivarman** (*i.e.* the Chōḷa king Rājarāja

¹ *I.e.* Warangal.

² See above, Nos. 656-658.

³ See above, No. 712.

⁴ See above, No. 649.

⁵ See above, No. 672 ff.

⁶ Compare above, No. 698.

⁷ See above, Nos. 652 and 663.

⁸ See above, No. 681 ff.

I.);¹ recording a gift by Kundapaṇ's daughter Amitravali, the mother of (Rājarāja's) queen Lōkamahādēvi.²

1077.—*Ep. Ind.* Vol. VII. p. 169, No. 61. Date of a Bāhūr (Mūlēsvara temple) Tamil inscription of the 11th year (of the reign) of king Rājarājakēsarivarman who destroyed the ships (at) Kāndaḷūr-Śālai; (*i.e.* the Chōḷa king Rājarāja I.):—

'In the 11th year . . . in daytime on the day of Kṛittikā, which corresponded to a Sunday of the second fortnight of the month of Mithuna in this year.'

[Ś. 918]: Sunday, 14th June A.D. 996.

1078.—*Ep. Ind.* Vol. VII. p. 169, No. 62. Date of an Uḍaiyārkōyil (Karavandīśvara temple) Tamil inscription of the 31st year (of the reign) of king Parakēsarivarman *alias* the lord, the glorious Rājēndra-Chōḷadēva [I.]:³—

'In the 31st year . . . on the day of Punarvasu, which corresponded to a Friday and to the fourth *tithi* of the first fortnight of the month of Karkāṭaka in this year.'

[Ś. 964]: Friday, 23rd July A.D. 1042; but the *nakṣatra* is irregular.

1079.—*Ep. Ind.* Vol. VII. p. 137. Tirunāmanallūr (Bhaktajanēśvara temple) Tamil inscription of the reign⁴ of king Parakēsarivarman *alias* the glorious Rājēndra-Chōḷadēva [I.].

1080.—*Ep. Ind.* Vol. VII. p. 145. Tirukkōvalūr (Trivikrama-Perumāl temple) Sanskrit and Tamil inscription of the 6th year (of the reign) of king Parakēsarivarman *alias* the lord, the glorious Rājēndradēva,⁵ who with his elder brother (Rājādhirāja I.) conquered Ratta-pāḍi, set up a pillar of victory at Kollāpuram, and terrified (the W. Chālukya) Āhavamalla (Sômēsvara I.) at Koppam.—The inscription records the rebuilding of a temple by a chief of Milāḍu, named Narasiṁhavarman,⁶ surnamed Raṇakēsari-Rāma, of the lineage of Bhārgava.⁷

1081.—*South-Ind. Inscr.* Vol. III. No. 81, p. 198. Tirunāmanallūr (Bhaktajanēśvara temple) incomplete Tamil inscription of the 4th year (of the reign) of king Rājakēsarivarman *alias* the lord, the glorious Virarājēndradēva (*i.e.* the Chōḷa king Virarājēndra I.),⁸ who was pleased to be seated on the throne of heroes together with (his queen) Ulagamulududaiyāl (*i.e.* 'the mistress of the whole world').—The inscription records that the king terrified (the W. Chālukya) Āhavamalla (Sômēsvara I.) at Kūḍalsāṅgam and put to flight Vikkalaṇ (*i.e.* Vikramāditya VI.) and Śiṅgaṇaṇ (*i.e.* Jayasimha III.). It gives a number of epithets of his, among which are Āhavamallakulakāḷa, Āhavamallanai-mummaḍi-veṇ-kaṇḍa (*i.e.* 'he who saw the back of Āhavamalla three times'), Vira-Chōḷa, Karikāla-Chōḷa, and Kōṇēriṇmaikoṇḍāṇ.⁹

1082.—*South-Ind. Inscr.* Vol. III. No. 82, p. 199. Kilūr (Virattāṇēsvara temple) Tamil inscription of the 5th year (of the reign) of king Rājakēsarivarman *alias* the lord, the glorious Virarājēndradēva [I.], who was pleased to be seated on the throne of heroes together with (his queen) Ulagamulududaiyāl (*i.e.* 'the mistress of the whole world').—The king terrified (the W. Chālukya) Āhavamalla (Sômēsvara I.) at Kūḍalsāṅgam, and put to flight Vikkalaṇ (*i.e.* Vikramāditya VI.) and Śiṅgaṇaṇ (*i.e.* Jayasimha III.); he terrified Āhavamalla a second time, seized Vēṅgai-nāḍu, and performed the anointment of victory.

1083.—*South-Ind. Inscr.* Vol. III. No. 83, p. 200. Tiṇḍiṇaṇam (Tintriṇīśvara temple) Tamil inscription of the 6th year (of the reign) of king Rājakēsarivarman *alias* the lord, the glorious Virarājēndradēva [I.], who was pleased to be seated on the throne of victory together with (his queen) Ulagamulududaiyāl (*i.e.* 'the mistress of the whole world').—After the

¹ See above, No. 696 ff.

² See above, No. 716.

³ See above, No. 721 ff.

⁴ The figure denoting the year of the reign is lost.

⁵ See above, No. 744 ff.

⁶ For two short Tamil inscriptions of his see *Ep. Ind.* Vol. VII. p. 146 f.

⁷ *I.e.* Sukra; see above, No. 1058. ⁸ See above, Nos. 753 and 754.

⁹ See No. 812.

information given in No. 1082, the inscription records that the king on a third occasion burnt (the city of) Kampili before Sômesvara [II.] could untie the necklace which he had put on,¹ and set up a pillar of victory at Kaṇḍikal; that he expelled Dêvanâtha and other *Sâmantas* from Chakrakôṭṭa, and recovered Kanyakubja.

1084.— *South-Ind. Inscr.* Vol. III. No. 84, p. 202. Perumbêr (Tândôṇṇisvara temple) Tamil inscription of the 7th year (of the reign) of king Râjakêsarivarman *alias* the lord, the glorious Virarâjêndradêva [I.], who was pleased to be seated on the throne of victory together with (his queen) Ulagamuḷuduḍaiyâl (*i.e.* 'the mistress of the whole world'). — The king took the head² of the king of the South (*i.e.* the Pândya), levied tribute from the Śêralaṇ (*i.e.* the Chêra king), and subdued the Śiṅgaḷa (*i.e.* Sinhala) country. He five times put to flight (the W. Châlukya) Âhavamalla (Sômesvara I.), regained Vêṅgai-nâḍu, and bestowed [Vêṅgai]-maṇḍalam on the [E.] Chalukya Vijayâditya [VII.]. He also conquered Kaḍâram and granted it to the king who worshipped his feet. He deprived Sômesvara [II.] of the Kaṇṇara country, invested Vikramâditya [VI.] with the necklace (of heir-apparent), and conquered and granted to him the seven and a half *lakshas* of Raṭṭa-pâḍi.

1085.— *Ep. Ind.* Vol. VII. p. 170, No. 63. Date of an Uḍaiyârkoḷil (Karavandisvara temple) Tamil inscription of the 16th year (of the reign) of king Râjakêsarivarman *alias* the Tribhuvanachakravartin, the glorious Kulôttuṅga-Chôladêva [I.]:³—

'In the 16th year . . . on the day of Uttarâshâḍhâ, which corresponded to a Thursday and to the ninth (?) *tithi* of the second fortnight of the month of Mîna.'

[Ś. 1007]: Thursday, 12th March A.D. 1086.

1086.— *Ep. Ind.* Vol. VII. p. 147. Tirukkôvalûr (Trivikrama-Perumâl temple) Tamil inscription of Kariya-Perumâl-Periyanâyaṇ *alias* Narasimha, lord of Malâḍu, grandson of Râma Narasimhavarman (above, No. 1080), recording donations that were to be made from the third year (of the reign) of Râjarâjadêva (*i.e.* the Chôla king Râjarâja II.).⁴

1087.— *South-Ind. Inscr.* Vol. III. No. 86, p. 210. Chidambaram (Natarâja temple) Tamil inscription of the 88th day of the 9th year (of the reign) of king Parakêsarivarman, who was pleased to be seated together with (his queen) Bhuvanamuḷuduḍaiyâl (*i.e.* 'the mistress of the whole world') on the throne of heroes (which consisted of) pure gold, *alias* the Tribhuvanachakravartin, the glorious Kulôttuṅga-Chôladêva [III.],⁵ who was pleased to take Madurai.— The king assisted Vikrama-Pândya against the son of Vîra-Pândya, subdued a place named Êlagam, defeated the Maṇa (*i.e.* Maṇava?) army, drove the Sinhala army into the sea, took Madurai from Vîra-Pândya and bestowed it on [Vikrama-]Pândya.

1088.— *South-Ind. Inscr.* Vol. III. No. 87, p. 214. Chidambaram (Natarâja temple) Tamil inscription of the 118th day of the 11th year (of the reign) of king Parakêsarivarman, who was pleased to be seated together with (his queen) Bhuvanamuḷuduḍaiyâl (*i.e.* 'the mistress of the whole world') on the throne of heroes (which consisted of) pure gold, *alias* the Tribhuvanachakravartin, the glorious Kulôttuṅga-Chôladêva [III.], who, having taken Madurai, was pleased to take the crowned head² of the Pândya.— The king had the nose of the son of Vîra-Pândya cut off, gave the great city of Kûḍal (*i.e.* Madhurâ) to Vikrama-Pândya, and took the crowned head of Vîra-Pândya.

¹ According to Dr. Hultzsch, the W. Châlukya "Sômesvara II. had to give up the necklace which was the sign of his dignity of heir-apparent in favour of his younger brother Vikramâditya VI. who had made his peace with Virarâjendra I." Compare below, No. 1084.

² See above, p. 115, note 2.

⁴ See above, Nos. 812 and 813.

³ See above, No. 756 ff.

⁵ See above, No. 814 ff.

1089.—**§. 875.**—*Ep. Ind.* Vol. VII. p. 136. Tirunâmanallûr (Bhaktajanêśvara temple)
Tamiḻ inscription of Kulamânikkan Irâmadêvan, chief of the district of Muṇai or Muṇai-
ppâḍi :—

(L. 1).—Śagar[ai] yâ[ṇ]ḍu 875âvadu.

1090.—**§. 876.**—*Ep. Ind.* Vol. VII. p. 137. Tirunâmanallûr (Bhaktajanêśvara temple)
Tamiḻ inscription of the queen of Kulamânikkerumânâr, chief of Muṇai.

(L. 1).—Śagarai yâṇḍu 87[6]âvadu.

ADDITIONS AND CORRECTIONS.

Page 3, No. 5.—Compare now *Ind. Ant.* Vol. XXXII. p. 213 ff.; in line 4, for -*paurṇa-*
mâsyâm read -*pûrṇamâsyâm*.

„ 9, No. 54.—Compare *ibid.* Vol. XXXI. p. 329 ff.

„ 10, No. 56.—Compare *Ep. Ind.* Vol. VII. p. 230 f.

„ 10, footnote 5.—For 78 read 780.

„ 10, footnote 6.—For 7 read 793.

„ 12, No. 68.—Compare *Ind. Ant.* Vol. XXXI. p. 363 ff.

„ 13, No. 74.—Compare *ibid.* Vol. XXXII. p. 221 ff.

„ 14, No. 76.—Re-edited, with Plate, in *Ep. Ind.* Vol. VII. p. 205.

„ 14, No. 79.—On this and No. 201 see now *Ind. Ant.* Vol. XXXII. p. 215 ff.

„ 15, No. 86.—For this and No. 87 compare *ibid.* Vol. XXXI. p. 395 ff.

„ 16, No. 91.—Compare *ibid.* Vol. XXXI. p. 393 ff.

„ 48, No. 267.—Compare *ibid.* Vol. XXXII. p. 216 ff.

„ 49, No. 273.—Compare No. 1018.

„ 58, No. 326.—Plate in *Ind. Inscr.* No. 46.

„ 79, No. 464, line 2.—For Ommana- read Jammaṇa-.

„ 83, No. 487, line 8.—For Nârayanâmbikâ read Nârâyanâmbikâ.

„ 88, footnote 5.—For 531 read 530.

„ 112, No. 668.—Compare *Ind. Ant.* Vol. XXXII. p. 57 ff.

„ 131, No. 813.—The date corresponds to Thursday, 12th Jannary A.D. 1161.

I.—LIST OF DATED INSCRIPTIONS

ARRANGED IN THE ORDER OF THE ŚAKA YEARS.¹

Śaka-S.	NUMBER	Śaka-S.	NUMBER
169.—† ¶ <i>W. Gaṅga</i> Arivarman, . . .	108	656.—† <i>W. Chāl.</i> Vikramāditya II., . .	41
188.—† ¶ <i>W. Gaṅga</i> Harivarman, . . .	109	672.—† (P) ¶ <i>W. Gaṅga</i> Śrīpurusha, . .	117
261.—† <i>W. Gaṅga</i> Saigoṭṭa Śivamāra II., .	120	675.—¶ <i>Rāshtrakūṭa</i> Dantidurgarāja, . .	53
261.—† ¶ <i>Bāna</i> Malladēva Nandivarman, .	668	[676].— <i>W. Chāl.</i> Kīrtivarman II., . .	43
272(P).—† ¶ <i>Son of W. Gaṅga</i> Viṣṇugōpa, .	110	679.—¶ <i>do.</i> , . . .	49
310.—† ¶ <i>W. Chāl.</i> Satyāśraya (Pulakēśin I. ?), . . .	1	679.—¶ <i>Guj. Rāshtrakūṭa</i> Kakkarāja II., .	54
366.—† ¶ <i>Chāl.</i> Vira-Nanamba, . . .	273	684.—† ¶ <i>W. Gaṅga</i> Śrīpurusha, . . .	118
388.—† ¶ <i>W. Gaṅga</i> Avinita, . . .	112	692.—¶ <i>Rāshtrakūṭa</i> Gōvindarāja II., . .	56
411*.—† ¶ <i>W. Chāl.</i> Pulakēśin I., . . .	2	698.—† ¶ <i>W. Gaṅga</i> Śrīpurusha, . . .	119
500.— <i>W. Chāl.</i> Maṅgalēśa (of the reign of Kīrtivarman I.), . . .	3	716.—¶ <i>Rāshtrakūṭa</i> Gōvindarāja III., .	61
[523-24].— <i>W. Chāl.</i> Maṅgalēśa, . . .	5	726.—¶ <i>do.</i> , . . .	62
532.—¶ Satyāśraya Dhruvarāja Indravarman of <i>Rēvatīdvīpa</i> , . . .	7	730.—¶¶ <i>do.</i> , . . .	63, 64
532(P).—† ¶ <i>W. Chāl.</i> Vikramāditya I., .	21	734.—¶ <i>Guj. Rāshtrakūṭa</i> Karkarāja, . .	65
534.—¶ <i>W. Chāl.</i> Pulakēśin II., . . .	9	735*.—¶ <i>Rāshtrakūṭa</i> Gōvindarāja III., .	66
[554].—¶ <i>E. Chāl.</i> Viṣṇuvardhana I., . .	548	735.—¶ <i>do.</i> , and Gōvindarāja of <i>Guj.</i> , .	67
556 (Ky. 3735).— <i>W. Chāl.</i> Pulakēśin II., .	10	738.—¶ <i>Guj. Rāshtrakūṭa</i> Karkarāja, . .	68
[581].—¶ <i>W. Chāl.</i> queen Vijayabhāṭṭarīkā, .	23	749.—¶ <i>Guj. Rāshtrakūṭa</i> Gōvindarāja, .	69
[586].—¶ <i>E. Chāl.</i> Viṣṇuvardhana II., . .	550	767.—¶ <i>Guj. Rāshtrakūṭa</i> Dhruvarāja I., .	70
[589].—¶ <i>do.</i> , . . .	551	765 (P).— <i>Rāshtrakūṭa</i> Amoghavarsha I. and Śīlāra Pullasakti, . . .	72
608.—† <i>W. Chāl.</i> Vinayāditya, . . .	26	775 (for 773).— <i>Rāshtrakūṭa</i> Amoghavarsha I. and Śīlāra Kapardin II., . . .	73
611.—¶ <i>do.</i> , . . .	27	782.—† <i>Rāshtrakūṭa</i> Amoghavarsha I. and <i>ch.</i> Bankēśa, . . .	74
613.—¶ <i>do.</i> , . . .	28	787.— <i>Rāshtrakūṭa</i> Amoghavarsha I., . .	1054
614.—¶ <i>do.</i> , and <i>Ālupa k.</i> Chitravāha, . .	29	788.— <i>do.</i> , . . .	75, 76
616.—¶ <i>W. Chāl.</i> Vinayāditya, . . .	30	789.—¶ <i>Guj. Rāshtrakūṭa</i> Dhruvarāja II., .	77
621.— <i>W. Chāl.</i> Vijayāditya, . . .	32	789.—¶ <i>Guj. Rāshtrakūṭa</i> Dantivarman, . .	78
622.—¶ <i>do.</i> , . . .	33	797.— <i>Raṭṭa</i> (?) Prithvirāma, . . .	79
627.—¶ <i>do.</i> , . . .	34	799.— <i>Rāshtrakūṭa</i> Amoghavarsha I. and Śīlāra Kapardin II., . . .	80
[631].— <i>do.</i> , . . .	35	809.— <i>W. Gaṅga</i> Satyavākya (Bātuga I.), .	125
635.—† ¶ <i>W. Gaṅga</i> Śivamāra I., . . .	115	810.—¶ <i>Guj. Rāshtrakūṭa</i> Kṛishnarāja, . .	81
645.—† <i>W. Chāl.</i> Vijayāditya, . . .	36	822 (for 824).— <i>Rāshtrakūṭa</i> Kṛishnarāja II., .	82
651.—† <i>do.</i> , . . .	37		

An asterisk (*) after the figures for a year denotes that the year is a current year. The Śaka year is enclosed in square brackets when it is not actually given in the inscription, but is obtained by calculation or by the reduction to a year of the Śaka era of a year which in the inscription itself is given according to another era or as a Jovian year. The sign † indicates that the inscription referred to is considered spurious; the sign ¶, that it is on copper-plates.

Here and in the Index below the figures on the right refer to the numbers of the list; 'n' after a figure, to foot-notes. The following other abbreviations are used:—*ch.*=chief; *Chāl.* or *Chāl.*=Chalukya or Chālukya; *co.*=country; *di.*=district or division; *do.*=ditto; *E.*=Eastern; *f.*=female; *Guj.*=Gujarāt; *k.*=king; *m.*=male; *min.*=minister; *ri.*=river; *s. a.*=same as; *sur.*=surname; *vi.*=village or town; *W.*=Western.

Saka-S.	NUMBER	Saka-S.	NUMBER
824.— <i>Rāshtrakūṭa</i> Kṛishṇarāja II., . . .	83	919.— <i>W. Chāl.</i> Taila II., . . .	145
831 (for 833).— <i>do.</i> , . . .	85	919.— ¶ <i>Śilāra</i> Aparājita, . . .	305
832.— ¶ <i>do.</i> , . . .	84	[921].— <i>Chōla</i> Rājārāja I., . . .	705
836.— ¶¶ <i>Rāshtrakūṭa</i> Indrarāja III., . . .	86, 87	[922].— <i>do.</i> , . . .	706
838.— <i>do.</i> , . . .	88	922.— ¶ <i>Yādava</i> Bhīllama II., . . .	328
840.— <i>Rāshtrakūṭa</i> Gōvindarāja IV., . . .	89	924.— <i>W. Chāl.</i> Irivabedaṅga Satyāśraya, . . .	146
851.— <i>do.</i> , . . .	90	928.— <i>Chōla</i> Rājārāja I., . . .	713
852.— ¶ <i>do.</i> , . . .	91	928 (for 929).— <i>W. Chāl.</i> Jayasimha, II. (?)	
855.— ¶ <i>do.</i> , . . .	92	and <i>Kādamba</i> Shashṭha I., . . .	147
856.— <i>Ch.</i> Bappuvarasa, . . .	967	930.— <i>W. Chāl.</i> Irivabedaṅga Satyāśraya, . . .	148
860.— + ¶ <i>W. Gaṅga</i> Bātuga II., . . .	127	930.— ¶ <i>do.</i> , and <i>Silāra</i> Raṭṭarāja, . . .	301
862.— ¶ <i>Rāshtrakūṭa</i> Kṛishṇarāja III., . . .	93	930 (for 931).— ¶ <i>W. Chāl.</i> Vikramāditya V., . . .	150
867.— <i>do.</i> , . . .	94	933.— ¶ <i>E. Chāl.</i> Vimalāditya, . . .	568
867.— ¶ <i>E. Chāl.</i> Ammarāja II., . . .	563	934.— <i>Chōla</i> Rājārāja I., . . .	717
[868 ?].— <i>Chōla</i> Parāntaka I., . . .	691	939.— ¶ <i>Śilāra</i> Arikēsarin, . . .	306
871.— <i>Rāshtrakūṭa</i> Kṛishṇarāja III. and		940.— <i>W. Chāl.</i> Jayasimha II.(P), . . .	151
<i>Chōla</i> Rājāditya, . . .	1056	941.— <i>W. Chāl.</i> Jayasimha II., . . .	152
872*.— <i>Rāshtrakūṭa</i> Kṛishṇarāja III. and		943*.— <i>Chōla</i> Rājendra-Chōla I., . . .	728, 731
<i>W. Gaṅga</i> Bātuga II., . . .	95	944.— <i>W. Chāl.</i> Jayasimha II., . . .	153
872*(?)— <i>W. Chāl.</i> Vikramāditya VI. and		944.— ¶ <i>E. Chāl.</i> Rājārāja I., . . .	569
<i>Sinda</i> Permādi I., . . .	224	946.— ¶ <i>W. Chāl.</i> Jayasimha II., . . .	154
872 (?)— <i>W. Chāl.</i> Jagadēkamalla II. and		946*.— ¶ <i>Yādava</i> Bhīllama III., . . .	329
<i>Sinda</i> Permādi I., . . .	234	948.— ¶ <i>Śilāra</i> Chhittarāja, . . .	307
873.— <i>Rāshtrakūṭa</i> Kṛishṇarāja III., . . .	96	950.— <i>W. Chāl.</i> Jayasimha II., . . .	155
875.— <i>Gaṅga</i> <i>ch.</i> Attimallar Kaṇṇaradēva-		951.— <i>Chōla</i> Rājendra-Chōla I., . . .	735
Prithvigaṅgaraiyar, . . .	1057	955.— <i>do.</i> , . . .	736
875.— <i>Muṇai</i> <i>ch.</i> Kulamāpikkar Irāmādēvan, . . .	1089	955.— <i>W. Chāl.</i> Jayasimha II. and <i>Sinda</i>	
876*.— <i>Rāshtrakūṭa</i> Kṛishṇarāja III., . . .	97	<i>Nāgātayarasa</i> , . . .	156
876.— <i>Muṇai</i> <i>ch.</i> Kulamāpikkerumāṇār, . . .	1090	957.— <i>W. Chāl.</i> Jayasimha II., . . .	157
880.— ¶ <i>Rāshtrakūṭa</i> Kṛishṇarāja III., . . .	98	959.— <i>Chōla</i> Rājendra-Chōla I., . . .	737
884*.— <i>do.</i> , . . .	99	[961].— <i>Chōla</i> Rājādhirāja I., . . .	738
890.— + <i>W. Gaṅga</i> Mārasimha II., . . .	129	961 (?).— <i>Hoyasa</i> Vinayāditya, . . .	383
893.— <i>Rāshtrakūṭa</i> Khoṭṭiga and <i>W. Gaṅga</i>		962.— <i>W. Chāl.</i> Jayasimha II. and <i>Raṭṭa</i>	
<i>Mārasimha</i> II., . . .	104	<i>Eṛega</i> , . . .	158
894.— ¶ <i>Rāshtrakūṭa</i> Kakkarāja II., . . .	105	[964].— <i>Chōla</i> Rājendra-Chōla I., . . .	1078
[895].— <i>W. Chāl.</i> Taila II., . . .	140	965.— <i>Chōla</i> Rājādhirāja I., . . .	739
896*.— <i>Rāshtrakūṭa</i> Kakkarāja II. and <i>W.</i>		966.— <i>W. Chāl.</i> Sōmēśvara I., . . .	159
<i>Gaṅga</i> Mārasimha II., . . .	106	[966].— <i>Chōla</i> Rājādhirāja I., . . .	740
896.— <i>W. Gaṅga</i> Mārasimha II., . . .	130	[967].— <i>W. Chāl.</i> Sōmēśvara I., . . .	160
897.— <i>W. Gaṅga</i> Pañchaladēva, . . .	132	968.— <i>do.</i> , . . .	161
899.— <i>W. Gaṅga</i> Rāchamalla II., . . .	133	[968].— <i>Chōla</i> Rājādhirāja I., . . .	741
902.— <i>W. Chāl.</i> Taila II. and <i>Raṭṭa</i>		970*.— <i>do.</i> , . . .	742
<i>Kārtavīrya</i> I., . . .	141	970.— <i>W. Chāl.</i> Sōmēśvara I., . . .	162
902.— <i>W. Chāl.</i> Taila II. and <i>Raṭṭa</i> Śānti-		970.— <i>do.</i> , and <i>Raṭṭa</i> Añka, . . .	163
<i>varman</i> , . . .	142	973 (for 974).— <i>do.</i> , and <i>Kādamba</i>	
904.— <i>Rāshtrakūṭa</i> Indrarāja IV., . . .	107	<i>Jayakēśin</i> I., . . .	164
904.— <i>W. Chāl.</i> Taila II., . . .	143	975.— <i>W. Chāl.</i> Sōmēśvara I., . . .	165
911 (for 912).— <i>do.</i> , and <i>Sinda</i> Pulikāla, . . .	144	975.— <i>Chōla</i> Rājādhirāja I., . . .	743
[913].— <i>Chōla</i> Rājārāja I., . . .	696	[975 ?].— ¶ <i>E. Chāl.</i> Rājārāja I., . . .	570
[918].— <i>do.</i> , . . .	1077	976.— <i>W. Chāl.</i> Sōmēśvara I., . . .	166, 167

Chā.S.	NUMBER
7.— <i>W. Chāl. Vikramāditya VI. and</i>	
<i>Kādamba Harikēśarin,</i>	168
[7].— <i>Chōla Rājēndradēva,</i>	745
<i>do.,</i>	747
[8].— <i>Śīlāhāra Mārasimha,</i>	315
[9].— <i>Śīlāra Māmvaṇirāja,</i>	308
[10].— <i>W. Chāl. Sōmēśvara I.,</i>	169, 170
[11].— <i>Chōla Rājēndradēva,</i>	751
[12].— <i>W. Chāl. Vishṇuvardhana Vijayāditya,</i>	171
[13].— <i>W. Gaṅga Gaṅgarasa (?) and</i>	
<i>Hoysaḷa Vishṇuvardhana (?),</i>	384
[14].— <i>W. Chāl. Sōmēśvara I. and Vishṇu-</i>	
<i>vardhana Vijayāditya,</i>	172
[15].— <i>Chōla Virarājēndra I.,</i>	754
[16].— <i>W. Chāl. Sōmēśvara I. and Kādamba</i>	
<i>Kirtivarman II.,</i>	173
[17].— <i>Yādava Sēupachandra II. and Maurya</i>	
<i>Gōvindarāja,</i>	330
[18].— <i>Yādava Sēupachandra II.,</i>	331
[19].— <i>W. Chāl. Sōmēśvara II.,</i>	174, 175
[20].— <i>W. Chāl. Jayasimha III.,</i>	176
[21].— <i>Chōla Kulōttuṅga-Chōla I.,</i>	760
[22].— <i>W. Chāl. Sōmēśvara II.,</i>	177
[23].— <i>do.,</i>	178
[24].— <i>do., and W. Gaṅga Udayāditya,</i>	179
[25].— <i>Āchārya Śrinandi-paṇḍita,</i>	183
[26].— <i>Chōla Kulōttuṅga-Chōla I.,</i>	762
[27].— <i>W. Chāl. Vikramāditya VI. and</i>	
<i>Jayasimha III.,</i>	184
[28].— <i>Chāl. Vikramāditya VI.,</i>	185, 186, 187
[29].— <i>E. Chāl. Vira-Chōla,</i>	572
[30].— <i>Chāl. Vikram-</i>	
<i>āditya VI. and Jayasimha III.,</i>	188
[31].— <i>Chāl. Vikram-</i>	
<i>āditya VI., Sinda Muñja, and Raṭṭa</i>	
<i>Kannakaira II.,</i>	189
[32].— <i>W. Chāl. Vikramāditya</i>	
<i>VI.,</i>	190
[33].— <i>E. Chāl. Chōdaganga Rājārāja,</i>	571
[34].— <i>Chōla Kulōttuṅga-Chōla I.,</i>	1085
[35].— <i>W. Chāl. Vikramāditya VI.,</i>	191
[36].— <i>do., and Raṭṭa Kārtavīrya II.,</i>	192
[37].— <i>Chāl. Vikram-</i>	
<i>āditya VI. and Jayakarṇa,</i>	193
[38].— <i>W. Chāl. Vikram-</i>	
<i>āditya VI.,</i>	194, 195
[39].— <i>do.,</i>	196
[40].— <i>Hoysaḷa inscription,</i>	197
[41].— <i>Śīlāra Anantapāla,</i>	309

Śaka-S.	NUMBER
[1017 (Chā. Vi. 19 for 20 ?)].— <i>W. Chāl.</i>	
<i>Vikramāditya VI.,</i>	198
[1018 (Chā. Vi. 21)].— <i>Private inscription,</i>	199
[1018 (Chā. Vi. 21)].— <i>W. Chāl. Vikramāditya</i>	
<i>VI.,</i>	200
[1018 (Chā. Vi. 21)].— <i>do., and (?) Raṭṭa</i>	
<i>Sēna II.,</i>	201
[1020 (Chā. Vi. 22 for 23)].— <i>W. Chāl.</i>	
<i>Vikramāditya VI.,</i>	202
[1021 (Chā. Vi. 24)].— <i>do.,</i>	203
[1024 (Chā. Vi. 27)].— <i>do.,</i>	204
[1024 (Chā. Vi. 27)].— <i>W. Chāl. Vikram-</i>	
<i>āditya VI. (or W. Gaṅga Udayāditya),</i>	205
[1024 (Chā. Vi. 27)].— <i>W. Chāl. Vikram-</i>	
<i>āditya VI.,</i>	206
[1025 (Chā. Vi. 28)].— <i>do.,</i>	207
1025.— <i>Hoysaḷa Ballāla I.,</i>	385
[1029 (Chā. Vi. 32)].— <i>W. Chāl. Vikram-</i>	
<i>āditya VI.,</i>	208
[1029 (Chā. Vi. 32)].— <i>Memorial tablet,</i>	209
1030 (for 1028).— <i>Chōla Kulōttuṅga-Chōla I.,</i>	779
[1030 (Chā. Vi. 33)].— <i>W. Chāl. Vikramāditya</i>	
<i>VI. and Kādamba Tailapa II.,</i>	210
[1030 (Chā. Vi. 33)].— <i>W. Chāl. Vikramāditya</i>	
<i>VI.,</i>	211
1032*[and 1033*].— <i>Śīlāhāra Gaṇḍarāditya,</i>	317
[1034 (Chā. Vi. 37)].— <i>W. Chāl. Vikram-</i>	
<i>āditya VI. and Paṇḍya ch. Kāmadēva,</i>	212
[1034 (Chā. Vi. 38 for 37 ?)].— <i>W. Chāl.</i>	
<i>Vikramāditya VI.,</i>	213
[1035 (Chā. Vi. 38)].— <i>do.,</i>	214
1035.— <i>Chōla Kulōttuṅga-Chōla I.,</i>	783
[1035].— <i>do.,</i>	784
[1036 (Chā. Vi. 39)].— <i>W. Chāl. Vikram-</i>	
<i>āditya VI.,</i>	216
[1036].— <i>Chōla Kulōttuṅga-Chōla I.,</i>	785
1036.— <i>do.,</i>	786
1037 (for 1035).— <i>Son of Hoysaḷa min.</i>	
<i>Gaṅgarāja,</i>	386
1037.— <i>Jaina Mēghachandra-traividya-dēva,</i>	387
1037.— <i>Chōla Kulōttuṅga-Chōla I.,</i>	787
1039.— <i>Hoysaḷa Vishṇuvardhana,</i>	388, 389
[1039].— <i>Chōla Kulōttuṅga-Chōla I.,</i>	789, 790, 791
[1040 (Chā. Vi. 43)].— <i>Private inscription,</i>	217
1040.— <i>Chōla Kulōttuṅga-Chōla I.,</i>	792
1040.— <i>Śīlāhāra Gaṇḍarāditya,</i>	318
1041*.— <i>Disciple of Divākaranandi-siddhānta-</i>	
<i>dēva,</i>	968
1042*.— <i>Daughter of Hoysaḷa min. Gaṅga-</i>	
<i>rāja,</i>	390

Śaka-S.	NUMBER	Śaka-S.	NUMBER
1013*.— <i>Mother of Hoysala min</i> Gaṅgarāja, . . .	392	[1069].— <i>W. Chāl. Jagadēkamalla II.</i> , . . .	235
[1043 (Chā. Vi. 46)].— <i>W. Chāl. Vikramāditya</i>		[1069].— <i>do., and ch. Vira-Pāṇḍyadēva</i> , . . .	236
VI. <i>and ch. Tribhuvanamalla Pāṇḍyadēva</i> , . . .	219	[1071].— <i>do., and ch. Jagaddēva</i> , . . .	237
1044*.— <i>Wife of Hoysala min.</i> Gaṅgarāja, . . .	393	1073*.— <i>Śilāhāra Vijayāditya</i> , . . .	323
[1044].— <i>Chōla Vikrama-Chōla</i> , . . .	794, 797	1075.— <i>Nikumbha ch. Indrarāja</i> , . . .	333
[1044 (Chā. Vi. 45 for 47) P].— <i>W. Chāl.</i>		1076.— <i>W. Chāl. Taila III.</i> , . . .	239
Vikramāditya VI. <i>and Sinda Ācha II.</i> , . . .	218	1076.— <i>Śilāra Haripāla</i> , . . .	310
1045.— <i>Tēridāla ch. Gonka</i> , . . .	220	[1077].— <i>W. Chāl. Taila III. and</i>	
[1045].— <i>Chōla Vikrama-Chōla</i> , . . .	798, 799	<i>Kaḷachurya Bijjana</i> , . . .	240
1045.— <i>Queen of Hoysala Vishnuvardhana</i> , . . .	396, 397	1078.— <i>Śilāra Mallikārjuna</i> , . . .	311
1045.— <i>Jaina Śubhachandra-siddhāntadēva</i>		1079.— <i>Kaḷachurya Bijjana</i> , . . .	275
<i>and min. Gaṅgarāja</i> , . . .	398	1079.— <i>E. Chāl. Vijayāditya III. of</i>	
1045 (?).— <i>W. Chāl. Jagadēkamalla II. (P)</i>		<i>Piṭhāpuram</i> , . . .	575
<i>and ch. Vijaya-Pāṇḍyadēva</i> , . . .	225	1080.— <i>Kādambas Śivachitta Permādi and</i>	
1047.— <i>W. Chāl. Vikramāditya VI.</i> , . . .	221	<i>Vijayāditya II.</i> , . . .	241
[1047-48 (Kollam 301)].— <i>Vira-Kēraḷavarman</i>		[1080].— <i>Kaḷachurya Bijjana</i> , . . .	276
<i>of Vēṇāḍu</i> , . . .	943	1080.— <i>do.</i> , . . .	277
1049.— <i>Chōla Vikrama-Chōla</i> , . . .	800	1081.— <i>Hoysala Narasimha I. and min.</i>	
[1050].— <i>do.</i> , . . .	802, 803, 804	<i>Huḷla</i> , . . .	409
[1050].— <i>W. Chāl. Sōmēśvara III. and</i>		[1081-82 (Kollam 335)].— <i>Private inscription</i> , . . .	945
<i>Kādamba Tailapa II.</i> , . . .	227	[1082, 1085, and 1094].— <i>Kādamba Śivachitta</i>	
1050.— <i>Jaina Mallishēpa Maladhāridēva</i> , . . .	969	<i>Permādi</i> , . . .	242
1051*.— <i>W. Chāl. Sōmēśvara III. and</i>		[1083 (Kollam 336)].— <i>Vira-Ravivarman of</i>	
<i>Kaḷachurya Permādi</i> , . . .	226	<i>Vēṇāḍu</i> , . . .	946
[1052].— <i>W. Chāl. Sōmēśvara III.</i> , . . .	228	[1083].— <i>Kaḷachurya Bijjala</i> , . . .	278, 279
1053.— <i>Queen of Hoysala Vishnuvardhana</i> , . . .	400	1084.— <i>Kākatya Rudradēva</i> , . . .	584
1054 (for 1057).— <i>Chōla Vikrama-Chōla</i> , . . .	808	1084 (for 1085).— <i>Sinda Chāvunḍa II.</i> , . . .	243
[1056].— <i>do.</i> , . . .	807	1085.— <i>Jaina Dēvakīrti-pāṇḍitadēva</i> , . . .	412
1056 (for 1065).— ¶ <i>E. Chāl. Kulōttunga-</i>		[1087].— <i>Ch. Vijaya-Pāṇḍyadēva</i> , . . .	244
<i>Chōla II.</i> , . . .	574	[1087].— <i>Kaḷachurya Bijjala</i> , . . .	280
1058*.— <i>Śilāhāra Gaṇḍarāditya</i> , . . .	319	[1088-89 (Kollam 342)].— <i>Vira-Ravivarman</i>	
1059 (for 1051 P).— <i>Tribhuvanamalla</i>		<i>of Vēṇāḍu (P)</i> , . . .	947
<i>Chaladānkarāva Hoysalasetṭi</i> , . . .	970	[1090].— <i>Kaḷachuryas Bijjana and Sōvidēva</i> , . . .	285
1060*.— <i>Hoysala Vishnuvardhana</i> , . . .	401	[1091 (Chā. Vi. 94)].— <i>Sindas Chāvunḍa II.</i> , . . .	
[1061].— <i>W. Chāl. Jagadēkamalla II.</i> , . . .	229	<i>Bijjala and Vikrama</i> , . . .	247
[1061].— <i>W. Chāl. Sōmēśvara III. (P)</i> , . . .	230	1091.— <i>Ch. Vijaya-Pāṇḍyadēva</i> , . . .	248
[1061 P].— <i>Ch. Singimayya</i> , . . .	403	[1091 and 1093 (Ky. 4270 and 4272)].—	
[1061 P].— <i>Ch. Baladēva</i> , . . .	404	<i>Kādambas Śivachitta Paramardin and</i>	
1063 (for 1064).— <i>Yādava ch. Sēunadēva</i> , . . .	332	<i>Vishnuchitta</i> , . . .	249
[1064].— <i>W. Chāl. Sōmēśvara III. (P) and</i>		1093* and 1095*.— <i>Ch. Vijaya-Pāṇḍyadēva</i> , . . .	250
<i>ch. Vira-Pāṇḍyadēva</i> , . . .	231	[1093].— <i>Kaḷachurya Sōvidēva</i> , . . .	286
[1064].— <i>W. Chāl. Jagadēkamalla II.</i> , . . .	232	1093.— <i>Koṇḍapaḍmaṭi ch. Buddharāja</i> , . . .	581
1065*.— <i>Śilāhāra Vijayāditya</i> , . . .	321	[1094 (Kollam 348 for 347 P)].— <i>Vira-</i>	
1065* and 1066*.— <i>do.</i> , . . .	322	<i>Uдайyamārtāṇḍavarman of Vēṇāḍu</i> , . . .	948
[1065-66 (Kollam 319)].— <i>Vira-Kēraḷavarman</i>		[1095].— <i>Kaḷachurya Sōvidēva</i> , . . .	287
<i>of Vēṇāḍu</i> , . . .	944	1095 and 1103.— <i>W. Chāl. Sōmēśvara IV. (P)</i>	
[1066].— <i>W. Chāl. Jagadēkamalla II. and</i>		<i>and (Sinda) ch. Irmaḍi-Rāchamalla</i> , . . .	253
<i>Sinda Permādi I.</i> , . . .	233	1096.— ¶ <i>Kaḷachurya Sōvidēva</i> , . . .	288, 289
1068*.— <i>Jaina Prabhāchandra-siddhāntadēva</i> , . . .	408	[1096 (Ky. 4275)].— <i>Kādamba Śivachitta</i>	
		<i>Permādi</i> , . . .	254

Śaka-S.	NUMBER	Śaka-S.	NUMBER
1099*.— <i>Jaina</i> Nayakīrtidēva, . . .	414	1121.— <i>Hoysala</i> Ballāla II., . . .	427
[1100].— <i>Kalachurya</i> Saṅkama, . . .	291	1121.— <i>Maiduna-Chaudayya</i> , . . .	971
1101*.— <i>Śilāhāra</i> Bhōjadēva II., . . .	324	[1121 (Ky. 430)].— <i>Kādamba</i> Jayakēsin III., . . .	261
[1101].— <i>Kalachurya</i> Saṅkama, . . .	292, 293	[1121].— <i>Chōla</i> Kulōttuṅga-Chōla III., . . .	831, 832
[1102].— <i>Chōla</i> Kulōttuṅga-Chōla III., . . .	814	1123.— <i>Nāṭavāḍi</i> ch. Rudradēvarāja, . . .	591
[1102].— <i>Kalachurya</i> Āhavamalla, . . .	295, 296	[1123 (Ky. 4302)].— <i>Kādamba</i> Jayakēsin III., . . .	262
[1103].— do., . . .	297	1124*.— <i>Raṭṭa</i> Kārtavīrya IV., . . .	264
1103.— do., and <i>Gutta</i> Jōyidēva I., . . .	298	1124.— <i>E. Chōl.</i> Mallapadēva III. of <i>Piṭhāpuram</i> , . . .	576
1104*.— <i>Private</i> inscription, . . .	256	[1124].— <i>Hoysala</i> Ballāla II., . . .	428, 429
1104*.— <i>Hoysala</i> Ballāla II., . . .	418	[1125].— <i>Pāṇḍya</i> Jaṭavarman Kulāśekhara, . . .	889
1104.— <i>Amarāvati</i> ch. Kēta II., . . .	590	1127*.— <i>Raṭṭas</i> Kārtavīrya IV. and <i>Mallikārjuna</i> , . . .	265
[1105].— <i>Kalachurya</i> Āhavamalla, . . .	299	1127.— <i>Telugu-Chōla</i> Tammusiddhi, . . .	880
1105.— ¶ <i>Kalachurya</i> Singhapa, . . .	300	[1127].— <i>Hoysala</i> Ballāla II., . . .	430
1106.— <i>W. Chōl.</i> Sōmēśvara IV., . . .	257	[1127].— <i>Chōla</i> Kulōttuṅga-Chōla III., . . .	837
[1106].— <i>Chōla</i> Kulōttuṅga-Chōla III., . . .	816	[1128].— do., . . .	839
1107.— <i>Śilāra</i> Aparāditya, . . .	312	1128 (for 1129).— <i>Dēvagiri-Yādava</i> Singhapa and <i>Nikumbha</i> ch. Sōidēva, . . .	337
[1107].— <i>Chōla</i> Kulōttuṅga-Chōla III., . . .	817	1129.— <i>Telugu-Chōla</i> Tammusiddhi, . . .	881, 882, 883
1108.— <i>Velanāṇḍu</i> ch. Prithivīśvara, . . .	582	[1129].— <i>Hoysala</i> Ballāla II., . . .	431
1109*.— <i>Śilāra</i> Aparāditya, . . .	313	1130 (for 1131).— <i>Sinda</i> (P) Sōmēśvara, . . .	972
1109.— <i>Ch.</i> Bhāyidēva, . . .	258	[1130-31 (Kollam 384)].— <i>Vira-Rāma</i> [Kēraja- varman] of <i>Vēṇāḍu</i> , . . .	951
1109.— <i>Śilāhāra</i> Bhōjadēva II., . . .	325	1131*.— ¶ <i>Raṭṭas</i> Kārtavīrya IV. and <i>Mallikārjuna</i> , . . .	266
1110*.— <i>Toṇṇagale</i> ch. Barma, . . .	259	[1133].— <i>Chōla</i> Kulōttuṅga-Chōla III., . . .	840
1110*.— <i>Gutta</i> Vira-Vikramāditya II., . . .	298	1135*.— <i>Dēvagiri-Yādava</i> Singhapa, . . .	338
1111.— <i>W. Chōl.</i> Sōmēśvara IV. and <i>Kādamba</i> <i>Kāmadēva</i> , . . .	280	1135.— <i>General</i> Jāya of <i>Kākatya</i> Gaṇapati, . . .	585
[1111].— <i>Chōla</i> Kulōttuṅga-Chōla III., . . .	821	1136*.— <i>Dēvagiri-Yādava</i> Singhapa, . . .	339
1112, 1114 [and 1115].— <i>Śilāhāra</i> Bhōjadēva II., . . .	326	1136*.— <i>Gutta</i> Vira-Vikramāditya II., . . .	340
1113.— <i>Dēvagiri-Yādava</i> Bhīllama, . . .	334	[1136].— ¶ <i>Pāṇḍya</i> Jaṭavarman Kulāśekhara, . . .	890
1113.— ¶ <i>Śilāhāra</i> Bhōjadēva II., . . .	327	[1137 (Kollam 389 for 390)].— <i>Vira-Rāma</i> <i>Kērajarman</i> of <i>Vēṇāḍu</i> , . . .	952
1113.— <i>Gutta</i> Vira-Vikramāditya II., . . .	335	[1137].— <i>Chōla</i> Kulōttuṅga-Chōla III., . . .	842
1113 (?).— <i>Hoysala</i> Ballāla II., . . .	418	1137.— <i>Dēvagiri-Yādava</i> Singhapa, . . .	341
[1113].— <i>Chōla</i> Kulōttuṅga-Chōla III., . . .	822	[1138 (Ky. 4317, Kollam 392)].— <i>Private</i> (?) <i>inscription</i> , . . .	953
1114.— <i>Hoysala</i> Ballāla II., . . .	419, 420	1140.— <i>Dēvagiri-Yādava</i> Singhapa, . . .	342
1114 (for 1115).— do., . . .	421	1141*.— <i>Raṭṭa</i> Kārtavīrya IV., . . .	267
1114-15 (Kollam 368).— <i>Vira-Kērajarman</i> (?) of <i>Vēṇāḍu</i> , . . .	949	[1142].— <i>Chōla</i> Rājārāja III., . . .	843
[1116].— <i>Chōla</i> Kulōttuṅga-Chōla III., . . .	823, 824	[1142-43 (Kollam 396)].— <i>Private</i> (?) in- <i>scription</i> , . . .	954
1117*.— <i>Hoysala</i> Ballāla II., . . .	422	1144.— <i>Astrologer</i> Anantadēva of <i>Dēvagiri-</i> <i>Yādava</i> Singhapa, . . .	343
[1117].— <i>Chōla</i> Kulōttuṅga-Chōla III., . . .	825	[1144].— <i>Chōla</i> Rājārāja III., . . .	844
1117.— <i>Kōṇamāṇḍala</i> chiefs Malhidēva and <i>Manma-Satya</i> II., . . .	583	1145*.— <i>Dēvagiri-Yādava</i> Singhapa, . . .	344
[1117-18 (Kollam 371)].— <i>Vira-Rāmavarman</i> of <i>Vēṇāḍu</i> , . . .	950	[1145].— <i>Pāṇḍya</i> Māravarman <i>Sundara-</i> <i>Pāṇḍya</i> I., . . .	891
1118*.— <i>Hoysala</i> Ballāla II., . . .	423		
1118].— do., . . .	426		
1118].— do., and <i>Kādamba</i> Kāmadēva, . . .	424		
1118].— <i>Chōla</i> Kulōttuṅga-Chōla III., . . .	826, 827		
1119].— do., . . .	828		
1119.— do., . . .	829		

Śaka-S.	NUMBER	Śaka-S.	NUMBER
1145.— <i>Dēvagiri-Yādava</i> Singhana, . . .	345	[1175].— <i>Pāṇḍya</i> Jaṭavarman Sundara-	
1145.— <i>Hoysaḷa</i> Narasimha II., . . .	434	Pāṇḍya I.,	900, 901, 902
[1147].— <i>Pāṇḍya</i> Māṇavarman Sundara-		[1176].— ¶ <i>Hoysaḷa</i> Narasimha III., . . .	439
Pāṇḍya I.,	893	1177.— <i>do.</i> ,	440
1148*.— <i>Dēvagiri-Yādava</i> Singhana (?), . . .	346	[1178].— <i>Telugu-Chōḷa</i> Vijaya-Gaṇḍagopāla, .	885
[1148].— <i>Chōḷa</i> Rājārāja III.,	845	[1178].— <i>Hoysaḷa</i> Vīra-Rāmanātha, . . .	441
1151*.— <i>Raṭṭa</i> Lakṣmidēva II.,	268	[1179].— <i>Pāṇḍya</i> Jaṭavarman Sundara-	
1153.— <i>Kākatīya</i> Gaṇapati,	586	Pāṇḍya I.,	903
[1153].— <i>Hoysaḷa</i> Narasimha II.,	435	1180.— Rājagambhīra Śambavarāyaṇ, . . .	866
[1154].— <i>Chōḷa</i> Rājārāja III.,	848, 849	1181.— <i>Śīlāhara</i> Sōmēśvara,	314
[1155].— <i>do.</i> ,	850, 851, 852	[1181].— <i>Dēvagiri-Yādava</i> Kanhara, . . .	861
1156.— <i>Dēvagiri-Yādava</i> Singhana,	347	[1181].— <i>Pāṇḍya</i> Jaṭavarman Sundara-Pāṇḍya	
1156.— <i>Daughter of Nātavādī ch.</i> Rudra-		I.,	904, 905
dēva,	592	[1181].— <i>Pāṇḍya</i> Vīra-Pāṇḍya,	906
[1156].— <i>Chōḷa</i> Rājārāja III.,	853	[1182].— <i>Pāṇḍya</i> Jaṭavarman Sundara-Pāṇḍya	
[1156].— <i>Pāṇḍya</i> Māṇavarman Sundara-		I.,	907
Pāṇḍya I.,	895, 896	1182.— ¶ <i>Chōḷ.</i> Kāṇvadēvarāya,	271
1156.— <i>Image inscription</i> ,	973	1183.— <i>Dēvagiri-Yādava</i> Mahādēva,	362
[1156-57 (Kollam 410)].— Vīra-Ravi Kēṣava-		[1183].— <i>Pāṇḍya</i> Jaṭavarman Sundara-	
man of <i>Vēṇāḍu</i> ,	955	Pāṇḍya I.,	908
1157.— <i>Dēvagiri-Yādava</i> Singhana,	348	[1183].— <i>Hoysaḷa</i> Vīra-Rāmanātha,	442
1157.— <i>Kākatīya</i> general Jāya,	587	1184*.— ¶ <i>Hoysaḷa</i> Narasimha III.,	443
1158.— <i>Dēvagiri-Yādava</i> Singhana,	349	[1184].— <i>Dēvagiri-Yādava</i> Mahādēva and	
[1159].— <i>Chōḷa</i> Rājārāja III.,	855	<i>Gutta</i> Gutta III.,	363
1160*.— ¶ <i>Dēvagiri-Yādava</i> Singhana, 350, 351		1185*.— <i>do.</i> <i>do.</i> ,	364
1160*.— <i>Chōḷa</i> Rājārāja III.,	856	[1185].— <i>do.</i> ,	365
[1160].— <i>do.</i> ,	857, 858, 859	1187.— <i>Telugu-Chōḷa</i> Vijaya-Gaṇḍagopāla, 886, 887	
1161.— <i>do.</i> ,	860	1187.— <i>Dēvagiri-Yādava</i> Mahādēva,	366
1162.— <i>Dēvagiri-Yādava</i> Singhana,	352	[1188].— <i>Chōḷa</i> Rājendra-Chōḷa III.,	867
[1164].— <i>do.</i> ,	354	1188.— <i>Kēraḷa k.</i> Ravivarman,	939, 940
1165.— <i>Chōḷa</i> Rājārāja III.,	862	[1189].— <i>Chōḷa</i> Rājendra-Chōḷa III.,	868
[1168].— <i>Dēvagiri-Yādava</i> Singhana,	355	1189.— <i>Dēvagiri-Yādava</i> Mahādēva,	367
[1171].— <i>Chōḷa</i> Rājendra-Chōḷa III.,	863	[1189].— <i>Pāṇḍya</i> Vīra-Pāṇḍya,	910
[1171].— <i>Pāṇḍya</i> Māṇavarman Sundara-		1189.— <i>Jaina</i> Śrinandi-bhaṭṭārakadēva, . . .	974
Pāṇḍya II.,	897	1190.— <i>Hoysaḷa</i> Narasimha III. (?),	444
1171.— ¶ <i>Dēvagiri-Yādava</i> Kanhara, 357, 358		1191.— ¶ <i>Oḍḍavādī ch.</i> Arjuna,	600
1172*.— <i>do.</i> ,	356	[1191].— <i>Hoysaḷa</i> Vīra-Rāmanātha,	445
1172*.— <i>Kākatīya</i> Gaṇapati,	588	1191 (for 1195 ?).— <i>Hoysaḷa</i> Narasimha III., .	446
[1172*].— Gaṇapāmbā, <i>daughter of do.</i> , . . .	589	1192* [and 1198].— <i>do.</i> ,	447
[1173 (Ky. 4351)].— ¶ <i>Kādamba</i> Śivachitta		[1192].— <i>Hoysaḷa</i> Vīra-Rāmanātha,	448
Shashṭha II.,	269	[1193].— <i>Dēvagiri-Yādava</i> Mahādēva (?), . . .	368
[1172].— <i>Pāṇḍya</i> Māṇavarman Sundara-		[1193].— <i>Hoysaḷa</i> Vīra-Rāmanātha,	449
Pāṇḍya II.,	898	1193.— ¶ <i>Dēvagiri-Yādava</i> Rāmachandra, . . .	369
[1173].— <i>do.</i> ,	899	1194.— ¶ <i>do.</i> ,	370, 371
1174*.— <i>Dēvagiri-Yādava</i> Kanhara,	359	1195.— <i>E. Chōḷ.</i> Vijayāditya II. of	
[1174 (Kollam 427)].— Vīra-Padmanābha		<i>Śrīkūrmam</i> ,	577
Mārtāṇḍavarman of <i>Vēṇāḍu</i> ,	956	1197*.— <i>Jaina</i> Māghanandi-bhaṭṭārakadēva, .	975
[1174].— <i>Chōḷa</i> Rājendra-Chōḷa III.,	864	1199*.— <i>Dēvagiri-Yādava</i> Rāmachandra, . . .	372
1175*.— ¶ <i>Hoysaḷa</i> Sōmēśvara,	436	1199.— <i>do.</i> ,	373
1175.— ¶ <i>Dēvagiri-Yādava</i> Kanhara,	360	1199.— <i>E. Chōḷ.</i> Purushōttama of <i>Śrīkūrmam</i> , 573	

Saka-S.	NUMBER	Saka-S.	NUMBER
[1199].— <i>Pāṇḍya</i> Māvarman Kulasēkhara I.,	911	[1274].— <i>Pāṇḍya</i> Māvarman Parākrama-	
1200.— <i>Disciple of Jaina</i> Udayachandradēva,	976	<i>Pāṇḍya</i> ,	926
1200.— <i>Hoysala</i> Narasimha III.,	450	1276*.— <i>¶</i> Bukkarāya I. of <i>Vijayanagara</i> , .	455
1201.— <i>Disciple of Jaina</i> Padumasina-		1277.—	456
bhaṭṭārakadēva (?),	977	1278.—	457
1203 (for 1201 ?) [and 1210].— <i>Private</i>		1278.— <i>¶</i> Saṅgama II. of <i>Vijayanagara</i> , .	459
<i>inscription</i> ,	978	1286 (for 1287).—Kampapa II. of <i>Vijaya-</i>	
[1203].— <i>Pāṇḍya</i> Jaṭavarman Sundara-Pāṇḍya		<i>nagara</i> ,	460
II.,	912	[1290].—	462
1203.—Naraharitirtha, governor of <i>Kaliṅga</i> (?),	979	1290.—Bukkarāya I. (?) of <i>Vijayanagara</i> , .	461
[1204].— <i>Dēvagiri-Yādava</i> Rāmachandra, .	374	1293.—General Goppapāya of Kampapa II.	
1205*.— <i>Disciple of Jaina</i> Nēmichandra-		of <i>Vijayanagara</i> ,	463
paṇḍitadēva,	980	1293.— <i>Pāṇḍya</i> Jaṭavarman Parākrama-	
[1205].— <i>Dēvagiri-Yādava</i> Rāmachandra, .	375	<i>Pāṇḍya</i> ,	927
[1206].—	376, 377	1295*.— <i>Jaina</i> Vardhamānasvāmin (?), .	982
[1207].— <i>Pāṇḍya</i> Jaṭavarman Sundara-		1296.—Jannapa-Uḍaiyar, son of Kampapa	
<i>Pāṇḍya</i> II.,	913	II. of <i>Vijayanagara</i> ,	464
[1208].— <i>Dēvagiri-Yādava</i> Rāmachandra, .	378	1296.— <i>¶</i> Redḍi Anna-Vēma of <i>Koṇḍaviḍu</i> , .	593
1208.— <i>Hoysala</i> Narasimha III.,	451	1296.— <i>Kēraḷa</i> (?) ch. Sarvaṅganātha, . .	941
[1209].— <i>Pāṇḍya</i> Jaṭavarman Sundara-		1300 (for 1301).— <i>¶</i> Redḍi Anna-Vēma of	
<i>Pāṇḍya</i> II.,	914	<i>Koṇḍaviḍu</i> ,	594
[1211].—	915, 916	1301.— <i>¶</i> Harihara II. of <i>Vijayanagara</i> , 465, 466	
1212*.— <i>¶</i> <i>Dēvagiri-Yādava</i> Rāmachandra, .	379	1304.— <i>¶</i>	467
[1212].— <i>Pāṇḍya</i> Jaṭavarman Sundara-		[1304].— <i>Min.</i> Irugappa,	1062
<i>Pāṇḍya</i> II.,	917, 918	1305 (for 1306).— <i>¶</i> Virūpāksha I. of <i>Vijaya-</i>	
[1215].— <i>Pāṇḍya</i> Māvarman Kulasēkhara I.,	919	<i>nagara</i> ,	468
[1216].—	920	1307.—Harihara II. of <i>Vijayanagara</i> , . .	469
1219*.— <i>Dēvagiri-Yādava</i> Rāmachandra, .	380	1309*.— <i>¶</i>	470
1222.—	381	[1309].—General Irugappa,	1063
1227.—	382	1312.— <i>Kēraḷa</i> k. Mārtāṇḍavarman, . .	942
[1229].— <i>Pāṇḍya</i> Māvarman Kulasēkhara I.,	921	1313.— <i>¶</i> Harihara II. of <i>Vijayanagara</i> , .	471
1231.— <i>E. Chāl.</i> Viśvannātha of <i>Śrīkūṣṭam</i> , 579		1313.— <i>Redḍi</i> Kāṭaya-Vēma,	595
[1232].— <i>Hoysala</i> Ballāla III.,	453	1315.—Harihara II. of <i>Vijayanagara</i> , .	472
1235.— <i>Jaina</i> Śubhachandramuni,	981	1317.— <i>¶</i>	473
1236.— <i>Chōḷa</i> Vira-Champa,	869, 870	1317 (for 1318).— <i>¶</i>	474
[1237-38 (Kollam 491)].—Vira-Udaiyamār-		1320*.— <i>Jaina</i> Purupāṇḍita,	983
tāṇḍavarman of <i>Vēṇāḍu</i> ,	957	1321.— <i>¶</i> Harihara II. of <i>Vijayanagara</i> , .	475
1238.— <i>Kākaṭiya</i> Pratāparudra,	1066	[1325 (Kollam 578)].— <i>Kēraḷa</i> k. Vira-Kēraḷa	
[1239].— <i>Pāṇḍya</i> Māvarman Kulasēkhara II.,	922	Mārtāṇḍavarman,	958
1240.— <i>E. Chāl.</i> Purushōttama of <i>Śrīkūṣṭam</i> , 580		1325 [and 1327].—Bukkarāya II. of <i>Vijaya-</i>	
[1240].— <i>Pāṇḍya</i> Māvarman Kulasēkhara II.,	923	<i>nagara</i> ,	470
[1241].— <i>¶</i> Vira-Bāghava-Chakravartin (of		1328.— <i>¶</i> Dēvarāya I. of <i>Vijayanagara</i> , .	480
<i>Kēraḷa</i>),	965	1328 (for 1338).— <i>Subordinate of Redḍi</i>	
[1243].— <i>Pāṇḍya</i> Māvarman Kulasēkhara II.,	924	Kāṭaya-Vēma,	598
1259.—(for 1260 ?).— <i>¶</i> Nāmaya-Nāyaka of		1331.— <i>Disciple of Jaina</i> Chandrakirti, .	984
<i>Piṭṭāpurē</i> ,	601	1332.—Dēvarāya I. of <i>Vijayanagara</i> , .	481
[1261].—Venṅumapkoṇḍa Śambavarāya, .	871	1333.— <i>¶</i> Redḍi Kāṭaya-Vēma of <i>Rājya-</i>	
1261 (for 1262).—Harihara I. of <i>Vijayanagara</i> , 454		<i>mahēndranagara</i> ,	596
1262.— <i>Pāṇḍya</i> Māvarman Parākrama-		1334*.— <i>Son of Dēvarāya I. of Vijayanagara</i> , 483	
<i>Pāṇḍya</i> ,	925	1336.— <i>Subordinate of Redḍi</i> Kāṭaya-Vēma, .	597

Śaka-S.	NUMBER	Śaka-S.	NUMBER
1338.—¶ Vijaya of Vijayanagara, . . .	484	1450 and 1451.—Kṛṣṇarāya of Vijaya-	
1344.—do., . . .	485	nagara, . . .	513
[1344].—General Irugapa, . . .	486	1452.—Achyutarāya of Vijayanagara, . . .	514
1346.—¶ Dévarāya II. of Vijayanagara, 487, 488		1453.—do., . . .	515
1347.—do., . . .	489	1455*.—do., . . .	516
1348.—do., . . .	490	1459.—Pāṇḍya Jaṭilavarman . . . Śrīvallabha-	
1352.—¶ Redḍi Allaya-Dodda of Rājamahēn-		dēva, . . .	933
dranagara, . . .	599	1459 (for 1460).—Private inscription, . . .	990
1353*.—¶ Dévarāya II. of Vijayanagara, 491, 492		1460.—Achyutarāya of Vijayanagara, . . .	517
1353.—Vīra-Pāṇḍya, son of Bhairava, . . .	985	1461.—do., . . .	518
1355*.—Jaina Śrutamuni, . . .	986	1462.—¶ do., . . .	519
[1355].—Dévarāya II. of Vijayanagara, . . .	493	1463*.—do., . . .	520
[1356].—do., . . .	494	[1465].—Sadāśivarāya of Vijayanagara, 521, 522	
1358*.—Vīra-Pāṇḍya, son of Bhairava, . . .	987	1466*.—do., . . .	523
[1368].—Pratāpa-Dévarāya of Vijayanagara, 495		1466.—Jaina Śāntikīrtidēva, . . .	991
1368.—Dévarāya II. of Vijayanagara, . . .	496	1467.—Sadāśivarāya of Vijayanagara, . . .	524
1371.—Mallikārjuna of Vijayanagara, . . .	497	1469.—do., . . .	525
[1375].—Pāṇḍya Jaṭilavarman Parākrama-		1470.—do., . . .	526
Pāṇḍya, . . .	928	1471.—Bōmmu-Nāyaka of Vēlūr, . . .	527
1377.—Sāluva Tirumalaidēva, . . .	498	1476*.—Private inscription, . . .	992
1377.—Pāṇḍya Parākrama-Pāṇḍya, . . .	929	1476.—Sadāśivarāya of Vijayanagara, . . .	528
[1378].—Pāṇḍya Jaṭilavarman Parākrama-		1477.—do., . . .	529
Pāṇḍya, . . .	930	1477.—Pāṇḍya Māṇavarman Sundara-Pāṇḍya	
1381 (for 1353).—Pāṇḍya Arikēsaridēva Parā-		III., . . .	934
krama-Pāṇḍya, . . .	931	1478.—¶ Sadāśivarāya of Vijayanagara, . . .	530
1387.—Mallikārjuna of Vijayanagara, . . .	499	1482 (for 1483).—do., . . .	531
[1390-91 (Kollam 644)].—Kēraḷa prince		1482 (? for 1485).—do., . . .	533
Āḍityavarman, . . .	959	1483.—do., . . .	532
1392.—Virūpākṣa II. of Vijayanagara, . . .	500	1488.—do., . . .	534
[1400 (Kollam 654)].—Kēraḷa prince Rāma-		1489.—Pāṇḍya Jaṭilavarman . . . Ativīrarāma	
varman, . . .	960	Śrīvallabhadēva, . . .	935
[1402 (Kollam 655)].—Kēraḷa prince Mārtāṇḍa		1497.—Śrīraṅgarāya II. of Kārṇāṭa, . . .	535
1403.—Vāḷaka-Kāmaya alias Akkalarāja, . . .	874	1500.—do., . . .	536
1421.—Pāṇḍya Jaṭilavarman Parākrama-		1506.—¶ do., . . .	537
Pāṇḍya Kulaśēkhara, . . .	932	1508.—Immaḍi-Bhairava-Oḍeya (Bhairava II.), 993	
1427*.—¶ Sāluva Immaḍi-Nṛsiṃha, . . .	501	1514.—Venkaṭapati I. of Kārṇāṭa, . . .	538
1430 (for 1431).—Kṛṣṇarāya of Vijaya-		1523.—¶ do., . . .	539
nagara, . . .	502	1525.—Chāmūṇḍa ch. Timmarāja, . . .	994
1432*.—Kulōttuṅga-Chaṅgāḷa-Mahādēva, . . .	988	1543.—¶ Rāmadēva (IV. of Kārṇāṭa ?), . . .	540
1434 (for 1435).—¶ Kṛṣṇarāya of Vijaya-		1547.—Kṛṣṇappa-Nāyaka, etc., . . .	541
nagara, . . .	503	1556.—¶ Venkaṭapati II. of Kārṇāṭa, . . .	542
1435.—do., . . .	504	1556.—¶ Chāmarāja-Voḍeyar of Mahīśūra, . . .	995
1435 (for 1436).—do., . . .	505	1558.—¶ Venkaṭapati II. of Kārṇāṭa, . . .	543
1436.—do., . . .	506, 507	1560*.—Venkaṭādri-Nāyaka Ayya of Bēlūr, . . .	544
1437.—do., . . .	1064	1565.—Jaina Chārukiṛti-paṇḍita, . . .	996
1437-1448.—do., . . .	508	1566.—¶ Śrīraṅgarāya VI. of Kārṇāṭa, . . .	545
1438 (?).—Ch. Gōparāja (Sāluva-Gōparāja), . . .	989	1576.—Mudda-bhūpati of Padinbōḍu, . . .	997
1442.—Kṛṣṇarāya of Vijayanagara, . . .	509, 510	1594*.—¶ Keladi-Sōmasēkhara-Nāyaka, . . .	998
1444 (for 1445).—¶ do., . . .	511	1601.—¶ Chikkadēvēndra of Mahīśūra, . . .	999
1448.—¶ do., . . .	512	1615.—¶ Kṛṣṇappa-Nāyaka of Bēlūr, . . .	546

Śaka-S	NUMBER	Śaka-S.	NUMBER
1619.—¶ Gôpâla-Gaṇḍa, 'lord of Āvatīnād,'	1000	[1701 (Ky. 4881*)].—¶ <i>Koḍagu ch.</i> Liṅga-	
1620.—¶ 'Prithvi Satti,' etc.	1001	Rājendra-Voḍeyar,	1003
1621 (for 1645 ?).—Kṛishṇarāja of <i>Mahīśūra</i> ,	1002	1718.—¶ <i>Koḍagu ch.</i> Vīra-Rājendra-Voḍeyar,	1009
1636*.—¶ Basavappa-Nāyaka,	1003	1731.—Aditakīrtidēva,	1010
1644.—¶ Kṛishṇarāja of <i>Mahīśūra</i> ,	1004	1739 [and 1742].—¶ <i>Koḍagu ch.</i> Liṅga-	
1646.—¶ do.,	1005	Rājendra-Voḍeyar,	1011
1650.—¶ <i>Koḍagu ch.</i> Dodda-Virappa-		1748.—Kṛishṇarāja of <i>Mahīśūra</i> ,	1012
Voḍeyar,	1006	1752 (V. 1888*, Vardhamāna's-Nirvāṇa 2493).—	
1683.—¶ Chikkanna-Setti, etc.,	1007	do.,	1013

II.—INDEX TO THE APPENDIX.

A

NUMBER

NUMBER

Abbalabbā, <i>queen of Būtuga I.</i> ,	127
Abhimānavalli, <i>queen of Chōḍa Rājārāja I.</i> ,	716
Abhinava-Chārūkīrtipāṇḍita, <i>Jaina teacher</i> ,	991
Abhinava-Dēvarāja, <i>s. a. Dēvarāja II.</i> ,	490
Abhinavapāṇḍita, <i>Jaina teacher</i> ,	983
Ācha (Āchugi) I., <i>Sinda ch.</i> ,	224, 243
Ācha (Āchama, Āchugi) II., <i>do.</i> ,	218, 224, 243
Āchala, <i>poet</i> ,	1042
Āchaladēvi (Āchiyakka), <i>wife of Chandramauli</i> , 417	
Āchama (Ācha) II., <i>Sinda ch.</i> ,	218
Āchidēva III., <i>do.</i> ,	243
Āchintēndravara, <i>poet</i> ,	584
Āchugi (Ācha) I., II., <i>Sinda chiefs</i> ,	224, 243
Achyutamallapāṇḍa (Akkapa), <i>min. of Achyutarāja</i> ,	517
Achyuta-Nāyaka, <i>ch.</i> ,	370
Achyutarāja, <i>Vijayanagara k.</i> ,	514-520, 530
Achyutēndra, <i>s. a. Achyutarāja</i> ,	519
Adhika, <i>s. a. Adigaṇ</i> ,	834
Adhirājendra, <i>Chōḍa k.</i> ,	755
Adhōra or Ādhōra, <i>Makula ch.</i> ,	74
Adigai, <i>vi. (Tiruvadi)</i> ,	833n, 834n
Adigaṇ, ' <i>lord of Adigai</i> ,'	833, 834
Ādinagar, <i>vi.</i> ,	733
Āditakīrtidēva, <i>m.</i> ,	1010
Āditya, <i>Oḍḍavādi ch.</i> ,	600
Āditya I., <i>Chōḍa k.</i> ,	676-681, 685, 712
Āditya II. Karikāla, <i>do.</i> ,	694n, 712
Ādityadēva, <i>poets</i> ,	266, 268, 300
Ādityavarman, <i>k.</i> ,	941n
Ādityavarman, <i>Pallava k.</i> ,	635
Ādityavarman, <i>ruler of Vañchī</i> ,	959
Ādityavarman, <i>Silāra ch.</i> ,	301
Ādityavarman, <i>son and grandson of Pulakēśin II.</i> ,	25, 150
Ādityavarmanrāja, <i>dātaka</i> ,	54
Adiyama, <i>Chōḍa feudatory</i> ,	396n, 409, 415n
Adiyaṇ, <i>ch.</i> ,	937n
Ādiyappēndra Nāyakas,	519
Ādvayāṃṛita, <i>m.</i> ,	584
Agarayya, <i>m.</i> ,	124
Agaisarman, <i>poet</i> ,	419
Agramalla (P), <i>s. a. Malla (Mallisaṭṭi)</i> ,	360

Agranipidngu, <i>Telugu-Chōḍa ch.</i> ,	888
Āhavamalla, <i>Kaḷachūrya k.</i> ,	235-300
Āhavamalla, <i>sur. of W. Chōḍ.</i> Sōmēśvara I., 166, 171, 185, 741, 744-746, 748, 749, 751, 753, 969, 1060-82, 1084	
Āhavamalla, <i>sur. of W. Chōḍ.</i> Taila II., 143, 145, 201, 328	
Āhavamalla-Bhūtiga, <i>ch.</i> ,	259
Āhavamallakulakāla, <i>sur. of Virarājendra I.</i> ,	1081
Āhavamallānāi-mummaḍi-veṇ-kaṇḍa, <i>do.</i> ,	1081
Aiyapadēva, <i>ch.</i> ,	309
Aiyaparāja, <i>Silāra ch.</i> ,	301
Ajavarman, <i>k. or ch.</i> ,	142
Ajitasēna, <i>Jaina teachers</i> ,	131, 138, 969
Ajjapāṇḍi, <i>Jaina teacher</i> ,	667n
Akalabka, <i>do.</i> ,	969
Akalāṅka, <i>sur. of Vikrama-Chōḍa</i> ,	807
Akalāṅkacarita, <i>sur. of Irivabedāṅga Satyāśraya</i> ,	150n
Akalavarsha, <i>sur. of Rāshṭrakūṭa</i> Krishnarāja I., 55, 56, 61, 66	
Akalavarsha, <i>sur. of Rāshṭrakūṭa</i> Krishnarāja II.,	82, 84, 86, 91, 105, 130, 301
Akalavarsha, <i>sur. of Rāshṭrakūṭa</i> Krishnarāja III.,	93, 94, 96, 98, 105
Akalavarsha Krishnarāja, <i>Guj. Rāshṭrakūṭa ch.</i> , 81	
Akalavarsha Śubhatuṅga, <i>do.</i> ,	77, 78
Akkādēvi, <i>sister of W. Chōḍ.</i> Jayasinha II., 153	
Akkalarāja, <i>Uraiyār ch.</i> ,	874
Akkāmbikā (Āṅkama), <i>queen of Velanāṇḍu ch.</i> Rājendra-Chōḍa,	581, 582
Akkapa, <i>s. a. Achyutamallapāṇḍa</i> ,	517
Akkavve, <i>mother of Chandramauli</i> ,	416
Akkuka (Akkuva), <i>ch.</i> ,	84
Alachapura, <i>vi.</i> ,	127
Alagaṇ Ativirarāma Śrīvallabha, <i>Pāṇḍya k.</i> ,	935
Alagiya-Pallavaṇ, <i>ch.</i> ,	884
Alagiya-Śōḷaṇ, <i>Sēngēṇi ch.</i> ,	856, 860, 863
Alla, <i>k. or ch.</i> ,	131
Alla or Allāḍa, <i>Redḍi ch. of Rājamahēndra-nagara</i> ,	599
Allāḍaredḍi-Dodḍa, <i>s. a. Dodḍa II.</i> ,	599
Allaya-Dodḍa, <i>do.</i> ,	599
Allaya-Vēma, <i>Redḍi ch. of Rājamahēndra-nagara</i> ,	599

	NUMBER		NUMBER
Âluka, co.,	5	Ankama, s. a. Akkambikâ,	581
Âlupa, Âlupa, people or k.,	10, 29, 249	Ankulêsvara, vi.,	81
Âlupa, do.,	30	Anmakonḍa, °kundâ, vi.,	584, 586
Âmaṇa, <i>Dêvagiri-Yâdava k.</i> ,	369	Anna, <i>Redḍi ch. of Râjamahêṇḍranagara</i> ,	599
Amarâbharana-Śiyagaṅga, <i>Gaṅga ch.</i> ,	841	Anna-Vêma, <i>Redḍi ch. of Koṇḍaviḍu</i> ,	593, 594, 596
Amaragaṅga, <i>Dêvagiri-Yâdava k.</i> ,	334	Anna-Vôta, do.,	593, 595, 596
Amaragâṅgêya, do.,	351, 360	Annavrôla, <i>Redḍi ch. of Râjamahêṇḍra-</i>	
Amarâvatî, vi.,	589, 590n	nagara,	599
Ambarâja I., s. a. Ammarâja I.,	566	Anṇiga, <i>Pallava k.</i> ,	93, 98
Ambêra or °râ (°), son or daughter (?) of		Anumakonḍa, s. a. Anmakonḍa,	584
Pulakêsin II.,	15	Aparâditya, <i>Śîlâra ch.</i> ,	312, 313
Amitravalli, f.,	1076	Aparâjita, do.,	305-307, 309
Amma I., s. a. Ammarâja I.,	559, 560	Aparâjita, sur. of Prithivîpati I.,	670
Ammaiappan Kannuḍaipperumân, <i>Seṅgêni ch.</i> ,	820	Aparimitavarsha Dantivarman, <i>Guj.</i>	
Ammaiappan (Ammaiyappan) Âlâgiya-Śôlan, do.,	856, 860, 862	<i>Râshṭrakûṭa ch.</i> ,	78
Ammanadêva, <i>Chêdi k.</i> ,	91	Appa (Nâḍiṇḍla-Appa), min.,	503
Ammapayya, <i>Danḍanâdyaka</i> ,	280	Appâjêṇḍra-Voḍeyar, <i>Koḍagu ch.</i> ,	1008, 1009
Ammaṅgadêvi, queen of E. Chal. Râjarâja I.,	571	Appâji-Râjêṇḍra, do.,	1011
Ammarâja I., E. Chal. k.,	558-560,	Appaṇa, <i>Hoysala general</i> ,	847
562, 563, 566-568, 576, 1065		Appâyika, k. or ch.,	10
Ammarâja II. (Vijayâditya VI.), do., 563-568,		Appimayya, <i>Danḍanâdyaka</i> ,	742
574, 1065		Apramêya, general of Chôla Râjarâja I.,	713
Amôghavarsha, k.,	120	Âradavâḍa, vi.,	576
Amôghavarsha I., <i>Râshṭrakûṭa k.</i> ,	68, 70-77,	Aravaṇai Mâl-Ari-Kêśavaṇ, m.,	1046
80, 84, 86, 91, 93, 105, 127, 301, 305, 652n,		Âravîḍu, Âravîḍu, vi.,	530, 539
670, 1054, 1055, 1065n		Arhaddâsa, poet,	983
Amôghavarsha II., do.,	93, 301, 305	Arhanandin, <i>Jaina teacher</i> ,	1065
Amôghavarsha III., do., 93, 94, 95n, 98, 105,		Arihararâja, s. a. Harihara II.,	1062
127, 130		Arikêśarin, <i>Śîlâra ch.</i> ,	306, 307, 309
Amôghavarsha, sur. of <i>Râshṭrakûṭa</i> Kakkarâja		Arikêśarin Parâkrama-Pâṇḍya Jaṭilavarman,	
II.,	105	<i>Pâṇḍya k.</i> ,	928-931
Amṛitâmbâ, queen of Doḍḍadêvarâja,	999	Arikulakêśarin, s. a. (°) Arimjaya,	1074
Ânanda, sage,	1015	Arimjaya, <i>Chôla k.</i> ,	712, 1074
Ânandatîrtha, author,	979	Arishtanêmi-âchârya, m.,	1047
Ananta, family of,	519	Arivarman (Hari°), <i>W. Gaṅga k.</i> ,	108
Anantadêva, astronomer,	343	Ariyapillai, queen of Amarâbharana-Śiyagaṅga,	841
Anantadêva, Anantapâla, <i>Śîlâra ch.</i> ,	309	Arjuna, <i>Chêdi k.</i> ,	91
Anantapâla, <i>Danḍanâdyaka</i> ,	204, 207, 208, 216	Arjuna, <i>Oḍḍavâdi ch.</i> ,	600
Anantapâlâyya, do.,	213	Arjuna, probably <i>Paramâra k.</i>	
Ana-Vêma, s. a. Anna-Vêma,	593, 594, 596	Arjunavarman,	343, 369
Ana-Vôta, s. a. Anna-Vôta,	596	Arkakîrti, <i>Jaina teacher</i> ,	66
Andhra, co.,	343, 369, 663, 880	Arkavarman, <i>Pallava k.</i> ,	641
Ândhra maṇḍala,	668	Arumoli, sur. of Chôla Râjarâja I.,	711n
Ânga, co.,	5	Arumoli-Naṅgaiyâr, queen of Virarâjêṇḍra I.,	765
Anivârîta, sur. of W. Chal. Vikramâditya I.		Ârya, <i>Oḍḍavâdi ch.</i> ,	600
and II.,	20n, 48n	Ârya-mahâdêvi, queen of Dâna,	568
Aniyankabhima, sur. of <i>Koṇḍapaḍmaṭi ch.</i>		Âryanandin, <i>Jaina teacher</i> ,	667n
Buddharâja,	581	Âryapura, vi. (Aihole),	1026
Âṅka, <i>Raṭṭa ch.</i> ,	163, 181, 201	Âryasêna, <i>Jaina teacher</i> ,	167
		Âsatîmayûrapura, vi.,	427

	NUMBER
Aśōkavarman, ancestor of Pallava kings, . . .	635
Aśvatthāman, legendary being, . . .	644
Aṭavidurjaya, dūtaka, . . .	548
Atirapachanḍa, Pallava k., . . .	629
Atisayadhavala, sur. of Amoghavarsha I., . .	75
Ativirarāma Śrīvallabha Jaṭilavarman, Pāṇḍya k., . . .	935
Attimallaṇ (Miṇḍaṇ A?), Śēṅḡēni ch., . .	818
Attimallaṇ Śambukula-Perumāl, ch., . .	854
Attimallar Kapparadēva-Pyithvigahgaraiyar, Gaṅga ch., . . .	1058, 1057
Attirāja, father of Polālva, . . .	434
Attivarman, k., . . .	1015
Atvivarman (?), W. Gaṅga ch., . . .	1070
Aṭyantakāma, Pallava k., . . .	623, 638
Avanibhājana-Pallavēśvara, temple, . .	621
Avanisiṁha, Pallava k. Siṁhavishṇu, . .	635
Āvanyapura, vi., . . .	663
Avasara I, II, III, Śilāra chiefs, . . .	301
Āvatinaḍ, dā, . . .	1000
Aviṇṭa, W. Gaṅga k., . . .	112, 114, 115
Arvalladēvi (Hammā), queen of Bhīlāma III., .	331
Ayōdhya, vi., . . .	150, 568
Ayyapa I., W. Chāl. k., . . .	150, 232
Ayyapa II., do., . . .	179
Ayyapa, k. or ch., . . .	1065
Ayyapadēva, Nolamba k., . . .	126, 1035n
Ayyapillāya, poet, . . .	582
Ayyapōpi, Jaina teacher, . . .	1065
Ayyāvōle, vi. (Aihole), . . .	1026

B

Bāchaladēvi, queen of Kādamba Tailapa II., .	210
Bāchikabbe, mother of Singimayya, 400n, 403, 404	
Bādāmi, W. Chalukyas of, . . .	1 ff.
Baddēga, Baddiga, Rāshtrakūṭa Amoghavarsha III. (Vaddiga), . .	93, 127, 130
Bāgaṇabbe, f., . . .	406
Baicha (Baichapa), Vijayanagara min. (Vaichaya), . . .	469, 486
Baichapa, grandson of Baicha, . . .	486
Bālachandra, Jaina teachers, . . .	637n, 980
Bālachandra, m., . . .	408
Baladēva, father of Singimayya, . . .	400n, 403, 404
Baladēva, grandson of Baladēva, . . .	404
Balāmma-Thakkura, m., . . .	17
Balavarman, Chāl. ch., . . .	66
Bali, Asura, . . .	663
Ballāla, Sāntālī māṇḍala ch., . . .	340

	NUMBER
Ballāla, Ballāla, Śilāhāra ch., . . .	316, 317, 321, 327
Ballāla I., Hoysala k., . . .	385, 388, 405, 406, 419, 434
Ballāla II., do., . . .	369, 388, 415-424, 426-434, 437, 443
Ballāla III., do., . . .	453
Ballāladēva-Vēlābhāṭa (Boḍḍiya), ch., . .	564
Bamma, brother of Gaṅgarāja, . . .	406
Bamma, Śinda ch., . . .	224, 243
Bammadēva, father of min. Nāgādēva, . .	414
Bammappaya, Daṇḍanāyaka, . . .	232
Bammarasa (Barmarasa), do., . . .	211
Bāṇa, family and kings, . . .	119, 659 ff., 685
Bāṇa, poet, . . .	641n
Bāṇa, son of Asura Bali, . . .	663
Bāṇādhirāja, ancestor of Bāṇa kings, . .	663
Bāparāya, 'a Bāṇa k.,' . . .	667
Banavāsapura, vi., . . .	227
Banavāsi, vi., . . .	127, 162, 173, 210, 241, 242, 262
Bānavidyādhara, Bāṇa k., . . .	663
Bānavidyādhara, sur. of Bāṇa Vikramāditya I.,	662
Baṅkāpura, vi., . . .	131, 174
Baṅkēsa, Baṅkēya, Baṅkēyanāja, Cāsa, Mukūṭa ch., . . .	74, 1055
Bappūra, family, . . .	7
Bappuvansa, ch., . . .	967
Barabarābha, sur. of Nṛsiṁharāja, . . .	501
Baregedēva-Nāyaka, ch., . . .	1027
Barma, ch. (son of Bhūtiga), . . .	259
Barmadēva, Daṇḍanāyakas, . . .	136, 187, 294
Barmarasa, do., . . .	211, 279, 281
Basappaya, Basappa, Basavappa-Nāyaka, ch.,	1003
Batpūra, family, . . .	5
Bayappa-Nāyaka, ch., . . .	523, 533
Bāyiga, Bāyika, m., . . .	134, 135
Bayyamāmbā, daughter of Nātavāḍi ch. Rudradēva, . . .	592
Bayyāmbikā, queen of Kākatīya Mahādēva, .	586
Bēlāpura (Vēlāpura), vi., . . .	385, 388
Bellakonḍa, vi., . . .	1064
Bēlūr, vi., . . .	544, 546
Bēta, E. Chāl. Vijayāditya V., . . .	576
Bēta, Kākatīya Tribhuvanamalla, . . .	585
Bēta, Kōnamāṇḍala ch., . . .	583
Bēta, Kōnnātavāḍi-vishaya ch., . . .	589
Betmarāja, Kākatīya Bēta, . . .	589
Betta (Vetta) I., II., III., Telugu-Chōḍa chiefs, . . .	880, 881, 883
Bhadrabāhu, Jaina teacher, . . .	669
Bhāgaladēvi, Bhāgalāmbikā, queen of Katta II., . . .	191, 192, 201

	NUMBER		NUMBER
Bhāgaladēvi (Bhāgyavati), mother of W. Chāl.		Bhīma, s. a. Vimaṇ,	795
Vikramāditya V.,	153	Bhīmanabhaṭṭa, poet,	568n
Bhagiratha, Kādamba k.,	603	Bhīmarāja, Maurya ch.,	330
Bhāgyavati (Bhāgaladēvi), mother of W. Chāl.		Bhīmarasa, ch.,	145
Vikramāditya V.,	150	Bhīmavarman, Pallava k.,	635
Bhāilēka, Maurya ch.,	330	Bhīvaṇayya, Daṇḍanāyaka,	202
Bhairava I. (Bhairarasa-Oḍeya), ch.,	993	Bhōgadēvarasa, ch.,	165
Bhairava II. (Immaḍi-Bhairarasa-Oḍeya), ch.,	993	Bhōganātha, narma-sachiva of Saṃgama II.,	459
Bhairava or Bhairavēndra, ch.,	985, 987	Bhōgavati, vi.,	144, 156, 189, 972
Bhambhāgiri, vi.,	369	Bhōja, kings,	337, 940
Bhammaha-Raṭṭa, Rāṣṭrakūṭa ch.,	150	Bhōja, Paramāra k.,	152
Bhaṇḍanāditya-Kuntāditya, officer of		Bhōja I., Bhōjadēva I., Śilāhāra ch.,	243,
Ammarāja I.,	559		317, 321, 327
Bhaṇḍāragaviṭṭage, vi.,	49	Bhōja II., Bhōjadēva II., do.,	325-327, 369
Bhānūdēva II., E. Gaṅga k.,	579n	Bhōjarāja, k. of Dhārā,	1022
Bhānukirtidēva, Jaina teacher,	406	Bhṛīgukacchella, vi.,	77
Bhānusaṅgi, Śēndraka k.,	612	Bhujabala-Gaṅga, sur. of Hoysala Vishṇu-	
Bhānuvarman, Kādamba prince,	610	vardhana,	388
Bharata, author,	1042	Bhujabala-Vīra-Gaṅga, sur. of Hoysala	
Bharata, Bharatana, Bharatamayya,		Narasimha I.,	409
Daṇḍanāyaka,	401, 402	Bhujagēndra, lineage,	16
Bhāravi, poet,	10	Bhujagādhirāja (?), k.,	1016
Bhārgava, lineage of,	1080	Bhujjabbarasi, mother of Bātuga II.,	130
Bharukacchella, vi.,	69	Bhukka, s. a. Pukka I.,	475
Bhāskara, min.,	1001	Bhūlōkamalla, sur. of W. Chāl. Sōmēśvara III.,	
Bhāskarabhaṭṭa, Vidyāpati,	337		227, 228, 230, 231
Bhāskarāchārya, astronomer,	337	Bhūpamahēndra, sur. of E. Chāl. Vimalāditya,	568
Bhāskara Ravivarman, k.,	962, 963	Bhūta (Bhūtiga), ch.,	259
Bhāyidēva, Daṇḍanāyaka,	258	Bhūtārya, s. a. Bātuga II.,	93, 98
Bhīllama, Dēvagiri-Yādava k.,	334, 336,	Bhūtiga (Bhūta), ch.,	259
	337, 342, 343, 351, 369, 370, 379, 419	Bhuvanaikamalla, sur. of W. Chāl. Sōmēśvara	
Bhīllama, k.,	309	II.,	156, 174, 175, 177-183, 185
Bhīllama I., Yādava ch. of Śēmadēśa, 323, 329, 331		Bhuvanaikamalla-Śāntināthadēva, Jaina	
Bhīllama II., do.,	328, 329, 331	temple or image,	183
Bhīllama III., do.,	329, 331	Bhuvanaikavīra Udayāditya, ch.,	179, 180
Bhīma, ch.,	582n	Bhuvanamulududaiyāl, ōyār, title of Chōla	
Bhīma, Chōla ch.,	599	queens,	768, 774, 814, 827, 1087, 1088
Bhīma, E. Chāl. k.,	560	Bhūvikrama, W. Gaṅga k.,	115, 116, 121,
Bhīma, Maurya ch.,	330		127, 670
Bhīma, Śilāra ch.,	301	Bīcha, Bichirāya, Daṇḍēśa (Vichana),	351, 357
Bhīma, Sinda ch.,	189	Bijja, ch.,	1065
Bhīma, W. Chāl. kings,	150	Bijjabe, wife of Maruḷadēva,	130
Bhīma I., E. Chāl. Chālukya-Bhīma I., 557,		Bijja-Dantivarman, Banavāsī k.,	127, 1065n
	558, 566, 1065	Bijjala (Bijjana), Kālachurya k.,	232, 238,
Bhīma II., E. Chāl. Chālukya-Bhīma II., 560,			245, 277-280
	563, 566-568, 1065	Bijjala, Sinda ch.,	247
Bhīma I., II., III., Kōṇamanḍala chiefs,	583	Bijjalā, queen of Hoysala Sōmēśvara,	443
Bhīma I., II., III., IV., Oḍḍavādī chiefs,	600	Bijjana (Bijjala), Kālachurya k.,	240, 275,
Bhīma I., II., Śrī-Dhānyakāṭaka chiefs,	590		276, 281-285, 288, 293
Bhīma, s. a. Bhīmanabhaṭṭa,	569n	Birudānka-Bhīma, sur. of E. Chāl. Vimalāditya,	568

	NUMBER		NUMBER
Birudañka-Rāma, <i>sur. of Śilāra Aparājita</i> , . . .	309n	Chaladankarāva Hoysalasetṭi, <i>m.</i> , . . .	970
Biṭṭarasa, <i>E. Chal. Vishṇuvardhana I.</i> , . . .	547n	Chalikya, Chalikya, <i>s. a.</i> Chalukya, 5, 5n, 6n ff.,	547
Biṭṭidēva, Biṭṭiga, <i>Hoysala Vishṇuvardhana</i> , . . .	234, 396, 434	Chālikya, <i>s. a.</i> Chālukya,	6
Boddiya (Ballādēva-Vēlābhāṭa), <i>ch.</i> , . . .	564	Chalkya, <i>s. a.</i> Chalukya,	3n
Bolikeya-Kēsimayya, <i>Daṇḍanāyaka</i> , . . .	285	Chālukya, <i>kings</i> ,	249
Bomma, <i>s. a.</i> Bommu-Nāyaka,	539	Chalukya- or Chālukya-Bhīma I., <i>E. Chal. k.</i> , . . .	557-560, 562, 563, 566, 567, 1065
Bomma Guṇḍa II., <i>Sāluva ch.</i> ,	501	Chalukya- or Chālukya-Bhīma II., <i>do.</i> , . . .	126n, 560-568, 1065
Bommu-Nāyaka, <i>Vēlār ch.</i> ,	527, 534, 535, 539n	Chālukya-Chandra, <i>sur. of E. Chal. Śakti-varman</i> , . . .	569
Bonthādēvi, <i>queen of W. Chāl. Vikramāditya IV.</i> ,	140, 150	Chāluky-Ārjuna, <i>sur. of E. Chal. Vijayāditya II.</i> , . . .	556
Boppadēva, Boppaṇa, <i>son of Gaṅgarāja</i> , . . .	406, 407	Chalukyas or Chālukyas, Eastern, 86, 91, 105, . . .	547 ff., 1065
Boppadēvi, <i>queen of Ballāla I.</i> ,	385	Chalukyas, Western, <i>of Bādāmi</i> ,	1 ff.
Boppa Sujanōttarīsa, <i>poet</i> ,	137	Chalukyas, Western, <i>of Gujārāt</i> ,	1n
Brahmadēva (Barmarasa), <i>Daṇḍanāyaka</i> , . . .	291	Chālukyas, Western, <i>of Kalyāṇi</i> ,	140 ff.
Brahmakshatra, <i>lineage</i> ,	136, 179n	Chāmaṇḍa, <i>Daṇḍādhipa</i> ,	193
Brahman, <i>general</i> ,	294n, 419	Chāmarāja (Chāmeya-Nāyaka), <i>ch.</i> ,	454
Brahman, <i>Haiḥaya ch.</i> ,	576	Chāmarāja, <i>Daṇḍanūṭha</i> ,	489
Brahmasēna, <i>Jaina teacher</i> ,	167	Chāmarāja, <i>Mahēśvara k.</i> ,	1013
Brahmaśrīrāja, <i>min.</i> ,	635	Chāmarāja-Voḍeyar, <i>do.</i> ,	995
Brahmavaka, <i>race of</i> ,	84	Chāmekāmbā, <i>f.</i> ,	1035
Brahmayuvārāja, <i>min.</i> ,	635	Chāmeya-Nāyaka (Chāmarāja), <i>ch.</i> ,	454
Bṛihatphalāyanas, <i>gōtra of</i> ,	1014	Champa, <i>s. a.</i> Vira-Champa,	870
Būchapa, Būchirāja, <i>son of Gaṅgarāja</i> , . . .	386, 390	Chāmūṇḍa, <i>family</i> ,	994
Budda, <i>Nātadāḍi ch.</i> ,	591, 592	Chāmūṇḍa, Chāmūṇḍarāja, <i>raja</i> , <i>min. of W. Gaṅga kings</i> ,	137-139
Buddha, Buddharāja, <i>Kalachuri k.</i> ,	5, 6	Chāmūṇḍa (Chāvūṇḍa) II., <i>Sinda ch.</i> ,	243, 247
Buddharāja, <i>Koṇḍapaḍmaṭi ch.</i> ,	581	Chāmūṇḍasetṭi, <i>m.</i> ,	390
Buddhavarasa, <i>brother (P) of Pulakēsin II.</i> , . . .	1n	Chandaladēvi, <i>queen of Mallapa II.</i> ,	576
Buddhavarasa, <i>Sulūkika ch.</i> ,	67	Chandaladēvi, <i>Raṭṭa queen Chandrikādēvi</i> , . . .	265
Buddhavarman, <i>ancestor of Koṇḍapaḍmaṭi chiefs</i> ,	581	Chandradēva, <i>m.</i> ,	634n
Buddhavarman, <i>Pallava k.</i> ,	635	Chandrāditya (Chandrarāja), <i>Śilāhāra ch.</i> , . . .	321, 327
Budhamitra, <i>father of Gaṅgarāja</i> ,	395	Chandrāditya, <i>W. Chal. prince</i> ,	23, 24
Bukka, <i>Karṇāṭa ch. of Āraviḍu</i> ,	530, 539	Chandrādityapura, <i>vi.</i> ,	331
Bukka, <i>perhaps s. a.</i> Bukkarāja I.,	458	Chandragupta, <i>k.</i> ,	969
Bukka I., <i>s. a.</i> Bukkarāja I.,	456n, 459, 465, 469, 475, 484, 487, 490	Chandrakīrti, <i>Jaina teacher</i> ,	984
Bukkamā, <i>wife of general Īsvara</i> ,	502	Chandramauli, <i>min.</i> ,	416, 417
Bukkapa, <i>son of Baicha (Baichapa)</i> ,	486	Chandrapandin, <i>Jaina teacher</i> ,	119
Bukkarāja (Bukkarāja) I., <i>Vijayanagara k.</i> , . . .	455-458, 460n, 461, 463, 468, 474, 480, 486	Chandrapillai, <i>m.</i> ,	1048
Bukkarāja (Bukkarāja) II., <i>do.</i> ,	479, 1062	Chandraprabhadēva, <i>Jaina teacher</i> ,	446
Būtayya, <i>s. a.</i> Būtuga II.,	130	Chandrarāja, <i>Śilāhāra ch.</i> ,	317, 327
Būtuga I., <i>W. Gaṅga k.</i> ,	125n, 127	Chandrikādēvi, Chandrike, <i>queen of Raṭṭa Lakshmidēva I.</i> ,	265, 266
Būtuga II., <i>do.</i> ,	93, 95, 98, 127, 128, 130	Chāṅgadēva, <i>astrologer</i> ,	337
		Chāṅgadēva, <i>min.</i> ,	333
		Chāṅkaṇārya, Chāṅkimayya, Chāṅkirāja, <i>m.</i> , . . .	167
		Chārūkīrti, <i>Jaina priest</i> ,	994

C

Chākirāja, <i>Gaṅga ch.</i> ,	66
Chakragōṭṭa, Chakrakōṭṭa, <i>vi.</i> ,	396n, 409, 733, 756, 761, 1083

	NUMBER
ārukīrti-paṇḍita, <i>Jaina teacher</i> ,	996
maṭṭa, <i>ch.</i> ,	234
maṭṭa I., II., <i>chiefs</i> ,	259
maṭṭaladevi, <i>f.</i> ,	254, 255
maṭṭara-Revadi-Ovajja, <i>m.</i> ,	1040
matutthābhijana, <i>Sūdra caste</i> ,	581
matuttha-kula, <i>do.</i> ,	592
matutthānvaya, <i>do.</i> ,	582
maṭṭyaṇḍāya, <i>poet</i> ,	269
maṇḍa (Chāvaṇḍa) I., <i>Sinda ch.</i> ,	224, 243
maṇḍaṇḍa (Chāvaṇḍa-āja), <i>mn.</i> ,	360
maṇḍasatṭhi, <i>Chāvaṇḍa-āja, mn.</i> ,	357, 358
maṇḍa, <i>Sindu ch.</i> ,	224, 243
maṇḍaladevi, <i>queen of Ballāla I.</i> ,	385
maṇḍa (Chāvaṇḍa) I., <i>Sinda ch.</i> ,	224, 243
maṇḍa (Chāvaṇḍa) II., <i>do.</i> ,	243, 247
maṇḍaṇḍa, <i>s. a. Chāvaṇḍa-āja</i> ,	136, 139
maṇḍaṇḍa, <i>s. a. Chāvaṇḍa-āja</i> ,	360
maṇḍaṇḍa, <i>ch.</i> ,	161, 162
maṇḍi <i>kings</i> ,	86, 98, 105
maṇḍa, <i>co.</i> ,	741n
maṇḍa, <i>k. (P)</i> ,	1016
maṇḍa, <i>vi.</i> ,	518
maṇḍa, <i>poet</i> ,	569n
maṇḍa, <i>sur. of Kākaṭiya Gaṇapati</i> ,	585
maṇḍa, <i>Silāra ch.</i> ,	307-309
maṇḍa, <i>father of Bhoja</i> ,	351, 357
maṇḍa, <i>Mahāsāra k.</i> ,	999, 1004
maṇḍa-Kōtaya, <i>Daṇḍāyaka</i> ,	447
maṇḍa, <i>m.</i> ,	1007
maṇḍa (Pina)-Vēṇkaṭa III., <i>Karnāṭa prince</i> ,	545
maṇḍa, <i>queen of Oḍḍaṇḍi ch. Jayanta</i> ,	600
maṇḍa-Nāyaka, <i>general</i> ,	516
maṇḍa, <i>Jaina teacher</i> ,	2
maṇḍa, <i>Pallava k.</i> ,	634
maṇḍa, <i>vi.</i> ,	29
maṇḍa, <i>Alupa k.</i> ,	29
maṇḍa, <i>Chōḍa, Chōḍa-āja, Koṇḍapaṇḍi ch.</i> ,	581n
maṇḍa, <i>Vēṇkaṭa ch.</i> ,	582
maṇḍa, <i>(Rājaraṭa), E. Chal. ruler of</i>	
maṇḍa, <i>Vēṇkaṭa</i> ,	571
maṇḍa, <i>queen of Prōḍa-Nāyaka</i> ,	601
maṇḍa, <i>Koṇḍapaṇḍi ch.</i> ,	581n
maṇḍa, <i>Sri-Dhanyakāṭaka ch.</i> ,	590
maṇḍa, <i>ch.</i> ,	584, 586
maṇḍa, <i>Kādamba ch.</i> ,	210
maṇḍa, <i>Pāṇḍya ch.</i> ,	999
maṇḍa, <i>co., people, race</i> ,	10, 586, 891-896, 904, 939
maṇḍa, <i>kings</i> ,	672 ff.
maṇḍa, <i>legendary Chōḍa k.</i> ,	685, 712

	NUMBER
Chōḍamahādēvi, <i>queen of Chōḍa Rājaraṭa I.</i> ,	716
Chōḍa, <i>co.</i> ,	5
Chōḍamaṇḍa, <i>Kaṭṭa (Kāṭara) k.</i> ,	712n
Comorin, <i>Cape</i> ,	764

D

Daddara, <i>k.</i> ,	559n
Dadigaṇa, <i>governor of a di.</i> ,	122
Dahāla, <i>co.</i> ,	127
Dakṣiṇa-Lāṭa, <i>co.</i> ,	733
Dāma (Dāva), <i>Sinda ch.</i> ,	224, 243
Dāma, <i>Tigula ch.</i> ,	415n
Dāmari, <i>Nuluvugiri k.</i> ,	127
Dāmodara, <i>ch.</i> ,	415n
Dāmodara, <i>Kadamba k.</i> ,	615
Dāma, Dāmaṇḍa, <i>E. Chal. k.</i> ,	568, 569, 574
Dāma, <i>co.</i> ,	733
Dantidurga, <i>durgarāja, Rāṣṭrakūṭa k.</i> ,	53,
	61, 66, 71, 86, 91, 93, 105, 301
Dantiga, <i>k. (Bijja-Dantivarman P)</i> ,	93, 98
Dantiga, <i>Kāṇḍi k. (Dantivarman P)</i> ,	62
Dantivarman, <i>dūtaka</i> ,	65
Dantivarman, <i>Gaṇa-Pallava k.</i> ,	652
Dantivarman, <i>Kāṇḍi k.</i> ,	62n
Dantivarman, <i>Rāṣṭrakūṭa ch. (P)</i> ,	56
Dantivarman I., <i>Rāṣṭrakūṭa k.</i> ,	71
Dantivarman II. (Dantidurga), <i>do.</i> ,	53, 56, 305
Dantivarman, <i>Aparimitavarsha</i> ,	Guj.
Dantivarman, <i>Rāṣṭrakūṭa ch.</i> ,	78, 81
Dāsa, <i>Sinda ch.</i> ,	224, 243
Dāsa, <i>vi.</i> ,	620, 622
Dāsa, <i>Yasovarman (Yasovarman), W. Chal. prince</i> ,	153, 154n
Dattakāṣṭha-vritti, <i>vyākhyā</i> ,	108, 111-113, 129
Dāva (Dāma), <i>Sinda ch.</i> ,	224, 243
Dāvaramalla I., II., <i>chiefs</i> ,	259
Dāvāri (Dāyima), <i>Raṭṭa ch.</i> ,	181, 201
Dāvabhīma, <i>Telugu-Chōḍa ch.</i> ,	880
Dāyima (Dāvāri), <i>Raṭṭa ch.</i> ,	181, 201
Dēgaḍi, <i>ch.</i> ,	84
Dēmaladevi, <i>queen of Chāvaṇḍa II.</i> ,	243
Dēmati, Dēmiyyaka, <i>daughter of Gaṇaraṭa</i> ,	300
Dēvagiri, <i>vi.</i> ,	339, 344, 359
Dēvagiri, <i>Yādava of</i> ,	334 ff.
Dēvaḥastin, <i>Maurya ch.</i> ,	330
Dēvaki, <i>queen of Tulaṭa k Timma</i> ,	502
Dēvakīrti-guru, <i>Jaina teacher</i> ,	120
Dēvakīrti-paṇḍita, <i>Mahāmaṇḍalāchārya</i> ,	412, 413
Dēvaladevi, <i>queen of Hoysala Sōmēśvara</i> ,	441

	NUMBER		NUMBER
Dēvanātha, <i>Chakrakōṭṭa ch.</i> ,	1053	Divākaranandi-siddhāntadēva, <i>Jaina teacher</i> , . .	963
Dēvarāja, <i>Mahīśūra k.</i> ,	999	Divalāmbā, <i>mistress of Būtuga II.</i> ,	127
Dēvarāya (Dēvarāja) I., <i>Vijayanagara k.</i> , 480-485, 487, 490		Dōchi, <i>father of Sāmanta-Bhōja</i> ,	588n
Dēvarāya (Dēvarāja) II., <i>do.</i> , 487-496, 499, 501		Doḍḍa I., II., <i>Redḍi chiefs of Rājamahēndra-</i> <i>nagara</i> ,	599
Dēvaśakti-paṇḍita, <i>Jaina priest</i> ,	180	Doḍḍadēvarāja, <i>Mahīśūra k.</i> ,	999
Dēvaśaktirāja, <i>Sēndraka k.</i> ,	19	Doḍḍa-Krishṇarāja-Voḍeyar, <i>do.</i> ,	1002
Dēvavarman, <i>Kadamba prince</i> ,	613	Doḍḍāmbikā, <i>mother of Kāṭaya-Vēma</i> ,	596n
Dēvēndra, <i>Jaina priest</i> ,	74	Doḍḍasāni-amma, <i>do.</i> ,	595
Dēvēndra, <i>Jaina teacher</i> ,	129	Doḍḍa-Virappa-Voḍeyar, <i>Koḍagu ch.</i> ,	1006, 1009
Dēvēndragiri, <i>s. a. Dēvagiri</i> ,	345	ḍomma, <i>ch.</i> ,	584
Dhādīadēva, Dhādībhaṇḍaka, <i>Mahārāshtrakūṭa</i> <i>ch.</i> ,	191	Dōra (Dhōra), <i>Rāshtrakūṭa k. Dhruvarāja</i> , . .	58
Dhādīyappa, <i>Yādava ch. of Sēṇadēsa</i> , 328, 329, 331		Dōrasamudra, <i>vi.</i> ,	401, 434, 443, 446, 447, 450, 451, 453, 847
Dhaladi (P), <i>ch.</i> ,	562	Dōsi, <i>Banavāsī governor</i> ,	51
Dhalaga, <i>ch.</i> ,	1065	Dōsirāja, <i>m.</i> ,	49
Dhammiyara, <i>Silāra ch.</i> ,	301	Dramila, <i>co.</i> ,	5
Dhanadapura, <i>°pōlu, vi. (Tsandavōlu)</i> ,	581n	Dṛiḍṇaprahāra, <i>ancestor of Yādavas of</i> <i>Sēṇadēsa</i> ,	331
Dhārā, <i>vi.</i> ,	409, 756, 1022	Drōhārjuna, <i>sur. of Chālukya-Bhīma I.</i> ,	559n
Dharanīmūlududairāl, <i>title of Chōla queen</i> ,	803	Dunḍu-Nirgunda-yuvarāja, <i>Bāṇa (P) ch.</i> ,	119
Dharanivarāha, <i>sur. of Nṛsiṃharāja</i> ,	511	Durga, <i>Nāṭavāḍi ch.</i> ,	592
Dhārāśraya Jayasimhavarmanrāja, <i>W. Chal.</i> <i>prince</i> ,	17	Durgasakti, <i>Sēndra k.</i> ,	16
Dharāvarāha, <i>sur. of Nṛsiṃharāja</i> ,	501	Durjaya, <i>family</i> ,	581, 800
Dhārāvarsha, <i>sur. of Guj. Rāshtrakūṭa ch.</i> Dhruvarāja I. and II.,	70, 77	Durjaya, <i>Kākatīya k.</i> ,	585
Dhārāvarsha, <i>sur. of Rāshtrakūṭa Dhruvarāja</i> , 57, 61, 64, 66		Durlabha, <i>sur. of Amoghavarsha I.</i> ,	305
Dharmapāla, <i>Daṇḍabhukti k.</i> ,	733	Durlabhadēvi, <i>queen of W. Chal. Kirtivar-</i> <i>man I.</i> ,	5
Dhavalappa, <i>ch.</i> ,	84	Durvinita, <i>W. Gaṅga k.</i> ,	114, 115, 670
Dhātātaran Mūrti-Eyinaṇ, <i>ch.</i> ,	937	Dvārakā, <i>vi.</i> ,	999
Dhōra, <i>Rāshtrakūṭa k. Dhruvarāja</i> ,	58, 64	Dvāravatī, <i>Dvārāvati, vi.</i> ,	328, 331, 332, 339, 341, 349, 351, 359, 360, 362, 370, 373, 379, 383, 388, 389, 396, 401, 405, 410, 416, 419, 423, 434, 435, 443, 447, 450
Dhōrappa, <i>probably Rāshtrakūṭa prince</i> Nirupama,	328		
Dhruvarāja, <i>Guj. Rāshtrakūṭa k.</i> ,	54		
Dhruvarāja, <i>Rāshtrakūṭa ch. (P)</i> ,	56		
Dhruvarāja, <i>Rāshtrakūṭa k.</i> , 57-61, 64-66, 68, 70, 75, 84, 86, 91, 93, 105, 301, 305			
Dhruvarāja I., <i>Guj. Rāshtrakūṭa ch.</i> ,	70, 77		
Dhruvarāja II., <i>do.</i> ,	77, 78, 81		
Dhruvarāja Indravarmān, <i>governor of</i> <i>Rēvatīdvīpa</i> ,	7		
Dhuliprabhu, <i>m.</i> ,	44n		
Digambara <i>Jainas</i> ,	969		
Dinachintāmanī, <i>queen of Kulōttuṅga-Chōla</i> I.,	775, 777		
Diṇḍi, <i>k.</i> ,	670		
Divākara, <i>Daṇḍanāyaka</i> ,	300n		
Divākara, <i>Telugu-Chōla ch.</i> ,	888		
		E	
		Eastern country,	735, 736, 756
		Ēcha (Ēchirāja), <i>nephew of Gaṅgarāja</i> ,	406
		Ēchaladēvi, <i>queen of Eṇṇayaṅga</i> ,	388, 405, 409
		Ēchaladēvi, <i>queen of Hoysala Narasiṃha I.</i> , 409, 416, 419	
		Ēchaladēvi, <i>queen of Irūṅgula</i> ,	253
		Ēchaladēvi, <i>queen of Kārtivīrya IV.</i> ,	265, 266
		Ēcham (Ēchirāja), <i>father of Gaṅgarāja</i> ,	389
		Ēchapa, <i>s. a. Boppadēva</i> ,	407
		Ēchikabbe, <i>wife of Ēcha</i> ,	406
		Ēchirāja, <i>s. a. Ēcha and Ēcham</i> ,	389, 406
		Edirili-Sōla-Sambavarāyaṇ, <i>s. a. Alagiya-</i> <i>Pallava</i> ,	884

	NUMBER
Edirilli-Śōla-Sambuvārāyaṇ, s. a. Alagiya-Śōlaṇ,	856, 860, 862
Ēkadēva, <i>Jaina teacher</i> ,	129
Ēkaśilānagari, vi. (Warangal),	1066
Eladāyasimha, <i>sur. of Koṇḍapaḍmaṭi ch.</i> Bud-	
dharāja,	551
Ēlagam, vi.,	1087
Elajōla, <i>Telugu-Chōḍa ch.</i> ,	888
Elīṇi, <i>Kēraḷa k. (Yavanikā)</i> ,	834
Ēlisui-Vallabhi, <i>queen of Kulōttunga-Chōla I.</i> , 775	
Ellore, vi.,	795n, 833
Elumpundale, vi.,	28
Erega, <i>Hoysala k. Ereyāṅga</i> ,	406
Erega (Erega), <i>Raṭṭa ch.</i> ,	181, 201
Eraha, <i>ch.</i> ,	293
Erakōri, <i>Mukula ch.</i> ,	74
Erambarage, Erambirage, vi.,	224, 234
Ērasiddhi (Gaṇḍagōpāla), <i>Telugu-Chōḍa ch.</i> ,	880, 882
Erega (Ereyammarasa), <i>Raṭṭa ch.</i> ,	158, 181, 201
Eregāṅga, <i>ch., or W. Gaṅga Śivamāra I. (?)</i> ,	116
Eregāṅga I., II., <i>W. Gaṅga kings</i> ,	127
Ereve, <i>ch.</i> ,	1031
Ereyamma, <i>Telugu-Chōḍa ch.</i> ,	858
Ereyammarasa (Erega), <i>Raṭṭa ch.</i> ,	158
Ereyāṅga, <i>Hoysala k.</i> , 388, 405, 406, 409, 419,	
434, 443	
Ereyapa, <i>W. Gaṅga k.</i> ,	95
Ereyapa, <i>W. Gaṅga k. Ereyapparasa</i> ,	126
Ereyappa, <i>W. Gaṅga k. (?)</i> ,	127
Ereyapparasa, <i>W. Gaṅga k.</i> ,	126
Ereyya, s. a. (?) Pulakēsin II.,	16
Eriyavarman, <i>Velanāṇḍu ch.</i> ,	582
Erra-Maṇḍa, <i>Koṇḍapaḍmaṭi ch.</i> ,	581n
Erraya, <i>Velanāṇḍu ch.</i> ,	582
Ētagiri, vi.,	186, 187

G

Gajapati kings of Orissa,	508, 904n, 1064
Gāmundaḍḍa, <i>queen of Gōvindarāja III.</i> ,	62
Gaṇapa, <i>Kākatīya Gaṇapati</i> ,	589
Gaṇapāmbā, <i>bhikā, daughter of Kākatīya Ga-</i>	
ṇapati,	589
Gaṇapati, <i>k.</i> ,	741
Gaṇapati, <i>Kākatīya k.</i> ,	343, 369, 585,
586, 588, 589, 591, 904	
843	
Gaṇapati, <i>m.</i> ,	1025n
Ganasobha, <i>m.</i> ,	

	NUMBER
Gaṇḍa, <i>Koṇḍapaḍmaṭi ch.</i> ,	581
Gaṇḍa, <i>Velanāṇḍu ch.</i> ,	582
Gaṇḍagōpāla (Ērasiddhi), <i>Telugu-Chōḍa ch.</i> ,	880
Gaṇḍagōpāla (Vijaya- ¹⁰), <i>do.</i> ,	884-887
Gaṇḍagōpāla (Vira-G ^o), <i>k.</i> ,	904
Gaṇḍamahēndra, <i>sur. of Chālukya-Bhīma II.</i> ,	560
Gaṇḍarāditya (?), <i>k.</i> ,	741
Gaṇḍarāditya, <i>Śilāhāra ch.</i> ,	316-321,
323, 327	
Gaṇḍarāditya, <i>Śilāhāra prince</i> ,	327
Gaṇḍarāditya, <i>son of Chōla k. (?) Madhurāntaka</i> ,	695
Gaṇḍarāditya (varman), <i>Chōla k.</i> ,	689, 712
Gaṇḍar-Dinakaraṇ, <i>k. (Gaṇḍarāditya ?)</i> ,	741
Gaṅga, <i>co., family, k., people</i> ,	5, 10, 64, 556n
Gaṅga, <i>Oḍḍavādi ch.</i> ,	600
Gaṅgā, <i>co.</i> ,	733, 735, 736
Gaṅgā, <i>queen of E. Chōl. Vijayāditya III. of</i>	
<i>Piṭṭapuram</i> ,	576
Gaṅga-Bāṇas,	669 ff.
Gaṅgadēva, <i>Śilāhāra ch.</i> ,	321
Gaṅgādharaśūri, <i>poet</i> ,	261
Gaṅgamahādēvi, <i>queen of Śinda (?) Sōmēśvara</i> ,	972
Gaṅga-maṇḍalam, <i>co.</i> ,	763
Gaṅga-Nārāyaṇa, <i>sur. of Bātuga II.</i> ,	127
Gaṅga-pāṇi, <i>co.</i> ,	702-704
Gaṅga-Pallavas,	644 ff.
Gaṅga-pāṇi, Gaṅga-pāṇi, <i>co.</i> ,	93, 98
Gaṅgapermāṇḍi Bhuvanaikavira Udayāditya,	
<i>ch.</i> ,	179
Gaṅgarāja, <i>Hoysala min.</i> ,	139, 386, 387,
389, 391-395, 398, 406, 407, 415	
Gaṅgarasa, <i>W. Gaṅga ch.</i> ,	384
Gaṅgas, Western,	108 ff.
Gaṅgavādi, <i>co.</i> ,	74n
Gaṅgegaṇḍa, <i>sur. of Chōla Rājendra-Chōla I.</i> ,	737
Gāṇḍēya, <i>family</i> ,	1070
Gaurāmbikā, Gauri, <i>queen of Bukkarāja I.</i> ,	474, 475, 484, 487
Gauri, <i>queen of Satyāśraya of Piṭṭapuram</i> ,	576
Gauta, Gautaya I., II., <i>Sāluva chiefs</i> ,	501
Ghayuvanta (P Vappuvanna), <i>Śilāra ch.</i> ,	307
Gōḍa-Mārtāṇḍa, <i>lord of Gōḷamba</i> ,	966
Gōḍavari, <i>vi.</i> ,	91n
Goggi, Goggirāja, <i>Śilāra ch.</i> ,	305, 307, 309
Gōgi, <i>Chōl. ch.</i> ,	331
Gōjjigadēva, s. a. Gōvindarāja IV.,	90
Gōkala, Gōkalla, <i>Śilāhāra ch. (Gōṅka)</i> ,	327
Gōkarna, <i>vi.</i> ,	212
Gōḷamba, <i>vi. (Kōḷamba)</i> ,	0
Golkonda, <i>vi.</i> ,	2 B

Haihaya, <i>family</i> ,	48, 86, 553, 576
Haihaya, <i>grandfather of Kārtavīrya</i> ,	583
Hammā, <i>s. a. Avvalladēvi</i> ,	331
Hari, <i>W. Gaṅga k.</i> ,	679
Harichandra, <i>poet</i> ,	329
Harihara I., <i>Vijayanagara k.</i> ,	454, 459, 465, 474	
Harihara II., <i>do.</i> ,	. 465-477, 478n,	
	479n, 480, 484, 487, 490, 1062	
Hariharaśāya, <i>s. a. (P) Harihara II.</i> ,	478
Harikēśarin, <i>Kādamba ch.</i> ,	168
Haripāla, <i>Śīlāra ch.</i> ,	310
Harivarman, <i>Kadamba k.</i> ,	611, 612
Harivarman, <i>W. Gaṅga k.</i> ,	. 108, 109, 111-113, 129	
Harsha, <i>Kanauj k.</i> ,	10, 17, 53, 56, 150
Harshavardhana, <i>s. a. Harsha</i> ,	18, 20, 25, 27
Hastimalla, <i>Gaṅga-Bāṇa k. Prithivīpati II.</i> ,		
	669-671, 681, 682, 685	
Hastimalla, <i>s. a. Attimallar</i> ,	1056, 1057
Hastināpura, <i>vi.</i> ,	1018-1020
Hemāchchhādanarāja, <i>sur. of Jaṭavarman Sun-</i>		
<i>dara-Pāṇḍya I.</i> ,	909n
Hemādideva, <i>Nikumbha ch.</i> ,	337

	NUMBER		NUMBER
Hemāmbikā, <i>queen of Dévarāya I.</i> ,	484, 487	Iraṭṭa-pāḍi, <i>co.</i> ,	714, 720, 744
Rēṭurā, <i>vi.</i> ,	354	Iriga, <i>son of k. Diṇḍi</i> ,	670
Himaṣitala, <i>k.</i> ,	969	Iṛivabedaṅgadēva, <i>s. a. (P) Iṛivabedaṅga Saty-</i>	
Hiranya, <i>Pallava k.</i> ,	635	āśraya,	152
Honnāvura, <i>vi. (Honavar)</i> ,	470	Iṛivabedaṅga Satyāśraya, <i>W. Chd. k.</i> ,	146,
Hosapaṭṭapa, <i>vi.</i> ,	456, 457	148-150, 179, 301, 712, 716	
Hoysaḷas,	383 ff.	Iṛmaḍi-Rāchamalla, <i>Sinda ch.</i> ,	253
Hoysaḷaseṭṭi, <i>m.</i> ,	970	Iṛuga, <i>leader of the Nāgattaras</i> ,	126
Hoysapa, Hoysapa, <i>s. a. Hoysala</i> ,	424, 847	Iṛuga, Iṛugapa, <i>Danḍēsa, son of Baicha</i> ,	462, 486
Huḷla, Huḷlamayya; Huḷlana, Huḷlapa, Huḷla-		Iṛugapa, <i>Danḍanātha, grandson of Baicha</i> ,	486
rāja, Huḷlayya, <i>Hoysala min.</i> ,	409-411, 413-415	Iṛugappa, <i>s. a. Iṛuga, Iṛugapa</i> ,	1062, 1063
I		Iṛuṅḍola, <i>k.</i> ,	409, 414
Iḍaiturai-nāḍu, <i>co.</i> ,	727	Iṛuṅḍola, <i>Sinda ch.</i> ,	253
Iḍḍhatējas, <i>sur. of Rāshṭrakūṭa k. Dhruva-</i>		Īśvara, <i>general of Nṛisīrāharāya</i> ,	502
rāja,	91	Īśvara, <i>Pallava Paramēśvaravarman I.</i> ,	20
Iḍigama, <i>s. a. Adiyama</i> ,	396n	Īśvara, <i>Sinda ch.</i> ,	233
Iḷāḍarāyar, <i>s. a. Lāṭarāja</i> ,	1075	Īśvarapōtarāja, <i>Pallava Paramēśvaravarman I.</i> ,	20
Iḷam, <i>co.</i> ,	691, 692, 727, 821, 822, 829,	Īśvaravarman, <i>Gaṅga-Pallava k.</i> ,	654, 655
	831, 832, 835, 836, 839,		
	840, 842, 847, 1075	J	
Iḷa-maṇḍalam, <i>co.</i> ,	710, 727	Jagaddēva, <i>s. a. (P) Jagaddēva</i>	
Iḷamuri-dēśam, <i>co.</i> ,	734	Tribhuvanamalla,	388, 409, 419, 584
Iḷaṅḡāśōgam (Lankāśōka), <i>co. (P)</i> ,	734	Jagaddēva Tribhuvanamalla, <i>ch. of Paṭṭi-</i>	
Iḷaṭṭa-pāḍi, <i>co.</i> ,	714, 729	Pombuchchapura,	237
Immaḍi-Bhairarasa-Oḍeya, <i>s. a. Bhairava II.</i> ,	993	Jagadēkabhūṣaṇa-Mahārāja, <i>Sinda (P) ch.</i>	
Immaḍi-Dēvarāya, <i>s. a. Vijayanagara k.</i>		Sōmēśvara,	972
Mallikārjuna,	497	Jagadēkamalla, <i>W. Chd. Jayasīma II.</i> ,	
Immaḍi-Nṛisīma, <i>Sāḷva ch.</i> ,	498n, 501	151-153, 185	
Indiradaṇ, <i>k. (Indraratha P)</i> ,	793	Jagadēkamalla II., <i>W. Chd. k.</i> ,	225, 229,
Indra, <i>pearl-necklace of</i> ,	727	232-238	
Indra, <i>Rāshṭrakūṭa k.</i> ,	150	Jagadēkamalla Malladēva, <i>Bāṇa k.</i> ,	663
Indra-bhaṭṭāraka, <i>E. Chal. prince</i> , 550-552,		Jagadēkamalla Permāḍi I., <i>Sinda ch.</i> ,	233, 234
557, 568n, 574n		Jagadēkavira, <i>sur. of Mārasīma II.</i> ,	136
Indradēva, <i>s. a. Indrarāja III.</i> ,	305	Jagannātha (Viśvanātha), <i>E. Chd. ch. of</i>	
Indrakīrtisvāmin, <i>Jaina teacher</i> ,	79n	Śrīkūṛmam,	579
Indrarāja, <i>Guj. Rāshṭrakūṭa ch.</i> ,	65, 67-70, 77	Jaganobbagaṇḍa, <i>sur. of Anna-Vēma</i> ,	594
Indrarāja, <i>Nikumbha ch.</i> ,	333, 337	Jaganobbagaṇḍa, <i>sur. of Dodḍa II.</i> ,	599
Indrarāja, <i>s. a. Indra-bhaṭṭāraka</i> ,	568n, 574n,	Jaganobbagaṇḍa, <i>sur. of Koṇḍaviḍu ch. Vēma</i> ,	596
1065n		Jagatikēsarīn, <i>sur. of Kākatīya Prōḍarāja</i> ,	588
Indrarāja, <i>Silāra ch.</i> ,	301	Jagattuṅga I., <i>s. a. Gōvindarāja III.</i> ,	67,
Indrarāja I., <i>Rāshṭrakūṭa k.</i> ,	71	73-75, 86, 91, 93, 105, 301, 305	
Indrarāja II., <i>do.</i> ,	53, 56, 66, 71, 305	Jagattuṅga II., <i>Rāshṭrakūṭa prince</i> ,	86,
Indrarāja III., <i>do.</i> ,	86-88, 91-93,	91, 93, 105, 301, 305	
105, 301, 305		Jagattuṅga III., <i>do.</i> ,	93
Indrarāja IV., <i>do.</i> ,	107, 131, 136	Jagattuṅga, <i>in verse for Jagattuṅga</i> ,	67n
Indraratha, <i>k.</i> ,	733	Jāhnavēya, <i>Jāhnaviya, family</i> ,	108,
Indravarmān Dhruvarāja, <i>governor of</i>		110-113, 129	
Rēvatidīpa,	7	Jaitapāla I., <i>s. a. Jaitugi I.</i> ,	33f

	NUMBER		NUMBER
Jaitasimha, Jaitrasimha, <i>min.</i> , . . .	334, 419	Jayanta (Trilochana), <i>mythical founder of</i>	
Jairapala I., <i>s. a. Jaitugi I.</i> , . . .	337, 342,	<i>Kadamba family</i> , . . .	249, 261, 269
	343, 370, 379	Jayantipura, <i>vi.</i> , . . .	218
Jaitrapala II., <i>s. a. Jaitugi II.</i> , . . .	379	Jāyapa-Nāyaka, <i>s. a. Jāya</i> , . . .	586
Jaitrasimha, Jaitasimha, <i>min.</i> , . . .	334, 419	Jayasimha, <i>Kērola k.</i> , . . .	989, 940, 959
Jaitugi I., <i>Dēvagiri-Yādava k.</i> , . . .	336, 351,	Jayasimha I., <i>E. Chal. k.</i> , . . .	549-552, 557,
	360, 369		563n, 564n
Jaitugi II., <i>do.</i> , . . .	357, 359, 369	Jayasimha II., <i>do.</i> , . . .	557
Jākavvā, <i>queen of W. Chdl. Taila II.</i> , . . .	150	Jayasimha I., <i>W. Chal. k.</i> , . . .	2, 5, 10, 150
Jakhapavva, <i>f.</i> , . . .	294	Jayasimha II., <i>W. Chdl. k.</i> , . . .	147, 151-158,
Jakirāja (Yaksharāja), <i>father of Hulla</i> , . . .	409		186, 331, 729
Jamnapa-Uḍaiyar, <i>son of Kampapa II.</i> , . . .	464	Jayasimha III., <i>W. Chdl. prince</i> , . . .	176, 184,
Janamējaya, <i>Pāṇḍava k.</i> , . . .	1017-1020		188, 753, 763n, 774, 1081, 1082
Jananāthanagarī, <i>vi.</i> , . . .	571	Jayasimhavarmarāja, <i>W. Chal. prince</i> , . . .	17
Jannāmbikā, <i>sister (?) of Harihara II.</i> , . . .	468	Jayāśraya (P), <i>W. Chal. Nāgavardhanarāja</i> , . . .	17
Jaṭavarman Kulāśekhara, <i>Pāṇḍya k.</i> , . . .	889, 890	Jayāśraya-Maṅgalarasārāja, <i>Guj. W. Chal.</i> , . . .	1n
Jaṭavarman Parākrama-Pāṇḍya, <i>do.</i> , . . .	927	Jayatsēna, <i>Utkala k.</i> , . . .	600
Jaṭavarman Sundara-Pāṇḍya I., <i>do.</i> , . . .	900-905,	Jayavarman, <i>k. of Brihatphalāyana gotra</i> , . . .	1014
	907-909	Jayavarman II., <i>Kādamba ch.</i> , . . .	210
Jaṭavarman Sundara-Pāṇḍya II., <i>do.</i> , . . .	912-918	Jhañjha, <i>Maurya ch.</i> , . . .	330
Jatiga I., <i>Śilāhāra ch.</i> , . . .	317, 327	Jhañjha, <i>Śilāra ch.</i> , . . .	305, 307, 309
Jatiga II., <i>do.</i> , . . .	315, 317, 321, 323, 327	Jhañjha, <i>do. (P)</i> , . . .	331
Jaṭilavarman, <i>Pāṇḍya k. (Neḍuñjadaiyan)</i> , . . .	937	Jimūtakētu, <i>father of Jimūtavāhana</i> , . . .	301,
Jaṭilavarman Ativirāma Śrīvallabha, <i>Pāṇḍya</i>			305, 307, 309
<i>k.</i> , . . .	935	Jimūtavāha, <i>s. a. Jimūtavāhana</i> , . . .	315
Jaṭilavarman Parākrama-Pāṇḍya Arikésarin,		Jimūtavāhana, <i>mythical ancestor of Śilāra</i>	
<i>do.</i> , . . .	928-931	(<i>Śilāra, Śilāhāra</i>) <i>family</i> , . . .	220n, 301,
Jaṭilavarman Parākrama-Pāṇḍya Kulāśekhara,			305, 307, 309, 315
<i>do.</i> , . . .	932	Jinachandra, <i>Jaina teacher</i> , . . .	120
Jaṭilavarman Śrīvallabha, <i>do.</i> , . . .	933	Jinadatta, <i>family of</i> , . . .	987, 993
Javanike-Nārāyaṇa, <i>sur. of Perumāle</i> , . . .	451	Jinanandin, <i>Jaina teacher</i> , . . .	2
Jaya, <i>Pallavādhirāja</i> , . . .	115	Jñānasakti-paṇḍita, <i>priest or sage</i> , . . .	190
Jāya, Jāyana, <i>general of Kākaiya</i>		Jōgama, <i>Kaḷachurya ch.</i> , . . .	288
Ganapati, . . .	585-587	Jōgambā, <i>f.</i> , . . .	414
Jayadēva-paṇḍita, <i>Jaina teacher</i> , . . .	129	Jōma (Jōyidēva) I., <i>Gutta ch.</i> , . . .	298
Jayadhara, <i>s. a. Kulōttunga-Chōla I.</i> , . . .	776, 784	Jōvidēva (Jōyidēva) II., <i>do.</i> , . . .	340
Jayaduttaraṅga, <i>sur. of Bātuga II.</i> , . . .	127	Jōyidēva I., <i>do.</i> , . . .	298
Jayakarna, <i>son of W. Chdl. Vikramāditya</i>		Jōyidēva II., <i>do.</i> , . . .	340, 351
VI., . . .	193		
Jayakēśin I., <i>Kādamba ch.</i> , . . .	164, 249, 254,		
	261, 269		
Jayakēśin II., <i>do.</i> , . . .	234, 235, 249, 254,		
	261, 269, 405n		
Jayakēśin III., <i>do.</i> , . . .	261, 262, 269		
Jāyamadēvi, Jāyamāmbā, Jāyāmbikā, <i>queen</i>			
<i>of Goṅka III.</i> , . . .	582		
Jāyamēru, <i>Bāṇa Vikramāditya I.</i> , . . .	662		
Jāyanandivarman, <i>Bāṇa k.</i> , . . .	663		
Jāyangonḍa-Chōla, <i>Chōla Rājādhirāja I.</i> , . . .	738-741		
Javanta, <i>Oḍḍavāddi ch.</i> , . . .	600		

K

Kachehya-Gaṅga, <i>sur. of Rājamalla (?) III.</i> , . . .	127
Kachehi, <i>s. a. Kāñchi</i> , . . .	100-102, 827
Kādamba, <i>people</i> , . . .	10
<i>Kādambavī</i> , . . .	641n
Kādambas, . . .	602 ff.
Kādambas, . . .	140n
Kādāram (Kaṭāha), <i>co.</i> , . . .	734-736, 1084
Kādava, <i>s. a. Pallava</i> , . . .	642, 847n
Kaikēya, <i>ch.</i> , . . .	614

	NUMBER		NUMBER
Kākati, <i>race of</i> ,	586	Kāmadēva, <i>father of</i> Kamalādēvi,	254, 255
Kākotīśa, <i>s. a.</i> Kākatiya,	589	Kāmadēva, <i>Kādamba ch.</i> ,	260, 424, 425
Kākatiyas,	584 ff., 1036	Kāmadēva, <i>Pāṇḍya k.</i> ,	415n, 416, 423
Kākatiya, <i>s. a.</i> Kākatiya,	584	Kāmadēva (Kāvapa), <i>brother-in-law of</i> Shashṭha II.,	269
Kakkaladēva, <i>Rāshtrakūṭa k.</i> Kakkarāja II., 105, 106, 301, 305		Kāmadēva Tribhuvanamalla, <i>Pāṇḍya ch.</i> ,	212
Kakkalla, <i>perhaps a Kalachuri k.</i> Kōkkalla,	369	Kāmakōṭi, <i>m.</i> ,	539, 542, 543, 545
Kakkara, <i>Rāshtrakūṭa k.</i> Kakkarāja II.,	232	Kāmākshi, <i>queen of</i> Saṅgama I.,	468
Kakkarāja, <i>Aḷachapura k.</i> ,	127	Kamalādēvi, <i>queen of</i> Śivachitta Permāḍi,	254, 255
Kakkarāja <i>or</i> Karkarāja, <i>Guj. Rāshtrakūṭa</i> <i>ch.</i> ,	65, 67-70, 77	Kambayya (Stambha), <i>son of (?) Rāshtrakūṭa</i> <i>k.</i> Dhruvarāja,	60
Kakkarāja I., II., <i>Guj. Rāshtrakūṭa kings</i> ,	54	Kambharasa, <i>W. Gaṅga ch.</i> ,	120
Kakkarāja <i>or</i> Karkarāja I., <i>Rāshtrakūṭa k.</i> , 53, 56, 61, 65, 66, 71, 305		Kambōja <i>k.</i> ,	734
Kakkarāja II. (Kakkaladēva), <i>do.</i> , 105, 106, 150, 232, 301, 305		Kammara, <i>Kamayyarsa, Sinda ch.</i> ,	144
Kākustha, Kākusthavarman, <i>Kadamba k.</i> , 602- 604, 606, 608, 610		Kampa, <i>Kampapa I., Vijayanagara k.</i> ,	459, 474
Kalachuri, <i>s. a.</i> Kalachurya,	288	Kampapa II., <i>do.</i> ,	460, 462-464
Kalachuryas,	275 ff.	Kampapa-Uḍaiyar, <i>s. a.</i> Kampapa II.,	463
Kālāñjara, <i>vi.</i> ,	240, 275, 277, 279, 280, 291, 293	Kampavarman, <i>probably s. a.</i> Kampavikrama- varman,	657, 658
Kālasēna (Sēna) I., <i>Raṭṭa ch.</i> ,	181, 201	Kampavikramavarman, <i>Gaṅga-Pallava k.</i> ,	656
Kālasēna (Sēna) II., <i>do.</i> ,	181, 193, 201	Kampili, <i>vi.</i> ,	171, 741n, 1083
Kalatsūri, <i>family</i> ,	5	Kāṁvadēvarāja, <i>Chāl. ch.</i> ,	271
Kalaturya, <i>s. a.</i> Kalachurya,	289	Kāṇagōpa, <i>Pallava k.</i> ,	635
Kaliballaha (Kalivallabha), <i>sur. of Rāshtrakūṭa</i> <i>k.</i> Dhruvarāja,	57	Kanauj, <i>vi.</i> ,	10, 17, 18, 20, 25, 27, 53, 56, 150
Kālidāsa, <i>poet</i> ,	10	Kanavadi (Gaṇapati), <i>k.</i> ,	741
Kālīga (P Kālī-Gaṅga), <i>Hoysala general</i> ,	713	Kāñchi, <i>vi.</i> ,	20, 62, 86, 603, 904, 931, 1066
Kalikāla, <i>legendary Chōla k.</i> ,	880	Kāñchiga, <i>Selara ch.</i> ,	94n
Kalindavarman, <i>Pallava k.</i> ,	635	Kāñchipura, Kāñchipuram, <i>vi.</i> , 10, 27, 219, 225, 248, 250, 617, 618, 621, 777, 1066	
Kalīnga, <i>co., people</i> , 5, 10, 566, 588, 708, 796, 801, 979		Kāñḍajūr-Śālai, <i>vi.</i> ,	700, 703, 704, 742n, 1077
Kalīnga-maṇḍalam, <i>co.</i> ,	775	Kandara, <i>k.</i> ,	1015
Kalivallabha, <i>sur. of Rāshtrakūṭa k.</i> Dhruvarāja,	57, 64, 75, 93	Kandhara, <i>s. a.</i> Kanhara,	359
Kali-Vishṇuvardhana, <i>E. Chāl. Vishṇuvar-</i> <i>dhana V.</i> ,	555, 557, 559, 560, 1065	Kaṇḍi I., II., <i>Odḍavādi chiefs</i> ,	600
Kaliyarttyaṅka, <i>sur. of E. Chāl. Vijayāditya</i> IV.,	559n	Kaṇḍ[e]varman, <i>Kadamba k.</i> ,	603
Kallabbarasi, <i>queen of</i> Bātuga II.,	130	Kanhara, <i>Kanhāra, Dēvāgiri-Yādava k.</i> , 356- 358, 360, 361, 366	
Kallēduppūr-maryādā, <i>di.</i> ,	1057	Kaṇḍigārāja, <i>ch.</i> ,	258n
Kalyāṇa, <i>vi.</i> ,	185, 253, 280	Kanna, <i>Kannakaira I., Raṭṭa ch.</i> ,	181, 201
Kalyāṇapura, <i>vi.</i> ,	271-273	Kanna, <i>Kannakaira II., do.</i> ,	189, 193, 201
Kalyāṇi, <i>W. Chālukyas of</i> ,	140 ff.	Kaṇṇapūr, <i>vi. (Vikramapura)</i> ,	436n, 903n
Kāma, <i>E. Chāl. ch. of Pithḥpuram</i> ,	576	Kannapa <i>or</i> Kennapa, <i>ch.</i> ,	143
Kāma, <i>father of</i> queen of Ammarāja II.,	566	Kannapa, <i>co.</i> ,	1084
Kāma (Kāvapa), <i>Dandānyaka</i> ,	294n	Kannara, <i>Rāshtrakūṭa k.</i> Krishnarāja II.,	85
Kāmadēva, <i>chiefs</i> ,	254, 321, 413	Kannara, <i>do.</i> ,	130
		Kannaradēva, <i>do.</i> ,	
		Kannaradēva, <i>Kannara°, Kannara°, Rāshtra-</i> <i>kūṭa k.</i> Krishnarāja III., 95, 96, 100-103, 190, 1056, 1053 ff.	
		Kannaradēva-Priṭhivigaṅgaraiyar, <i>Gaṅga ch.</i> 1055, 1067	
		Kannariga, <i>s. a.</i> Karpātaka,	364

	NUMBERS		NUMBERS
Kannēśvarā, <i>Rāshṭrakūṭa</i> k. Krishnarāja I.,	66	Kaṭaka, vi. (Cuttaek),	904n
Kannuḍaiipperumāṇ Ammaiaṣṣan, <i>Śēṅṅē</i> ch.,	820	Kāṭamareḍḍi, s. a. Kāṭa II.,	595
Kaṇṭhikā-Bēta, <i>E. Chal.</i> Vijayāditya V.,	576	Kāṭamareḍḍi-Vēṁireḍḍi (-Vēṁareḍḍi), s. a.	
Kaṇṭhīrava, <i>Mahīśūra</i> k.,	999	Kāṭaya-Vēma,	595, 597
Kaṇṭhīrava-Narasa, do.,	1004	Kāṭaya I., <i>great-grandfather of</i> Kāṭaya-	
Kaṇva, <i>ancestor of W. Gaṅga</i> kings,	670	Vēma,	595
Kāṇvāyana, <i>gōtra</i> ,	103, 112, 113, 129	Kāṭaya-Vēma or -Vēmayya, <i>Redḍi</i> ch. of	
Kanyakubja, vi.,	741n, 1083	<i>Rājamahēndranagara</i> ,	595-598
Kāpardika-dvīpa, co.,	254	Kāṭhaka, <i>probably s. a. Kaṭaka</i> k.,	904, 909
Kapardin I., <i>Śīlāra</i> ch.,	72, 305, 307, 309	Kāṭhāri, <i>sur. of Nṛsiṁharāja</i> ,	501
Kapardin II., do.,	73, 80, 305, 307, 309	Katta (Kārtavīrya) I., <i>Raṭṭa</i> ch.,	181, 201
Kapitthaka, vi.,	91n	Katta (Kārtavīrya) II., do.,	181, 192, 201
Kappe-Arabhaṭṭa, m.,	1032	Kattama (Kārtavīrya) III., do.,	263, 265
Kaṇḍikā, vi.,	1083	Kaṭṭāri, <i>sur. of Tirumalaidēva-mahārāja</i> ,	498
Karabāṭa, vi.,	238	Kāṭṭēri, vi.,	1048
Karāṇjapatra, vi.,	30	Kāṭṭirai, 'king of the forest,' title of the	
Kaṇayilladāta, <i>sur. of Chālukya-Bhima</i> II.,	566	<i>Pallavas</i> ,	655
Kāreya, <i>gaṇa</i> ,	120	Kattiyara, <i>W. Chal.</i> (?) k.,	61
Karikāla, <i>legendary Chōla</i> k.,	685, 712, 888	Kattiyaradēva, <i>Chal.</i> ,	232
Karikāla, <i>sur. of Chōla</i> k. Āditya II.,	712	<i>Kaumāra</i> , <i>grammar</i> ,	279n
Karikāla-Chōla, <i>sur. of Virarājendra</i> I.,	1081	Kaunāla, <i>Killeru lake</i> ,	10
Kariya-Perumāḷ-Periyanāyan	Narasimha,	Kāvapa (Kāmadēva), <i>brother-in-law of</i>	
<i>Māḍāṇu</i> ch.,	1086	Shashṭha II.,	269
Karkara, <i>Rāshṭrakūṭa</i> k.,	74	Kāvapa, Kāvapaṇṇa, <i>Daṇḍandya</i> k.,	293n, 294
Karkara, <i>Rāshṭrakūṭa</i> k. Kakkarāja II.,	150	Kāvēri, <i>ri.</i> ,	10, 74n, 76i
Karkarāja or Kakkarāja, <i>Guj. Rāshṭrakūṭa</i>		Kavibhūṣaṇa, <i>poet</i> ,	940
<i>ch.</i> ,	65, 67-69, 70, 77	Kavirāja (?), <i>poet</i> ,	352
Karkarāja or Kakkarāja I., <i>Rāshṭrakūṭa</i> k.,		Kayirūr Perumāṇār, <i>Māḍāṇu</i> ch.,	1073
	53, 56, 61, 65, 66, 71, 305	Kēḍala, <i>fort</i> ,	74n
Karṇa, <i>Chāl.</i> k.,	274	Kēḍarasakti, <i>priest or sage</i> ,	196
Karṇa, <i>Dēvagiri-Yādava</i> ,	334	Keladi, <i>prince of</i> ,	999
Karṇāṭa, co., k., <i>kingdom</i> , 530, 534, 539, 540,		Keladi-Sadāśiva-Nāyaka, <i>ch.</i> ,	1008
	542, 543, 545, 586, 904, 909, 999	Keladi-Sōmasēkhara-Nāyaka, <i>ch.</i> ,	998
Karṇāṭaka, <i>army</i> , k.,	53, 56, 864	Kēlyaladēvi, Keleyabbarisi, Keleyabbe,	
Kārōniri, <i>Bāṇa</i> ch.,	654	Kēliyadēvi, <i>queen of Hoysala</i> Vinayāditya,	
Karpūrasantarāja, <i>sur. of Anna-Vēma</i> ,	594		383, 398, 409
Karpūrasantarāja, <i>sur. of Doḍḍa</i> II.,	599	Kennapa or Kannapa, <i>ch.</i> ,	143
Kārtavīrya, <i>mythical ancestor of Kōṇaman-</i>		Kēraja, co., <i>people, race</i> ,	5, 10, 727, 798, 904
<i>dala chiefs</i> ,	583	Kēraja <i>kings</i> ,	939 ff.
Kārtavīrya (Katta) I., <i>Raṭṭa</i> ch.,	141, 181, 201	Kērajavarmān, Vira-K°,	948, 944, 949
Kārtavīrya (Katta) II., do.,	181, 192, 201, 220	Kērajavarmān, Vira-Rāma K°,	951, 952
Kārtavīrya (Kattama) III., do.,	263, 265, 266	Kērajavarmān, Vira-Ravi K°,	955
Kārtavīrya IV., do.,	264-268	Kēśava (Kēśimayya), <i>Daṇḍandya</i> k., 275, 277,	
Karuvūr, vi.,	835, 836, 840, 842		285, 291, 297
Kusapaṇṇa-Nāyaka, <i>ch.</i> ,	245, 279, 281	Kēśava, <i>min.</i> ,	271
Kāṣyapa, <i>gōtra</i> ,	542, 1016	Kēśavāditya, <i>ch.</i> ,	178
Kāṭa or Kāṭama-Nāyaka, <i>Kolamu</i> ch.,	574	Kēśavanātha, <i>min.</i> ,	988
Kāṭa II., <i>father of Kāṭaya-Vēma</i> ,	595	Kēśidēva (? Arikēsarin), <i>Śīlāra</i> ch.,	307
Kāṭachehūrī, <i>family</i> ,	10	Kēśimayya, Kēśirāja, Kēśirājayya, <i>Daṇḍa-</i>	
Kāṭāha (Kāḍāram, Kidāram), co	712n, 734n	<i>nāyaka</i> ,	275, 277, 285, 291, 292, 296, 297

	NUMBER		NUMBER
Kēta I., II., <i>Śrī-Dhānyakāṭaka chiefs</i> ,	590, 592n	Kollabigaṇḍa-Vijayāditya or -bhāskara, <i>E.</i>	
Kētaladāvi, <i>queen of W. Chāl. Sōmāśvara I.</i> , 167		<i>Chāl. Vijayāditya IV.</i> ,	563n, 566, 1065
Kētarāja, <i>s. a. Kēta II.</i> ,	589	Kollagira, <i>s. a. Kollāpura</i> ,	220
Kētarasa, <i>Kādamba ch.</i> ,	250n	Kollam, <i>co.</i> ,	708
Khaḍgāvalōka, <i>sur. of Dantidurga</i> ,	53	Kollāpura, Kollāpuram, <i>vi.</i> ,	150, 154, 220, 325, 413, 744, 748n, 751, 1034, 1080
Khaṇḍeya-Kāra-Kāmeya-Nāyaka, <i>ch.</i> ,	335	Kolleru, <i>lake</i> ,	10, 582n
Khōṭaka, <i>vi.</i> ,	68, 70, 91	Kollipākā, Kollippākkai, <i>vi.</i> ,	727, 800
Khiligiḷadurga, <i>vi.</i> ,	315	Komaragirireddi, <i>son of Kātaya-Vēma</i> ,	597, 598
Khōlōśvara, <i>general</i> ,	352, 353	Kō Mārāṇ-Jadaiya, <i>Pāṇḍya k.</i> ,	938
Khōṭika, Khōṭṭiga, <i>Rāshtrakūṭa k.</i> , 104, 105,	301, 305	Komara-vedēga, <i>sur. of Eregaṅga II.</i> ,	127
Kiḍāram (Kaṭāha), <i>co.</i> ,	712n	Kommarāja, <i>m.</i> ,	167
Kikāṭa, <i>Maurya ch.</i> ,	330	Kōnamaṇḍala, <i>di.</i> ,	583
Kiḷappārār, <i>vi.</i> ,	952, 958	Kōpasthala, <i>di.</i> ,	593n
Kiḷigiḷadurga, <i>vi.</i> ,	315	Koṇḍapaḍmaṭi, <i>di.</i> ,	581
Kiraṇapura, <i>vi.</i> ,	559, 560	Koṇḍarāja, <i>ch.</i> ,	521, 522, 530
Kirātārjunīya,	115	Koṇḍaviḍu (Koṇḍavīṭi), <i>vi.</i> ,	508, 509, 593-596, 1064
Kirtinandin, <i>Jaina teacher</i> ,	119	Kōṇērīmēlkoṇḍa, <i>title of Kulōttuṅga-Chōla</i>	
Kirti-Nārāyaṇa, <i>sur. of Govindarāja III.</i> ,	75	III.,	820
Kirti-Nārāyaṇa, <i>sur. of Indrarāja III.</i> ,	86n	Kōṇērīmēlkoṇḍān, <i>title of a Vira-Chōla</i> ,	875
Kirtipura (P), <i>vi.</i> ,	1016	Kōṇērīmēnkoṇḍa, <i>title of Kulōttuṅga-Chōla</i>	
Kirtirāja, <i>s. a. Kirtivarman I.</i> ,	12	III.,	819
Kirtirāja, <i>Śilāhāra ch.</i> ,	317, 321, 327	Kōṇēriṇmaikoṇḍa, <i>title of kings</i> ,	819n
Kirtivarman II., <i>Kādamba ch.</i> ,	173	Kōṇēriṇmaikoṇḍān, <i>title of Kēraḷa k. Ravi-</i>	
Kirtivarman I., <i>W. Chāl. k.</i> ,	3, 5, 9, 10, 12, 13, 17, 18, 20, 25, 27, 150, 547, 549, 551, 568	varman,	939
Kirtivarman II., <i>do.</i> ,	48-50, 53, 56, 62, 71n, 150	Kōṇēriṇmaikoṇḍān, <i>title of kings</i> ,	876-879
Kirtivarman III., <i>W. Chāl.</i> ,	150	Kōṇēriṇmaikoṇḍān, <i>title of Kulōttuṅga-Chōla</i>	
Kirtivarmanrāja, <i>s. a. Kirtivarman I.</i> ,	17	III.,	835
Kishkindhyā-nagarī, <i>vi.</i> ,	1017	Kōṇēriṇmaikoṇḍān, <i>title of Virarājendra I.</i> ,	1081
Kisuvola, <i>vi.</i> ,	21	Kōṇērmaikoṇḍān, <i>title of Pāṇḍya kings</i> ,	933-935
Kitthipura (P Kirtipura), <i>vi.</i> ,	1016	Koṅgaṇa-dēsam, <i>co.</i> ,	763n
Kōchchaṅkaṇ, Kōchchaṅkappān, <i>legendary</i>		Koṅgaṇi-mahādhiraḷa, or -mahārāja, or -rāja,	
<i>Chōla k.</i> ,	685, 712	<i>title of W. Gaṅga kings</i> ,	111-115
Koḍagu (Coorg) <i>chiefs</i> ,	1006, 1008, 1009, 1011	Koṅgaṇivarma-dharmamahādhiraḷa or -dharma-	
Kōḍōṇmaikoṇḍān, <i>title of Bhāskara Ravivar-</i>		mahārājādhiraḷa, <i>do.</i> ,	108, 111, 113, 116, 129
<i>man</i> ,	962	Koṅgaṇi-vriddharāja, <i>do.</i> ,	114, 115
Kōkkili, <i>Telugu-Chōla ch.</i> ,	888	Koṅgaṇivarma-dharmamahārājādhiraḷa, <i>do.</i> ,	133
Kōkkala, Kōkkalla, <i>Chōḷi k.</i> ,	86, 91, 105	Koṅgaṇivarma-dharmamahārājādhiraḷa, <i>do.</i> ,	110
Kōkkila, <i>Oḍḍavādi ch.</i> ,	600	Koṅgaṇi-dharmamahārāja, <i>do.</i> ,	659
Kōkkilāpaḍi, <i>queen of Parāntaka I.</i> ,	1072	Koṅgaṇi-mahārājādhiraḷa, <i>do.</i> ,	121
Kōkkili, <i>E. Chāl. k.</i> ,	557	Koṅgaṇivarma-dharmamahārāja or -dharma-	
Kōkkili, <i>legendary Chōla k.</i> ,	685, 712	mahārājādhiraḷa, <i>do.</i> ,	95, 124, 125, 127-132, 660, 723, 724
Kōḷāla, Kōḷāla, Kōḷālapura, Kōḷālapura, <i>vi.</i> ,	95, 100, 130, 133, 179n, 205n	Koṅkaṇa, <i>co.</i> ,	10, 34n, 72, 73, 80, 212, 224, 274, 307, 729, 763n
Kōḷamba, <i>vi.</i> ,	939, 966	Koṅkaṇa, <i>Pāṇḍya of</i> ,	140n
Kolani-Kātama-Nāyaka, <i>Kolanu ch.</i> ,	574	Koṅkaṇi, <i>W. Gaṅga k.</i> ,	
Kolanu, <i>vi.</i> ,	574	Koṅkaṇika, <i>mythical Gaṅga</i> ,	

	NUMBER		NUMBER
Konnátavāḍi-vishaya, <i>di.</i> ,	589	Krishnavarman II., <i>Kadamba k.</i> ,	614
Koppam, <i>vi.</i> ,	744-746, 748, 749, 751, 1080	Krishnavernā, <i>vi.</i> ,	56
Kōpperuñjiṅga, <i>k.</i> ,	847	Kshatriyamalla, <i>sur. of</i> Nandivarman Pallava-	
Koppulakāpa-Nāyaka, <i>Pitṭhāpurī ch.</i> ,	601	malla,	635
Kōsala, <i>people</i> ,	10	Kshullakapura, <i>s. a.</i> Kollāpura,	321n
Kōśalai-nāḍu, <i>co.</i> ,	733	Ksburikākalivētāla, <i>sur. of</i> Anna-Vēma,	594
Kōṭa-Bayyalamahādēvi, <i>s. a.</i> Payyamāmbā,	592	Kshurikāśahāya, <i>do.</i> ,	596
Kōṭa-Kētarāja, <i>s. a.</i> Kōta II.,	590	Kubja, <i>poet.</i> ,	603
Kōṭaya, <i>Redḍi ch. of</i> Rājamahēndranagara,	589	Kubja-Vishnu, <i>s. a.</i> Kubja-Vishnuvardhana,	
Kōṭṣa, <i>family of</i> ,	517		581, 1065n
Kōṭṣārādhyā, <i>m.</i> ,	475	Kubja-Vishnuvardhana, <i>E. Chal.</i> Vishnuvar-	
Kōṭṭīrtha at Kollāpura,	150	dhana I.,	557, 559, 568, 574, 576, 581n
Kotta-maṇḍala, <i>di.</i> ,	713	Kūḍal, <i>vi.</i> (Madhurā),	1088
Kōṭṭāra, Kōṭṭāru, <i>fort.</i> ,	764, 793	Kūḍalaśāgam, Śāngamam, <i>vi.</i> ,	753, 1081, 1082
Kōṭṭiga (Khotṭiga), <i>Rāshtrakūṭa k.</i> ,	104	Kudamalai-nāḍu, <i>co.</i> (Malabar),	704, 764
Kovalāla, <i>s. a.</i> Kōlāla,	124, 125	Kuḍiyavarman I., II., <i>Velanāṇḍu chiefs</i> ,	592
Krishna, <i>Dēvagiri-Yādava</i> Kanhava,	356-	Kūḍūra, <i>vi.</i> ,	1014
	361, 366, 369, 370, 379	Kūḍūrahāra, <i>di.</i> ,	1014n
Krishna, <i>Kalachurya k.</i> ,	283	Kuḷam, <i>vi.</i> (Ellore),	795, 833
Krishna, <i>Paramāra k.</i> , or <i>Rāshtrakūṭa</i>		Kulamānikkaṇ Irāmādēvaṇ, <i>Muppi ch.</i> ,	1089
Krishnarāja II.,	559	Kulamānikkerumāpār, <i>do.</i> ,	1080
Krishna, <i>Rāshtrakūṭa k.</i> ,	150	Kuḷaṇ, <i>s. a.</i> Kuḷam,	833
Krishnadēva, <i>Koṅkaṇa governor</i> ,	379	Kuḷaṇūr, <i>do.</i> ,	833
Krishnadēva-mahārāja, <i>s. a.</i> Krishnarāja,	502	Kulaśekhara, Jaṭavarman, <i>Pāṇḍya k.</i> ,	880, 890
Krishna-Kēśava (Kēśimayya), <i>Daṇḍanāyaka</i> ,	297	Kulaśekhara I., Mājavarman, <i>do.</i> ,	911, 919-921
Krishnamāmbā, <i>Krishnāmbā, wife of min.</i>		Kulaśekhara II., Mājavarman, <i>do.</i> ,	922-924
Timma,	508	Kulaśekhara, Parākrama-Pāṇḍya Jaṭilavarman,	
Krishnapa-Nāvaka, <i>Madhurā ch.</i> ,	542	<i>do.</i> ,	932
Krishnapapa-Nāyaka, <i>chiefs</i> ,	521, 523, 528,	Kulaśekharaḍēva, <i>Kēraḷa k.</i> Ravivarman,	939, 940
	533, 536, 541, 546	Kulaśekharaṅka, <i>k. or ch.</i> ,	234
Krishnapapa-Nāyaka Ayya or Ayyaṇ, <i>ch.</i> ,	535, 544	Kūḷi-āchārya, <i>Jaina teacher</i> ,	66
Krishnarāja, <i>k.</i> ,	969	Kulōttunga, <i>s. a.</i> Kulōttunga-Chōḍa I.,	571, 572
Krishnarāja, <i>Mahisūra k.</i> ,	1002, 1004, 1005	Kulōttunga-Chaṅgāḷa-Mahāḍēva, <i>ch.</i> ,	988
Krishnarāja I., II., <i>Nikumbha chiefs</i> ,	333, 337	Kulōttunga-Chōḍa I., <i>E. Chal. k.</i> (<i>s. a.</i> Kulōt-	
Krishnarāja I., <i>Rāshtrakūṭa k.</i> ,	55, 56,	tuṅga-Chōḷa I.),	571-574, 582
	61, 64-66, 70, 84, 86, 91, 93, 105, 301, 305	Kulōttunga-Chōḍa II., <i>do.</i> (<i>s. a.</i> Kulōttunga-	
Krishnarāja II., <i>do.</i> ,	78, 82-86, 91, 93,	Chōḷa II.),	574, 581
	105, 130, 268n, 301, 305, 559n, 663n, 1065n	Kulōttunga-Chōḷa I., <i>Chōḷa k.</i> ,	225n, 766-
Krishnarāja III., <i>do.</i> ,	93-108, 105, 107, 127,		793, 1085
	180, 181, 301, 305, 328, 712, 1056n, 1058 ff.	Kulōttunga-Chōḷa [II. P], <i>do.</i> ,	810, 811
Krishnarāja Akālavarsha, <i>Guj. Rāshtrakūṭa</i>		Kulōttunga-Chōḷa III., <i>do.</i> ,	814-833,
<i>ch.</i> ,	81		835-842, 1087, 1098
Krishnarāja-Voḍeyar, <i>Mahisūra k.</i> ,	1012, 1013	Kulōttunga-Manma-Gotkarāja, <i>s. a.</i> Gotka	
Krishna Rāma, <i>general of</i> Chōḷa Rājārāja I.,	716	III.,	582
Krishnarāja, <i>Vijayanagara k.</i> ,	502-513,	Kulōttunga-Priṭhivīśvara, <i>Velanāṇḍu ch.</i> ,	583
	519, 530n, 1064	Kumāra, <i>poet.</i> ,	681n
Krishnavallabha, <i>Rāshtrakūṭa</i> Krishnarāja		Kumārāgiri, <i>Redḍi ch. of</i> Koṇḍavidu,	596
II.,	83, 1065	Kumāra-Kampāna-Uḍaiyar, <i>s. a.</i> Kampāna II.,	464
Krishnavarman, <i>Kadamba k.</i> ,	112-115	Kumāra-Lakshma, -Lakshmidēva, -Lakshmi	
Krishnavarman I., <i>do.</i> ,	613, 614	dhara, <i>Daṇḍanāyaka</i> ,	433

	NUMBER		NUMBER
Kumārānandin, <i>Jaina teacher</i> ,	119	Lakshmi, <i>mother of poet Śrīvallabha</i> ,	596
Kumbāḍi, <i>ch.</i> ,	84	Lakshmi, <i>queen of Bhīllama II.</i> ,	323, 329, 331
Kundāchehi, <i>f.</i> ,	119	Lakshmi, <i>queen of Kādamba Vijayāditya III.</i> ,	261
Kundakadēvi, <i>queen of Amoghavarsha III.</i> ,	105	Lakshmi (Lakshmidēvi, Lakshmimati, Lakshmyambike), <i>wife of Gaṅgarāja</i> ,	386, 387, 389-391, 393, 395
Kundamarasa, <i>ch.</i> ,	152	Lakshmi, <i>wife of Jagattunga II.</i> ,	86, 91, 105
Kundāmbikā, <i>queen of Maṇḍa II.</i> ,	581	Lakshmi, <i>wife of Śālva-Timma</i> ,	508, 509
Kundapaṇ, <i>m.</i> ,	1076	Lakshmidēva, <i>father of Kāmadēva (Kāvana)</i> ,	269
Kundasakti, <i>Sēndra k.</i> ,	16	Lakshmidēva I., <i>Raṭṭa ch.</i> ,	235, 266
Kundaṭṭe, <i>son of Baṅkēya</i> ,	1055	Lakshmidēva II., <i>do.</i> ,	268
Kundavā, <i>queen of E. Chal. Vimalāditya</i> ,	569, 570	Lakshmidēvi (Lakmadēvi), <i>queen of Hoysala Vishnavardhana</i> ,	409, 434
Kundavai Ālvār, <i>younger sister of Kulōttunga-Chōla I.</i> ,	784	Lakshmidēvi, <i>queen of Sēna II.</i> ,	265
Kundavaiyār, <i>elder sister of Chōla Rājārāja I.</i> ,	716, 722	Lakshmidhara, <i>s. a. Lakshmidēva I.</i> ,	266
Kundavaiyār, <i>queen of Bāna Vikramāditya I.</i> ,	660	Lakshmidhara, <i>son of Bhaskarācārya</i> ,	337
Kūṇḍi, <i>co.</i> ,	141	Lalitakīrti, <i>Jaina priest</i> ,	985
Kuṇilapura, <i>for Kuvalālapura</i> ,	659	Lalitānkura, <i>Pallava k.</i> ,	623, 626
Kunkumamahādēvi, <i>sister of Chōl. Vijayāditya-vallabha</i> ,	183	Lankā, <i>island</i> ,	904
Kuṇiyama, <i>ch.</i> ,	1024	Lankāśōka, <i>s. a. Maṅgāsōgam</i> ,	734
Kuntala, <i>co.</i> ,	761	Lāṭa, <i>co., people</i> ,	10, 65, 67-69, 77, 568n, 586
Kunūṅgil, <i>di.</i> ,	66	Latalaura, <i>vi.</i> ,	191
Kūṭapa, <i>universal monarch</i> ,	940	Lāṭarāja, <i>father of Mahādēvaḍi</i> ,	1075
Kuppēya, <i>ch.</i> ,	1054	Lāṭarāja Vira-Chōla, <i>ch.</i> ,	698
Kuru, <i>kula</i> ,	1017	Lattalūr, Lattalūra, Lattanūr, Lattanūra, <i>vi.</i> ,	75, 158, 181, 201, 220, 265, 266, 268
Kurugōḍadurga, <i>vi.</i> ,	253	Leṇḍeyarasa, <i>ch.</i> ,	88
Kurumārathyā, <i>vi.</i> ,	547	Linga, Liṅgama-Nāyaka, <i>Vēḷūr ch.</i> ,	539
Kurundaka, <i>vi.</i> ,	86	Linga-Rājendra-Voḍeyar, <i>Koḍagu chiefs</i> ,	1008, 1009, 1011
Kuvalāla, Kuvalālapura, <i>s. a. Kōlāla</i> ,	120, 132, 653n, 660n, 670, 708n, 724n, 837	Lōka-bhūpālaka, -mahipāla, <i>Kōnamanḍala ch.</i> ,	583
Kuvēra, <i>nine treasures of</i> ,	729	Lōkaditya, <i>Pallava k.</i> ,	632
		Lōkamahādēvi, <i>queen of Chālukya-Rhīma II.</i> ,	563-567, 1065
		Lōkamahādēvi, <i>queen of Chōla Rājārāja I.</i> ,	716, 1076
		Lōkamahādēvi, <i>queen of W. Chal. Vikramāditya II.</i> ,	44-46, 48
		Lōkamahipāla, <i>s. a. Lōkabhūpālaka</i> ,	583
		Lōkāmbikā, <i>ke. mother of Hulla</i> ,	409, 413
		Lōka-Vidyādhara, <i>m.</i> ,	135
		Lokkigunḍi, <i>vi.</i> ,	419, 420
		Lōlla-Lakshmidhara Yajvan, <i>poet</i> ,	509
		Lōvabikki, <i>Chōla ch.</i> ,	1065
		M	
		Māchikabbe, <i>mother of Śāntaladēvi</i> ,	400n, 408
		Mādamalingam, <i>co. or vi.</i> ,	734

	NUMBER		NUMBER
Maḍapalla, <i>Ōli, vi.</i> ,	591, 592	Mahārāja-Śarva, <i>sur. of Amoghavarsha I.</i> , 68, 70, 71	
Mādēvi (Mahādēvi), <i>queen of Ācha II.</i> ,	224	Mahārāja-Shaṇḍa, <i>do.</i> ,	84
Mādēvi, <i>queen of Kārtavīrya IV.</i> ,	268	Mahārāshṭraka, <i>co.</i> ,	10
Mādhava, <i>Kākatīya k. Mahādēva</i> ,	589	Mahārāshṭrakūṭa, <i>lineage</i> ,	191
Mādhava, <i>probably brother of Bhōganātha</i> ,	459n	Mahāsēna, <i>Jaina teacher</i> ,	167
Mādhava, <i>W. Gaṅga ch.</i> ,	1070	Mahāvali, <i>s. a. Mahābali</i> ,	666
Mādhava, <i>W. Gaṅga k.</i> ,	670	Mahāvali-B[ā]ṇarasa, <i>designation of Bāṇa</i>	
Mādhava I., <i>do.</i> ,	108, 111-113, 129	<i>kings</i> ,	666
Mādhava II., <i>do.</i> ,	111-115, 129	Mahāvali-Vāṇarāja, <i>ṛāya, do.</i> , 644, 651, 664, 665	
Mādhavabhaṭṭa, <i>poet</i> ,	563n, 566n	Mahendra, <i>s. a. Mahēndravarman I.</i> ,	624
Mādhavachandradēva, <i>Jaina teacher</i> ,	406	Mahendra, <i>s. a. Mahēndravarman II.</i> ,	20
Mādhavarāja, <i>min. of Harihara II.</i> ,	471	Mahendra, <i>s. a. Mahēndravarman III.</i> ,	632
Mādhavatti, <i>k.</i> ,	50	Mahēndrapōtarāja, <i>Pallava k.</i> ,	623
Madhurā, <i>Pāṇḍyas of</i> ,	889 ff.	Mahēndravarman, <i>do.</i> ,	641
Madhurā, <i>vi.</i> ,	542, 904, 909	Mahēndravarman I., <i>do.</i> ,	623-626, 634, 635
Madhurāntaka, <i>Chōla k.</i> ,	695n, 696, 712	Mahēndravarman II., <i>do.</i> ,	628, 634, 635
Madhurāntaka Pottappi-Chōla, <i>Telugu-Chōla</i>		Mahēndravarman III., <i>do.</i> ,	632
<i>ch.</i> ,	880	Mahēndravarman, <i>Telugu-Chōla ch.</i> ,	888
Madhurāntakī, <i>queen of Kulōttunga-Chōla I.</i> ,	572	Mahēśvara, <i>poet, son of Śrīpati</i> ,	343
Madhusūdana, <i>k.</i> ,	741	Mahēśvara, <i>Mahēśvarāchārya, poet and</i>	
Madhusūdanasūtri, <i>poet</i> ,	249	<i>astronomer</i> ,	337, 343
Madirai, <i>vi.</i> ,	621, 634, 670, 683-	Mahīpāla, <i>perhaps Pāla k. Mahīpāla I.</i> ,	733
	693, 695, 1072	Mahīpālaṇḍu, <i>Kōnamāṇḍala ch.</i> ,	583
Mādirāja, <i>Sāluva ch.</i> ,	501	Mahīśūra, <i>Mahīśūra-pattana or -pura, vi.</i> , 995,	
Mādirayya, <i>min.</i> ,	322	999, 1002, 1004, 1005, 1012, 1013	
Mādisūdanāṇ (Madhusūdana), <i>k.</i> ,	741	Mahōdaya, <i>vi.</i> ,	91
Madra, <i>co.</i> ,	5	Maiduna-Chauḍayya, <i>m.</i> ,	971
Madurai, <i>vi.</i> ,	821, 822, 824-832,	Mailaladēvi, <i>queen of Gutta Vikramāditya</i>	
	835-840, 842, 1073-1075, 1087, 1088	III.,	363
Madura-maṇḍalam, <i>co.</i> ,	733	Mailaladēvi, <i>Mailaladēvi, queen of Sēna I.</i> , 181, 201	
Magadha, <i>co.</i> ,	5	Mailalamahādēvi, <i>queen of Jayakēsin II.</i> , 249,	
Magara, <i>kingdom</i> ,	847n		254, 261, 269
Māghanandi-bhaṭṭārakadēva, <i>Jaina teacher</i> ,	975	Mailāpa, <i>anvaya</i> ,	120
Māghanandin, <i>do.</i> ,	413	Mailigidēva, <i>perhaps s. a. Mallugi</i> ,	584
Māghanandi-saiddhāntika, <i>Maṇḍalāchārya</i> ,	220	Maisūru, <i>vi.</i> ,	995
Māgutta, <i>Gutta ch.</i> ,	223	Mākanabbe, <i>wife of Māra (Māramayya)</i> ,	389
Mahābali, <i>Dānava</i> ,	668	Makara, <i>kingdom</i> ,	434, 847n
Mahābali, <i>family of</i> ,	651, 659-661, 664, 665	Maladhāridēva, <i>Jaina teacher</i> ,	398, 968
Mahābhārata, <i>Telugu translation of</i> ,	577	Maladhāridēva Mallishēpa, <i>do.</i> ,	969
Mahādēva, <i>Dandānāyaka</i> ,	229, 240	Malāḍu, <i>di.</i> ,	1058, 1086
Mahādēva, <i>Dēvagiri-Yādava k.</i> ,	362-370, 379	Malai-nāḍu, <i>Malaiya-nāḍu, di.</i> ,	1058
Mahādēva, <i>Kākatīya k.</i> ,	585, 586, 588, 589	Malaiyakula, <i>family of Malai-nāḍu chiefs</i> ,	1058
Mahādēvadi, <i>queen of Chōla Rājāditya</i> ,	1075	Malaiyūr, <i>co. or vi.</i> ,	734
Mahādēvi (Mādēvi), <i>queen of Ācha II.</i> ,	224	Malāmbikā (Mallādēvi), <i>queen of Harihara</i>	
Mahādēvi, <i>queen of Jayakēsin III.</i> ,	269	II.,	468, 487
Mahākāla, <i>general of Chālukya-Bhīma I.</i> ,	558	Māl-Ari-Kēsavaṇ, <i>Aravapai, m.</i> ,	1046
Mahāmalla kula, <i>Pallava family</i> ,	20n, 627	Mālava, <i>Mālava, people or k.</i> ,	10, 64, 409
Mahamandasāhu, <i>Golkonḍa k. Muḥammad</i>		Malikibharāma, <i>Golkonḍa k. Malik Ibrāhīm</i> , 539	
<i>Shāh</i> ,	539	Mālkḥēd, <i>Rāshṭrakūṭas of</i> ,	63 ff.
Mahara, <i>kingdom</i> ,	847	Malla, <i>ch. of Durjaya family</i> ,	800n

	NUMBER		NUMBER
Malla, <i>E. Chal.</i> Yuddhamalla II.,	560	Maṅgapa, son of Baicha,	456
Malla, <i>Gutta ch.</i> ,	223	Maṅgarāja, poet,	983
Malla (Mallerāja), <i>Koṇḍapaḍmaṭi ch.</i> ,	581n	Maṅgi. k.,	556, 559, 560
Malla, poet,	747	Maṅgi-yuvarāja, <i>E. Chal. k.</i> ,	552, 557, 583
Malla, s. a. Mallapa III.,	576	Māṇikādēvi, queen of Kādamba 'Iribhuvana-	
Malla I., II., <i>Velanāṇḍu chiefs</i> ,	582	malla,	269
Malla or Mallisaiṭṭi, 'oṣeṭṭi, brother of Bicha,		Māṇikyadēvi, queen of Chāl. ch. Sōmadēva	
351, 357, 358, 360		(Sōmēśvara),	274
Malladēva Jagadēkamalla, <i>Bāṇa k.</i> ,	663	Māṇikyanandin, <i>Jaina teacher</i> ,	414
Malladēva Nandivarman, do.,	668	Maṇipāga, <i>Śaṭukika ch.</i> ,	67
Mallādēvi, s. a. Malāmbikā,	468, 487	Maṇjaya, <i>Hoysala general</i> ,	713
Mallāmbikā, queen of Guṇḍa III.,	501	Māṇikāditya, <i>Oḍḍavādī ch.</i> ,	600
Mallāmbikā, queen of Kāṭaya-Vēma,	596n	Manma-Chōḍa II., <i>Kōṇamanḍala ch.</i> ,	583
Mallapa-Oḍeyar, dependent of Harihara II.,	470	Manma-Manḍa, <i>Koṇḍapaḍmaṭi ch.</i> ,	581n
Mallanārādhyavrittika, poet,	475	Manma-Satya II. (Manma-Satti), <i>Kōṇaman-</i>	
Mallapa I., II., III., <i>E. Chālukyas of</i>		ḍala ch.,	583
<i>Piṭhāpuram</i> ,	576	Manmasiddha, 'siddhi, <i>Telugu-Chōḍa ch.</i> ,	880, 881
Mallapaḍēva-Chakravartin, s. a. Mallapa III.,	576	Mannai, camp of,	727
Mallappa-Nāyakkar, m.,	1049	Mannakkkaḍagam ('ḍakkam), vi.,	727
Mallapp-Oḍeyar (Mallinātha), son of Bukka I.,	456n	Maṅṅār, <i>Gulf of</i> ,	764
Mallaya, <i>Velanāṇḍu ch.</i> ,	582	Maṇṇegrama, vi.,	117
Mallayavve, queen of Dēvarāja I.,	483	Manōratha, m.,	837, 343
Mallidēva, <i>Danḍanātha</i> ,	386	Mantena-Guṇḍa, Manthena-Guṇḍa, s. a.	
Mallidēva, <i>Danḍanāyaka</i> ,	447	<i>Mantrakūṭi ch. Guṇḍa</i> ,	586
Mallidēva (Malla), <i>Gutta ch.</i> ,	223, 298	Mantrakūṭa, vi.,	584
Mallidēva, <i>Kōṇamanḍala ch.</i> ,	583	Mānyakhēṭa, vi.,	74, 86, 91-94, 105
Mallikārjuna, <i>Raṭṭa ch.</i> ,	265, 266	Mānyapura, vi.,	118, 119
Mallikārjuna, <i>Śilāra ch.</i> ,	311	Māra (i.e. Mārava?) army,	1087
Mallikārjuna, <i>Vijayanagara k.</i> ,	497, 499	Māra (Māramaya), grandfather of Gaṅgarāja,	389
Mallinātha, poet,	989	Māra, grandfather of Kāṭaya-Vēma,	595
Mallinātha, s. a. Mallapp-Oḍeyar,	456n	Mārakkarasa, ch.,	58
Mallinātha-Voḍeyar, ch.,	456, 457	Mārāpa, <i>Vijayanagara prince</i> ,	459, 474
Mallishēṇa Maladhāridēva, <i>Jaina teacher</i> ,	969	Mārāsarva, <i>W. Gaṅga (?) k.</i> ,	64, 122n
Mallugi, <i>Dēvagiri-Yādava k.</i> , 334, 351, 369, 584n		Mārasimha, <i>Śilāhāra ch.</i> , 315, 317, 321, 323, 327	
Māmvaṇirāja, <i>Śilāra ch.</i> ,	308	Mārasimha I., <i>W. Gaṅga k.</i> ,	670
Mānābharāṇa, <i>Ceylon k.</i> ,	741, 745	Mārasimha II., do.,	103, 106, 129-132, 136
Maṇalera, <i>Sagara ch.</i> ,	95	Mārasimhadēvarasa, ch.,	228
Māpāvalōka, sur. of Rāshtrakūṭa ch. (?)		Mārasingayya, father of Śāntaladēvi,	400n
Vijayāditya,	56	Mārassalpa, (<i>W. Gaṅga k.</i> (Mārāsarva),	122
Mānavira, governor of Kāñchi,	1066	Māravarman, <i>Pāṇḍya k.</i> ,	937
Maṇḍa I., II., <i>Koṇḍapaḍmaṭi chiefs</i> ,	581	Māravarman Kulasēkhara I., do.,	911, 919-921
Maṇḍana, s. a. Maṇḍa I.,	581	Māravarman Kulasēkhara II., do.,	922-924
Maṇḍerāja, <i>Koṇḍapaḍmaṭi ch.</i> ,	581n	Māravarman Parākrama-Pāṇḍya, do.,	925, 926
Māṇḍhātri, progenitor of Maurya family,	330	Māravarman Sundara-Pāṇḍya I., do.,	891-893
Māṇḍhātriyarman, <i>Kādamba k.</i> ,	607	Māravarman Sundara-Pāṇḍya II., do.,	897-899
Maṅgalarāja, s. a. Maṅgalēśa,	6	Māravarman Sundara-Pāṇḍya III., do.,	934
Maṅgalarasarāja, <i>Guj. W. Chal.</i> ,	1n	Māravarman Vira-Pāṇḍya, do.,	936
Maṅgalēśa, <i>W. Chal. k.</i> ,	4-7, 10	Māravijayōttuṅgavarman, <i>Kaṭāka (Kiddam)</i>	
Maṅgalēśvara, s. a. Maṅgalēśa,	8	<i>k.</i> ,	
Maṅgalīśa, do.,	150	Mariyāṇa, <i>Danḍanāyaka</i> ,	

	NUMBER		NUMBER
Mārtāṇḍa, <i>k.</i> ,	961	Mukkōkkilāṇaḍi, <i>ḷāṇaḍiḷaḷ, title of Chōla</i>	
Mārtāṇḍavarman, <i>Kēraḷa k.</i> ,	942	<i>queens</i> ,	795, 801, 812
Mārtāṇḍavarman, <i>Vīra-Kēraḷa, do.</i> ,	958	Mukkuttūr, <i>vi.</i> ,	688
Mārtāṇḍavarman, <i>Vīra-Padmanābha, do.</i> ,	956	Mukula, <i>family</i> ,	74
Marulaḍēva, <i>son of Būtuga II.</i> ,	180	Mūla-saṅgha,	167
Maruvarman, <i>Sagara ch.</i> ,	119	Mulla-bhaṭṭāraka, <i>Jaina teacher</i> ,	79n
Māsuni-dēsam, <i>co.</i> ,	733	Mummaḍi-Bhima, <i>E. Chal. Vimalāditya</i> ,	568
Matsya, <i>family</i> ,	548, 600	Mummaḍi-Bhima I., II., <i>Kōṇamaṇḍala chiefs</i> ,	583
Mattamayūra, <i>line of ascetics</i> ,	301	Mummaḍi-Chōḷa (Rājārāja), <i>E. Chal. ruler of</i>	
Maudgala, <i>family</i> ,	352	<i>Vēṅgi</i> ,	571, 572
Maurya, <i>do.</i> ,	330	Mummaḍi-Chōḷa, <i>Chōḷa Rājārāja I.</i> ,	704
Mauriya, <i>people</i> ,	10	Mummuni, <i>Sīḷdra ch.</i> ,	309
Māvali-Vāparāya, <i>s. a. Mahāvali-Vāparāya</i> ,	649, 651, 670	Munai, <i>Munaiṇṇāḍi, di.</i> ,	1089, 1090
Māvulidēva, <i>Kāḍamba ch.</i> ,	210	Munichandra, <i>rājaguru</i> ,	268
Māyappa, <i>m.</i> ,	984	Munichandraḍēva, <i>Jaina teacher</i> ,	976
Māyirudiṅgam, <i>island (?)</i> ,	734	Munija, <i>Maurya ch.</i> ,	330
Mayūrakhaṇḍi, <i>vi.</i> ,	63, 64, 66	Munija, <i>Paramāra k.</i> ,	140, 150, 328
Mayūraśarman, <i>Kāḍamba k.</i> ,	603	Munija, <i>Sinda ch.</i> ,	189
Mayūravarmān I., <i>Kāḍamba ch.</i> ,	210	Munjaladēva, <i>father of Barmarasa</i> ,	281
Mēdhāvin, <i>family of</i> ,	634n	Muppalaḍēvi, <i>Muppamaḍēvi, queen of Kāka-</i>	
Mēdinimisaragaṇḍa, <i>sur. of Tirumalaidēva-</i>		<i>tīya Prōla</i> ,	584, 586
<i>mahārāja</i> ,	498	Moppidi, <i>Muppidi-Nāyaka, general</i> ,	1066
Mēghachandra-traividya, <i>Jaina teacher</i> ,	74, 387, 408, 981	Muṣaṅgi, <i>vi.</i> ,	729
Mēlāmbā, <i>queen of E. Chal. Vijayāditya</i>		Mūshaka, <i>co.</i> ,	5
<i>IV.</i> ,	500, 501	Mushkara, <i>W. Gaṅga k.</i> ,	115
Mēlpāṭi, <i>vi.</i> ,	98	Mushtika, <i>ch.</i> ,	999
Mēraḍa, <i>Raṭṭa (?) ch.</i> ,	79	Musi, <i>ri.</i> ,	56
Mēru, <i>s. a. (?) Mahōdaya</i> ,	86	Mūvaḍi-Chōḷa Rājāditya, <i>Chōḷa k.</i> ,	95
Meṭṭaṇḍi Kunniyarasa, <i>ch.</i> ,	1024	Muyāṅgi, <i>s. a. Muṣaṅgi</i> ,	729n
Mēvillimbaṅgam, <i>co. or vi.</i> ,	734	Muyirikkōḷu, <i>vi. (Cranganore)</i> ,	962
Mihira, <i>k.</i> ,	77		
Milāḍu, <i>di.</i> ,	1058, 1073, 1080		
Minḍaṇ Attimallaṇ Śambuvārāyaṇ, <i>Seṅgēni</i>			
<i>ch.</i> ,	818		
Misaragaṇḍa, <i>sur. of Nrisimharāja</i> ,	501		
Mpiḷāṅka, <i>sur. of Sīḷdra Aparājita</i> ,	305		
Mpiḷēsa, <i>Mpiḷēsavarmān, Varavarman</i> ,			
<i>Kāḍamba k.</i> ,	604-606, 608, 610		
Mpityujit, <i>legendary Chōḷa k.</i> ,	712		
Muda, <i>Mudda, Daṇḍanāyaka</i> ,	466, 467		
Mudda-bhūpati, <i>Muddu-rāja, Padināḍu ch.</i> ,	997		
Muddapa, <i>Vijayanagara prince</i> ,	459, 474		
Maddukrishṇa, <i>Madhurā Nāyaka</i> ,	542		
Mudduvira, <i>do.</i> ,	542		
Mudgapa, <i>for Muddapa</i> ,	474		
Mudigaṇḍa, <i>Chōḷa Rājendra-Chōḷa I.</i> ,	728, 737		
Mudikondaśōlapuram, <i>vi.</i> ,	895, 896		
Muhammad Shāh, <i>Golkonda k.</i> ,	539		

	NUMBER		NUMBER
Nāgātiyarasa, s. a. Nāgāditya,	156	Narasa (Nṛhari, Nṛsiṃha), <i>Vijayanagara k.</i> ,	502, 504, 519, 530, 1064
Nāgattaras,	126	Narasimha, <i>Pallava k.</i> ,	637, 638
Nāgātya, s. a. Nāgāditya,	156	Narasimha, <i>Pallava k.</i> Narasimhavarman I.,	20
Nāgavardhanarāja, <i>W. Chal. prince</i> ,	17	Narasimha I., <i>E. Gaṅga k.</i> ,	577n
Nāgavarman, <i>father of Māra (Māramayya)</i> ,	389n	Narasimha, Nārasimha (Nārasinga) I.,	
Nāgavarman, <i>Hoysala general</i> ,	713	<i>Hoysala k.</i> ,	409-411, 413, 416, 419, 431, 413
Nāgavarman, <i>k.</i> ,	127	Narasimha II., <i>do.</i> ,	434, 435, 847
Nāgavarman, <i>k. or ch.</i> ,	54	Narasimha III., <i>do.</i> ,	439, 440, 413, 444, 416, 447, 450-453
Nāgiyukka, <i>f.</i> ,	404	Narasimha, Nara-simhavarman, <i>Chōla feudatory</i> ,	388, 396n, 406n, 403, 415n
Nāka, <i>Sindu ch.</i> ,	224, 243	Narasimhadēva II., <i>E. Gaṅga k.</i> ,	979n
Nakharāśvaradēva, <i>god</i> ,	196	Narasimha Kariya-Perumāḷ-Periyaṇḍayan, <i>Malāḍu ch.</i> ,	1056
Nākimayya, <i>ch.</i> ,	177	Narasimhapōttavarman, <i>Pallava k.</i> Narasimhavarman,	40
Nakkavāram, <i>Nicobar Islands</i> ,	734	Narasimhavarman, <i>Gaṅga-Pallava k.</i> ,	645-647
Naja, <i>people</i> ,	10	Narasimhavarman I., <i>Pallava k.</i> ,	627, 628, 631, 635, 680
Nallanūka, <i>ch.</i> ,	593	Narasimhavarman II., <i>do.</i> ,	629-632, 634, 635
Nallasiddhi, <i>Telugu-Chōḍa ch.</i> ,	882	Narasimhavarman Rapakōsari-Rāma, <i>Milāḍu ch.</i> ,	1080
Nāmaṇaikkōṇai, <i>co. or vi.</i> ,	733	Narasimhavarman Śaktinātha, <i>do.</i> ,	1058
Nānaya-Nāyaka, <i>Piḷḍupurī ch.</i> ,	601	Narasimhavishṇu, <i>Pallava kings</i> ,	627, 631
Nambaya, <i>Kollipākā ch.</i> ,	800	Narasingappōttaraiyar, s. a. Narasimhavarman I.,	680
Nambha, Nambirāja, s. a. Nambaya,	800n	Narasingha, <i>W. Gaṅga k.</i> ,	127
Nāni-Nēni, s. a. Nānaya-Nāyaka,	601	Narasobba, <i>m.</i> ,	1025
Nānārtharatnamāḷā,	469n	Nārāyaṇa, <i>k.</i> ,	741
Nandagiri, <i>mountain</i> ,	95, 124, 125, 130, 132, 133, 179n	Nārāyaṇadēva, <i>son of Timmarasa</i> ,	514
Nandanārāyaṇa, <i>poet</i> ,	712n	Nārāyaṇāmbikā, <i>queen of Vira-Vijaya</i> ,	457
Nandereya, <i>m.</i> ,	33	Narēndrampigarāja, <i>sur. of E. Chal. Vijayāditya II.</i> ,	533, 560, 562n
Nandi, s. a. Nandagiri,	670	Nāsika, <i>vi.</i> ,	325
Nandin, s. a. Nandivarman Pallavamalla,	635	Nātavāḍi, Nāthavāḍi or Vāṭi, <i>di.</i> ,	591, 592
Nandipōtarāja, <i>Pallava k.</i> Nandivarman,	636	Navakāma, <i>W. Gaṅga Śivamāra I.</i> ,	115, 116
Nandipōtarāja, s. a. Nandivarman Pallavamalla,	635	Navarāma, <i>Telugu-Chōḍa ch.</i> ,	888
Nandipōtavarman, <i>Pallava k.</i> Nandivarman,	49	Nāyaki, <i>queen of Maurya Gōvindarāja</i> ,	330
Nandippōttaraiyaṇ, <i>do.</i> ,	633	Nayakīrtidēva, <i>Jaina teacher</i> ,	414, 415
Nandippōttarasar, <i>do.</i> ,	636	Nayakīrtidēva, <i>Mahāmaṇḍalākārya</i> ,	446
Nandivarman, <i>Bāṇa k.</i> ,	663	Nāyaladēvi, <i>queen of Vēsuka (Vēsū)</i> ,	331
Nandivarman, <i>Pallava k.</i> ,	121, 621, 633, 636, 641	Nāyamāmbā, <i>mother of queen of Ammarāja II.</i> ,	566
Nandivarman, s. a. Nandivikramavarman,	662	Nāyamma, Nāyivarman, <i>Śilāhāra ch.</i> ,	317, 327
Nandivarman Malladēva, <i>Bāṇa k.</i> ,	668	Neḍamari, <i>W. Chāl. k.</i> ,	150
Nandivarman Pallavamalla, <i>Pallava k.</i> ,	634, 635	Neḍuñḍaiyaṇ (Jaṭilavarman), <i>Pāṇḍya k.</i> ,	937
Nandivikramavarman, <i>Gaṅga-Pallava k.</i> ,	648-651	Nellār, <i>vi. (Nellore)</i> ,	880
Nanna, <i>Kaṭṭa ch.</i> ,	181, 201	Nellūrapura, <i>vi.</i> ,	904
Nannirāja, <i>Velandṇḍu ch.</i> ,	582	Nēmāditya, <i>father of Trivikramabhaṭṭa</i> ,	86
Nanniyabhaṭṭa, <i>poet</i> ,	570n		
Nanniya-Gaṅga, <i>sur. of Bātuga II.</i> ,	127		
Naraga, <i>Śabara ch.</i> ,	131		
Naraharitīrtha, <i>probably governor of Kāliṅga</i> ,	979		
Nārāma, Nārāmbā, <i>queen of Kākatya Gapapati</i> ,	586		
Nārāyaṇ (Nārāyaṇa), <i>k.</i> ,	741		

[illegible]

	NUMBER		NUMBER
Pañchapa, <i>legendary Chōla k.</i> ,	712	Parākrama-Pāṇḍya, Māravarman, <i>Pāṇḍya k.</i> ,	925, 926
Pañchappalli, <i>co. or vi.</i> ,	733	Paramagūḷa-Prithuvi-Nirgunda-rāja, <i>Bāṇa (?)</i>	
Pañchavanmahādēvi, <i>queen of Chōla Rājārāja</i>		<i>ch.</i> ,	119
I.,	716	Paramardin (Permāḍi), <i>Kaḷachurya ch.</i> ,	226n, 238
Pañchavas, <i>s. a. Pāṇḍyas</i> ,	764	Paramardin Śivachitta, <i>Kādamba ch.</i> ,	249
Paṇḍa, <i>Velanāṇḍu ch.</i> ,	582	Paramēśvara, <i>poet</i> ,	634n
Pāṇḍi-Amirdamaṅgalam, <i>vi.</i> ,	938	Paramēśvara, <i>s. a. Paramēśvaravarman I.</i> ,	629
Pāṇḍipura, <i>vi.</i> ,	50	Paramēśvarapōtavarman I., II., <i>Pallava</i>	
Pāṇḍya, <i>ch.</i> ,	994	<i>kings</i> ,	635
Pāṇḍya, <i>co.</i> , <i>kings, people</i> ,	5, 10, 939	Paramēśvaravarman I., <i>Pallava k.</i> ,	628, 629,
Pāṇḍya, <i>crowned head of</i> ,	821, 824-832,		632, 634, 635
	835-840, 842	Paramēśvaravarman II., <i>do.</i> ,	634, 635
Pāṇḍyadēva Tribhuvanamalla, <i>ch.</i> ,	219	Parāntaka, <i>sur. of Kulōttunga-Chōla I.</i> ,	787
Pāṇḍyaka, <i>queen</i> ,	994	Parāntaka I., <i>Chōla k.</i> ,	631, 634, 669-693,
Pāṇḍyarāya (Vira-Pāṇḍya), <i>ch.</i> ,	985		712, 1071-1075
Pāṇḍyas, <i>five</i> ,	764, 793	Parāntaka II., <i>do.</i> ,	712, 716
Pāṇḍyas, <i>of Koṅkaṇa and Nōlambavāḍi</i> ,	140n	Paravādimalla, <i>Jaina teacher or teachers</i> ,	969, 1047
Pāṇḍyas, <i>of Madhurā</i> ,	889 ff.	Paṇṇai, Paṇṇipurī, <i>vi.</i> ,	663, 670
Pāṇṇiya, <i>grammar</i> ,	279n	Paśchima-Raṅganagara, <i>vi. (Śrīraṅgapattana)</i> ,	999
Pāṇṇai, <i>co. or vi.</i> ,	734	Pātālamalla, <i>k. or ch.</i> ,	138
Pāṇṇāledurga, <i>vi.</i> ,	326	Paṭṭamādēvi, <i>queen of Vira-Vikramāditya II.</i> ,	340
Paṇṇa, <i>kula</i> ,	596, 599	Paṭṭavardhika, Paṭṭavardhini, <i>family</i> ,	559, 564, 1065
Pāṇṭhipura, <i>vi.</i> ,	210	Paṭṭi-Perumāla, <i>k.</i> ,	396n
Pappālam, <i>co.</i> ,	734	Paṭṭi-Pombuchchapura, <i>vi.</i> ,	237, 993
Paragaṇḍa, <i>Oḍḍavādi ch.</i> ,	690	Peda-Venkaṭa, <i>s. a. Venkaṭapati II.</i> ,	542
Parahitarāja, <i>Chal. prince</i> ,	52	Pemma (Permāḍi) I., <i>Sinda ch.</i> ,	243
Parakēsarīn, <i>Chōla Parāntaka I.</i> ,	685	Pemmāḍi II., <i>do.</i> ,	243
Parakēsarīn, <i>legendary Chōla k.</i> ,	712	Pemmāṇaḍi Satyavākya, <i>W. Gaṅga Rājamalla (?)</i> ,	124
Parakēsarivarman, <i>Chōla Adhirājendra</i> ,	755	Penugonḍa, <i>di. and vi.</i> ,	501, 542
Parakēsarivarman, <i>Chōla Aditya II. (?)</i> ,	694	Pērama, Pēramāmbā, <i>queen of Kākatya</i>	
Parakēsarivarman, <i>Chōla Kulōttunga-Chōla</i>		Ganapati,	586
III.,	814, 815, 817, 827, 832, 840, 1087, 1088	Periya-Erama-Nāyaka, <i>ch.</i> ,	538
Parakēsarivarman, <i>Chōla Parāntaka I.</i> ,	621,	Permāḍi (Paramardin), <i>Kaḷachurya ch.</i> ,	226
	634, 669-671, 681-693, 712, 1072-1075	Permāḍi, <i>W. Chōl. Vikramāditya VI.</i> ,	224, 261, 269
Parakēsarivarman, <i>Chōla Rājārāja II.</i> ,	812, 813	Permāḍi I., <i>Sinda ch.</i> ,	224
Parakēsarivarman, <i>Chōla Rājendra-Chōla I.</i> ,	722-727, 729, 732-736, 1078, 1079	Permāḍidēva, <i>W. Chōl. Vikramāditya VI.</i> ,	201, 389
Parakēsarivarman, <i>Chōla Rājendradēva</i> ,	744-	Permāḍidēva, <i>W. Gaṅga ch.</i> ,	205n
	746, 748-750, 1080	Permāḍi I. Jagadēkamalla, <i>Sinda ch.</i> ,	233,
Parakēsarivarman, <i>Chōla Uttama-Chōla</i> ,	657n		234, 243
Parakēsarivarman, <i>Chōla Vijayālaya (?)</i> ,	672-675, 1071	Permāḍirāya, <i>W. Chōl. Vikramāditya VI.</i> ,	220
Parakēsarivarman, <i>Chōla Vikrama-Chōla</i> ,	794-	Permāḍi (Paramardin) Śivachitta, <i>Kādamba</i>	
	797, 799, 801-803, 805, 806	<i>ch.</i> ,	241, 242, 254, 255, 261, 269
Parākramabāhu, <i>k. of Īlam</i> ,	847	Perma Jagadēkamalla II., <i>W. Chōl. k.</i> ,	236
Parākrama-Pāṇḍya, Jaṭavarman, <i>Pāṇḍya k.</i> ,	927	Permāṇaḍi Būtaya (Būtuga II.), <i>W. Gaṅga</i>	
Parākrama-Pāṇḍya, Jaṭilavarman Arikēsarīn,	928-931	<i>k.</i> ,	130
<i>do.</i> ,		Permāṇaḍi Būtuga II., <i>do.</i> ,	95, 128
Parākrama-Pāṇḍya, Jaṭilavarman Kulasēkhara,	932	Permāṇaḍi Mārasinha II., <i>do.</i> ,	104, 106
<i>do.</i> ,		Permāṇaḍi Nītimārga, <i>W. Gaṅga Rājavikrama</i>	
		(?),	124
			2 D

	NUMBER		NUMBER
Permanāḍi Satyavākya, <i>W. Gaṅga</i> Bātuga		Prabhūtavarsha, <i>sur. of</i> Gōvindarāja III.,	
I. (?),	125	61-64, 66, 67, 75	
Permanāḍi Satyavākya, <i>W. Gaṅga</i> Rāchamalla		Prabhūtavarsha, <i>sur. of</i> Gōvindarāja IV.,	98, 91
II.,	133	Prabhūtavarsha, <i>sur. of</i> Guj. Rāshtrakūṭa ch.	
Permānadi Śivamāra II., <i>W. Gaṅga</i> k.,	120	Gōvindarāja,	69
Perumāle, Perumāledēva, <i>min. and</i>		Prachanḍa, <i>ch.</i> ,	84
<i>Danḍanāyaka</i> ,	443, 451	Pranālakadurga, <i>vi.</i> ,	326
Perumāḷ Śrīvallabha, Jaṭilavarman, <i>Pāṇḍya</i> k.,	933	Pratāpa-Dēvarāja, <i>s. a.</i> Dēvarāja I.,	484, 487
Perumāṇḍigaḷ Śivamabārāja, <i>s. a.</i> Śivamāra		Pratāpa-Dēvarāja, <i>younger brother of</i> Dēvarāja	
II.,	659, 660	II.,	487, 495
Piḍuvārāditya, <i>sur. of</i> Velanāṇḍu ch. Malla		Pratāpa-Hoysala, <i>sur. of</i> Hoysala Narasimha	
II.,	582	I.,	409
Pillā, <i>m.</i> ,	1023	Pratāparudra, <i>Kākatīya</i> k.,	1066
Pina (China)-Veṅkaṭa III., <i>Karṇāṭa</i> prince, .	545	Pratipati-Araiya, <i>s. a.</i> Prithivīpati I.,	659, 660
Pinnama I., II., <i>Karṇāṭa</i> chiefs of <i>Āravīḍu</i> , .	539	Pratishṭhāna, <i>vi.</i> ,	61
Pirāntakaṇ-Kaṇḍarādittadēvar, <i>s. a.</i> Gaṇḍarā-		Prāṇḍha-Immaḍi-Dēvarāja, <i>Vijayanagara</i> k.	
dityavarman,	689	Mallikārjuna,	497
Pirudi-Gaṅgaraiya, <i>perhaps s. a.</i> Prithivīpati		Pravarasūkara (?), <i>Maurya</i> ch.,	330
I.,	653	Prīchhahakarāja, <i>Rāshtrakūṭa</i> k.,	74
Pishṭupura, <i>vi.</i> ,	10	Prithivigaṅgaraiya, <i>W. Gaṅga</i> ch.,	1070
Piṭhāpuram, <i>E. Chālukya</i> of,	575, 576	Prithivī-Koṅgaṇi (or -Koṅgaṇi)-mahārāja, <i>de-</i>	
Piṭhāpurī, <i>vi.</i> ,	601	<i>signation of</i> <i>W. Gaṅga</i> kings,	115, 117, 118
Piṭṭuga, <i>Raṭṭa</i> (?) <i>ch.</i> ,	142	Prithivīpati I., <i>W. Gaṅga</i> k.,	653, 659n, 670
Pōchaladēvī, Pōchāmbikā, ōke, Pōchavve,		Prithivīpati II., <i>Gaṅga-Bāṇa</i> k.,	669-671,
Pōchikabbo, <i>mother of</i> Gaṅgarāja, 389, 392,		681, 682, 685	
	394, 395	Prithivivāghra, <i>Nishāda</i> ch.,	634
Podiyil, <i>mountain</i> ,	764	Prithuvī-Koṅgaṇi-mahārāja, <i>s. a.</i> Prithivī-K°, .	119
Pogari-gachchha,	167	Prithuvīsāgara, <i>Ālupa</i> k.,	29n
Pogilli, <i>Sēndrakka</i> k.,	31	Prithvirāma, <i>Raṭṭa</i> (?) <i>ch.</i> ,	79, 142
Polakēśivallabha, <i>s. a.</i> Pulakēśin I.,	568	Prithvi Saṭṭi (?), <i>m.</i> ,	1001
Polālva, <i>min. and</i> <i>Danḍanāyaka</i> ,	434	Prithviśvara, <i>Velanāṇḍu</i> ch.,	582, 583
Polasinda, <i>Sinda</i> ch.,	156	Prithvivallabha, <i>sur. of</i> Gōvindarāja III.,	68
Polekēśin I., <i>s. a.</i> Pulakēśin I.,	10	Prōḍarāja, <i>Kākatīya</i> Prōla,	588
Polekēśin II., <i>s. a.</i> Pulakēśin II.,	10	Prōla, Prōlārāja, <i>Kākatīya</i> k.,	584-586, 589
Polekēśivallabha, <i>s. a.</i> Pulakēśin I.,	9, 18	Prōla, <i>Redḍi</i> ch, of <i>Koṇḍavīḍu</i> ,	593
Polekēśivallabha, <i>s. a.</i> Pulakēśin II.,	12	Prōlaya-Nāyaka, <i>Piṭhāpurī</i> ch.,	601
Polvōla, <i>gōtra</i> ,	599	Pūchān, <i>family</i> ,	634
Pōtanabhaṭṭa, <i>poet</i> ,	565n	Pugaḷvippavarganḍa, <i>ch.</i> ,	698
Poṭṭalakere, <i>vi.</i> ,	157, 158	Pugaḷvippavarganḍa, <i>sur. of</i> Bāṇa Vijayāditya	
Pottappi, <i>vi.</i> ,	880	II.,	663
Pottappi (or Pottapi)-Chōla, <i>Telugu-Chōla</i>		Pugaḷvippavarganḍa, <i>sur. of</i> Rājādittan, .	1075
<i>ch.</i> ,	880, 881, 883	Pūjyapāda, <i>priest</i> ,	37
Poysala, <i>s. a.</i> Hoysala, 224, 383, 388, 406, 441,		Pulakēśin I., <i>W. Chal</i> , k.,	1, 2, 5, 6, 9, 18,
442, 448, 449, 713, 969		20, 25, 27, 150, 547, 568	
Prabhāchandra, <i>Jaina āchārya</i> ,	1021	Pulakēśin II., <i>do.</i> , 9-18, 20, 23-25, 27, 29,	
Prabhāchandra, <i>Jaina teacher</i> ,	1022	150, 547, 548, 557n, 628, 634	
Prabhāchandra-siddhāntadēva, <i>do.</i> , 387, 400n, 408		Pulasakti, <i>Sīlāra</i> ch.,	305, 307, 309
Prabhākara, <i>m.</i> ,	337	Pulekēśivallabha, <i>s. a.</i> Pulakēśin II.,	11
Prabhumēru, <i>Bāṇa</i> k.,	663	Pulikāla, <i>Sinda</i> ch.,	144, 156
Prabhūtavarsha, <i>sur. of</i> Gōvindarāja II.,	56, 66	Pullana, <i>s. a.</i> Hulla,	410

	NUMBER		NUMBER
Pullasakti, s. a. Pulasakti,	72, 73	Rājakēsarivarman, <i>Chōla</i> Kulōttunga-Chōla I.,	
Puñjālike, <i>kingdom of</i> ,	994n	756-761, 763-765, 767, 769, 770, 774,	
Punnāḍa, <i>co.</i> ,	114	775, 777, 781, 785, 788-790, 1085	
Punnāḍu-vishaya, <i>di.</i> ,	1016	Rājakēsarivarman, <i>Chōla</i> Kulōttunga-Chōla	
Puṇṇāṇḍar, <i>vi.</i> ,	538	[II. ?],	811
Punnāṭarāja (?), <i>k.</i> ,	1016	Rājakēsarivarman, <i>Chōla</i> Madhurāntaka (?), . . .	695
Puraigilānāḍu, <i>di.</i> ,	963	Rājakēsarivarman, <i>Chōla</i> Rājādhirāja I., . . .	738-742
Pūṇḍi, <i>ri.</i> ,	78	Rājakēsarivarman, <i>Chōla</i> Rājamahēndra, . . .	752
Purī, <i>vi.</i> ,	10	Rājakēsarivarman, <i>Chōla</i> Rājarāja I., . . .	704,
Purikara, <i>vi.</i> ,	127	708-710, 712, 715, 716, 719	
Puru-panḍita, <i>Jaina teacher</i> ,	983	Rājakēsarivarman, <i>Chōla</i> Rājarāja III., . . .	848
Puru-Ranaparākrama, <i>W. Chal.</i> Kirtivarman		Rājakēsarivarman (!), <i>Chōla</i> Rājēndradēva, . . .	751
I.,	5	Rājakēsarivarman, <i>Chōla</i> Viratājēndra I., 753,	
Purushōttama, <i>Danḍanāyaka</i> ,	344	754, 1081-1084	
Purushōttama, <i>E. Chāl. ch. of Śrīkūrmam</i> , 578-580		Rājamahēndra, <i>Chōla k.</i> ,	752
Purushōttama, <i>Pallava k.</i> ,	625	Rājamahēndra, <i>sur. of</i> Ammarāja I., . . .	559, 1065
Purushōttama-mahātīrtha, <i>author</i> ,	979	Rājamahēndra, <i>sur. of</i> Ammarāja II., . . .	564, 566
Pushpasēna, <i>Jaina priest</i> ,	1063	Rājamahēndra-nagara, -nagari, -paṭṭana, <i>vi.</i> ,	
Puttār, <i>vi.</i> ,	860n	577, 596, 599	
R		Rājamalla, <i>sur. of W. Chal.</i> Vikramāditya I., . . .	20n
Rācha, <i>min.</i> ,	508	Rājamalla, <i>W. Gaṅga k.</i> ,	123, 124n
Rāchamalla, <i>Sinda ch.</i> ,	253	Rājamalla I., <i>do.</i> ,	121, 127
Rāchamalla I., <i>W. Gaṅga k.</i> ,	93, 95, 98	Rājamalla II., <i>do.</i> ,	127
Rāchamalla II., <i>do.</i> ,	133, 137	Rājamalla (?), III., <i>do.</i> ,	127
Rachcha (?)-Gaṅga, <i>do.</i> ,	130	Rājamārtanḍa, <i>E. Chāl. ch. of Piṭhāpuram</i> , . . .	576
Rachhyāmalla, s. a. Rāchamalla I.,	93, 98	Rājamārtanḍa, <i>sur. of</i> Chālukya-Bhima II., . . .	562
Rāghavadēva, <i>Karṇāṭa ch.</i> ,	539	Rājamayya, <i>ch.</i> ,	1065
Raghu, <i>Kadamba k.</i> ,	603	Rājanārāyaṇa Śambuvārāja, 'rāya, 'rāyar,	
Raghus, <i>family of the</i> ,	585	<i>ch.</i> ,	872, 873
Rāhappa, <i>k.</i> ,	61	Rājapagendū I., II., <i>Kōnamāṇḍala chiefs</i> , . . .	583
Rāja or Rājan (Śrīrāja), <i>Īādava ch. of</i>		Rājarāja, <i>E. Chāl. ch. of Śrīkūrmam</i> , 577, 578, 580	
<i>Sēṇadēśa</i> ,	328, 329, 331	Rājarāja, <i>E. Chāl. k.</i> ,	583
Rājabhīma, <i>sur. of</i> Chālukya-Bhima II.,	568, 1065	Rājarāja I., <i>Chōla k.</i> ,	569, 696-720, 722,
Rājādhirāja I., <i>Chōla k.</i> ,	738-744, 751, 1080	1076, 1077	
Rājādittan Pugalvippavarganḍa, <i>brother of</i>		Rājarāja II., <i>do.</i> ,	812, 813, 1086
Mahādēvaḍi,	1075	Rājarāja III., <i>do.</i> ,	843-862
Rājāditya, <i>Chāl. k. or ch.</i> ,	131	Rājarāja I., <i>E. Chal. k.</i> ,	569-571, 574, 577, 784
Rājāditya, <i>Chōla k.</i> ,	95, 127, 712, 1056,	Rājarāja-Adigaṇ, <i>ch.</i> ,	833, 834
1072, 1075		Rājarāja Chōḍagaṅga, <i>E. Chal. ruler of</i>	
Rājāditya, <i>Śalukika ch.</i> ,	67	<i>Vēṅgi</i> ,	571
Rājāditya, <i>W. Gaṅga ch.</i> ,	1070	Rājarājakēsarivarman, <i>Chōla</i> Rājarāja I.,	
Rājagambhīra, <i>sur. of</i> Jātavarman Kulasē-		696-703, 705, 707, 711, 714, 717,	
khara,	890	718, 720, 1076, 1077	
Rājagambhīra Śambuvārāyaṇ, <i>ch.</i> ,	854, 866	Rājarāja Mummaḍi-Chōḍa, <i>E. Chal. ruler of</i>	
Rājamaṇsa, <i>ch.</i> ,	84	<i>Vēṅgi</i> ,	571, 572
Rājakēsarīn, <i>legendary Chōla k.</i> ,	712	Rājasimha, <i>Pallava k.</i> ,	629-632
Rājakēsarivarman, <i>Chōla</i> Āditya I. (?),	676-680	Rājasimha, <i>Pēṇḍya k.</i> ,	685
		Rājāśraya, <i>sur. of Chōla</i> Rājarāja I., . . .	712
		Rājāśraya, <i>sur. of W. Chal.</i> Vinayāditya, . . .	31
		Rājavarman, <i>k.</i> ,	127, 1065n

	NUMBER		NUMBER
Rājendra, <i>legendary Chōla k.</i> ,	712	Rānavikramayya, <i>W. Gaṅga k.</i> ,	121
Rājendra-Chōḍa, <i>Velanāṇḍu ch.</i> ,	581, 582	Rānavikrānta, <i>sur. of Maṅgalēsa</i> ,	3, 5
Rājendra-Chōḍa I., <i>Kōnamāṇḍala ch.</i> ,	583	Rāṅga, <i>brother of Achyutarāya</i> ,	530
Rājendra-Chōḍa I., <i>s. a. Rājendra-Chōḍa I.</i> , 569, 571		Rāṅgapatākā, <i>queen of Narasiṃhavarman II.</i> ,	631
Rājendra-Chōḍa II., <i>s. a. Kulōttuṅga-Chōḍa I.</i> , 225n, 571		Rāṅgarāja, <i>s. a. Śrīraṅgarāja I.</i> ,	530
Rājendra-Chōḍa, <i>s. a. Rājendradēva</i> ,	750	Rāsenanagara, <i>vi.</i> ,	33
Rājendra-Chōḍa I., <i>Chōḍa k.</i> , 152, 721-737, 1078, 1079		Rāshtrakūta, <i>son of Raṭṭa</i> ,	93
Rājendra-Chōḍa II., <i>s. a. Kulōttuṅga-Chōḍa I.</i> , 756-760, 784		Rāshtrakūtas, <i>of Gujārāt</i> , 54, 65, 67-70, 77, 78, 81	
Rājendra-Chōḍa III., <i>Chōḍa k.</i> , 863-865, 867, 868		Rāshtrakūtas, <i>of Mālkhēd</i> , 53 ff., 301, 305, 1054 ff.	
Rājendra-Chōḍa-Brahmamarāya, <i>Danḍanāyaka</i> , 742		Rāshtravarman, <i>k.</i> ,	1016
Rājendradēva, <i>Chōḍa k.</i> ,	572, 744-751, 1080	Ratnapāla, <i>k.</i> ,	451n
Rājiga-Chōḍa, <i>s. a. Kulōttuṅga-Chōḍa I.</i> , 225n, 250n		Ratnāvalōka, <i>sur. (?) of Bappuvarasa</i> ,	967n
Rakkasa, <i>brother of Rāchamalla II. (?)</i> ,	133, 134	Ratnavarsha, <i>sur. of Rāshtrakūta ch. (?)</i>	
Raktapura, <i>vi.</i> ,	26, 36, 37, 41	Vijayāditya,	56
Rāma, <i>general, son of Khōlēśvara</i> ,	352	Raṭṭa, <i>ancestor of Rāshtrakūtas</i> ,	93
Rāma, <i>poet</i> ,	539, 542, 543, 545	Raṭṭa, <i>s. a. Rāshtrakūta</i> ,	305
Rāma, <i>s. a. Rāmachandra</i> ,	369	Raṭṭa-Kandarpa, <i>sur. of Indrarāja III.</i> ,	86n
Rāmachandra, <i>Dēvagiri-Yādava k.</i> , 368-382, 468n		Raṭṭa-Kandarpa, <i>sur. of Khottiga</i> ,	104n
Rāmadēva, <i>s. a. Rāmachandra</i> ,	371, 468	Raṭṭa-pāḍi, Raṭṭa-pāṭi, <i>co.</i> ,	301, 729, 1080, 1084
Rāmadēva IV. (?), <i>Karṇāṭa k.</i> ,	540	Raṭṭarāja, <i>Sīldra ch.</i> ,	149, 301
Rāma Narasiṃhavarman, <i>Mālāḍu ch.</i> ,	1086	Raṭṭas,	75, 140, 140n
Rāmānujāchārya, <i>Śāsana of</i> ,	461	Rāuttarāya, <i>sur. of Perumālēdēva</i> ,	451
Rāmappa-Gauḍa, <i>ch.</i> ,	999	Ravi, Ravivarman, <i>Kadamba k.</i> ,	608-610, 612
Rāmarāja I., <i>Karṇāṭa ch.</i> ,	539	Ravi, Sthāpu R ^o , <i>k.</i> ,	964
Rāmarāja II., <i>do.</i> ,	530, 534, 539, 542, 545	Ravidatta, <i>Punnāḍu-vishaya (?) k.</i> ,	1016
Rāmavarman, <i>ruler of Vañchē</i> ,	960	Ravidēva-tridaṇḍin, <i>m.</i> ,	1034
Rāmavarman, <i>s. a. Vīra-Rāmavarman</i> ,	950	Ravikīrti, <i>poet</i> ,	10
Rāmāyana-Tirumalārya, <i>poet</i> ,	1004, 1005	Ravivarman, Bhāskara R ^o , <i>k.</i> ,	962, 963
Rāmēśvara-dīkshita, <i>m.</i> ,	584	Ravivarman, Ravi, <i>Kadamba k.</i> ,	608-610, 612
Rapadulā-khāna, <i>ch.</i> ,	999	Ravivarman, <i>Kēraḷa k.</i> ,	939, 940
Rapajaya, <i>Pallava k.</i> ,	629	Ravivarman, <i>s. a. Vīra-Ravivarman</i> ,	946, 947
Rapakambha (Ranastambha), <i>Rāshtrakūta ch.</i> , 232		Rāyadēva, <i>ch.</i> ,	427
Rapakēsari-Rāma, <i>sur. of Mīlāḍu ch. Narasiṃhavarman</i> ,	1080	Rāyakumāra or Rāyakuvara, <i>ch.</i> ,	994
Rapaparākramāṅka, <i>W. Chal. Kīrtivarman I. (?)</i> ,	16	Rāya-Murāri, <i>sur. of Sōvidēva</i> ,	285n
Raparāga, <i>W. Chal. k.</i> ,	2, 5, 10, 150	Redḍi, <i>family</i> ,	593 ff.
Raparāṅgabbhīma, <i>probably W. Chal. Taila II.</i> , 328		Rēvakanimmaḍi, <i>queen of Bātuga II.</i> ,	130
Raparāsika, <i>sur. of W. Chal. Vikramāditya I.</i> , 20n, 629, 632		Rēvapa I., II., <i>Oḍḍavāḍi chiefs</i> ,	600
Rapasāgara, <i>Ālupa k.</i> ,	29n	Rēvatidvīpa, <i>island</i> ,	7, 10
Ranastambha (Rapakambha), <i>Rāshtrakūta ch.</i> ,	150, 232	Rōhīṇī, <i>queen of Hiranya</i> ,	635
Rapasūra, <i>Dakṣhiṇa-Lāṭa k.</i> ,	733	Rudra, Rudradēva, <i>Kākatīya k.</i> ,	584-586, 588
Rapāvalōka, <i>sur. of Kambayya</i> ,	60	Rudradēva, <i>Nātavāḍi ch.</i> ,	591, 592
Ranavighraha, <i>Chēḍi k. (Śamkaragana)</i> ,	86, 91	Rudra-paṇḍita, <i>m.</i> ,	329
Ranavikrama, <i>s. a. Pulakēśin I.</i> ,	5, 547	Rudrarāja, <i>Konnātavāḍi-vishaya ch.</i> ,	589
Ranavikrama, <i>W. Gaṅga k.</i> ,	123, 124n	Rundranīla or Rundranīla-Saindraka, <i>family</i> , 2	
		Rūpa-Nārāyana, <i>temple of</i> ,	220, 413
		S	
		Śabara, <i>people, tribe</i> ,	131, 634
		Sabbamādēvi, <i>queen of Śrī-Dhānyakāṭaka ch.</i>	
		Bhīma II.,	590

	NUMBER		NUMBER
Sabbāmbikā, <i>queen of Goṅka II.</i> ,	582	Saṅgrāmahima, <i>sur. of Doḍḍa II.</i> ,	599
Śābdachaturmukha, <i>Jaina teacher</i> (Śānti-nātha ?),	969	Saṅgrāmadhira, <i>sur. of Kēraḷa k. Ravi-varman</i> ,	939, 940
Sabhāpati, <i>poet</i> ,	519, 530, 539, 542, 543, 545	Saṅgrāma-Rāghava, <i>sur. of Parāntaka I.</i> ,	685
Saddāsivārāya, <i>Vijayanagara k.</i> , 521, 523-526,	528-534	Saṅgrāma Vijayottuṅgavarman, <i>Kaḍāram k.</i> ,	734
Sādhasika, <i>Maruṇa chiefs</i> ,	330	Sāmidēva, <i>E. Chāl. ch. of Piṭhāpuram</i> ,	576
Sagara, <i>family, lineage of</i> ,	95, 119, 281, 333	Sāmiyāra, <i>ch.</i> ,	2
Sagara-vishaya, <i>di.</i> ,	576	Śaṅkaradēva, <i>W. Gaṅga or Vaidumba ch.</i> ,	708, 724
Sahadēva, <i>Danḍanātha</i> ,	336	Śaṅkaragana, <i>Chēdi k. (Baṇavigraha)</i> ,	105
Śāhasāṅka, <i>sur. of Gōvindarāja IV.</i> ,	91n	Śaṅkaragana, <i>(Kalachuri) k.</i> ,	6
Śāhasatūṅga, <i>k.</i> ,	969	Śaṅkara-Kōḍavarman, <i>ch.</i> ,	963
Sahasrārjuna, <i>Chēdi k.</i> ,	98	Sampagādi, <i>vi.</i> ,	241
Sahya, <i>Western Ghāṭs</i> ,	764	Sampakarasa, <i>Gutta ch.</i> ,	292
Saigotta, <i>W. Gaṅga Śivamāra II.</i> ,	120, 127	Samudra-Goppaya, <i>Hoysaḷa general</i> ,	847
Śailāhara, <i>s. a. Śilāhara</i> ,	317	Saṇaphulla, <i>Silāra ch.</i> ,	301
Saindraka (?), <i>family</i> ,	2	Śandayan Tiruvayan, <i>Vaidumba-mahārāja</i> ,	1059
Śāka, <i>people</i> ,	568n	Śāṇḍilya, <i>family</i> ,	337, 343
Sakalachandra (Sōmadēva), <i>Jaina teacher</i> ,	337	Śāṇḍimattivu, <i>vi. (?)</i> ,	729
Sakalachandra-siddhānta, <i>do.</i> ,	1065	Śāṅgamayan, <i>k.</i> ,	741
Śākaṭāyana, <i>grammar</i> ,	279n	Saṅkama, <i>Kaḷachurya k.</i> ,	291-294, 300
Śākara-kōṭṭam (Chakrakōṭṭa), <i>vi.</i> ,	733	Śāṅkhā, <i>queen of Gaṅga-Pallava Nandi-varman</i> ,	652
Śakti (Śatti), <i>Pallava k.</i> ,	642	Sāṅkila, <i>k.</i> ,	559
Śaktinātha, <i>sur. of Milādū ch. Narasiṃha-varman</i> ,	1058	Sāṅkuka, <i>Chēdi k. or prince</i> ,	105
Śaktivarman, <i>E. Chāl. k.</i> ,	568, 569, 574	Śānta (Śāntivarman), <i>Raṭṭa (?) ch.</i> ,	142
Sala, Śala, <i>legendary ancestor of Hoysaḷa kings</i> ,	388, 405, 419, 434, 443	Śāntaladēvi, <i>queen of Hoysaḷa Vishpu-varḍhana</i> ,	388, 396, 397, 399, 400, 403
Śālai, Śāle, <i>s. a. Kāṇḍalūr-Śālai</i> ,	701, 702, 742	Śāntali, <i>maṇḍala</i> ,	340
Śālukika, <i>family</i> ,	67	Śāntara, <i>family</i> ,	237
Śālukki, <i>s. a. Chālukya</i> ,	745	Śāntidēva, <i>Jaina teacher</i> ,	969
Śāluva chiefs,	501	Śāntikīrtidēva, <i>do.</i> ,	991
Śāluva, <i>sur. of Nṛsiṃharāja</i> ,	501	Śāntinātha, <i>do.</i> ,	969
Śāluva-Gōparāja, <i>ch.</i> ,	989	Śāntirāja, <i>Maurya ch.</i> ,	330
Śāluva-Maṅgi, <i>Śāluva ch.</i> ,	501	Śāntivarman, <i>Varavarman, Kaḍamba k.</i> , 603,	604, 606, 608, 610, 614n
Śāluva-Nṛsiṃha, <i>ch.</i> ,	539	Śāntivarman (Śānta), <i>Raṭṭa (?) ch.</i> ,	142
Śāluva-śāluva, <i>sur. of Tirumalaidēva-mahārāja</i> ,	498	Śāntivarman II., <i>Kaḍamba ch.</i> ,	210
Śāluva-Tikkamadēva, <i>ch.</i> ,	373	Sarvadēva, <i>ch.</i> ,	200
Śāluva-Timma, <i>min. of Krishnarāja</i> ,	508	Sarvalōkāśraya, <i>sur. of Maṅgi-yuvarāja</i> ,	552
Śāluva-Timma, <i>do.</i> ,	508, 509	Sarvamāṅgalāsattā, <i>vi.</i> ,	70
Sāmanta-Bhōja, <i>min. of Kākaṭiya Gaṇapati</i> ,	588	Sarvāṅganātha, <i>prince</i> ,	941
Śambhudēva, <i>father of Chandramauli</i> ,	416	Sarvasiddhi, <i>sur. of E. Chāl. Jayasimha I.</i> ,	549
Sambu (Śambhu), <i>Saiva ascetic</i> ,	52	Sarvasūra, <i>Maurya ch.</i> ,	330
Śambukula-Perumāl, <i>Attimallaṅ ḡḡ ch.</i> ,	854	Śasapura, Śasakapura, <i>vi.</i> ,	388, 419
Śambuvārāja, <i>rāya, rāyan, rāyar</i> ,	813, 820, 854, 856, 860, 862, 866, 871-873, 884	Śatrubhayamkara, <i>k.</i> ,	969
Saṅgama I., <i>Vijayanagara k.</i> ,	455, 459, 465, 468, 474, 475, 480, 484, 487	Śatrumalla, <i>Pallava k.</i> ,	623, 625
Saṅgama II., <i>do.</i> ,	459	Śāttan Gaṇapati, <i>ch.</i> ,	938
Saṅgamēśvara, <i>vi.</i> ,	274	Śatti (Śakti), <i>Pallava k.</i> ,	642
		Sattiga, Sattima, <i>s. a. Iṇṇabedāṅga Satyāśraya</i> , 146n	

	NUMBER		NUMBER
Satya I. (Satyāśraya), <i>Kōnamāṇḍala ch.</i> ,	583	Sēupa, s. a. Sēupachandra II.,	330
Sātyaki, <i>family</i> ,	86, 93	Sēupachandra I., <i>Yādava ch. of Sēupadēsa</i> ,	328, 329, 331
Satyamārtanda, <i>mythical Oḍḍavādi ch.</i> ,	600	Sēupachandra II., <i>do.</i> ,	330, 331
Satyantivākya, <i>W. Gaṅga Būtuga II.</i> ,	127	Sēupadēsa, <i>Yādavas of</i> ,	328 ff.
Satyasaṁdha, <i>Pallava k.</i> ,	625	Sēupadēva [III.], <i>Yādava ch. of Sēupadēsa</i> ,	332
Satyāśraya, <i>E. Chāl. ch. of Piṭhāpuram</i> ,	576	Sēupapura, <i>vi.</i> ,	331
Satyāśraya (Satya I.), <i>Kōnamāṇḍala ch.</i> ,	583	Sēvaṇa, <i>co.</i> ,	586
Satyāśraya, <i>W. Chāl. Irivabedāṅga</i> ,	146,	Sēvaṇa, <i>probably s. a. Sēupachandra II.</i> ,	334
	148-150, 179, 301, 712, 716	Sēva, Sēvyarasa, <i>Sinda ch.</i> ,	156
Satyāśraya, <i>W. Chāl. Kirtivarman I.</i> ,	17	Shanmukha, <i>city of, s. a. Tāmrapuri</i> ,	585
Satyāśraya, <i>W. Chāl. Kirtivarman II.</i> ,	48 f.	Shashṭha (Shashṭhadēva) I., <i>Kādamba ch.</i> ,	147, 254, 261, 269
Satyāśraya, <i>W. Chāl. Pulakēśin I.</i> ,	1 ff., 547	Shashṭha (Shashṭhadēva) II. Śivachitta, <i>do.</i> ,	269
Satyāśraya, <i>W. Chāl. Pulakēśin II.</i> ,	9 ff.,	Śibi, <i>mythical ancestor of Chōla kings</i> ,	685
	150, 548, 557	Siddappa-Nāyaka, <i>ch.</i> ,	1003
Satyāśraya, <i>W. Chāl. Vijayāditya</i> ,	32 ff.	Siddhanandin, <i>Jaina teacher</i> ,	2
Satyāśraya, <i>W. Chāl. Vikramāditya I.</i> ,	18 ff.	<i>Siddhāntasīrōmaṇi, astronomical work</i> ,	337
Satyāśraya, <i>W. Chāl. Vikramāditya II.</i> ,	40 ff.	Siddhaśami, <i>vi.</i> ,	65
Satyāśraya, <i>W. Chāl. Vinayāditya</i> ,	26 ff.	Siddhavaḍava, <i>sur. of Mīlādū ch.</i> Narasiṁha-	
Satyāśraya Dhruvarāja Indravarman, <i>governor</i>		varman,	1058
of <i>Rēvatidvīpa</i> ,	7	Siddhi, <i>Telugu-Chōḍa ch.</i> ,	880
Satyavākya, <i>W. Gaṅga Būtuga I. (P.)</i> ,	125	Śilāhāra, <i>race</i> ,	94n
Satyavākya, <i>W. Gaṅga Būtuga II.</i> ,	95, 128, 130	Śilāhāras, Śilāras, Śilāras,	301 ff.
Satyavākya, <i>W. Gaṅga Mārasimha II.</i> ,	129-131	Simha (Singa, Singidēva), <i>ch. of Sāntālī</i>	
Satyavākya, <i>W. Gaṅga Narasiṅgha</i> ,	127	<i>maṇḍala</i> ,	340
Satyavākya, <i>W. Gaṅga Pañchaladēva</i> ,	132	Simha, <i>Dēvagiri-Yādava k.</i> Singhapa,	337,
Satyavākya, <i>W. Gaṅga Rājamalla II.</i> ,	133		339, 343, 352
Satyavākya, <i>W. Gaṅga Rājamalla (P.)</i> ,	124	Simha (Singa) I., <i>Sinda ch.</i> ,	224, 243
Satyavākya, <i>W. Gaṅga Rājamalla I.</i> ,	127	Simhala, <i>co.</i> ,	1084, 1087
Satyavākya, <i>W. Gaṅga Rājamalla II.</i> ,	127	Simhala, <i>Dēvagiri-Yādava k.</i> Singhapa,	360
Sāvaladēvi, <i>queen of Sōvidēva</i> ,	288	Simhapa, <i>do.</i> ,	341, 342, 347, 350, 354, 355,
Sāvanti-Thakkura, <i>ch.</i> ,	350		357, 588
Sāvitrī-Māṅgi, <i>Sāḷva ch.</i> ,	501	Simhanandin, <i>legendary being</i> ,	670
Sāyana, <i>probably brother of Bhōganātha</i> ,	459n	Simhaparāya, <i>ch.</i> ,	258n
Śēkkaṇūr, <i>vi.</i> ,	1050	Simhavarman, <i>Kādamba k.</i> ,	614
Seḷara, <i>race</i> ,	94n	Simhavarman, <i>Pallava kings</i> ,	621, 635, 641
Seḷiyas, s. a. Pāṇḍyas,	704	Simhavarman I., <i>Pallava k.</i> ,	619
Sellakōtana, <i>sur. of Baṅkēsa</i> ,	74	Simhavarman II., <i>do.</i> ,	620
Sella-Vidyādhara, <i>ch.</i> ,	84	Simhavishṇu, <i>do.</i> ,	634, 635, 641
Śembiyaṇ-Māvali-Vānarāyar, s. a. Prithivi-		Sinda, <i>mythical founder of Sinda family</i> ,	253
pati II.,	670	Sinda, <i>Pāṇḍipura k.</i> ,	50
Śēna (Kālasēna) I., <i>Raṭṭa ch.</i> ,	181, 201	Sindagere, <i>di.</i> ,	383, 385
Śēna (Kālasēna) II., <i>do.</i> ,	181, 193, 201,	Sindagōvinda, <i>Sinda ch.</i> Irmaṇi-Rāchamalla,	253
	265-267	Sindarāja, <i>Sinda ch.</i> ,	189
Śēna-gaṇa,	167	Sindas,	140n, 972n
Śēnānandarāja, <i>Sēndraka ch.</i> ,	13	Sindhurāja, <i>k.</i> ,	115
Śēndamaṅgalam, <i>vi.</i> ,	847	Sindinagara, <i>vi.</i> ,	328, 329
Śēndra, <i>Sēndraka, family</i> ,	13, 16, 19, 31, 612	Sindinēra, <i>co.</i> ,	331
Śēngēni, <i>do.</i> ,	818-820, 856, 862	Singa (Simha) I., <i>Sinda ch.</i> ,	224, 243
Śēralaṇ, 'the Chēra k.',	1084		
Śērama, <i>do.</i> ,	742		

	NUMBER		NUMBER
Singa II., <i>Sinda ch.</i> ,	243	Sôidêva, <i>Nikumbha ch.</i> ,	337
Singala (Simhala), <i>co.</i> ,	1084	Sôma, <i>Danḍandya and min. (son of Nava-</i>	
Singana, <i>m.</i> ,	404	<i>simha III.?)</i> ,	441, 447
Singunadêvarasa, <i>ch.</i> ,	160	Sôma, <i>Hoysala Sômêśvara</i> ,	443
Singanam, <i>co. (of W. Châl. Jayasimha III.)</i> , .	763	Sôma, <i>s. a. Sôvidêva</i> ,	285, 288, 293, 300
Singapan, <i>W. Châl. Jayasimha III.</i> ,	753,	Sôma, <i>Sinda ch.</i> ,	253
	774, 1081, 1082	Sôma, <i>W. Châl. Sômêśvara II.</i> ,	261
Singavarman, <i>k.</i> ,	1016	Sômadêva (Sômêśvara), <i>Châl. ch.</i> ,	274
Singhadêva-bhûpa, <i>Padinâḍu ch.</i> ,	997	Sômadêva (Sakalachandra), <i>Jaina teacher</i> , .	387
Singhana, <i>Dêvagiri-Yâdava k.</i> ,	337-339,	Sômaladêvi, <i>queen of Hoysala Sômêśvara</i> , .	436
	341-355, 357, 359, 360, 369, 370,	Sômana, <i>W. Châl. Sômêśvara IV.</i> ,	434
	379, 538	Sômanâtha, <i>m.</i> ,	260
Singhana, <i>Dêvagiri-Yâdava prince</i> ,	369	Sômanâtha, <i>W. Gaṅga ch.</i> ,	724
Singhana, <i>Kalachurya k.</i> ,	300	Sômasêkhara-Nâyaka, <i>ch.</i> ,	1008
Singhmayya (Singa), <i>brother of Śāntaladêvi</i> ,		Sômêśvara (Sômadêva), <i>Châl. ch.</i> ,	274
	400n, 403	Sômêśvara, <i>Hoysala k.</i> ,	436-438, 441,
Singga-Bommu-Nâyaka, <i>Vêlûr ch.</i> ,	534, 535		453, 864, 865, 904n
Siriadêvi, <i>queen of Châmuṇḍa II.</i> ,	247	Sômêśvara, <i>s. a. Sôvidêva</i> ,	283, 283
Siriadêvi, <i>queen of Śāntivarman II.</i> ,	210	Sômêśvara, <i>Śilâhâra ch.</i> ,	314
Śivachitta Permâḍi (Paramardin), <i>Kādamba</i>		Sômêśvara, <i>Sinda (?) ch.</i> ,	372
<i>ch.</i> ,	241, 242, 249, 254, 255, 261	Sômêśvara I., <i>W. Châl. k.</i> ,	159-173, 179,
Śivachitta Shashthadêva II., <i>do.</i> ,	269		185, 741, 744-746, 748, 749, 751, 753,
Śivamahârāja-Perumāṇaḍigal, <i>s. a. Śivamâra</i>			969, 1080-1082, 1034
II.,	659, 660	Sômêśvara II., <i>do.</i> ,	156, 174-183, 185,
Śivamahârāja Śamkaradêva, <i>W. Gaṅga or</i>			261, 1033, 1034
<i>Tailumba ch.</i> ,	724	Sômêśvara III., <i>do.</i> ,	226-228, 230, 231
Śivamahârāja Tiruvaiyaṇ, <i>W. Gaṅga ch.</i> ,	708	Sômêśvara IV., <i>do.</i> ,	253, 257, 260, 434
Śivamâra I., <i>W. Gaṅga k.</i> ,	123	Sômêśvaradêva-Chakravartin, <i>Sinda (?) ch.</i> , .	972
Śivamâra II., <i>do.</i> ,	659n, 670	Sômêśvara-panḍita, <i>priest or sage</i> ,	196
Śivamâra I. Navakâma, <i>do.</i> ,	115, 117, 121, 127	Sômêśvara, <i>Karṇâṭa ch.</i> ,	539
Śivamâra II. Saigoṭṭa, <i>do.</i> ,	120, 121, 127	Sosavûru (?), <i>vi.</i> ,	383
Śivanasamudra, <i>vi.</i> ,	1064	Sôvaladêvi, <i>queen of Sinda ch. Râchamalla</i> , .	253
Śivappa-Nâyaka, <i>ch.</i> ,	1003	Sôvidêva, <i>Kalachurya k.</i> ,	235-290, 293
Śivâra, <i>ch.</i> ,	2	Śrîballaha (Śrîvallabha), <i>sur. of Râshtrakûṭa</i>	
Śivaratha, <i>Kadamba prince</i> ,	611	<i>k. Dhruvarâja</i> ,	59
Śivaskandavarman, <i>Pallava k.</i> ,	617, 618	Śrîbhara, <i>Pallava k.</i> ,	629
Śiyagaṅgaṇ Amarâbharapaṇ, <i>Gaṅga ch.</i> ,	837, 841	Śrîdêvi, <i>queen of Êrasiddhi</i> ,	880
Śiyalâra, <i>s. a. Śilâhâra</i> ,	315	Śrîdêvi, <i>queen of Nikumbha Indrarâja</i> , .	333
Skanda, <i>Bâṇa ch.</i> ,	647	Śrî-Dhânyakâṭaka, <i>vi. (Amarâvati)</i> ,	590
Skandasêna, <i>ch.</i> ,	623	Śrî-Dhânyâṅkapura, <i>do.</i> ,	589
Skandasishya, <i>Gaṅga-Pallava k.</i> ,	644	Śrîdhara, <i>sur. of Nandivarman Paliavamalla</i> , .	635
Skandasishya, <i>legendary do.</i> ,	644	Śrîdharabhûtesvara, <i>m. (?)</i> ,	1033
Skandasishya, <i>probably s. a. Pallava k.</i>		Śrîkanṭha, <i>Telugu-Chôḍa ch.</i> ,	585
Skandavarman,	680	Śrîkanṭha-panḍita, <i>priest or sage</i> ,	196
Skandavarman, <i>k.</i> ,	1016	Śrîkûrmam, <i>E. Chôlukyas of</i> ,	577-580
Skandavarman, <i>Pallava kings</i> ,	621, 635, 680	Śrinandi-bhaṭṭarakadêva, <i>Jaina teacher</i> , .	974
Skandavarman, <i>Punnâḍa k.</i> ,	114	Śrinandi-panḍita, <i>do.</i> ,	153
Skandavarman I., <i>Pallava k.</i> ,	619	Śrinâtha, <i>title of kings</i> ,	659, 660, 708, 724
Skandavarman II., <i>do.</i> ,	619, 620	Śrîpâda, <i>m.</i> ,	288, 300
Sôbhana, Sôbhanarasa, <i>ch.</i> ,	143, 146	Śrîpatî, <i>m.</i> ,	343

	NUMBER		NUMBER
Śrī-Perumāl Ativirarāma Śrīvallabha, <i>Pāṇḍya</i>		Suggaladēvi, <i>wife of Barma</i> ,	259
<i>k.</i> ,	935	Sujanōttama Boppa, <i>poet</i> ,	137
Śrīprithivī-vallabha, <i>sur. of Maṅgalēsa</i> ,	7	Śukra, <i>lineage of</i> ,	1058
Śrīpura, <i>vi.</i> ,	119	Sundara, <i>crown of</i> ,	727
Śrīpurusha, <i>W. Gaṅga k.</i> ,	117-119, 121,	Sundarananda, <i>Telugu-Chōḍa ch.</i> ,	888
	123, 127	Sundara-Pāṇḍya, <i>Pāṇḍya k.</i> ,	741
Śrīrāja (Rāja), <i>Yādava ch. of Sēṇadēsa</i> ,	329, 331	Sundara-Pāṇḍya I., <i>Jaṭavarman, do.</i> ,	900-
Śrīraṅga V., <i>Karṇāṭa prince</i> ,	545		905, 907-909
Śrīraṅgam, <i>vi.</i> ,	903n, 909	Sundara-Pāṇḍya II., <i>Jaṭavarman, do.</i> ,	912-918
Śrīraṅgamāmbā, <i>queen of Nṛsiṃharāya</i> ,	501	Sundara-Pāṇḍya I., <i>Māṇavarman, do.</i> ,	891-896
Śrīraṅgapattana, <i>vi.</i> ,	999, 1004, 1005	Sundara-Pāṇḍya II., <i>Māṇavarman, do.</i> ,	897-899
Śrīraṅgarāja, <i>Ṛāja I., Karṇāṭa ch.</i> ,	530, 539	Sundara-Pāṇḍya III., <i>Māṇavarman, do.</i> ,	934
Śrīraṅgarāja II., <i>Karṇāṭa k.</i> ,	535-537, 539	Supparaśa, <i>min.</i> ,	165
Śrīraṅgarāja IV., <i>Karṇāṭa prince</i> ,	542	Suraguru, <i>legendary Chōḍa k.</i> ,	712
Śrīraṅgarāja VI., <i>Karṇāṭa k.</i> ,	545	Surāshṭra, <i>co.</i> ,	330
Śrīvadhuvallabha, <i>sur. of Malladēva Nandi-</i>		Sūrya, <i>Kōṇamanḍala ch.</i> ,	583
<i>varman</i> ,	668	Śūttiradēvi, <i>queen of Tiruvayaṇ</i> ,	1059
Śrīvallabha, <i>poet</i> ,	596	Suvarṇavarsha, <i>sur. of Gōvindarāja IV.</i> ,	91, 92, 305
Śrīvallabha, <i>sur. of Amōghavarsha I.</i> ,	86	Suvarṇavarsha, <i>sur. of Guj. Rāshṭrakūṭa ch.</i>	
Śrīvallabha, <i>sur. of Bhūvikrama</i> ,	115	Karkarāja,	65, 68
Śrīvallabha, <i>sur. of Dantidurga</i> ,	71n	Svāmīrāja, <i>Chālikya ch.</i> ,	6
Śrīvallabha, <i>sur. of Gōvindarāja III.</i> ,	65	Syānandūra, <i>vi. (Trivandrum)</i> ,	941n, 966n
Śrīvallabha, <i>sur. of Rāshṭrakūṭa k.</i>			
Dhruvarāja,	59, 60		
Śrīvallabha, <i>sur. of W. Chal. Vikramāditya</i>			
I.,	20n		
Śrīvallabha, Ativirarāma Jaṭilavarman,			
<i>Pāṇḍya k.</i> ,	935		
Śrīvallabha, Jaṭilavarman, <i>do.</i> ,	933		
Śrīvallabha-Madanarāja, <i>Ceylon k.</i> ,	741		
Śrīvallabhāya, <i>m.</i> ,	596		
Śrīvallabha Sēnānandarāja, <i>Sēndraka ch.</i> ,	13		
Śrīvikrama, <i>W. Gaṅga k.</i> ,	115		
Śrīvishayam, <i>co.</i> ,	734		
Śrutamuni, <i>Jaina teacher</i> ,	986		
Stambha, <i>son of (P) Rāshṭrakūṭa k. Dhruvarāja</i> ,			
	60, 68		
Sthānaka, <i>vi.</i> ,	305		
Sthāṇu Ravi, <i>k.</i> ,	964		
Śubhachandra-muni, <i>Jaina teacher</i> ,	981		
Śubhachandra-paṇḍita, <i>do.</i> ,	122		
Śubhachandra-siddhāntadēva, <i>do.</i> ,	386, 389,		
	390, 393, 398, 406, 968		
Śubhakīrti, <i>Jaina teachers</i> ,	120, 408		
Śubhatuṅga, <i>sur. of Rāshṭrakūṭa Krishṇarāja</i>			
I.,	56, 61, 84		
Śubhatuṅga, <i>sur. of Rāshṭrakūṭa Krishṇarāja</i>			
II.,	84		
Śubhatuṅga Akālavarsha, <i>Guj. Rāshṭrakūṭa</i>			
<i>ch.</i> ,	77		


	NUMBER		NUMBER
Takshaka, <i>Maurya ch.</i> ,	330	Tribhuvanamalla, <i>sur. of Ballāla II.</i> ,	416
Tāla, Tālādhipa, Tālādhipati, Tālapa, Tālapa,		Tribhuvanamalla, <i>sur. of Bijjala (Bijjana)</i> , 277,	
<i>E. Chal. k.</i> (Tāha, Tādapa),	562, 563,	279, 281, 285, 293	
564n, 566, 567, 568n, 574n, 1065		Tribhuvanamalla, <i>sur. of Hoysala Narasimha</i>	
Talaikkōlam, <i>co. or vi.</i> ,	734	I.,	410
Tālupa, Tālupa, <i>see</i> Tāla.		Tribhuvanamalla, <i>sur. of Hoysala Vinayalīya</i> , 353	
Talavanapura, <i>vi.</i> ,	74n, 109, 115	Tribhuvanamalla, <i>sur. of Hoysala Vishnu-</i>	
Tammusiddha, <i>Ṣiddhi Telugu-Chōḍa ch.</i> ,	880-883	vardhana,	388, 389
Tāmarapuri, <i>vi.</i> (Chēbrōlu),	585	Tribhuvanamalla, <i>sur. of Kākatiya Bēta</i> ,	584,
Tandabhutti (Daṇḍabhukti), <i>co.</i> ,	733	585, 586	
Tañjui, Tañjāpuri, Tañjāvūr, <i>vi.</i> , 100-102, 127,		Tribhuvanamalla, <i>sur. of Sōmēśvara IV.</i> ,	253,
714, 716		257, 260	
Tātāḍikki, <i>k. or ch.</i> ,	1065	Tribhuvanamalla, <i>sur. of W. Chal. Vikramā-</i>	
Tātāḍikya, <i>k. (s. a. Tātāḍikki ?)</i> ,	562	ditya V.,	150, 155
Tāta-Pinnama I., <i>Karnāṭa ch.</i> ,	539	Tribhuvanamalla, <i>sur. of W. Chal. Vikramā-</i>	
Tavaragere, <i>vi.</i> ,	196	ditya VI.,	173n, 182, 185-191, 193-196,
Tijagi, <i>Daṇḍanāyaka</i> ,	258	198, 200-208, 210-216, 218-220,	
Telugu-Chōḍas,	880 ff.	222-224, 389, 406	
Tirihū, <i>vi.</i> ,	220	Tribhuvanamalla-Chaladānkarāva Hoysalesetti,	
Tigula, <i>co.</i> ,	415n	<i>m.</i> ,	970
Tilang-vidya, <i>or -bijja, Telugu-Chōḍa ch.</i> , 881, 883		Tribhuvanamalla Jagaddēva, <i>ch. of Paṭṭi-</i>	
Tinana, <i>min.</i> ,	508	<i>Pombuchchapura</i> ,	237
Tinana, <i>Taḷuva k.</i> ,	502	Tribhuvanamalla Kāmadēva, <i>Pāṇḍya ch.</i> ,	212
Tinānāmbā, <i>wife of Raṅga</i> ,	530	Tribhuvanamalla Pāṇḍyadēva, <i>ch.</i> ,	219
Tinamapārādhya, <i>m.</i> ,	517	Tribhuvanānkuśa, <i>sur. of E. Chal. Vimalā-</i>	
Tinamappa-Chauḍa, <i>ch.</i> ,	999	ditya,	568
Tinmarāja, <i>k. of Puṇyalike</i> ,	994	Tribhuvanāśraya Nāgavardhanarāja, <i>W. Chal.</i>	
Tinmarasa, <i>min. (?)</i> ,	514	<i>prince</i> ,	17
Tippūji, <i>queen of Narasa</i> ,	502	Tribhuvanavīra, <i>s. a. Kulōttuṅga-Chōḷa III.</i> ,	
Tiravūḍa, <i>vi.</i> ,	317	840, 842	
Tirumalidēva-mahārāja, <i>Sāluva ch.</i> ,	498	Trikalīnga, <i>co.</i> ,	363
Tirumala-Nāyaka, <i>Madhurā ch.</i> ,	542	Trilōchana-Kadamba, <i>mythical founder of</i>	
Tirumalarāja <i>or</i> Rāya I., <i>Karnāṭa ch.</i> ,	534, 539	<i>Kādamba family</i> ,	254, 261
Tiruvaiyan, <i>W. Gaṅga ch.</i> ,	703, 1059n	Trilōchana-Pallava, <i>legendary k.</i> ,	568
Tiruvayan, <i>Vaidumba-mahārāja</i> ,	1059-1061	Trilōchanārya, <i>poet</i> ,	594
Tiruvēgambam-uḍaiyān, <i>Gaṅga ch.</i> ,	837	Tripervata, <i>vi.</i> ,	613
Tondai-maṇḍalam, <i>co.</i> ,	1056	Tripuri, <i>vi.</i> ,	127
Toragale, <i>vi.</i> ,	259	Trivikrama, <i>father of Khōlēśvara</i> ,	352
Trailōkyamahādēvi, <i>queen of Chōḷa Rājārāja I.</i> , 716		Trivikrama, <i>poets</i> ,	337, 635n
Trailōkyamahādēvi, <i>queen of W. Chal.</i>		Trivikramabhaṭṭa, <i>poet</i> ,	86
Vikramāditya II.,	48	Tuḷuva kings,	502
Trailōkyamalla, <i>ch. of Durjaya family</i> ,	800n	Tuḷvaladēvi, <i>Tuḷvaladēvi, daughter of Vira-</i>	
Trailōkyamalla, <i>sur. of Sōmēśvara I.</i> , 160-163,		Vikramāditya II.,	340
165-167, 171-173, 179		Tuṅgas, <i>kings of Sātyaki branch of Yadu's</i>	
Trailōkyamalla, <i>sur. of Taila III.</i> ,	240, 244	<i>family (Rāshtrakūṭas)</i> ,	93
Trailōkyamalla-Nolamba-Pallava-Permāḍi-Jaya-		Turvasu, <i>race of</i> ,	502
simha, <i>s. a. Jayasimha III.</i> ,	176n	Tyāgapatākā, <i>queen of Vikrama-Chōḷa</i> ,	795, 805
Trailōkyamalla-Vira-Nolamba-Pallava-Perma-		Tyāgasamudra, <i>sur. of Vikrama-Chōḷa</i> ,	576
naḍi-Jayasimha, <i>do.</i> ,	188n	Tyāgavallī, <i>queen of Kulōttuṅga-Chōḷa I.</i> ,	775
Tribhuvanamalla, <i>Kādamba ch.</i> ,	269	Tyāgavārākara, <i>s. a. Tyāgasamudra</i> ,	807
			2 R

U		NUMBER			NUMBER
Uchchaṅgi, <i>vi.</i> ,	225, 244, 248, 415n, 416, 423		Vaidumba, <i>family, k, Mahārāja</i> ,	685, 710,	
Uchchaṅgidurga, Uchchaṅgigiri, <i>s. a.</i> Uchchaṅgi,	231, 250n			724, 1059-1061	
Uchchaṅgingi, <i>vi.</i> ,	611		Vaidya, <i>race</i> ,	937, 938	
Udaiyamārtāṇḍavarman, <i>s. a.</i> Vira-U°,	948, 957		Vaijayanti, <i>vi.</i> ,	5, 604-607	
Udaya, <i>s. a.</i> Chōḍodaya,	584		Vairamēgha, <i>s. a.</i> Dantidurga,	66	
Udayachandra, <i>ch.</i> ,	634		Vāji (Vāchi), <i>family</i> ,	409, 413	
Udayachandradēva, <i>Mahāmaṇḍalāchārya</i> ,	976		Vajjaḍa I., <i>Śilāra ch.</i> ,	305, 307, 309	
Udayadēva-panḍita, <i>priest</i> ,	37		Vajjaḍa II., <i>do.</i> ,	306, 307, 309	
Udayāditya, <i>ch.</i> ,	174, 175		Vajjaḷa, Vajjaḷadēva, <i>ch. or k.</i> ,	131, 136	
Udayāditya, <i>Hogsaḷa prince</i> ,	388, 405, 419, 434		Vājjaḷa, <i>prince of Pānara family</i> ,	562	
Udayāditya, Bhuvanaikavira (Gaṅga-permāṇḍi),			Vajrākara (Vāyirāgaram), <i>vi.</i> ,	756, 761	
<i>W. Gaṅga ch.</i> ,	179, 180		Vajraṭa, <i>k.</i> ,	53, 56	
Udayāditya-Gaṅga-Permāḍi, <i>do.</i> ,	205n		Valabhi, Valabhī, <i>vi.</i> ,	95, 330	
Udayādri, <i>vi.</i> ,	1064		Valaippandūru, <i>co. or vi.</i> ,	734	
Udayana, <i>k. of Ayōdhya</i> ,	568		Vālaka-Kāmaya, <i>Uṇṇiyūr ch.</i> ,	874	
Udayana, <i>Śabara k.</i> ,	634		Vālaparāja, <i>Maurya ch.</i> ,	330	
Udayapūra, <i>vi.</i> ,	549		Vālavāḍa, <i>vi.</i> ,	318, 321, 323, 324	
Ugradanḍa, <i>Pallava k.</i> ,	629		Valipattana, <i>vi.</i> ,	301	
Ugravarman, <i>do.</i> ,	641		Vallabha, <i>i.e. 'W. Chālukya king'</i> ,	754	
Ujjayani, <i>vi.</i> ,	351		Vallabha, <i>Kōnamāṇḍala ch.</i> ,	583	
Ulagamuluduḍaiyāl, <i>ṇyār, title of Chōḷa queens</i> ,			Vallabha, <i>Oḍḍavādi ch.</i> ,	660	
	755, 1081-1084		Vallabha, <i>sur. of Rāshṭrakūṭa Gōvindarāja</i>		
Ulaguḍaiyāl, <i>do.</i> ,	790		II.,	61, 68, 70	
Umādevī, <i>queen of Kēraḷa k. Jayasimha</i> ,	939		Vallabha, <i>sur. of Rāshṭrakūṭa k. Dhruvarāja</i> ,	66	
Upendra, <i>m.</i> ,	34		Vallabha, <i>sur. of Rāshṭrakūṭa Krishnarāja I.</i> ,	64	
Uṇṇiyūr, <i>vi.</i> ,	874		Vallabha, <i>sur. of W. Chal. Kirtivarman II.</i> ,		
Uru-Ranavikrānta, <i>W. Chal. Maṅgalēsa</i> ,	5		53, 56, 71n		
Utkala, <i>co.</i> ,	600		Vallabha, <i>sur. of W. Chal. Pulakēsin I.</i> ,	6	
Utpala, <i>Paramāra k. Muñja</i> ,	143, 150		Vallabha, <i>sur. of W. Chal. Pulakēsin II.</i> ,	12n	
Uttama-Chālukya, <i>E. Chāl. Satyāśraya of</i>			Vallabha, <i>sur. of W. Chal. Vikramāditya</i>		
<i>Fiñhāpuram</i> ,	576		I.,	20n, 634	
Uttama-Chōḷa, <i>Chōḷa k.</i> ,	657n		Vallabha king, <i>Rāshṭrakūṭa Amōghavarsha I.</i>		
Uttama-Chōḷa, <i>probably sur. of Rājendra-</i>			<i>or Krishnarāja II.</i> ,	1065	
<i>Chōḷa I.</i> ,	723n		Vallabharāja, <i>sur. of Rāshṭrakūṭa</i>		
Uttara-Lāṭa, <i>Uttirālāṭam, co.</i> ,	733		Dantivarman II.,	56n, 61n	
V			Vallabharāja, <i>sur. of Rāshṭrakūṭa Krishnarāja</i>		
Vāchāmbā, <i>mother of Sāmanta-Bhōja</i> ,	588n		II.,	84	
Vāchi (Vāji), <i>family</i> ,	410		Vallabharāja, <i>sur. of W. Chal. Pulakēsin II.</i> ,	634	
Vaddiga, <i>s. a.</i> Baddiga,	301, 305		Vallabhendra, <i>sur. of Rāshṭrakūṭa Gōvindarāja</i>		
Vaddiga (Vandiga), <i>Yādava ch. of Sēmaḍēsa</i> ,			III.,	66	
	328, 329, 331		Vallavamiyar Vandyadēvar, <i>husband of</i>		
Vādhūla Mallanārādhya, <i>poet</i> ,	517		Kundavaiyār,	716	
Vadugavāḷi twelve-thousand, <i>di.</i> ,	651		Vamēṣiga-Biṭṭu, <i>m.</i> ,	1028	
Vagan, <i>s. a.</i> Rājarāja-Adigaṇ,	834		Vanabhid, <i>min. of Vira-Champa</i> ,	870	
Vaichaya, <i>s. a.</i> Baicha,	1062, 1063		Vāpa-mahālēvi, 'a Bāṇa queen',	659, 660	
			Vāparāja, 'a Bāṇa k.',	649, 659-661	
			Vānasa, <i>family</i> ,	167	
			Vanavāsi, Vanavāsi, <i>vi.</i> ,	10, 18, 727	
			Vāpavidyādhara, <i>Bāṇa Vikramāditya I.</i> ,	659-661	
			Vañchi, <i>vi. (Vañji)</i> ,	959, 960	

	NUMBER		NUMBER
Vandiga (Vaddiga), <i>Yādava ch. of</i>		Vetta (Betta) I., II., III., <i>Telugu-Chōḍa</i>	
<i>Śūṇadēśa</i> ,	328	<i>chiefs</i> ,	880, 881
Vaṅga, <i>co.</i> ,	5	Vēṭugidēva, <i>Chāl. ch.</i> ,	274
Vaṅgāla-dēśam, <i>co.</i> ,	733	Vichapa (Bicha), <i>Danḍēśa</i> ,	351, 360
Vāṇibhūṣaṇa, <i>sur. of Kādamba</i>		Viddayabhaṭṭa, <i>poet</i> ,	571n, 572n
III.,	261	Vidugādalagiya-Perumāl (Vyāmuktaśravaṇaj- jvala), <i>k. of Tagaḍai (Takatā)</i> ,	833, 834
Vaṇji, <i>vi.</i> ,	834, 959n, 960n	Vidyānagara, <i>ṛī, s. a.</i> Vijayanagara, 474,	
Vappaiya, <i>Maurya ch.</i> ,	330		528-531, 533
Vappuga or Vappuka, <i>k.</i> ,	93, 98	Vidyāvinīta, <i>Pallava lord</i> ,	628
Vappuvanna, <i>Śilāra ch.</i> ,	305, 307, 309	Vijāmbā, <i>queen of Indrarāja III.</i> ,	91
Varaguna, <i>Pāṇḍya k.</i> ,	670	Vijaya, <i>Vijayanagara k.</i> ,	484, 490, 492
Vardhamānasvāmin (P), <i>m.</i> ,	982	Vijaya (Vijayāditya) II., <i>Kādamba ch.</i> ,	269
Vasantapriyārāja, <i>ch.</i> ,	632	Vijayā, <i>queen of Piṭhāpuram ch.</i> Vijayāditya	
Vasantarāja, <i>sur. of Anna-Vēma</i> ,	593, 596	II.,	576
Vātāpi, Vātāpinagari, Vātāpuri, <i>vi.</i> ,	9, 10,	Vijayabāhu, <i>Bāṇa Vikramāditya II.</i> ,	663
	150, 627, 635, 680	Vijayabhaṭṭārīkā, <i>queen of W. Chal.</i>	
Vatsarāja, <i>k. or k. of the Vatsas</i> ,	64	Chandrāditya,	23
Vattūra, <i>vi.</i> ,	5	Vijaya-Buddhavarman, <i>Pallava k.</i> ,	616
Vayirāgaram (Vajrākara), <i>vi.</i> ,	756, 761	Vijayāditya, <i>Alupa k.</i> ,	29n
Vayiri-Aḍiyā, <i>Gaṅga ch.</i> ,	1056	Vijayāditya, <i>Bāṇa k.</i> ,	668
Vedura I., II., <i>Velanāṇḍu chiefs</i> ,	582	Vijayāditya, <i>legendary ancestors of E. Chal.</i>	
Vēgavati, <i>vi.</i> ,	939	<i>kings</i> ,	568
Velanāṇḍu, <i>co.</i> ,	591n, 582, 583, 586	Vijayāditya, <i>Rāṣṭrakūṭa ch. (P)</i> ,	56
Velanāṇḍi-Kulōttuṅga-Rājendra-Chōḍayarāja,		Vijayāditya, <i>Śilāhāra ch.</i> ,	321-323, 327
<i>Velanāṇḍu ch.</i> ,	582	Vijayāditya, <i>W. Chal. k.</i> , 28, 32-41, 44, 48,	
Velanda or Vilanda, <i>vi.</i> ,	115		49, 150, 193
Vēlāpura (Bēlāpura), <i>vi.</i> ,	385, 388	Vijayāditya, <i>W. Gaṅga k.</i> ,	121, 137
Vēlūr or Vēlūru, <i>vi.</i> ,	527, 534, 535, 539	Vijayāditya I., II., <i>Bāṇa kings</i> ,	663
Vēma, <i>min.</i> ,	508	Vijayāditya I., II., <i>E. Chāl. chiefs of</i>	
Vēma, <i>Redḍi ch. of Koṇḍaviḍu</i> ,	593, 596	<i>Piṭhāpuram</i> ,	576
Vēma, <i>s. a.</i> Allaya-Vēma,	599	Vijayāditya III., <i>E. Chāl. ch. of do.</i> ,	575, 576
Vēma, <i>s. a.</i> Kāṭaya-Vēma,	595-598	Vijayāditya I., <i>E. Chāl. ch. of Śrīkūrmam</i> ,	577
Vēmāmbikā, <i>queen of Redḍi Alla</i> ,	599	Vijayāditya II., <i>do.</i> ,	577, 578, 580
Vēmapura, <i>vi.</i> ,	593n	Vijayāditya I., <i>E. Chal. k. (Vijayāditya-</i>	
Vēmasāni, <i>sister of Anna-Vēma</i> ,	593	<i>bhaṭṭāraka)</i> ,	553, 554, 557
Vēṇāḍu, <i>co. (Travancore)</i> ,	943 ff.	Vijayāditya II., <i>do. (Narēndrampigarāja)</i> ,	
Vēṅgai-manḍalam, <i>co.</i> ,	795		553-557, 559, 560, 562n
Vēṅgai-nāḍu, Vēṅgaiññāḍu, <i>co.</i> , 702-704,		Vijayāditya III., <i>do. (Guṇaga-V^o)</i> ,	556-560, 1065
	1082, 1084	Vijayāditya IV., <i>do. (Kollabigaṇḍa)</i> , 558-562,	
Vēṅgi, <i>co.</i> ,	56, 64, 571-574, 756n, 1065		563n, 566, 1065
Vēṅkaṭādrī, <i>Karṇāṭa ch.</i> ,	539, 545	Vijayāditya V., <i>do.</i> , 560, 562, 563, 566, 576n,	
Vēṅkaṭādrī-Nāyaka, <i>ch. or chiefs</i> ,	536, 541, 546		1065
Vēṅkaṭādrī-Nāyaka Ayya, <i>ch.</i> ,	544	Vijayāditya VI., <i>do. (Ammarāja II.)</i> ,	
Vēṅkaṭapati I., <i>Karṇāṭa k.</i> ,	538, 539		563-567, 1065
Vēṅkaṭapati II., <i>do.</i> ,	542, 543, 545	Vijayāditya VII., <i>E. Chal. ruler of Vēṅgi</i> ,	
Vēṅkaṭarāja, <i>Vijayanagara k.</i> ,	530		571, 572, 754, 1084
Vēṇṇa, <i>Kōṇamāṇḍala ch.</i> ,	583	Vijayāditya I., <i>Kādamba ch.</i> ,	249, 254, 261
Vēṇṇamāṇḍala Śāmbuvarāja, <i>ch.</i> ,	871	Vijayāditya II., <i>do.</i> ,	241
Vēṇṇagrāma, Vēṇṇapura, <i>vi.</i> ,	265-268	Vijayāditya III., <i>do.</i> ,	261
Vēṣu or Vēṣuka, <i>Yādava ch. of Śūṇadēśa</i> , 329, 331			

	NUMBER		NUMBER
Vijayāditya-bhaṭṭāraka, <i>E. Chal.</i>	Vijayāditya	Vikrama-Chōḍa, <i>E. Chal. k. (s. a. Vikrama-Chōḍa),</i>	574, 576
I.,	557	Vikrama-Chōḍa, <i>s. a. Vikrama-Chōḍa,</i>	808
Vijayāditya-vallabha, <i>probably W. Chal.</i>		Vikrama-Chōḍa, <i>Chōḍa k.,</i>	794-807, 810
Vijayāditya,	183	Vikramāditya, <i>E. Chāl. ch. of Piṭhāpuram,</i>	576
Vijayāditya Vishṇuvardhana, <i>W. Chāl. prince,</i>		Vikramāditya I., <i>Bāṇa k.,</i>	649, 659n, 662, 663
	171, 172, 741	Vikramāditya II., <i>do.,</i>	663
Vijaya-Gaṇḍagōpāla, <i>Telugu-Chōḍa ch.,</i>	884-887	Vikramāditya I., <i>E. Chal.,</i>	557-560, 1065
Vijaya-Īśvaravarman, <i>Gaṅga-Pallava k.,</i>	654, 655	Vikramāditya II., <i>E. Chal. k.,</i>	560-563, 566, 567, 1065
Vijayakāma, <i>Telugu-Chōḍa ch.,</i>	888	Vikramāditya III., <i>Gutta ch.,</i>	340, 363
Vijaya-Kampa or -Kampavikramavarman,		Vikramāditya I., <i>W. Chal. k.,</i>	1n, 18-24, 27, 150, 628, 629, 632, 634
<i>Gaṅga-Pallava k.,</i>	656, 1070	Vikramāditya II., <i>do.,</i>	39-49, 150
Vijayakīrti, <i>Jaina teacher,</i>	66	Vikramāditya III., <i>W. Chāl. ch.,</i>	150
Vijayālaya, <i>Chōḍa k.,</i>	672-675, 685, 712, 1071	Vikramāditya IV., <i>do.,</i>	140, 150, 232
Vijayamahādēvi, <i>queen of W. Chal.</i>		Vikramāditya V., <i>W. Chāl. k.,</i>	150, 153, 154, 179
Chandrāditya,	24	Vikramāditya VI., <i>do.,</i>	168, 173n, 182, 181-196, 198, 200-208, 210-216, 218-224, 249, 254, 261, 269, 389, 406, 741, 753, 754, 763, 774, 1081, 1082, 1084
Vijayanagara, <i>dynasties of,</i>	454 ff.	Vikrama-Pāṇḍya, <i>Ceylon k.,</i>	741
Vijayanagara, <i>vi.,</i>	465, 466, 475, 487, 490, 502, 508, 509, 512, 515, 519, 530, 1064	Vikrama-Pāṇḍya, <i>Pāṇḍya k.,</i>	827, 1087, 1088
Vijaya-Nandivikrama or °vikramavarman,		Vikramapura, <i>vi. (Kappanāṭr),</i>	436
<i>Gaṅga-Pallava k.,</i>	648-651, 1067	Vikramārāma, <i>s. a. E. Chal. Vijayāditya I.,</i>	554
Vijaya-Narasimhavarman or °simhavikrama-varman, <i>do.,</i>	645-647	Vikramārka, <i>s. a. W. Chāl. Vikramāditya VI.,</i>	219
Vijaya-Nripatungavarman or °tūṅgavikrama-varman, <i>do.,</i>	652, 653, 656n, 1068, 1069	Vikrama-Śōḷa-Sambuvārāyaṇ, <i>Śeṅṅēni ch.,</i>	820
Vijaya-Pāṇḍyadēva, <i>ch.,</i>	225, 238, 244, 248, 250-252	Vikramāvalōka, <i>sur. of Gōvindarāja II.,</i>	56
Vijaya-Permāḍi, <i>Danḍanātha,</i>	250	Vikrānta-Nārāyaṇa, <i>sur. of Gōvindarāja IV.,</i>	91n
Vijayārka, <i>s. a. E. Chāl. Vijayāditya II. of Śrīkūrmam,</i>	580	Vijānda or Veḷānda, <i>vi.,</i>	115
Vijayārka, <i>s. a. Śīlāhāra Vijayāditya,</i>	327	Vilvalapura, <i>vi.,</i>	634
Vijayārka (Vijayāditya) I., <i>Kādamba ch.,</i>	269	Vimāla, <i>mythical Gaṅga k.,</i>	652
Vijayārka (Vijayāditya) III., <i>do.,</i>	261	Vimalachandra, <i>Jaina teacher,</i>	969
Vijayasakti, <i>Śēndra k.,</i>	16	Vimalachandrāchārya, <i>do.,</i>	119
Vijayasiddhi, <i>sur. of Maṅgi-yuvarāja,</i>	552	Vimalāditya, <i>Chāl. ch.,</i>	66
Vijaya-Śiva-Māndhātṛivarman, <i>Kādamba k.,</i>	602	Vimalāditya, <i>E. Chāl. ch. of Piṭhāpuram,</i>	576
Vijaya-Śiva-Mṛigēśavarman, <i>do.,</i>	605	Vimalāditya, <i>E. Chal. k.,</i>	568-571, 574, 577, 582
Vijaya-Skandasishyavikramavarman, <i>Gaṅga-Pallava k.,</i>	644	Vīmaṇ (Bhīma), <i>Teliṅga ch. of Kuḷam,</i>	795
Vijaya-Skandavarman, <i>Pallava k.,</i>	616	Vināpoti, <i>mistress of W. Chal. Vijayāditya,</i>	38
'Vijaypat', <i>vi.,</i>	274	Vinayāditya, <i>Hoysala k.,</i>	383, 388, 405, 406, 409, 419, 434, 443, 969
Vikkalan, <i>s. a. W. Chāl. Vikramāditya VI.,</i>	753, 763, 774, 1081, 1082	Vinayāditya, <i>W. Chal. k.,</i>	26-31, 33
Vikki, <i>do.,</i>	741	Vinayāditya, <i>W. Chal. Maṅgalarasārāja,</i>	1n
Vikkiramāditta-Vānarāja, <i>Bāṇa Vikramāditya I.,</i>	649	Vingavalli, <i>vi.,</i>	91
Vikrama, <i>Kādamba ch.,</i>	210	Vinikonda, <i>vi.,</i>	1064
Vikrama, <i>s. a. W. Chāl. Vikramāditya VI.,</i>	254	Vīra-Ballāla, <i>s. a. Ballāla II.,</i>	388, 415-423, 426-433, 437
Vikrama, <i>Sinda ch.,</i>	247	Vīra-Bāṇudēva, <i>E. Gaṅga k. Bhānudēva II.,</i>	579
Vikrama (Vikramāditya) III., <i>Gutta ch.,</i>	340, 363	Vīrabhadra, <i>Gajapati k.'s son,</i>	1064
Vikramabāhu, <i>Ceylon k.,</i>	741		

	NUMBER		NUMBER
Virabhadra, <i>Reddī ch. of Rājamahēndra-nagara</i> ,	599	Vira-Nanamba, <i>Chōl. k.</i> ,	277
Vira-Bhōjadēva, <i>s. a. Bhōjadēva II.</i> ,	326	Vira-Nṛisimha, <i>E. Guṇḡa k. Namsamā I.</i> ,	277
Vira-Bhukka, <i>s. a. Bukka I.</i> ,	475	Vira-Nṛisimha or -Narasimha or -Nārasimha, <i>Vijayanagara k.</i> ,	502
Vira-Bokkapa-Uḍaiyar, <i>s. a. Bukkarāya I.</i> ,	463	Virapa, <i>Madhurā Nāyaka</i> ,	542
Vira-Bukkarāya, <i>do.</i> ,	461	Vira-Padmanābha Mārtāṇḍavarman, <i>k. of Vēṇāḍu</i> ,	556
Vira-Bukkarāya-Voḍeyar, <i>do.</i> ,	456, 457	Vira-Pāṇḍya (Pāṇḍyarāya), <i>ch.</i> ,	985, 987
Vira-Champa, <i>Chōla prince</i> ,	869, 870	Vira-Pāṇḍya, Māṇavarman, <i>Pāṇḍya k.</i> ,	986
Vira-Chōla, <i>E. Chal. ruler of Vēṅḡi</i> , 571-573,	582, 773	Vira-Pāṇḍya, <i>Pāṇḍya kings</i> , 694, 712, 742,	827, 906, 910, 1087, 1088
Vira-Chōla, <i>father of Vira-Champa</i> ,	870	Vira-Pāṇḍya, <i>Vēṇāḍu k. Vira Uḍaiyannṛtāṇḍavarman</i> ,	933, 937
Vira-Chōla, <i>perhaps s. a. Prithivīpati II.</i> ,	103	Vira-Pāṇḍyadēva, <i>ch.</i> ,	231, 233, 271
Vira-Chōla, <i>s. a. E. Chal. Vira-Chōla</i> ,	773	Virappa-Nāyaka, <i>Vēlūr ch.</i> ,	560
Vira-Chōla, <i>s. a. Prithivīpati II.</i> , 669, 671,	681, 682	Virapratāpa Achyutarāya, <i>s. a. Achyutarāya</i> ,	514-516, 518
Vira-Chōla, <i>sur. of Virarājendra I.</i> ,	1081	Virapratāpa Bukkamahārāya, <i>s. a. Bukkarāya II.</i> ,	473
Vira-Chōla (P) Kōṇṇerimēlkonḍāṇ, <i>k.</i> ,	875	Virapratāpa Dēvarāya, <i>s. a. Dēvarāya I.</i> ,	480, 483, 485
Vira-Chōla Lāṭṭarāja, <i>ch.</i> ,	698	Virapratāpa Dēvarāya, <i>s. a. Dēvarāya II.</i> ,	488, 489, 491, 496
Vira-Dēvarāya, <i>Ṛāja, s. a. Dēvarāya II.</i> ,	490, 493, 494	Virapratāpa Harihara, <i>s. a. Harihara II.</i> ,	465, 475
Vira-Gaṇḍagōpāla, <i>ch.</i> ,	904	Virapratāpa Praudha-Immaḍi-Dēvarāya, <i>s. a. Vijayanagara k. Mallikārjuna</i> ,	497
Vira-Gōpāla (P), <i>k. (P)</i> ,	967	Virapratāpa Sadāsivarāya, <i>s. a. Sadāsivarāya</i> ,	523, 525, 528, 529, 531
Vira-Harihara, <i>s. a. Harihara II.</i> ,	470	Virapratāpa Śrīrāgarāya, <i>s. a. Śrīrāgarāya II.</i> ,	536
Vira-Hariyappa-Voḍeyar, <i>s. a. Harihara I.</i> ,	454	Virapratāpa Vijayarāya, <i>s. a. Vijayanagara k. Vijaya</i> ,	484
Virahōbala, <i>Sāḷuva ch.</i> ,	501	Virapratāpa Vira-Kṛishṇarāya, <i>s. a. Kṛishṇarāya</i> ,	502, 513
Vira-Kampana (or -Kampana)-Uḍaiyar, <i>s. a. Kampana II.</i> ,	460, 462, 464	Vira-Rāghava-Chakravartin, <i>k.</i> ,	907
Vira-Kēraḷa, <i>kings</i> ,	741, 827	Virarājendra I., <i>Chōla k.</i> , 753, 754, 755n,	765, 1081-1084
Vira-Kēraḷa-Chakravartin, <i>k.</i> ,	965	Virarājendra-Chōla, <i>Velanāṇḍu ch.</i> ,	582
Vira-Kēraḷa Mārtāṇḍavarman, <i>Kēraḷa k.</i> ,	958	Virarājendra-Chōla, <i>s. a. Kulōttunga-Chōla III.</i> ,	816
Vira-Kēraḷavarman, <i>kings of Vēṇāḍu</i> , 943, 944, 949	943, 944, 949	Vira-Rājendra-Voḍeyar, <i>Koḍagu ch.</i> ,	1008, 1009
Virakūrchavarman, <i>Pallava k.</i> ,	622	Vira-Rāma Kēraḷavarman, <i>k. of Vēṇāḍu</i> ,	951, 952
Virakūrchā, <i>do.</i> ,	635	Vira-Rāmanātha, <i>Poysala (Hoysala) prince</i> ,	441, 442, 445, 448, 449
Viramahēndra, <i>sur. of Chālukya-Bhīma II. (P)</i> ,	126	Vira-Rāmarvarman, <i>k. of Vēṇāḍu</i> ,	950
Vira-Mallappa-Voḍeyar, <i>son of Dēvarāya I.</i> ,	483	Vira-Ravi Kēraḷavarman, <i>do.</i> ,	955
Viramangalam, <i>vi.</i> ,	937	Vira-Ravivarman, <i>do.</i> ,	946, 947
Viranandin, <i>Viraṇandin, son of Mēghachandra-traividya</i> ,	74, 408	Virārjuna, <i>Telugu-Chōla ch.</i> ,	884
Vira-Narasimha or -Nārasimha, <i>s. a. Hoysala Narasimha II.</i> ,	435, 847	Vira-Salāmēgaṇ, <i>Ceylon k.</i> ,	741, 743
Vira-Narasimha or -Nārasimha, <i>s. a. Hoysala Narasimha III.</i> ,	440, 446, 447, 452		
Vira-Narasimha or -Nārasimha or -Nṛisimha, <i>Vijayanagara k.</i> ,	502		
Viranarasimha-Chaṅṅanarēndra, <i>sur. of Bhairava II.</i> ,	993		
Vira-Nārāyaṇa, <i>sur. of Amōghavarsha I.</i> ,	74, 86		
Vira-Nārāyaṇa, <i>sur. of Parāntaka I.</i> ,	681, 685		
Vira-Nārāyaṇa, <i>sur. of Rāshṭrakūṭa Kakka-rāja II.</i> ,	105n		



	NUMBER		NUMBER
Virāsani-Ammalaiyappan Alagiya-Sōlan, <i>Sēngēni</i>		Vishnuvardhana, <i>sur. of E. Chal. Chālukya-</i>	
<i>ch.</i> ,	856, 860, 862	Bhīma II.,	560-562
Vira-Satyāśraya, <i>Chāl. k.</i> ,	272	Vishnuvardhana, <i>sur. of E. Chal. Chōḍagaṅga</i> ,	571
Virasinha, <i>Pallava k.</i> ,	635	Vishnuvardhana, <i>sur. of E. Chal. Rājārāja</i>	
Vira-Sōmēśvara, <i>s. a. Hoysala Sōmēśvara</i> ,		I.,	569, 570
436, 438, 864		Vishnuvardhana, <i>sur. of E. Chal. Vimalāditya</i> ,	568
Vira-Sōmēśvara, <i>s. a. W. Chāl. Sōmēśvara</i>		Vishnuvardhana, <i>sur. of E. Chal. Vira-Chōḍa</i> ,	
IV.,	253	572, 573	
Vira-Udaiyamārtāṇḍavarman, <i>k. of Vēṇḍu</i> ,		Vishnuvardhana, <i>sur. of E. Chāl. ch. Mallapa</i>	
948, 957		III.,	576
Viravarman, <i>Pallava k.</i> ,	619, 620	Vishnuvardhana I., II., <i>E. Chāl. chiefs of</i>	
Vira-veḍēṅga, <i>sur. of W. Gaṅga Narasiṅga</i> ,	127	<i>Piṭhāpuram</i> ,	576
Vira-Veṅkaṭapati-mahārāja, <i>s. a. Veṅkaṭapati</i>		Vishnuvardhana I., <i>E. Chal. k. (Kubja-V^o)</i> ,	
I.,	539	547, 548, 549n, 550, 551, 557	
Vira-Veṅkaṭapati-mahārāja, <i>s. a. Veṅkaṭapati</i>		Vishnuvardhana II., <i>E. Chal. k.</i> ,	550-552, 557
II.,	542	Vishnuvardhana III., <i>do.</i> ,	557, 634
Vira-Vijaya, <i>s. a. Vijayanagara k. Vijaya</i> ,		Vishnuvardhana IV., <i>do.</i> ,	553-555, 557, 559, 560
484, 485, 487, 490		Vishnuvardhana V., <i>do. (Kali-V^o)</i> ,	555-557,
Vira-Vikramāditya I., <i>Gutta ch.</i> ,	298	559, 560, 1065	
Vira-Vikramāditya II., <i>do.</i> ,	298, 335, 340	Vishnuvardhana Vijayāditya, <i>W. Chāl. prince</i> ,	
Virudarājabhayankara, <i>sur. of Kulōttunga-</i>		171, 172, 741	
Chōla I.,	769n	Vishnuvarman, <i>general</i> ,	619n
Virūpāksha I., <i>Vijayanagara k.</i> ,	468	Vishnuvarman, <i>Kadamba k.</i> ,	609(?), 614
Virūpāksha II., <i>do.</i> ,	500	Viśvanātha, <i>Madhurā Nāyaka</i> ,	542
Virūpāksha-Nāyaka, <i>min. of Achyutarāja</i> ,	519	Viśvanātha (Jagannātha), <i>E. Chāl. ch. of</i>	
Viśala, <i>Chaulukya (Vāghēlā) k.</i> ,	369	<i>Śrīkūrmam</i> ,	579
Vishamasiddhi, <i>sur. of E. Chal. Vishnu-</i>		Viśvapa-Nāyaka, <i>Madhurā ch.</i> ,	542
vardhana I.,	547-549	Voddiyanvā, <i>queen of Yādava Vaddiga</i> ,	323
Vishamasiddhi, <i>sur. of E. Chal. Vishnu-</i>		Vṛiddhi, <i>Pallavādhirāja</i> ,	115
vardhana II.,	550, 551	Vyāghrakētu, <i>legendary Chōla k.</i> ,	712
Vishnu, <i>s. a. Hoysala Vishnuvardhana</i> ,	388,	Vyāghramārin, <i>Gūhalla, Kādamba ch.</i> ,	254
399, 405, 409, 443		Vyāmuktasravanapōjjvala, <i>s. a. Viṇuḍaḍagiya-</i>	
Vishnuchitta, <i>Kādamba ch.</i> ,	249	Perumāi,	834
Vishnugōpa, <i>Pallava k.</i> ,	635	<i>Vyāsa-sūtras</i> ,	979
Vishnugōpa, <i>W. Gaṅga k.</i> ,	110-113, 670		
Vishnugōpa or °gōpavarman, <i>Pallava k.</i> ,	619, 620		
Vishnurāja, <i>s. a. E. Chal. Vishnuvardhana</i>			
III.,	634		
Vishnurāja, <i>s. a. E. Chal. Vishnuvardhana</i>			
IV.,	557		
Vishnusiṅha, <i>Pallava k.</i> ,	635		
Vishnuvardhana, <i>ancestor of E. Chal. kings</i> ,	568		
Vishnuvardhana, <i>Hoysala k.</i> ,	234, 384, 387-		
389, 396, 399, 400, 401, 405, 406, 408, 415,			
419, 434			
Vishnuvardhana, <i>s. a. or sur. of Kulōttunga-</i>			
Chōla I.,	762, 786, 787, 792		
Vishnuvardhana, <i>sur. of E. Chal. Ammarāja</i>			
I.,	558, 559		
Vishnuvardhana, <i>sur. of E. Chal. Chālukya-</i>			
Bhīma I.,	557		

Y

Yādava, <i>lineage of Rāshṭrakūṭas</i> ,	74
Yādavas, <i>of Dēvagiri</i> ,	334 ff.
Yādavas, <i>of Sēunadēsa</i> ,	328 ff.
Yadu, <i>Yadus, family or lineage of</i> ,	86, 91, 93,
105, 323, 329, 334, 337, 343, 360, 369, 370,	
379, 388, 405, 409, 419, 434, 443, 474,	
484, 487, 583, 939, 996	
Yajñavarya, <i>probably s. a. Yajñēśvara</i> ,	269
Yajñēśvara, <i>Yajñēśvarasūri, poet</i> ,	249, 261, 269r
Yaksharāja (Jakkirāja), <i>father of Hulla</i> ,	410, 411
Yaśovarmān, <i>Chāl. ch.</i> ,	66
Yaśovarmān (Daśavarmān), <i>W. Chāl. prince</i> ,	15

	NUMBER		NUMBER
Yavanikā, s. a. Elipi,	834	Yuddhamalla I., E. Chal.,	566, 1065
Yuddhamalla, Oḍḍavādi ch.,	600	Yuddhamalla II., E. Chal. k., 560, 563, 567,	568, 1065
Yuddhamalla, W. Chal. k. (Vinayāditya ?),	150	Yuvarājadēva, Chēdi k.,	105
Yuddhamalla, W. Chal. Maṅgalarasārāja,	1n		

104266

Due Date

15-2-85
(No 9)

5-3-85
(No 8)
4